

# PIC18F2X1X/4X1X Data Sheet

28/40/44-Pin Flash Microcontrollers with 10-Bit A/D and nanoWatt Technology

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our
  knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data
  Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is intended through suggestion only and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. No representation or warranty is given and no liability is assumed by Microchip Technology Incorporated with respect to the accuracy or use of such information, or infringement of patents or other intellectual property rights arising from such use or otherwise. Use of Microchip's products as critical components in life support systems is not authorized except with express written approval by Microchip. No licenses are conveyed, implicitly or otherwise, under any intellectual property rights.

#### **Trademarks**

The Microchip name and logo, the Microchip logo, Accuron, dsPIC, KEELOQ, microID, MPLAB, PIC, PICmicro, PICSTART, PRO MATE, PowerSmart, rfPIC, and SmartShunt are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AmpLab, FilterLab, MXDEV, MXLAB, PICMASTER, SEEVAL, SmartSensor and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, dsPICDEM, dsPICDEM.net, dsPICworks, ECAN, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, Migratable Memory, MPASM, MPLIB, MPLINK, MPSIM, PICkit, PICDEM, PICDEM.net, PICLAB, PICtail, PowerCal, PowerInfo, PowerMate, PowerTool, rfLAB, rfPICDEM, Select Mode, Smart Serial, SmartTel and Total Endurance are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2004, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

QUALITY MANAGEMENT SYSTEM

CERTIFIED BY DNV

ISO/TS 16949:2002 ===

Microchip received ISO/TS-16949:2002 quality system certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona and Mountain View, California in October 2003. The Company's quality system processes and procedures are for its PICmicro® 8-bit MCUs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.



## 28/40/44-Pin Flash Microcontrollers with 10-bit A/D and nanoWatt Technology

#### **Power Managed Modes:**

- Run: CPU on, peripherals on
- · Idle: CPU off, peripherals on
- · Sleep: CPU off, peripherals off
- Idle mode currents down to 3.0  $\mu\text{A}$  typical
- Sleep mode currents down to 20 nA typical
- Timer1 Oscillator: 1.8 μA, 32 kHz, 2V
- Watchdog Timer: 2.1 μA
- Two-Speed Oscillator Start-up

#### Peripheral Highlights:

- High-current sink/source 25 mA/25 mA
- Up to 2 Capture/Compare/PWM (CCP) modules, one with Auto-Shutdown (28-pin devices)
- Enhanced Capture/Compare/PWM (ECCP) module (40/44-pin devices only):
  - One, two or four PWM outputs
  - Selectable polarity
  - Programmable dead time
  - Auto-Shutdown and Auto-Restart
- Master Synchronous Serial Port (MSSP) module supporting 3-wire SPI™ (all 4 modes) and I<sup>2</sup>C™ Master and Slave Modes
- Enhanced Addressable USART module:
  - Supports RS-485, RS-232 and LIN 1.2
  - RS-232 operation using internal oscillator block (no external crystal required)
  - Auto-Wake-up on Start bit
  - Auto-Baud Detect
- 10-bit, up to 13-channel Analog-to-Digital Converter module (A/D):
  - Auto-acquisition capability
  - Conversion available during Sleep
- Dual analog comparators with input multiplexing
- Programmable 16-level High/Low-Voltage Detection (HLVD) module:
  - Supports interrupt on High/Low-Voltage Detection

#### Flexible Oscillator Structure:


- Four Crystal modes, up to 40 MHz
- 4x Phase Lock Loop (PLL) available for crystal and internal oscillators
- Two External RC modes, up to 4 MHz
- Two External Clock modes, up to 40 MHz
- Internal oscillator block:
  - 8 user selectable frequencies, from 31 kHz to 8 MHz
  - Provides a complete range of clock speeds from 31 kHz to 32 MHz when used with PLL
  - User tunable to compensate for frequency drift
- Secondary oscillator using Timer1 @ 32 kHz
- · Fail-Safe Clock Monitor:
  - Allows for safe shutdown if peripheral clock stops

#### **Special Microcontroller Features:**


- · C compiler optimized architecture:
  - Optional extended instruction set designed to optimize re-entrant code
- 100,000 erase/write cycle Flash program memory typical
- · Three programmable external interrupts
- Four input-change interrupts
- Priority levels for interrupts
- 8 x 8 Single-Cycle Hardware Multiplier
- Extended Watchdog Timer (WDT):
  - Programmable period from 4 ms to 131s
- Single-supply 5V In-Circuit Serial Programming™ (ICSP™) via two pins
- · In-Circuit Debug (ICD) via two pins
- Wide operating voltage range: 2.0V to 5.5V
- Programmable Brown-out Reset (BOR) with software enable option

| Davida     | Progra           | am Memory                     | Data<br>Memory  | I/O | 10-bit   | CCP/ECCP<br>(PWM) | MS   | SP                          | EUSART | 0     | Timers<br>8/16-bit |
|------------|------------------|-------------------------------|-----------------|-----|----------|-------------------|------|-----------------------------|--------|-------|--------------------|
| Device     | Flash<br>(bytes) | # Single-Word<br>Instructions | SRAM<br>(bytes) | 1/0 | A/D (ch) |                   | SPI™ | Master<br>I <sup>2</sup> C™ | EUS    | Comp. |                    |
| PIC18F2410 | 16K              | 8192                          | 768             | 25  | 10       | 2/0               | Y    | Y                           | 1      | 2     | 1/3                |
| PIC18F2510 | 32K              | 16384                         | 1536            | 25  | 10       | 2/0               | Y    | Y                           | 1      | 2     | 1/3                |
| PIC18F2515 | 48K              | 24576                         | 3968            | 25  | 10       | 2/0               | Υ    | Υ                           | 1      | 2     | 1/3                |
| PIC18F2610 | 64K              | 32768                         | 3968            | 25  | 10       | 2/0               | Υ    | Υ                           | 1      | 2     | 1/3                |
| PIC18F4410 | 16K              | 8192                          | 768             | 36  | 13       | 1/1               | Υ    | Υ                           | 1      | 2     | 1/3                |
| PIC18F4510 | 32K              | 16384                         | 1536            | 36  | 13       | 1/1               | Υ    | Υ                           | 1      | 2     | 1/3                |
| PIC18F4515 | 48K              | 24576                         | 3968            | 36  | 13       | 1/1               | Y    | Y                           | 1      | 2     | 1/3                |
| PIC18F4610 | 64K              | 32768                         | 3968            | 36  | 13       | 1/1               | Y    | Y                           | 1      | 2     | 1/3                |

#### **Pin Diagrams**



#### Pin Diagrams (Cont.'d)



#### **Table of Contents**

| 1.0   | Device Overview  | 7     |
|-------|--|-------|
| 2.0   | Oscillator Configurations                                    | 23    |
| 3.0   | Power Managed Modes  | 33    |
| 4.0   | Reset  | 41    |
| 5.0   | Memory Organization  | 53    |
| 6.0   | Flash Program Memory   | 75    |
| 7.0   | 8 x 8 Hardware Multiplier                                    | 79    |
| 8.0   | Interrupts   | 81    |
| 9.0   | VO Ports   | 95    |
| 10.0  | Timer0 Module  | . 113 |
| 11.0  | Timer1 Module  | . 117 |
| 12.0  | Timer2 Module  | . 123 |
| 13.0  | Timer3 Module  | . 125 |
| 14.0  | Capture/Compare/PWM (CCP) Modules                            | . 129 |
| 15.0  | Enhanced Capture/Compare/PWM (ECCP) Module                   | . 137 |
| 16.0  | Master Synchronous Serial Port (MSSP) Module                 | . 151 |
| 17.0  | Enhanced Universal Synchronous Receiver Transmitter (EUSART) | . 191 |
| 18.0  | 10-Bit Analog-to-Digital Converter (A/D) Module              | . 211 |
| 19.0  | Comparator Module  | . 221 |
| 20.0  | Comparator Voltage Reference Module                          | . 227 |
|       | High/Low-Voltage Detect (HLVD)                               |       |
|       | Special Features of the CPU                                  |       |
| 23.0  | Instruction Set Summary                                      | . 257 |
| 24.0  | Development Support  | . 307 |
| 25.0  | Electrical Characteristics                                   | . 313 |
|       | DC and AC Characteristics Graphs And Tables                  |       |
| 27.0  | Packaging Information  | . 353 |
| Appe  | ndix A: Revision History                                     | . 361 |
| Appe  | ndix B: Device Differences                                   | . 361 |
| Appe  | ndix C: Conversion Considerations                            | . 362 |
| Appe  | ndix D: Migration From Baseline to Enhanced Devices          | . 362 |
| Appe  | ndix E: Migration From Mid-Range to Enhanced Devices         | 363   |
| Appe  | ndix F: Migration From High-End to Enhanced Devices          | . 363 |
| Index |  | 365   |
| On-Li | ne Support   | . 375 |
| Syste | ems Information and Upgrade Hot Line                         | . 375 |
|       | er Response  |       |
| PIC1  | 8F2X1X/4X1X Product Identification System                    | . 377 |

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@mail.microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- · Your local Microchip sales office (see last page)
- The Microchip Corporate Literature Center; U.S. FAX: (480) 792-7277

When contacting a sales office or the literature center, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our Web site at www.microchip.com/cn to receive the most current information on all of our products.

#### 1.0 DEVICE OVERVIEW

This document contains device specific information for the following devices:

• PIC18F2410 PIC18LF2410 PIC18F2510 PIC18LF2510 PIC18F2515 PIC18LF2515 PIC18F2610 PIC18LF2610 PIC18F4410 PIC18LF4410 • PIC18F4510 PIC18LF4510 PIC18F4515 PIC18LF4515 PIC18F4610 PIC18LF4610

This family offers the advantages of all PIC18 microcontrollers — namely, high computational performance at an economical price — with the addition of high-endurance, Flash program memory. On top of these features, the PIC18F2X1X/4X1X family introduces design enhancements that make these microcontrollers a logical choice for many high-performance, power sensitive applications.

#### 1.1 New Core Features

#### 1.1.1 nanoWatt TECHNOLOGY

All of the devices in the PIC18F2X1X/4X1X family incorporate a range of features that can significantly reduce power consumption during operation. Key items include:

- Alternate Run Modes: By clocking the controller from the Timer1 source or the internal oscillator block, power consumption during code execution can be reduced by as much as 90%.
- Multiple Idle Modes: The controller can also run
  with its CPU core disabled but the peripherals still
  active. In these states, power consumption can be
  reduced even further, to as little as 4% of normal
  operation requirements.
- On-the-fly Mode Switching: The power managed modes are invoked by user code during operation, allowing the user to incorporate powersaving ideas into their application's software design.
- Lower Consumption in Key Modules: The power requirements for both Timer1 and the Watchdog Timer have been minimized. See Section 25.0 "Electrical Characteristics" for values.

### 1.1.2 MULTIPLE OSCILLATOR OPTIONS AND FEATURES

All of the devices in the PIC18F2X1X/4X1X family offer ten different oscillator options, allowing users a wide range of choices in developing application hardware. These include:

- Four Crystal modes, using crystals or ceramic resonators
- Two External Clock modes, offering the option of using two pins (oscillator input and a divide-by-4 clock output) or one pin (oscillator input, with the second pin reassigned as general I/O)
- Two External RC Oscillator modes with the same pin options as the External Clock modes
- An internal oscillator block which provides an 8 MHz clock and an INTRC source (approximately 31 kHz), as well as a range of 6 user selectable clock frequencies, between 125 kHz to 4 MHz, for a total of 8 clock frequencies. This option frees the two oscillator pins for use as additional general purpose I/O.
- A Phase Lock Loop (PLL) frequency multiplier, available to both the high-speed crystal and internal oscillator modes, which allows clock speeds of up to 40 MHz. Used with the internal oscillator, the PLL gives users a complete selection of clock speeds, from 31 kHz to 32 MHz – all without using an external crystal or clock circuit.

Besides its availability as a clock source, the internal oscillator block provides a stable reference source that gives the family additional features for robust operation:

- Fail-Safe Clock Monitor: This option constantly
  monitors the main clock source against a
  reference signal provided by the internal
  oscillator. If a clock failure occurs, the controller is
  switched to the internal oscillator block, allowing
  for continued low-speed operation or a safe
  application shutdown.
- Two-Speed Start-up: This option allows the internal oscillator to serve as the clock source from Power-on Reset, or wake-up from Sleep mode, until the primary clock source is available.

#### 1.2 Other Special Features

- Memory Endurance: The Flash cells for program memory are rated to 100,000 erase/write cycles.
   Data retention without refresh is conservatively estimated to be greater than 40 years.
- Extended Instruction Set: The PIC18F2X1X/ 4X1X family introduces an optional extension to the PIC18 instruction set, which adds 8 new instructions and an Indexed Addressing mode. This extension, enabled as a device configuration option, has been specifically designed to optimize re-entrant application code originally developed in high-level languages, such as C.
- Enhanced CCP Module: In PWM mode, this
  module provides 1, 2 or 4 modulated outputs for
  controlling half-bridge and full-bridge drivers.
  Other features include Auto-Shutdown, for
  disabling PWM outputs on interrupt or other select
  conditions and Auto-Restart, to reactivate outputs
  once the condition has cleared.
- Enhanced Addressable USART: This serial communication module is capable of standard RS-232 operation and provides support for the LIN bus protocol. Other enhancements include automatic baud rate detection and a 16-bit Baud Rate Generator for improved resolution. When the microcontroller is using the internal oscillator block, the USART provides stable operation for applications that talk to the outside world without using an external crystal (or its accompanying power requirement).
- 10-bit A/D Converter: This module incorporates programmable acquisition time, allowing for a channel to be selected and a conversion to be initiated without waiting for a sampling period and thus, reduce code overhead.
- Extended Watchdog Timer (WDT): This
  enhanced version incorporates a 16-bit prescaler,
  allowing an extended time-out range that is stable
  across operating voltage and temperature. See
  Section 25.0 "Electrical Characteristics" for
  time-out periods.

### 1.3 Details on Individual Family Members

Devices in the PIC18F2X1X/4X1X family are available in 28-pin and 40/44-pin packages. Block diagrams for the two groups are shown in Figure 1-1 and Figure 1-2.

The devices are differentiated from each other in five ways:

- 1. Flash program memory
  - 16 Kbytes for PIC18F2410/4410 devices
  - 32 Kbytes for PIC18F2510/4510 devices
  - 48 Kbytes for PIC18F2515/4515 devices
  - 64 Kbytes for PIC18F2610/4610 devices
- A/D channels (10 for 28-pin devices, 13 for 40/44-pin devices).
- 3. I/O ports (3 bidirectional ports on 28-pin devices, 5 bidirectional ports on 40/44-pin devices).
- CCP and Enhanced CCP implementation (28-pin devices have 2 standard CCP modules; 40/44-pin devices have one standard CCP module and one ECCP module).
- Parallel Slave Port (present only on 40/44-pin devices).

All other features for devices in this family are identical. These are summarized in Table 1-1.

The pinouts for all devices are listed in Table 1-3 and Table 1-4.


Like all Microchip PIC18 devices, members of the PIC18F2X1X/4X1X family are available as both standard and low-voltage devices. Standard devices with Flash memory, designated with an "F" in the part number (such as PIC18F2610), accommodate an operating VDD range of 4.2V to 5.5V. Low-voltage parts, designated by "LF" (such as PIC18LF2610), function over an extended VDD range of 2.0V to 5.5V.


TABLE 1-1: DEVICE FEATURES (PIC18F2410/2510/2515/2610)

| Features                                | PIC18F2410   | PIC18F2510   | PIC18F2515   | PIC18F2610   |
|---|--|--|--|--|
| Operating Frequency                     | DC – 40 MHz  |
| Program Memory (Bytes)                  | 16384  | 32768  | 49152  | 65536  |
| Program Memory<br>(Instructions)        | 8192   | 16384  | 24576  | 32768  |
| Data Memory (Bytes)                     | 768  | 1536   | 3968   | 3968   |
| Interrupt Sources                       | 18   | 18   | 18   | 18   |
| I/O Ports                               | Ports A, B, C, (E)   |
| Timers                                  | 4  | 4  | 4  | 4  |
| Capture/Compare/PWM Modules             | 2  | 2  | 2  | 2  |
| Enhanced<br>Capture/Compare/PWM Modules | 0  | 0  | 0  | 0  |
| Serial Communications                   | MSSP,<br>Enhanced USART  | MSSP,<br>Enhanced USART  | MSSP,<br>Enhanced USART  | MSSP,<br>Enhanced USART  |
| Parallel Communications (PSP)           | No   | No   | No   | No   |
| 10-bit Analog-to-Digital Module         | 10 Input Channels  | 10 Input Channels  | 10 Input Channels  | 10 Input Channels  |
| Resets (and Delays)                     | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT |
| Programmable<br>High/Low-Voltage Detect | Yes  | Yes  | Yes  | Yes  |
| Programmable<br>Brown-out Reset         | Yes  | Yes  | Yes  | Yes  |
| Instruction Set                         | 75 Instructions;<br>83 with Extended<br>Instruction Set enabled                            |
| Packages                                | 28-pin SPDIP<br>28-pin SOIC<br>28-pin QFN  | 28-pin SPDIP<br>28-pin SOIC<br>28-pin QFN  | 28-pin SPDIP<br>28-pin SOIC  | 28-pin SPDIP<br>28-pin SOIC  |

TABLE 1-2: DEVICE FEATURES (PIC18F4410/4510/4515/4610)

| Features                                | PIC18F4410   | PIC18F4510   | PIC18F4515   | PIC18F4610   |
|---|--|--|--|--|
| Operating Frequency                     | DC – 40 MHz  |
| Program Memory (Bytes)                  | 16384  | 32768  | 49152  | 65536  |
| Program Memory<br>(Instructions)        | 8192   | 16384  | 24576  | 32768  |
| Data Memory (Bytes)                     | 768  | 1536   | 3968   | 3968   |
| Interrupt Sources                       | 19   | 19   | 19   | 19   |
| I/O Ports                               | Ports A, B, C, D, E  |
| Timers                                  | 4  | 4  | 4  | 4  |
| Capture/Compare/PWM Modules             | 1  | 1  | 1  | 1  |
| Enhanced<br>Capture/Compare/PWM Modules | 1  | 1  | 1  | 1  |
| Serial Communications                   | MSSP,<br>Enhanced USART  | MSSP,<br>Enhanced USART  | MSSP,<br>Enhanced USART  | MSSP,<br>Enhanced USART  |
| Parallel Communications (PSP)           | Yes  | Yes  | Yes  | Yes  |
| 10-bit Analog-to-Digital Module         | 13 Input Channels  | 13 Input Channels  | 13 Input Channels  | 13 Input Channels  |
| Resets (and Delays)                     | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT | POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST), MCLR (optional), WDT |
| Programmable<br>High/Low-Voltage Detect | Yes  | Yes  | Yes  | Yes  |
| Programmable<br>Brown-out Reset         | Yes  | Yes  | Yes  | Yes  |
| Instruction Set                         | 75 Instructions;<br>83 with Extended<br>Instruction Set enabled                            |
| Packages                                | 40-pin PDIP<br>44-pin QFN<br>44-pin TQFP   |





PIC18F4410/4510/4515/4610 (40/44-PIN) BLOCK DIAGRAM FIGURE 1-2:

TABLE 1-3: PIC18F2410/2510/2515/2610 PINOUT I/O DESCRIPTIONS

|                               | Pin Nu         | ımber | Pin  | Buffer     |  |
|-------------------------------|----------------|-------|------|------------|--|
| Pin Name                      | SPDIP,<br>SOIC | QFN   | Туре |            | Description  |
| MCLR/VPP/RE3<br>MCLR          | 1              | 26    | I    | ST         | Master Clear (input) or programming voltage (input).  Master Clear (Reset) input. This pin is an active-low Reset to the device.   |
| VPP                           |                |       | Р    |            | Programming voltage input.   |
| RE3                           |                |       | I    | ST         | Digital input.   |
| OSC1/CLKI/RA7<br>OSC1<br>CLKI | 9              | 6     | 1    | ST<br>CMOS | Oscillator crystal or external clock input. Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; CMOS otherwise. External clock source input. Always associated with pin function OSC1. (See related OSC1/CLKI, OSC2/CLKO pins.) |
| RA7                           |                |       | I/O  | TTL        | General purpose I/O pin.   |
| OSC2/CLKO/RA6<br>OSC2         | 10             | 7     | 0    | _          | Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.  |
| CLKO                          |                |       | 0    | _          | In RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes the instruction cycle rate.   |
| RA6                           |                |       | I/O  | TTL        | General purpose I/O pin.   |

**Legend:** TTL = TTL compatible input CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I = Input O = Output P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-3: PIC18F2410/2510/2515/2610 PINOUT I/O DESCRIPTIONS (CONTINUED)

|  | Pin Nu         | ımber | Pin Buffe                                  |                                     |  |
|--|----------------|-------|--|-------------------------------------|--|
| Pin Name   | SPDIP,<br>SOIC | QFN   | Туре                                       |                                     | Description  |
|  |                |       |  |                                     | PORTA is a bidirectional I/O port.                               |
| RA0/AN0<br>RA0<br>AN0  | 2              | 27    | I/O<br>I                                   | TTL<br>Analog                       | Digital I/O.<br>Analog input 0.                                  |
| RA1/AN1<br>RA1<br>AN1  | 3              | 28    | I/O<br>I                                   | TTL<br>Analog                       | Digital I/O.<br>Analog input 1.                                  |
| RA2/AN2/VREF-/CVREF<br>RA2<br>AN2<br>VREF-<br>CVREF                | 4              | 1     | I/O<br>I<br>I<br>O                         | TTL<br>Analog<br>Analog<br>Analog   | ,  |
| RA3/AN3/VREF+<br>RA3<br>AN3<br>VREF+                               | 5              | 2     | I/O<br>I<br>I                              | TTL<br>Analog<br>Analog             | Digital I/O. Analog input 3. A/D reference voltage (high) input. |
| RA4/T0CKI/C1OUT<br>RA4<br>T0CKI<br>C1OUT                           | 6              | 3     | I/O<br>I<br>O                              | ST<br>ST<br>—                       | Digital I/O. Timer0 external clock input. Comparator 1 output.   |
| RA5/AN4/SS/HLVDIN/<br>C2OUT<br>RA5<br>AN4<br>SS<br>HLVDIN<br>C2OUT | 7              | 4     | I/O<br> <br> <br> <br> <br> <br> <br> <br> | TTL<br>Analog<br>TTL<br>Analog<br>— | SPI™ slave select input.   |
| RA6  |                |       |  |                                     | See the OSC2/CLKO/RA6 pin.                                       |
| RA7  |                |       |  |                                     | See the OSC1/CLKI/RA7 pin.                                       |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I

= Input

O = Output

P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-3: PIC18F2410/2510/2515/2610 PINOUT I/O DESCRIPTIONS (CONTINUED)

|   | Pin Nu         | ımber | D:-             | Duffer                    |   |
|---|----------------|-------|-----------------|---------------------------|---|
| Pin Name  | SPDIP,<br>SOIC | QFN   | Pin<br>Type     | Buffer<br>Type            | Description   |
|   |                | 40    |                 |                           | PORTB is a bidirectional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs. |
| RB0/INT0/FLT0/AN12<br>RB0<br>INT0<br>FLT0<br>AN12 | 21             | 18    | I/O<br>I<br>I   | TTL<br>ST<br>ST<br>Analog | Digital I/O. External interrupt 0. PWM Fault input for CCP1. Analog input 12.                                 |
| RB1/INT1/AN10<br>RB1<br>INT1<br>AN10              | 22             | 19    | I/O<br>I<br>I   | TTL<br>ST<br>Analog       | Digital I/O.<br>External interrupt 1.<br>Analog input 10.   |
| RB2/INT2/AN8<br>RB2<br>INT2<br>AN8                | 23             | 20    | I/O<br>I<br>I   | TTL<br>ST<br>Analog       | Digital I/O.<br>External interrupt 2.<br>Analog input 8.  |
| RB3/AN9/CCP2<br>RB3<br>AN9<br>CCP2 <sup>(1)</sup> | 24             | 21    | I/O<br>I<br>I/O | TTL<br>Analog<br>ST       | Digital I/O.<br>Analog input 9.<br>Capture 2 input/Compare 2 output/PWM 2 output.                             |
| RB4/KBI0/AN11<br>RB4<br>KBI0<br>AN11              | 25             | 22    | I/O<br>I<br>I   | TTL<br>TTL<br>Analog      | Digital I/O.<br>Interrupt-on-change pin.<br>Analog input 11.  |
| RB5/KBI1/PGM<br>RB5<br>KBI1<br>PGM                | 26             | 23    | I/O<br>I<br>I/O | TTL<br>TTL<br>ST          | Digital I/O.<br>Interrupt-on-change pin.<br>Low-Voltage ICSP™ Programming enable pin.                         |
| RB6/KBI2/PGC<br>RB6<br>KBI2<br>PGC                | 27             | 24    | I/O<br>I<br>I/O | TTL<br>TTL<br>ST          | Digital I/O.<br>Interrupt-on-change pin.<br>In-Circuit Debugger and ICSP programming clock pin.               |
| RB7/KBI3/PGD<br>RB7<br>KBI3<br>PGD                | 28             | 25    | I/O<br>I<br>I/O | TTL<br>TTL<br>ST          | Digital I/O.<br>Interrupt-on-change pin.<br>In-Circuit Debugger and ICSP programming data pin.                |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I
O = Output F

I = Input P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

**2:** Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-3: PIC18F2410/2510/2515/2610 PINOUT I/O DESCRIPTIONS (CONTINUED)

|   | Pin Nu         | ımber | Pin               | Buffer             |   |  |  |  |  |
|---|----------------|-------|-------------------|--------------------|---|--|--|--|--|
| Pin Name  | SPDIP,<br>SOIC | QFN   | Type              |                    | Description   |  |  |  |  |
|   |                |       |                   |                    | PORTC is a bidirectional I/O port.  |  |  |  |  |
| RC0/T1OSO/T13CKI<br>RC0<br>T1OSO<br>T13CKI            | 11             | 8     | I/O<br>O<br>I     | ST<br>—<br>ST      | Digital I/O. Timer1 oscillator output. Timer1/Timer3 external clock input.  |  |  |  |  |
| RC1/T1OSI/CCP2<br>RC1<br>T1OSI<br>CCP2 <sup>(2)</sup> | 12             | 9     | I/O<br>I<br>I/O   | ST<br>Analog<br>ST | Digital I/O. Timer1 oscillator input. Capture 2 input/Compare 2 output/PWM 2 output.  |  |  |  |  |
| RC2/CCP1<br>RC2<br>CCP1                               | 13             | 10    | I/O<br>I/O        | ST<br>ST           | Digital I/O.<br>Capture 1 input/Compare 1 output/PWM 1 output.  |  |  |  |  |
| RC3/SCK/SCL<br>RC3<br>SCK<br>SCL                      | 14             | 11    | I/O<br>I/O<br>I/O | ST<br>ST<br>ST     | Digital I/O.  Synchronous serial clock input/output for SPI™ mode.  Synchronous serial clock input/output for I <sup>2</sup> C™ mode. |  |  |  |  |
| RC4/SDI/SDA<br>RC4<br>SDI<br>SDA                      | 15             | 12    | I/O<br>I<br>I/O   | ST<br>ST<br>ST     | Digital I/O.<br>SPI data in.<br>I <sup>2</sup> C data I/O.  |  |  |  |  |
| RC5/SDO<br>RC5<br>SDO                                 | 16             | 13    | I/O<br>O          | ST<br>—            | Digital I/O.<br>SPI data out.   |  |  |  |  |
| RC6/TX/CK<br>RC6<br>TX<br>CK                          | 17             | 14    | I/O<br>O<br>I/O   | ST<br>—<br>ST      | Digital I/O. EUSART asynchronous transmit. EUSART synchronous clock (see related RX/DT).  |  |  |  |  |
| RC7/RX/DT<br>RC7<br>RX<br>DT                          | 18             | 15    | I/O<br>I<br>I/O   | ST<br>ST<br>ST     | Digital I/O. EUSART asynchronous receive. EUSART synchronous data (see related TX/CK).  |  |  |  |  |
| RE3   | _              | _     | _                 | _                  | See MCLR/VPP/RE3 pin.   |  |  |  |  |
| Vss   | 8, 19          | 5, 16 | Р                 | _                  | Ground reference for logic and I/O pins.  |  |  |  |  |
| VDD   | 20             | 17    | Р                 | _                  | Positive supply for logic and I/O pins.   |  |  |  |  |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I

= Input

O = Output

P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-4: PIC18F4410/4510/4515/4610 PINOUT I/O DESCRIPTIONS

| Pin Name                      | Piı  | n Numb | oer  | Pin Buffer | Decariation |  |  |
|-------------------------------|------|--------|------|------------|-------------|--|--|
| Pin Name                      | PDIP | QFN    | TQFP | Туре       | Туре        | Description  |  |
| MCLR/VPP/RE3<br>MCLR          | 1    | 18     | 18   | I          | ST          | Master Clear (input) or programming voltage (input).  Master Clear (Reset) input. This pin is an active-low Reset to the device.   |  |
| VPP<br>RE3                    |      |        |      | P          | ST          | Programming voltage input. Digital input.  |  |
| OSC1/CLKI/RA7<br>OSC1<br>CLKI | 13   | 32     | 30   | I          | ST          | Oscillator crystal or external clock input. Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; analog otherwise. External clock source input. Always associated with pin function OSC1. (See related OSC1/CLKI, OSC2/CLKO pins.) |  |
| RA7                           |      |        |      | I/O        | TTL         | General purpose I/O pin.   |  |
| OSC2/CLKO/RA6<br>OSC2         | 14   | 33     | 31   | 0          | _           | Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.  |  |
| CLKO                          |      |        |      | 0          | _           | In RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes the instruction cycle rate.   |  |
| RA6                           |      |        |      | I/O        | TTL         | General purpose I/O pin.   |  |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

= Input

ST = Schmitt Trigger input with CMOS levels I

P = Output P = Power

**Note 1:** Default assignment for CCP2 when configuration bit CCP2MX is set.

**2:** Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-4: PIC18F4410/4510/4515/4610 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name   | Piı  | n Numb | er   | Pin                              | Buffer                              | Description   |  |  |
|--|------|--------|------|----------------------------------|-------------------------------------|---|--|--|
| riii Naine   | PDIP | QFN    | TQFP | Туре                             | Туре                                | Description   |  |  |
| RA0/AN0<br>RA0<br>AN0  | 2    | 19     | 19   | I/O<br>I                         | TTL<br>Analog                       | PORTA is a bidirectional I/O port.  Digital I/O. Analog input 0.  |  |  |
| RA1/AN1<br>RA1<br>AN1  | 3    | 20     | 20   | I/O<br>I                         | TTL<br>Analog                       | Digital I/O.<br>Analog input 1.   |  |  |
| RA2/AN2/VREF-/CVREF<br>RA2<br>AN2<br>VREF-<br>CVREF                | 4    | 21     | 21   | I/O<br>I<br>I<br>O               | TTL<br>Analog<br>Analog<br>Analog   | Digital I/O. Analog input 2. A/D reference voltage (low) input. Comparator reference voltage output.      |  |  |
| RA3/AN3/VREF+<br>RA3<br>AN3<br>VREF+                               | 5    | 22     | 22   | I/O<br>I<br>I                    | TTL<br>Analog<br>Analog             | Digital I/O.<br>Analog input 3.<br>A/D reference voltage (high) input.                                    |  |  |
| RA4/T0CKI/C1OUT<br>RA4<br>T0CKI<br>C1OUT                           | 6    | 23     | 23   | I/O<br>I<br>O                    | ST<br>ST<br>—                       | Digital I/O.<br>Timer0 external clock input.<br>Comparator 1 output.                                      |  |  |
| RA5/AN4/SS/HLVDIN/<br>C2OUT<br>RA5<br>AN4<br>SS<br>HLVDIN<br>C2OUT | 7    | 24     | 24   | I/O<br> <br> <br> <br> <br> <br> | TTL<br>Analog<br>TTL<br>Analog<br>— | Digital I/O. Analog input 4. SPI™ slave select input. High/Low-Voltage Detect input. Comparator 2 output. |  |  |
| RA6<br>RA7   |      |        |      |                                  |                                     | See the OSC2/CLKO/RA6 pin. See the OSC1/CLKI/RA7 pin.   |  |  |

**Legend:** TTL = TTL compatible input CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I = Input
O = Output P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

**2:** Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-4: PIC18F4410/4510/4515/4610 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Dia Nama  | Piı  | n Numb | oer  | Pin             | Buffer                    | Description:  |  |  |
|---|------|--------|------|-----------------|---------------------------|---|--|--|
| Pin Name  | PDIP | QFN    | TQFP | Туре            | Type                      | Description   |  |  |
| RB0/INT0/FLT0/AN12                                | 33   | 9      | 8    |                 |                           | PORTB is a bidirectional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs. |  |  |
| RB0<br>INT0<br>FLT0<br>AN12                       |      | Ç      |      | I/O<br>I<br>I   | TTL<br>ST<br>ST<br>Analog | Digital I/O. External interrupt 0. PWM Fault input for Enhanced CCP1. Analog input 12.                        |  |  |
| RB1/INT1/AN10<br>RB1<br>INT1<br>AN10              | 34   | 10     | 9    | I/O<br>I<br>I   | TTL<br>ST<br>Analog       | Digital I/O.<br>External interrupt 1.<br>Analog input 10.   |  |  |
| RB2/INT2/AN8<br>RB2<br>INT2<br>AN8                | 35   | 11     | 10   | I/O<br>I<br>I   | TTL<br>ST<br>Analog       | Digital I/O.<br>External interrupt 2.<br>Analog input 8.  |  |  |
| RB3/AN9/CCP2<br>RB3<br>AN9<br>CCP2 <sup>(1)</sup> | 36   | 12     | 11   | I/O<br>I<br>I/O | TTL<br>Analog<br>ST       | Digital I/O. Analog input 9. Capture 2 input/Compare 2 output/PWM 2 output.                                   |  |  |
| RB4/KBI0/AN11<br>RB4<br>KBI0<br>AN11              | 37   | 14     | 14   | I/O<br>I<br>I   | TTL<br>TTL<br>Analog      | Digital I/O.<br>Interrupt-on-change pin.<br>Analog input 11.  |  |  |
| RB5/KBI1/PGM<br>RB5<br>KBI1<br>PGM                | 38   | 15     | 15   | I/O<br>I<br>I/O | TTL<br>TTL<br>ST          | Digital I/O.<br>Interrupt-on-change pin.<br>Low-Voltage ICSP™ Programming enable pin.                         |  |  |
| RB6/KBI2/PGC<br>RB6<br>KBI2<br>PGC                | 39   | 16     | 16   | I/O<br>I<br>I/O | TTL<br>TTL<br>ST          | Digital I/O. Interrupt-on-change pin. In-Circuit Debugger and ICSP programming clock pin.                     |  |  |
| RB7/KBI3/PGD<br>RB7<br>KBI3<br>PGD                | 40   | 17     | 17   | I/O<br>I<br>I/O | TTL<br>TTL<br>ST          | Digital I/O. Interrupt-on-change pin. In-Circuit Debugger and ICSP programming data pin.                      |  |  |

**Legend:** TTL = TTL compatible input CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I = Input
O = Output P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-4: PIC18F4410/4510/4515/4610 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name  | Piı  | n Numb | oer  | Pin Buffer             |                        | Description   |
|---|------|--------|------|------------------------|------------------------|---|
| Pin Name  | PDIP | QFN    | TQFP | Туре                   | Туре                   | Description   |
| RC0/T1OSO/T13CKI<br>RC0<br>T1OSO                    | 15   | 34     | 32   | I/O<br>O               | ST<br>—                | PORTC is a bidirectional I/O port.  Digital I/O. Timer1 oscillator output.  |
| T13CKI RC1/T1OSI/CCP2 RC1 T1OSI CCP2 <sup>(2)</sup> | 16   | 35     | 35   |                        | ST<br>ST<br>CMOS<br>ST | Timer1/Timer3 external clock input.  Digital I/O. Timer1 oscillator input. Capture 2 input/Compare 2 output/PWM 2 output. |
| RC2/CCP1/P1A<br>RC2<br>CCP1<br>P1A                  | 17   | 36     | 36   | I/O<br>I/O<br>O        | ST<br>ST<br>—          | Digital I/O. Capture1 input/Compare1 output/PWM1 output. Enhanced CCP1 output.  |
| RC3/SCK/SCL<br>RC3<br>SCK                           | 18   | 37     | 37   | I/O<br>I/O             | ST<br>ST               | Digital I/O. Synchronous serial clock input/output for SPI™ mode.   |
| SCL<br>RC4/SDI/SDA<br>RC4<br>SDI<br>SDA             | 23   | 42     | 42   | I/O<br>I/O<br>I<br>I/O | ST<br>ST<br>ST<br>ST   | Synchronous serial clock input/output for I <sup>2</sup> C™ mode.  Digital I/O.  SPI data in. I <sup>2</sup> C data I/O.  |
| RC5/SDO<br>RC5<br>SDO                               | 24   | 43     | 43   | I/O<br>O               | ST<br>—                | Digital I/O.<br>SPI data out.   |
| RC6/TX/CK<br>RC6<br>TX<br>CK                        | 25   | 44     | 44   | I/O<br>O<br>I/O        | ST<br>—<br>ST          | Digital I/O. EUSART asynchronous transmit. EUSART synchronous clock (see related RX/DT).                                  |
| RC7/RX/DT<br>RC7<br>RX<br>DT                        | 26   | 1      | 1    | I/O<br>I<br>I/O        | ST<br>ST<br>ST         | Digital I/O. EUSART asynchronous receive. EUSART synchronous data (see related TX/CK).                                    |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I

= Input

O = Output

P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-4: PIC18F4410/4510/4515/4610 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Din Nama                           | Pin Number |     |      | Pin Buffer      | Description    |  |  |
|------------------------------------|------------|-----|------|-----------------|----------------|--|--|
| Pin Name                           | PDIP       | QFN | TQFP | Туре            | Type           | Description  |  |
|                                    |            |     |      |                 |                | PORTD is a bidirectional I/O port or a Parallel Slave Port (PSP) for interfacing to a microprocessor port. These pins have TTL input buffers when PSP module is enabled. |  |
| RD0/PSP0<br>RD0<br>PSP0            | 19         | 38  | 38   | I/O<br>I/O      | ST<br>TTL      | Digital I/O.<br>Parallel Slave Port data.  |  |
| RD1/PSP1<br>RD1<br>PSP1            | 20         | 39  | 39   | I/O<br>I/O      | ST<br>TTL      | Digital I/O.<br>Parallel Slave Port data.  |  |
| RD2/PSP2<br>RD2<br>PSP2            | 21         | 40  | 40   | I/O<br>I/O      | ST<br>TTL      | Digital I/O.<br>Parallel Slave Port data.  |  |
| RD3/PSP3<br>RD3<br>PSP3            | 22         | 41  | 41   | I/O<br>I/O      | ST<br>TTL      | Digital I/O.<br>Parallel Slave Port data.  |  |
| RD4/PSP4<br>RD4<br>PSP4            | 27         | 2   | 2    | I/O<br>I/O      | ST<br>TTL      | Digital I/O.<br>Parallel Slave Port data.  |  |
| RD5/PSP5/P1B<br>RD5<br>PSP5<br>P1B | 28         | 3   | 3    | I/O<br>I/O<br>O | ST<br>TTL<br>— | Digital I/O.<br>Parallel Slave Port data.<br>Enhanced CCP1 output.   |  |
| RD6/PSP6/P1C<br>RD6<br>PSP6<br>P1C | 29         | 4   | 4    | I/O<br>I/O<br>O | ST<br>TTL<br>— | Digital I/O.<br>Parallel Slave Port data.<br>Enhanced CCP1 output.   |  |
| RD7/PSP7/P1D<br>RD7<br>PSP7<br>P1D | 30         | 5   | 5    | I/O<br>I/O<br>O | ST<br>TTL<br>— | Digital I/O.<br>Parallel Slave Port data.<br>Enhanced CCP1 output.   |  |

**Legend:** TTL = TTL compatible input CMOS = CMOS compatible input or output

 $\begin{array}{lll} \mathsf{ST} &=& \mathsf{Schmitt} \; \mathsf{Trigger} \; \mathsf{input} \; \mathsf{with} \; \mathsf{CMOS} \; \mathsf{levels} \; \; \mathsf{I} & = \; \mathsf{Input} \\ \mathsf{O} &=& \mathsf{Output} & \mathsf{P} & = \; \mathsf{Power} \end{array}$ 

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

TABLE 1-4: PIC18F4410/4510/4515/4610 PINOUT I/O DESCRIPTIONS (CONTINUED)

| Pin Name   | Pin Number |        |        | Pin Buffer |        | Description                                 |  |
|------------|------------|--------|--------|------------|--------|---|--|
| Fili Name  | PDIP       | QFN    | TQFP   | Туре       | Туре   | Description                                 |  |
|            |            |        |        |            |        | PORTE is a bidirectional I/O port.          |  |
| RE0/RD/AN5 | 8          | 25     | 25     |            |        |   |  |
| RE0        |            |        |        | I/O        | ST     | Digital I/O.                                |  |
| RD         |            |        |        | I          | TTL    | Read control for Parallel Slave Port        |  |
|            |            |        |        |            |        | (see also WR and CS pins).                  |  |
| AN5        |            |        |        | I          | Analog | Analog input 5.                             |  |
| RE1/WR/AN6 | 9          | 26     | 26     |            |        |   |  |
| RE1        |            |        |        | I/O        | ST     | Digital I/O.                                |  |
| WR         |            |        |        | I          | TTL    | Write control for Parallel Slave Port       |  |
|            |            |        |        |            |        | (see CS and RD pins).                       |  |
| AN6        |            |        |        | ı          | Analog | Analog input 6.                             |  |
| RE2/CS/AN7 | 10         | 27     | 27     |            |        |   |  |
| RE2        |            |        |        | I/O        | ST     | Digital I/O.                                |  |
| CS         |            |        |        | I          | TTL    | Chip select control for Parallel Slave Port |  |
|            |            |        |        |            |        | (see related RD and WR).                    |  |
| AN7        |            |        |        | I          | Analog | Analog input 7.                             |  |
| RE3        | _          | _      | _      | _          | _      | See MCLR/VPP/RE3 pin.                       |  |
| Vss        | 12, 31     | 6, 30, | 6, 29  | Р          |        | Ground reference for logic and I/O pins.    |  |
|            |            | 31     |        |            |        |   |  |
| VDD        | 11, 32     | 7, 8,  | 7, 28  | Р          | _      | Positive supply for logic and I/O pins.     |  |
|            |            | 28, 29 |        |            |        |   |  |
| NC         | _          | 13     | 12,13, | _          | _      | No connect.                                 |  |
|            |            |        | 33, 34 |            |        |   |  |

**Legend:** TTL = TTL compatible input

CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels I
O = Output P

I = Input P = Power

Note 1: Default assignment for CCP2 when configuration bit CCP2MX is set.

2: Alternate assignment for CCP2 when configuration bit CCP2MX is cleared.

### 2.0 OSCILLATOR CONFIGURATIONS

#### 2.1 Oscillator Types

PIC18F2X1X/4X1X devices can be operated in ten different oscillator modes. The user can program the configuration bits, FOSC3:FOSC0, in Configuration Register 1H to select one of these ten modes:

| 1.  | LP     | Low-Power Crystal  |
|-----|--------|--|
| 2.  | XT     | Crystal/Resonator  |
| 3.  | HS     | High-Speed Crystal/Resonator                                 |
| 4.  | HSPLL  | High-Speed Crystal/Resonator with PLL enabled                |
| 5.  | RC     | External Resistor/Capacitor with Fosc/4 output on RA6        |
| 6.  | RCIO   | External Resistor/Capacitor with I/O on RA6                  |
| 7.  | INTIO1 | Internal Oscillator with Fosc/4 output on RA6 and I/O on RA7 |
| 8.  | INTIO2 | Internal Oscillator with I/O on RA6 and RA7                  |
| 9.  | EC     | External Clock with Fosc/4 output                            |
| 10. | ECIO   | External Clock with I/O on RA6                               |


### 2.2 Crystal Oscillator/Ceramic Resonators

In XT, LP, HS or HSPLL Oscillator modes, a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation. Figure 2-1 shows the pin connections.

The oscillator design requires the use of a parallel cut crystal.

**Note:** Use of a series cut crystal may give a frequency out of the crystal manufacturer's specifications.

# FIGURE 2-1: CRYSTAL/CERAMIC RESONATOR OPERATION (XT, LP, HS OR HSPLL CONFIGURATION)



Note 1: See Table 2-1 and Table 2-2 for initial values of C1 and C2.

- 2: A series resistor (Rs) may be required for AT strip cut crystals.
- 3: RF varies with the oscillator mode chosen.

### TABLE 2-1: CAPACITOR SELECTION FOR CERAMIC RESONATORS

| Typical Capacitor Values Used: |          |       |       |  |  |  |  |  |
|--------------------------------|----------|-------|-------|--|--|--|--|--|
| Mode                           | Freq     | OSC1  | OSC2  |  |  |  |  |  |
| XT                             | 3.58 MHz | 15 pF | 15 pF |  |  |  |  |  |
|                                | 4.19 MHz | 15 pF | 15 pF |  |  |  |  |  |
|                                | 4 MHz    | 30 pF | 30 pF |  |  |  |  |  |
|                                | 4 MHz    | 50 pF | 50 pF |  |  |  |  |  |

#### Capacitor values are for design guidance only.

Different capacitor values may be required to produce acceptable oscillator operation. The user should test the performance of the oscillator over the expected VDD and temperature range for the application.

See the notes following Table 2-2 for additional information.

Note: When using resonators with frequencies above 3.5 MHz, the use of HS mode, rather than XT mode, is recommended. HS mode may be used at any VDD for which the controller is rated. If HS is selected, it is possible that the gain of the oscillator will overdrive the resonator. Therefore, a series resistor should be placed between the OSC2 pin and the resonator. As a good starting point, the recommended value of Rs is  $330\Omega$ .

TABLE 2-2: CAPACITOR SELECTION FOR CRYSTAL OSCILLATOR

| Osc Type | Crystal                             | Typical Capacitor Values Tested: |                                  |  |  |
|----------|-------------------------------------|----------------------------------|----------------------------------|--|--|
|          | Freq                                | C1                               | C2                               |  |  |
| LP       | 32 kHz                              | 30 pF                            | 30 pF                            |  |  |
| XT       | 1 MHz<br>4 MHz                      | 15 pF<br>15 pF                   | 15 pF<br>15 pF                   |  |  |
| HS       | 4 MHz<br>10 MHz<br>20 MHz<br>25 MHz | 15 pF<br>15 pF<br>15 pF<br>15 pF | 15 pF<br>15 pF<br>15 pF<br>15 pF |  |  |

#### Capacitor values are for design guidance only.


Different capacitor values may be required to produce acceptable oscillator operation. The user should test the performance of the oscillator over the expected VDD and temperature range for the application.

See the notes following this table for additional information.

- **Note 1:** Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 2: When operating below 3V VDD, or when using certain ceramic resonators at any voltage, it may be necessary to use the HS mode or switch to a crystal oscillator.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **4:** Rs may be required to avoid overdriving crystals with low drive level specification.
  - **5:** Always verify oscillator performance over the VDD and temperature range that is expected for the application.

An external clock source may also be connected to the OSC1 pin in the HS mode, as shown in Figure 2-2.

FIGURE 2-2: EXTERNAL CLOCK INPUT
OPERATION
(HS OSCILLATOR
CONFIGURATION)




#### 2.3 External Clock Input

The EC and ECIO Oscillator modes require an external clock source to be connected to the OSC1 pin. There is no oscillator start-up time required after a Power-on Reset or after an exit from Sleep mode.


In the EC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic. Figure 2-3 shows the pin connections for the EC Oscillator mode.

FIGURE 2-3: EXTERNAL CLOCK INPUT OPERATION (EC CONFIGURATION)



The ECIO Oscillator mode functions like the EC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6). Figure 2-4 shows the pin connections for the ECIO Oscillator mode.

FIGURE 2-4: EXTERNAL CLOCK INPUT OPERATION (ECIO CONFIGURATION)



#### 2.4 RC Oscillator

For timing insensitive applications, the "RC" and "RCIO" device options offer additional cost savings. The actual oscillator frequency is a function of several factors:


- · supply voltage
- values of the external resistor (REXT) and capacitor (CEXT)
- · operating temperature

Given the same device, operating voltage and temperature and component values, there will also be unit-to-unit frequency variations. These are due to factors such as:

- · normal manufacturing variation
- difference in lead frame capacitance between package types (especially for low CEXT values)
- variations within the tolerance of limits of REXT and CEXT


In the RC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic. Figure 2-5 shows how the R/C combination is connected.

FIGURE 2-5: RC OSCILLATOR MODE



The RCIO Oscillator mode (Figure 2-6) functions like the RC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6).

FIGURE 2-6: RCIO OSCILLATOR MODE



#### 2.5 PLL Frequency Multiplier


A Phase Locked Loop (PLL) circuit is provided as an option for users who wish to use a lower frequency oscillator circuit or to clock the device up to its highest rated frequency from a crystal oscillator. This may be useful for customers who are concerned with EMI due to high-frequency crystals or users who require higher clock speeds from an internal oscillator.

#### 2.5.1 HSPLL OSCILLATOR MODE

The HSPLL mode makes use of the HS mode oscillator for frequencies up to 10 MHz. A PLL then multiplies the oscillator output frequency by 4 to produce an internal clock frequency up to 40 MHz. The PLLEN bit is not available in this oscillator mode.

The PLL is only available to the crystal oscillator when the FOSC3:FOSC0 configuration bits are programmed for HSPLL mode (= 0110).

FIGURE 2-7: PLL BLOCK DIAGRAM (HS MODE)



#### 2.5.2 PLL AND INTOSC

The PLL is also available to the internal oscillator block in selected oscillator modes. In this configuration, the PLL is enabled in software and generates a clock output of up to 32 MHz. The operation of INTOSC with the PLL is described in **Section 2.6.4** "PLL in INTOSC **Modes**".

#### 2.6 Internal Oscillator Block

The PIC18F2X1X/4X1X devices include an internal oscillator block which generates two different clock signals; either can be used as the microcontroller's clock source. This may eliminate the need for external oscillator circuits on the OSC1 and/or OSC2 pins.

The main output (INTOSC) is an 8 MHz clock source, which can be used to directly drive the device clock. It also drives a postscaler, which can provide a range of clock frequencies from 31 kHz to 4 MHz. The INTOSC output is enabled when a clock frequency from 125 kHz to 8 MHz is selected.

The other clock source is the internal RC oscillator (INTRC), which provides a nominal 31 kHz output. INTRC is enabled if it is selected as the device clock source; it is also enabled automatically when any of the following are enabled:

- · Power-up Timer
- · Fail-Safe Clock Monitor
- · Watchdog Timer
- Two-Speed Start-up

These features are discussed in greater detail in Section 22.0 "Special Features of the CPU".

The clock source frequency (INTOSC direct, INTRC direct or INTOSC postscaler) is selected by configuring the IRCF bits of the OSCCON register (page 30).

#### 2.6.1 INTIO MODES

Using the internal oscillator as the clock source eliminates the need for up to two external oscillator pins, which can then be used for digital I/O. Two distinct configurations are available:

- In INTIO1 mode, the OSC2 pin outputs Fosc/4, while OSC1 functions as RA7 for digital input and output.
- In INTIO2 mode, OSC1 functions as RA7 and OSC2 functions as RA6, both for digital input and output.

#### 2.6.2 INTOSC OUTPUT FREQUENCY

The internal oscillator block is calibrated at the factory to produce an INTOSC output frequency of 8.0 MHz.

The INTRC oscillator operates independently of the INTOSC source. Any changes in INTOSC across voltage and temperature are not necessarily reflected by changes in INTRC and vice versa.

#### 2.6.3 OSCTUNE REGISTER

The internal oscillator's output has been calibrated at the factory but can be adjusted in the user's application. This is done by writing to the OSCTUNE register (Register 2-1). The tuning sensitivity is constant throughout the tuning range. When the OSCTUNE register is modified, the INTOSC frequency will begin shifting to the new frequency. The INTRC clock will reach the new frequency within 8 clock cycles (approximately 8 \* 32  $\mu$ s = 256  $\mu$ s). The INTOSC clock will stabilize within 1 ms. Code execution continues during this shift. There is no indication that the shift has occurred.

The OSCTUNE register also implements the INTSRC and PLLEN bits, which control certain features of the internal oscillator block. The INTSRC bit allows users to select which internal oscillator provides the clock source when the 31 kHz frequency option is selected. This is covered in greater detail in **Section 2.7.1** "Oscillator Control Register".

The PLLEN bit controls the operation of the frequency multiplier, PLL, in internal oscillator modes.

#### 2.6.4 PLL IN INTOSC MODES

The 4x frequency multiplier can be used with the internal oscillator block to produce faster device clock speeds than are normally possible with an internal oscillator. When enabled, the PLL produces a clock speed of up to 32 MHz.

Unlike HSPLL mode, the PLL is controlled through software. The control bit, PLLEN (OSCTUNE<6>), is used to enable or disable its operation.

The PLL is available when the device is configured to use the internal oscillator block as its primary clock source (FOSC3:FOSC0 = 1001 or 1000). Additionally, the PLL will only function when the selected output frequency is either 4 MHz or 8 MHz (OSCCON<6:4> = 111 or 110). If both of these conditions are not met, the PLL is disabled.

The PLLEN control bit is only functional in those internal oscillator modes where the PLL is available. In all other modes, it is forced to '0' and is effectively unavailable.

#### 2.6.5 INTOSC FREQUENCY DRIFT

The factory calibrates the internal oscillator block output (INTOSC) for 8 MHz. However, this frequency may drift as VDD or temperature changes, which can affect the controller operation in a variety of ways. It is possible to adjust the INTOSC frequency by modifying the value in the OSCTUNE register. This has no effect on the INTRC clock source frequency.

Tuning the INTOSC source requires knowing when to make the adjustment, in which direction it should be made and in some cases, how large a change is needed. Three compensation techniques are discussed in Section 2.6.5.1 "Compensating with the USART", Section 2.6.5.2 "Compensating with the Timers" and Section 2.6.5.3 "Compensating with the CCP Module in Capture Mode", but other techniques may be used.

#### REGISTER 2-1: **OSCTUNE: OSCILLATOR TUNING REGISTER**

| R/W-0  | R/W-0 <sup>(1)</sup> | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|--------|----------------------|-----|-------|-------|-------|-------|-------|
| INTSRC | PLLEN <sup>(1)</sup> | _   | TUN4  | TUN3  | TUN2  | TUN1  | TUN0  |
| bit 7  |                      |     |       |       |       |       | bit 0 |

bit 0

bit 7 INTSRC: Internal Oscillator Low-Frequency Source Select bit

1 = 31.25 kHz device clock derived from 8 MHz INTOSC source (divide-by-256 enabled)

0 = 31 kHz device clock derived directly from INTRC internal oscillator

bit 6 PLLEN: Frequency Multiplier PLL for INTOSC Enable bit<sup>(1)</sup>

1 = PLL enabled for INTOSC (4 MHz and 8 MHz only)

0 = PLL disabled

Note 1: Available only in certain oscillator configurations; otherwise, this bit is unavailable and reads as '0'. See Section 2.6.4 "PLL in INTOSC Modes" for details.

bit 5 Unimplemented: Read as '0'

bit 4-0 TUN4:TUN0: Frequency Tuning bits

01111 = Maximum frequency

00001

00000 = Center frequency. Oscillator module is running at the calibrated frequency.

11111

10000 = Minimum frequency

#### Legend:

W = Writable bit R = Readable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 2.6.5.1 Compensating with the USART

An adjustment may be required when the USART begins to generate framing errors or receives data with errors while in Asynchronous mode. Framing errors indicate that the device clock frequency is too high; to adjust for this, decrement the value in OSCTUNE to reduce the clock frequency. On the other hand, errors in data may suggest that the clock speed is too low; to compensate, increment OSCTUNE to increase the clock frequency.

#### 2.6.5.2 Compensating with the Timers

This technique compares device clock speed to some reference clock. Two timers may be used; one timer is clocked by the peripheral clock, while the other is clocked by a fixed reference source, such as the Timer1 oscillator.

Both timers are cleared, but the timer clocked by the reference generates interrupts. When an interrupt occurs, the internally clocked timer is read and both timers are cleared. If the internally clocked timer value is greater than expected, then the internal oscillator block is running too fast. To adjust for this, decrement the OSCTUNE register.

#### 2.6.5.3 Compensating with the CCP Module in Capture Mode

A CCP module can use free running Timer1 (or Timer3), clocked by the internal oscillator block and an external event with a known period (i.e., AC power frequency). The time of the first event is captured in the CCPRxH:CCPRxL registers and is recorded for use later. When the second event causes a capture, the time of the first event is subtracted from the time of the second event. Since the period of the external event is known, the time difference between events can be calculated.

If the measured time is much greater than the calculated time, the internal oscillator block is running too fast; to compensate, decrement the OSCTUNE register. If the measured time is much less than the calculated time, the internal oscillator block is running too slow; to compensate, increment the OSCTUNE register.

#### 2.7 Clock Sources and Oscillator Switching

Like previous PIC18 devices, the PIC18F2X1X/4X1X family includes a feature that allows the device clock source to be switched from the main oscillator to an alternate low-frequency clock source. PIC18F2X1X/4X1X devices offer two alternate clock sources. When an alternate clock source is enabled, the various power managed operating modes are available.

Essentially, there are three clock sources for these devices:

- · Primary oscillators
- · Secondary oscillators
- · Internal oscillator block

The **primary oscillators** include the External Crystal and Resonator modes, the External RC modes, the External Clock modes and the internal oscillator block. The particular mode is defined by the FOSC3:FOSC0 configuration bits. The details of these modes are covered earlier in this chapter.

The **secondary oscillators** are those external sources not connected to the OSC1 or OSC2 pins. These sources may continue to operate even after the controller is placed in a power managed mode.

PIC18F2X1X/4X1X devices offer the Timer1 oscillator as a secondary oscillator. This oscillator, in all power managed modes, is often the time base for functions such as a real-time clock.

Most often, a 32.768 kHz watch crystal is connected between the RC0/T10S0/T13CKI and RC1/T10SI pins. Like the LP mode oscillator circuit, loading capacitors are also connected from each pin to ground.

The Timer1 oscillator is discussed in greater detail in **Section 11.3** "Timer1 Oscillator".

In addition to being a primary clock source, the **internal oscillator block** is available as a power managed mode clock source. The INTRC source is also used as the clock source for several special features, such as the WDT and Fail-Safe Clock Monitor.

The clock sources for the PIC18F2X1X/4X1X devices are shown in Figure 2-8. See **Section 22.0** "**Special Features of the CPU**" for Configuration register details.




FIGURE 2-8: PIC18F2X1X/4X1X CLOCK DIAGRAM

#### 2.7.1 OSCILLATOR CONTROL REGISTER

The OSCCON register (Register 2-2) controls several aspects of the device clock's operation, both in full power operation and in power managed modes.

The System Clock Select bits, SCS1:SCS0, select the clock source. The available clock sources are the primary clock (defined by the FOSC3:FOSC0 configuration bits), the secondary clock (Timer1 oscillator) and the internal oscillator block. The clock source changes immediately after one or more of the bits is written to, following a brief clock transition interval. The SCS bits are cleared on all forms of Reset.

The Internal Oscillator Frequency Select bits (IRCF2:IRCF0) select the frequency output of the internal oscillator block to drive the device clock. The choices are the INTRC source, the INTOSC source (8 MHz) or one of the frequencies derived from the INTOSC postscaler (31.25 kHz to 4 MHz). If the internal oscillator block is supplying the device clock, changing the states of these bits will have an immediate change on the internal oscillator's output. On device Resets, the default output frequency of the internal oscillator block is set at 1 MHz.

When a nominal output frequency of 31 kHz is selected (IRCF2:IRCF0 = 000), users may choose which internal oscillator acts as the source. This is done with the INTSRC bit in the OSCTUNE register (OSCTUNE<7>). Setting this bit selects INTOSC as a 31.25 kHz clock source by enabling the divide-by-256 output of the INTOSC postscaler. Clearing INTSRC selects INTRC (nominally 31 kHz) as the clock source.

This option allows users to select the tunable and more precise INTOSC as a clock source, while maintaining power savings with a very low clock speed. Regardless of the setting of INTSRC, INTRC always remains the clock source for features such as the Watchdog Timer and the Fail-Safe Clock Monitor.

The OSTS, IOFS and T1RUN bits indicate which clock source is currently providing the device clock. The OSTS bit indicates that the Oscillator Start-up Timer has timed out and the primary clock is providing the device clock in primary clock modes. The IOFS bit indicates when the internal oscillator block has stabilized and is providing the device clock in RC Clock modes. The T1RUN bit (T1CON<6>) indicates when the Timer1 oscillator is providing the device clock in secondary clock modes. In power managed modes, only one of these three bits will be set at any time. If none of these bits are set, the INTRC is providing the clock or the internal oscillator block has just started and is not yet stable.

The IDLEN bit determines if the device goes into Sleep mode or one of the Idle modes when the SLEEP instruction is executed.

The use of the flag and control bits in the OSCCON register is discussed in more detail in **Section 3.0** "Power Managed Modes".

- Note 1: The Timer1 oscillator must be enabled to select the secondary clock source. The Timer1 oscillator is enabled by setting the T1OSCEN bit in the Timer1 Control register (T1CON<3>). If the Timer1 oscillator is not enabled, then any attempt to select a secondary clock source will be ignored.
  - 2: It is recommended that the Timer1 oscillator be operating and stable before selecting the secondary clock source or a very long delay may occur while the Timer1 oscillator starts.

#### 2.7.2 OSCILLATOR TRANSITIONS

PIC18F2X1X/4X1X devices contain circuitry to prevent clock "glitches" when switching between clock sources. A short pause in the device clock occurs during the clock switch. The length of this pause is the sum of two cycles of the old clock source and three to four cycles of the new clock source. This formula assumes that the new clock source is stable.

Clock transitions are discussed in greater detail in **Section 3.1.2 "Entering Power Managed Modes"**.

#### OSCCON: OSCILLATOR CONTROL REGISTER **REGISTER 2-2:**

| R/W-0 | R/W-1 | R/W-0 | R/W-0 | R <sup>(1)</sup> | R-0  | R/W-0 | R/W-0 |
|-------|-------|-------|-------|------------------|------|-------|-------|
| IDLEN | IRCF2 | IRCF1 | IRCF0 | OSTS             | IOFS | SCS1  | SCS0  |
| bit 7 |       |       |       |                  |      |       | bit 0 |

bit 0

- bit 7 IDLEN: Idle Enable bit
  - 1 = Device enters Idle mode on SLEEP instruction
  - 0 = Device enters Sleep mode on SLEEP instruction
- bit 6-4 IRCF2:IRCF0: Internal Oscillator Frequency Select bits
  - 111 = 8 MHz (INTOSC drives clock directly)
  - 110 **= 4 MHz**
  - 101 = 2 MHz
  - 100 = 1 MHz<sup>(3)</sup>
  - 011 = 500 kHz
  - 010 = 250 kHz
  - 001 = 125 kHz
  - 000 = 31 kHz (from either INTOSC/256 or INTRC directly)(2)
- OSTS: Oscillator Start-up Time-out Status bit(1) bit 3
  - 1 = Oscillator start-up time-out timer has expired; primary oscillator is running
  - 0 = Oscillator start-up time-out timer is running; primary oscillator is not ready
- bit 2 IOFS: INTOSC Frequency Stable bit
  - 1 = INTOSC frequency is stable
  - 0 = INTOSC frequency is not stable
- bit 1-0 SCS1:SCS0: System Clock Select bits
  - 1x = Internal oscillator block
  - 01 = Secondary (Timer1) oscillator
  - 00 = Primary oscillator
    - Note 1: Reset state depends on state of the IESO configuration bit.
      - 2: Source selected by the INTSRC bit (OSCTUNE<7>), see text.
      - 3: Default output frequency of INTOSC on Reset.

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### 2.8 Effects of Power Managed Modes on the Various Clock Sources

When PRI\_IDLE mode is selected, the designated primary oscillator continues to run without interruption. For all other power managed modes, the oscillator using the OSC1 pin is disabled. The OSC1 pin (and OSC2 pin, if used by the oscillator) will stop oscillating.

In secondary clock modes (SEC\_RUN and SEC\_IDLE), the Timer1 oscillator is operating and providing the device clock. The Timer1 oscillator may also run in all power managed modes if required to clock Timer1 or Timer3.

In internal oscillator modes (RC\_RUN and RC\_IDLE), the internal oscillator block provides the device clock source. The 31 kHz INTRC output can be used directly to provide the clock and may be enabled to support various special features, regardless of the power managed mode (see Section 22.2 "Watchdog Timer (WDT)", Section 22.3 "Two-Speed Start-up" and Section 22.4 "Fail-Safe Clock Monitor" for more information on WDT, Fail-Safe Clock Monitor and Two-Speed Start-up). The INTOSC output at 8 MHz may be used directly to clock the device or may be divided down by the postscaler. The INTOSC output is disabled if the clock is provided directly from the INTRC output.

If the Sleep mode is selected, all clock sources are stopped. Since all the transistor switching currents have been stopped, Sleep mode achieves the lowest current consumption of the device (only leakage currents).

Enabling any on-chip feature that will operate during Sleep will increase the current consumed during Sleep. The INTRC is required to support WDT operation. The Timer1 oscillator may be operating to support a realtime clock. Other features may be operating that do not require a device clock source (i.e., SSP slave, PSP, INTn pins and others). Peripherals that may add significant current consumption are listed in **Section 25.2 "DC Characteristics".** 

#### 2.9 Power-up Delays

Power-up delays are controlled by two timers, so that no external Reset circuitry is required for most applications. The delays ensure that the device is kept in Reset until the device power supply is stable under normal circumstances and the primary clock is operating and stable. For additional information on power-up delays, see **Section 4.5** "**Device Reset Timers**".

The first timer is the Power-up Timer (PWRT), which provides a fixed delay on power-up (parameter 33, Table 25-10). It is enabled by clearing (= 0) the PWRTEN configuration bit.

The second timer is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable (LP, XT and HS modes). The OST does this by counting 1024 oscillator cycles before allowing the oscillator to clock the device.

When the HSPLL Oscillator mode is selected, the device is kept in Reset for an additional 2 ms, following the HS mode OST delay, so the PLL can lock to the incoming clock frequency.

There is a delay of interval TCSD (parameter 38, Table 25-10), following POR, while the controller becomes ready to execute instructions. This delay runs concurrently with any other delays. This may be the only delay that occurs when any of the EC, RC or INTIO modes are used as the primary clock source.

TABLE 2-3: OSC1 AND OSC2 PIN STATES IN SLEEP MODE

| Oscillator Mode | OSC1 Pin  | OSC2 Pin  |  |  |
|-----------------|---|---|--|--|
| RC, INTIO1      | Floating, external resistor should pull high          | At logic low (clock/4 output)                         |  |  |
| RCIO            | Floating, external resistor should pull high          | Configured as PORTA, bit 6                            |  |  |
| INTIO2          | Configured as PORTA, bit 7                            | Configured as PORTA, bit 6                            |  |  |
| ECIO            | Floating, pulled by external clock                    | Configured as PORTA, bit 6                            |  |  |
| EC              | Floating, pulled by external clock                    | At logic low (clock/4 output)                         |  |  |
| LP, XT and HS   | Feedback inverter disabled at quiescent voltage level | Feedback inverter disabled at quiescent voltage level |  |  |

Note: See Table 4-2 in Section 4.0 "Reset" for time-outs due to Sleep and MCLR Reset.

NOTES:

#### 3.0 POWER MANAGED MODES

PIC18F2X1X/4X1X devices offer a total of seven operating modes for more efficient power management. These modes provide a variety of options for selective power conservation in applications where resources may be limited (i.e., battery-powered devices).

There are three categories of power managed modes:

- · Run modes
- · Idle modes
- · Sleep mode

These categories define which portions of the device are clocked and sometimes, what speed. The Run and Idle modes may use any of the three available clock sources (primary, secondary or internal oscillator block); the Sleep mode does not use a clock source.

The power managed modes include several power-saving features offered on previous PICmicro® devices. One is the clock switching feature, offered in other PIC18 devices, allowing the controller to use the Timer1 oscillator in place of the primary oscillator. Also included is the Sleep mode, offered by all PICmicro devices, where all device clocks are stopped.

#### 3.1 Selecting Power Managed Modes

Selecting a power managed mode requires two decisions: if the CPU is to be clocked or not and the selection of a clock source. The IDLEN bit (OSCCON<7>) controls CPU clocking, while the SCS1:SCS0 bits (OSCCON<1:0>) select the clock source. The individual modes, bit settings, clock sources and affected modules are summarized in Table 3-1.

#### 3.1.1 CLOCK SOURCES

The SCS1:SCS0 bits allow the selection of one of three clock sources for power managed modes. They are:

- the primary clock, as defined by the FOSC3:FOSC0 configuration bits
- the secondary clock (the Timer1 oscillator)
- the internal oscillator block (for RC modes)

### 3.1.2 ENTERING POWER MANAGED MODES

Switching from one power managed mode to another begins by loading the OSCCON register. The SCS1:SCS0 bits select the clock source and determine which Run or Idle mode is to be used. Changing these bits causes an immediate switch to the new clock source, assuming that it is running. The switch may also be subject to clock transition delays. These are discussed in Section 3.1.3 "Clock Transitions and Status Indicators" and subsequent sections.

Entry to the Power Managed Idle or Sleep modes is triggered by the execution of a SLEEP instruction. The actual mode that results depends on the status of the IDLEN bit.

Depending on the current mode and the mode being switched to, a change to a power managed mode does not always require setting all of these bits. Many transitions may be done by changing the oscillator select bits, or changing the IDLEN bit, prior to issuing a SLEEP instruction. If the IDLEN bit is already configured correctly, it may only be necessary to perform a SLEEP instruction to switch to the desired mode.

TABLE 3-1: POWER MANAGED MODES

|          | osco                        | CON Bits           | Module  | Clocking    |  |
|----------|-----------------------------|--------------------|---------|-------------|--|
| Mode     | IDLEN <sup>(1)</sup><br><7> | SCS1:SCS0<br><1:0> | CPU     | Peripherals | Available Clock and Oscillator Source  |
| Sleep    | 0                           | N/A                | Off     | Off         | None – All clocks are disabled   |
| PRI_RUN  | N/A                         | 00                 | Clocked | Clocked     | Primary – LP, XT, HS, HSPLL, RC, EC and Internal Oscillator Block <sup>(2)</sup> . This is the normal full power execution mode. |
| SEC_RUN  | N/A                         | 01                 | Clocked | Clocked     | Secondary - Timer1 Oscillator  |
| RC_RUN   | N/A                         | 1x                 | Clocked | Clocked     | Internal Oscillator Block <sup>(2)</sup>   |
| PRI_IDLE | 1                           | 00                 | Off     | Clocked     | Primary – LP, XT, HS, HSPLL, RC, EC  |
| SEC_IDLE | 1                           | 01                 | Off     | Clocked     | Secondary - Timer1 Oscillator  |
| RC_IDLE  | 1                           | 1x                 | Off     | Clocked     | Internal Oscillator Block <sup>(2)</sup>   |

Note 1: IDLEN reflects its value when the SLEEP instruction is executed.

2: Includes INTOSC and INTOSC postscaler, as well as the INTRC source.

### 3.1.3 CLOCK TRANSITIONS AND STATUS INDICATORS

The length of the transition between clock sources is the sum of two cycles of the old clock source and three to four cycles of the new clock source. This formula assumes that the new clock source is stable.

Three bits indicate the current clock source and its status. They are:

- OSTS (OSCCON<3>)
- IOFS (OSCCON<2>)
- T1RUN (T1CON<6>)

In general, only one of these bits will be set while in a given power managed mode. When the OSTS bit is set, the primary clock is providing the device clock. When the IOFS bit is set, the INTOSC output is providing a stable 8 MHz clock source to a divider that actually drives the device clock. When the T1RUN bit is set, the Timer1 oscillator is providing the clock. If none of these bits are set, then either the INTRC clock source is clocking the device, or the INTOSC source is not yet stable.

If the internal oscillator block is configured as the primary clock source by the FOSC3:FOSC0 configuration bits, then both the OSTS and IOFS bits may be set when in PRI\_RUN or PRI\_IDLE modes. This indicates that the primary clock (INTOSC output) is generating a stable 8 MHz output. Entering another RC Power Managed mode at the same frequency would clear the OSTS bit.

- Note 1: Caution should be used when modifying a single IRCF bit. If VDD is less than 3V, it is possible to select a higher clock speed than is supported by the low VDD. Improper device operation may result if the VDD/Fosc specifications are violated.
  - 2: Executing a SLEEP instruction does not necessarily place the device into Sleep mode. It acts as the trigger to place the controller into either the Sleep mode or one of the Idle modes, depending on the setting of the IDLEN bit.

#### 3.1.4 MULTIPLE SLEEP COMMANDS

The power managed mode that is invoked with the SLEEP instruction is determined by the setting of the IDLEN bit at the time the instruction is executed. If another SLEEP instruction is executed, the device will enter the power managed mode specified by IDLEN at that time. If IDLEN has changed, the device will enter the new power managed mode specified by the new setting.

#### 3.2 Run Modes

In the Run modes, clocks to both the core and peripherals are active. The difference between these modes is the clock source.

#### 3.2.1 PRI RUN MODE

The PRI\_RUN mode is the normal, full power execution mode of the microcontroller. This is also the default mode upon a device Reset, unless Two-Speed Start-up is enabled (see **Section 22.3** "Two-Speed Start-up" for details). In this mode, the OSTS bit is set. The IOFS bit may be set if the internal oscillator block is the primary clock source (see **Section 2.7.1** "Oscillator Control Register").

#### 3.2.2 SEC RUN MODE

result.


The SEC\_RUN mode is the compatible mode to the "clock switching" feature offered in other PIC18 devices. In this mode, the CPU and peripherals are clocked from the Timer1 oscillator. This gives users the option of lower power consumption while still using a high accuracy clock source.

SEC\_RUN mode is entered by setting the SCS1:SCS0 bits to '01'. The device clock source is switched to the Timer1 oscillator (see Figure 3-1), the primary oscillator is shut down, the T1RUN bit (T1CON<6>) is set and the OSTS bit is cleared.


Note: The Timer1 oscillator should already be running prior to entering SEC\_RUN mode. If the T1OSCEN bit is not set when the SCS1:SCS0 bits are set to '01', entry to SEC\_RUN mode will not occur. If the Timer1 oscillator is enabled but not yet running, device clocks will be delayed until the oscillator has started. In such situations, initial oscillator operation is far from stable and unpredictable operation may

On transitions from SEC\_RUN mode to PRI\_RUN, the peripherals and CPU continue to be clocked from the Timer1 oscillator while the primary clock is started. When the primary clock becomes ready, a clock switch back to the primary clock occurs (see Figure 3-2). When the clock switch is complete, the T1RUN bit is cleared, the OSTS bit is set and the primary clock is providing the clock. The IDLEN and SCS bits are not affected by the wake-up; the Timer1 oscillator continues to run.





## FIGURE 3-2: TRANSITION TIMING FROM SEC\_RUN MODE TO PRI\_RUN MODE (HSPLL)



## 3.2.3 RC\_RUN MODE

In RC\_RUN mode, the CPU and peripherals are clocked from the internal oscillator block using the INTOSC multiplexer. In this mode, the primary clock is shut down. When using the INTRC source, this mode provides the best power conservation of all the Run modes, while still executing code. It works well for user applications which are not highly timing sensitive or do not require high-speed clocks at all times.

If the primary clock source is the internal oscillator block (either INTRC or INTOSC), there are no distinguishable differences between PRI\_RUN and RC\_RUN modes during execution. However, a clock switch delay will occur during entry to and exit from RC\_RUN mode. Therefore, if the primary clock source is the internal oscillator block, the use of RC\_RUN mode is not recommended.

This mode is entered by setting SCS1 to '1'. Although it is ignored, it is recommended that SCS0 also be cleared; this is to maintain software compatibility with future devices. When the clock source is switched to the INTOSC multiplexer (see Figure 3-3), the primary oscillator is shut down and the OSTS bit is cleared. The IRCF bits may be modified at any time to immediately change the clock speed.

Note: Caution should be used when modifying a single IRCF bit. If VDD is less than 3V, it is possible to select a higher clock speed than is supported by the low VDD. Improper device operation may result if the VDD/FOSC specifications are violated.


If the IRCF bits and the INTSRC bit are all clear, the INTOSC output is not enabled and the IOFS bit will remain clear; there will be no indication of the current clock source. The INTRC source is providing the device clocks.

If the IRCF bits are changed from all clear (thus, enabling the INTOSC output) or if INTSRC is set, the IOFS bit becomes set after the INTOSC output becomes stable. Clocks to the device continue while the INTOSC source stabilizes after an interval of TIOBST.


If the IRCF bits were previously at a non-zero value, or if INTSRC was set before setting SCS1 and the INTOSC source was already stable, the IOFS bit will remain set.

On transitions from RC\_RUN mode to PRI\_RUN mode, the device continues to be clocked from the INTOSC multiplexer while the primary clock is started. When the primary clock becomes ready, a clock switch to the primary clock occurs (see Figure 3-4). When the clock switch is complete, the IOFS bit is cleared, the OSTS bit is set and the primary clock is providing the device clock. The IDLEN and SCS bits are not affected by the switch. The INTRC source will continue to run if either the WDT or the Fail-Safe Clock Monitor is enabled.

## FIGURE 3-3: TRANSITION TIMING TO RC RUN MODE



## FIGURE 3-4: TRANSITION TIMING FROM RC\_RUN MODE TO PRI\_RUN MODE



## 3.3 Sleep Mode

The Power Managed Sleep mode in the PIC18F2X1X/4X1X devices is identical to the legacy Sleep mode offered in all other PICmicro devices. It is entered by clearing the IDLEN bit (the default state on device Reset) and executing the SLEEP instruction. This shuts down the selected oscillator (Figure 3-5). All clock source status bits are cleared.

Entering the Sleep mode from any other mode does not require a clock switch. This is because no clocks are needed once the controller has entered Sleep. If the WDT is selected, the INTRC source will continue to operate. If the Timer1 oscillator is enabled, it will also continue to run.

When a wake event occurs in Sleep mode (by interrupt, Reset or WDT time-out), the device will not be clocked until the clock source selected by the SCS1:SCS0 bits becomes ready (see Figure 3-6), or it will be clocked from the internal oscillator block if either the Two-Speed Start-up or the Fail-Safe Clock Monitor are enabled (see Section 22.0 "Special Features of the CPU"). In either case, the OSTS bit is set when the primary clock is providing the device clocks. The IDLEN and SCS bits are not affected by the wake-up.

## 3.4 Idle Modes

The Idle modes allow the controller's CPU to be selectively shut down while the peripherals continue to operate. Selecting a particular Idle mode allows users to further manage power consumption.

If the IDLEN bit is set to a '1' when a SLEEP instruction is executed, the peripherals will be clocked from the clock source selected using the SCS1:SCS0 bits; however, the CPU will not be clocked. The clock source status bits are not affected. Setting IDLEN and executing a SLEEP instruction provides a quick method of switching from a given Run mode to its corresponding Idle mode.

If the WDT is selected, the INTRC source will continue to operate. If the Timer1 oscillator is enabled, it will also continue to run.

Since the CPU is not executing instructions, the only exits from any of the Idle modes are by interrupt, WDT time-out or a Reset. When a wake event occurs, CPU execution is delayed by an interval of TCSD (parameter 38, Table 25-10) while it becomes ready to execute code. When the CPU begins executing code, it resumes with the same clock source for the current Idle mode. For example, when waking from RC\_IDLE mode, the internal oscillator block will clock the CPU and peripherals (in other words, RC\_RUN mode). The IDLEN and SCS bits are not affected by the wake-up.

While in any Idle mode or the Sleep mode, a WDT timeout will result in a WDT wake-up to the Run mode currently specified by the SCS1:SCS0 bits.

Peripheral Clock Sleep PC PC+2

PLL Clock Output

CPU Clock
Peripheral Clock
Program Counter

Wake Event

OSC1 DST bit set

Note 1: Tost = 1024 Tosc; TPLL = 2 ms (approx). These intervals are not shown to scale.

## 3.4.1 PRI\_IDLE MODE

This mode is unique among the three low-power Idle modes, in that it does not disable the primary device clock. For timing sensitive applications, this allows for the fastest resumption of device operation with its more accurate primary clock source, since the clock source does not have to "warm up" or transition from another oscillator.

PRI\_IDLE mode is entered from PRI\_RUN mode by setting the IDLEN bit and executing a SLEEP instruction. If the device is in another Run mode, set IDLEN first, then clear the SCS bits and execute SLEEP. Although the CPU is disabled, the peripherals continue to be clocked from the primary clock source specified by the FOSC3:FOSC0 configuration bits. The OSTS bit remains set (see Figure 3-7).


When a wake event occurs, the CPU is clocked from the primary clock source. A delay of interval Tcsp is required between the wake event and when code execution starts. This is required to allow the CPU to become ready to execute instructions. After the wake-up, the OSTS bit remains set. The IDLEN and SCS bits are not affected by the wake-up (see Figure 3-8).

## 3.4.2 SEC\_IDLE MODE

In SEC\_IDLE mode, the CPU is disabled but the peripherals continue to be clocked from the Timer1 oscillator. This mode is entered from SEC\_RUN by setting the IDLEN bit and executing a SLEEP instruction. If the device is in another Run mode, set IDLEN first, then set SCS1:SCS0 to '01' and execute SLEEP. When the clock source is switched to the Timer1 oscillator, the primary oscillator is shut down, the OSTS bit is cleared and the T1RUN bit is set.

When a wake event occurs, the peripherals continue to be clocked from the Timer1 oscillator. After an interval of TCSD following the wake event, the CPU begins executing code being clocked by the Timer1 oscillator. The IDLEN and SCS bits are not affected by the wake-up; the Timer1 oscillator continues to run (see Figure 3-8).

Note: The Timer1 oscillator should already be running prior to entering SEC\_IDLE mode. If the T1OSCEN bit is not set when the SLEEP instruction is executed, the SLEEP instruction will be ignored and entry to SEC\_IDLE mode will not occur. If the Timer1 oscillator is enabled but not yet running, peripheral clocks will be delayed until the oscillator has started. In such situations, initial oscillator operation is far from stable and unpredictable operation may result.







FIGURE 3-8: TRANSITION TIMING FOR WAKE FROM IDLE TO RUN MODE



### 3.4.3 RC IDLE MODE

In RC\_IDLE mode, the CPU is disabled but the peripherals continue to be clocked from the internal oscillator block using the INTOSC multiplexer. This mode allows for controllable power conservation during Idle periods.

From RC\_RUN, this mode is entered by setting the IDLEN bit and executing a SLEEP instruction. If the device is in another Run mode, first set IDLEN, then set the SCS1 bit and execute SLEEP. Although its value is ignored, it is recommended that SCS0 also be cleared; this is to maintain software compatibility with future devices. The INTOSC multiplexer may be used to select a higher clock frequency by modifying the IRCF bits before executing the SLEEP instruction. When the clock source is switched to the INTOSC multiplexer, the primary oscillator is shut down and the OSTS bit is cleared.

If the IRCF bits are set to any non-zero value, or the INTSRC bit is set, the INTOSC output is enabled. The IOFS bit becomes set, after the INTOSC output becomes stable, after an interval of TIOBST (parameter 39, Table 25-10). Clocks to the peripherals continue while the INTOSC source stabilizes. If the IRCF bits were previously at a non-zero value, or INTSRC was set before the SLEEP instruction was executed and the INTOSC source was already stable, the IOFS bit will remain set. If the IRCF bits and INTSRC are all clear, the INTOSC output will not be enabled, the IOFS bit will remain clear and there will be no indication of the current clock source.

When a wake event occurs, the peripherals continue to be clocked from the INTOSC multiplexer. After a delay of TCSD following the wake event, the CPU begins executing code being clocked by the INTOSC multiplexer. The IDLEN and SCS bits are not affected by the wake-up. The INTRC source will continue to run if either the WDT or the Fail-Safe Clock Monitor is enabled.

## 3.5 Exiting Idle and Sleep Modes

An exit from Sleep mode or any of the Idle modes is triggered by an interrupt, a Reset or a WDT time-out. This section discusses the triggers that cause exits from power managed modes. The clocking subsystem actions are discussed in each of the power managed modes (see Section 3.2 "Run Modes", Section 3.3 "Sleep Mode" and Section 3.4 "Idle Modes").

## 3.5.1 EXIT BY INTERRUPT

Any of the available interrupt sources can cause the device to exit from an Idle mode or the Sleep mode to a Run mode. To enable this functionality, an interrupt source must be enabled by setting its enable bit in one of the INTCON or PIE registers. The exit sequence is initiated when the corresponding interrupt flag bit is set.

On all exits from Idle or Sleep modes by interrupt, code execution branches to the interrupt vector if the GIE/GIEH bit (INTCON<7>) is set. Otherwise, code execution continues or resumes without branching (see Section 8.0 "Interrupts").

A fixed delay of interval TCSD following the wake event is required when leaving Sleep and Idle modes. This delay is required for the CPU to prepare for execution. Instruction execution resumes on the first clock cycle following this delay.

### 3.5.2 EXIT BY WDT TIME-OUT

A WDT time-out will cause different actions depending on which power managed mode the device is in when the time-out occurs.

If the device is not executing code (all Idle modes and Sleep mode), the time-out will result in an exit from the power managed mode (see Section 3.2 "Run Modes" and Section 3.3 "Sleep Mode"). If the device is executing code (all Run modes), the time-out will result in a WDT Reset (see Section 22.2 "Watchdog Timer (WDT)").

The WDT timer and postscaler are cleared by executing a SLEEP or CLRWDT instruction, the loss of a currently selected clock source (if the Fail-Safe Clock Monitor is enabled) and modifying the IRCF bits in the OSCCON register if the internal oscillator block is the device clock source.

### 3.5.3 EXIT BY RESET

Normally, the device is held in Reset by the Oscillator Start-up Timer (OST) until the primary clock becomes ready. At that time, the OSTS bit is set and the device begins executing code. If the internal oscillator block is the new clock source, the IOFS bit is set instead.

The exit delay time from Reset to the start of code execution depends on both the clock sources before and after the wake-up and the type of oscillator if the new clock source is the primary clock. Exit delays are summarized in Table 3-2.

Code execution can begin before the primary clock becomes ready. If either the Two-Speed Start-up (see Section 22.3 "Two-Speed Start-up") or Fail-Safe Clock Monitor (see Section 22.4 "Fail-Safe Clock Monitor") is enabled, the device may begin execution as soon as the Reset source has cleared. Execution is clocked by the INTOSC multiplexer driven by the internal oscillator block. Execution is clocked by the internal oscillator block until either the primary clock becomes ready or a power managed mode is entered before the primary clock becomes ready; the primary clock is then shut down.

## 3.5.4 EXIT WITHOUT AN OSCILLATOR START-UP DELAY

Certain exits from power managed modes do not invoke the OST at all. There are two cases:

- PRI\_IDLE mode, where the primary clock source is not stopped; and
- the primary clock source is not any of the LP, XT, HS or HSPLL modes.

In these instances, the primary clock source either does not require an oscillator start-up delay since it is already running (PRI\_IDLE), or normally does not require an oscillator start-up delay (RC, EC and INTIO Oscillator modes). However, a fixed delay of interval TCSD following the wake event is still required when leaving Sleep and Idle modes to allow the CPU to prepare for execution. Instruction execution resumes on the first clock cycle following this delay.

TABLE 3-2: EXIT DELAY ON WAKE-UP BY RESET FROM SLEEP MODE OR ANY IDLE MODE (BY CLOCK SOURCES)

| Clock Source<br>before Wake-up       | Clock Source<br>after Wake-up | Exit Delay                 | Clock Ready Status<br>bit (OSCCON) |
|--------------------------------------|-------------------------------|----------------------------|------------------------------------|
|                                      | LP, XT, HS                    |                            |                                    |
| Drive and Devides Olerals            | HSPLL                         |                            | OSTS                               |
| Primary Device Clock (PRI_IDLE mode) | EC, RC                        | Tcsp <sup>(2)</sup>        |                                    |
| (FRI_IDEE Mode)                      | INTRC <sup>(1)</sup>          |                            | _                                  |
|                                      | INTOSC <sup>(3)</sup>         |                            | IOFS                               |
|                                      | LP, XT, HS                    | Tost <sup>(4)</sup>        |                                    |
| T1OSC or INTRC <sup>(1)</sup>        | HSPLL                         | Tost + t <sub>rc</sub> (4) | OSTS                               |
| 1103C OF INTROV                      | EC, RC                        | Tcsp <sup>(2)</sup>        |                                    |
|                                      | INTOSC <sup>(2)</sup>         | Tiobst <sup>(5)</sup>      | IOFS                               |
|                                      | LP, XT, HS                    | Tost <sup>(5)</sup>        |                                    |
| INTOSC <sup>(3)</sup>                | HSPLL                         | Tost + t <sub>rc</sub> (4) | OSTS                               |
| INTOSC <sup>(*)</sup>                | EC, RC                        | Tcsp <sup>(2)</sup>        | ]                                  |
|                                      | INTOSC <sup>(2)</sup>         | None                       | IOFS                               |
|                                      | LP, XT, HS                    | Tost <sup>(4)</sup>        |                                    |
| None                                 | HSPLL                         | Tost + t <sub>rc</sub> (4) | OSTS                               |
| (Sleep mode)                         | EC, RC                        | Tcsp <sup>(2)</sup>        | 1                                  |
|                                      | INTOSC <sup>(2)</sup>         | Tiobst <sup>(5)</sup>      | IOFS                               |

- **Note 1:** In this instance, refers specifically to the 31 kHz INTRC clock source.
  - 2: TCSD (parameter 38) is a required delay when waking from Sleep and all Idle modes and runs concurrently with any other required delays (see **Section 3.4 "Idle Modes"**). On Reset, INTOSC defaults to 1 MHz.
  - 3: Includes both the INTOSC 8 MHz source and postscaler derived frequencies.
  - **4:** Tost is the Oscillator Start-up Timer (parameter 32). t<sub>rc</sub> is the PLL Lock-out Timer (parameter F12); it is also designated as TPLL.
  - **5:** Execution continues during Tiobst (parameter 39), the INTOSC stabilization period.

#### 4.0 RESET

The PIC18F2X1X/4X1X devices differentiate between various kinds of Reset:

- Power-on Reset (POR)
- MCLR Reset during normal operation
- MCLR Reset during power managed modes
- Watchdog Timer (WDT) Reset (during execution)
- e) Programmable Brown-out Reset (BOR)
- f) **RESET Instruction**
- Stack Full Reset
- Stack Underflow Reset

This section discusses Resets generated by MCLR, POR and BOR and covers the operation of the various start-up timers. Stack Reset events are covered in Section 5.1.2.4 "Stack Full and Underflow Resets". WDT Resets are covered in Section 22.2 "Watchdog Timer (WDT)".


A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 4-1.

#### 4.1 **RCON Register**

Device Reset events are tracked through the RCON register (Register 4-1). The lower five bits of the register indicate that a specific Reset event has occurred. In most cases, these bits can only be cleared by the event and must be set by the application after the event. The state of these flag bits, taken together. can be read to indicate the type of Reset that just occurred. This is described in more detail in Section 4.6 "Reset State of Registers".

The RCON register also has control bits for setting interrupt priority (IPEN) and software control of the BOR (SBOREN). Interrupt priority is discussed in Section 8.0 "Interrupts". BOR is covered in Section 4.4 "Brown-out Reset (BOR)".

FIGURE 4-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



Note 1: This is the INTRC source from the internal oscillator block and is separate from the RC oscillator of the CLKI pin.

2: See Table 4-2 for time-out situations.

#### **REGISTER 4-1:** RCON: RESET CONTROL REGISTER

| R/W-0 | R/W-1 <sup>(1)</sup> | U-0 | R/W-1 | R-1 | R-1 | R/W-0 <sup>(2)</sup> | R/W-0 |   |
|-------|----------------------|-----|-------|-----|-----|----------------------|-------|---|
| IPEN  | SBOREN               | _   | RI    | TO  | PD  | POR                  | BOR   | Ī |
| bit 7 |                      |     |       |     |     |                      | bit 0 | _ |

bit 0

bit 7 IPEN: Interrupt Priority Enable bit

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (PIC16CXXX Compatibility mode)

**SBOREN:** BOR Software Enable bit<sup>(1)</sup> bit 6

If BOREN1:BOREN0 = 01:

1 = BOR is enabled

0 = BOR is disabled

If BOREN1:BOREN0 = 00, 10 or 11:

Bit is disabled and read as '0'.

bit 5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

1 = The RESET instruction was not executed (set by firmware only)

0 = The RESET instruction was executed causing a device Reset (must be set in software after a Brown-out Reset occurs)

bit 3 TO: Watchdog Time-out Flag bit

1 = Set by power-up, CLRWDT instruction or SLEEP instruction

0 = A WDT time-out occurred

PD: Power-down Detection Flag bit bit 2

1 = Set by power-up or by the CLRWDT instruction

0 = Set by execution of the SLEEP instruction

POR: Power-on Reset Status bit(2) bit 1

1 = A Power-on Reset has not occurred (set by firmware only)

0 = A Power-on Reset occurred (must be set in software after a Power-on Reset occurs)

bit 0 **BOR:** Brown-out Reset Status bit

1 = A Brown-out Reset has not occurred (set by firmware only)

0 = A Brown-out Reset occurred (must be set in software after a Brown-out Reset occurs)

Note 1: The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See Section 4.4 "Brown-out Reset (BOR)".

2: The actual Reset value of  $\overline{POR}$  is determined by the type of device Reset. See the notes following this register and Section 4.6 "Reset State of Registers" for additional information.

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Note 1: It is recommended that the POR bit be set after a Power-on Reset has been detected so that subsequent Power-on Resets may be detected.

2: Brown-out Reset is said to have occurred when BOR is '0' and POR is '1' (assuming that POR was set to '1' by software immediately after POR).

## 4.2 Master Clear (MCLR)

The MCLR pin provides a method for triggering an external Reset of the device. A Reset is generated by holding the pin low. These devices have a noise filter in the MCLR Reset path which detects and ignores small pulses.

The MCLR pin is not driven low by any internal Resets, including the WDT.

In PIC18F2X1X/4X1X devices, the MCLR input can be disabled with the MCLRE configuration bit. When MCLR is disabled, the pin becomes a digital input. See Section 9.5 "PORTE, TRISE and LATE Registers" for more information.

## 4.3 Power-on Reset (POR)


A Power-on Reset pulse is generated on-chip whenever VDD rises above a certain threshold. This allows the device to start in the initialized state when VDD is adequate for operation.

To take advantage of the POR circuitry, tie the  $\overline{MCLR}$  pin through a resistor (1 k $\Omega$  to 10 k $\Omega$ ) to VDD. This will eliminate external RC components usually needed to create a Power-on Reset delay. A minimum rise rate for VDD is specified (parameter D004). For a slow rise time, see Figure 4-2.

When the device starts normal operation (i.e., exits the Reset condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met.

POR events are captured by the POR bit (RCON<1>). The state of the bit is set to '0' whenever a POR occurs; it does not change for any other Reset event. POR is not reset to '1' by any hardware event. To capture multiple events, the user manually resets the bit to '1' in software following any POR.

# FIGURE 4-2: EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)



- Note 1: External Power-on Reset circuit is required only if the VDD power-up slope is too slow. The diode D helps discharge the capacitor quickly when VDD powers down.
  - 2:  $R < 40 \text{ k}\Omega$  is recommended to make sure that the voltage drop across R does not violate the device's electrical specification.
  - 3:  $R1 \ge 1$  k $\Omega$  will limit any current flowing into  $\overline{MCLR}$  from external capacitor C, in the event of  $\overline{MCLR}/VPP$  pin breakdown, due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS).

## 4.4 Brown-out Reset (BOR)

PIC18F2X1X/4X1X devices implement a BOR circuit that provides the user with a number of configuration and power-saving options. The BOR is controlled by the BORV1:BORV0 and BOREN1:BOREN0 configuration bits. There are a total of four BOR configurations which are summarized in Table 4-1.

The BOR threshold is set by the BORV1:BORV0 bits. If BOR is enabled (any values of BOREN1:BOREN0, except '00'), any drop of VDD below VBOR (parameter D005) for greater than TBOR (parameter 35) will reset the device. A Reset may or may not occur if VDD falls below VBOR for less than TBOR. The chip will remain in Brown-out Reset until VDD rises above VBOR.

If the Power-up Timer is enabled, it will be invoked after VDD rises above VBOR; it then will keep the chip in Reset for an additional time delay, TPWRT (parameter 33). If VDD drops below VBOR while the Power-up Timer is running, the chip will go back into a Brown-out Reset and the Power-up Timer will be initialized. Once VDD rises above VBOR, the Power-up Timer will execute the additional time delay.

BOR and the Power-on Timer (PWRT) are independently configured. Enabling BOR Reset does not automatically enable the PWRT.

### 4.4.1 SOFTWARE ENABLED BOR

When BOREN1:BOREN0 = 01, the BOR can be enabled or disabled by the user in software. This is done with the control bit, SBOREN (RCON<6>). Setting SBOREN enables the BOR to function as previously described. Clearing SBOREN disables the BOR entirely. The SBOREN bit operates only in this mode; otherwise it is read as '0'.

Placing the BOR under software control gives the user the additional flexibility of tailoring the application to its environment without having to reprogram the device to change BOR configuration. It also allows the user to tailor device power consumption in software by eliminating the incremental current that the BOR consumes. While the BOR current is typically very small, it may have some impact in low-power applications.

Note: Even when BOR is under software control, the BOR Reset voltage level is still set by the BORV1:BORV0 configuration bits. It cannot be changed in software.

## 4.4.2 DETECTING BOR

When BOR is enabled, the  $\overline{\text{BOR}}$  bit always resets to '0' on any BOR or POR event. This makes it difficult to determine if a BOR event has occurred just by reading the state of  $\overline{\text{BOR}}$  alone. A more reliable method is to simultaneously check the state of both  $\overline{\text{POR}}$  and  $\overline{\text{BOR}}$ . This assumes that the  $\overline{\text{POR}}$  bit is reset to '1' in software immediately after any POR event. If  $\overline{\text{BOR}}$  is '0' while  $\overline{\text{POR}}$  is '1', it can be reliably assumed that a BOR event has occurred.

### 4.4.3 DISABLING BOR IN SLEEP MODE

When BOREN1:BOREN0 = 10, the BOR remains under hardware control and operates as previously described. Whenever the device enters Sleep mode, however, the BOR is automatically disabled. When the device returns to any other operating mode, BOR is automatically re-enabled.

This mode allows for applications to recover from brown-out situations, while actively executing code, when the device requires BOR protection the most. At the same time, it saves additional power in Sleep mode by eliminating the small incremental BOR current.

TABLE 4-1: BOR CONFIGURATIONS

| BOR Con | BOR Configuration St |                     |  |  |  |  |  |  |
|---------|----------------------|---------------------|--|--|--|--|--|--|
| BOREN1  | BOREN0               | SBOREN<br>(RCON<6>) | BOR Operation  |  |  |  |  |  |
| 0       | 0                    | Unavailable         | BOR disabled; must be enabled by reprogramming the configuration bits.             |  |  |  |  |  |
| 0       | 1                    | Available           | BOR enabled in software; operation controlled by SBOREN.                           |  |  |  |  |  |
| 1       | 0                    | Unavailable         | BOR enabled in hardware in Run and Idle modes, disabled during Sleep mode.         |  |  |  |  |  |
| 1       | 1                    | Unavailable         | BOR enabled in hardware; must be disabled by reprogramming the configuration bits. |  |  |  |  |  |

### 4.5 Device Reset Timers

PIC18F2X1X/4X1X devices incorporate three separate on-chip timers that help regulate the Power-on Reset process. Their main function is to ensure that the device clock is stable before code is executed. These timers are:

- Power-up Timer (PWRT)
- Oscillator Start-up Timer (OST)
- · PLL Lock Time-out

## 4.5.1 POWER-UP TIMER (PWRT)

The Power-up Timer (PWRT) of PIC18F2X1X/4X1X devices is an 11-bit counter which uses the INTRC source as the clock input. This yields an approximate time interval of 2048 x 32  $\mu$ s = 65.6 ms. While the PWRT is counting, the device is held in Reset.

The power-up time delay depends on the INTRC clock and will vary from chip to chip due to temperature and process variation. See DC parameter 33 for details.

The PWRT is enabled by clearing the  $\overline{\text{PWRTEN}}$  configuration bit.

## 4.5.2 OSCILLATOR START-UP TIMER (OST)

The Oscillator Start-up Timer (OST) provides a 1024 oscillator cycle (from OSC1 input) delay after the PWRT delay is over (parameter 33). This ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP, HS and HSPLL modes and only on Power-on Reset, or on exit from most power managed modes.

### 4.5.3 PLL LOCK TIME-OUT

With the PLL enabled in its PLL mode, the time-out sequence following a Power-on Reset is slightly different from other oscillator modes. A separate timer is used to provide a fixed time-out that is sufficient for the PLL to lock to the main oscillator frequency. This PLL lock time-out (TPLL) is typically 2 ms and follows the oscillator start-up time-out.

### 4.5.4 TIME-OUT SEQUENCE

On power-up, the time-out sequence is as follows:

- 1. After the POR pulse has cleared, PWRT time-out is invoked (if enabled).
- 2. Then, the OST is activated.

The total time-out will vary based on oscillator configuration and the status of the PWRT. Figure 4-3, Figure 4-4, Figure 4-5, Figure 4-6 and Figure 4-7 all depict time-out sequences on power-up, with the Power-up Timer enabled and the device operating in HS Oscillator mode. Figures 4-3 through 4-6 also apply to devices operating in XT or LP modes. For devices in RC mode and with the PWRT disabled, there will be no time-out at all.

Since the time-outs occur from the POR pulse, if MCLR is kept low long enough, all time-outs will expire. Bringing MCLR high will begin execution immediately (Figure 4-5). This is useful for testing purposes or to synchronize more than one PIC18FXXXX device operating in parallel.

TABLE 4-2: TIME-OUT IN VARIOUS SITUATIONS

| Oscillator     | Power-up <sup>(2)</sup> ar                             | Power-up <sup>(2)</sup> and Brown-out |                                 |  |  |  |  |  |  |
|----------------|--|---------------------------------------|---------------------------------|--|--|--|--|--|--|
| Configuration  | PWRTEN = 0   | PWRTEN = 1                            | Power Managed Mode              |  |  |  |  |  |  |
| HSPLL          | 66 ms <sup>(1)</sup> + 1024 Tosc + 2 ms <sup>(2)</sup> | 1024 Tosc + 2 ms <sup>(2)</sup>       | 1024 Tosc + 2 ms <sup>(2)</sup> |  |  |  |  |  |  |
| HS, XT, LP     | 66 ms <sup>(1)</sup> + 1024 Tosc                       | 1024 Tosc                             | 1024 Tosc                       |  |  |  |  |  |  |
| EC, ECIO       | 66 ms <sup>(1)</sup>                                   | _                                     | _                               |  |  |  |  |  |  |
| RC, RCIO       | 66 ms <sup>(1)</sup>                                   | _                                     | _                               |  |  |  |  |  |  |
| INTIO1, INTIO2 | 66 ms <sup>(1)</sup>                                   | _                                     | _                               |  |  |  |  |  |  |

Note 1: 66 ms (65.5 ms) is the nominal Power-up Timer (PWRT) delay.

2: 2 ms is the nominal time required for the PLL to lock.

FIGURE 4-3: TIME-OUT SEQUENCE ON POWER-UP (MCLR TIED TO VDD, VDD RISE < TPWRT)




FIGURE 4-4: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 1







FIGURE 4-5: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2











## 4.6 Reset State of Registers

Most registers are unaffected by a Reset. Their status is unknown on POR and unchanged by all other Resets. The other registers are forced to a "Reset state" depending on the type of Reset that occurred.

Most registers are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. Status bits from the RCON register, RI, TO, PD, POR and BOR, are set or cleared differently in different Reset situations, as indicated in Table 4-3. These bits are used in software to determine the nature of the Reset.

Table 4-4 describes the Reset states for all of the Special Function Registers. These are categorized by Power-on and Brown-out Resets, Master Clear and WDT Resets and WDT wake-ups.

TABLE 4-3: STATUS BITS, THEIR SIGNIFICANCE AND THE INITIALIZATION CONDITION FOR RCON REGISTER

| Condition  | Program               |              | RCC | N Reg | jister |     |     | STKPTR Register |        |  |
|--|-----------------------|--------------|-----|-------|--------|-----|-----|-----------------|--------|--|
| Condition  | Counter               | SBOREN       | RI  | то    | PD     | POR | BOR | STKFUL          | STKUNF |  |
| Power-on Reset   | 0000h                 | 1            | 1   | 1     | 1      | 0   | 0   | 0               | 0      |  |
| RESET Instruction  | 0000h                 | ս <b>(2)</b> | 0   | u     | u      | u   | u   | u               | u      |  |
| Brown-out Reset  | 0000h                 | ս <b>(2)</b> | 1   | 1     | 1      | u   | 0   | u               | u      |  |
| MCLR during Power Managed<br>Run Modes                   | 0000h                 | ս <b>(2)</b> | u   | 1     | u      | u   | u   | u               | u      |  |
| MCLR during Power Managed Idle Modes and Sleep Mode      | 0000h                 | <b>u</b> (2) | u   | 1     | 0      | u   | u   | u               | u      |  |
| WDT Time-out during Full Power or Power Managed Run Mode | 0000h                 | <b>u</b> (2) | u   | 0     | u      | u   | u   | u               | u      |  |
| MCLR during Full Power Execution                         | 0000h                 | ս <b>(2)</b> | u   | u     | u      | u   | u   | u               | u      |  |
| Stack Full Reset (STVREN = 1)                            | 0000h                 | ս <b>(2)</b> | u   | u     | u      | u   | u   | 1               | u      |  |
| Stack Underflow Reset (STVREN = 1)                       | 0000h                 | ս <b>(2)</b> | u   | u     | u      | u   | u   | u               | 1      |  |
| Stack Underflow Error (not an actual Reset, STVREN = 0)  | 0000h                 | <b>u</b> (2) | u   | u     | u      | u   | u   | u               | 1      |  |
| WDT Time-out during Power<br>Managed Idle or Sleep Modes | PC + 2                | <b>u</b> (2) | u   | 0     | 0      | u   | u   | u               | u      |  |
| Interrupt Exit from Power Managed Modes                  | PC + 2 <sup>(1)</sup> | ս <b>(2)</b> | u   | u     | 0      | u   | u   | u               | u      |  |

**Legend:** u = unchanged

**Note 1:** When the wake-up is due to an interrupt and the GIEH or GIEL bits are set, the PC is loaded with the interrupt vector (008h or 0018h).

2: Reset state is '1' for POR and unchanged for all other Resets when software BOR is enabled (BOREN1:BOREN0 configuration bits = 01 and SBOREN = 1). Otherwise, the Reset state is '0'.

TABLE 4-4: INITIALIZATION CONDITIONS FOR ALL REGISTERS

| Register |      |      | Ap   | plicabl | e Devid | ces  |      | Power-on Reset,<br>Brown-out<br>Reset | MCLR Resets,<br>WDT Reset,<br>RESET<br>Instruction,<br>Stack Resets | Wake-up via<br>WDT<br>or Interrupt |                          |
|----------|------|------|------|---------|---------|------|------|---------------------------------------|---|------------------------------------|--------------------------|
| TOSU     | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0 0000  | 0 0000                             | 0 uuuu <b>(3)</b>        |
| TOSH     | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu(3)             |
| TOSL     | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu <sup>(3)</sup> |
| STKPTR   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 00-0 0000   | uu-0 0000                          | uu-u uuuu <sup>(3)</sup> |
| PCLATU   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0 0000  | 0 0000                             | u uuuu                   |
| PCLATH   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu                |
| PCL      | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | PC + 2 <sup>(2)</sup>    |
| TBLPTRU  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 00 0000   | 00 0000                            | uu uuuu                  |
| TBLPTRH  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu                |
| TBLPTRL  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu                |
| TABLAT   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu                |
| PRODH    | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| PRODL    | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| INTCON   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 000x   | 0000 000u                          | uuuu uuuu(1)             |
| INTCON2  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 1111 -1-1   | 1111 -1-1                          | uuuu -u-u <sup>(1)</sup> |
| INTCON3  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 11-0 0-00   | 11-0 0-00                          | uu-u u-uu <b>(1)</b>     |
| INDF0    | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| POSTINC0 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| POSTDEC0 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| PREINC0  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| PLUSW0   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| FSR0H    | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000  | 0000                               | uuuu                     |
| FSR0L    | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| WREG     | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| INDF1    | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| POSTINC1 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| POSTDEC1 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| PREINC1  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |
| PLUSW1   | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | N/A   | N/A                                | N/A                      |

 $\label{eq:update} \begin{tabular}{ll} $u$ = unchanged, $x$ = unknown, $-$ = unimplemented bit, read as `0', $q$ = value depends on condition. \\ Shaded cells indicate conditions do not apply for the designated device. \\ \end{tabular}$ 

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 4-3 for Reset value for specific condition.
  - 5: Bits 6 and 7 of PORTA, LATA and TRISA are enabled, depending on the oscillator mode selected. When not enabled as PORTA pins, they are disabled and read '0'.

TABLE 4-4: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

| Register            | Applicable Devices |      |      |      | Power-on Reset,<br>Brown-out<br>Reset | MCLR Resets,<br>WDT Reset,<br>RESET<br>Instruction,<br>Stack Resets | Wake-up via<br>WDT<br>or Interrupt |      |           |           |           |
|---------------------|--------------------|------|------|------|---------------------------------------|---|------------------------------------|------|-----------|-----------|-----------|
| FSR1H               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000      | 0000      | uuuu      |
| FSR1L               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | xxxx xxxx | uuuu uuuu | uuuu uuuu |
| BSR                 | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000      | 0000      | uuuu      |
| INDF2               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | N/A       | N/A       | N/A       |
| POSTINC2            | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | N/A       | N/A       | N/A       |
| POSTDEC2            | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | N/A       | N/A       | N/A       |
| PREINC2             | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | N/A       | N/A       | N/A       |
| PLUSW2              | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | N/A       | N/A       | N/A       |
| FSR2H               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000      | 0000      | uuuu      |
| FSR2L               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | xxxx xxxx | uuuu uuuu | uuuu uuuu |
| STATUS              | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | x xxxx    | u uuuu    | u uuuu    |
| TMR0H               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | 0000 0000 | uuuu uuuu |
| TMR0L               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | xxxx xxxx | uuuu uuuu | uuuu uuuu |
| T0CON               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 1111 1111 | 1111 1111 | uuuu uuuu |
| OSCCON              | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0100 q000 | 0100 q000 | uuuu uuqu |
| HLVDCON             | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0-00 0101 | 0-00 0101 | u-uu uuuu |
| WDTCON              | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0         | 0         | u         |
| RCON <sup>(4)</sup> | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0q-1 11q0 | 0q-q qquu | uq-u qquu |
| TMR1H               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | xxxx xxxx | uuuu uuuu | uuuu uuuu |
| TMR1L               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | xxxx xxxx | uuuu uuuu | uuuu uuuu |
| T1CON               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | u0uu uuuu | uuuu uuuu |
| TMR2                | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | 0000 0000 | uuuu uuuu |
| PR2                 | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 1111 1111 | 1111 1111 | 1111 1111 |
| T2CON               | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | -000 0000 | -000 0000 | -uuu uuuu |
| SSPBUF              | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | xxxx xxxx | uuuu uuuu | uuuu uuuu |
| SSPADD              | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | 0000 0000 | uuuu uuuu |
| SSPSTAT             | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | 0000 0000 | uuuu uuuu |
| SSPCON1             | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | 0000 0000 | uuuu uuuu |
| SSPCON2             | 2410               | 2510 | 2515 | 2610 | 4410                                  | 4510  | 4515                               | 4610 | 0000 0000 | 0000 0000 | uuuu uuuu |

 $\label{eq:update} \begin{tabular}{ll} $u$ = unchanged, $x$ = unknown, $-$ = unimplemented bit, read as '0', $q$ = value depends on condition. \\ Shaded cells indicate conditions do not apply for the designated device. \\ \end{tabular}$ 

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 4-3 for Reset value for specific condition.
  - 5: Bits 6 and 7 of PORTA, LATA and TRISA are enabled, depending on the oscillator mode selected. When not enabled as PORTA pins, they are disabled and read '0'.

TABLE 4-4: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

| Register | Applicable Devices |      |      |      |      |      |      | Power-on Reset,<br>Brown-out<br>Reset | MCLR Resets,<br>WDT Reset,<br>RESET<br>Instruction,<br>Stack Resets | Wake-up via<br>WDT<br>or Interrupt |           |
|----------|--------------------|------|------|------|------|------|------|---------------------------------------|---|------------------------------------|-----------|
| ADRESH   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| ADRESL   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| ADCON0   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 00 0000   | 00 0000                            | uu uuuu   |
| ADCON1   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 00 0qqq   | 00 0qqq                            | uu uuuu   |
| ADCON2   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0-00 0000   | 0-00 0000                          | u-uu uuuu |
| CCPR1H   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| CCPR1L   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| CCP1CON  | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
|          | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 00 0000   | 00 0000                            | uu uuuu   |
| CCPR2H   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| CCPR2L   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| CCP2CON  | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 00 0000   | 00 0000                            | uu uuuu   |
| BAUDCON  | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 01-0 0-00   | 01-0 0-00                          | uu uuuu   |
| PWM1CON  | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
| ECCP1AS  | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
|          | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 00   | 0000 00                            | uuuu uu   |
| CVRCON   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
| CMCON    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0111   | 0000 0111                          | uuuu uuuu |
| TMR3H    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| TMR3L    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu |
| T3CON    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | uuuu uuuu                          | uuuu uuuu |
| SPBRGH   | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
| SPBRG    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
| RCREG    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
| TXREG    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu |
| TXSTA    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 0010   | 0000 0010                          | uuuu uuuu |
| RCSTA    | 2410               | 2510 | 2515 | 2610 | 4410 | 4510 | 4515 | 4610                                  | 0000 000x   | 0000 000x                          | uuuu uuuu |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', <math>q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

- Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
  - 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
  - 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
  - 4: See Table 4-3 for Reset value for specific condition.
  - 5: Bits 6 and 7 of PORTA, LATA and TRISA are enabled, depending on the oscillator mode selected. When not enabled as PORTA pins, they are disabled and read '0'.

TABLE 4-4: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

| Register             |      |      | Ар   | plicabl | e Devid | ces  |      | Power-on Reset,<br>Brown-out<br>Reset | MCLR Resets,<br>WDT Reset,<br>RESET<br>Instruction,<br>Stack Resets | Wake-up via<br>WDT<br>or Interrupt |                          |
|----------------------|------|------|------|---------|---------|------|------|---------------------------------------|---|------------------------------------|--------------------------|
| IPR2                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 11 1111   | 11 1111                            | uu uuuu                  |
| PIR2                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 00 0000   | 00 0000                            | uu uuuu <sup>(1)</sup>   |
| PIE2                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 00 0000   | 00 0000                            | uu uuuu                  |
| IPR1                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 1111 1111   | 1111 1111                          | uuuu uuuu                |
|                      | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | -111 1111   | -111 1111                          | -uuu uuuu                |
| PIR1                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu <sup>(1)</sup> |
|                      | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | -000 0000   | -000 0000                          | -uuu uuuu <sup>(1)</sup> |
| PIE1                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 0000   | 0000 0000                          | uuuu uuuu                |
|                      | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | -000 0000   | -000 0000                          | -uuu uuuu                |
| OSCTUNE              | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 00-0 0000   | 00-0 0000                          | uu-u uuuu                |
| TRISE                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 0000 -111   | 0000 -111                          | uuuu -uuu                |
| TRISD                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 1111 1111   | 1111 1111                          | uuuu uuuu                |
| TRISC                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 1111 1111   | 1111 1111                          | uuuu uuuu                |
| TRISB                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 1111 1111   | 1111 1111                          | uuuu uuuu                |
| TRISA <sup>(5)</sup> | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | 1111 1111(5)  | 1111 1111(5)                       | uuuu uuuu <sup>(5)</sup> |
| LATE                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxx   | uuu                                | uuu                      |
| LATD                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| LATC                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| LATB                 | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| LATA <sup>(5)</sup>  | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx(5)  | uuuu uuuu <sup>(5)</sup>           | uuuu uuuu <sup>(5)</sup> |
| PORTE                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | x000  | x000                               | uuuu                     |
| PORTD                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| PORTC                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| PORTB                | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xxxx xxxx   | uuuu uuuu                          | uuuu uuuu                |
| PORTA <sup>(5)</sup> | 2410 | 2510 | 2515 | 2610    | 4410    | 4510 | 4515 | 4610                                  | xx0x 0000 <b>(5)</b>  | uu0u 0000 <b>(5)</b>               | uuuu uuuu(5)             |

 $\label{eq:update} \begin{tabular}{ll} $u$ = unchanged, $x$ = unknown, $-$ = unimplemented bit, read as '0', $q$ = value depends on condition. \\ Shaded cells indicate conditions do not apply for the designated device. \\ \end{tabular}$ 

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

- 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
- 3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
- **4:** See Table 4-3 for Reset value for specific condition.
- 5: Bits 6 and 7 of PORTA, LATA and TRISA are enabled, depending on the oscillator mode selected. When not enabled as PORTA pins, they are disabled and read '0'.

## 5.0 MEMORY ORGANIZATION

There are two types of memory in PIC18F2X1X/4X1X microcontroller devices:

- · Program Memory
- Data RAM

As Harvard architecture devices, the data and program memories use separate busses; this allows for concurrent access of the two memory spaces.

Additional detailed information on the operation of the Flash program memory is provided in **Section 6.0** "Flash Program Memory".

## 5.1 Program Memory Organization


PIC18 microcontrollers implement a 21-bit program counter, which is capable of addressing a 2-Mbyte program memory space. Accessing a location between the upper boundary of the physically implemented memory and the 2-Mbyte address will return all '0's (a NOP instruction).

The PIC18F2410/4410 and PIC18F2510 each have 16 Kbytes of Flash memory and can store up to 8,192 single-word instructions. The PIC18F2510/4510 each have 32 Kbytes of Flash memory and can store up to 16,384 single-word instructions. The PIC18F2515/4515 each have 48 Kbytes of Flash memory and can store up to 24,576 single-word instructions. The PIC18F2610/4610 each have 64 Kbytes of Flash memory and can store up to 32,768 single-word instructions.

PIC18 devices have two interrupt vectors. The Reset vector address is at 0000h and the interrupt vector addresses are at 0008h and 0018h.

The program memory map for PIC18F2X1X/4X1X devices is shown in Figure 5-1.

FIGURE 5-1: PROGRAM MEMORY MAP AND STACK FOR PIC18F2X1X/4X1X DEVICES



#### 5.1.1 PROGRAM COUNTER

The Program Counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21 bits wide and is contained in three separate 8-bit registers. The low byte, known as the PCL register, is both readable and writable. The high byte, or PCH register, contains the PC<15:8> bits; it is not directly readable or writable. Updates to the PCH register are performed through the PCLATH register. The upper byte is called PCU. This register contains the PC<20:16> bits; it is also not directly readable or writable. Updates to the PCU register are performed through the PCLATU register.

The contents of PCLATH and PCLATU are transferred to the program counter by any operation that writes PCL. Similarly, the upper two bytes of the program counter are transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see Section 5.1.4.1 "Computed GOTO").

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the Least Significant bit of PCL is fixed to a value of '0'. The PC increments by 2 to address sequential instructions in the program memory.

The CALL, RCALL, GOTO and program branch instructions write to the program counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the program counter.

#### 5.1.2 RETURN ADDRESS STACK

The return address stack allows any combination of up to 31 program calls and interrupts to occur. The PC is pushed onto the stack when a CALL or RCALL instruction is executed or an interrupt is Acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction. PCLATU and PCLATH are not affected by any of the RETURN or CALL instructions.

The stack operates as a 31-word by 21-bit RAM and a 5-bit Stack Pointer, STKPTR. The stack space is not part of either program or data space. The Stack Pointer is readable and writable and the address on the top of the stack is readable and writable through the top-ofstack Special File Registers. Data can also be pushed to, or popped from the stack, using these registers.

A CALL type instruction causes a push onto the stack; the Stack Pointer is first incremented and the location pointed to by the Stack Pointer is written with the contents of the PC (already pointing to the instruction following the CALL). A RETURN type instruction causes a pop from the stack; the contents of the location pointed to by the STKPTR are transferred to the PC and then the Stack Pointer is decremented.

The Stack Pointer is initialized to '00000' after all Resets. There is no RAM associated with the location corresponding to a Stack Pointer value of '00000': this is only a Reset value. Status bits indicate if the stack is full or has overflowed or has underflowed.

#### 5.1.2.1 Top-of-Stack Access

Only the top of the return address stack (TOS) is readable and writable. A set of three registers, TOSU:TOSH:TOSL, hold the contents of the stack location pointed to by the STKPTR register (Figure 5-2). This allows users to implement a software stack if necessary. After a CALL, RCALL or interrupt, the software can read the pushed value by reading the TOSU:TOSH:TOSL registers. These values can be placed on a user defined software stack. At return time, the software can return these values to TOSU:TOSH:TOSL and do a return.

The user must disable the global interrupt enable bits while accessing the stack to prevent inadvertent stack corruption.




FIGURE 5-2:

## 5.1.2.2 Return Stack Pointer (STKPTR)

The STKPTR register (Register 5-1) contains the Stack Pointer value, the STKFUL (Stack Full) status bit and the STKUNF (Stack Underflow) status bits. The value of the Stack Pointer can be 0 through 31. The Stack Pointer increments before values are pushed onto the stack and decrements after values are popped off the stack. On Reset, the Stack Pointer value will be zero. The user may read and write the Stack Pointer value. This feature can be used by a Real-Time Operating System (RTOS) for return stack maintenance.

After the PC is pushed onto the stack 31 times (without popping any values off the stack), the STKFUL bit is set. The STKFUL bit is cleared by software or by a POR.

The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) configuration bit. (Refer to Section 22.1 "Configuration Bits" for a description of the device configuration bits.) If STVREN is set (default), the 31st push will push the (PC + 2) value onto the stack, set the STKFUL bit and reset the device. The STKFUL bit will remain set and the Stack Pointer will be set to zero.

If STVREN is cleared, the STKFUL bit will be set on the 31st push and the Stack Pointer will increment to 31. Any additional pushes will not overwrite the 31st push and STKPTR will remain at 31.

When the stack has been popped enough times to unload the stack, the next pop will return a value of zero to the PC and sets the STKUNF bit, while the Stack Pointer remains at zero. The STKUNF bit will remain set until cleared by software or until a POR occurs.

Note: Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the Reset vector, where the stack conditions can be verified and appropriate actions can be taken. This is not the same as a Reset, as the contents of the SFRs are not affected.

## 5.1.2.3 PUSH and POP Instructions

Since the Top-of-Stack is readable and writable, the ability to push values onto the stack and pull values off the stack without disturbing normal program execution is a desirable feature. The PIC18 instruction set includes two instructions, PUSH and POP, that permit the TOS to be manipulated under software control. TOSU, TOSH and TOSL can be modified to place data or a return address on the stack.

The PUSH instruction places the current PC value onto the stack. This increments the Stack Pointer and loads the current PC value onto the stack.

The POP instruction discards the current TOS by decrementing the Stack Pointer. The previous value pushed onto the stack then becomes the TOS value.

## REGISTER 5-1: STKPTR: STACK POINTER REGISTER

| R/C-0                 | R/C-0                 | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-----------------------|-----------------------|-----|-------|-------|-------|-------|-------|
| STKFUL <sup>(1)</sup> | STKUNF <sup>(1)</sup> | _   | SP4   | SP3   | SP2   | SP1   | SP0   |
| bit 7                 |                       |     |       |       |       |       | bit 0 |

bit 7 STKFUL: Stack Full Flag bit<sup>(1)</sup>

1 = Stack became full or overflowed

0 = Stack has not become full or overflowed

bit 6 STKUNF: Stack Underflow Flag bit<sup>(1)</sup>

1 = Stack underflow occurred0 = Stack underflow did not occur

0 = Stack dildernow did not occu

bit 5 **Unimplemented:** Read as '0'

bit 4-0

SP4:SP0: Stack Pointer Location bits

Note 1: Bit 7 and bit 6 are cleared by user software or by a POR.

| Legend:           |                  |                      |                        |
|-------------------|------------------|----------------------|------------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | C = Clearable only bit |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown     |

### 5.1.2.4 Stack Full and Underflow Resets

Device Resets on stack overflow and stack underflow conditions are enabled by setting the STVREN bit in Configuration Register 4L. When STVREN is set, a full or underflow will set the appropriate STKFUL or STKUNF bit and then cause a device Reset. When STVREN is cleared, a full or underflow condition will set the appropriate STKFUL or STKUNF bit but not cause a device Reset. The STKFUL or STKUNF bits are cleared by the user software or a Power-on Reset.

### 5.1.3 FAST REGISTER STACK


A fast register stack is provided for the Status, WREG and BSR registers, to provide a "fast return" option for interrupts. The stack for each register is only one level deep and is neither readable nor writable. It is loaded with the current value of the corresponding register when the processor vectors for an interrupt. All interrupt sources will push values into the stack registers. The values in the registers are then loaded back into their associated registers if the RETFIE, FAST instruction is used to return from the interrupt.

If both low and high priority interrupts are enabled, the stack registers cannot be used reliably to return from low priority interrupts. If a high priority interrupt occurs while servicing a low priority interrupt, the stack register values stored by the low priority interrupt will be overwritten. In these cases, users must save the key registers in software during a low priority interrupt.

If interrupt priority is not used, all interrupts may use the fast register stack for returns from interrupt. If no interrupts are used, the fast register stack can be used to restore the Status, WREG and BSR registers at the end of a subroutine call. To use the fast register stack for a subroutine call, a CALL label, FAST instruction must be executed to save the Status, WREG and BSR registers to the fast register stack. A RETURN, FAST instruction is then executed to restore these registers from the fast register stack.

Example 5-1 shows a source code example that uses the fast register stack during a subroutine call and return.

EXAMPLE 5-1: FAST REGISTER STACK CODE EXAMPLE



## 5.1.4 LOOK-UP TABLES IN PROGRAM MEMORY

There may be programming situations that require the creation of data structures, or look-up tables, in program memory. For PIC18 devices, look-up tables can be implemented in two ways:

- Computed GOTO
- · Table Reads

## 5.1.4.1 Computed GOTO

A computed GOTO is accomplished by adding an offset to the program counter. An example is shown in Example 5-2.

A look-up table can be formed with an ADDWF PCL instruction and a group of RETLW  $\,\mathrm{nn}$  instructions. The W register is loaded with an offset into the table before executing a call to that table. The first instruction of the called routine is the ADDWF PCL instruction. The next instruction executed will be one of the RETLW  $\,\mathrm{nn}$  instructions that returns the value ' $\,\mathrm{nn}$ ' to the calling function.

The offset value (in WREG) specifies the number of bytes that the program counter should advance and should be multiples of 2 (LSb = 0).

In this method, only one data byte may be stored in each instruction location and room on the return address stack is required.

EXAMPLE 5-2: COMPUTED GOTO USING AN OFFSET VALUE

|       | MOVF  | OFFSET, | W |
|-------|-------|---------|---|
|       | CALL  | TABLE   |   |
| ORG   | nn00h |         |   |
| TABLE | ADDWF | PCL     |   |
|       | RETLW | nnh     |   |
|       | RETLW | nnh     |   |
|       | RETLW | nnh     |   |
|       |       |         |   |
|       |       |         |   |
|       |       |         |   |
|       |       |         |   |

### 5.1.4.2 Table Reads and Table Writes

A better method of storing data in program memory allows two bytes of data to be stored in each instruction location.

Look-up table data may be stored two bytes per program word by using table reads and writes. The Table Pointer (TBLPTR) register specifies the byte address and the Table Latch (TABLAT) register contains the data that is read from or written to program memory. Data is transferred to or from program memory one byte at a time.

Table read and table write operations are discussed further in **Section 6.1 "Table Reads"**.

## 5.2 PIC18 Instruction Cycle

### 5.2.1 CLOCKING SCHEME

The microcontroller clock input, whether from an internal or external source, is internally divided by four to generate four non-overlapping quadrature clocks (Q1, Q2, Q3 and Q4). Internally, the program counter is incremented on every Q1; the instruction is fetched from the program memory and latched into the instruction register during Q4. The instruction is decoded and executed during the following Q1 through Q4. The clocks and instruction execution flow are shown in Figure 5-3.


### 5.2.2 INSTRUCTION FLOW/PIPELINING

An "Instruction Cycle" consists of four Q cycles: Q1 through Q4. The instruction fetch and execute are pipelined in such a manner that a fetch takes one instruction cycle, while the decode and execute take another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the program counter to change (e.g., GOTO), then two cycles are required to complete the instruction (Example 5-3).


A fetch cycle begins with the Program Counter (PC) incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the Instruction Register (IR) in cycle Q1. This instruction is then decoded and executed during the Q2, Q3 and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).





### **EXAMPLE 5-3: INSTRUCTION PIPELINE FLOW**



All instructions are single cycle, except for any program branches. These take two cycles since the fetch instruction is "flushed" from the pipeline while the new instruction is being fetched and then executed.

## 5.2.3 INSTRUCTIONS IN PROGRAM MEMORY

The program memory is addressed in bytes. Instructions are stored as two bytes or four bytes in program memory. The Least Significant Byte of an instruction word is always stored in a program memory location with an even address (LSb = 0). To maintain alignment with instruction boundaries, the PC increments in steps of 2 and the LSb will always read '0' (see **Section 5.1.1** "**Program Counter**").

Figure 5-4 shows an example of how instruction words are stored in the program memory.

The CALL and GOTO instructions have the absolute program memory address embedded into the instruction. Since instructions are always stored on word boundaries, the data contained in the instruction is a word address. The word address is written to PC<20:1>, which accesses the desired byte address in program memory. Instruction #2 in Figure 5-4 shows how the instruction GOTO 0006h is encoded in the program memory. Program branch instructions, which encode a relative address offset, operate in the same manner. The offset value stored in a branch instruction represents the number of single-word instructions that the PC will be offset by. Section 23.0 "Instruction Set Summary" provides further details of the instruction set.

## FIGURE 5-4: INSTRUCTIONS IN PROGRAM MEMORY

|                |            |                     | LSB = 1 | <b>LSB</b> = 0 | Word Address<br>↓ |
|----------------|------------|---------------------|---------|----------------|-------------------|
|                | Program N  | •                   |         |                | 000000h           |
|                | Byte Locat | tions $\rightarrow$ |         |                | 000002h           |
|                |            |                     |         |                | 000004h           |
|                |            |                     |         |                | 000006h           |
| Instruction 1: | MOVLW      | 055h                | 0Fh     | 55h            | 000008h           |
| Instruction 2: | GOTO       | 0006h               | EFh     | 03h            | 00000Ah           |
|                |            |                     | F0h     | 00h            | 00000Ch           |
| Instruction 3: | MOVFF      | 123h, 456h          | C1h     | 23h            | 00000Eh           |
|                |            |                     | F4h     | 56h            | 000010h           |
|                |            |                     |         |                | 000012h           |
|                |            |                     |         |                | 000014h           |

## 5.2.4 TWO-WORD INSTRUCTIONS

The standard PIC18 instruction set has four two-word instructions: CALL, MOVFF, GOTO and LSFR. In all cases, the second word of the instructions always has '1111' as its four Most Significant bits; the other 12 bits are literal data, usually a data memory address.

The use of '1111' in the 4 MSbs of an instruction specifies a special form of NOP. If the instruction is executed in proper sequence – immediately after the first word – the data in the second word is accessed and used by the instruction sequence. If the first word is skipped for

some reason and the second word is executed by itself, a  $\mathtt{NOP}$  is executed instead. This is necessary for cases when the two-word instruction is preceded by a conditional instruction that changes the PC. Example 5-4 shows how this works.

Note: See Section 5.6 "PIC18 Instruction Execution and the Extended Instruction Set" for information on two-word instructions in the extended instruction set.

**EXAMPLE 5-4: TWO-WORD INSTRUCTIONS** 

| CASE 1:             |                  |                              |  |  |  |  |  |  |
|---------------------|------------------|------------------------------|--|--|--|--|--|--|
| Object Code         | Source Code      |                              |  |  |  |  |  |  |
| 0110 0110 0000 0000 | TSTFSZ REG1      | ; is RAM location 0?         |  |  |  |  |  |  |
| 1100 0001 0010 0011 | MOVFF REG1, REG2 | ; No, skip this word         |  |  |  |  |  |  |
| 1111 0100 0101 0110 |                  | ; Execute this word as a NOP |  |  |  |  |  |  |
| 0010 0100 0000 0000 | ADDWF REG3       | ; continue code              |  |  |  |  |  |  |
| CASE 2:             | CASE 2:          |                              |  |  |  |  |  |  |
| Object Code         | Source Code      |                              |  |  |  |  |  |  |
| 0110 0110 0000 0000 | TSTFSZ REG1      | ; is RAM location 0?         |  |  |  |  |  |  |
| 1100 0001 0010 0011 | MOVFF REG1, REG2 | ; Yes, execute this word     |  |  |  |  |  |  |
| 1111 0100 0101 0110 |                  | ; 2nd word of instruction    |  |  |  |  |  |  |
| 0010 0100 0000 0000 | ADDWF REG3       | ; continue code              |  |  |  |  |  |  |

## 5.3 Data Memory Organization

Note:

The operation of some aspects of data memory are changed when the PIC18 extended instruction set is enabled. See Section 5.5 "Data Memory and the Extended Instruction Set" for more information.

The data memory in PIC18 devices is implemented as static RAM. Figures 5-5, 5-6 and 5-7 show the data memory organization for the PIC18F2X1X/4X1X devices.

The data memory contains Special Function Registers (SFRs) and General Purpose Registers (GPRs). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratchpad operations in the user's application. Any read of an unimplemented location will read as '0's.

The instruction set and architecture allow operations across all banks. The entire data memory may be accessed by Direct, Indirect or Indexed Addressing modes. Addressing modes are discussed later in this subsection.

To ensure that commonly used registers (SFRs and select GPRs) can be accessed in a single cycle, PIC18 devices implement an Access Bank. This is a 256-byte memory space that provides fast access to SFRs and the lower portion of GPR Bank 0 without using the BSR. **Section 5.3.2 "Access Bank"** provides a detailed description of the Access RAM.

## 5.3.1 BANK SELECT REGISTER (BSR)

Large areas of data memory require an efficient addressing scheme to make rapid access to any address possible. Ideally, this means that an entire address does not need to be provided for each read or write operation. For PIC18 devices, this is accomplished with a RAM banking scheme. This divides the memory space into 16 contiguous banks of 256 bytes. Depending on the instruction, each location can be addressed directly by its full 12-bit address, or an 8-bit low-order address and a 4-bit bank pointer.

Most instructions in the PIC18 instruction set make use of the bank pointer, known as the Bank Select Register (BSR). This SFR holds the 4 Most Significant bits of a location's address; the instruction itself includes the 8 Least Significant bits. Only the four lower bits of the BSR are implemented (BSR3:BSR0). The upper four bits are unused; they will always read '0' and cannot be written to. The BSR can be loaded directly by using the MOVLB instruction.

The value of the BSR indicates the bank in data memory; the 8 bits in the instruction show the location in the bank and can be thought of as an offset from the bank's lower boundary. The relationship between the BSR's value and the bank division in data memory is shown in Figure 5-8.

Since up to 16 registers may share the same low-order address, the user must always be careful to ensure that the proper bank is selected before performing a data read or write. For example, writing what should be program data to an 8-bit address of F9h, while the BSR is 0Fh, will end up resetting the program counter.

While any bank can be selected, only those banks that are actually implemented can be read or written to. Writes to unimplemented banks are ignored, while reads from unimplemented banks will return '0's. Even so, the Status register will still be affected as if the operation was successful. The data memory map in Figure 5-5 indicates which banks are implemented.

In the core PIC18 instruction set, only the MOVFF instruction fully specifies the 12-bit address of the source and target registers. This instruction ignores the BSR completely when it executes. All other instructions include only the low-order address as an operand and must use either the BSR or the Access Bank to locate their target registers.

When 'a' = 0: BSR<3:0> **Data Memory Map** The BSR is ignored and the Access Bank is used. 000h 00h Access RAM = 0000 07Fh The first 128 bytes are Bank 0 080h **GPR** general purpose RAM FFh 0FFh (from Bank 0). 100h 00h = 0001 The second 128 bytes are **GPR** Bank 1 Special Function Registers FFh 1FFh (from Bank 15). 00h 200h = 0010 Bank 2 **GPR** FFh 2FFh When 'a' = 1: 300h 00h = 0011 The BSR specifies the Bank Bank 3 used by the instruction. FFh 3FFh 400h 00h = 0100Bank 4 FFh 4FFh 500h 00h = 0101Bank 5 5FFh FFh 00h 600h = 0110Bank 6 **Access Bank** FFh 6FFh 00h 00h 700h = 0111 Access RAM Low Bank 7 7Fh FFh 7FFh Access RAM High 80h 800h 00h (SFRs) = 1000 FFh Bank 8 FFh 8FFh Unused 900h 00h = 1001 Read 00h Bank 9 FFh 9FFh A00h 00h = 1010 Bank 10 **AFFh** FFh B00h 00h = 1011 Bank 11 **BFFh** FFh C00h 00h = 1100 Bank 12 **CFFh** FFh D00h = 110100h Bank 13 DFFh FFh E00h 00h = 1110Bank 14 **EFFh** FFh F00h 00h Unused = 1111 F7Fh Bank 15 F80h **SFR** FFh **FFFh** 

FIGURE 5-5: DATA MEMORY MAP FOR PIC18F2410/4410 DEVICES






FIGURE 5-6: DATA MEMORY MAP FOR PIC18F2510/4510 DEVICES





### 5.3.2 ACCESS BANK

While the use of the BSR with an embedded 8-bit address allows users to address the entire range of data memory, it also means that the user must always ensure that the correct bank is selected. Otherwise, data may be read from or written to the wrong location. This can be disastrous if a GPR is the intended target of an operation, but an SFR is written to instead. Verifying and/or changing the BSR for each read or write to data memory can become very inefficient.

To streamline access for the most commonly used data memory locations, the data memory is configured with an Access Bank, which allows users to access a mapped block of memory without specifying a BSR. The Access Bank consists of the first 128 bytes of memory (00h-7Fh) in Bank 0 and the last 128 bytes of memory (80h-FFh) in Block 15. The lower half is known as the "Access RAM" and is composed of GPRs. This upper half is also where the device's SFRs are mapped. These two areas are mapped contiguously in the Access Bank and can be addressed in a linear fashion by an 8-bit address (Figure 5-5).

The Access Bank is used by core PIC18 instructions that include the Access RAM bit (the 'a' parameter in the instruction). When 'a' is equal to '1', the instruction uses the BSR and the 8-bit address included in the opcode for the data memory address. When 'a' is '0', however, the instruction is forced to use the Access Bank address map; the current value of the BSR is ignored entirely.

Using this "forced" addressing allows the instruction to operate on a data address in a single cycle, without updating the BSR first. For 8-bit addresses of 80h and above, this means that users can evaluate and operate on SFRs more efficiently. The Access RAM below 80h is a good place for data values that the user might need to access rapidly, such as immediate computational results or common program variables. Access RAM also allows for faster and more code efficient context saving and switching of variables.

The mapping of the Access Bank is slightly different when the extended instruction set is enabled (XINST configuration bit = 1). This is discussed in more detail in Section 5.5.3 "Mapping the Access Bank in Indexed Literal Offset Addressing Mode".

## 5.3.3 GENERAL PURPOSE REGISTER FILE

PIC18 devices may have banked memory in the GPR area. This is data RAM, which is available for use by all instructions. GPRs start at the bottom of Bank 0 (address 000h) and grow upwards towards the bottom of the SFR area. GPRs are not initialized by a Power-on Reset and are unchanged on all other Resets.

## 5.3.4 SPECIAL FUNCTION REGISTERS

The Special Function Registers (SFRs) are registers used by the CPU and peripheral modules for controlling the desired operation of the device. These registers are implemented as static RAM. SFRs start at the top of data memory (FFFh) and extend downward to occupy the top half of Bank 15 (F80h to FFFh). A list of these registers is given in Table 5-1 and Table 5-2.

The SFRs can be classified into two sets: those associated with the "core" device functionality (ALU, Resets and interrupts) and those related to the peripheral functions. The reset and interrupt registers are described in their respective chapters, while the ALU's Status register is described later in this section. Registers related to the operation of a peripheral feature are described in the chapter for that peripheral.

The SFRs are typically distributed among the peripherals whose functions they control. Unused SFR locations are unimplemented and read as '0's.

TABLE 5-1: SPECIAL FUNCTION REGISTER MAP FOR PIC18F2X1X/4X1X DEVICES

| Address | Name                    | Address | Name                    | Address | Name                   | Address | Name                 |
|---------|-------------------------|---------|-------------------------|---------|------------------------|---------|----------------------|
| FFFh    | TOSU                    | FDFh    | INDF2 <sup>(1)</sup>    | FBFh    | CCPR1H                 | F9Fh    | IPR1                 |
| FFEh    | TOSH                    | FDEh    | POSTINC2 <sup>(1)</sup> | FBEh    | CCPR1L                 | F9Eh    | PIR1                 |
| FFDh    | TOSL                    | FDDh    | POSTDEC2 <sup>(1)</sup> | FBDh    | CCP1CON                | F9Dh    | PIE1                 |
| FFCh    | STKPTR                  | FDCh    | PREINC2 <sup>(1)</sup>  | FBCh    | CCPR2H                 | F9Ch    | (2)                  |
| FFBh    | PCLATU                  | FDBh    | PLUSW2 <sup>(1)</sup>   | FBBh    | CCPR2L                 | F9Bh    | OSCTUNE              |
| FFAh    | PCLATH                  | FDAh    | FSR2H                   | FBAh    | CCP2CON                | F9Ah    | (2)                  |
| FF9h    | PCL                     | FD9h    | FSR2L                   | FB9h    | (2)                    | F99h    | (2)                  |
| FF8h    | TBLPTRU                 | FD8h    | STATUS                  | FB8h    | BAUDCON                | F98h    | (2)                  |
| FF7h    | TBLPTRH                 | FD7h    | TMR0H                   | FB7h    | PWM1CON <sup>(3)</sup> | F97h    | (2)                  |
| FF6h    | TBLPTRL                 | FD6h    | TMR0L                   | FB6h    | ECCP1AS <sup>(3)</sup> | F96h    | TRISE <sup>(3)</sup> |
| FF5h    | TABLAT                  | FD5h    | T0CON                   | FB5h    | CVRCON                 | F95h    | TRISD <sup>(3)</sup> |
| FF4h    | PRODH                   | FD4h    | (2)                     | FB4h    | CMCON                  | F94h    | TRISC                |
| FF3h    | PRODL                   | FD3h    | OSCCON                  | FB3h    | TMR3H                  | F93h    | TRISB                |
| FF2h    | INTCON                  | FD2h    | HLVDCON                 | FB2h    | TMR3L                  | F92h    | TRISA                |
| FF1h    | INTCON2                 | FD1h    | WDTCON                  | FB1h    | T3CON                  | F91h    | (2)                  |
| FF0h    | INTCON3                 | FD0h    | RCON                    | FB0h    | SPBRGH                 | F90h    | (2)                  |
| FEFh    | INDF0 <sup>(1)</sup>    | FCFh    | TMR1H                   | FAFh    | SPBRG                  | F8Fh    | (2)                  |
| FEEh    | POSTINC0 <sup>(1)</sup> | FCEh    | TMR1L                   | FAEh    | RCREG                  | F8Eh    | (2)                  |
| FEDh    | POSTDEC0 <sup>(1)</sup> | FCDh    | T1CON                   | FADh    | TXREG                  | F8Dh    | LATE <sup>(3)</sup>  |
| FECh    | PREINC0 <sup>(1)</sup>  | FCCh    | TMR2                    | FACh    | TXSTA                  | F8Ch    | LATD <sup>(3)</sup>  |
| FEBh    | PLUSW0 <sup>(1)</sup>   | FCBh    | PR2                     | FABh    | RCSTA                  | F8Bh    | LATC                 |
| FEAh    | FSR0H                   | FCAh    | T2CON                   | FAAh    | (2)                    | F8Ah    | LATB                 |
| FE9h    | FSR0L                   | FC9h    | SSPBUF                  | FA9h    | (2)                    | F89h    | LATA                 |
| FE8h    | WREG                    | FC8h    | SSPADD                  | FA8h    | (2)                    | F88h    | (2)                  |
| FE7h    | INDF1 <sup>(1)</sup>    | FC7h    | SSPSTAT                 | FA7h    | (2)                    | F87h    | (2)                  |
| FE6h    | POSTINC1 <sup>(1)</sup> | FC6h    | SSPCON1                 | FA6h    | (2)                    | F86h    | (2)                  |
| FE5h    | POSTDEC1 <sup>(1)</sup> | FC5h    | SSPCON2                 | FA5h    | (2)                    | F85h    | (2)                  |
| FE4h    | PREINC1 <sup>(1)</sup>  | FC4h    | ADRESH                  | FA4h    | (2)                    | F84h    | PORTE <sup>(3)</sup> |
| FE3h    | PLUSW1 <sup>(1)</sup>   | FC3h    | ADRESL                  | FA3h    | (2)                    | F83h    | PORTD <sup>(3)</sup> |
| FE2h    | FSR1H                   | FC2h    | ADCON0                  | FA2h    | IPR2                   | F82h    | PORTC                |
| FE1h    | FSR1L                   | FC1h    | ADCON1                  | FA1h    | PIR2                   | F81h    | PORTB                |
| FE0h    | BSR                     | FC0h    | ADCON2                  | FA0h    | PIE2                   | F80h    | PORTA                |

**Note 1:** This is not a physical register.

- 2: Unimplemented registers are read as '0'.
- 3: This register is not available on 28-pin devices.

TABLE 5-2: REGISTER FILE SUMMARY (PIC18F2X1X/4X1X)

| File Name | Bit 7   | Bit 6   | Bit 5           | Bit 4          | Bit 3          | Bit 2         | Bit 1           | Bit 0        | Value on POR, BOR | Details on page: |
|-----------|---|---|-----------------|----------------|----------------|---------------|-----------------|--------------|-------------------|------------------|
| TOSU      | _   | -   | -               | Top-of-Stack   | Upper Byte (T  | 0 0000        | 49, 54          |              |                   |                  |
| TOSH      | Top-of-Stack High Byte (TOS<15:8>)  |   |                 |                |                |               |                 |              | 0000 0000         | 49, 54           |
| TOSL      | Top-of-Stack  | Low Byte (TO  | S<7:0>)         |                |                |               |                 |              | 0000 0000         | 49, 54           |
| STKPTR    | STKFUL <sup>(6)</sup>   | STKUNF <sup>(6)</sup>   | _               | SP4            | SP3            | SP2           | SP1             | SP0          | 00-0 0000         | 49, 55           |
| PCLATU    | _   |   | _               | Holding Regis  | ster for PC<20 | :16>          | •               |              | 0 0000            | 49, 54           |
| PCLATH    | Holding Regis   | ster for PC<15  | :8>             | •              |                |               |                 |              | 0000 0000         | 49, 54           |
| PCL       | PC Low Byte   | (PC<7:0>)   |                 |                |                |               |                 |              | 0000 0000         | 49, 54           |
| TBLPTRU   | _   | _   | bit 21          | Program Men    | nory Table Poi | nter Upper By | te (TBLPTR<2    | 20:16>)      | 00 0000           | 49, 77           |
| TBLPTRH   | Program Men   | nory Table Poi  | nter High Byte  | (TBLPTR<15     | :8>)           |               |                 |              | 0000 0000         | 49, 77           |
| TBLPTRL   | Program Men   | nory Table Poi  | nter Low Byte   | (TBLPTR<7:0    | l>)            |               |                 |              | 0000 0000         | 49, 77           |
| TABLAT    | Program Men   | nory Table Late   | ch              |                |                |               |                 |              | 0000 0000         | 49, 77           |
| PRODH     | Product Regis   | ster High Byte  |                 |                |                |               |                 |              | xxxx xxxx         | 49, 79           |
| PRODL     | Product Regis   | ster Low Byte   |                 |                |                |               |                 |              | xxxx xxxx         | 49, 79           |
| INTCON    | GIE/GIEH  | PEIE/GIEL   | TMR0IE          | INT0IE         | RBIE           | TMR0IF        | INT0IF          | RBIF         | 0000 000x         | 49, 83           |
| INTCON2   | RBPU  | INTEDG0   | INTEDG1         | INTEDG2        | _              | TMR0IP        | _               | RBIP         | 1111 -1-1         | 49, 84           |
| INTCON3   | INT2IP  | INT1IP  |                 | INT2IE         | INT1IE         | _             | INT2IF          | INT1IF       | 11-0 0-00         | 49, 85           |
| INDF0     | Uses contents   | s of FSR0 to a  | ddress data m   | nemory – value | of FSR0 not    | changed (not  | a physical reg  | ister)       | N/A               | 49, 70           |
| POSTINC0  | Uses contents of FSR0 to address data memory – value of FSR0 post-incremented (not a physical register) |   |                 |                |                |               |                 |              | N/A               | 49, 70           |
| POSTDEC0  | Uses contents of FSR0 to address data memory – value of FSR0 post-decremented (not a physical register) |   |                 |                |                |               |                 | al register) | N/A               | 49, 70           |
| PREINC0   | Uses contents of FSR0 to address data memory – value of FSR0 pre-incremented (not a physical register)  |   |                 |                |                |               |                 | register)    | N/A               | 49, 70           |
| PLUSW0    |   | ents of FSR0 to address data memory – value of FSR0 pre-incremented (not a physical register) – SR0 offset by W |                 |                |                |               |                 |              | N/A               | 49, 70           |
| FSR0H     | _   | _   | -               | _              | Indirect Data  | Memory Addr   | ess Pointer 0 I | High         | 0000              | 49, 70           |
| FSR0L     | Indirect Data   | Memory Addre  | ess Pointer 0 l | _ow Byte       |                |               |                 |              | xxxx xxxx         | 49, 70           |
| WREG      | Working Regi  | ster  |                 |                |                |               |                 |              | xxxx xxxx         | 49               |
| INDF1     | Uses contents   | s of FSR1 to a  | ddress data m   | nemory – value | e of FSR1 not  | changed (not  | a physical reg  | ister)       | N/A               | 49, 70           |
| POSTINC1  | Uses contents   | s of FSR1 to a  | ddress data m   | nemory – value | e of FSR1 pos  | t-incremented | (not a physica  | ıl register) | N/A               | 49, 70           |
| POSTDEC1  | Uses contents   | s of FSR1 to a  | ddress data m   | nemory – value | e of FSR1 pos  | t-decremented | d (not a physic | al register) | N/A               | 49, 70           |
| PREINC1   | Uses contents   | s of FSR1 to a  | ddress data m   | nemory – value | e of FSR1 pre- | incremented ( | not a physical  | register)    | N/A               | 49, 70           |
| PLUSW1    | Uses contents value of FSR  | s of FSR1 to a<br>1 offset by W   | ddress data m   | nemory – value | e of FSR1 pre- | incremented ( | not a physical  | register) –  | N/A               | 49, 70           |
| FSR1H     | _   | _   | _               | _              | Indirect Data  | Memory Addr   | ess Pointer 1 I | High         | 0000              | 50, 70           |
| FSR1L     | Indirect Data   | Memory Addre  | ess Pointer 1 l | _ow Byte       |                |               |                 |              | xxxx xxxx         | 50, 70           |
| BSR       | _   | _   | _               | _              | Bank Select F  | Register      |                 |              | 0000              | 50, 59           |
| INDF2     | Uses contents   | s of FSR2 to a  | ddress data m   | nemory – value | of FSR2 not    | changed (not  | a physical reg  | ister)       | N/A               | 50, 70           |
| POSTINC2  | Uses contents   | s of FSR2 to a  | ddress data m   | nemory – value | of FSR2 pos    | t-incremented | (not a physica  | ıl register) | N/A               | 50, 70           |
| POSTDEC2  | Uses contents of FSR2 to address data memory – value of FSR2 post-decremented (not a physical register) |   |                 |                |                |               |                 | al register) | N/A               | 50, 70           |
| PREINC2   | Uses contents   | s of FSR2 to a  | ddress data m   | nemory – value | e of FSR2 pre- | incremented ( | not a physical  | register)    | N/A               | 50, 70           |
| PLUSW2    | Uses contents value of FSR  | s of FSR2 to a<br>2 offset by W   | ddress data m   | nemory – value | e of FSR2 pre- | incremented ( | not a physical  | register) –  | N/A               | 50, 70           |
| FSR2H     |   | _   | _               | _              | Indirect Data  | Memory Addr   | ess Pointer 2 I | ligh         | 0000              | 50, 70           |
| FSR2L     | Indirect Data   | Memory Addre  | ess Pointer 2 l | Low Byte       |                |               |                 |              | xxxx xxxx         | 50, 70           |
| STATUS    |   | _   | _               | N              | OV             | Z             | DC              | С            | x xxxx            | 50, 68           |

Legend:

- x = unknown, u = unchanged, --- = unimplemented, q = value depends on condition
- Note 1: The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See Section 4.4 "Brown-out Reset (BOR)".
  - 2: These registers and/or bits are not implemented on 28-pin devices and are read as '0'. Reset values are shown for 40/44-pin devices; individual unimplemented bits should be interpreted as '-'.
  - 3: The PLLEN bit is only available in specific oscillator configuration; otherwise it is disabled and reads as '0'. See Section 2.6.4 "PLL in INTOSC Modes".
  - 4: The RE3 bit is only available when Master Clear Reset is disabled (MCLRE configuration bit = 0). Otherwise, RE3 reads as '0'. This bit is read-only.
  - 5: RA6/RA7 and their associated latch and direction bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.
  - 6: Bit 7 and bit 6 are cleared by user software or by a POR.

TABLE 5-2: REGISTER FILE SUMMARY (PIC18F2X1X/4X1X) (CONTINUED)

| File Name | Bit 7                         | Bit 6                      | Bit 5               | Bit 4               | Bit 3               | Bit 2                        | Bit 1                 | Bit 0                 | Value on POR, BOR | Details on page: |
|-----------|-------------------------------|----------------------------|---------------------|---------------------|---------------------|------------------------------|-----------------------|-----------------------|-------------------|------------------|
| TMR0H     | Timer0 Regis                  | ter High Byte              |                     |                     |                     |                              |                       |                       | 0000 0000         | 50, 115          |
| TMR0L     | Timer0 Regis                  |                            |                     |                     |                     |                              |                       |                       | xxxx xxxx         | 50, 115          |
| T0CON     | TMR0ON                        | T08BIT                     | T0CS                | T0SE                | PSA                 | T0PS2                        | T0PS1                 | T0PS0                 | 1111 1111         | 50, 113          |
| OSCCON    | IDLEN                         | IRCF2                      | IRCF1               | IRCF0               | OSTS                | IOFS                         | SCS1                  | SCS0                  | 0100 q000         | 30, 50           |
| HLVDCON   | VDIRMAG                       | _                          | IRVST               | HLVDEN              | HLVDL3              | HLVDL2                       | HLVDL1                | HLVDL0                | 0-00 0101         | 50, 231          |
| WDTCON    | _                             | _                          | _                   | _                   | _                   | _                            | _                     | SWDTEN                | 0                 | 50, 247          |
| RCON      | IPEN                          | SBOREN <sup>(1)</sup>      | _                   | RI                  | TO                  | PD                           | POR                   | BOR                   | 0q-1 11q0         | 42, 48, 92       |
| TMR1H     | Timer1 Regis                  |                            |                     |                     | L                   |                              |                       |                       | xxxx xxxx         | 50, 121          |
| TMR1L     | Timer1 Regis                  | ter Low Bytes              |                     |                     |                     |                              |                       |                       | xxxx xxxx         | 50, 121          |
| T1CON     | RD16                          | T1RUN                      | T1CKPS1             | T1CKPS0             | T10SCEN             | T1SYNC                       | TMR1CS                | TMR10N                | 0000 0000         | 50, 117          |
| TMR2      | Timer2 Regis                  | ter                        |                     |                     | L                   |                              |                       |                       | 0000 0000         | 50, 124          |
| PR2       | Timer2 Period                 | d Register                 |                     |                     |                     |                              |                       |                       | 1111 1111         | 50, 124          |
| T2CON     | _                             | T2OUTPS3                   | T2OUTPS2            | T2OUTPS1            | T2OUTPS0            | TMR2ON                       | T2CKPS1               | T2CKPS0               | -000 0000         | 50, 123          |
| SSPBUF    | SSP Receive                   | Buffer/Transn              | nit Register        |                     |                     |                              |                       |                       | xxxx xxxx         | 50, 159,<br>160  |
| SSPADD    | SSP Address                   | Register in I <sup>2</sup> | C Slave Mode        | . SSP Baud R        | ate Reload Re       | gister in I <sup>2</sup> C N | faster Mode.          |                       | 0000 0000         | 50, 160          |
| SSPSTAT   | SMP                           | CKE                        | D/A                 | Р                   | S                   | R/W                          | UA                    | BF                    | 0000 0000         | 50, 152,<br>161  |
| SSPCON1   | WCOL                          | SSPOV                      | SSPEN               | CKP                 | SSPM3               | SSPM2                        | SSPM1                 | SSPM0                 | 0000 0000         | 50, 153,<br>162  |
| SSPCON2   | GCEN                          | ACKSTAT                    | ACKDT               | ACKEN               | RCEN                | PEN                          | RSEN                  | SEN                   | 0000 0000         | 50, 163          |
| ADRESH    | A/D Result Register High Byte |                            |                     |                     |                     |                              |                       |                       | xxxx xxxx         | 51, 220          |
| ADRESL    | A/D Result Re                 | egister Low By             | rte                 |                     |                     |                              |                       |                       | xxxx xxxx         | 51, 220          |
| ADCON0    | _                             | _                          | CHS3                | CHS2                | CHS1                | CHS0                         | GO/DONE               | ADON                  | 00 0000           | 51, 211          |
| ADCON1    | _                             | _                          | VCFG1               | VCFG0               | PCFG3               | PCFG2                        | PCFG1                 | PCFG0                 | 00 0qqq           | 51, 212          |
| ADCON2    | ADFM                          | _                          | ACQT2               | ACQT1               | ACQT0               | ADCS2                        | ADCS1                 | ADCS0                 | 0-00 0000         | 51, 213          |
| CCPR1H    | Capture/Com                   | pare/PWM Re                | gister 1 High E     | Byte                |                     |                              |                       |                       | xxxx xxxx         | 51, 130          |
| CCPR1L    | Capture/Com                   | pare/PWM Re                | gister 1 Low B      | syte                |                     |                              |                       |                       | xxxx xxxx         | 51, 130          |
| CCP1CON   | P1M1 <sup>(2)</sup>           | P1M0 <sup>(2)</sup>        | DC1B1               | DC1B0               | CCP1M3              | CCP1M2                       | CCP1M1                | CCP1M0                | 0000 0000         | 51, 129,<br>137  |
| CCPR2H    | Capture/Com                   | pare/PWM Re                | gister 2 High E     | Byte                |                     |                              |                       |                       | xxxx xxxx         | 51, 130          |
| CCPR2L    | Capture/Com                   | pare/PWM Re                | gister 2 Low B      | Syte                |                     |                              |                       |                       | xxxx xxxx         | 51, 130          |
| CCP2CON   | _                             | _                          | DC2B1               | DC2B0               | CCP2M3              | CCP2M2                       | CCP2M1                | CCP2M0                | 00 0000           | 51, 129          |
| BAUDCON   | ABDOVF                        | RCIDL                      | _                   | SCKP                | BRG16               | _                            | WUE                   | ABDEN                 | 01-0 0-00         | 51, 194          |
| PWM1CON   | PRSEN                         | PDC6 <sup>(2)</sup>        | PDC5 <sup>(2)</sup> | PDC4 <sup>(2)</sup> | PDC3 <sup>(2)</sup> | PDC2 <sup>(2)</sup>          | PDC1 <sup>(2)</sup>   | PDC0 <sup>(2)</sup>   | 0000 0000         | 51, 146          |
| ECCP1AS   | ECCPASE                       | ECCPAS2                    | ECCPAS1             | ECCPAS0             | PSSAC1              | PSSAC0                       | PSSBD1 <sup>(2)</sup> | PSSBD0 <sup>(2)</sup> | 0000 0000         | 51, 147          |
| CVRCON    | CVREN                         | CVROE                      | CVRR                | CVRSS               | CVR3                | CVR2                         | CVR1                  | CVR0                  | 0000 0000         | 51, 227          |
| CMCON     | C2OUT                         | C1OUT                      | C2INV               | C1INV               | CIS                 | CM2                          | CM1                   | CM0                   | 0000 0111         | 51, 221          |
| TMR3H     | Timer3 Regis                  |                            |                     |                     |                     |                              |                       |                       | xxxx xxxx         | 51, 127          |
| TMR3L     | Timer3 Regis                  | ter Low Byte               |                     |                     | Т                   |                              |                       |                       | xxxx xxxx         | 51, 127          |
| T3CON     | RD16                          | T3CCP2                     | T3CKPS1             | T3CKPS0             | T3CCP1              | T3SYNC                       | TMR3CS                | TMR3ON                | 0000 0000         | 51, 125          |

Legend:

- x = unknown, u = unchanged, = unimplemented, q = value depends on condition
- Note 1: The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See Section 4.4 "Brown-out Reset (BOR)".
  - 2: These registers and/or bits are not implemented on 28-pin devices and are read as '0'. Reset values are shown for 40/44-pin devices; individual unimplemented bits should be interpreted as '-'.
  - 3: The PLLEN bit is only available in specific oscillator configuration; otherwise it is disabled and reads as '0'. See Section 2.6.4 "PLL in INTOSC Modes".
  - 4: The RE3 bit is only available when Master Clear Reset is disabled (MCLRE configuration bit = 0). Otherwise, RE3 reads as '0'. This bit is read-only.
  - 5: RA6/RA7 and their associated latch and direction bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.
  - 6: Bit 7 and bit 6 are cleared by user software or by a POR.

TABLE 5-2: REGISTER FILE SUMMARY (PIC18F2X1X/4X1X) (CONTINUED)

| File Name            | Bit 7                 | Bit 6                 | Bit 5  | Bit 4            | Bit 3              | Bit 2              | Bit 1              | Bit 0              | Value on POR, BOR | Details on page: |
|----------------------|-----------------------|-----------------------|--|------------------|--------------------|--------------------|--------------------|--------------------|-------------------|------------------|
| SPBRGH               | EUSART Bau            | 0000 0000             | 51, 195  |                  |                    |                    |                    |                    |                   |                  |
| SPBRG                | EUSART Bau            | ıd Rate Gener         | ator Register  | Low Byte         |                    |                    |                    |                    | 0000 0000         | 51, 195          |
| RCREG                | EUSART Red            | eive Register         |  |                  |                    |                    |                    |                    | 0000 0000         | 51, 202          |
| TXREG                | EUSART Trai           | nsmit Register        |  |                  |                    |                    |                    |                    | 0000 0000         | 51, 200          |
| TXSTA                | CSRC                  | TX9                   | TXEN   | SYNC             | SENDB              | BRGH               | TRMT               | TX9D               | 0000 0010         | 51, 192          |
| RCSTA                | SPEN                  | RX9                   | SREN   | CREN             | ADDEN              | FERR               | OERR               | RX9D               | 0000 000x         | 51, 193          |
| IPR2                 | OSCFIP                | CMIP                  | _  | _                | BCLIP              | HLVDIP             | TMR3IP             | CCP2IP             | 11 1111           | 52, 91           |
| PIR2                 | OSCFIF                | CMIF                  | _  | _                | BCLIF              | HLVDIF             | TMR3IF             | CCP2IF             | 00 0000           | 52, 87           |
| PIE2                 | OSCFIE                | CMIE                  | _  | _                | BCLIE              | HLVDIE             | TMR3IE             | CCP2IE             | 00 0000           | 52, 89           |
| IPR1                 | PSPIP <sup>(2)</sup>  | ADIP                  | RCIP   | TXIP             | SSPIP              | CCP1IP             | TMR2IP             | TMR1IP             | 1111 1111         | 52, 90           |
| PIR1                 | PSPIF <sup>(2)</sup>  | ADIF                  | RCIF   | TXIF             | SSPIF              | CCP1IF             | TMR2IF             | TMR1IF             | 0000 0000         | 52, 86           |
| PIE1                 | PSPIE <sup>(2)</sup>  | ADIE                  | RCIE   | TXIE             | SSPIE              | CCP1IE             | TMR2IE             | TMR1IE             | 0000 0000         | 52, 88           |
| OSCTUNE              | INTSRC                | PLLEN <sup>(3)</sup>  | _  | TUN4             | TUN3               | TUN2               | TUN1               | TUN0               | 0q-0 0000         | 27, 52           |
| TRISE <sup>(2)</sup> | IBF                   | OBF                   | IBOV   | PSPMODE          | _                  | TRISE2             | TRISE1             | TRISE0             | 0000 -111         | 52, 108          |
| TRISD <sup>(2)</sup> | PORTD Data            | Direction Con         | trol Register  |                  |                    |                    |                    |                    | 1111 1111         | 52, 104          |
| TRISC                | PORTC Data            | Direction Con         | trol Register  |                  |                    |                    |                    |                    | 1111 1111         | 52, 101          |
| TRISB                | PORTB Data            | Direction Con         | trol Register  |                  |                    |                    |                    |                    | 1111 1111         | 52, 98           |
| TRISA                | TRISA7 <sup>(5)</sup> | TRISA6 <sup>(5)</sup> | Data Directio  | n Control Regi   | ister for PORT     | Ά                  |                    |                    | 1111 1111         | 52, 95           |
| LATE <sup>(2)</sup>  | _                     | _                     | _  | _                | _                  |                    | Latch Registe      |                    | xxx               | 52, 107          |
| LATD <sup>(2)</sup>  | PORTD Data            | Latch Registe         | r (Read and V  | Vrite to Data L  | atch)              |                    |                    |                    | xxxx xxxx         | 52, 104          |
| LATC                 | PORTC Data            | Latch Registe         | r (Read and V  | Vrite to Data L  | atch)              |                    |                    |                    | xxxx xxxx         | 52, 101          |
| LATB                 | PORTB Data            | Latch Registe         | r (Read and V  | Vrite to Data La | atch)              |                    |                    |                    | xxxx xxxx         | 52, 98           |
| LATA                 | LATA7 <sup>(6)</sup>  | LATA6 <sup>(6)</sup>  | PORTA Data Latch Register (Read and Write to Data Latch) |                  |                    |                    |                    |                    |                   | 52, 95           |
| PORTE                | _                     | _                     | _  | _                | RE3 <sup>(4)</sup> | RE2 <sup>(2)</sup> | RE1 <sup>(2)</sup> | RE0 <sup>(2)</sup> | xxxx              | 52, 107          |
| PORTD <sup>(2)</sup> | RD7                   | RD6                   | RD5  | RD4              | RD3                | RD2                | RD1                | RD0                | xxxx xxxx         | 52, 104          |
| PORTC                | RC7                   | RC6                   | RC5  | RC4              | RC3                | RC2                | RC1                | RC0                | xxxx xxxx         | 52, 101          |
| PORTB                | RB7                   | RB6                   | RB5  | RB4              | RB3                | RB2                | RB1                | RB0                | xxxx xxxx         | 52, 98           |
| PORTA                | RA7 <sup>(5)</sup>    | RA6 <sup>(5)</sup>    | RA5  | RA4              | RA3                | RA2                | RA1                | RA0                | xx0x 0000         | 52, 95           |

Legend:

- x = unknown,  $\mathtt{u}$  = unchanged, = unimplemented,  $\mathtt{q}$  = value depends on condition
- Note 1: The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See Section 4.4 "Brown-out Reset (BOR)".
  - 2: These registers and/or bits are not implemented on 28-pin devices and are read as '0'. Reset values are shown for 40/44-pin devices; individual unimplemented bits should be interpreted as '-'.
  - 3: The PLLEN bit is only available in specific oscillator configuration; otherwise it is disabled and reads as '0'. See Section 2.6.4 "PLL in INTOSC Modes".
  - 4: The RE3 bit is only available when Master Clear Reset is disabled (MCLRE configuration bit = 0). Otherwise, RE3 reads as '0'. This bit is read-only.
  - 5: RA6/RA7 and their associated latch and direction bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.
  - 6: Bit 7 and bit 6 are cleared by user software or by a POR.

### 5.3.5 STATUS REGISTER

The Status register, shown in Register 5-2, contains the arithmetic status of the ALU. As with any other SFR, it can be the operand for any instruction.

If the Status register is the destination for an instruction that affects the Z, DC, C, OV or N bits, the results of the instruction are not written; instead, the status is updated according to the instruction performed. Therefore, the result of an instruction with the Status register as its destination may be different than intended. As an example, CLRF STATUS will set the Z bit and leave the remaining status bits unchanged ('000u uluu').

It is recommended that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the Status register, because these instructions do not affect the Z, C, DC, OV or N bits in the Status register.

For other instructions that do not affect status bits, see the instruction set summaries in Table 23-2 and Table 23-3.

Note: The C and DC bits operate as the borrow and digit borrow bits, respectively, in subtraction.

### REGISTER 5-2: STATUS REGISTER

| U-0   | U-0 | U-0 | R/W-x | R/W-x | R/W-x | R/W-x | R/W-x |
|-------|-----|-----|-------|-------|-------|-------|-------|
| _     | _   | _   | N     | OV    | Z     | DC    | С     |
| bit 7 |     |     |       |       |       |       | bit 0 |

## bit 7-5 **Unimplemented:** Read as '0'

bit 4 N: Negative bit

This bit is used for signed arithmetic (2's complement). It indicates whether the result was negative (ALU MSB = 1).

- 1 = Result was negative
- 0 = Result was positive
- bit 3 **OV:** Overflow bit

This bit is used for signed arithmetic (2's complement). It indicates an overflow of the 7-bit magnitude which causes the sign bit (bit 7 of the result) to change state.

- 1 = Overflow occurred for signed arithmetic (in this arithmetic operation)
- 0 = No overflow occurred
- bit 2 Z: Zero bit
  - 1 = The result of an arithmetic or logic operation is zero
  - 0 = The result of an arithmetic or logic operation is not zero
- bit 1 **DC:** Digit carry/borrow bit

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the 4th low-order bit of the result occurred
- 0 = No carry-out from the 4th low-order bit of the result

**Note:** For borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either bit 4 or bit 3 of the source register.

## bit 0 C: Carry/borrow bit

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the Most Significant bit of the result occurred
- 0 = No carry-out from the Most Significant bit of the result occurred

**Note:** For borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low-order bit of the source register.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented I  | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

## 5.4 Data Addressing Modes

Note:

The execution of some instructions in the core PIC18 instruction set are changed when the PIC18 extended instruction set is enabled. See Section 5.5 "Data Memory and the Extended Instruction Set" for more information.

The data memory space can be addressed in several ways. For most instructions, the addressing mode is fixed. Other instructions may use up to three modes, depending on which operands are used and whether or not the extended instruction set is enabled.

The addressing modes are:

- Inherent
- Literal
- Direct
- Indirect

An additional addressing mode, Indexed Literal Offset, is available when the extended instruction set is enabled (XINST configuration bit = 1). Its operation is discussed in greater detail in **Section 5.5.1 "Indexed Addressing with Literal Offset"**.

## 5.4.1 INHERENT AND LITERAL ADDRESSING

Many PIC18 control instructions do not need any argument at all; they either perform an operation that globally affects the device or they operate implicitly on one register. This addressing mode is known as Inherent Addressing. Examples include SLEEP, RESET and DAW.

Other instructions work in a similar way but require an additional explicit argument in the opcode. This is known as Literal Addressing mode because they require some literal value as an argument. Examples include ADDLW and MOVLW which, respectively, add or move a literal value to the W register. Other examples include CALL and GOTO, which include a 20-bit program memory address.

## 5.4.2 DIRECT ADDRESSING

Direct addressing specifies all or part of the source and/or destination address of the operation within the opcode itself. The options are specified by the arguments accompanying the instruction.

In the core PIC18 instruction set, bit-oriented and byteoriented instructions use some version of direct addressing by default. All of these instructions include some 8-bit literal address as their Least Significant Byte. This address specifies either a register address in one of the banks of data RAM (Section 5.3.3 "General Purpose Register File") or a location in the Access Bank (Section 5.3.2 "Access Bank") as the data source for the instruction. The Access RAM bit 'a' determines how the address is interpreted. When 'a' is '1', the contents of the BSR (Section 5.3.1 "Bank Select Register (BSR)") are used with the address to determine the complete 12-bit address of the register. When 'a' is '0', the address is interpreted as being a register in the Access Bank. Addressing that uses the Access RAM is sometimes also known as Direct Forced Addressing mode.

A few instructions, such as MOVFF, include the entire 12-bit address (either source or destination) in their opcodes. In these cases, the BSR is ignored entirely.

The destination of the operation's results is determined by the destination bit 'd'. When 'd' is '1', the results are stored back in the source register, overwriting its original contents. When 'd' is '0', the results are stored in the W register. Instructions without the 'd' argument have a destination that is implicit in the instruction; their destination is either the target register being operated on or the W register.

### 5.4.3 INDIRECT ADDRESSING

Indirect addressing allows the user to access a location in data memory without giving a fixed address in the instruction. This is done by using File Select Registers (FSRs) as pointers to the locations to be read or written to. Since the FSRs are themselves located in RAM as Special File Registers, they can also be directly manipulated under program control. This makes FSRs very useful in implementing data structures, such as tables and arrays in data memory.

The registers for indirect addressing are also implemented with Indirect File Operands (INDFs) that permit automatic manipulation of the pointer value with auto-incrementing, auto-decrementing or offsetting with another value. This allows for efficient code, using loops, such as the example of clearing an entire RAM bank in Example 5-5.

EXAMPLE 5-5: HOW TO CLEAR RAM
(BANK 1) USING
INDIRECT ADDRESSING

| LFSR  | FSR0, 100h     | ;                                       |   |
|-------|----------------|---|---|
| CLRF  | POSTINC0       | ;                                       | Clear INDF                                    |
|       |                | ;                                       | register then                                 |
|       |                | ;                                       | inc pointer                                   |
| BTFSS | FSROH, 1       | ;                                       | All done with                                 |
|       |                | ;                                       | Bank1?  |
| BRA   | NEXT           | ;                                       | NO, clear next                                |
| Έ     |                | ;                                       | YES, continue                                 |
|       | CLRF BTFSS BRA | CLRF POSTINCO  BTFSS FSR0H, 1  BRA NEXT | CLRF POSTINCO ; ; BTFSS FSROH, 1 ; BRA NEXT ; |

## 5.4.3.1 FSR Registers and the INDF Operand

At the core of indirect addressing are three sets of registers: FSR0, FSR1 and FSR2. Each represents a pair of 8-bit registers, FSRnH and FSRnL. The four upper bits of the FSRnH register are not used so each FSR pair holds a 12-bit value. This represents a value that can address the entire range of the data memory in a linear fashion. The FSR register pairs, then, serve as pointers to data memory locations.

Indirect addressing is accomplished with a set of Indirect File Operands, INDF0 through INDF2. These can be thought of as "virtual" registers: they are mapped in the SFR space but are not physically implemented. Reading or writing to a particular INDF register actually accesses its corresponding FSR register pair. A read from INDF1, for example, reads the data at the address indicated by FSR1H:FSR1L. Instructions that use the INDF registers as operands actually use the contents of their corresponding FSR as a pointer to the instruction's target. The INDF operand is just a convenient way of using the pointer.

Because indirect addressing uses a full 12-bit address, data RAM banking is not necessary. Thus, the current contents of the BSR and the Access RAM bit have no effect on determining the target address.

## 5.4.3.2 FSR Registers and POSTINC, POSTDEC, PREINC and PLUSW


In addition to the INDF operand, each FSR register pair also has four additional indirect operands. Like INDF, these are "virtual" registers that cannot be indirectly read or written to. Accessing these registers actually accesses the associated FSR register pair, but also performs a specific action on its stored value. They are:

- POSTDEC: accesses the FSR value, then automatically decrements it by 1 afterwards
- POSTINC: accesses the FSR value, then automatically increments it by 1 afterwards
- PREINC: increments the FSR value by 1, then uses it in the operation
- PLUSW: adds the signed value of the W register (range of -127 to 128) to that of the FSR and uses the new value in the operation.

In this context, accessing an INDF register uses the value in the FSR registers without changing them. Similarly, accessing a PLUSW register gives the FSR value offset by that in the W register; neither value is actually changed in the operation. Accessing the other virtual registers changes the value of the FSR registers.

Operations on the FSRs with POSTDEC, POSTINC and PREINC affect the entire register pair; that is, roll-overs of the FSRnL register from FFh to 00h carry over to the FSRnH register. On the other hand, results of these operations do not change the value of any flags in the Status register (e.g., Z, N, OV, etc.).





The PLUSW register can be used to implement a form of indexed addressing in the data memory space. By manipulating the value in the W register, users can reach addresses that are fixed offsets from pointer addresses. In some applications, this can be used to implement some powerful program control structure, such as software stacks, inside of data memory.

#### 5.4.3.3 Operations by FSRs on FSRs

Indirect addressing operations that target other FSRs or virtual registers represent special cases. For example, using an FSR to point to one of the virtual registers will not result in successful operations. As a specific case, assume that FSR0H:FSR0L contains FE7h, the address of INDF1. Attempts to read the value of the INDF1 using INDF0 as an operand will return 00h. Attempts to write to INDF1 using INDF0 as the operand will result in a NOP.

On the other hand, using the virtual registers to write to an FSR pair may not occur as planned. In these cases, the value will be written to the FSR pair but without any incrementing or decrementing. Thus, writing to INDF2 or POSTDEC2 will write the same value to the FSR2H:FSR2L.

Since the FSRs are physical registers mapped in the SFR space, they can be manipulated through all direct operations. Users should proceed cautiously when working on these registers, particularly if their code uses indirect addressing.

Similarly, operations by indirect addressing are generally permitted on all other SFRs. Users should exercise the appropriate caution that they do not inadvertently change settings that might affect the operation of the device.

# 5.5 Data Memory and the Extended Instruction Set

Enabling the PIC18 extended instruction set (XINST configuration bit = 1) significantly changes certain aspects of data memory and its addressing. Specifically, the use of the Access Bank for many of the core PIC18 instructions is different; this is due to the introduction of a new addressing mode for the data memory space.

What does not change is just as important. The size of the data memory space is unchanged, as well as its linear addressing. The SFR map remains the same. Core PIC18 instructions can still operate in both Direct and Indirect Addressing mode; inherent and literal instructions do not change at all. Indirect addressing with FSR0 and FSR1 also remain unchanged.

# 5.5.1 INDEXED ADDRESSING WITH LITERAL OFFSET

Enabling the PIC18 extended instruction set changes the behavior of indirect addressing using the FSR2 register pair within access RAM. Under the proper conditions, instructions that use the Access Bank – that is, most bit-oriented and byte-oriented instructions – can invoke a form of indexed addressing using an offset specified in the instruction. This special addressing mode is known as Indexed Addressing with Literal Offset, or Indexed Literal Offset mode.

When using the extended instruction set, this addressing mode requires the following:

- The use of the Access Bank is forced ('a' = 0);
   and
- The file address argument is less than or equal to 5Fh.

Under these conditions, the file address of the instruction is not interpreted as the lower byte of an address (used with the BSR in direct addressing), or as an 8-bit address in the Access Bank. Instead, the value is interpreted as an offset value to an address pointer, specified by FSR2. The offset and the contents of FSR2 are added to obtain the target address of the operation.

## 5.5.2 INSTRUCTIONS AFFECTED BY INDEXED LITERAL OFFSET MODE

Any of the core PIC18 instructions that can use direct addressing are potentially affected by the Indexed Literal Offset Addressing mode. This includes all byte-oriented and bit-oriented instructions, or almost one-half of the standard PIC18 instruction set. Instructions that only use Inherent or Literal Addressing modes are unaffected.

Additionally, byte-oriented and bit-oriented instructions are not affected if they do not use the Access Bank (Access RAM bit is '1'), or include a file address of 60h or above. Instructions meeting these criteria will continue to execute as before. A comparison of the different possible addressing modes when the extended instruction set is enabled is shown in Figure 5-10.

Those who desire to use bit-oriented or byte-oriented instructions in the Indexed Literal Offset mode should note the changes to assembler syntax for this mode. This is described in more detail in **Section 23.2.1** "Extended Instruction Syntax".

# FIGURE 5-10: COMPARING ADDRESSING OPTIONS FOR BIT-ORIENTED AND BYTE-ORIENTED INSTRUCTIONS (EXTENDED INSTRUCTION SET ENABLED)

**EXAMPLE INSTRUCTION:** ADDWF, f, d, a (Opcode: 0010 01da fffff fffff)

#### When 'a' = 0 and $f \ge 60h$ :

The instruction executes in Direct Forced mode. 'f' is interpreted as a location in the Access RAM between 060h and 0FFh. This is the same as locations 060h to 07Fh (Bank 0) and F80h to FFFh (Bank 15) of data memory.

Locations below 60h are not available in this addressing mode.


#### When 'a' = 0 and $f \le 5Fh$ :


The instruction executes in Indexed Literal Offset mode. 'f' is interpreted as an offset to the address value in FSR2. The two are added together to obtain the address of the target register for the instruction. The address can be anywhere in the data memory space.


Note that in this mode, the correct syntax is now:  $\label{eq:add_power} \text{ADDWF } [k] \text{ , } d$  where 'k' is the same as 'f'.

#### When 'a' = 1 (all values of f):

The instruction executes in Direct mode (also known as Direct Long mode). 'f' is interpreted as a location in one of the 16 banks of the data memory space. The bank is designated by the Bank Select Register (BSR). The address can be in any implemented bank in the data memory space.







# 5.5.3 MAPPING THE ACCESS BANK IN INDEXED LITERAL OFFSET ADDRESSING MODE


The use of Indexed Literal Offset Addressing mode effectively changes how the first 96 locations of access RAM (00h to 5Fh) are mapped. Rather than containing just the contents of the bottom half of Bank 0, this mode maps the contents from Bank 0 and a user defined "window" that can be located anywhere in the data memory space. The value of FSR2 establishes the lower boundary of the addresses mapped into the window, while the upper boundary is defined by FSR2 plus 95 (5Fh). Addresses in the Access RAM above 5Fh are mapped as previously described (see Section 5.3.2 "Access Bank"). An example of Access Bank remapping in this addressing mode is shown in Figure 5-11.

Remapping of the Access Bank applies *only* to operations using the Indexed Literal Offset Addressing mode. Operations that use the BSR (Access RAM bit is '1') will continue to use direct addressing as before.

# 5.6 PIC18 Instruction Execution and the Extended Instruction Set

Enabling the extended instruction set adds eight additional commands to the existing PIC18 instruction set. These instructions are executed as described in Section 23.2 "Extended Instruction Set".

FIGURE 5-11: REMAPPING THE ACCESS BANK WITH INDEXED LITERAL OFFSET ADDRESSING



© 2004 Microchip Technology Inc. Preliminary DS39636A-page 73

NOTES:

#### 6.0 FLASH PROGRAM MEMORY

In PIC18F2X1X/4X1X devices, the program memory is implemented as read-only Flash memory. It is readable over the entire VDD range during normal operation. A read from program memory is executed on one byte at a time.

#### 6.1 Table Reads

For PIC18 devices, there are two operations that allow the processor to move bytes between the program memory space and the data RAM: table read (TBLRD) and table write (TBLWT).

Table read operations retrieve data from program memory and place it into the data RAM space. Figure 6-1 shows the operation of a table read with program memory and data RAM.


The program memory space is 16 bits wide, while the data RAM space is 8 bits wide. Table reads and table writes move data between these two memory spaces through an 8-bit register, TABLAT.

Table reads work with byte entities. A table block containing data, rather than program instructions, is not required to be word-aligned. Therefore, a table block can start and end at any byte address.

Because the program memory cannot be written to or erased under normal operation, the TBLWT operation is not discussed here.

- Note 1: Although it cannot be used in PIC18F2X1X/4X1X devices in normal operation, the TBLWT instruction is still implemented in the instruction set. Executing the instruction takes two instruction cycles, but effectively results in a NOP.
  - 2: The TBLWT instruction is available only in programming modes and is used during In-Circuit Serial Programming™ (ICSP™).

FIGURE 6-1: TABLE READ OPERATION



© 2004 Microchip Technology Inc. Preliminary DS39636A-page 75

#### 6.2 Control Registers

Two control registers are used in conjunction with the TBLRD instruction: the TABLAT register and the TBLPTR register set.

#### 6.2.1 TABLAT – TABLE LATCH REGISTER

The Table Latch (TABLAT) is an 8-bit register mapped into the SFR space. The Table Latch register is used to hold 8-bit data during data transfers between program memory and data RAM.

# 6.2.2 TBLPTR – TABLE POINTER REGISTER

The Table Pointer register (TBLPTR) addresses a byte within the program memory. It is comprised of three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). Only the lower six bits of TBLPTRU are used with TBLPTRH and TBLPTRL, to form a 22-bit wide pointer.

The contents of TBLPTR indicate a location in program memory space. The low-order 21 bits allow the device to address the full 2 Mbytes of program memory space. The 22nd bit allows access to the configuration space, including the device ID, user ID locations and the configuration bits.

The TBLPTR register set is updated when executing a TBLRD in one of four ways, based on the instruction's arguments. These are detailed in Table 6-1. These operations on the TBLPTR only affect the low-order 21 bits.

When a TBLRD is executed, all 22 bits of the TBLPTR determine which byte is read from program memory into TABLAT.

TABLE 6-1: TABLE POINTER
OPERATIONS WITH TBLRD
INSTRUCTIONS

| Example | Operation on Table Pointer            |
|---------|---------------------------------------|
| TBLRD*  | TBLPTR is not modified                |
| TBLRD*+ | TBLPTR is incremented after the read  |
| TBLRD*- | TBLPTR is decremented after the read  |
| TBLRD+* | TBLPTR is incremented before the read |

# 6.3 Reading the Flash Program Memory


The TBLRD instruction is used to retrieve data from program memory and place it into data RAM. Table reads from program memory are performed one byte at a time.

TBLPTR points to a byte address in program space. Executing TBLRD places the byte pointed to into TABLAT. In addition, TBLPTR can be modified automatically for the next table read operation.

The internal program memory is typically organized by words. The Least Significant bit of the address selects between the high and low bytes of the word. Figure 6-2 shows the interface between the internal program memory and the TABLAT.

A typical method for reading data from program memory is shown in Example 6-1.





#### **EXAMPLE 6-1: READING A FLASH PROGRAM MEMORY WORD**

| 1<br>1<br>1<br>1 | MOVWF<br>MOVLW<br>MOVWF<br>MOVLW | CODE_ADDR_UPPER TBLPTRU CODE_ADDR_HIGH TBLPTRH CODE_ADDR_LOW TBLPTRL | • | Load TBLPTR with the base address of the word |
|------------------|----------------------------------|--|---|---|
| READ_WORD        |                                  |  |   |   |
| 7                | TBLRD*+                          |  | ; | read into TABLAT and increment                |
| N                | MOVF                             | TABLAT, W  | ; | get data                                      |
| N                | MOVWF                            | WORD_EVEN  |   |   |
| 7                | TBLRD*+                          |  | ; | read into TABLAT and increment                |
| I                | MOVF                             | TABLAT, W  | ; | get data                                      |
| 1                | MOVF                             | WORD_ODD   |   |   |

#### TABLE 6-2: REGISTERS ASSOCIATED WITH READING PROGRAM FLASH MEMORY

| Name    | Bit 7      | Bit 6       | Bit 5       | Bit 4                       | Bit 3  | Bit 2 | Bit 1 | Bit 0 | Reset<br>Values on<br>Page |  |
|---------|------------|-------------|-------------|-----------------------------|--|-------|-------|-------|----------------------------|--|
| TBLPTRU | _          | _           | bit 21      | _                           | Program Memory Table Pointer Upper Byte TBLPTR<20:16>) |       |       |       |                            |  |
| TBPLTRH | Program Me | emory Table | Pointer Hig | h Byte (TBI                 | LPTR<15:8  | >)    |       |       | 49                         |  |
| TBLPTRL | Program Me | emory Table | Pointer Lov | nter Low Byte (TBLPTR<7:0>) |  |       |       |       | 49                         |  |
| TABLAT  | Program Me | emory Table | Latch       |                             |  |       |       |       | 49                         |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used during Flash access.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 77

NOTES:

#### 7.0 8 x 8 HARDWARE MULTIPLIER

#### 7.1 Introduction

All PIC18 devices include an 8 x 8 hardware multiplier as part of the ALU. The multiplier performs an unsigned operation and yields a 16-bit result that is stored in the product register pair, PRODH:PRODL. The multiplier's operation does not affect any flags in the Status register.

Making multiplication a hardware operation allows it to be completed in a single instruction cycle. This has the advantages of higher computational throughput and reduced code size for multiplication algorithms and allows the PIC18 devices to be used in many applications previously reserved for digital signal processors. A comparison of various hardware and software multiply operations, along with the savings in memory and execution time, is shown in Table 7-1.

#### 7.2 Operation

Example 7-1 shows the instruction sequence for an  $8\times8$  unsigned multiplication. Only one instruction is required when one of the arguments is already loaded in the WREG register.

Example 7-2 shows the sequence to do an  $8 \times 8$  signed multiplication. To account for the sign bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

# EXAMPLE 7-1: 8 x 8 UNSIGNED MULTIPLY ROUTINE

MOVF ARG1, W ;
MULWF ARG2 ; ARG1 \* ARG2 ->
; PRODH:PRODL

# EXAMPLE 7-2: 8 x 8 SIGNED MULTIPLY ROUTINE

| MOVF  | ARG1, W  |                  |
|-------|----------|------------------|
| MULWF | ARG2     | ; ARG1 * ARG2 -> |
|       |          | ; PRODH:PRODL    |
| BTFSC | ARG2, SB | ; Test Sign Bit  |
| SUBWF | PRODH, F | ; PRODH = PRODH  |
|       |          | ; - ARG1         |
| MOVF  | ARG2, W  |                  |
| BTFSC | ARG1, SB | ; Test Sign Bit  |
| SUBWF | PRODH, F | ; PRODH = PRODH  |
|       |          | ; - ARG2         |
|       |          |                  |

TABLE 7-1: PERFORMANCE COMPARISON FOR VARIOUS MULTIPLY OPERATIONS

| <b>D</b>         | M. Idaha Mada at          | Program           | Cycles | Time     |          |         |  |
|------------------|---------------------------|-------------------|--------|----------|----------|---------|--|
| Routine          | Multiply Method           | Memory<br>(Words) | (Max)  | @ 40 MHz | @ 10 MHz | @ 4 MHz |  |
| 8 x 8 unsigned   | Without hardware multiply | 13                | 69     | 6.9 μs   | 27.6 μs  | 69 μs   |  |
| o x o unsigned   | Hardware multiply         | 1                 | 1      | 100 ns   | 400 ns   | 1 μs    |  |
| 9 v 9 signed     | Without hardware multiply | 33                | 91     | 9.1 μs   | 36.4 μs  | 91 μs   |  |
| 8 x 8 signed     | Hardware multiply         | 6                 | 6      | 600 ns   | 2.4 μs   | 6 μs    |  |
| 16 x 16 unsigned | Without hardware multiply | 21                | 242    | 24.2 μs  | 96.8 μs  | 242 μs  |  |
| 16 x 16 unsigned | Hardware multiply         | 28                | 28     | 2.8 μs   | 11.2 μs  | 28 μs   |  |
| 16 v 16 signed   | Without hardware multiply | 52                | 254    | 25.4 μs  | 102.6 μs | 254 μs  |  |
| 16 x 16 signed   | Hardware multiply         | 35                | 40     | 4.0 μs   | 16.0 μs  | 40 μs   |  |

Example 7-3 shows the sequence to do a 16 x 16 unsigned multiplication. Equation 7-1 shows the algorithm that is used. The 32-bit result is stored in four registers (RES3:RES0).

# EQUATION 7-1: 16 x 16 UNSIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0 = ARG1H:ARG1L \bullet ARG2H:ARG2L

= (ARG1H \bullet ARG2H \bullet 2<sup>16</sup>) +

(ARG1H \bullet ARG2L \bullet 2<sup>8</sup>) +

(ARG1L \bullet ARG2H \bullet 2<sup>8</sup>) +

(ARG1L \bullet ARG2L)
```

# EXAMPLE 7-3: 16 x 16 UNSIGNED MULTIPLY ROUTINE

```
MOVF
       ARG1L, W
MULWF
       ARG2L
                       ; ARG1L * ARG2L->
                       ; PRODH: PRODL
{\tt MOVFF}
       PRODH, RES1
                       ;
MOVFF
       PRODL, RESO
MOVF
       ARG1H, W
MULWF
       ARG2H
                       ; ARG1H * ARG2H->
                       ; PRODH:PRODL
       PRODH, RES3
MOVFF
MOVFF
       PRODL, RES2
MOVF
       ARG1L, W
                       ; ARG1L * ARG2H->
MULWF
       ARG2H
                       ; PRODH:PRODL
MOVF
       PRODL, W
ADDWF
       RES1, F
                      ; Add cross
MOVF
       PRODH, W
                       ; products
ADDWFC RES2, F
       WREG
CLRF
ADDWFC RES3, F
MOVF
       ARG1H, W
                       ; ARG1H * ARG2L->
MULWF
       ARG2L
                       ; PRODH:PRODL
MOVF
       PRODL, W
                      ; Add cross
ADDWF
       RES1, F
       PRODH, W
MOVF
                       ; products
ADDWFC RES2, F
CLRF
       WREG
                       ;
ADDWFC RES3, F
                       ;
```

Example 7-4 shows the sequence to do a 16 x 16 signed multiply. Equation 7-2 shows the algorithm used. The 32-bit result is stored in four registers (RES3:RES0). To account for the sign bits of the arguments, the MSb for each argument pair is tested and the appropriate subtractions are done.

# EQUATION 7-2: 16 x 16 SIGNED MULTIPLICATION ALGORITHM

```
RES3:RES0 = ARG1H:ARG1L • ARG2H:ARG2L

= (ARG1H • ARG2H • 2^{16}) +

(ARG1H • ARG2L • 2^{8}) +

(ARG1L • ARG2H • 2^{8}) +

(ARG1L • ARG2L) +

(-1 • ARG2H<7> • ARG1H:ARG1L • 2^{16}) +

(-1 • ARG1H<7> • ARG2H:ARG2L • 2^{16})
```

# EXAMPLE 7-4: 16 x 16 SIGNED MULTIPLY ROUTINE

```
MOVF
           ARG1L, W
                         ; ARG1L * ARG2L ->
   MULWF
           ARG2L
                        ; PRODH:PRODL
   MOVFF
           PRODH, RES1
           PRODL, RESO
   MOVFF
   MOVF
           ARG1H, W
                        ; ARG1H * ARG2H ->
   MULWF
           ARG2H
                        ; PRODH: PRODL
   MOVFF
           PRODH, RES3
   MOVFF
           PRODL, RES2
   MOVF
           ARG1L, W
                        ; ARG1L * ARG2H ->
   MULWF
           ARG2H
                        ; PRODH: PRODL
   MOVF
           PRODL, W
                        ; Add cross
           RES1, F
   ADDWF
           PRODH, W
                        ; products
   MOVF
   ADDWFC RES2, F
   CLRF
           WREG
   ADDWFC RES3, F
   MOVF
           ARG1H, W
                        ; ARG1H * ARG2L ->
   \mathtt{MULWF}
           ARG2L
                        ; PRODH: PRODL
           PRODL, W
   MOVF
                        ; Add cross
   ADDWF
           RES1, F
                        ; products
   MOVF
           PRODH, W
   ADDWFC RES2, F
   CLRF
           WREG
   ADDWFC RES3, F
   BTFSS
           ARG2H, 7
                        ; ARG2H:ARG2L neg?
   BRA
           SIGN ARG1
                        ; no, check ARG1
   MOVF
           ARG1L, W
                        ;
   SUBWF
           RES2
   MOVF
           ARG1H. W
   SUBWFB RES3
SIGN ARG1
   BTFSS
           ARG1H, 7
                        ; ARG1H: ARG1L neg?
           CONT_CODE
   BRA
                        ; no, done
   MOVF
           ARG2L, W
   SUBWF
           RES2
   MOVF
           ARG2H, W
   SUBWFB RES3
CONT_CODE
```

#### 8.0 INTERRUPTS

The PIC18F2X1X/4X1X devices have multiple interrupt sources and an interrupt priority feature that allows most interrupt sources to be assigned a high priority level or a low priority level. The high priority interrupt vector is at 0008h and the low priority interrupt vector is at 0018h. High priority interrupt events will interrupt any low priority interrupts that may be in progress.

There are ten registers which are used to control interrupt operation. These registers are:

- RCON
- INTCON
- INTCON2
- INTCON3
- PIR1, PIR2
- PIE1, PIE2
- IPR1, IPR2

It is recommended that the Microchip header files supplied with MPLAB® IDE be used for the symbolic bit names in these registers. This allows the assembler/compiler to automatically take care of the placement of these bits within the specified register.

In general, interrupt sources have three bits to control their operation. They are:

- Flag bit to indicate that an interrupt event occurred
- Enable bit that allows program execution to branch to the interrupt vector address when the flag bit is set
- Priority bit to select high priority or low priority

The interrupt priority feature is enabled by setting the IPEN bit (RCON<7>). When interrupt priority is enabled, there are two bits which enable interrupts globally. Setting the GIEH bit (INTCON<7>) enables all interrupts that have the priority bit set (high priority). Setting the GIEL bit (INTCON<6>) enables all interrupts that have the priority bit cleared (low priority). When the interrupt flag, enable bit and appropriate global interrupt enable bit are set, the interrupt will vector immediately to address 0008h or 0018h, depending on the priority bit setting. Individual interrupts can be disabled through their corresponding enable bits.

When the IPEN bit is cleared (default state), the interrupt priority feature is disabled and interrupts are compatible with PICmicro® mid-range devices. In Compatibility mode, the interrupt priority bits for each source have no effect. INTCON<6> is the PEIE bit, which enables/disables all peripheral interrupt sources. INTCON<7> is the GIE bit, which enables/disables all interrupt sources. All interrupts branch to address 0008h in Compatibility mode.

When an interrupt is responded to, the global interrupt enable bit is cleared to disable further interrupts. If the IPEN bit is cleared, this is the GIE bit. If interrupt priority levels are used, this will be either the GIEH or GIEL bit. High priority interrupt sources can interrupt a low priority interrupt. Low priority interrupts are not processed while high priority interrupts are in progress.

The return address is pushed onto the stack and the PC is loaded with the interrupt vector address (0008h or 0018h). Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bits must be cleared in software before re-enabling interrupts to avoid recursive interrupts.


The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit (GIEH or GIEL if priority levels are used), which re-enables interrupts.

For external interrupt events, such as the INT pins or the PORTB input change interrupt, the interrupt latency will be three to four instruction cycles. The exact latency is the same for one or two-cycle instructions. Individual interrupt flag bits are set, regardless of the status of their corresponding enable bit or the GIE bit.

Note: Do not use the MOVFF instruction to modify any of the interrupt control registers while any interrupt is enabled. Doing so may cause erratic microcontroller behavior.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 81

FIGURE 8-1: PIC18 INTERRUPT LOGIC



#### 8.1 INTCON Registers

The INTCON registers are readable and writable registers, which contain various enable, priority and flag bits.

Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### **REGISTER 8-1: INTCON REGISTER**

| R/W-0    | R/W-0     | R/W-0  | R/W-0  | R/W-0 | R/W-0  | R/W-0  | R/W-x |
|----------|-----------|--------|--------|-------|--------|--------|-------|
| GIE/GIEH | PEIE/GIEL | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF  |
| bit 7    |           |        |        |       |        |        | bit 0 |

Note:

bit 7 GIE/GIEH: Global Interrupt Enable bit

#### When IPEN = 0:

- 1 = Enables all unmasked interrupts
- 0 = Disables all interrupts

#### When IPEN = 1:

- 1 = Enables all high priority interrupts
- 0 = Disables all interrupts
- bit 6 PEIE/GIEL: Peripheral Interrupt Enable bit

#### When IPEN = 0:

- 1 = Enables all unmasked peripheral interrupts
- 0 = Disables all peripheral interrupts

#### When IPEN = 1:

- 1 = Enables all low priority peripheral interrupts
- 0 = Disables all low priority peripheral interrupts
- bit 5 TMR0IE: TMR0 Overflow Interrupt Enable bit
  - 1 = Enables the TMR0 overflow interrupt
  - 0 = Disables the TMR0 overflow interrupt
- bit 4 INT0IE: INT0 External Interrupt Enable bit
  - 1 = Enables the INT0 external interrupt
  - 0 = Disables the INT0 external interrupt
- bit 3 RBIE: RB Port Change Interrupt Enable bit
  - 1 = Enables the RB port change interrupt
  - 0 = Disables the RB port change interrupt
- bit 2 TMR0IF: TMR0 Overflow Interrupt Flag bit
  - 1 = TMR0 register has overflowed (must be cleared in software)
  - 0 = TMR0 register did not overflow
- bit 1 INT0IF: INT0 External Interrupt Flag bit
  - 1 = The INT0 external interrupt occurred (must be cleared in software)
  - 0 = The INT0 external interrupt did not occur
- bit 0 RBIF: RB Port Change Interrupt Flag bit
  - 1 = At least one of the RB7:RB4 pins changed state (must be cleared in software)
  - 0 = None of the RB7:RB4 pins have changed state

**Note:** A mismatch condition will continue to set this bit. Reading PORTB will end the mismatch condition and allow the bit to be cleared.

| Legend: |  |
|---------|--|
|---------|--|

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### **REGISTER 8-2:** INTCON2 REGISTER

| R/W-1 | R/W-1   | R/W-1   | R/W-1   | U-0 | R/W-1  | U-0 | R/W-1 |
|-------|---------|---------|---------|-----|--------|-----|-------|
| RBPU  | INTEDG0 | INTEDG1 | INTEDG2 | _   | TMR0IP | _   | RBIP  |
| bit 7 |         |         |         |     |        |     | bit 0 |

bit 0

bit 7 RBPU: PORTB Pull-up Enable bit

1 = All PORTB pull-ups are disabled

0 = PORTB pull-ups are enabled by individual port latch values

INTEDG0: External Interrupt 0 Edge Select bit bit 6

> 1 = Interrupt on rising edge 0 = Interrupt on falling edge

bit 5 INTEDG1: External Interrupt 1 Edge Select bit

> 1 = Interrupt on rising edge 0 = Interrupt on falling edge

bit 4 INTEDG2: External Interrupt 2 Edge Select bit

> 1 = Interrupt on rising edge 0 = Interrupt on falling edge

bit 3 Unimplemented: Read as '0'

bit 2 TMR0IP: TMR0 Overflow Interrupt Priority bit

> 1 = High priority 0 = Low priority

bit 1 Unimplemented: Read as '0'

bit 0 **RBIP:** RB Port Change Interrupt Priority bit

> 1 = High priority 0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' '1' = Bit is set '0' = Bit is cleared -n = Value at POR x = Bit is unknown

Note: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### **REGISTER 8-3: INTCON3 REGISTER**

| R/W-1  | R/W-1  | U-0 | R/W-0  | R/W-0  | U-0 | R/W-0  | R/W-0  |
|--------|--------|-----|--------|--------|-----|--------|--------|
| INT2IP | INT1IP | _   | INT2IE | INT1IE | _   | INT2IF | INT1IF |
| bit 7  |        |     |        |        |     |        | bit 0  |

bit 0

bit 7 INT2IP: INT2 External Interrupt Priority bit

1 = High priority

0 = Low priority

bit 6 INT1IP: INT1 External Interrupt Priority bit

1 = High priority

0 = Low priority

Unimplemented: Read as '0' bit 5

bit 4 INT2IE: INT2 External Interrupt Enable bit

1 = Enables the INT2 external interrupt

0 = Disables the INT2 external interrupt

bit 3 **INT1IE:** INT1 External Interrupt Enable bit

1 = Enables the INT1 external interrupt

0 = Disables the INT1 external interrupt

bit 2 Unimplemented: Read as '0'

bit 1 INT2IF: INT2 External Interrupt Flag bit

1 = The INT2 external interrupt occurred (must be cleared in software)

0 = The INT2 external interrupt did not occur

bit 0 INT1IF: INT1 External Interrupt Flag bit

1 = The INT1 external interrupt occurred (must be cleared in software)

0 = The INT1 external interrupt did not occur

#### Legend:

U = Unimplemented bit, read as '0' R = Readable bit W = Writable bit -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

Note: Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### 8.2 PIR Registers

The PIR registers contain the individual flag bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are two Peripheral Interrupt Request (Flag) registers (PIR1 and PIR2).

- Note 1: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the Global Interrupt Enable bit, GIE (INTCON<7>).
  - 2: User software should ensure the appropriate interrupt flag bits are cleared prior to enabling an interrupt and after servicing that interrupt.

#### REGISTER 8-4: PIR1: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 1

| R/W-0                | R/W-0 | R-0  | R-0  | R/W-0 | R/W-0  | R/W-0  | R/W-0  |
|----------------------|-------|------|------|-------|--------|--------|--------|
| PSPIF <sup>(1)</sup> | ADIF  | RCIF | TXIF | SSPIF | CCP1IF | TMR2IF | TMR1IF |
| bit 7                |       |      |      |       |        |        | bit 0  |

- bit 7 **PSPIF**: Parallel Slave Port Read/Write Interrupt Flag bit<sup>(1)</sup>
  - 1 = A read or a write operation has taken place (must be cleared in software)
  - 0 = No read or write has occurred
    - Note 1: This bit is unimplemented on 28-pin devices and is read as '0'.
- bit 6 ADIF: A/D Converter Interrupt Flag bit
  - 1 = An A/D conversion completed (must be cleared in software)
  - 0 = The A/D conversion is not complete
- bit 5 RCIF: EUSART Receive Interrupt Flag bit
  - 1 = The EUSART receive buffer, RCREG, is full (cleared when RCREG is read)
  - 0 = The EUSART receive buffer is empty
- bit 4 TXIF: EUSART Transmit Interrupt Flag bit
  - 1 = The EUSART transmit buffer, TXREG, is empty (cleared when TXREG is written)
  - 0 = The EUSART transmit buffer is full
- bit 3 SSPIF: Master Synchronous Serial Port Interrupt Flag bit
  - 1 = The transmission/reception is complete (must be cleared in software)
  - 0 = Waiting to transmit/receive
- bit 2 **CCP1IF:** CCP1 Interrupt Flag bit

#### Capture mode:

- 1 = A TMR1 register capture occurred (must be cleared in software)
- 0 = No TMR1 register capture occurred

#### Compare mode:

- 1 = A TMR1 register compare match occurred (must be cleared in software)
- 0 = No TMR1 register compare match occurred

#### PWM mode:

Unused in this mode.

- bit 1 TMR2IF: TMR2 to PR2 Match Interrupt Flag bit
  - 1 = TMR2 to PR2 match occurred (must be cleared in software)
  - 0 = No TMR2 to PR2 match occurred
- bit 0 TMR1IF: TMR1 Overflow Interrupt Flag bit
  - 1 = TMR1 register overflowed (must be cleared in software)
  - 0 = TMR1 register did not overflow

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented b  | it, read as '0'    |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

#### **REGISTER 8-5:** PIR2: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 2

| R/W-0  | R/W-0 | U-0 | U-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  |
|--------|-------|-----|-----|-------|--------|--------|--------|
| OSCFIF | CMIF  | _   | _   | BCLIF | HLVDIF | TMR3IF | CCP2IF |
| bit 7  |       |     |     |       |        |        | bit 0  |

bit 0

- bit 7 **OSCFIF:** Oscillator Fail Interrupt Flag bit
  - 1 = Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)
  - 0 = Device clock operating
- bit 6 **CMIF:** Comparator Interrupt Flag bit
  - 1 = Comparator input has changed (must be cleared in software)
  - 0 = Comparator input has not changed
- Unimplemented: Read as '0' bit 5-4
- **BCLIF:** Bus Collision Interrupt Flag bit bit 3
  - 1 = A bus collision occurred (must be cleared in software)
  - 0 = No bus collision occurred
- bit 2 HLVDIF: High/Low-Voltage Detect Interrupt Flag bit
  - 1 = A low-voltage condition occurred (must be cleared in software)
  - 0 = The device voltage is above the High/Low-Voltage Detect trip point
- bit 1 TMR3IF: TMR3 Overflow Interrupt Flag bit
  - 1 = TMR3 register overflowed (must be cleared in software)
  - 0 = TMR3 register did not overflow
- bit 0 CCP2IF: CCPx Interrupt Flag bit

#### Capture mode:

- 1 = A TMR1 register capture occurred (must be cleared in software)
- 0 = No TMR1 register capture occurred

- 1 = A TMR1 register compare match occurred (must be cleared in software)
- 0 = No TMR1 register compare match occurred

#### PWM mode:

Unused in this mode.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented b  | oit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Rit is unknown |

#### 8.3 PIE Registers

The PIE registers contain the individual enable bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are two Peripheral Interrupt Enable registers (PIE1 and PIE2). When IPEN = 0, the PEIE bit must be set to enable any of these peripheral interrupts.

#### REGISTER 8-6: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1

| R/W-0                | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  |
|----------------------|-------|-------|-------|-------|--------|--------|--------|
| PSPIE <sup>(1)</sup> | ADIE  | RCIE  | TXIE  | SSPIE | CCP1IE | TMR2IE | TMR1IE |
| bit 7                |       |       |       |       |        |        | bit 0  |

bit 7 **PSPIE:** Parallel Slave Port Read/Write Interrupt Enable bit<sup>(1)</sup>

1 = Enables the PSP read/write interrupt

0 = Disables the PSP read/write interrupt

Note 1: This bit is unimplemented on 28-pin devices and is read as '0'.

bit 6 ADIE: A/D Converter Interrupt Enable bit

1 = Enables the A/D interrupt

0 = Disables the A/D interrupt

bit 5 RCIE: EUSART Receive Interrupt Enable bit

1 = Enables the EUSART receive interrupt

0 = Disables the EUSART receive interrupt

bit 4 TXIE: EUSART Transmit Interrupt Enable bit

1 = Enables the EUSART transmit interrupt

0 = Disables the EUSART transmit interrupt

bit 3 SSPIE: Master Synchronous Serial Port Interrupt Enable bit

1 = Enables the MSSP interrupt

0 = Disables the MSSP interrupt

bit 2 CCP1IE: CCP1 Interrupt Enable bit

1 = Enables the CCP1 interrupt

0 = Disables the CCP1 interrupt

bit 1 TMR2IE: TMR2 to PR2 Match Interrupt Enable bit

1 = Enables the TMR2 to PR2 match interrupt

0 = Disables the TMR2 to PR2 match interrupt

bit 0 TMR1IE: TMR1 Overflow Interrupt Enable bit

1 = Enables the TMR1 overflow interrupt

0 = Disables the TMR1 overflow interrupt

| _ | <br>_ | <br>-1 |   |
|---|-------|--------|---|
|   | е     |        | • |
|   |       |        |   |

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

#### REGISTER 8-7: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2

| R/W-0  | R/W-0 | U-0 | U-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  |
|--------|-------|-----|-----|-------|--------|--------|--------|
| OSCFIE | CMIE  | _   | _   | BCLIE | HLVDIE | TMR3IE | CCP2IE |
|        |       |     |     |       |        |        |        |

bit 7 bit 0

bit 7 OSCFIE: Oscillator Fail Interrupt Enable bit

1 = Enabled
0 = Disabled

bit 6 CMIE: Comparator Interrupt Enable bit

1 = Enabled
0 = Disabled

bit 5-4 **Unimplemented:** Read as '0'

bit 3 BCLIE: Bus Collision Interrupt Enable bit

1 = Enabled0 = Disabled

bit 2 **HLVDIE:** High/Low-Voltage Detect Interrupt Enable bit

1 = Enabled0 = Disabled

bit 1 TMR3IE: TMR3 Overflow Interrupt Enable bit

1 = Enabled
0 = Disabled

bit 0 CCP2IE: CCP2 Interrupt Enable bit

1 = Enabled
0 = Disabled

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

#### 8.4 IPR Registers

The IPR registers contain the individual priority bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are two Peripheral Interrupt Priority registers (IPR1 and IPR2). Using the priority bits requires that the Interrupt Priority Enable (IPEN) bit be set.

#### REGISTER 8-8: IPR1: PERIPHERAL INTERRUPT PRIORITY REGISTER 1

| R/W-1                | R/W-1 | R/W-1 | R/W-1 | R/W-1 | R/W-1  | R/W-1  | R/W-1  |
|----------------------|-------|-------|-------|-------|--------|--------|--------|
| PSPIP <sup>(1)</sup> | ADIP  | RCIP  | TXIP  | SSPIP | CCP1IP | TMR2IP | TMR1IP |
| bit 7                |       |       |       |       |        |        | bit 0  |

bit 7 **PSPIP:** Parallel Slave Port Read/Write Interrupt Priority bit<sup>(1)</sup>

1 = High priority

0 = Low priority

**Note 1:** This bit is unimplemented on 28-pin devices and is read as '0'.

bit 6 ADIP: A/D Converter Interrupt Priority bit

1 = High priority0 = Low priority

bit 5 RCIP: EUSART Receive Interrupt Priority bit

1 = High priority0 = Low priority

bit 4 TXIP: EUSART Transmit Interrupt Priority bit

1 = High priority0 = Low priority

bit 3 SSPIP: Master Synchronous Serial Port Interrupt Priority bit

1 = High priority0 = Low priority

bit 2 **CCP1IP:** CCP1 Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 TMR2IP: TMR2 to PR2 Match Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 TMR1IP: TMR1 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

#### REGISTER 8-9: IPR2: PERIPHERAL INTERRUPT PRIORITY REGISTER 2

| R/W-1  | R/W-1 | U-0 | U-0 | R/W-1 | R/W-1  | R/W-1  | R/W-1  |
|--------|-------|-----|-----|-------|--------|--------|--------|
| OSCFIP | CMIP  | 1   | 1   | BCLIP | HLVDIP | TMR3IP | CCP2IP |

bit 7 bit 0

bit 7 OSCFIP: Oscillator Fail Interrupt Priority bit

1 = High priority0 = Low priority

bit 6 CMIP: Comparator Interrupt Priority bit

1 = High priority0 = Low priority

bit 5-4 **Unimplemented:** Read as '0'

bit 3 BCLIP: Bus Collision Interrupt Priority bit

1 = High priority0 = Low priority

bit 2 **HLVDIP:** High/Low-Voltage Detect Interrupt Priority bit

1 = High priority0 = Low priority

bit 1 TMR3IP: TMR3 Overflow Interrupt Priority bit

1 = High priority0 = Low priority

bit 0 CCP2IP: CCP2 Interrupt Priority bit

1 = High priority0 = Low priority

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

#### 8.5 RCON Register

The RCON register contains flag bits which are used to determine the cause of the last Reset or wake-up from Idle or Sleep modes. RCON also contains the IPEN bit which enables interrupt priorities.

The operation of the SBOREN bit and the Reset flag bits is discussed in more detail in **Section 4.1** "RCON Register".

#### **REGISTER 8-10: RCON REGISTER**

|   | R/W-0 | R/W-1 <sup>(1)</sup> | U-0 | R/W-1 | R-1 | R-1 | R/W-0 <sup>(1)</sup> | R/W-0 |
|---|-------|----------------------|-----|-------|-----|-----|----------------------|-------|
|   | IPEN  | SBOREN               | _   | RI    | TO  | PD  | POR                  | BOR   |
| , | bit 7 |                      |     |       |     |     |                      | bit 0 |

1 = Enable priority levels on interrupts

0 = Disable priority levels on interrupts (PIC16XXX Compatibility mode)

bit 6 **SBOREN:** Software BOR Enable bit<sup>(1)</sup>

For details of bit operation, see Register 4-1.

**Note 1:** Actual Reset values are determined by device configuration and the nature of the device Reset. See Register 4-1 for additional information.

bit 5 Unimplemented: Read as '0'

bit 4 RI: RESET Instruction Flag bit

For details of bit operation, see Register 4-1.

bit 3 TO: Watchdog Time-out Flag bit

For details of bit operation, see Register 4-1.

bit 2 PD: Power-down Detection Flag bit

For details of bit operation, see Register 4-1.

bit 1 POR: Power-on Reset Status bit

For details of bit operation, see Register 4-1.

bit 0 BOR: Brown-out Reset Status bit

For details of bit operation, see Register 4-1.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented b  | oit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

#### 8.6 INTn Pin Interrupts

External interrupts on the RB0/INT0, RB1/INT1 and RB2/INT2 pins are edge-triggered. If the corresponding INTEDGx bit in the INTCON2 register is set (= 1), the interrupt is triggered by a rising edge; if the bit is clear, the trigger is on the falling edge. When a valid edge appears on the RBx/INTx pin, the corresponding flag bit INTxF is set. This interrupt can be disabled by clearing the corresponding enable bit INTxE. Flag bit INTxF must be cleared in software in the Interrupt Service Routine before re-enabling the interrupt.

All external interrupts (INT0, INT1 and INT2) can wakeup the processor from Idle or Sleep modes if bit INTxE was set prior to going into those modes. If the Global Interrupt Enable bit, GIE, is set, the processor will branch to the interrupt vector following wake-up.

Interrupt priority for INT1 and INT2 is determined by the value contained in the interrupt priority bits, INT1IP (INTCON3<6>) and INT2IP (INTCON3<7>). There is no priority bit associated with INT0. It is always a high priority interrupt source.

#### 8.7 TMR0 Interrupt

In 8-bit mode (which is the default), an overflow in the TMR0 register (FFh  $\rightarrow$  00h) will set flag bit TMR0IF. In 16-bit mode, an overflow in the TMR0H:TMR0L register pair (FFFFh  $\rightarrow$  0000h) will set TMR0IF. The interrupt can be enabled/disabled by setting/clearing enable bit, TMR0IE (INTCON<5>). Interrupt priority for Timer0 is determined by the value contained in the interrupt priority bit, TMR0IP (INTCON2<2>). See **Section 10.0** "Timer0 Module" for further details on the Timer0 module.

#### 8.8 PORTB Interrupt-on-Change

An input change on PORTB<7:4> sets flag bit, RBIF (INTCON<0>). The interrupt can be enabled/disabled by setting/clearing enable bit, RBIE (INTCON<3>). Interrupt priority for PORTB interrupt-on-change is determined by the value contained in the interrupt priority bit, RBIP (INTCON2<0>).

#### 8.9 Context Saving During Interrupts

During interrupts, the return PC address is saved on the stack. Additionally, the WREG, Status and BSR registers are saved on the fast return stack. If a fast return from interrupt is not used (see **Section 5.3** "**Data Memory Organization**"), the user may need to save the WREG, Status and BSR registers on entry to the Interrupt Service Routine. Depending on the user's application, other registers may also need to be saved. Example 8-1 saves and restores the WREG, Status and BSR registers during an Interrupt Service Routine.

#### EXAMPLE 8-1: SAVING STATUS, WREG AND BSR REGISTERS IN RAM

```
MOVWE
          W TEMP
                                           ; W_TEMP is in virtual bank
MOVFF
          STATUS, STATUS TEMP
                                           ; STATUS TEMP located anywhere
MOVFF
          BSR, BSR TEMP
                                           ; BSR TMEP located anywhere
; USER ISR CODE
MOVFF
          BSR TEMP, BSR
                                           ; Restore BSR
MOVF
          W TEMP, W
                                           ; Restore WREG
          STATUS TEMP, STATUS
MOVFF
                                           ; Restore STATUS
```

NOTES:

#### 9.0 I/O PORTS

Depending on the device selected and features enabled, there are up to five ports available. Some pins of the I/O ports are multiplexed with an alternate function from the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.


Each port has three registers for its operation. These registers are:

- TRIS register (data direction register)
- PORT register (reads the levels on the pins of the device)
- LAT register (output latch)

The Data Latch (LAT register) is useful for read-modify-write operations on the value that the I/O pins are driving.

A simplified model of a generic I/O port, without the interfaces to other peripherals, is shown in Figure 9-1.

FIGURE 9-1: GENERIC I/O PORT OPERATION



#### 9.1 PORTA, TRISA and LATA Registers

PORTA is a 8-bit wide, bidirectional port. The corresponding data direction register is TRISA. Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., put the contents of the output latch on the selected pin).

Reading the PORTA register reads the status of the pins, whereas writing to it will write to the port latch.

The Data Latch (LATA) register is also memory mapped. Read-modify-write operations on the LATA register read and write the latched output value for PORTA.

The RA4 pin is multiplexed with the Timer0 module clock input and one of the comparator outputs to become the RA4/T0CKI/C1OUT pin. Pins RA6 and RA7 are multiplexed with the main oscillator pins; they are enabled as oscillator or I/O pins by the selection of the main oscillator in the configuration register (see **Section 22.1 "Configuration Bits"** for details). When they are not used as port pins, RA6 and RA7 and their associated TRIS and LAT bits are read as '0'.

The other PORTA pins are multiplexed with analog inputs, the analog VREF+ and VREF- inputs and the comparator voltage reference output. The operation of pins RA3:RA0 and RA5 as A/D converter inputs is selected by clearing or setting the control bits in the ADCON1 register (A/D Control Register 1).

Pins RA0 through RA5 may also be used as comparator inputs or outputs by setting the appropriate bits in the CMCON register. To use RA3:RA0 as digital inputs, it is also necessary to turn off the comparators.

**Note:** On a Power-on Reset, RA5 and RA3:RA0 are configured as analog inputs and read as '0'. RA4 is configured as a digital input.

The RA4/T0CKI/C1OUT pin is a Schmitt Trigger input. All other PORTA pins have TTL input levels and full CMOS output drivers.

The TRISA register controls the direction of the PORTA pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set when using them as analog inputs.

**EXAMPLE 9-1: INITIALIZING PORTA** 

|       | •      |   |                       |
|-------|--------|---|-----------------------|
| CLRF  | PORTA  | ; | Initialize PORTA by   |
|       |        | ; | clearing output       |
|       |        | ; | data latches          |
| CLRF  | LATA   | ; | Alternate method      |
|       |        | ; | to clear output       |
|       |        | ; | data latches          |
| MOVLW | 07h    | ; | Configure A/D         |
| MOVWF | ADCON1 | ; | for digital inputs    |
| MOVWF | 07h    | ; | Configure comparators |
| MOVWF | CMCON  | ; | for digital input     |
| MOVLW | 0CFh   | ; | Value used to         |
|       |        | ; | initialize data       |
|       |        | ; | direction             |
| MOVWF | TRISA  | ; | Set RA<3:0> as inputs |
|       |        | ; | RA<5:4> as outputs    |
|       |        |   |                       |

TABLE 9-1: PORTA I/O SUMMARY

| Pin                     | Function | TRIS<br>Setting | I/O | I/O<br>Type | Description   |
|-------------------------|----------|-----------------|-----|-------------|---|
| RA0/AN0                 | RA0      | 0               | 0   | DIG         | LATA<0> data output; not affected by analog input.  |
|                         |          | 1               | I   | TTL         | PORTA<0> data input; disabled when analog input enabled.  |
|                         | AN0      | 1               | I   | ANA         | A/D input channel 0 and Comparator C1- input. Default input configuration on POR; does not affect digital output. |
| RA1/AN1                 | RA1      | 0               | 0   | DIG         | LATA<1> data output; not affected by analog input.  |
|                         |          | 1               |     | TTL         | PORTA<1> data input; disabled when analog input enabled.  |
|                         | AN1      | 1               | ı   | ANA         | A/D input channel 1 and comparator C2- input. Default input configuration on POR; does not affect digital output. |
| RA2/AN2/<br>VREF-/CVREF | RA2      | 0               | 0   | DIG         | LATA<2> data output; not affected by analog input. Disabled when CVREF output enabled.                            |
|                         |          | 1               | I   | TTL         | PORTA<2> data input. Disabled when analog functions enabled; disabled when CVREF output enabled.                  |
|                         | AN2      | 1               | I   | ANA         | A/D input channel 2 and comparator C2+ input. Default input configuration on POR; not affected by analog output.  |
|                         | VREF-    | 1               | I   | ANA         | A/D and comparator voltage reference low input.   |
|                         | CVREF    | х               | 0   | ANA         | Comparator voltage reference output. Enabling this feature disables digital I/O.                                  |
| RA3/AN3/VREF+           | RA3      | 0               | 0   | DIG         | LATA<3> data output; not affected by analog input.  |
|                         |          | 1               | I   | TTL         | PORTA<3> data input; disabled when analog input enabled.  |
|                         | AN3      | 1               | I   | ANA         | A/D input channel 3 and comparator C1+ input. Default input configuration on POR.                                 |
|                         | VREF+    | 1               | I   | ANA         | A/D and comparator voltage reference high input.  |
| RA4/T0CKI/C1OUT         | RA4      | 0               | 0   | DIG         | LATA<4> data output.  |
|                         |          | 1               |     | ST          | PORTA<4> data input; default configuration on POR.  |
|                         | T0CKI    | 1               | I   | ST          | Timer0 clock input.   |
|                         | C1OUT    | 0               | 0   | DIG         | Comparator 1 output; takes priority over port data.   |
| RA5/AN4/SS/             | RA5      | 0               | 0   | DIG         | LATA<5> data output; not affected by analog input.  |
| HLVDIN/C2OUT            |          | 1               | ı   | TTL         | PORTA<5> data input; disabled when analog input enabled.  |
|                         | AN4      | 1               | ı   | ANA         | A/D input channel 4. Default configuration on POR.  |
|                         | SS       | 1               | I   | TTL         | Slave select input for SSP (MSSP module).   |
|                         | HLVDIN   | 1               | I   | ANA         | High/Low-Voltage Detect external trip point input.  |
|                         | C2OUT    | 0               | 0   | DIG         | Comparator 2 output; takes priority over port data.   |
| OSC2/CLKO/RA6           | RA6      | 0               | 0   | DIG         | LATA<6> data output. Enabled in RCIO, INTIO2 and ECIO modes only.   |
|                         |          | 1               |     | TTL         | PORTA<6> data input. Enabled in RCIO, INTIO2 and ECIO modes only.   |
|                         | OSC2     | х               | 0   | ANA         | Main oscillator feedback output connection (XT, HS and LP modes).   |
|                         | CLKO     | х               | 0   | DIG         | System cycle clock output (Fosc/4) in RC, INTIO1 and EC Oscillator modes.   |
| OSC1/CLKI/RA7           | RA7      | 0               | 0   | DIG         | LATA<7> data output. Disabled in external oscillator modes.   |
|                         |          | 1               | I   | TTL         | PORTA<7> data input. Disabled in external oscillator modes.   |
|                         | OSC1     | х               | I   | ANA         | Main oscillator input connection.   |
|                         | CLKI     | х               | I   | ANA         | Main clock input connection.  |

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

TABLE 9-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

| Name   | Bit 7                 | Bit 6                 | Bit 5    | Bit 4  | Bit 3      | Bit 2  | Bit 1 | Bit 0 | Reset<br>Values<br>on page |
|--------|-----------------------|-----------------------|----------|--|------------|--------|-------|-------|----------------------------|
| PORTA  | RA7 <sup>(1)</sup>    | RA6 <sup>(1)</sup>    | RA5      | RA4  | RA3        | RA2    | RA1   | RA0   | 52                         |
| LATA   | LATA7 <sup>(1)</sup>  | LATA6 <sup>(1)</sup>  | PORTA Da | PORTA Data Latch Register (Read and Write to Data Latch) |            |        |       |       |                            |
| TRISA  | TRISA7 <sup>(1)</sup> | TRISA6 <sup>(1)</sup> | PORTA Da | ta Direction   | Control Re | gister |       |       | 52                         |
| ADCON1 | _                     | _                     | VCFG1    | VCFG0  | PCFG3      | PCFG2  | PCFG1 | PCFG0 | 51                         |
| CMCON  | C2OUT                 | C10UT                 | C2INV    | C1INV  | CIS        | CM2    | CM1   | CM0   | 51                         |
| CVRCON | CVREN                 | CVROE                 | CVRR     | CVRSS  | CVR3       | CVR2   | CVR1  | CVR0  | 51                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTA.

**Note 1:** RA7:RA6 and their associated latch and data direction bits are enabled as I/O pins based on oscillator configuration; otherwise, they are read as '0'.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 97

# 9.2 PORTB, TRISB and LATB Registers

PORTB is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISB. Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATB) is also memory mapped. Read-modify-write operations on the LATB register read and write the latched output value for PORTB.

#### **EXAMPLE 9-2: INITIALIZING PORTB**

| CLRF  | PORTB  | ; Initialize PORTB by     |
|-------|--------|---------------------------|
|       |        | ; clearing output         |
|       |        | ; data latches            |
| CLRF  | LATB   | ; Alternate method        |
|       |        | ; to clear output         |
|       |        | ; data latches            |
| MOVLW | 0Fh    | ; Set RB<4:0> as          |
| MOVWF | ADCON1 | ; digital I/O pins        |
|       |        | ; (required if config bit |
|       |        | ; PBADEN is set)          |
| MOVLW | 0CFh   | ; Value used to           |
|       |        | ; initialize data         |
|       |        | ; direction               |
| MOVWF | TRISB  | ; Set RB<3:0> as inputs   |
|       |        | ; RB<5:4> as outputs      |
|       |        | ; RB<7:6> as inputs       |
| 1     |        |                           |

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by clearing bit, RBPU (INTCON2<7>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset.

Note: On a Power-on Reset, RB4:RB0 are configured as analog inputs by default and read as '0'; RB7:RB5 are configured as digital inputs.

By programming the configuration bit, PBADEN, RB4:RB0 will alternatively be configured as digital inputs on POR.

Four of the PORTB pins (RB7:RB4) have an interrupton-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB7:RB4 pin configured as an output is excluded from the interrupton-change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are ORed together to generate the RB Port Change Interrupt with Flag bit, RBIF (INTCON<0>).

This interrupt can wake the device from the Sleep mode, or any of the Idle modes. The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of PORTB (except with the MOVFF (ANY), PORTB instruction).
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared.

The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.

RB3 can be configured by the configuration bit CCP2MX as the alternate peripheral pin for the CCP2 module (CCP2MX = 0).

TABLE 9-3: PORTB I/O SUMMARY

| Pin            | Function            | TRIS<br>Setting | I/O | I/O<br>Type | Description   |
|----------------|---------------------|-----------------|-----|-------------|---|
| RB0/INT0/FLT0/ | RB0                 | 0               | 0   | DIG         | LATB<0> data output; not affected by analog input.  |
| AN12           |                     | 1               | I   | TTL         | PORTB<0> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled. (1)               |
|                | INT0                | 1               | I   | ST          | External interrupt 0 input.   |
|                | FLT0                | 1               | I   | ST          | Enhanced PWM Fault input (ECCP1 module); enabled in software.   |
|                | AN12                | 1               | I   | ANA         | A/D input channel 12. <sup>(1)</sup>  |
| RB1/INT1/AN10  | RB1                 | 0               | 0   | DIG         | LATB<1> data output; not affected by analog input.  |
|                |                     | 1               | I   | TTL         | PORTB<1> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled.(1)                |
|                | INT1                | 1               | I   | ST          | External interrupt 1 input.   |
|                | AN10                | 1               | I   | ANA         | A/D input channel 10. <sup>(1)</sup>  |
| RB2/INT2/AN8   | RB2                 | 0               | 0   | DIG         | LATB<2> data output; not affected by analog input.  |
|                |                     | 1               | I   | TTL         | PORTB<2> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled.(1)                |
|                | INT2                | 1               | I   | ST          | External interrupt 2 input.   |
|                | AN8                 | 1               | I   | ANA         | A/D input channel 8. <sup>(1)</sup>   |
| RB3/AN9/CCP2   | RB3                 | 0               | 0   | DIG         | LATB<3> data output; not affected by analog input.  |
|                |                     | 1               | I   | TTL         | PORTB<3> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled.(1)                |
|                | AN9                 | 1               | I   | ANA         | A/D input channel 9. <sup>(1)</sup>   |
|                | CCP2 <sup>(2)</sup> | 0               | 0   | DIG         | CCP2 compare and PWM output.  |
|                |                     | 1               | I   | ST          | CCP2 capture input  |
| RB4/KBI0/AN11  | RB4                 | 0               | 0   | DIG         | LATB<4> data output; not affected by analog input.  |
|                |                     | 1               | I   | TTL         | PORTB<4> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled.(1)                |
|                | KBI0                | 1               | I   | TTL         | Interrupt on pin change.  |
|                | AN11                | 1               | I   | ANA         | A/D input channel 11. <sup>(1)</sup>  |
| RB5/KBI1/PGM   | RB5                 | 0               | 0   | DIG         | LATB<5> data output.  |
|                |                     | 1               | - 1 | TTL         | PORTB<5> data input; weak pull-up when RBPU bit is cleared.   |
|                | KBI1                | 1               | I   | TTL         | Interrupt on pin change.  |
|                | PGM                 | х               | I   | ST          | Single-Supply Programming mode entry (ICSP™). Enabled by LVP configuration bit; all other pin functions disabled. |
| RB6/KBI2/PGC   | RB6                 | 0               | 0   | DIG         | LATB<6> data output.  |
|                |                     | 1               | I   | TTL         | PORTB<6> data input; weak pull-up when RBPU bit is cleared.   |
|                | KBI2                | 1               | I   | TTL         | Interrupt on pin change.  |
|                | PGC                 | х               | I   | ST          | Serial execution (ICSP) clock input for ICSP and ICD operation. (3)   |
| RB7/KBI3/PGD   | RB7                 | 0               | 0   | DIG         | LATB<7> data output.  |
|                |                     | 1               | I   | TTL         | PORTB<7> data input; weak pull-up when RBPU bit is cleared.   |
|                | KBI3                | 1               | I   | TTL         | Interrupt on pin change.  |
|                | PGD                 | х               | 0   | DIG         | Serial execution data output for ICSP and ICD operation. (3)  |
|                | ĺ                   |                 |     | ST          | Serial execution data input for ICSP and ICD operation. (3)   |

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

- 2: Alternate assignment for CCP2 when the CCP2MX configuration bit is '0'. Default assignment is RC1.
- 3: All other pin functions are disabled when ICSP or ICD are enabled.

Note 1: Configuration on POR is determined by the PBADEN configuration bit. Pins are configured as analog inputs by default when PBADEN is set and digital inputs when PBADEN is cleared.

TABLE 9-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

| Name  | Bit 7     | Bit 6         | Bit 5        | Bit 4   | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---|-----------|---------------|--------------|---------|--------|--------|--------|--------|----------------------------|--|
| PORTB   | RB7       | RB6           | RB5          | RB4     | RB3    | RB2    | RB1    | RB0    | 52                         |  |
| LATB PORTB Data Latch Register (Read and Write to Data Latch) |           |               |              |         |        |        |        |        |                            |  |
| TRISB   | PORTB Dat | a Direction C | Control Regi | ster    |        |        |        |        | 52                         |  |
| INTCON  | GIE/GIEH  | PEIE/GIEL     | TMR0IE       | INT0IE  | RBIE   | TMR0IF | INT0IF | RBIF   | 49                         |  |
| INTCON2   | RBPU      | INTEDG0       | INTEDG1      | INTEDG2 | -      | TMR0IP | -      | RBIP   | 49                         |  |
| INTCON3   | INT2IP    | INT1IP        | _            | INT2IE  | INT1IE | _      | INT2IF | INT1IF | 49                         |  |
| ADCON1  | _         | _             | VCFG1        | VCFG0   | PCFG3  | PCFG2  | PCFG1  | PCFG0  | 51                         |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTB.

# 9.3 PORTC, TRISC and LATC Registers

PORTC is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISC. Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATC) is also memory mapped. Read-modify-write operations on the LATC register read and write the latched output value for PORTC.

PORTC is multiplexed with several peripheral functions (Table 9-5). The pins have Schmitt Trigger input buffers. RC1 is normally configured by configuration bit CCP2MX as the default peripheral pin of the CCP2 module (default/erased state, CCP2MX = 1).

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for additional information.

**Note:** On a Power-on Reset, these pins are configured as digital inputs.

The contents of the TRISC register are affected by peripheral overrides. Reading TRISC always returns the current contents, even though a peripheral device may be overriding one or more of the pins.

#### **EXAMPLE 9-3: INITIALIZING PORTC**

| CLRF  | PORTC | ; Initialize PORTC by   |
|-------|-------|-------------------------|
|       |       | ; clearing output       |
|       |       | ; data latches          |
| CLRF  | LATC  | ; Alternate method      |
|       |       | ; to clear output       |
|       |       | ; data latches          |
| MOVLW | 0CFh  | ; Value used to         |
|       |       | ; initialize data       |
|       |       | ; direction             |
| MOVWF | TRISC | ; Set RC<3:0> as inputs |
|       |       | ; RC<5:4> as outputs    |
|       |       | ; RC<7:6> as inputs     |
|       |       |                         |

TABLE 9-5: PORTC I/O SUMMARY

|                |                     | 1/O 301V        |     |                      |   |  |  |  |
|----------------|---------------------|-----------------|-----|----------------------|---|--|--|--|
| Pin            | Function            | TRIS<br>Setting | I/O | I/O<br>Type          | Description   |  |  |  |
| RC0/T1OSO/     | RC0                 | 0               | 0   | DIG                  | LATC<0> data output.  |  |  |  |
| T13CKI         |                     | 1               | ı   | ST                   | PORTC<0> data input.  |  |  |  |
|                | T1OSO               | х               | 0   | ANA                  | Timer1 oscillator output; enabled when Timer1 oscillator enabled. Disables digital I/O.   |  |  |  |
|                | T13CKI              | 1               | I   | ST                   | Timer1/Timer3 counter input.  |  |  |  |
| RC1/T1OSI/CCP2 | RC1                 | 0               | 0   | DIG                  | LATC<1> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<1> data input.  |  |  |  |
|                | T1OSI               | х               | I   | ANA                  | Timer1 oscillator input; enabled when Timer1 oscillator enabled. Disables digital I/O.  |  |  |  |
|                | CCP2 <sup>(1)</sup> | 0               | 0   | DIG                  | CCP2 compare and PWM output; takes priority over port data.   |  |  |  |
|                |                     | 1               | I   | ST                   | CCP2 capture input.   |  |  |  |
| RC2/CCP1/P1A   | RC2                 | 0               | 0   | DIG                  | LATC<2> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<2> data input.  |  |  |  |
|                | CCP1                | 0               | 0   | DIG                  | ECCP1 compare or PWM output; takes priority over port data.   |  |  |  |
|                |                     | 1               | ı   | ST                   | ECCP1 capture input.  |  |  |  |
|                | P1A <sup>(2)</sup>  | 0               | 0   | DIG                  | ECCP1 Enhanced PWM output, channel A. May be configured for tri-state during Enhanced PWM shutdown events. Takes priority over port data. |  |  |  |
| RC3/SCK/SCL    | RC3                 | 0               | 0   | DIG                  | LATC<3> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<3> data input.  |  |  |  |
|                | SCK                 | 0               | 0   | DIG                  | SPI clock output (MSSP module); takes priority over port data.  |  |  |  |
|                |                     | 1               | ı   | ST                   | SPI clock input (MSSP module).  |  |  |  |
|                | SCL                 | 0               | 0   | DIG                  | I <sup>2</sup> C™ clock output (MSSP module); takes priority over port data.  |  |  |  |
|                |                     | 1               | I   | I <sup>2</sup> C/SMB | I <sup>2</sup> C clock input (MSSP module); input type depends on module setting.   |  |  |  |
| RC4/SDI/SDA    | RC4                 | 0               | 0   | DIG                  | LATC<4> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<4> data input.  |  |  |  |
|                | SDI                 | 1               | I   | ST                   | SPI™ data input (MSSP module).  |  |  |  |
|                | SDA                 | 1               | 0   | DIG                  | I <sup>2</sup> C data output (MSSP module); takes priority over port data.  |  |  |  |
|                |                     | 1               | I   | I <sup>2</sup> C/SMB | I <sup>2</sup> C data input (MSSP module); input type depends on module setting.  |  |  |  |
| RC5/SDO        | RC5                 | 0               | 0   | DIG                  | LATC<5> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<5> data input.  |  |  |  |
|                | SDO                 | 0               | 0   | DIG                  | SPI data output (MSSP module); takes priority over port data.   |  |  |  |
| RC6/TX/CK      | RC6                 | 0               | 0   | DIG                  | LATC<6> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<6> data input.  |  |  |  |
|                | TX                  | 1               | 0   | DIG                  | Asynchronous serial transmit data output (USART module); takes priority over port data. User must configure as output.                    |  |  |  |
|                | CK                  | 1               | 0   | DIG                  | Synchronous serial clock output (USART module); takes priority over port data.  |  |  |  |
|                |                     | 1               | ı   | ST                   | Synchronous serial clock input (USART module).  |  |  |  |
| RC7/RX/DT      | RC7                 | 0               | 0   | DIG                  | LATC<7> data output.  |  |  |  |
|                |                     | 1               | I   | ST                   | PORTC<7> data input.  |  |  |  |
|                | RX                  | 1               | I   | ST                   | Asynchronous serial receive data input (USART module).  |  |  |  |
|                | DT                  | 1               | 0   | DIG                  | Synchronous serial data output (USART module); takes priority over port data.   |  |  |  |
|                |                     | 1               | I   | ST                   | Synchronous serial data input (USART module). User must configure as an input.  |  |  |  |

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; I<sup>2</sup>C/SMB = I<sup>2</sup>C/SMBus input buffer; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

Note 1: Default assignment for CCP2 when the CCP2MX configuration bit is set. Alternate assignment is RB3.

2: Enhanced PWM output is available only on PIC18F4410/4510/4515/4610 devices.

#### TABLE 9-6: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

| Name  | Bit 7  | Bit 6        | Bit 5        | Bit 4   | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Reset<br>Values<br>on page |  |
|-------|--|--------------|--------------|---------|-------|-------|-------|-------|----------------------------|--|
| PORTC | RC7  | RC6          | RC5          | RC4     | RC3   | RC2   | RC1   | RC0   | 52                         |  |
| LATC  | PORTC Data Latch Register (Read and Write to Data Latch) |              |              |         |       |       |       |       |                            |  |
| TRISC | PORTC Da   | ata Directio | n Control Re | egister |       |       |       |       | 52                         |  |

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 103

# 9.4 PORTD, TRISD and LATD Registers

**Note:** PORTD is only available on 40/44-pin devices.

PORTD is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISD. Setting a TRISD bit (= 1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISD bit (= 0) will make the corresponding PORTD pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATD) is also memory mapped. Read-modify-write operations on the LATD register read and write the latched output value for PORTD.

All pins on PORTD are implemented with Schmitt Trigger input buffers. Each pin is individually configurable as an input or output.

Three of the PORTD pins are multiplexed with outputs P1B, P1C and P1D of the enhanced CCP module. The operation of these additional PWM output pins is covered in greater detail in **Section 15.0 "Enhanced Capture/Compare/PWM (ECCP) Module"**.

**Note:** On a Power-on Reset, these pins are configured as digital inputs.

PORTD can also be configured as an 8-bit wide microprocessor port (Parallel Slave Port) by setting control bit, PSPMODE (TRISE<4>). In this mode, the input buffers are TTL. See **Section 9.6 "Parallel Slave Port"** for additional information on the Parallel Slave Port (PSP).

Note: When the enhanced PWM mode is used with either dual or quad outputs, the PSP functions of PORTD are automatically disabled.

#### **EXAMPLE 9-4: INITIALIZING PORTD**

|       | _     |   |
|-------|-------|---|
| CLRF  | PORTD | ; Initialize PORTD by ; clearing output   |
| CLRF  | LATD  | <pre>; data latches ; Alternate method ; to clear output</pre>                        |
| MOVLW | 0CFh  | <pre>; data latches ; Value used to ; initialize data</pre>                           |
| MOVWF | TRISD | ; direction<br>; Set RD<3:0> as inputs<br>; RD<5:4> as outputs<br>; RD<7:6> as inputs |

TABLE 9-7: PORTD I/O SUMMARY

| Pin          | Function | TRIS<br>Setting | I/O                         | I/O<br>Type | Description   |
|--------------|----------|-----------------|-----------------------------|-------------|---|
| RD0/PSP0     | RD0      | 0               | 0                           | DIG         | LATD<0> data output.  |
|              |          | 1               | I                           | ST          | PORTD<0> data input.  |
|              | PSP0     | х               | 0                           | DIG         | PSP read data output (LATD<0>); takes priority over port data.  |
|              |          | х               | I                           | TTL         | PSP write data input.   |
| RD1/PSP1     | RD1      | 0               | 0                           | DIG         | LATD<1> data output.  |
|              |          | 1               | I                           | ST          | PORTD<1> data input.  |
|              | PSP1     | х               | 0                           | DIG         | PSP read data output (LATD<1>); takes priority over port data.  |
|              |          | х               | I                           | TTL         | PSP write data input.   |
| RD2/PSP2     | RD2      | 0               | 0                           | DIG         | LATD<2> data output.  |
|              |          | 1               | I                           | ST          | PORTD<2> data input.  |
|              | PSP2     | х               | 0                           | DIG         | PSP read data output (LATD<2>); takes priority over port data.  |
|              |          | х               | I TTL PSP write data input. |             | PSP write data input.   |
| RD3/PSP3     | RD3      | 0               | 0                           | DIG         | LATD<3> data output.  |
|              |          | 1               | I                           | ST          | PORTD<3> data input.  |
|              | PSP3     | х               | 0                           | DIG         | PSP read data output (LATD<3>); takes priority over port data.  |
|              |          | х               | I                           | TTL         | PSP write data input.   |
| RD4/PSP4     | RD4      | 0               | 0                           | DIG         | LATD<4> data output.  |
|              |          | 1               | I                           | ST          | PORTD<4> data input.  |
|              | PSP4     | х               | 0                           | DIG         | PSP read data output (LATD<4>); takes priority over port data.  |
|              |          | х               | I                           | TTL         | PSP write data input.   |
| RD5/PSP5/P1B | RD5      | 0               | 0                           | DIG         | LATD<5> data output.  |
|              |          | 1               | I                           | ST          | PORTD<5> data input.  |
|              | PSP5     | х               | 0                           | DIG         | PSP read data output (LATD<5>); takes priority over port data.  |
|              |          | х               | I                           | TTL         | PSP write data input.   |
|              | P1B      | 0               | 0                           | DIG         | ECCP1 Enhanced PWM output, channel B; takes priority over port and PSP data. May be configured for tri-state during Enhanced PWM shutdown events. |
| RD6/PSP6/P1C | RD6      | 0               | 0                           | DIG         | LATD<6> data output.  |
|              |          | 1               |                             | ST          | PORTD<6> data input.  |
|              | PSP6     | х               | 0                           | DIG         | PSP read data output (LATD<6>); takes priority over port data.  |
|              |          | х               |                             | TTL         | PSP write data input.   |
|              | P1C      | 0               | 0                           | DIG         | ECCP1 Enhanced PWM output, channel C; takes priority over port and PSP data. May be configured for tri-state during Enhanced PWM shutdown events. |
| RD7/PSP7/P1D | RD7      | 0               | 0                           | DIG         | LATD<7> data output.  |
|              |          | 1               | I                           | ST          | PORTD<7> data input.  |
|              | PSP7     | х               | 0                           | DIG         | PSP read data output (LATD<7>); takes priority over port data.  |
|              |          | х               | I                           | TTL         | PSP write data input.   |
|              | P1D      | 0               | 0                           | DIG         | ECCP1 Enhanced PWM output, channel D; takes priority over port and PSP data. May be configured for tri-state during Enhanced PWM shutdown events. |

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

TABLE 9-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTD

| Name    | Bit 7  | Bit 6 | Bit 5 | Bit 4   | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|--|-------|-------|---------|--------|--------|--------|--------|----------------------------|--|
| PORTD   | RD7  | RD6   | RD5   | RD4     | RD3    | RD2    | RD1    | RD0    | 52                         |  |
| LATD    | PORTD Data Latch Register (Read and Write to Data Latch) |       |       |         |        |        |        |        |                            |  |
| TRISD   | PORTD Data Direction Control Register                    |       |       |         |        |        |        |        |                            |  |
| TRISE   | IBF  | OBF   | IBOV  | PSPMODE | _      | TRISE2 | TRISE1 | TRISE0 | 52                         |  |
| CCP1CON | P1M1   | P1M0  | DC1B1 | DC1B0   | CCP1M3 | CCP1M2 | CCP1M1 | CCP1M0 | 51                         |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTD.

## 9.5 PORTE, TRISE and LATE Registers

Depending on the particular PIC18F2X1X/4X1X device selected, PORTE is implemented in two different ways.

For 40/44-pin devices, PORTE is a 4-bit wide port. Three pins (RE0/RD/AN5, RE1/WR/AN6 and RE2/CS/AN7) are individually configurable as inputs or outputs. These pins have Schmitt Trigger input buffers. When selected as an analog input, these pins will read as '0's.

The corresponding data direction register is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., put the contents of the output latch on the selected pin).

TRISE controls the direction of the RE pins, even when they are being used as analog inputs. The user must make sure to keep the pins configured as inputs when using them as analog inputs.

**Note:** On a Power-on Reset, RE2:RE0 are configured as analog inputs.

The upper four bits of the TRISE register also control the operation of the Parallel Slave Port. Their operation is explained in Register 9-1.

The Data Latch register (LATE) is also memory mapped. Read-modify-write operations on the LATE register, read and write the latched output value for PORTE.

The fourth pin of PORTE (MCLR/VPP/RE3) is an input only pin. Its operation is controlled by the MCLRE configuration bit. When selected as a port pin (MCLRE = 0), it functions as a digital input only pin; as such, it does not have TRIS or LAT bits associated with its operation. Otherwise, it functions as the device's Master Clear input. In either configuration, RE3 also functions as the programming voltage input during programming.

**Note:** On a Power-on Reset, RE3 is enabled as a digital input only if Master Clear functionality is disabled.

#### **EXAMPLE 9-5: INITIALIZING PORTE**

| CLRF  | PORTE  | ; Initialize PORTE by |
|-------|--------|-----------------------|
|       |        | ; clearing output     |
|       |        | ; data latches        |
| CLRF  | LATE   | ; Alternate method    |
|       |        | ; to clear output     |
|       |        | ; data latches        |
| MOVLW | 0Ah    | ; Configure A/D       |
| MOVWF | ADCON1 | ; for digital inputs  |
| MOVLW | 03h    | ; Value used to       |
|       |        | ; initialize data     |
|       |        | ; direction           |
| MOVWF | TRISE  | ; Set RE<0> as inputs |
|       |        | ; RE<1> as outputs    |
|       |        | ; RE<2> as inputs     |

#### 9.5.1 PORTE IN 28-PIN DEVICES

For 28-pin devices, PORTE is only available when Master Clear functionality is disabled (MCLRE = 0). In these cases, PORTE is a single bit, input only port comprised of RE3 only. The pin operates as previously described.

#### REGISTER 9-1: TRISE REGISTER (40/44-PIN DEVICES ONLY)

| R-0 | R-0 | R/W-0 | R/W-0   | U-0 | R/W-1  | R/W-1  | R/W-1  |
|-----|-----|-------|---------|-----|--------|--------|--------|
| IBF | OBF | IBOV  | PSPMODE | 1   | TRISE2 | TRISE1 | TRISE0 |

bit 7 bit 0

bit 7 IBF: Input Buffer Full Status bit

1 = A word has been received and waiting to be read by the CPU

0 = No word has been received

bit 6 OBF: Output Buffer Full Status bit

1 = The output buffer still holds a previously written word

0 = The output buffer has been read

bit 5 **IBOV:** Input Buffer Overflow Detect bit (in Microprocessor mode)

1 = A write occurred when a previously input word has not been read (must be cleared in software)

0 = No overflow occurred

bit 4 **PSPMODE**: Parallel Slave Port Mode Select bit

1 = Parallel Slave Port mode 0 = General purpose I/O mode

bit 3 Unimplemented: Read as '0'

bit 2 TRISE2: RE2 Direction Control bit

1 = Input0 = Output

bit 1 TRISE1: RE1 Direction Control bit

1 = Input 0 = Output

bit 0 TRISE0: RE0 Direction Control bit

1 = Input
0 = Output

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

TABLE 9-9: PORTE I/O SUMMARY

| Pin                         | Function | TRIS<br>Setting | I/O                             | I/O<br>Type | Description  |
|-----------------------------|----------|-----------------|---------------------------------|-------------|--|
| RE0/RD/AN5                  | RE0      | 0               | 0                               | DIG         | LATE<0> data output; not affected by analog input.   |
|                             |          | 1               | I                               | ST          | PORTE<0> data input; disabled when analog input enabled.   |
|                             | RD       | 1               | - 1                             | TTL         | PSP read enable input (PSP enabled).   |
|                             | AN5      | 1               | I                               | ANA         | A/D input channel 5; default input configuration on POR.   |
| RE1/WR/AN6                  | RE1      | 0               | 0                               | DIG         | LATE<1> data output; not affected by analog input.   |
|                             |          | 1               | 1 I ST PORTE<1> data input; dis |             | PORTE<1> data input; disabled when analog input enabled.   |
|                             | WR       | VR 1 I          |                                 | TTL         | PSP write enable input (PSP enabled).  |
|                             | AN6      | 1               | 1                               | ANA         | A/D input channel 6; default input configuration on POR.   |
| RE2/CS/AN7                  | RE2      | 0               | 0                               | DIG         | LATE<2> data output; not affected by analog input.   |
|                             |          | 1               | 1                               | ST          | PORTE<2> data input; disabled when analog input enabled.   |
|                             | cs       | 1               | -                               | TTL         | PSP write enable input (PSP enabled).  |
|                             | AN7      | 1               | 1                               | ANA         | A/D input channel 7; default input configuration on POR.   |
| MCLR/VPP/RE3 <sup>(1)</sup> | MCLR     |                 | Ι                               | ST          | External Master Clear input; enabled when MCLRE configuration bit is set.                              |
|                             | VPP      | _               | I                               | ANA         | High-voltage detection; used for ICSP™ mode entry detection. Always available, regardless of pin mode. |
|                             | RE3      | _(2)            | 1                               | ST          | PORTE<3> data input; enabled when MCLRE configuration bit is clear.                                    |

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

Note 1: RE3 is available on both 28-pin and 40/44-pin devices. All other PORTE pins are only implemented on 40/44-pin devices.

2: RE3 does not have a corresponding TRIS bit to control data direction.

TABLE 9-10: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

| Name                | Bit 7 | Bit 6 | Bit 5 | Bit 4   | Bit 3                | Bit 2                     | Bit 1  | Bit 0  | Reset<br>Values<br>on page |
|---------------------|-------|-------|-------|---------|----------------------|---------------------------|--------|--------|----------------------------|
| PORTE               | _     | _     |       | _       | RE3 <sup>(1,2)</sup> | RE2                       | RE1    | RE0    | 52                         |
| LATE <sup>(2)</sup> |       | _     | _     | _       | _                    | LATE Data Output Register |        |        | 52                         |
| TRISE               | IBF   | OBF   | IBOV  | PSPMODE | _                    | TRISE2                    | TRISE1 | TRISE0 | 52                         |
| ADCON1              |       | _     | VCFG1 | VCFG0   | PCFG3                | PCFG2                     | PCFG1  | PCFG0  | 51                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTE.

Note 1: Implemented only when Master Clear functionality is disabled (MCLRE configuration bit = 0).

**2:** RE3 is the only PORTE bit implemented on both 28-pin and 40/44-pin devices. All other bits are implemented only when PORTE is implemented (i.e., 40/44-pin devices).

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 109

#### 9.6 Parallel Slave Port

**Note:** The Parallel Slave Port is only available on 40/44-pin devices.

In addition to its function as a general I/O port, PORTD can also operate as an 8-bit wide Parallel Slave Port (PSP) or microprocessor port. PSP operation is controlled by the 4 upper bits of the TRISE register (Register 9-1). Setting control bit, PSPMODE (TRISE<4>), enables PSP operation as long as the enhanced CCP module is not operating in dual output or quad output PWM mode. In Slave mode, the port is asynchronously readable and writable by the external world.

The PSP can directly interface to an 8-bit microprocessor data bus. The external microprocessor can read or write the PORTD latch as an 8-bit latch. Setting the control bit PSPMODE enables the PORTE I/O pins to become control inputs for the microprocessor port. When set, port pin RE0 is the RD input, RE1 is the WR input and RE2 is the CS (Chip Select) input. For this functionality, the corresponding data direction bits of the TRISE register (TRISE<2:0>) must be configured as inputs (set). The A/D port configuration bits, PFCG3:PFCG0 (ADCON1<3:0>), must also be set to a value in the range of '1010' through '1111'.

A write to the PSP occurs when both the  $\overline{\text{CS}}$  and  $\overline{\text{WR}}$  lines are first detected low and ends when either are detected high. The PSPIF and IBF flag bits are both set when the write ends.

A read from the PSP occurs when both the  $\overline{CS}$  and  $\overline{RD}$  lines are first detected low. The data in PORTD is read out and the OBF bit is clear. If the user writes new data to PORTD to set OBF, the data is immediately read out; however, the OBF bit is not set.

When either the  $\overline{\text{CS}}$  or  $\overline{\text{RD}}$  lines are detected high, the PORTD pins return to the input state and the PSPIF bit is set. User applications should wait for PSPIF to be set before servicing the PSP; when this happens, the IBF and OBF bits can be polled and the appropriate action taken.

The timing for the control signals in Write and Read modes is shown in Figure 9-3 and Figure 9-4, respectively.

FIGURE 9-2: PORTD AND PORTE
BLOCK DIAGRAM
(PARALLEL SLAVE PORT)




FIGURE 9-3: PARALLEL SLAVE PORT WRITE WAVEFORMS




FIGURE 9-4: PARALLEL SLAVE PORT READ WAVEFORMS




TABLE 9-11: REGISTERS ASSOCIATED WITH PARALLEL SLAVE PORT

| Name   | Bit 7  | Bit 6     | Bit 5  | Bit 4   | Bit 3 | Bit 2     | Bit 1       | Bit 0  | Reset<br>Values<br>on page |  |
|--------|--|-----------|--------|---------|-------|-----------|-------------|--------|----------------------------|--|
| PORTD  | RD7  | RD6       | RD5    | RD4     | RD3   | RD2       | RD1         | RD0    | 52                         |  |
| LATD   | PORTD Data Latch Register (Read and Write to Data Latch) |           |        |         |       |           |             |        |                            |  |
| TRISD  | PORTD Data Direction Control Register                    |           |        |         |       |           |             |        | 52                         |  |
| PORTE  | _  | _         | _      | _       | RE3   | RE2       | RE1         | RE0    | 52                         |  |
| LATE   | _  | _         | _      | _       | _     | LATE Data | Output bits |        | 52                         |  |
| TRISE  | IBF  | OBF       | IBOV   | PSPMODE | _     | TRISE2    | TRISE1      | TRISE0 | 52                         |  |
| INTCON | GIE/GIEH   | PEIE/GIEL | TMR0IF | INT0IE  | RBIE  | TMR0IF    | INT0IF      | RBIF   | 49                         |  |
| PIR1   | PSPIF <sup>(1)</sup>                                     | ADIF      | RCIF   | TXIF    | SSPIF | CCP1IF    | TMR2IF      | TMR1IF | 52                         |  |
| PIE1   | PSPIE <sup>(1)</sup>                                     | ADIE      | RCIE   | TXIE    | SSPIE | CCP1IE    | TMR2IE      | TMR1IE | 52                         |  |
| IPR1   | PSPIP <sup>(1)</sup>                                     | ADIP      | RCIP   | TXIP    | SSPIP | CCP1IP    | TMR2IP      | TMR1IP | 52                         |  |
| ADCON1 | _  | _         | VCFG1  | VCFG0   | PCFG3 | PCFG2     | PCFG1       | PCFG0  | 51                         |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Parallel Slave Port.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 111

NOTES:

#### 10.0 TIMERO MODULE

The Timer0 module incorporates the following features:

- Software selectable operation as a timer or counter in both 8-bit or 16-bit modes
- · Readable and writable registers
- Dedicated 8-bit, software programmable prescaler
- Selectable clock source (internal or external)
- · Edge select for external clock
- Interrupt-on-overflow

The T0CON register (Register 10-1) controls all aspects of the module's operation, including the prescale selection. It is both readable and writable.

A simplified block diagram of the Timer0 module in 8-bit mode is shown in Figure 10-1. Figure 10-2 shows a simplified block diagram of the Timer0 module in 16-bit mode.

#### REGISTER 10-1: TOCON: TIMERO CONTROL REGISTER

| R/W-1  | R/W-1  | R/W-1 | R/W-1 | R/W-1 | R/W-1 | R/W-1 | R/W-1 |
|--------|--------|-------|-------|-------|-------|-------|-------|
| TMR00N | T08BIT | T0CS  | T0SE  | PSA   | T0PS2 | T0PS1 | T0PS0 |
| bit 7  |        |       |       |       |       |       | bit 0 |

- bit 7 TMR00N: Timer0 On/Off Control bit
  - 1 = Enables Timer0
  - 0 = Stops Timer0
- bit 6 T08BIT: Timer0 8-bit/16-bit Control bit
  - 1 = Timer0 is configured as an 8-bit timer/counter
  - 0 = Timer0 is configured as a 16-bit timer/counter
- bit 5 TOCS: Timer0 Clock Source Select bit
  - 1 = Transition on T0CKI pin
  - 0 = Internal instruction cycle clock (CLKO)
- bit 4 T0SE: Timer0 Source Edge Select bit
  - 1 = Increment on high-to-low transition on TOCKI pin
  - 0 = Increment on low-to-high transition on T0CKI pin
- bit 3 **PSA**: Timer0 Prescaler Assignment bit
  - 1 = Tlmer0 prescaler is NOT assigned. Timer0 clock input bypasses prescaler.
  - 0 = Timer0 prescaler is assigned. Timer0 clock input comes from prescaler output.
- bit 2-0 TOPS2:TOPS0: Timer0 Prescaler Select bits
  - 111 = 1:256 Prescale value
  - 110 = 1:128 Prescale value
  - 101 = 1:64 Prescale value
  - 100 = 1:32 Prescale value
  - 011 = 1:16 Prescale value
  - 010 = 1:8 Prescale value
  - 001 = 1:4 Prescale value
  - 000 = 1:2 Prescale value

#### Legend:

| R = Readable bit  | = Readable bit W = Writable bit |  | oit, read as '0'   |
|-------------------|---------------------------------|--|--------------------|
| -n = Value at POR | Value at POR '1' = Bit is set   |  | x = Bit is unknown |

#### 10.1 Timer0 Operation

Timer0 can operate as either a timer or a counter; the mode is selected with the ToCS bit (ToCON<5>). In Timer mode (ToCS = 0), the module increments on every clock by default unless a different prescaler value is selected (see **Section 10.3 "Prescaler"**). If the TMR0 register is written to, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0 register.

The Counter mode is selected by setting the T0CS bit (= 1). In this mode, Timer0 increments either on every rising or falling edge of pin RA4/T0CKI. The incrementing edge is determined by the Timer0 Source Edge Select bit, T0SE (T0CON<4>); clearing this bit selects the rising edge. Restrictions on the external clock input are discussed below.

An external clock source can be used to drive Timer0; however, it must meet certain requirements to ensure that the external clock can be synchronized with the


internal phase clock (Tosc). There is a delay between synchronization and the onset of incrementing the timer/counter.

## 10.2 Timer0 Reads and Writes in 16-Bit Mode


TMR0H is not the actual high byte of Timer0 in 16-bit mode; it is actually a buffered version of the real high byte of Timer0 which is not directly readable nor writable (refer to Figure 10-2). TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16 bits of Timer0 without having to verify that the read of the high and low byte were valid, due to a rollover between successive reads of the high and low byte.

Similarly, a write to the high byte of Timer0 must also take place through the TMR0H Buffer register. The high byte is updated with the contents of TMR0H when a write occurs to TMR0L. This allows all 16 bits of Timer0 to be updated at once.

#### FIGURE 10-1: TIMERO BLOCK DIAGRAM (8-BIT MODE)



#### FIGURE 10-2: TIMERO BLOCK DIAGRAM (16-BIT MODE)



#### 10.3 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module. The prescaler is not directly readable or writable; its value is set by the PSA and T0PS2:T0PS0 bits (T0CON<3:0>), which determine the prescaler assignment and prescale ratio.

Clearing the PSA bit assigns the prescaler to the Timer0 module. When it is assigned, prescale values from 1:2 through 1:256 in power-of-2 increments are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF TMR0, MOVWF TMR0, BSF TMR0, etc.) clear the prescaler count.

**Note:** Writing to TMR0 when the prescaler is assigned to Timer0 will clear the prescaler count but will not change the prescaler assignment.

## 10.3.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control and can be changed "on-the-fly" during program execution.

#### 10.4 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h in 8-bit mode, or from FFFFh to 0000h in 16-bit mode. This overflow sets the TMR0IF flag bit. The interrupt can be masked by clearing the TMR0IE bit (INTCON<5>). Before re-enabling the interrupt, the TMR0IF bit must be cleared in software by the Interrupt Service Routine.

Since Timer0 is shut down in Sleep mode, the TMR0 interrupt cannot awaken the processor from Sleep.

TABLE 10-1: REGISTERS ASSOCIATED WITH TIMERO

| Name   | Bit 7              | Bit 6                     | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0 | Reset<br>Values<br>on page |  |
|--------|--------------------|---------------------------|--------|--------|-------|--------|--------|-------|----------------------------|--|
| TMR0L  | Timer0 Reg         | Timer0 Register, Low Byte |        |        |       |        |        |       |                            |  |
| TMR0H  | Timer0 Reg         | ister, High B             | yte    |        |       |        |        |       | 50                         |  |
| INTCON | GIE/GIEH           | PEIE/GIEL                 | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF  | 49                         |  |
| T0CON  | TMR00N             | T08BIT                    | T0CS   | T0SE   | PSA   | T0PS2  | T0PS1  | T0PS0 | 50                         |  |
| TRISA  | RA7 <sup>(1)</sup> | RA6 <sup>(1)</sup>        | RA5    | RA4    | RA3   | RA2    | RA1    | RA0   | 52                         |  |

**Legend:** Shaded cells are not used by Timer0.

**Note 1:** PORTA<7:6> and their direction bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 115

NOTES:

#### 11.0 TIMER1 MODULE

The Timer1 timer/counter module incorporates these features:

- Software selectable operation as a 16-bit timer or counter
- Readable and writable 8-bit registers (TMR1H and TMR1L)
- Selectable clock source (internal or external) with device clock or Timer1 oscillator internal options
- Interrupt-on-overflow
- · Reset on CCP special event trigger
- Device clock status flag (T1RUN)

A simplified block diagram of the Timer1 module is shown in Figure 11-1. A block diagram of the module's operation in Read/Write mode is shown in Figure 11-2.

The module incorporates its own low-power oscillator to provide an additional clocking option. The Timer1 oscillator can also be used as a low-power clock source for the microcontroller in power managed operation.

Timer1 can also be used to provide Real-Time Clock (RTC) functionality to applications with only a minimal addition of external components and code overhead.

Timer1 is controlled through the T1CON Control register (Register 11-1). It also contains the Timer1 Oscillator Enable bit (T1OSCEN). Timer1 can be enabled or disabled by setting or clearing control bit, TMR1ON (T1CON<0>).

#### REGISTER 11-1: T1CON: TIMER1 CONTROL REGISTER

| R/W-0 | R-0   | R/W-0   | R/W-0   | R/W-0   | R/W-0  | R/W-0  | R/W-0  |
|-------|-------|---------|---------|---------|--------|--------|--------|
| RD16  | T1RUN | T1CKPS1 | T1CKPS0 | T1OSCEN | T1SYNC | TMR1CS | TMR10N |
| bit 7 |       |         |         |         |        |        | bit 0  |

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register read/write of Tlmer1 in one 16-bit operation
  - 0 = Enables register read/write of Timer1 in two 8-bit operations
- bit 6 T1RUN: Timer1 System Clock Status bit
  - 1 = Device clock is derived from Timer1 oscillator
  - 0 = Device clock is derived from another source
- bit 5-4 T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 3 T10SCEN: Timer1 Oscillator Enable bit
  - 1 = Timer1 oscillator is enabled
  - 0 = Timer1 oscillator is shut off

The oscillator inverter and feedback resistor are turned off to eliminate power drain.

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Select bit

#### When TMR1CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

#### When TMR1CS = 0:

This bit is ignored. Timer1 uses the internal clock when TMR1CS = 0.

- bit 1 TMR1CS: Timer1 Clock Source Select bit
  - 1 = External clock from pin RC0/T10SO/T13CKI (on the rising edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR10N: Timer1 On bit
  - 1 = Enables Timer1
  - 0 = Stops Timer1

| Legend | : |
|--------|---|
|--------|---|

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 11.1 Timer1 Operation

Timer1 can operate in one of these modes:


- Timer
- · Synchronous Counter
- · Asynchronous Counter

The operating mode is determined by the clock select bit, TMR1CS (T1CON<1>). When TMR3CS is cleared (= 0), Timer1 increments on every internal instruction


cycle (Fosc/4). When the bit is set, Timer1 increments on every rising edge of the Timer1 external clock input or the Timer1 oscillator. if enabled.

When Timer1 is enabled, the RC1/T1OSI and RC0/T1OSO/T13CKI pins become inputs. This means the values of TRISC<1:0> are ignored and the pins are read as '0'.

#### FIGURE 11-1: TIMER1 BLOCK DIAGRAM



#### FIGURE 11-2: TIMER1 BLOCK DIAGRAM (16-BIT READ/WRITE MODE)



#### 11.2 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes (see Figure 11-2). When the RD16 control bit (T1CON<7>) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L will load the contents of the high byte of Timer1 into the Timer1 high byte buffer. This provides the user with the ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, has become invalid due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H Buffer register. The Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits to both the high and low bytes of Timer1 at once.

The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 High Byte Buffer register. Writes to TMR1H do not clear the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

#### 11.3 Timer1 Oscillator

An on-chip crystal oscillator circuit is incorporated between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting the Timer1 Oscillator Enable bit, T1OSCEN (T1CON<3>). The oscillator is a low-power circuit rated for 32 kHz crystals. It will continue to run during all power managed modes. The circuit for a typical LP oscillator is shown in Figure 11-3. Table 11-1 shows the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper start-up of the Timer1 oscillator.

FIGURE 11-3: EXTERNAL

COMPONENTS FOR THE

TIMER1 LP OSCILLATOR




TABLE 11-1: CAPACITOR SELECTION FOR THE TIMER OSCILLATOR

| Osc Type | Freq   | C1                   | C2                   |  |
|----------|--------|----------------------|----------------------|--|
| LP       | 32 kHz | 27 pF <sup>(1)</sup> | 27 pF <sup>(1)</sup> |  |

- Note 1: Microchip suggests these values as a starting point in validating the oscillator circuit.
  - 2: Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **4:** Capacitor values are for design guidance only.

### 11.3.1 USING TIMER1 AS A CLOCK SOURCE

The Timer1 oscillator is also available as a clock source in power managed modes. By setting the clock select bits, SCS1:SCS0 (OSCCON<1:0>), to '01', the device switches to SEC\_RUN mode; both the CPU and peripherals are clocked from the Timer1 oscillator. If the IDLEN bit (OSCCON<7>) is cleared and a SLEEP instruction is executed, the device enter SEC\_IDLE mode. Additional details are available in **Section 3.0** "Power Managed Modes".

Whenever the Timer1 oscillator is providing the clock source, the Timer1 system clock status flag, T1RUN (T1CON<6>), is set. This can be used to determine the controller's current clocking mode. It can also indicate the clock source being currently used by the Fail-Safe Clock Monitor. If the Clock Monitor is enabled and the Timer1 oscillator fails while providing the clock, polling the T1RUN bit will indicate whether the clock is being provided by the Timer1 oscillator or another source.

#### 11.3.2 LOW-POWER TIMER1 OPTION

The Timer1 oscillator can operate at two distinct levels of power consumption based on device configuration. When the LPT1OSC configuration bit is set, the Timer1 oscillator operates in a low-power mode. When LPT1OSC is not set, Timer1 operates at a higher power level. Power consumption for a particular mode is relatively constant, regardless of the device's operating mode. The default Timer1 configuration is the higher power mode.

As the low-power Timer1 mode tends to be more sensitive to interference, high noise environments may cause some oscillator instability. The low-power option is, therefore, best suited for low noise applications where power conservation is an important design consideration.


### 11.3.3 TIMER1 OSCILLATOR LAYOUT CONSIDERATIONS

The Timer1 oscillator circuit draws very little power during operation. Due to the low-power nature of the oscillator, it may also be sensitive to rapidly changing signals in close proximity.

The oscillator circuit, shown in Figure 11-3, should be located as close as possible to the microcontroller. There should be no circuits passing within the oscillator circuit boundaries other than Vss or VDD.

If a high-speed circuit must be located near the oscillator (such as the CCP1 pin in Output Compare or PWM mode, or the primary oscillator using the OSC2 pin), a grounded guard ring around the oscillator circuit, as shown in Figure 11-4, may be helpful when used on a single-sided PCB or in addition to a ground plane.

FIGURE 11-4: OSCILLATOR CIRCUIT WITH GROUNDED GUARD RING



### 11.4 Timer1 Interrupt

The TMR1 register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The Timer1 interrupt, if enabled, is generated on overflow, which is latched in interrupt flag bit, TMR1IF (PIR1<0>). This interrupt can be enabled or disabled by setting or clearing the Timer1 Interrupt Enable bit, TMR1IE (PIE1<0>).

## 11.5 Resetting Timer1 Using the CCP Special Event Trigger

If either of the CCP modules is configured to use Timer1 and generate a Special Event Trigger in Compare mode (CCP1M3:CCP1M0 or CCP2M3:CCP2M0 = 1011), this signal will reset Timer1. The trigger from CCP2 will also start an A/D conversion if the A/D module is enabled (see **Section 14.3.4 "Special Event Trigger"** for more information).

The module must be configured as either a timer or a synchronous counter to take advantage of this feature. When used this way, the CCPRH:CCPRL register pair effectively becomes a period register for Timer1.

If Timer1 is running in Asynchronous Counter mode, this Reset operation may not work.

In the event that a write to Timer1 coincides with a special event trigger, the write operation will take precedence.

**Note:** The special event triggers from the CCP2 module will not set the TMR1IF interrupt flag bit (PIR1<0>).

### 11.6 Using Timer1 as a Real-Time Clock


Adding an external LP oscillator to Timer1 (such as the one described in **Section 11.3** "Timer1 Oscillator" above) gives users the option to include RTC functionality to their applications. This is accomplished with an inexpensive watch crystal to provide an accurate time base and several lines of application code to calculate the time. When operating in Sleep mode and using a battery or supercapacitor as a power source, it can completely eliminate the need for a separate RTC device and battery backup.

The application code routine, RTCisr, shown in Example 11-1, demonstrates a simple method to increment a counter at one-second intervals using an Interrupt Service Routine. Incrementing the TMR1 register pair to overflow triggers the interrupt and calls the routine, which increments the seconds counter by one; additional counters for minutes and hours are incremented as the previous counter overflow.

Since the register pair is 16 bits wide, counting up to overflow the register directly from a 32.768 kHz clock would take 2 seconds. To force the overflow at the required one-second intervals, it is necessary to preload it. The simplest method is to set the MSb of TMR1H with a BSF instruction. Note that the TMR1L register is never preloaded or altered. Doing so may introduce cumulative errors over many cycles.

For this method to be accurate, Timer1 must operate in Asynchronous mode and the Timer1 overflow interrupt must be enabled (PIE1<0> = 1), as shown in the routine, RTCinit. The Timer1 oscillator must also be enabled and running at all times.

#### EXAMPLE 11-1: IMPLEMENTING A REAL-TIME CLOCK USING A TIMER1 INTERRUPT SERVICE



#### TABLE 11-2: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

| Name   | Bit 7                      | Bit 6         | Bit 5   | Bit 4   | Bit 3   | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |
|--------|----------------------------|---------------|---------|---------|---------|--------|--------|--------|----------------------------|
| INTCON | GIE/GIEH                   | PEIE/GIEL     | TMR0IE  | INT0IE  | RBIE    | TMR0IF | INT0IF | RBIF   | 49                         |
| PIR1   | PSPIF <sup>(1)</sup>       | ADIF          | RCIF    | TXIF    | SSPIF   | CCP1IF | TMR2IF | TMR1IF | 52                         |
| PIE1   | PSPIE <sup>(1)</sup>       | ADIE          | RCIE    | TXIE    | SSPIE   | CCP1IE | TMR2IE | TMR1IE | 52                         |
| IPR1   | PSPIP <sup>(1)</sup>       | ADIP          | RCIP    | TXIP    | SSPIP   | CCP1IP | TMR2IP | TMR1IP | 52                         |
| TMR1L  | Timer1 Reg                 | gister, Low B | yte     |         |         |        |        |        | 50                         |
| TMR1H  | Timer1 Register, High Byte |               |         |         |         |        |        |        |                            |
| T1CON  | RD16                       | T1RUN         | T1CKPS1 | T1CKPS0 | T10SCEN | T1SYNC | TMR1CS | TMR10N | 50                         |

Legend: Shaded cells are not used by the Timer1 module.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 121

NOTES:

#### 12.0 TIMER2 MODULE

The Timer2 module timer incorporates the following features:

- 8-bit timer and period registers (TMR2 and PR2, respectively)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4 and 1:16)
- Software programmable postscaler (1:1 through 1:16)
- Interrupt on TMR2-to-PR2 match
- Optional use as the shift clock for the MSSP module

The module is controlled through the T2CON register (Register 12-1), which enables or disables the timer and configures the prescaler and postscaler. Timer2 can be shut off by clearing control bit, TMR2ON (T2CON<2>), to minimize power consumption.

A simplified block diagram of the module is shown in Figure 12-1.

#### 12.1 Timer2 Operation

In normal operation, TMR2 is incremented from 00h on each clock (Fosc/4). A 4-bit counter/prescaler on the clock input gives direct input, divide-by-4 and divide-by-16 prescale options; these are selected by the prescaler control bits, T2CKPS1:T2CKPS0 (T2CON<1:0>). The value of TMR2 is compared to that of the period register, PR2, on each clock cycle. When the two values match, the comparator generates a match signal as the timer output. This signal also resets the value of TMR2 to 00h on the next cycle and drives the output counter/postscaler (see Section 12.2 "Timer2 Interrupt").

The TMR2 and PR2 registers are both directly readable and writable. The TMR2 register is cleared on any device Reset, while the PR2 register initializes at FFh. Both the prescaler and postscaler counters are cleared on the following events:

- a write to the TMR2 register
- a write to the T2CON register
- any device Reset (Power-on Reset, MCLR Reset, Watchdog Timer Reset or Brown-out Reset)

TMR2 is not cleared when T2CON is written.

#### REGISTER 12-1: T2CON: TIMER2 CONTROL REGISTER

| U-0   | R/W-0    | R/W-0    | R/W-0    | R/W-0    | R/W-0  | R/W-0   | R/W-0   |
|-------|----------|----------|----------|----------|--------|---------|---------|
| _     | T2OUTPS3 | T2OUTPS2 | T2OUTPS1 | T2OUTPS0 | TMR2ON | T2CKPS1 | T2CKPS0 |
| bit 7 |          |          |          |          |        |         | bit 0   |

bit 7 Unimplemented: Read as '0'

bit 6-3 T20UTPS3:T20UTPS0: Timer2 Output Postscale Select bits

0000 = 1:1 Postscale 0001 = 1:2 Postscale

•

1111 = 1:16 Postscale

bit 2 TMR2ON: Timer2 On bit

1 = Timer2 is on

0 = Timer2 is off

bit 1-0 T2CKPS1:T2CKPS0: Timer2 Clock Prescale Select bits

00 = Prescaler is 1 01 = Prescaler is 4 1x = Prescaler is 16

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 12.2 Timer2 Interrupt

Timer2 also can generate an optional device interrupt. The Timer2 output signal (TMR2-to-PR2 match) provides the input for the 4-bit output counter/ postscaler. This counter generates the TMR2 match interrupt flag which is latched in TMR2IF (PIR1<1>). The interrupt is enabled by setting the TMR2 Match Interrupt Enable bit, TMR2IE (PIE1<1>).

A range of 16 postscale options (from 1:1 through 1:16 inclusive) can be selected with the postscaler control bits, T2OUTPS3:T2OUTPS0 (T2CON<6:3>).

#### 12.3 Timer2 Output

The unscaled output of TMR2 is available primarily to the CCP modules, where it is used as a time base for operations in PWM mode.

Timer2 can be optionally used as the shift clock source for the MSSP module operating in SPI mode. Additional information is provided in **Section 16.0 "Master Synchronous Serial Port (MSSP) Module"**.

FIGURE 12-1: TIMER2 BLOCK DIAGRAM




TABLE 12-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

| Name   | Bit 7                | Bit 6                  | Bit 5    | Bit 4    | Bit 3    | Bit 2  | Bit 1   | Bit 0   | Reset<br>Values<br>on page |
|--------|----------------------|------------------------|----------|----------|----------|--------|---------|---------|----------------------------|
| INTCON | GIE/GIEH             | PEIE/GIEL              | TMR0IE   | INT0IE   | RBIE     | TMR0IF | INT0IF  | RBIF    | 49                         |
| PIR1   | PSPIF <sup>(1)</sup> | ADIF                   | RCIF     | TXIF     | SSPIF    | CCP1IF | TMR2IF  | TMR1IF  | 52                         |
| PIE1   | PSPIE <sup>(1)</sup> | ADIE                   | RCIE     | TXIE     | SSPIE    | CCP1IE | TMR2IE  | TMR1IE  | 52                         |
| IPR1   | PSPIP <sup>(1)</sup> | ADIP                   | RCIP     | TXIP     | SSPIP    | CCP1IP | TMR2IP  | TMR1IP  | 52                         |
| TMR2   | Timer2 Reg           | ister                  |          |          |          |        |         |         | 50                         |
| T2CON  | 1                    | T2OUTPS3               | T2OUTPS2 | T2OUTPS1 | T2OUTPS0 | TMR2ON | T2CKPS1 | T2CKPS0 | 50                         |
| PR2    | Timer2 Peri          | Timer2 Period Register |          |          |          |        |         |         |                            |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Timer2 module.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

#### 13.0 TIMER3 MODULE

The Timer3 module timer/counter incorporates these features:

- Software selectable operation as a 16-bit timer or counter
- Readable and writable 8-bit registers (TMR3H and TMR3L)
- Selectable clock source (internal or external) with device clock or Timer1 oscillator internal options
- Interrupt-on-overflow
- · Module Reset on CCP special event trigger

A simplified block diagram of the Timer3 module is shown in Figure 13-1. A block diagram of the module's operation in Read/Write mode is shown in Figure 13-2.

The Timer3 module is controlled through the T3CON register (Register 13-1). It also selects the clock source options for the CCP modules (see **Section 14.1.1** "CCP Modules and Timer Resources" for more information).

#### REGISTER 13-1: T3CON: TIMER3 CONTROL REGISTER

| R/W-0 | R/W-0  | R/W-0   | R/W-0   | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|--------|---------|---------|--------|--------|--------|--------|
| RD16  | T3CCP2 | T3CKPS1 | T3CKPS0 | T3CCP1 | T3SYNC | TMR3CS | TMR3ON |
| bit 7 |        |         |         |        |        |        | bit 0  |

- bit 7 RD16: 16-bit Read/Write Mode Enable bit
  - 1 = Enables register read/write of Timer3 in one 16-bit operation
  - 0 = Enables register read/write of Timer3 in two 8-bit operations
- bit 6,3 T3CCP2:T3CCP1: Timer3 and Timer1 to CCPx Enable bits
  - 1x = Timer3 is the capture/compare clock source for the CCP modules
  - 01 = Timer3 is the capture/compare clock source for CCP2; Timer1 is the capture/compare clock source for CCP1
  - 00 = Timer1 is the capture/compare clock source for the CCP modules
- bit 5-4 T3CKPS1:T3CKPS0: Timer3 Input Clock Prescale Select bits
  - 11 = 1:8 Prescale value
  - 10 = 1:4 Prescale value
  - 01 = 1:2 Prescale value
  - 00 = 1:1 Prescale value
- bit 2 **T3SYNC:** Timer3 External Clock Input Synchronization Control bit

(Not usable if the device clock comes from Timer1/Timer3.)

#### When TMR3CS = 1:

- 1 = Do not synchronize external clock input
- 0 = Synchronize external clock input

#### When TMR3CS = 0:

This bit is ignored. Timer3 uses the internal clock when TMR3CS = 0.

- bit 1 TMR3CS: Timer3 Clock Source Select bit
  - 1 = External clock input from Timer1 oscillator or T13CKI (on the rising edge after the first falling edge)
  - 0 = Internal clock (Fosc/4)
- bit 0 TMR3ON: Timer3 On bit
  - 1 = Enables Timer3
  - 0 = Stops Timer3

| Lea | CII | u. |
|-----|-----|----|

| R = Readable bit  | R = Readable bit W = Writable bit |                      | bit, read as '0'   |
|-------------------|-----------------------------------|----------------------|--------------------|
| -n = Value at POR | '1' = Bit is set                  | '0' = Bit is cleared | x = Bit is unknown |

#### 13.1 Timer3 Operation


Timer3 can operate in one of three modes:

- Timer
- · Synchronous Counter
- · Asynchronous Counter


The operating mode is determined by the clock select bit, TMR3CS (T3CON<1>). When TMR3CS is cleared (= 0), Timer3 increments on every internal instruction cycle (Fosc/4). When the bit is set, Timer3 increments on every rising edge of the Timer1 external clock input or the Timer1 oscillator, if enabled.

As with Timer1, the RC1/T1OSI and RC0/T1OSO/T13CKI pins become inputs when the Timer1 oscillator is enabled. This means the values of TRISC<1:0> are ignored and the pins are read as '0'.

#### FIGURE 13-1: TIMER3 BLOCK DIAGRAM



#### FIGURE 13-2: TIMER3 BLOCK DIAGRAM (16-BIT READ/WRITE MODE)



#### 13.2 Timer3 16-Bit Read/Write Mode

Timer3 can be configured for 16-bit reads and writes (see Figure 13-2). When the RD16 control bit (T3CON<7>) is set, the address for TMR3H is mapped to a buffer register for the high byte of Timer3. A read from TMR3L will load the contents of the high byte of Timer3 into the Timer3 High Byte Buffer register. This provides the user with the ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, has become invalid due to a rollover between reads.

A write to the high byte of Timer3 must also take place through the TMR3H Buffer register. The Timer3 high byte is updated with the contents of TMR3H when a write occurs to TMR3L. This allows a user to write all 16 bits to both the high and low bytes of Timer3 at once.

The high byte of Timer3 is not directly readable or writable in this mode. All reads and writes must take place through the Timer3 High Byte Buffer register.

Writes to TMR3H do not clear the Timer3 prescaler. The prescaler is only cleared on writes to TMR3L.

## 13.3 Using the Timer1 Oscillator as the Timer3 Clock Source

The Timer1 internal oscillator may be used as the clock source for Timer3. The Timer1 oscillator is enabled by setting the T1OSCEN (T1CON<3>) bit. To use it as the Timer3 clock source, the TMR3CS bit must also be set. As previously noted, this also configures Timer3 to increment on every rising edge of the oscillator source.

The Timer1 oscillator is described in **Section 11.0** "Timer1 Module".

#### 13.4 Timer3 Interrupt

The TMR3 register pair (TMR3H:TMR3L) increments from 0000h to FFFFh and overflows to 0000h. The Timer3 interrupt, if enabled, is generated on overflow and is latched in interrupt flag bit, TMR3IF (PIR2<1>). This interrupt can be enabled or disabled by setting or clearing the Timer3 Interrupt Enable bit, TMR3IE (PIE2<1>).

### 13.5 Resetting Timer3 Using the CCP Special Event Trigger

If either of the CCP modules is configured to use Timer3 and to generate a special event trigger in Compare mode (CCP1M3:CCP1M0 or CCP2M3:CCP2M0 = 1011), this signal will reset Timer3. It will also start an A/D conversion if the A/D module is enabled (see **Section 14.3.4** "**Special Event Trigger**" for more information).

The module must be configured as either a timer or synchronous counter to take advantage of this feature. When used this way, the CCPR2H:CCPR2L register pair effectively becomes a period register for Timer3.

If Timer3 is running in Asynchronous Counter mode, the Reset operation may not work.

In the event that a write to Timer3 coincides with a special event trigger from a CCP module, the write will take precedence.

Note: The special event triggers from the CCP2 module will not set the TMR3IF interrupt flag bit (PIR1<0>).

TABLE 13-1: REGISTERS ASSOCIATED WITH TIMER3 AS A TIMER/COUNTER

| Name   | Bit 7                      | Bit 6         | Bit 5   | Bit 4   | Bit 3   | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |
|--------|----------------------------|---------------|---------|---------|---------|--------|--------|--------|----------------------------|
| INTCON | GIE/GIEH                   | PEIE/GIEL     | TMR0IE  | INT0IE  | RBIE    | TMR0IF | INT0IF | RBIF   | 49                         |
| PIR2   | OSCFIF                     | CMIF          | _       | _       | BCLIF   | HLVDIF | TMR3IF | CCP2IF | 52                         |
| PIE2   | OSCFIE                     | CMIE          | _       | _       | BCLIE   | HLVDIE | TMR3IE | CCP2IE | 52                         |
| IPR2   | OSCFIP                     | CMIP          | _       | _       | BCLIP   | HLVDIP | TMR3IP | CCP2IP | 52                         |
| TMR3L  | Timer3 Reg                 | gister, Low B | yte     |         |         |        |        |        | 51                         |
| TMR3H  | Timer3 Register, High Byte |               |         |         |         |        | 51     |        |                            |
| T1CON  | RD16                       | T1RUN         | T1CKPS1 | T1CKPS0 | T10SCEN | T1SYNC | TMR1CS | TMR10N | 50                         |
| T3CON  | RD16                       | T3CCP2        | T3CKPS1 | T3CKPS0 | T3CCP1  | T3SYNC | TMR3CS | TMR3ON | 51                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Timer3 module.

NOTES:

## 14.0 CAPTURE/COMPARE/PWM (CCP) MODULES

PIC18F2X1X/4X1X devices all have two CCP (Capture/Compare/PWM) modules. Each module contains a 16-bit register which can operate as a 16-bit Capture register, a 16-bit Compare register or a PWM Master/Slave Duty Cycle register.

In 28-pin devices, the two standard CCP modules (CCP1 and CCP2) operate as described in this chapter. In 40/44-pin devices, CCP1 is implemented as an Enhanced CCP module with standard Capture and Compare modes and Enhanced PWM modes. The ECCP implementation is discussed in **Section 15.0** "Enhanced Capture/Compare/PWM (ECCP) Module".

The Capture and Compare operations described in this chapter apply to all standard and Enhanced CCP modules.

Note: Throughout this section and Section 15.0 "Enhanced Capture/Compare/PWM (ECCP) Module", references to the register and bit names for CCP modules are referred to generically by the use of 'x' or 'y' in place of the specific module number. Thus, "CCPxCON" might refer to the control register for CCP1, CCP2 or ECCP1. "CCPxCON" is used throughout these sections to refer to the module control register, regardless of whether the CCP module is a standard or Enhanced implementation.

### REGISTER 14-1: CCPXCON REGISTER (CCP2 MODULE, CCP1 MODULE IN 28-PIN DEVICES)

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|-----|-------|-------|--------|--------|--------|--------|
| _     | _   | DCxB1 | DCxB0 | CCPxM3 | CCPxM2 | CCPxM1 | CCPxM0 |
| bit 7 |     |       |       |        |        |        | bit 0  |

bit 7-6 Unimplemented: Read as '0'

bit 5-4 DCxB1:DCxB0: PWM Duty Cycle bit 1 and bit 0 for CCP Module x

Capture mode:

Unused.

Compare mode:

Unused.

#### PWM mode:

These bits are the two LSbs (bit 1 and bit 0) of the 10-bit PWM duty cycle. The eight MSbs (DCx9:DCx2) of the duty cycle are found in CCPRxL.

#### bit 3-0 CCPxM3:CCPxM0: CCP Module x Mode Select bits

0000 = Capture/Compare/PWM disabled (resets CCP module)

0001 = Reserved

0010 = Compare mode, toggle output on match (CCPIF bit is set)

0011 = Reserved

0100 = Capture mode, every falling edge

0101 = Capture mode, every rising edge

0110 = Capture mode, every 4th rising edge

0111 = Capture mode, every 16th rising edge

1000 = Compare mode: initialize CCP pin low; on compare match, force CCP pin high (CCPIF bit is set)

1001 = Compare mode: initialize CCP pin high; on compare match, force CCP pin low (CCPIF bit is set)

1010 = Compare mode: generate software interrupt on compare match (CCPIF bit is set, CCP pin reflects I/O state)

1011 = Compare mode: trigger special event, reset timer, start A/D conversion on CCP2 match (CCPxIF bit is set)

 $11xx = PWM \mod e$ 

### Legend:

| •                                 |                  |                                    |                    |  |  |  |
|-----------------------------------|------------------|------------------------------------|--------------------|--|--|--|
| R = Readable bit W = Writable bit |                  | U = Unimplemented bit, read as '0' |                    |  |  |  |
| -n = Value at POR                 | '1' = Bit is set | '0' = Bit is cleared               | x = Bit is unknown |  |  |  |

#### 14.1 CCP Module Configuration

Each Capture/Compare/PWM module is associated with a control register (generically, CCPxCON) and a data register (CCPRx). The data register, in turn, is comprised of two 8-bit registers: CCPRxL (low byte) and CCPRxH (high byte). All registers are both readable and writable.

### 14.1.1 CCP MODULES AND TIMER RESOURCES

The CCP modules utilize Timers 1, 2 or 3, depending on the mode selected. Timer1 and Timer3 are available to modules in Capture or Compare modes, while Timer2 is available for modules in PWM mode.

TABLE 14-1: CCP MODE – TIMER RESOURCE

| CCP/ECCP Mode | Timer Resource   |
|---------------|------------------|
| Capture       | Timer1 or Timer3 |
| Compare       | Timer1 or Timer3 |
| PWM           | Timer2           |

The assignment of a particular timer to a module is determined by the Timer-to-CCP enable bits in the T3CON register (Register 13-1). Both modules may be active at any given time and may share the same timer resource if they are configured to operate in the same mode (Capture/Compare or PWM) at the same time. The interactions between the two modules are summarized in Figure 14-1 and Figure 14-2. In Timer1 in Asynchronous Counter mode, the capture operation will not work.

#### 14.1.2 CCP2 PIN ASSIGNMENT

The pin assignment for CCP2 (Capture input, Compare and PWM output) can change, based on device configuration. The CCP2MX configuration bit determines which pin CCP2 is multiplexed to. By default, it is assigned to RC1 (CCP2MX = 1). If the configuration bit is cleared, CCP2 is multiplexed with RB3.

Changing the pin assignment of CCP2 does not automatically change any requirements for configuring the port pin. Users must always verify that the appropriate TRIS register is configured correctly for CCP2 operation, regardless of where it is located.

TABLE 14-2: INTERACTIONS BETWEEN CCP1 AND CCP2 FOR TIMER RESOURCES

| CCP1 Mode          | CCP2 Mode          | Interaction   |
|--------------------|--------------------|---|
| Capture            | Capture            | Each module can use TMR1 or TMR3 as the time base. The time base can be different for each CCP.   |
| Capture            | Compare            | CCP2 can be configured for the special event trigger to reset TMR1 or TMR3 (depending upon which time base is used). Automatic A/D conversions on trigger event can also be done. Operation of CCP1 could be affected if it is using the same timer as a time base. |
| Compare            | Capture            | CCP1 can be configured for the special event trigger to reset TMR1 or TMR3 (depending upon which time base is used). Operation of CCP2 could be affected if it is using the same timer as a time base.  |
| Compare            | Compare            | Either module can be configured for the Special Event Trigger to reset the time base. Automatic A/D conversions on CCP2 trigger event can be done. Conflicts may occur if both modules are using the same time base.  |
| Capture            | PWM <sup>(1)</sup> | None  |
| Compare            | PWM <sup>(1)</sup> | None  |
| PWM <sup>(1)</sup> | Capture            | None  |
| PWM <sup>(1)</sup> | Compare            | None  |
| PWM <sup>(1)</sup> | PWM                | Both PWMs will have the same frequency and update rate (TMR2 interrupt).  |

Note 1: Includes standard and Enhanced PWM operation.

### 14.2 Capture Mode

In Capture mode, the CCPRxH:CCPRxL register pair captures the 16-bit value of the TMR1 or TMR3 registers when an event occurs on the corresponding CCPx pin. An event is defined as one of the following:

- · every falling edge
- · every rising edge
- · every 4th rising edge
- · every 16th rising edge

The event is selected by the mode select bits, CCPxM3:CCPxM0 (CCPxCON<3:0>). When a capture is made, the interrupt request flag bit, CCPxIF, is set; it must be cleared in software. If another capture occurs before the value in register CCPRx is read, the old captured value is overwritten by the new captured value.

#### 14.2.1 CCP PIN CONFIGURATION

In Capture mode, the appropriate CCPx pin should be configured as an input by setting the corresponding TRIS direction bit.

**Note:** If RB3/CCP2 or RC1/CCP2 is configured as an output, a write to the port can cause a capture condition.

#### 14.2.2 TIMER1/TIMER3 MODE SELECTION

The timers that are to be used with the capture feature (Timer1 and/or Timer3) must be running in Timer mode or Synchronized Counter mode. In Asynchronous Counter mode, the capture operation will not work. The timer to be used with each CCP module is selected in the T3CON register (see Section 14.1.1 "CCP Modules and Timer Resources").

#### 14.2.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep the CCPxIE interrupt enable bit clear to avoid false interrupts. The interrupt flag bit, CCPxIF, should also be cleared following any such change in operating mode.

#### 14.2.4 CCP PRESCALER


There are four prescaler settings in Capture mode; they are specified as part of the operating mode selected by the mode select bits (CCPxM3:CCPxM0). Whenever the CCP module is turned off or Capture mode is disabled, the prescaler counter is cleared. This means that any Reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared; therefore, the first capture may be from a non-zero prescaler. Example 14-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

# EXAMPLE 14-1: CHANGING BETWEEN CAPTURE PRESCALERS (CCP2 SHOWN)

```
CLRF CCP2CON ; Turn CCP module off
MOVLW NEW_CAPT_PS ; Load WREG with the
; new prescaler mode
; value and CCP ON
MOVWF CCP2CON ; Load CCP2CON with
; this value
```

#### FIGURE 14-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



#### 14.3 Compare Mode

In Compare mode, the 16-bit CCPRx register value is constantly compared against either the TMR1 or TMR3 register pair value. When a match occurs, the CCPx pin can be:

- · driven high
- · driven low
- toggled (high-to-low or low-to-high)
- remain unchanged (that is, reflects the state of the I/O latch)

The action on the pin is based on the value of the mode select bits (CCPxM3:CCPxM0). At the same time, the interrupt flag bit CCPxIF is set.

#### 14.3.1 CCP PIN CONFIGURATION

The user must configure the CCPx pin as an output by clearing the appropriate TRIS bit.

Note:

Clearing the CCP2CON register will force the RB3 or RC1 compare output latch (depending on device configuration) to the default low level. This is not the PORTB or PORTC I/O data latch.

#### 14.3.2 TIMER1/TIMER3 MODE SELECTION

Timer1 and/or Timer3 must be running in Timer mode or Synchronized Counter mode if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

#### 14.3.3 SOFTWARE INTERRUPT MODE

When the Generate Software Interrupt mode is chosen (CCPxM3:CCPxM0 = 1010), the corresponding CCPx pin is not affected. Only a CCP interrupt is generated, if enabled and the CCPxIE bit is set.

#### 14.3.4 SPECIAL EVENT TRIGGER

Both CCP modules are equipped with a special event trigger. This is an internal hardware signal generated in Compare mode to trigger actions by other modules. The special event trigger is enabled by selecting the Compare Special Event Trigger mode (CCPxM3:CCPxM0 = 1011).

For either CCP module, the special event trigger resets the timer register pair for whichever timer resource is currently assigned as the module's time base. This allows the CCPRx registers to serve as a programmable period register for either timer.

The special event trigger for CCP2 can also start an A/D conversion. In order to do this, the A/D converter must already be enabled.

FIGURE 14-2: COMPARE MODE OPERATION BLOCK DIAGRAM




TABLE 14-3: REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, TIMER1 AND TIMER3

| Name    | Bit 7                                 | Bit 6   | Bit 5      | Bit 4     | Bit 3   | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |
|---------|---------------------------------------|---|------------|-----------|---------|--------|--------|--------|----------------------------|
| INTCON  | GIE/GIEH                              | PEIE/GIEL   | TMR0IE     | INT0IE    | RBIE    | TMR0IF | INT0IF | RBIF   | 49                         |
| RCON    | IPEN                                  | SBOREN <sup>(2)</sup>   | _          | RI        | TO      | PD     | POR    | BOR    | 48                         |
| PIR1    | PSPIF <sup>(1)</sup>                  | ADIF  | RCIF       | TXIF      | SSPIF   | CCP1IF | TMR2IF | TMR1IF | 52                         |
| PIE1    | PSPIE <sup>(1)</sup>                  | ADIE  | RCIE       | TXIE      | SSPIE   | CCP1IE | TMR2IE | TMR1IE | 52                         |
| IPR1    | PSPIP <sup>(1)</sup>                  | ADIP  | RCIP       | TXIP      | SSPIP   | CCP1IP | TMR2IP | TMR1IP | 52                         |
| PIR2    | OSCFIF                                | CMIF  | _          | _         | BCLIF   | HLVDIF | TMR3IF | CCP2IF | 52                         |
| PIE2    | OSCFIE                                | CMIE  | _          | _         | BCLIE   | HLVDIE | TMR3IE | CCP2IE | 52                         |
| IPR2    | OSCFIP                                | CMIP  | _          | _         | BCLIP   | HLVDIP | TMR3IP | CCP2IP | 52                         |
| TRISB   | PORTB Data Direction Control Register |   |            |           |         |        |        |        | 52                         |
| TRISC   | PORTC Da                              | PORTC Data Direction Control Register   |            |           |         |        |        |        |                            |
| TMR1L   | Timer1 Reg                            | gister Low By   | rte        |           |         |        |        |        | 50                         |
| TMR1H   | Timer1 Reg                            | gister High By  | yte        |           |         |        |        |        | 50                         |
| T1CON   | RD16                                  | T1RUN   | T1CKPS1    | T1CKPS0   | T10SCEN | T1SYNC | TMR1CS | TMR10N | 50                         |
| TMR3H   | Timer3 Reg                            | gister High By  | yte        |           |         |        |        |        | 51                         |
| TMR3L   | Timer3 Reg                            | gister Low By   | rte        |           |         |        |        |        | 51                         |
| T3CON   | RD16                                  | T3CCP2  | T3CKPS1    | T3CKPS0   | T3CCP1  | T3SYNC | TMR3CS | TMR3ON | 51                         |
| CCPR1L  | Capture/Co                            | ompare/PWM  | Register 1 | Low Byte  |         |        |        |        | 51                         |
| CCPR1H  | Capture/Co                            | ompare/PWM  | Register 1 | High Byte |         |        |        |        | 51                         |
| CCP1CON | P1M1 <sup>(1)</sup>                   | P1M1 <sup>(1)</sup> P1M0 <sup>(1)</sup> DC1B1 DC1B0 CCP1M3 CCP1M2 CCP1M1 CCP1M0 |            |           |         |        |        |        | 51                         |
| CCPR2L  | Capture/Co                            | ompare/PWM  | Register 2 | Low Byte  |         |        |        |        | 51                         |
| CCPR2H  | Capture/Co                            | ompare/PWM  | Register 2 | High Byte |         |        |        |        | 51                         |
| CCP2CON | _                                     | _   | DC2B1      | DC2B0     | CCP2M3  | CCP2M2 | CCP2M1 | CCP2M0 | 51                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by Capture/Compare, Timer1 or Timer3.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 133

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

<sup>2:</sup> The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See **Section 4.4** "**Brown-out Reset (BOR)**".

#### 14.4 **PWM Mode**


In Pulse-Width Modulation (PWM) mode, the CCPx pin produces up to a 10-bit resolution PWM output. Since the CCP2 pin is multiplexed with a PORTB or PORTC data latch, the appropriate TRIS bit must be cleared to make the CCP2 pin an output.

Note: Clearing the CCP2CON register will force the RB3 or RC1 output latch (depending on device configuration) to the default low level. This is not the PORTB or PORTC I/O data latch.

Figure 14-3 shows a simplified block diagram of the CCP module in PWM mode.


For a step-by-step procedure on how to set up the CCP module for PWM operation, see Section 14.4.4 "Setup for PWM Operation".

#### SIMPLIFIED PWM BLOCK **FIGURE 14-3:** DIAGRAM



A PWM output (Figure 14-4) has a time base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (1/period).

#### **FIGURE 14-4: PWM OUTPUT**



#### 14.4.1 **PWM PERIOD**

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula:

#### **EQUATION 14-1:**

PWM frequency is defined as 1/[PWM period].

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- · TMR2 is cleared
- The CCPx pin is set (exception: if PWM duty cycle = 0%, the CCPx pin will not be set)
- The PWM duty cycle is latched from CCPRxL into **CCPRxH**

Note: The Timer2 postscalers (see Section 12.0 "Timer2 Module") are not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### 14.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPRxL register and to the CCPxCON<5:4> bits. Up to 10-bit resolution is available. The CCPRxL contains the eight MSbs and the CCPxCON<5:4> contains the two LSbs. This 10-bit value is represented by CCPRxL:CCPxCON<5:4>. The following equation is used to calculate the PWM duty cycle in time:

#### **EQUATION 14-2:**

PWM Duty Cycle = (CCPRxL:CCPxCON<5:4>) • Tosc • (TMR2 Prescale Value)

CCPRxL and CCPxCON<5:4> can be written to at any time but the duty cycle value is not latched into CCPR2H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPRxH is a read-only register.

The CCPRxH register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation.

When the CCPRxH and 2-bit latch match TMR2, concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCPx pin is cleared.

The maximum PWM resolution (bits) for a given PWM frequency is given by the equation:

#### **EQUATION 14-3:**

PWM Resolution (max) = 
$$\frac{\log(\frac{FOSC}{FPWM})}{\log(2)}$$
 bits

**Note:** If the PWM duty cycle value is longer than the PWM period, the CCP2 pin will not be cleared.

TABLE 14-4: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

| PWM Frequency              | 2.44 kHz | 9.77 kHz | 39.06 kHz | 156.25 kHz | 312.50 kHz | 416.67 kHz |
|----------------------------|----------|----------|-----------|------------|------------|------------|
| Timer Prescaler (1, 4, 16) | 16       | 4        | 1         | 1          | 1          | 1          |
| PR2 Value                  | FFh      | FFh      | FFh       | 3Fh        | 1Fh        | 17h        |
| Maximum Resolution (bits)  | 10       | 10       | 10        | 8          | 7          | 6.58       |

## 14.4.3 PWM AUTO-SHUTDOWN (CCP1 ONLY)

The PWM auto-shutdown features of the Enhanced CCP module are also available to CCP1 in 28-pin devices. The operation of this feature is discussed in detail in Section 15.4.7 "Enhanced PWM Auto-Shutdown".

Auto-shutdown features are not available for CCP2.

#### 14.4.4 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- Set the PWM period by writing to the PR2 register.
- Set the PWM duty cycle by writing to the CCPRxL register and CCPxCON<5:4> bits.
- Make the CCPx pin an output by clearing the appropriate TRIS bit.
- 4. Set the TMR2 prescale value, then enable Timer2 by writing to T2CON.
- 5. Configure the CCPx module for PWM operation.

TABLE 14-5: REGISTERS ASSOCIATED WITH PWM AND TIMER2

| Name    | Bit 7                                    | Bit 6   | Bit 5               | Bit 4               | Bit 3               | Bit 2               | Bit 1                 | Bit 0                 | Reset<br>Values<br>on page |
|---------|--|---|---------------------|---------------------|---------------------|---------------------|-----------------------|-----------------------|----------------------------|
| INTCON  | GIE/GIEH                                 | PEIE/GIEL   | TMR0IE              | INT0IE              | RBIE                | TMR0IF              | INT0IF                | RBIF                  | 49                         |
| RCON    | IPEN                                     | SBOREN <sup>(2)</sup>   | _                   | RI                  | TO                  | PD                  | POR                   | BOR                   | 48                         |
| PIR1    | PSPIF <sup>(1)</sup>                     | ADIF  | RCIF                | TXIF                | SSPIF               | CCP1IF              | TMR2IF                | TMR1IF                | 52                         |
| PIE1    | PSPIE <sup>(1)</sup>                     | ADIE  | RCIE                | TXIE                | SSPIE               | CCP1IE              | TMR2IE                | TMR1IE                | 52                         |
| IPR1    | PSPIP <sup>(1)</sup>                     | ADIP  | RCIP                | TXIP                | SSPIP               | CCP1IP              | TMR2IP                | TMR1IP                | 52                         |
| TRISB   | PORTB Da                                 | nta Direction   | Control Regi        | ster                |                     |                     |                       |                       | 52                         |
| TRISC   | PORTC Da                                 | PORTC Data Direction Control Register   |                     |                     |                     |                     |                       |                       | 52                         |
| TMR2    | Timer2 Register                          |   |                     |                     |                     |                     |                       | 50                    |                            |
| PR2     | Timer2 Period Register                   |   |                     |                     |                     |                     |                       | 50                    |                            |
| T2CON   | _  | T2OUTPS3  | T2OUTPS2            | T2OUTPS1            | T2OUTPS0            | TMR2ON              | T2CKPS1               | T2CKPS0               | 50                         |
| CCPR1L  | Capture/Co                               | Fimer2 Period Register  — T2OUTPS3 T2OUTPS2 T2OUTPS1 T2OUTPS0 TMR2ON T2CKPS1 T2CKPS0  Capture/Compare/PWM Register 1 Low Byte |                     |                     |                     |                     | 51                    |                       |                            |
| CCPR1H  | Capture/Compare/PWM Register 1 High Byte |   |                     |                     |                     |                     | 51                    |                       |                            |
| CCP1CON | P1M1 <sup>(1)</sup>                      | P1M0 <sup>(1)</sup>   | DC1B1               | DC1B0               | CCP1M3              | CCP1M2              | CCP1M1                | CCP1M0                | 51                         |
| CCPR2L  | Capture/Compare/PWM Register 2 Low Byte  |   |                     |                     |                     |                     | 51                    |                       |                            |
| CCPR2H  | Capture/Compare/PWM Register 2 High Byte |   |                     |                     |                     |                     | 51                    |                       |                            |
| CCP2CON | _  |   | DC2B1               | DC2B0               | CCP2M3              | CCP2M2              | CCP2M1                | CCP2M0                | 51                         |
| ECCP1AS | ECCPASE                                  | ECCPAS2   | ECCPAS1             | ECCPAS0             | PSSAC1              | PSSAC0              | PSSBD1 <sup>(1)</sup> | PSSBD0 <sup>(1)</sup> | 51                         |
| PWM1CON | PRSEN                                    | PDC6 <sup>(1)</sup>   | PDC5 <sup>(1)</sup> | PDC4 <sup>(1)</sup> | PDC3 <sup>(1)</sup> | PDC2 <sup>(1)</sup> | PDC1 <sup>(1)</sup>   | PDC0 <sup>(1)</sup>   | 51                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PWM or Timer2.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

2: The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See **Section 4.4 "Brown-out Reset (BOR)"**.

### 15.0 ENHANCED CAPTURE/ COMPARE/PWM (ECCP) MODULE

**Note:** The ECCP module is implemented only in 40/44-pin devices.

In PIC18F4410/4510/4515/4610 devices, CCP1 is implemented as a standard CCP module with enhanced PWM capabilities. These include the provision for 2 or 4 output channels, user selectable polarity, dead-band control and automatic shutdown

and restart. The Enhanced features are discussed in detail in **Section 15.4 "Enhanced PWM Mode"**. Capture, Compare and single-output PWM functions of the ECCP module are the same as described for the standard CCP module.

The control register for the Enhanced CCP module is shown in Register 15-1. It differs from the CCPxCON registers in PIC18F2410/2510/2515/2610 devices in that the two Most Significant bits are implemented to control PWM functionality.

### REGISTER 15-1: CCP1CON REGISTER (ECCP1 MODULE, 40/44-PIN DEVICES)

| R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0  | R/W-0  | R/W-0  | R/W-0  |
|-------|-------|-------|-------|--------|--------|--------|--------|
| P1M1  | P1M0  | DC1B1 | DC1B0 | CCP1M3 | CCP1M2 | CCP1M1 | CCP1M0 |
| bit 7 |       |       |       |        |        |        | bit 0  |

#### bit 7-6 P1M1:P1M0: Enhanced PWM Output Configuration bits

#### If CCP1M3:CCP1M2 = 00, 01, 10:

xx = P1A assigned as Capture/Compare input/output; P1B, P1C, P1D assigned as port pins If CCP1M3:CCP1M2 = 11:

- 00 = Single output: P1A modulated; P1B, P1C, P1D assigned as port pins
- 01 = Full-bridge output forward: P1D modulated; P1A active; P1B, P1C inactive
- 10 = Half-bridge output: P1A, P1B modulated with dead-band control; P1C, P1D assigned as port pins
- 11 = Full-bridge output reverse: P1B modulated; P1C active; P1A, P1D inactive

#### bit 5-4 DC1B1:DC1B0: PWM Duty Cycle bit 1 and bit 0

#### Capture mode:

Unused.

#### Compare mode:

Unused.

#### PWM mode:

These bits are the two LSbs of the 10-bit PWM duty cycle. The eight MSbs of the duty cycle are found in CCPR1L.

#### bit 3-0 CCP1M3:CCP1M0: Enhanced CCP Mode Select bits

- 0000 = Capture/Compare/PWM off (resets ECCP module)
- 0001 = Reserved
- 0010 = Compare mode, toggle output on match
- 0011 = Capture mode
- 0100 = Capture mode, every falling edge
- 0101 = Capture mode, every rising edge
- 0110 = Capture mode, every 4th rising edge
- 0111 = Capture mode, every 16th rising edge
- 1000 = Compare mode, initialize CCP1 pin low, set output on compare match (set CCP1IF)
- 1001 = Compare mode, initialize CCP1 pin high, clear output on compare match (set CCP1IF)
- 1010 = Compare mode, generate software interrupt only, CCP1 pin reverts to I/O state
- 1011 = Compare mode, trigger special event (ECCP resets TMR1 or TMR3, sets CC1IF bit)
- 1100 = PWM mode; P1A, P1C active-high; P1B, P1D active-high
- 1101 = PWM mode; P1A, P1C active-high; P1B, P1D active-low
- 1110 = PWM mode: P1A. P1C active-low: P1B. P1D active-high
- 1111 = PWM mode; P1A, P1C active-low; P1B, P1D active-low

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

In addition to the expanded range of modes available through the CCP1CON and ECCP1AS registers, the ECCP module has an additional register associated with Enhanced PWM operation and auto-shutdown features. This register is:

• PWM1CON (PWM Configuration register)

#### 15.1 ECCP Outputs and Configuration

The Enhanced CCP module may have up to four PWM outputs, depending on the selected operating mode. These outputs, designated P1A through P1D, are multiplexed with I/O pins on PORTC and PORTD. The outputs that are active depend on the CCP operating mode selected. The pin assignments are summarized in Table 15-1.

To configure the I/O pins as PWM outputs, the proper PWM mode must be selected by setting the P1M1:P1M0 and CCP1M3:CCP1M0 bits. The appropriate TRISC and TRISD direction bits for the port pins must also be set as outputs.

### 15.1.1 ECCP MODULES AND TIMER RESOURCES

Like the standard CCP modules, the ECCP module can utilize Timers 1, 2 or 3, depending on the mode selected. Timer1 and Timer3 are available for modules in Capture or Compare modes, while Timer2 is available for modules in PWM mode. Interactions between the standard and Enhanced CCP modules are identical to those described for standard CCP modules. Additional details on timer resources are provided in Section 14.1.1 "CCP Modules and Timer Resources".

### 15.2 Capture and Compare Modes

Except for the operation of the special event trigger discussed below, the Capture and Compare modes of the ECCP module are identical in operation to that of CCP2. These are discussed in detail in **Section 14.2** "Capture Mode" and Section 14.3 "Compare Mode". No changes are required when moving between 28-pin and 40/44-pin devices.

#### 15.2.1 SPECIAL EVENT TRIGGER

The special event trigger output of ECCP1 resets the TMR1 or TMR3 register pair, depending on which timer resource is currently selected. This allows the CCPR1 register to effectively be a 16-bit programmable period register for Timer1 or Timer3.

#### 15.3 Standard PWM Mode

When configured in Single Output mode, the ECCP module functions identically to the standard CCP module in PWM mode, as described in **Section 14.4** "**PWM Mode**". This is also sometimes referred to as "Compatible CCP" mode, as in Table 15-1.

Note: When setting up single output PWM operations, users are free to use either of the processes described in Section 14.4.4 "Setup for PWM Operation" or Section 15.4.9 "Setup for PWM Operation". The latter is more generic and will work for either single or multi-output PWM.

TABLE 15-1: PIN ASSIGNMENTS FOR VARIOUS ECCP1 MODES

| ECCP Mode              | CCP1CON<br>Configuration | RC2  | RD5      | RD6      | RD7      |  |  |
|------------------------|--------------------------|------|----------|----------|----------|--|--|
| All 40/44-pin devices: |                          |      |          |          |          |  |  |
| Compatible CCP         | 00xx 11xx                | CCP1 | RD5/PSP5 | RD6/PSP6 | RD7/PSP7 |  |  |
| Dual PWM               | 10xx 11xx                | P1A  | P1B      | RD6/PSP6 | RD7/PSP7 |  |  |
| Quad PWM               | x1xx 11xx                | P1A  | P1B      | P1C      | P1D      |  |  |

**Legend:** x = Don't care. Shaded cells indicate pin assignments not used by ECCP1 in a given mode.

#### 15.4 Enhanced PWM Mode

The Enhanced PWM mode provides additional PWM output options for a broader range of control applications. The module is a backward compatible version of the standard CCP module and offers up to four outputs, designated P1A through P1D. Users are also able to select the polarity of the signal (either active-high or active-low). The module's output mode and polarity are configured by setting the P1M1:P1M0 and CCP1M3:CCP1M0 bits of the CCP1CON register.

Figure 15-1 shows a simplified block diagram of PWM operation. All control registers are double-buffered and are loaded at the beginning of a new PWM cycle (the period boundary when Timer2 resets) in order to prevent glitches on any of the outputs. The exception is the PWM Delay register, PWM1CON, which is loaded at either the duty cycle boundary or the period boundary (whichever comes first). Because of the buffering, the module waits until the assigned timer resets instead of starting immediately. This means that Enhanced PWM waveforms do not exactly match the standard PWM waveforms, but are instead offset by one full instruction cycle (4 Tosc).

As before, the user must manually configure the appropriate TRIS bits for output.

#### 15.4.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following equation.

#### **EQUATION 15-1:**

PWM frequency is defined as 1/[PWM period]. When TMR2 is equal to PR2, the following three events occur on the next increment cycle:


· TMR2 is cleared

Note:

- The CCP1 pin is set (if PWM duty cycle = 0%, the CCP1 pin will not be set)
- The PWM duty cycle is copied from CCPR1L into CCPR1H

The Timer2 postscaler (see Section 12.0 "Timer2 Module") is not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### FIGURE 15-1: SIMPLIFIED BLOCK DIAGRAM OF THE ENHANCED PWM MODULE



© 2004 Microchip Technology Inc. Preliminary DS39636A-page 139

#### 15.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available. The CCPR1L contains the eight MSbs and the CCP1CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPR1L:CCP1CON<5:4>. The PWM duty cycle is calculated by the following equation.

#### **EQUATION 15-2:**

CCPR1L and CCP1CON<5:4> can be written to at any time, but the duty cycle value is not copied into CCPR1H until a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read-only register.

The CCPR1H register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation. When the CCPR1H and 2-bit latch match TMR2, concatenated with an internal 2-bit Q clock or two bits of the TMR2 prescaler, the CCP1 pin is cleared. The maximum PWM resolution (bits) for a given PWM frequency is given by the following equation.

#### **EQUATION 15-3:**

PWM Resolution (max) = 
$$\frac{\log\left(\frac{FOSC}{FPWM}\right)}{\log(2)}$$
 bits

**Note:** If the PWM duty cycle value is longer than the PWM period, the CCP1 pin will not be cleared.

#### 15.4.3 PWM OUTPUT CONFIGURATIONS

The P1M1:P1M0 bits in the CCP1CON register allow one of four configurations:

- Single Output
- · Half-Bridge Output
- Full-Bridge Output, Forward mode
- Full-Bridge Output, Reverse mode

The Single Output mode is the standard PWM mode discussed in **Section 15.4** "Enhanced PWM Mode". The Half-Bridge and Full-Bridge Output modes are covered in detail in the sections that follow.

The general relationship of the outputs in all configurations is summarized in Figure 15-2.


TABLE 15-2: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

| PWM Frequency              | 2.44 kHz | 9.77 kHz | 39.06 kHz | 156.25 kHz | 312.50 kHz | 416.67 kHz |
|----------------------------|----------|----------|-----------|------------|------------|------------|
| Timer Prescaler (1, 4, 16) | 16       | 4        | 1         | 1          | 1          | 1          |
| PR2 Value                  | FFh      | FFh      | FFh       | 3Fh        | 1Fh        | 17h        |
| Maximum Resolution (bits)  | 10       | 10       | 10        | 8          | 7          | 6.58       |

PR2 + 1 Duty **SIGNAL CCP1CON** Cycle <7:6> Period P1A Modulated (Single Output) 00 Delay(1) Delay<sup>(1)</sup> P1A Modulated (Half-Bridge) 10 P1B Modulated P1A Active P1B Inactive (Full-Bridge, 01 Forward) P1C Inactive P1D Modulated P1A Inactive P1B Modulated (Full-Bridge, 11 Reverse) P1C Active P1D Inactive

**PWM OUTPUT RELATIONSHIPS (ACTIVE-HIGH STATE) FIGURE 15-2:** 

**FIGURE 15-3:** PWM OUTPUT RELATIONSHIPS (ACTIVE-LOW STATE)



- Period = 4 \* Tosc \* (PR2 + 1) \* (TMR2 Prescale Value)
- Duty Cycle = Tosc \* (CCPR1L<7:0>:CCP1CON<5:4>) \* (TMR2 Prescale Value)
- Delay = 4 \* Tosc \* (ECCPDEL<6:0>)

Note 1: Dead-band delay is programmed using the PWM1CON register (Section 15.4.6 "Programmable Dead-Band Delay").


#### 15.4.4 HALF-BRIDGE MODE

In the Half-Bridge Output mode, two pins are used as outputs to drive push-pull loads. The PWM output signal is output on the P1A pin, while the complementary PWM output signal is output on the P1B pin (Figure 15-4). This mode can be used for half-bridge applications, as shown in Figure 15-5, or for full-bridge applications where four power switches are being modulated with two PWM signals.

In Half-Bridge Output mode, the programmable deadband delay can be used to prevent shoot-through current in half-bridge power devices. The value of bits PDC6:PDC0 sets the number of instruction cycles before the output is driven active. If the value is greater than the duty cycle, the corresponding output remains inactive during the entire cycle. See **Section 15.4.6** "**Programmable Dead-Band Delay**" for more details of the dead-band delay operations.


Since the P1A and P1B outputs are multiplexed with the PORTC<2> and PORTD<5> data latches, the TRISC<2> and TRISD<5> bits must be cleared to configure P1A and P1B as outputs.

FIGURE 15-4: HALF-BRIDGE PWM OUTPUT



- **Note 1:** At this time, the TMR2 register is equal to the PR2 register.
  - 2: Output signals are shown as active-high.

FIGURE 15-5: EXAMPLES OF HALF-BRIDGE OUTPUT MODE APPLICATIONS




#### **FULL-BRIDGE MODE** 15.4.5

In Full-Bridge Output mode, four pins are used as outputs; however, only two outputs are active at a time. In the Forward mode, pin P1A is continuously active and pin P1D is modulated. In the Reverse mode, pin P1C is continuously active and pin P1B is modulated. These are illustrated in Figure 15-6.

P1A, P1B, P1C and P1D outputs are multiplexed with the PORTC<2> and PORTD<7:5> data latches. The TRISC<2> and TRISD<7:5> bits must be cleared to make the P1A, P1B, P1C and P1D pins outputs.

**FIGURE 15-6: FULL-BRIDGE PWM OUTPUT** 






FIGURE 15-7: EXAMPLE OF FULL-BRIDGE APPLICATION

### 15.4.5.1 Direction Change in Full-Bridge Mode

In the Full-Bridge Output mode, the P1M1 bit in the CCP1CON register allows user to control the forward/reverse direction. When the application firmware changes this direction control bit, the module will assume the new direction on the next PWM cycle.

Just before the end of the current PWM period, the modulated outputs (P1B and P1D) are placed in their inactive state, while the unmodulated outputs (P1A and P1C) are switched to drive in the opposite direction. This occurs in a time interval of 4 Tosc \* (Timer2 Prescale Value) before the next PWM period begins. The Timer2 prescaler will be either 1, 4 or 16, depending on the value of the T2CKPS bit (T2CON<1:0>). During the interval from the switch of the unmodulated outputs to the beginning of the next period, the modulated outputs (P1B and P1D) remain inactive. This relationship is shown in Figure 15-8.

Note that in the Full-Bridge Output mode, the CCP1 module does not provide any dead-band delay. In general, since only one output is modulated at all times, dead-band delay is not required. However, there is a situation where a dead-band delay might be required. This situation occurs when both of the following conditions are true:

- The direction of the PWM output changes when the duty cycle of the output is at or near 100%.
- The turn-off time of the power switch, including the power device and driver circuit, is greater than the turn-on time.


Figure 15-9 shows an example where the PWM direction changes from forward to reverse at a near 100% duty cycle. At time t1, the outputs P1A and P1D become inactive, while output P1C becomes active. In this example, since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current may flow through power devices, QC and QD (see Figure 15-7), for the duration of 't'. The same phenomenon will occur to power devices, QA and QB, for PWM direction change from reverse to forward.

If changing PWM direction at high duty cycle is required for an application, one of the following requirements must be met:

- 1. Reduce PWM for a PWM period before changing directions.
- Use switch drivers that can drive the switches off faster than they can drive them on.

Other options to prevent shoot-through current may exist.


**FIGURE 15-8: PWM DIRECTION CHANGE** 



Note 1: The direction bit in the CCP1 Control register (CCP1CON<7>) is written any time during the PWM cycle.

2: When changing directions, the P1A and P1C signals switch before the end of the current PWM cycle at intervals of 4 Tosc, 16 Tosc or 64 Tosc, depending on the Timer2 prescaler value. The modulated P1B and P1D signals are inactive at this time.

**FIGURE 15-9: PWM DIRECTION CHANGE AT NEAR 100% DUTY CYCLE** 



3: t<sub>OFF</sub> is the turn-off delay of power switch QD and its driver.

**Preliminary** © 2004 Microchip Technology Inc. DS39636A-page 145

# 15.4.6 PROGRAMMABLE DEAD-BAND DELAY

**Note:** Programmable dead-band delay is not implemented in 28-pin devices with standard CCP modules.

In half-bridge applications where all power switches are modulated at the PWM frequency at all times, the power switches normally require more time to turn off than to turn on. If both the upper and lower power switches are switched at the same time (one turned on and the other turned off), both switches may be on for a short period of time until one switch completely turns off. During this brief interval, a very high current (shoot-through current) may flow through both power switches, shorting the bridge supply. To avoid this potentially destructive shoot-through current from flowing during switching, turning on either of the power switches is normally delayed to allow the other switch to completely turn off.

In the Half-Bridge Output mode, a digitally programmable dead-band delay is available to avoid shoot-through current from destroying the bridge power switches. The delay occurs at the signal transition from the non-active state to the active state. See Figure 15-4 for illustration. Bits PDC6:PDC0 of the PWM1CON register (Register 15-2) set the delay period in terms of microcontroller instruction cycles (TCY or 4 TOSC). These bits are not available on 28-pin devices as the standard CCP module does not support half-bridge operation.

#### 15.4.7 ENHANCED PWM AUTO-SHUTDOWN

When the CCP1 is programmed for any of the Enhanced PWM modes, the active output pins may be configured for auto-shutdown. Auto-shutdown immediately places the Enhanced PWM output pins into a defined shutdown state when a shutdown event occurs.

A shutdown event can be caused by either of the comparator modules, a low level on the Fault input pin (FLT0) or any combination of these three sources. The comparators may be used to monitor a voltage input proportional to a current being monitored in the bridge circuit. If the voltage exceeds a threshold, the comparator switches state and triggers a shutdown. Alternatively, a low digital signal on FLT0 can also trigger a shutdown. The auto-shutdown feature can be disabled by not selecting any auto-shutdown sources. The auto-shutdown sources to be used are selected using the ECCPAS2:ECCPAS0 bits (bits<6:4> of the ECCP1AS register).

When a shutdown occurs, the output pins are asynchronously placed in their shutdown states, specified by the PSSAC1:PSSAC0 and PSSBD1:PSSBD0 bits (ECCPAS3:ECCPAS0). Each pin pair (P1A/P1C and P1B/P1D) may be set to drive high, drive low or be tri-stated (not driving). The ECCPASE bit (ECCPAS<7>) is also set to hold the Enhanced PWM outputs in their shutdown states.

The ECCPASE bit is set by hardware when a shutdown event occurs. If automatic restarts are not enabled, the ECCPASE bit is cleared by firmware when the cause of the shutdown clears. If automatic restarts are enabled, the ECCPASE bit is automatically cleared when the cause of the auto-shutdown has cleared.

If the ECCPASE bit is set when a PWM period begins, the PWM outputs remain in their shutdown state for that entire PWM period. When the ECCPASE bit is cleared, the PWM outputs will return to normal operation at the beginning of the next PWM period.

**Note:** Writing to the ECCPASE bit is disabled while a shutdown condition is active.

## REGISTER 15-2: PWM1CON: PWM CONFIGURATION REGISTER

| R/W-0 | R/W-0               | R/W-0               | R/W-0               | R/W-0               | R/W-0               | R/W-0               | R/W-0               |
|-------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|
| PRSEN | PDC6 <sup>(1)</sup> | PDC5 <sup>(1)</sup> | PDC4 <sup>(1)</sup> | PDC3 <sup>(1)</sup> | PDC2 <sup>(1)</sup> | PDC1 <sup>(1)</sup> | PDC0 <sup>(1)</sup> |
| bit 7 |                     |                     |                     |                     |                     |                     | bit 0               |

bit 7 PRSEN: PWM Restart Enable bit

1 = Upon auto-shutdown, the ECCPASE bit clears automatically once the shutdown event goes away; the PWM restarts automatically

0 = Upon auto-shutdown, ECCPASE must be cleared in software to restart the PWM

bit 6-0 PDC6:PDC0: PWM Delay Count bits<sup>(1)</sup>

Delay time, in number of Fosc/4 (4 \* Tosc) cycles, between the scheduled and actual time for a PWM signal to transition to active.

Note 1: Unimplemented on 28-pin devices and read as '0'.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

# REGISTER 15-3: ECCP1AS: ENHANCED CAPTURE/COMPARE/PWM AUTO-SHUTDOWN CONTROL REGISTER

| R/W-0   | R/W-0   | R/W-0   | R/W-0   | R/W-0  | R/W-0  | R/W-0                 | R/W-0                 |
|---------|---------|---------|---------|--------|--------|-----------------------|-----------------------|
| ECCPASE | ECCPAS2 | ECCPAS1 | ECCPAS0 | PSSAC1 | PSSAC0 | PSSBD1 <sup>(1)</sup> | PSSBD0 <sup>(1)</sup> |
| bit 7   |         |         |         |        |        |                       | bit 0                 |

bit 7 ECCPASE: ECCP Auto-Shutdown Event Status bit

1 = A shutdown event has occurred; ECCP outputs are in shutdown state

0 = ECCP outputs are operating

bit 6-4 ECCPAS2:ECCPAS0: ECCP Auto-Shutdown Source Select bits

111 = FLT0 or Comparator 1 or Comparator 2

110 = FLT0 or Comparator 2

101 = FLT0 or Comparator 1

100 = FLT0

011 = Either Comparator 1 or 2010 = Comparator 2 output

001 = Comparator 1 output

000 = Auto-shutdown is disabled

bit 3-2 PSSAC1:PSSAC0: Pins A and C Shutdown State Control bits

1x = Pins A and C are tri-state (40/44-pin devices);

PWM output is tri-state (28-pin devices)

01 = Drive Pins A and C to '1'

00 = Drive Pins A and C to '0'

bit 1-0 **PSSBD1:PSSBD0:** Pins B and D Shutdown State Control bits<sup>(1)</sup>

1x = Pins B and D tri-state

01 = Drive Pins B and D to '1'

00 = Drive Pins B and D to '0'

Note 1: Unimplemented on 28-pin devices and read as '0'.

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 15.4.7.1 Auto-Shutdown and Automatic Restart

The auto-shutdown feature can be configured to allow automatic restarts of the module following a shutdown event. This is enabled by setting the PRSEN bit of the PWM1CON register (PWM1CON<7>).

In Shutdown mode with PRSEN = 1 (Figure 15-10), the ECCPASE bit will remain set for as long as the cause of the shutdown continues. When the shutdown condition clears, the ECCP1ASE bit is cleared. If PRSEN = 0 (Figure 15-11), once a shutdown condition occurs, the ECCPASE bit will remain set until it is cleared by firmware. Once ECCPASE is cleared, the Enhanced PWM will resume at the beginning of the next PWM period.

**Note:** Writing to the ECCPASE bit is disabled while a shutdown condition is active.

Independent of the PRSEN bit setting, if the autoshutdown source is one of the comparators, the shutdown condition is a level. The ECCPASE bit cannot be cleared as long as the cause of the shutdown persists.

The Auto-Shutdown mode can be forced by writing a '1' to the ECCPASE bit.

#### 15.4.8 START-UP CONSIDERATIONS

When the ECCP module is used in the PWM mode, the application hardware must use the proper external pull-up and/or pull-down resistors on the PWM output pins. When the microcontroller is released from Reset, all of the I/O pins are in the high-impedance state. The external circuits must keep the power switch devices in the off state until the microcontroller drives the I/O pins with the proper signal levels, or activates the PWM output(s).

The CCP1M1:CCP1M0 bits (CCP1CON<1:0>) allow the user to choose whether the PWM output signals are active-high or active-low for each pair of PWM output pins (P1A/P1C and P1B/P1D). The PWM output polarities must be selected before the PWM pins are configured as outputs. Changing the polarity configuration while the PWM pins are configured as outputs is not recommended, since it may result in damage to the application circuits.

The P1A, P1B, P1C and P1D output latches may not be in the proper states when the PWM module is initialized. Enabling the PWM pins for output at the same time as the ECCP module may cause damage to the application circuit. The ECCP module must be enabled in the proper output mode and complete a full PWM cycle before configuring the PWM pins as outputs. The completion of a full PWM cycle is indicated by the TMR2IF bit being set as the second PWM period begins.







FIGURE 15-11: PWM AUTO-SHUTDOWN (PRSEN = 0, AUTO-RESTART DISABLED)



#### 15.4.9 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the ECCP module for PWM operation:

- Configure the PWM pins, P1A and P1B (and P1C and P1D, if used), as inputs by setting the corresponding TRIS bits.
- 2. Set the PWM period by loading the PR2 register.
- 3. If auto-shutdown is required:
  - Disable auto-shutdown (ECCP1AS = 0)
  - Configure source (FLT0, Comparator 1 or Comparator 2)
  - · Wait for non-shutdown condition
- Configure the ECCP module for the desired PWM mode and configuration by loading the CCP1CON register with the appropriate values:
  - Select one of the available output configurations and direction with the P1M1:P1M0 bits.
  - Select the polarities of the PWM output signals with the CCP1M3:CCP1M0 bits.
- Set the PWM duty cycle by loading the CCPR1L register and CCP1CON<5:4> bits.
- For Half-Bridge Output mode, set the deadband delay by loading ECCPDEL<6:0> with the appropriate value.
- If auto-shutdown operation is required, load the ECCP1AS register:
  - Select the auto-shutdown sources using the ECCPAS2:ECCPAS0 bits.
  - Select the shutdown states of the PWM output pins using the PSSAC1:PSSAC0 and PSSBD1:PSSBD0 bits.
  - Set the ECCPASE bit (ECCPAS<7>).
  - Configure the comparators using the CMCON register.
  - Configure the comparator inputs as analog inputs.
- 8. If auto-restart operation is required, set the PRSEN bit (ECCPDEL<7>).
- 9. Configure and start TMR2:
  - Clear the TMR2 interrupt flag bit by clearing the TMR2IF bit (PIR1<1>).
  - Set the TMR2 prescale value by loading the T2CKPS bits (T2CON<1:0>).
  - Enable Timer2 by setting the TMR2ON bit (T2CON<2>).
- Enable PWM outputs after a new PWM cycle has started:
  - Wait until TMRn overflows (TMRnIF bit is set).
  - Enable the CCP1/P1A, P1B, P1C and/or P1D pin outputs by clearing the respective TRIS bits.
  - Clear the ECCPASE bit (ECCPAS<7>).

# 15.4.10 OPERATION IN POWER MANAGED MODES

In Sleep mode, all clock sources are disabled. Timer2 will not increment and the state of the module will not change. If the ECCP pin is driving a value, it will continue to drive that value. When the device wakes up, it will continue from this state. If Two-Speed Startups are enabled, the initial start-up frequency from INTOSC and the postscaler may not be stable immediately.

In PRI\_IDLE mode, the primary clock will continue to clock the ECCP module without change. In all other power managed modes, the selected power managed mode clock will clock Timer2. Other power managed mode clocks will most likely be different than the primary clock frequency.

# 15.4.10.1 Operation with Fail-Safe Clock Monitor

If the Fail-Safe Clock Monitor is enabled, a clock failure will force the device into the RC\_RUN Power Managed mode and the OSCFIF bit (PIR2<7>) will be set. The ECCP will then be clocked from the internal oscillator clock source, which may have a different clock frequency than the primary clock.

See the previous section for additional details.

### 15.4.11 EFFECTS OF A RESET

Both Power-on Reset and subsequent Resets will force all ports to Input mode and the CCP registers to their Reset states.

This forces the Enhanced CCP module to reset to a state compatible with the standard CCP module.

TABLE 15-3: REGISTERS ASSOCIATED WITH ECCP1 MODULE AND TIMER1 TO TIMER3

| Name    | Bit 7                | Bit 6                                    | Bit 5               | Bit 4               | Bit 3               | Bit 2               | Bit 1                 | Bit 0                 | Reset<br>Values<br>on page |  |  |
|---------|----------------------|--|---------------------|---------------------|---------------------|---------------------|-----------------------|-----------------------|----------------------------|--|--|
| INTCON  | GIE/GIEH             | PEIE/GIEL                                | TMR0IE              | INT0IE              | RBIE                | TMR0IF              | INT0IF                | RBIF                  | 49                         |  |  |
| RCON    | IPEN                 | SBOREN <sup>(2)</sup>                    | _                   | RI                  | TO                  | PD                  | POR                   | BOR                   | 48                         |  |  |
| PIR1    | PSPIF <sup>(1)</sup> | ADIF                                     | RCIF                | TXIF                | SSPIF               | CCP1IF              | TMR2IF                | TMR1IF                | 52                         |  |  |
| PIE1    | PSPIE <sup>(1)</sup> | ADIE                                     | RCIE                | TXIE                | SSPIE               | CCP1IE              | TMR2IE                | TMR1IE                | 52                         |  |  |
| IPR1    | PSPIP <sup>(1)</sup> | ADIP                                     | RCIP                | TXIP                | SSPIP               | CCP1IP              | TMR2IP                | TMR1IP                | 52                         |  |  |
| PIR2    | OSCFIF               | CMIF                                     | _                   | _                   | BCLIF               | HLVDIF              | TMR3IF                | CCP2IF                | 52                         |  |  |
| PIE2    | OSCFIE               | CMIE                                     | _                   | _                   | BCLIE               | HLVDIE              | TMR3IE                | CCP2IE                | 52                         |  |  |
| IPR2    | OSCFIP               | OSCFIP CMIP — BCLIP HLVDIP TMR3IP CCP2IP |                     |                     |                     |                     |                       |                       |                            |  |  |
| TRISB   | PORTB Da             | ORTB Data Direction Control Register     |                     |                     |                     |                     |                       |                       |                            |  |  |
| TRISC   | PORTC Da             | ORTC Data Direction Control Register     |                     |                     |                     |                     |                       |                       |                            |  |  |
| TRISD   | PORTD Da             | PORTD Data Direction Control Register    |                     |                     |                     |                     |                       |                       |                            |  |  |
| TMR1L   | Timer1 Reg           | ister Low Byte                           | е                   |                     |                     |                     |                       |                       | 50                         |  |  |
| TMR1H   | Timer1 Reg           | ister High Byt                           | e                   |                     |                     |                     |                       |                       | 50                         |  |  |
| T1CON   | RD16                 | T1RUN                                    | T1CKPS1             | T1CKPS0             | T10SCEN             | T1SYNC              | TMR1CS                | TMR10N                | 50                         |  |  |
| TMR2    | Timer2 Reg           | jister                                   |                     |                     |                     |                     |                       |                       | 50                         |  |  |
| T2CON   | _                    | T2OUTPS3                                 | T2OUTPS2            | T2OUTPS1            | T2OUTPS0            | TMR2ON              | T2CKPS1               | T2CKPS0               | 50                         |  |  |
| PR2     | Timer2 Peri          | od Register                              |                     |                     |                     |                     |                       |                       | 50                         |  |  |
| TMR3L   | Timer3 Reg           | ister Low Byte                           | е                   |                     |                     |                     |                       |                       | 51                         |  |  |
| TMR3H   | Timer3 Reg           | jister High Byt                          | :e                  |                     |                     |                     |                       |                       | 51                         |  |  |
| T3CON   | RD16                 | T3CCP2                                   | T3CKPS1             | T3CKPS0             | T3CCP1              | T3SYNC              | TMR3CS                | TMR3ON                | 51                         |  |  |
| CCPR1L  | Capture/Co           | mpare/PWM                                | Register 1 Lo       | w Byte              |                     |                     |                       |                       | 51                         |  |  |
| CCPR1H  | Capture/Co           | mpare/PWM                                | Register 1 Hi       | gh Byte             |                     |                     |                       |                       | 51                         |  |  |
| CCP1CON | P1M1                 | P1M0                                     | DC1B1               | DC1B0               | CCP1M3              | CCP1M2              | CCP1M1                | CCP1M0                | 51                         |  |  |
| ECCP1AS | ECCPASE              | ECCPAS2                                  | ECCPAS1             | ECCPAS0             | PSSAC1              | PSSAC0              | PSSBD1 <sup>(1)</sup> | PSSBD0 <sup>(1)</sup> | 51                         |  |  |
| PWM1CON | PRSEN                | PDC6 <sup>(1)</sup>                      | PDC5 <sup>(1)</sup> | PDC4 <sup>(1)</sup> | PDC3 <sup>(1)</sup> | PDC2 <sup>(1)</sup> | PDC1 <sup>(1)</sup>   | PDC0 <sup>(1)</sup>   | 51                         |  |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used during ECCP operation.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

<sup>2:</sup> The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See Section 4.4 "Brown-out Reset (BOR)".

# 16.0 MASTER SYNCHRONOUS SERIAL PORT (MSSP) MODULE

#### 16.1 MSSP Module Overview

The Master Synchronous Serial Port (MSSP) module is a serial interface, useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:

- Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C)
  - Full Master mode
  - Slave mode (with general address call)

The I<sup>2</sup>C interface supports the following modes in hardware:

- Master mode
- · Multi-Master mode
- Slave mode

## 16.2 Control Registers

The MSSP module has three associated registers. These include a status register (SSPSTAT) and two control registers (SSPCON1 and SSPCON2). The use of these registers and their individual configuration bits differ significantly depending on whether the MSSP module is operated in SPI or I<sup>2</sup>C mode.

Additional details are provided under the individual sections.

## 16.3 SPI Mode

The SPI mode allows 8 bits of data to be synchronously transmitted and received simultaneously. All four SPI modes are supported. To accomplish communication, typically three pins are used:


- Serial Data Out (SDO) RC5/SDO
- Serial Data In (SDI) RC4/SDI/SDA
- Serial Clock (SCK) RC3/SCK/SCL

Additionally, a fourth pin may be used when in a Slave mode of operation:

Slave Select (SS) – RA5/SS

Figure 16-1 shows the block diagram of the MSSP module when operating in SPI mode.

FIGURE 16-1: MSSP BLOCK DIAGRAM (SPI™ MODE)



#### 16.3.1 REGISTERS

The MSSP module has four registers for SPI mode operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer Register (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible

SSPCON1 and SSPSTAT are the control and status registers in SPI mode operation. The SSPCON1 register is readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double-buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

### REGISTER 16-1: SSPSTAT: MSSP STATUS REGISTER (SPI MODE)

| R/W-0 | R/W-0 | R-0 | R-0 | R-0 | R-0 | R-0 | R-0   |
|-------|-------|-----|-----|-----|-----|-----|-------|
| SMP   | CKE   | D/A | Р   | S   | R/W | UA  | BF    |
| bit 7 |       |     |     |     |     |     | bit 0 |

bit 7 SMP: Sample bit

SPI Master mode:

- 1 = Input data sampled at end of data output time
- 0 = Input data sampled at middle of data output time

SPI Slave mode:

SMP must be cleared when SPI operation is used in Slave mode.

- bit 6 CKE: SPI Clock Select bit
  - 1 = Transmit occurs on transition from active to Idle clock state
  - 0 = Transmit occurs on transition from Idle to active clock state

**Note:** Polarity of clock state is set by the CKP bit (SSPCON1<4>).

bit 5 **D/A**: Data/Address bit

Used in I<sup>2</sup>C mode only.

bit 4 **P:** Stop bit

Used in I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled; SSPEN is cleared.

bit 3 S: Start bit

Used in I<sup>2</sup>C mode only.

bit 2 R/W: Read/Write bit Information

Used in I<sup>2</sup>C mode only.

bit 1 UA: Update Address bit

Used in I<sup>2</sup>C mode only.

bit 0 **BF:** Buffer Full Status bit (Receive mode only)

1 = Receive complete, SSPBUF is full

0 = Receive not complete, SSPBUF is empty

| e | ~ | _ | n | ~ | • |
|---|---|---|---|---|---|
|   |   |   |   |   |   |

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### REGISTER 16-2: SSPCON1: MSSP CONTROL REGISTER 1 (SPI MODE)

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| WCOL  | SSPOV | SSPEN | CKP   | SSPM3 | SSPM2 | SSPM1 | SSPM0 |

bit 7

- bit 7 WCOL: Write Collision Detect bit (Transmit mode only)
  - 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
  - 0 = No collision
- bit 6 SSPOV: Receive Overflow Indicator bit

#### SPI Slave mode:

- 1 = A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in Slave mode. The user must read the SSPBUF, even if only transmitting data, to avoid setting overflow (must be cleared in software).
- 0 = No overflow

**Note:** In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

- bit 5 SSPEN: Synchronous Serial Port Enable bit
  - 1 = Enables serial port and configures SCK, SDO, SDI and SS as serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

**Note:** When enabled, these pins must be properly configured as input or output.

- bit 4 CKP: Clock Polarity Select bit
  - 1 = Idle state for clock is a high level
  - 0 = Idle state for clock is a low level
- bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits
  - 0101 = SPI Slave mode, clock = SCK pin, SS pin control disabled, SS can be used as I/O pin
  - 0100 = SPI Slave mode, clock = SCK pin, SS pin control enabled
  - 0011 = SPI Master mode, clock = TMR2 output/2
  - 0010 = SPI Master mode, clock = Fosc/64
  - 0001 = SPI Master mode, clock = Fosc/16
  - 0000 = SPI Master mode, clock = Fosc/4

**Note:** Bit combinations not specifically listed here are either reserved or implemented in I<sup>2</sup>C mode only.

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 16.3.2 OPERATION

When initializing SPI operation, several options need to be specified. This is done by programming the appropriate control bits (SSPCON1<5:0> and SSPSTAT<7:6>). These control bits allow the following to be specified:

- · Master mode (SCK is the clock output)
- Slave mode (SCK is the clock input)
- · Clock Polarity (Idle state of SCK)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Master mode only)
- Slave Select mode (Slave mode only)

The MSSP consists of a Transmit/Receive Shift register (SSPSR) and a Buffer register (SSPBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPBUF holds the data that was written to the SSPSR until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPBUF register. Then, the Buffer Full detect bit, BF (SSPSTAT<0>) and the interrupt flag bit, SSPIF, are set. This double-buffering of the received data (SSPBUF) allows the next byte to start reception before

reading the data that was just received. Any write to the SSPBUF register during transmission/reception of data will be ignored and the write collision detect bit, WCOL (SSPCON1<7>), will be set. User software must clear the WCOL bit so that it can be determined if the following write(s) to the SSPBUF register completed successfully.

When the application software is expecting to receive valid data, the SSPBUF should be read before the next byte of data to transfer is written to the SSPBUF. The Buffer Full bit, BF (SSPSTAT<0>), indicates when SSPBUF has been loaded with the received data (transmission is complete). When the SSPBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI interface is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. The SSPBUF must be read and/or written. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur. Example 16-1 shows the loading of the SSPBUF (SSPSR) for data transmission.

The SSPSR is not directly readable or writable and can only be accessed by addressing the SSPBUF register. Additionally, the MSSP status register (SSPSTAT) indicates the various status conditions.

## **EXAMPLE 16-1: LOADING THE SSPBUF (SSPSR) REGISTER**

| LOOP | BTFSS<br>BRA<br>MOVF | SSPSTAT, BF<br>LOOP<br>SSPBUF, W | ;Has data been received (transmit complete)? ;No ;WREG reg = contents of SSPBUF |
|------|----------------------|----------------------------------|---|
|      | MOVWF                | RXDATA                           | ;Save in user RAM, if data is meaningful  |
|      | MOVF<br>MOVWF        | TXDATA, W<br>SSPBUF              | ;W reg = contents of TXDATA ;New data to xmit                                   |

#### 16.3.3 ENABLING SPI I/O

To enable the serial port, SSP Enable bit, SSPEN (SSPCON1<5>), must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, reinitialize the SSPCON registers and then set the SSPEN bit. This configures the SDI, SDO, SCK and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed as follows:

- · SDI is automatically controlled by the SPI module
- · SDO must have TRISC<5> bit cleared
- SCK (Master mode) must have TRISC<3> bit cleared
- SCK (Slave mode) must have TRISC<3> bit set
- SS must have TRISA<5> bit set


Any serial port function that is not desired may be overridden by programming the corresponding Data Direction (TRIS) register to the opposite value.

#### 16.3.4 TYPICAL CONNECTION

Figure 16-2 shows a typical connection between two microcontrollers. The master controller (Processor 1) initiates the data transfer by sending the SCK signal. Data is shifted out of both shift registers on their programmed clock edge and latched on the opposite edge of the clock. Both processors should be programmed to the same Clock Polarity (CKP), then both controllers would send and receive data at the same time. Whether the data is meaningful (or dummy data) depends on the application software. This leads to three scenarios for data transmission:

- Master sends data Slave sends dummy data
- Master sends data Slave sends data
- Master sends dummy data Slave sends data

FIGURE 16-2: SPI™ MASTER/SLAVE CONNECTION



© 2004 Microchip Technology Inc. Preliminary DS39636A-page 155

#### 16.3.5 MASTER MODE

The master can initiate the data transfer at any time because it controls the SCK. The master determines when the slave (Processor 2, Figure 16-2) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPBUF register is written to. If the SPI interface is only going to receive, the SDO output could be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPBUF register as if a normal received byte (interrupts and status bits appropriately set). This could be useful in receiver applications as a "Line Activity Monitor" mode.


The clock polarity is selected by appropriately programming the CKP bit (SSPCON1<4>). This then, would give waveforms for SPI communication as shown in Figure 16-3, Figure 16-5 and Figure 16-6, where the MSB is transmitted first. In Master mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 Tcy)
- Fosc/64 (or 16 Tcy)
- Timer2 output/2

This allows a maximum data rate (at 40 MHz) of 10.00 Mbps.

Figure 16-3 shows the waveforms for Master mode. When the CKE bit is set, the SDO data is valid before there is a clock edge on SCK. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPBUF is loaded with the received data is shown.





#### 16.3.6 SLAVE MODE

In Slave mode, the data is transmitted and received as the external clock pulses appear on SCK. When the last bit is latched, the SSPIF interrupt flag bit is set.

Before enabling the module in SPI Slave mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit (SSPCON1<4>).

While in Slave mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in Sleep mode, the slave can transmit/receive data. When a byte is received, the device will wake-up from Sleep.

# 16.3.7 SLAVE SELECT SYNCHRONIZATION

The SS pin allows a Synchronous Slave mode. The SPI operation must be in Slave mode with  $\overline{SS}$  pin control enabled (SSPCON1<3:0> = 04h). When the  $\overline{SS}$  pin is low, transmission and reception are enabled and

the SDO pin is driven. When the  $\overline{SS}$  pin goes high, the SDO pin is no longer driven, even if in the middle of a transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.

- Note 1: When the SPI operation is in Slave mode with  $\overline{SS}$  pin control enabled (SSPCON<3:0> = 0100), the SPI module will reset if the  $\overline{SS}$  pin is set to VDD.
  - 2: If the SPI operation is used in Slave mode with CKE set, then the SS pin control must be enabled.

When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the SS pin to a high level or clearing the SSPEN bit.

To emulate two-wire communication, the SDO pin can be connected to the SDI pin. When the SPI module needs to operate as a receiver, the SDO pin can be configured as an input. This disables transmissions from the SDO. The SDI can always be left as an input (SDI function) since it cannot create a bus conflict.






FIGURE 16-5: SPI™ MODE WAVEFORM (SLAVE MODE WITH CKE = 0)





FIGURE 16-6: SPI™ MODE WAVEFORM (SLAVE MODE WITH CKE = 1)



# 16.3.8 OPERATION IN POWER MANAGED MODES

In SPI Master mode, module clocks may be operating at a different speed than when in full power mode. In the case of the Sleep mode, all clocks are halted.

In Idle modes, a clock is provided to the peripherals. That clock should be from the primary clock source, the secondary clock (Timer1 oscillator at 32.768 kHz) or the INTOSC source. See **Section 2.7** "Clock Sources and Oscillator Switching" for additional information.

In most cases, the speed that the master clocks SPI data is not important; however, this should be evaluated for each system.

If MSSP interrupts are enabled, they can wake the controller from Sleep mode, or one of the Idle modes, when the master completes sending data. If an exit from Sleep or Idle mode is not desired, MSSP interrupts should be disabled.

If the Sleep mode is selected, all module clocks are halted and the transmission/reception will remain in that state until the devices wakes. After the device returns to Run mode, the module will resume transmitting and receiving data.

In SPI Slave mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in any power managed mode and data to be shifted into the SPI Transmit/Receive Shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device.

#### 16.3.9 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

#### 16.3.10 BUS MODE COMPATIBILITY

Table 16-1 shows the compatibility between the standard SPI modes and the states of the CKP and CKE control bits.

TABLE 16-1: SPI BUS MODES

| Standard SPI™    | <b>Control Bits State</b> |     |  |  |  |
|------------------|---------------------------|-----|--|--|--|
| Mode Terminology | CKP                       | CKE |  |  |  |
| 0, 0             | 0                         | 1   |  |  |  |
| 0, 1             | 0                         | 0   |  |  |  |
| 1, 0             | 1                         | 1   |  |  |  |
| 1, 1             | 1                         | 0   |  |  |  |

There is also an SMP bit which controls when the data is sampled.

TABLE 16-2: REGISTERS ASSOCIATED WITH SPI OPERATION

| Name    | Bit 7  | Bit 6                 | Bit 5                                      | Bit 4        | Bit 3       | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|--|-----------------------|--|--------------|-------------|--------|--------|--------|----------------------------|--|
| INTCON  | GIE/GIEH                                     | PEIE/GIEL             | GIEL TMR0IE INT0IE RBIE TMR0IF INT0IF RBIF |              |             |        |        |        |                            |  |
| PIR1    | PSPIF <sup>(1)</sup>                         | ADIF                  | RCIF TXIF SSPIF CCP1IF TMR2IF TMR1IF       |              |             |        |        |        |                            |  |
| PIE1    | PSPIE <sup>(1)</sup>                         | ADIE                  | RCIE                                       | TXIE         | SSPIE       | CCP1IE | TMR2IE | TMR1IE | 52                         |  |
| IPR1    | PSPIP <sup>(1)</sup>                         | ADIP                  | RCIP                                       | TXIP         | SSPIP       | CCP1IP | TMR2IP | TMR1IP | 52                         |  |
| TRISA   | TRISA7 <sup>(2)</sup>                        | TRISA6 <sup>(2)</sup> | PORTA Da                                   | ta Direction | Control Req | gister |        |        | 52                         |  |
| TRISC   | PORTC Da                                     | ta Direction          | Control Req                                | gister       |             |        |        |        | 52                         |  |
| SSPBUF  | SSP Receive Buffer/Transmit Register         |                       |  |              |             |        |        |        | 50                         |  |
| SSPCON1 | WCOL SSPOV SSPEN CKP SSPM3 SSPM2 SSPM1 SSPM0 |                       |  |              |             |        |        |        | 50                         |  |
| SSPSTAT | SMP  | CKE                   | $D/\overline{A}$                           | Р            | S           | R/W    | UA     | BF     | 50                         |  |

Legend: Shaded cells are not used by the MSSP in SPI mode.

**Note 1:** These bits are unimplemented on 28-pin devices and read as '0'.

2: PORTA<7:6> and their direction bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.

## 16.4 I<sup>2</sup>C Mode


The MSSP module in I<sup>2</sup>C mode fully implements all master and slave functions (including general call support) and provides interrupts on Start and Stop bits in hardware to determine a free bus (multi-master function). The MSSP module implements the standard mode specifications, as well as 7-bit and 10-bit addressing.

Two pins are used for data transfer:

- Serial clock (SCL) RC3/SCK/SCL
- Serial data (SDA) RC4/SDI/SDA

The user must configure these pins as inputs or outputs through the TRISC<4:3> bits.

FIGURE 16-7: MSSP BLOCK DIAGRAM (I<sup>2</sup>CTM MODE)



#### 16.4.1 REGISTERS

The MSSP module has six registers for I<sup>2</sup>C operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Control Register 2 (SSPCON2)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer Register (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible
- MSSP Address Register (SSPADD)

SSPCON1, SSPCON2 and SSPSTAT are the control and status registers in  $I^2C$  mode operation. The SSPCON1 and SSPCON2 registers are readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

SSPADD register holds the slave device address when the SSP is configured in I<sup>2</sup>C Slave mode. When the SSP is configured in Master mode, the lower seven bits of SSPADD act as the Baud Rate Generator reload value.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not double-buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

# REGISTER 16-3: SSPSTAT: MSSP STATUS REGISTER (I<sup>2</sup>C MODE)

| R/W-0 | R/W-0 | R-0 | R-0 | R-0 | R-0 | R-0 | R-0 |
|-------|-------|-----|-----|-----|-----|-----|-----|
| SMP   | CKE   | D/A | Р   | S   | R/W | UA  | BF  |

bit 7 bit 0

#### bit 7 SMP: Slew Rate Control bit

#### In Master or Slave mode:

- 1 = Slew rate control disabled for Standard Speed mode (100 kHz and 1 MHz)
- 0 = Slew rate control enabled for High-Speed mode (400 kHz)

#### bit 6 CKE: SMBus Select bit

## In Master or Slave mode:

- 1 = Enable SMBus specific inputs
- 0 = Disable SMBus specific inputs
- bit 5 D/A: Data/Address bit

#### In Master mode:

Reserved.

#### In Slave mode:

- 1 = Indicates that the last byte received or transmitted was data
- 0 = Indicates that the last byte received or transmitted was address
- bit 4 **P:** Stop bit
  - 1 = Indicates that a Stop bit has been detected last
  - 0 = Stop bit was not detected last

Note: This bit is cleared on Reset and when SSPEN is cleared.

- bit 3 S: Start bit
  - 1 = Indicates that a Start bit has been detected last
  - 0 = Start bit was not detected last

Note: This bit is cleared on Reset and when SSPEN is cleared.

bit 2 R/W: Read/Write bit Information (I<sup>2</sup>C mode only)

### In Slave mode:

- 1 = Read
- 0 = Write

**Note:** This bit holds the R/W bit information following the last address match. This bit is only valid from the address match to the next Start bit, Stop bit or not ACK bit.

#### In Master mode:

- 1 = Transmit is in progress
- 0 = Transmit is not in progress

**Note:** ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is in Active mode.

- bit 1 **UA:** Update Address bit (10-bit Slave mode only)
  - 1 = Indicates that the user needs to update the address in the SSPADD register
  - 0 = Address does not need to be updated
- bit 0 BF: Buffer Full Status bit

### In Transmit mode:

- 1 = SSPBUF is full
- 0 = SSPBUF is empty

## In Receive mode:

- 1 = SSPBUF is full (does not include the  $\overline{ACK}$  and Stop bits)
- 0 = SSPBUF is empty (does not include the  $\overline{ACK}$  and Stop bits)

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# REGISTER 16-4: SSPCON1: MSSP CONTROL REGISTER 1 (I<sup>2</sup>C MODE)

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| WCOL  | SSPOV | SSPEN | CKP   | SSPM3 | SSPM2 | SSPM1 | SSPM0 |
|       |       |       |       |       |       |       |       |

bit 7 bit 0

### bit 7 WCOL: Write Collision Detect bit

#### In Master Transmit mode:

- 1 = A write to the SSPBUF register was attempted while the I<sup>2</sup>C conditions were not valid for a transmission to be started (must be cleared in software)
- 0 = No collision

#### In Slave Transmit mode:

- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision

#### In Receive mode (Master or Slave modes):

This is a "don't care" bit.

#### bit 6 SSPOV: Receive Overflow Indicator bit

#### In Receive mode:

- 1 = A byte is received while the SSPBUF register is still holding the previous byte (must be cleared in software)
- 0 = No overflow

#### In Transmit mode:

This is a "don't care" bit in Transmit mode.

- bit 5 SSPEN: Synchronous Serial Port Enable bit
  - 1 = Enables the serial port and configures the SDA and SCL pins as the serial port pins
  - 0 = Disables serial port and configures these pins as I/O port pins

**Note:** When enabled, the SDA and SCL pins must be properly configured as input or output.

# bit 4 CKP: SCK Release Control bit

#### In Slave mode:

- 1 = Release clock
- 0 = Holds clock low (clock stretch), used to ensure data setup time

#### In Master mode:

Unused in this mode.

#### bit 3-0 **SSPM3:SSPM0:** Synchronous Serial Port Mode Select bits

- $1111 = I^2C$  Slave mode, 10-bit address with Start and Stop bit interrupts enabled
- 1110 = I<sup>2</sup>C Slave mode, 7-bit address with Start and Stop bit interrupts enabled
- 1011 = I<sup>2</sup>C Firmware Controlled Master mode (Slave Idle)
- $1000 = I^2C$  Master mode, clock = Fosc/(4 \* (SSPADD + 1))
- $0111 = I^2C$  Slave mode, 10-bit address
- $0110 = I^2C$  Slave mode, 7-bit address

Bit combinations not specifically listed here are either reserved or implemented in SPI mode only.

| Legend:           |                  |                                    |                    |  |
|-------------------|------------------|------------------------------------|--------------------|--|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0' |                    |  |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared               | x = Bit is unknown |  |

#### SSPCON2: MSSP CONTROL REGISTER 2 (I<sup>2</sup>C MODE) REGISTER 16-5:

| R/W-0 | R/W-0   | R/W-0 | R/W-0                | R/W-0               | R/W-0              | R/W-0               | R/W-0              |
|-------|---------|-------|----------------------|---------------------|--------------------|---------------------|--------------------|
| GCEN  | ACKSTAT | ACKDT | ACKEN <sup>(1)</sup> | RCEN <sup>(1)</sup> | PEN <sup>(1)</sup> | RSEN <sup>(1)</sup> | SEN <sup>(1)</sup> |
| bit 7 |         |       |                      |                     |                    |                     | bit 0              |

bit 0

- bit 7 GCEN: General Call Enable bit (Slave mode only)
  - 1 = Enable interrupt when a general call address (0000h) is received in the SSPSR
  - 0 = General call address disabled
- bit 6 **ACKSTAT:** Acknowledge Status bit (Master Transmit mode only)
  - 1 = Acknowledge was not received from slave
  - 0 = Acknowledge was received from slave
- **ACKDT:** Acknowledge Data bit (Master Receive mode only) bit 5
  - 1 = Not Acknowledge
  - 0 = Acknowledge

Note: Value that will be transmitted when the user initiates an Acknowledge sequence at the end of a receive.

- **ACKEN:** Acknowledge Sequence Enable bit (Master Receive mode only)<sup>(1)</sup> bit 4
  - 1 = Initiate Acknowledge sequence on SDA and SCL pins and transmit ACKDT data bit. Automatically cleared by hardware.
  - 0 = Acknowledge sequence Idle
- **RCEN:** Receive Enable bit (Master mode only)<sup>(1)</sup> bit 3
  - 1 = Enables Receive mode for I<sup>2</sup>C operation
  - 0 = Receive Idle
- **PEN:** Stop Condition Enable bit (Master mode only)<sup>(1)</sup> bit 2
  - 1 = Initiate Stop condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Stop condition Idle
- **RSEN:** Repeated Start Condition Enable bit (Master mode only)<sup>(1)</sup> bit 1
  - 1 = Initiate Repeated Start condition on SDA and SCL pins. Automatically cleared by hardware.
  - 0 = Repeated Start condition Idle
- bit 0 **SEN:** Start Condition Enable/Stretch Enable bit<sup>(1)</sup>

## In Master mode:

- 1 = Initiate Start condition on SDA and SCL pins. Automatically cleared by hardware.
- 0 = Start condition Idle

### In Slave mode:

- 1 = Clock stretching is enabled for both slave transmit and slave receive (stretch enabled)
- 0 = Clock stretching is disabled

Note 1: For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I<sup>2</sup>C module is not in the Idle mode, these bits may not be set (no spooling) and the SSPBUF may not be written (or writes to the SSPBUF are disabled).

| Legend:           |                  |                                    |                    |
|-------------------|------------------|------------------------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0' |                    |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared               | x = Bit is unknown |

#### 16.4.2 OPERATION

The MSSP module functions are enabled by setting MSSP Enable bit, SSPEN (SSPCON<5>).

The SSPCON1 register allows control of the I<sup>2</sup>C operation. Four mode selection bits (SSPCON<3:0>) allow one of the following I<sup>2</sup>C modes to be selected:

- I<sup>2</sup>C Master mode clock
- I<sup>2</sup>C Slave mode (7-bit address)
- I<sup>2</sup>C Slave mode (10-bit address)
- I<sup>2</sup>C Slave mode (7-bit address) with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Slave mode (10-bit address) with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Firmware Controlled Master mode, slave is Idle

Selection of any I<sup>2</sup>C mode with the SSPEN bit set, forces the SCL and SDA pins to be open-drain, provided these pins are programmed to inputs by setting the appropriate TRISC bits. To ensure proper operation of the module, pull-up resistors must be provided externally to the SCL and SDA pins.

#### 16.4.3 SLAVE MODE

In Slave mode, the SCL and SDA pins must be configured as inputs (TRISC<4:3> set). The MSSP module will override the input state with the output data when required (slave-transmitter).

The I<sup>2</sup>C Slave mode hardware will always generate an interrupt on an address match. Through the mode select bits, the user can also choose to interrupt on Start and Stop bits

When an address is matched, or the data transfer after an address match is received, the hardware automatically will generate the Acknowledge (ACK) pulse and load the SSPBUF register with the received value currently in the SSPSR register.

Any combination of the following conditions will cause the MSSP module not to give this ACK pulse:

- The Buffer Full bit, BF (SSPSTAT<0>), was set before the transfer was received.
- The overflow bit, SSPOV (SSPCON<6>), was set before the transfer was received.

In this case, the SSPSR register value is not loaded into the SSPBUF, but bit SSPIF (PIR1<3>) is set. The BF bit is cleared by reading the SSPBUF register, while bit SSPOV is cleared through software.

The SCL clock input must have a minimum high and low for proper operation. The high and low times of the  $I^2C$  specification, as well as the requirement of the MSSP module, are shown in timing parameter 100 and parameter 101.

#### 16.4.3.1 Addressing

Once the MSSP module has been enabled, it waits for a Start condition to occur. Following the Start condition, the 8-bits are shifted into the SSPSR register. All incoming bits are sampled with the rising edge of the clock (SCL) line. The value of register SSPSR<7:1> is compared to the value of the SSPADD register. The address is compared on the falling edge of the eighth clock (SCL) pulse. If the addresses match and the BF and SSPOV bits are clear, the following events occur:

- The SSPSR register value is loaded into the SSPBUF register.
- 2. The Buffer Full bit, BF, is set.
- 3. An ACK pulse is generated.
- 4. MSSP Interrupt Flag bit, SSPIF (PIR1<3>), is set (interrupt is generated, if enabled) on the falling edge of the ninth SCL pulse.

In 10-bit Address mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit R/W (SSPSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal '11110 A9 A8 0', where 'A9' and 'A8' are the two MSbs of the address. The sequence of events for 10-bit address is as follows, with steps 7 through 9 for the slave-transmitter:

- Receive first (high) byte of address (bits SSPIF, BF and UA (SSPSTAT<1>) are set).
- Update the SSPADD register with second (low) byte of address (clears bit UA and releases the SCL line).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 4. Receive second (low) byte of address (bits SSPIF, BF and UA are set).
- Update the SSPADD register with the first (high) byte of address. If match releases SCL line, this will clear bit UA.
- 6. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 7. Receive Repeated Start condition.
- Receive first (high) byte of address (bits SSPIF and BF are set).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.

### 16.4.3.2 Reception

When the  $R/\overline{W}$  bit of the address byte is clear and an address match occurs, the  $R/\overline{W}$  bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register and the SDA line is held low  $(\overline{ACK})$ .

When the address byte overflow condition exists, then the no Acknowledge (ACK) pulse is given. An overflow condition is defined as either bit BF (SSPSTAT<0>) is set, or bit SSPOV (SSPCON1<6>) is set.

An MSSP interrupt is generated for each data transfer byte. Flag bit, SSPIF (PIR1<3>), must be cleared in software. The SSPSTAT register is used to determine the status of the byte.


If SEN is enabled (SSPCON2<0> = 1), RC3/SCK/SCL will be held low (clock stretch) following each data transfer. The clock must be released by setting bit CKP (SSPCON<4>). See **Section 16.4.4 "Clock Stretching"** for more detail.


#### 16.4.3.3 Transmission

When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register. The ACK pulse will be sent on the ninth bit and pin RC3/SCK/SCL is held low regardless of SEN (see Section 16.4.4 "Clock Stretching" for more detail). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data. The transmit data must be loaded into the SSPBUF register which also loads the SSPSR register. Then pin RC3/ SCK/SCL should be enabled by setting bit CKP (SSPCON1<4>). The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time (Figure 16-9).


The  $\overline{ACK}$  pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. If the SDA line is high (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the  $\overline{ACK}$  is latched by the slave, the slave logic is reset (resets SSPSTAT register) and the slave monitors for another occurrence of the Start bit. If the SDA line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPBUF register. Again, pin RC3/SCK/SCL must be enabled by setting bit CKP.


An MSSP interrupt is generated for each data transfer byte. The SSPIF bit must be cleared in software and the SSPSTAT register is used to determine the status of the byte. The SSPIF bit is set on the falling edge of the ninth clock pulse.





© 2004 Microchip Technology Inc. Preliminary DS39636A-page 167





**Preliminary** © 2004 Microchip Technology Inc. DS39636A-page 169

#### 16.4.4 CLOCK STRETCHING

Both 7-bit and 10-bit Slave modes implement automatic clock stretching during a transmit sequence.

The SEN bit (SSPCON2<0>) allows clock stretching to be enabled during receives. Setting SEN will cause the SCL pin to be held low at the end of each data receive sequence.

# 16.4.4.1 Clock Stretching for 7-bit Slave Receive Mode (SEN = 1)

In 7-bit Slave Receive mode, on the falling edge of the ninth clock at the end of the  $\overline{ACK}$  sequence if the BF bit is set, the CKP bit in the SSPCON1 register is automatically cleared, forcing the SCL output to be held low. The CKP being cleared to '0' will assert the SCL line low. The CKP bit must be set in the user's ISR before reception is allowed to continue. By holding the SCL line low, the user has time to service the ISR and read the contents of the SSPBUF before the master device can initiate another receive sequence. This will prevent buffer overruns from occurring (see Figure 16-13).

- Note 1: If the user reads the contents of the SSPBUF before the falling edge of the ninth clock, thus clearing the BF bit, the CKP bit will not be cleared and clock stretching will not occur.
  - 2: The CKP bit can be set in software regardless of the state of the BF bit. The user should be careful to clear the BF bit in the ISR before the next receive sequence in order to prevent an overflow condition.

## 16.4.4.2 Clock Stretching for 10-bit Slave Receive Mode (SEN = 1)

In 10-bit Slave Receive mode during the address sequence, clock stretching automatically takes place but CKP is not cleared. During this time, if the UA bit is set after the ninth clock, clock stretching is initiated. The UA bit is set after receiving the upper byte of the 10-bit address and following the receive of the second byte of the 10-bit address with the  $R\overline{\rm W}$  bit cleared to '0'. The release of the clock line occurs upon updating SSPADD. Clock stretching will occur on each data receive sequence as described in 7-bit mode.

Note: If the user polls the UA bit and clears it by updating the SSPADD register before the falling edge of the ninth clock occurs and if the user hasn't cleared the BF bit by reading the SSPBUF register before that time, then the CKP bit will still NOT be asserted low. Clock stretching on the basis of the state of the BF bit only occurs during a data sequence, not an address sequence.

## 16.4.4.3 Clock Stretching for 7-bit Slave Transmit Mode

7-bit Slave Transmit mode implements clock stretching by clearing the CKP bit after the falling edge of the ninth clock if the BF bit is clear. This occurs regardless of the state of the SEN bit.

The user's ISR must set the CKP bit before transmission is allowed to continue. By holding the SCL line low, the user has time to service the ISR and load the contents of the SSPBUF before the master device can initiate another transmit sequence (see Figure 16-9).

- Note 1: If the user loads the contents of SSPBUF, setting the BF bit before the falling edge of the ninth clock, the CKP bit will not be cleared and clock stretching will not occur.
  - **2:** The CKP bit can be set in software regardless of the state of the BF bit.

## 16.4.4.4 Clock Stretching for 10-bit Slave Transmit Mode


In 10-bit Slave Transmit mode, clock stretching is controlled during the first two address sequences by the state of the UA bit, just as it is in 10-bit Slave Receive mode. The first two addresses are followed by a third address sequence which contains the high-order bits of the 10-bit address and the  $R/\overline{W}$  bit set to '1'. After the third address sequence is performed, the UA bit is not set, the module is now configured in Transmit mode and clock stretching is controlled by the BF flag as in 7-bit Slave Transmit mode (see Figure 16-11).

# 16.4.4.5 Clock Synchronization and the CKP bit


When the CKP bit is cleared, the SCL output is forced to '0'. However, clearing the CKP bit will not assert the SCL output low until the SCL output is already sampled low. Therefore, the CKP bit will not assert the SCL line until an external I<sup>2</sup>C master device has


already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I<sup>2</sup>C bus have deasserted SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 16-12).





© 2004 Microchip Technology Inc. Preliminary DS39636A-page 171





**Preliminary** © 2004 Microchip Technology Inc. DS39636A-page 173

# 16.4.5 GENERAL CALL ADDRESS SUPPORT

The addressing procedure for the I<sup>2</sup>C bus is such that the first byte after the Start condition usually determines which device will be the slave addressed by the master. The exception is the general call address which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is one of eight addresses reserved for specific purposes by the  $I^2C$  protocol. It consists of all '0's with  $R/\overline{W} = 0$ .


The general call address is recognized when the General Call Enable bit (GCEN) is enabled (SSPCON2<7> set). Following a Start bit detect, 8 bits are shifted into the SSPSR and the address is compared against the SSPADD. It is also compared to the general call address and fixed in hardware.

If the general call address matches, the SSPSR is transferred to the SSPBUF, the BF flag bit is set (eighth bit) and on the falling edge of the ninth bit (ACK bit), the SSPIF interrupt flag bit is set.

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the SSPBUF. The value can be used to determine if the address was device specific or a general call address.

In 10-bit mode, the SSPADD is required to be updated for the second half of the address to match and the UA bit is set (SSPSTAT<1>). If the general call address is sampled when the GCEN bit is set, while the slave is configured in 10-bit Address mode, then the second half of the address is not necessary, the UA bit will not be set and the slave will begin receiving data after the Acknowledge (Figure 16-15).

FIGURE 16-15: SLAVE MODE GENERAL CALL ADDRESS SEQUENCE (7 OR 10-BIT ADDRESS MODE)



#### 16.4.6 MASTER MODE

Master mode is enabled by setting and clearing the appropriate SSPM bits in SSPCON1 and by setting the SSPEN bit. In Master mode, the SCL and SDA lines are manipulated by the MSSP hardware.

Master mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set, or the bus is Idle, with both the S and P bits clear.

In Firmware Controlled Master mode, user code conducts all I<sup>2</sup>C bus operations based on Start and Stop bit conditions.

Once Master mode is enabled, the user has six options.

- 1. Assert a Start condition on SDA and SCL.
- Assert a Repeated Start condition on SDA and SCL.
- 3. Write to the SSPBUF register initiating transmission of data/address.
- 4. Configure the I<sup>2</sup>C port to receive data.
- 5. Generate an Acknowledge condition at the end of a received byte of data.
- 6. Generate a Stop condition on SDA and SCL.

The MSSP module, when configured in I<sup>2</sup>C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a Start condition and immediately write the SSPBUF register to initiate transmission before the Start condition is complete. In this case, the SSPBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPBUF did not occur.


The following events will cause the SSP Interrupt Flag bit, SSPIF, to be set (SSP interrupt, if enabled):

· Start condition

Note:

- Stop condition
- · Data transfer byte transmitted/received
- · Acknowledge transmit
- · Repeated Start

FIGURE 16-16: MSSP BLOCK DIAGRAM (I<sup>2</sup>C™ MASTER MODE)



## 16.4.6.1 I<sup>2</sup>C Master Mode Operation

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus will not be released.

In Master Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the slave <u>address</u> of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the R/W bit. In this case, the R/W bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address followed by a '1' to indicate the receive bit. Serial data is received via SDA, while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

The Baud Rate Generator used for the SPI mode operation is used to set the SCL clock frequency for either 100 kHz, 400 kHz or 1 MHz I<sup>2</sup>C operation. See **Section 16.4.7 "Baud Rate"** for more detail.

A typical transmit sequence would go as follows:

- 1. The user generates a Start condition by setting the Start Enable bit, SEN (SSPCON2<0>).
- SSPIF is set. The MSSP module will wait the required start time before any other operation takes place.
- The user loads the SSPBUF with the slave address to transmit.
- Address is shifted out the SDA pin until all 8 bits are transmitted.
- 5. The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- The user loads the SSPBUF with eight bits of data
- Data is shifted out the SDA pin until all 8 bits are transmitted.
- The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF hit
- 11. The user generates a Stop condition by setting the Stop Enable bit, PEN (SSPCON2<2>).
- 12. Interrupt is generated once the Stop condition is complete.

#### 16.4.7 BAUD RATE

In I<sup>2</sup>C Master mode, the Baud Rate Generator (BRG) reload value is placed in the lower 7 bits of the SSPADD register (Figure 16-17). When a write occurs to SSPBUF, the Baud Rate Generator will automatically begin counting. The BRG counts down to '0' and stops until another reload has taken place. The BRG count is decremented twice per instruction cycle (TCY) on the Q2 and Q4 clocks. In I<sup>2</sup>C Master mode, the BRG is reloaded automatically.

Once the given operation is complete (i.e., transmission of the last data bit is followed by  $\overline{ACK}$ ), the internal clock will automatically stop counting and the SCL pin will remain in its last state.

Table 16-3 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPADD.

FIGURE 16-17: BAUD RATE GENERATOR BLOCK DIAGRAM




TABLE 16-3: I<sup>2</sup>C™ CLOCK RATE W/BRG

| Fosc   | FcY    | Fcy * 2 | BRG Value | FSCL<br>(2 Rollovers of BRG) |
|--------|--------|---------|-----------|------------------------------|
| 40 MHz | 10 MHz | 20 MHz  | 18h       | 400 kHz <sup>(1)</sup>       |
| 40 MHz | 10 MHz | 20 MHz  | 1Fh       | 312.5 kHz                    |
| 40 MHz | 10 MHz | 20 MHz  | 63h       | 100 kHz                      |
| 16 MHz | 4 MHz  | 8 MHz   | 09h       | 400 kHz <sup>(1)</sup>       |
| 16 MHz | 4 MHz  | 8 MHz   | 0Ch       | 308 kHz                      |
| 16 MHz | 4 MHz  | 8 MHz   | 27h       | 100 kHz                      |
| 4 MHz  | 1 MHz  | 2 MHz   | 02h       | 333 kHz <sup>(1)</sup>       |
| 4 MHz  | 1 MHz  | 2 MHz   | 09h       | 100 kHz                      |
| 4 MHz  | 1 MHz  | 2 MHz   | 00h       | 1 MHz <sup>(1)</sup>         |

**Note 1:** The I<sup>2</sup>C interface does not conform to the 400 kHz I<sup>2</sup>C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.


© 2004 Microchip Technology Inc. Preliminary DS39636A-page 177

#### 16.4.7.1 Clock Arbitration

Clock arbitration occurs when the master, during any receive, transmit or Repeated Start/Stop condition, deasserts the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the

SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 16-18).

FIGURE 16-18: BAUD RATE GENERATOR TIMING WITH CLOCK ARBITRATION



# 16.4.8 I<sup>2</sup>C MASTER MODE START CONDITION TIMING

To initiate a Start condition, the user sets the Start Enable bit, SEN (SSPCON2<0>). If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low while SCL is high is the Start condition and causes the S bit (SSPSTAT<3>) to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and resumes its count. When the Baud Rate Generator times out (TBRG), the SEN bit (SSPCON2<0>) will be automatically cleared by hardware; the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.

If at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag, BCLIF, is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.


## 16.4.8.1 WCOL Status Flag

Note:

If the user writes the SSPBUF when a Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Because queueing of events is not allowed, writing to the lower 5 bits of SSPCON2 is disabled until the Start condition is complete.





# 16.4.9 I<sup>2</sup>C MASTER MODE REPEATED START CONDITION TIMING

A Repeated Start condition occurs when the RSEN bit (SSPCON2<1>) is programmed high and the I<sup>2</sup>C logic module is in the Idle state. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded with the contents of SSPADD<5:0> and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count (TBRG). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. Following this, the RSEN bit (SSPCON2<1>) will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit (SSPSTAT<3>) will be set. The SSPIF bit will not be set until the Baud Rate Generator has timed out.

**Note 1:** If RSEN is programmed while any other event is in progress, it will not take effect.

- **2:** A bus collision during the Repeated Start condition occurs if:
  - SDA is sampled low when SCL goes from low-to-high.
  - SCL goes low before SDA is asserted low. This may indicate that another master is attempting to transmit a data '1'.


Immediately following the SSPIF bit getting set, the user may write the SSPBUF with the 7-bit address in 7-bit mode or the default first address in 10-bit mode. After the first eight bits are transmitted and an ACK is received, the user may then transmit an additional eight bits of address (10-bit mode) or eight bits of data (7-bit mode).

## 16.4.9.1 WCOL Status Flag

If the user writes the SSPBUF when a Repeated Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

**Note:** Because queueing of events is not allowed, writing of the lower 5 bits of SSPCON2 is disabled until the Repeated Start condition is complete.





# 16.4.10 I<sup>2</sup>C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPBUF register. This action will set the Buffer Full flag bit, BF and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted (see data hold time specification parameter 106). SCL is held low for one Baud Rate Generator rollover count (TBRG). Data should be valid before SCL is released high (see data setup time specification parameter 107). When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDA. This allows the slave device being addressed to respond with an ACK bit during the ninth bit time if an address match occurred, or if data was received properly. The status of ACK is written into the ACKDT bit on the falling edge of the ninth clock. If the master receives an Acknowledge, the Acknowledge Status bit, ACKSTAT, is cleared. If not, the bit is set. After the ninth clock, the SSPIF bit is set and the master clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPBUF, leaving SCL low and SDA unchanged (Figure 16-21).

After the write to the SSPBUF, each bit of the address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will deassert the SDA pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDA pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT status bit (SSPCON2<6>). Following the falling edge of the ninth clock transmission of the address, the SSPIF is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPBUF takes place, holding SCL low and allowing SDA to float.

## 16.4.10.1 BF Status Flag

In Transmit mode, the BF bit (SSPSTAT<0>) is set when the CPU writes to SSPBUF and is cleared when all 8 bits are shifted out.

## 16.4.10.2 WCOL Status Flag

If the user writes the SSPBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

WCOL must be cleared in software.

## 16.4.10.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit (SSPCON2<6>) is cleared when the slave has sent an Acknowledge  $(\overline{ACK} = 0)$  and is set when the slave does not Acknowledge  $(\overline{ACK} = 1)$ . A slave sends an Acknowledge when it has recognized its address (including a general call), or when the slave has properly received its data.

## 16.4.11 I<sup>2</sup>C MASTER MODE RECEPTION

Master mode reception is enabled by programming the Receive Enable bit, RCEN (SSPCON2<3>).

Note: The MSSP module must be in an Idle state before the RCEN bit is set or the RCEN bit will be disregarded.

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/low-to-high) and data is shifted into the SSPSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPSR are loaded into the SSPBUF, the BF flag bit is set, the SSPIF flag bit is set and the Baud Rate Generator is suspended from counting, holding SCL low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Acknowledge Sequence Enable bit, ACKEN (SSPCON2<4>).

#### 16.4.11.1 BF Status Flag


In receive operation, the BF bit is set when an address or data byte is loaded into SSPBUF from SSPSR. It is cleared when the SSPBUF register is read.


## 16.4.11.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when 8 bits are received into the SSPSR and the BF flag bit is already set from a previous reception.

## 16.4.11.3 WCOL Status Flag

If the user writes the SSPBUF when a receive is already in progress (i.e., SSPSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).





## 16.4.12 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge Sequence Enable bit. **ACKEN** (SSPCON2<4>). When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period (TBRG) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode (Figure 16-23).

## 16.4.12.1 WCOL Status Flag

If the user writes the SSPBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).


#### 16.4.13 STOP CONDITION TIMING

A Stop bit is asserted on the SDA pin at the end of a receive/transmit by setting the Stop Sequence Enable bit, PEN (SSPCON2<2>). At the end of a receive/transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to '0'. When the Baud Rate Generator times out, the SCL pin will be brought high and one TBRG (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit (SSPSTAT<4>) is set. A TBRG later, the PEN bit is cleared and the SSPIF bit is set (Figure 16-24).


## 16.4.13.1 WCOL Status Flag

If the user writes the SSPBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).

## FIGURE 16-23: ACKNOWLEDGE SEQUENCE WAVEFORM



## FIGURE 16-24: STOP CONDITION RECEIVE OR TRANSMIT MODE



#### 16.4.14 SLEEP OPERATION

While in Sleep mode, the I<sup>2</sup>C module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

## 16.4.15 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

## 16.4.16 MULTI-MASTER MODE

In Multi-Master mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit (SSPSTAT<4>) is set, or the bus is Idle, with both the S and P bits clear. When the bus is busy, enabling the SSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-master operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed in hardware with the result placed in the BCLIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- Data Transfer
- · A Start Condition
- · A Repeated Start Condition
- An Acknowledge Condition

## 16.4.17 MULTI -MASTER COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA, by letting SDA float high and another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin = 0, then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag, BCLIF and reset the  $I^2$ C port to its Idle state (Figure 16-25).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted and the SSPBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the  $\rm I^2C$  bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the SSPCON2 register are cleared. When the user services the bus collision Interrupt Service Routine and if the  $I^2C$  bus is free, the user can resume communication by asserting a Start condition.

The master will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPIF bit will be set.

A write to the SSPBUF will start the transmission of data at the first data bit regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the  $I^2C$  bus can be taken when the P bit is set in the SSPSTAT register, or the bus is Idle and the S and P bits are cleared.





## 16.4.17.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- a) SDA or SCL are sampled low at the beginning of the Start condition (Figure 16-26).
- SCL is sampled low before SDA is asserted low (Figure 16-27).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- · the Start condition is aborted,
- · the BCLIF flag is set and
- the MSSP module is reset to its Idle state (Figure 16-26).

The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded from SSPADD<6:0> and counts down to 0. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another master is attempting to drive a data '1' during the Start condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 16-28). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The Baud Rate Generator is then reloaded and counts down to 0; if the SCL pin is sampled as '0' during this time, a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.

Note:

The reason that bus collision is not a factor during a Start condition is that no two bus masters can assert a Start condition at the exact same time. Therefore, one master will always assert SDA before the other. This condition does not cause a bus collision because the two masters must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.

FIGURE 16-26: BUS COLLISION DURING START CONDITION (SDA ONLY)






FIGURE 16-27: BUS COLLISION DURING START CONDITION (SCL = 0)



## FIGURE 16-28: BRG RESET DUE TO SDA ARBITRATION DURING START CONDITION



## 16.4.17.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- A low level is sampled on SDA when SCL goes from low level to high level.
- SCL goes low before SDA is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user deasserts SDA and the pin is allowed to float high, the BRG is loaded with SSPADD<6:0> and counts down to 0. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.

If SDA is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', Figure 16-29). If SDA is sampled high, the BRG is reloaded and begins counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two masters can assert SDA at exactly the same time.

If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated Start condition, see Figure 16-30.

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.

FIGURE 16-29: BUS COLLISION DURING A REPEATED START CONDITION (CASE 1)





FIGURE 16-30: BUS COLLISION DURING REPEATED START CONDITION (CASE 2)



## 16.4.17.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:

- After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out.
- b) After the SCL pin is deasserted, SCL is sampled low before SDA goes high.

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPADD<6:0> and counts down to 0. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 16-31). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 16-32).

FIGURE 16-31: BUS COLLISION DURING A STOP CONDITION (CASE 1)





FIGURE 16-32: BUS COLLISION DURING A STOP CONDITION (CASE 2)



NOTES:

## 17.0 ENHANCED UNIVERSAL SYNCHRONOUS RECEIVER TRANSMITTER (EUSART)

The Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) module is one of the two serial I/O modules. (Generically, the USART is also known as a Serial Communications Interface or SCI.) The EUSART can be configured as a full-duplex asynchronous system that can communicate with peripheral devices, such as CRT terminals and personal computers. It can also be configured as a half-duplex synchronous system that can communicate with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs, etc.

The Enhanced USART module implements additional features, including automatic baud rate detection and calibration, automatic wake-up on Sync Break reception and 12-bit Break character transmit. These make it ideally suited for use in Local Interconnect Network bus (LIN bus) systems.

The EUSART can be configured in the following modes:

- Asynchronous (full duplex) with:
  - Auto-wake-up on character reception
  - Auto-baud calibration
  - 12-bit Break character transmission
- Synchronous Master (half duplex) with selectable clock polarity
- Synchronous Slave (half duplex) with selectable clock polarity

The pins of the Enhanced USART are multiplexed with PORTC. In order to configure RC6/TX/CK and RC7/RX/DT as a USART:

- bit SPEN (RCSTA<7>) must be set (= 1)
- bit TRISC<7> must be set (= 1)
- bit TRISC<6> must be set (= 1)

**Note:** The EUSART control will automatically reconfigure the pin from input to output as needed.

The operation of the Enhanced USART module is controlled through three registers:

- Transmit Status and Control (TXSTA)
- Receive Status and Control (RCSTA)
- Baud Rate Control (BAUDCON)

These are detailed on the following pages in Register 17-1, Register 17-2 and Register 17-3, respectively.

#### REGISTER 17-1: TXSTA: TRANSMIT STATUS AND CONTROL REGISTER

| R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R-1  | R/W-0 |
|-------|-------|-------|-------|-------|-------|------|-------|
| CSRC  | TX9   | TXEN  | SYNC  | SENDB | BRGH  | TRMT | TX9D  |

bit 7 bit 0

bit 7 CSRC: Clock Source Select bit

Asynchronous mode:

Don't care.

Synchronous mode:

1 = Master mode (clock generated internally from BRG)

0 = Slave mode (clock from external source)

bit 6 TX9: 9-bit Transmit Enable bit

1 = Selects 9-bit transmission

0 = Selects 8-bit transmission

bit 5 **TXEN:** Transmit Enable bit

1 = Transmit enabled

0 = Transmit disabled

Note: SREN/CREN overrides TXEN in Sync mode.

bit 4 SYNC: EUSART Mode Select bit

1 = Synchronous mode

0 = Asynchronous mode

bit 3 SENDB: Send Break Character bit

Asynchronous mode:

1 = Send Sync Break on next transmission (cleared by hardware upon completion)

0 = Sync Break transmission completed

Synchronous mode:

Don't care.

bit 2 BRGH: High Baud Rate Select bit

Asynchronous mode:

1 = High speed

0 = Low speed

Synchronous mode:

Unused in this mode.

bit 1 TRMT: Transmit Shift Register Status bit

1 = TSR empty

0 = TSR full

bit 0 **TX9D:** 9th bit of Transmit Data

Can be address/data bit or a parity bit.

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### RCSTA: RECEIVE STATUS AND CONTROL REGISTER REGISTER 17-2:

| bit 7 |       |       |       |       |      |      | bit 0 |
|-------|-------|-------|-------|-------|------|------|-------|
| SPEN  | RX9   | SREN  | CREN  | ADDEN | FERR | OERR | RX9D  |
| R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R-0  | R-0  | R-x   |

bit 0

#### bit 7 SPEN: Serial Port Enable bit

- 1 = Serial port enabled (configures RX/DT and TX/CK pins as serial port pins)
- 0 = Serial port disabled (held in Reset)

#### bit 6 RX9: 9-bit Receive Enable bit

- 1 = Selects 9-bit reception
- 0 = Selects 8-bit reception
- SREN: Single Receive Enable bit bit 5

## Asynchronous mode:

Don't care.

#### Synchronous mode - Master:

- 1 = Enables single receive
- 0 = Disables single receive

This bit is cleared after reception is complete.

#### Synchronous mode - Slave:

Don't care.

#### bit 4 **CREN:** Continuous Receive Enable bit

#### Asynchronous mode:

- 1 = Enables receiver
- 0 = Disables receiver

#### Synchronous mode:

- 1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)
- 0 = Disables continuous receive

#### bit 3 ADDEN: Address Detect Enable bit

## Asynchronous mode 9-bit (RX9 = 1):

- 1 = Enables address detection, enables interrupt and loads the receive buffer when RSR<8> is set
- 0 = Disables address detection, all bytes are received and ninth bit can be used as parity bit Asynchronous mode 9-bit (RX9 = 0):

Don't care.

#### bit 2 FERR: Framing Error bit

- 1 = Framing error (can be updated by reading RCREG register and receiving next valid byte)
- 0 = No framing error

#### bit 1 **OERR:** Overrun Error bit

- 1 = Overrun error (can be cleared by clearing bit CREN)
- 0 = No overrun error

#### bit 0 RX9D: 9th bit of Received Data

This can be address/data bit or a parity bit and must be calculated by user firmware.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

#### REGISTER 17-3: **BAUDCON: BAUD RATE CONTROL REGISTER**

| R/W-0  | R-1   | U-0 | R/W-0 | R/W-0 | U-0 | R/W-0 | R/W-0 |
|--------|-------|-----|-------|-------|-----|-------|-------|
| ABDOVF | RCIDL | _   | SCKP  | BRG16 | _   | WUE   | ABDEN |
| bit 7  |       |     |       |       |     |       | bit 0 |

bit 0

bit 7 ABDOVF: Auto-Baud Acquisition Rollover Status bit

> 1 = A BRG rollover has occurred during Auto-Baud Rate Detect mode (must be cleared in software)

0 = No BRG rollover has occurred

bit 6 RCIDL: Receive Operation Idle Status bit

> 1 = Receive operation is Idle 0 = Receive operation is active

bit 5 Unimplemented: Read as '0'

bit 4 SCKP: Synchronous Clock Polarity Select bit

> Asynchronous mode: Unused in this mode.

Synchronous mode:

1 = Idle state for clock (CK) is a high level 0 = Idle state for clock (CK) is a low level

bit 3 BRG16: 16-bit Baud Rate Register Enable bit

1 = 16-bit Baud Rate Generator - SPBRGH and SPBRG

0 = 8-bit Baud Rate Generator - SPBRG only (Compatible mode), SPBRGH value ignored

bit 2 Unimplemented: Read as '0'

bit 1 WUE: Wake-up Enable bit

Asynchronous mode:

1 = EUSART will continue to sample the RX pin - interrupt generated on falling edge; bit cleared in hardware on following rising edge

0 = RX pin not monitored or rising edge detected

Synchronous mode:

Unused in this mode.

bit 0 ABDEN: Auto-Baud Detect Enable bit

## Asynchronous mode:

1 = Enable baud rate measurement on the next character. Requires reception of a Sync field (55h); cleared in hardware upon completion

0 = Baud rate measurement disabled or completed

### Synchronous mode:

Unused in this mode.

| Lea | end | : |
|-----|-----|---|
|     |     |   |

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

## 17.1 Baud Rate Generator (BRG)

The BRG is a dedicated 8-bit or 16-bit generator that supports both the Asynchronous and Synchronous modes of the EUSART. By default, the BRG operates in 8-bit mode; setting the BRG16 bit (BAUDCON<3>) selects 16-bit mode.

The SPBRGH:SPBRG register pair controls the period of a free running timer. In Asynchronous mode, bits BRGH (TXSTA<2>) and BRG16 (BAUDCON<3>) also control the baud rate. In Synchronous mode, BRGH is ignored. Table 17-1 shows the formula for computation of the baud rate for different EUSART modes which only apply in Master mode (internally generated clock).

Given the desired baud rate and Fosc, the nearest integer value for the SPBRGH:SPBRG registers can be calculated using the formulas in Table 17-1. From this, the error in baud rate can be determined. An example calculation is shown in Example 17-1. Typical baud rates and error values for the various Asynchronous modes are shown in Table 17-2. It may be

advantageous to use the high baud rate (BRGH = 1) or the 16-bit BRG to reduce the baud rate error, or achieve a slow baud rate for a fast oscillator frequency.

Writing a new value to the SPBRGH:SPBRG registers causes the BRG timer to be reset (or cleared). This ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

# 17.1.1 OPERATION IN POWER MANAGED MODES

The device clock is used to generate the desired baud rate. When one of the power managed modes is entered, the new clock source may be operating at a different frequency. This may require an adjustment to the value in the SPBRG register pair.

#### 17.1.2 SAMPLING

The data on the RX pin is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RX pin.

TABLE 17-1: BAUD RATE FORMULAS

| Co   | onfiguration B | its  | BRG/EUSART Mode     | Baud Rate Formula  |
|------|----------------|------|---------------------|--------------------|
| SYNC | BRG16          | BRGH | BRG/EUSART Mode     | Baud Rate Formula  |
| 0    | 0              | 0    | 8-bit/Asynchronous  | Fosc/[64 (n + 1)]  |
| 0    | 0              | 1    | 8-bit/Asynchronous  | Fosc/[16 (n + 1)]  |
| 0    | 1              | 0    | 16-bit/Asynchronous | FOSC/[16 (11 + 1)] |
| 0    | 1              | 1    | 16-bit/Asynchronous |                    |
| 1    | 0              | х    | 8-bit/Synchronous   | Fosc/[4 (n + 1)]   |
| 1    | 1              | х    | 16-bit/Synchronous  |                    |

**Legend:** x = Don't care, n = value of SPBRGH:SPBRG register pair

#### EXAMPLE 17-1: CALCULATING BAUD RATE ERROR

For a device with Fosc of 16 MHz, desired baud rate of 9600, Asynchronous mode, 8-bit BRG:

Desired Baud Rate = Fosc/(64 ([SPBRGH:SPBRG] + 1))

Solving for SPBRGH:SPBRG:

X = ((FOSC/Desired Baud Rate)/64) - 1

= ((16000000/9600)/64) - 1

= [25.042] = 25

Calculated Baud Rate = 16000000/(64(25+1))

= 9615

Error = (Calculated Baud Rate – Desired Baud Rate)/Desired Baud Rate

= (9615 - 9600)/9600 = 0.16%

### TABLE 17-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

| Name    | Bit 7    | Bit 6  | Bit 5 | Bit 4 | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Reset Values on page |  |  |
|---------|----------|--|-------|-------|-------|-------|-------|-------|----------------------|--|--|
| TXSTA   | CSRC     | TX9  | TXEN  | SYNC  | SENDB | BRGH  | TRMT  | TX9D  | 51                   |  |  |
| RCSTA   | SPEN     | RX9  | SREN  | CREN  | ADDEN | FERR  | OERR  | RX9D  | 51                   |  |  |
| BAUDCON | ABDOVF   | RCIDL  | _     | SCKP  | BRG16 | _     | WUE   | ABDEN | 51                   |  |  |
| SPBRGH  | EUSART E |  | 51    |       |       |       |       |       |                      |  |  |
| SPBRG   | EUSART E | JSART Baud Rate Generator Register, Low Byte |       |       |       |       |       |       |                      |  |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the BRG.

TABLE 17-3: BAUD RATES FOR ASYNCHRONOUS MODES

|              |                       |            |                             |                       | SYNC       | = 0, BRGH                   | l = 0, BRG            | <b>316 =</b> 0 |                             |                       |            |                             |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|----------------|-----------------------------|-----------------------|------------|-----------------------------|
| BAUD<br>RATE | Fosc                  | = 40.000   | ) MHz                       | Fosc                  | = 20.000   | ) MHz                       | Fosc                  | = 10.000       | ) MHz                       | Fos                   | c = 8.000  | MHz                         |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error     | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |
| 0.3          | _                     | _          | _                           | _                     | _          | _                           | _                     |                | _                           | _                     | _          | _                           |
| 1.2          | _                     | _          | _                           | 1.221                 | 1.73       | 255                         | 1.202                 | 0.16           | 129                         | 1201                  | -0.16      | 103                         |
| 2.4          | 2.441                 | 1.73       | 255                         | 2.404                 | 0.16       | 129                         | 2.404                 | 0.16           | 64                          | 2403                  | -0.16      | 51                          |
| 9.6          | 9.615                 | 0.16       | 64                          | 9.766                 | 1.73       | 31                          | 9.766                 | 1.73           | 15                          | 9615                  | -0.16      | 12                          |
| 19.2         | 19.531                | 1.73       | 31                          | 19.531                | 1.73       | 15                          | 19.531                | 1.73           | 7                           | _                     | _          | _                           |
| 57.6         | 56.818                | -1.36      | 10                          | 62.500                | 8.51       | 4                           | 52.083                | -9.58          | 2                           | _                     | _          | _                           |
| 115.2        | 125.000               | 8.51       | 4                           | 104.167               | -9.58      | 2                           | 78.125                | -32.18         | 1                           |                       | _          | _                           |

|             |                       | SYNC = 0, BRGH = 0, BRG16 = 0 |                             |                       |            |                             |                       |            |                             |  |  |  |  |
|-------------|-----------------------|-------------------------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|--|--|--|
| BAUD        | Fos                   | c = 4.000                     | MHz                         | Fos                   | c = 2.000  | MHz                         | Fos                   | c = 1.000  | MHz                         |  |  |  |  |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error                    | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |  |  |  |
| 0.3         | 0.300                 | 0.16                          | 207                         | 300                   | -0.16      | 103                         | 300                   | -0.16      | 51                          |  |  |  |  |
| 1.2         | 1.202                 | 0.16                          | 51                          | 1201                  | -0.16      | 25                          | 1201                  | -0.16      | 12                          |  |  |  |  |
| 2.4         | 2.404                 | 0.16                          | 25                          | 2403                  | -0.16      | 12                          | _                     | _          | _                           |  |  |  |  |
| 9.6         | 8.929                 | -6.99                         | 6                           | _                     | _          | _                           | _                     | _          | _                           |  |  |  |  |
| 19.2        | 20.833                | 8.51                          | 2                           | _                     | _          | _                           | _                     | _          | _                           |  |  |  |  |
| 57.6        | 62.500                | 8.51                          | 0                           | _                     | _          | _                           | _                     | _          | _                           |  |  |  |  |
| 115.2       | 62.500                | -45.75                        | 0                           | _                     | _          | _                           | _                     | _          | _                           |  |  |  |  |

|              |                       |            |                             |                       | SYNC       | = 0, BRGI                   | l = 1, BRG            | i <b>16 =</b> 0 |                             |                       |            |                             |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|-----------------|-----------------------------|-----------------------|------------|-----------------------------|
| BAUD<br>RATE | Fosc                  | = 40.000   | ) MHz                       | Fosc                  | = 20.000   | ) MHz                       | Fosc                  | = 10.000        | ) MHz                       | Fos                   | c = 8.000  | MHz                         |
| (K) A        | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error      | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |
| 0.3          | _                     | _          | _                           | _                     | _          | _                           | _                     |                 | _                           | _                     | _          | _                           |
| 1.2          | _                     | _          | _                           | _                     |            | _                           | _                     | _               | _                           | _                     | _          | _                           |
| 2.4          | _                     | _          | _                           | _                     |            | _                           | 2.441                 | 1.73            | 255                         | 2403                  | -0.16      | 207                         |
| 9.6          | 9.766                 | 1.73       | 255                         | 9.615                 | 0.16       | 129                         | 9.615                 | 0.16            | 64                          | 9615                  | -0.16      | 51                          |
| 19.2         | 19.231                | 0.16       | 129                         | 19.231                | 0.16       | 64                          | 19.531                | 1.73            | 31                          | 19230                 | -0.16      | 25                          |
| 57.6         | 58.140                | 0.94       | 42                          | 56.818                | -1.36      | 21                          | 56.818                | -1.36           | 10                          | 55555                 | 3.55       | 8                           |
| 115.2        | 113.636               | -1.36      | 21                          | 113.636               | -1.36      | 10                          | 125.000               | 8.51            | 4                           | _                     | _          | _                           |

|              | SYNC = 0, BRGH = 1, BRG16 = 0 |            |                             |                       |            |                             |                       |                  |                             |  |  |  |
|--------------|-------------------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------------|-----------------------------|--|--|--|
| BAUD<br>RATE | Fosc                          | = 4.000    | MHz                         | Fos                   | c = 2.000  | MHz                         | Fos                   | Fosc = 1.000 MHz |                             |  |  |  |
| (K)          | Actual<br>Rate<br>(K)         | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error       | SPBRG<br>value<br>(decimal) |  |  |  |
| 0.3          | _                             | _          | _                           | _                     | _          | _                           | 300                   | -0.16            | 207                         |  |  |  |
| 1.2          | 1.202                         | 0.16       | 207                         | 1201                  | -0.16      | 103                         | 1201                  | -0.16            | 51                          |  |  |  |
| 2.4          | 2.404                         | 0.16       | 103                         | 2403                  | -0.16      | 51                          | 2403                  | -0.16            | 25                          |  |  |  |
| 9.6          | 9.615                         | 0.16       | 25                          | 9615                  | -0.16      | 12                          | _                     | _                | _                           |  |  |  |
| 19.2         | 19.231                        | 0.16       | 12                          | _                     | _          | _                           | _                     | _                | _                           |  |  |  |
| 57.6         | 62.500                        | 8.51       | 3                           | _                     | _          | _                           | _                     | _                | _                           |  |  |  |
| 115.2        | 125.000                       | 8.51       | 1                           | _                     | _          | _                           | _                     | _                | _                           |  |  |  |

TABLE 17-3: BAUD RATES FOR ASYNCHRONOUS MODES (CONTINUED)

|              |                       |            |                             |                       | SYNC       | = 0, BRG                    | l = 0, BRG            | 16 = 1     |                             |                       |            |                             |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|
| BAUD<br>RATE | Fosc                  | = 40.000   | ) MHz                       | Fosc                  | = 20.000   | ) MHz                       | Fosc                  | = 10.000   | ) MHz                       | Fos                   | c = 8.000  | MHz                         |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |
| 0.3          | 0.300                 | 0.00       | 8332                        | 0.300                 | 0.02       | 4165                        | 0.300                 | 0.02       | 2082                        | 300                   | -0.04      | 1665                        |
| 1.2          | 1.200                 | 0.02       | 2082                        | 1.200                 | -0.03      | 1041                        | 1.200                 | -0.03      | 520                         | 1201                  | -0.16      | 415                         |
| 2.4          | 2.402                 | 0.06       | 1040                        | 2.399                 | -0.03      | 520                         | 2.404                 | 0.16       | 259                         | 2403                  | -0.16      | 207                         |
| 9.6          | 9.615                 | 0.16       | 259                         | 9.615                 | 0.16       | 129                         | 9.615                 | 0.16       | 64                          | 9615                  | -0.16      | 51                          |
| 19.2         | 19.231                | 0.16       | 129                         | 19.231                | 0.16       | 64                          | 19.531                | 1.73       | 31                          | 19230                 | -0.16      | 25                          |
| 57.6         | 58.140                | 0.94       | 42                          | 56.818                | -1.36      | 21                          | 56.818                | -1.36      | 10                          | 55555                 | 3.55       | 8                           |
| 115.2        | 113.636               | -1.36      | 21                          | 113.636               | -1.36      | 10                          | 125.000               | 8.51       | 4                           | _                     | _          | _                           |

|             |                       |                  | S                           | /NC = 0, E            | BRGH = 0   | , BRG16 =                   | 1                     |            |                             |  |
|-------------|-----------------------|------------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|
| BAUD        | Fosc                  | Fosc = 4.000 MHz |                             |                       | c = 2.000  | MHz                         | Fosc = 1.000 MHz      |            |                             |  |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error       | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |
| 0.3         | 0.300                 | 0.04             | 832                         | 300                   | -0.16      | 415                         | 300                   | -0.16      | 207                         |  |
| 1.2         | 1.202                 | 0.16             | 207                         | 1201                  | -0.16      | 103                         | 1201                  | -0.16      | 51                          |  |
| 2.4         | 2.404                 | 0.16             | 103                         | 2403                  | -0.16      | 51                          | 2403                  | -0.16      | 25                          |  |
| 9.6         | 9.615                 | 0.16             | 25                          | 9615                  | -0.16      | 12                          | _                     | _          | _                           |  |
| 19.2        | 19.231                | 0.16             | 12                          | _                     | _          | _                           | _                     | _          | _                           |  |
| 57.6        | 62.500                | 8.51             | 3                           | _                     | _          | _                           | _                     | _          | _                           |  |
| 115.2       | 125.000               | 8.51             | 1                           | _                     | _          | _                           | _                     | _          | _                           |  |

|              |                       |            |                             | SYNC = 0              | , BRGH =   | = 1, BRG16                  | = 1 or SY             | NC = 1,    | BRG16 = 1                   |                       |            |                             |
|--------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|
| BAUD<br>RATE | Fosc = 40.000 MHz     |            |                             | Fosc = 20.000 MHz     |            |                             | Fosc = 10.000 MHz     |            |                             | Fosc = 8.000 MHz      |            |                             |
| (K)          | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |
| 0.3          | 0.300                 | 0.00       | 33332                       | 0.300                 | 0.00       | 16665                       | 0.300                 | 0.00       | 8332                        | 300                   | -0.01      | 6665                        |
| 1.2          | 1.200                 | 0.00       | 8332                        | 1.200                 | 0.02       | 4165                        | 1.200                 | 0.02       | 2082                        | 1200                  | -0.04      | 1665                        |
| 2.4          | 2.400                 | 0.02       | 4165                        | 2.400                 | 0.02       | 2082                        | 2.402                 | 0.06       | 1040                        | 2400                  | -0.04      | 832                         |
| 9.6          | 9.606                 | 0.06       | 1040                        | 9.596                 | -0.03      | 520                         | 9.615                 | 0.16       | 259                         | 9615                  | -0.16      | 207                         |
| 19.2         | 19.193                | -0.03      | 520                         | 19.231                | 0.16       | 259                         | 19.231                | 0.16       | 129                         | 19230                 | -0.16      | 103                         |
| 57.6         | 57.803                | 0.35       | 172                         | 57.471                | -0.22      | 86                          | 58.140                | 0.94       | 42                          | 57142                 | 0.79       | 34                          |
| 115.2        | 114.943               | -0.22      | 86                          | 116.279               | 0.94       | 42                          | 113.636               | -1.36      | 21                          | 117647                | -2.12      | 16                          |

|             |                       | SYN        | NC = 0, BR                  | GH = 1, BF            | RG16 = 1   | or SYNC =                   | 1, BRG1               | 6 = 1      |                             |  |
|-------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|-----------------------|------------|-----------------------------|--|
| BAUD        | Fos                   | c = 4.000  | MHz                         | Fos                   | c = 2.000  | MHz                         | Fosc = 1.000 MHz      |            |                             |  |
| RATE<br>(K) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate<br>(K) | %<br>Error | SPBRG<br>value<br>(decimal) |  |
| 0.3         | 0.300                 | 0.01       | 3332                        | 300                   | -0.04      | 1665                        | 300                   | -0.04      | 832                         |  |
| 1.2         | 1.200                 | 0.04       | 832                         | 1201                  | -0.16      | 415                         | 1201                  | -0.16      | 207                         |  |
| 2.4         | 2.404                 | 0.16       | 415                         | 2403                  | -0.16      | 207                         | 2403                  | -0.16      | 103                         |  |
| 9.6         | 9.615                 | 0.16       | 103                         | 9615                  | -0.16      | 51                          | 9615                  | -0.16      | 25                          |  |
| 19.2        | 19.231                | 0.16       | 51                          | 19230                 | -0.16      | 25                          | 19230                 | -0.16      | 12                          |  |
| 57.6        | 58.824                | 2.12       | 16                          | 55555                 | 3.55       | 8                           | _                     | _          | _                           |  |
| 115.2       | 111.111               | -3.55      | 8                           | _                     | _          | _                           | _                     | _          | _                           |  |

#### 17.1.3 AUTO-BAUD RATE DETECT

The Enhanced USART module supports the automatic detection and calibration of baud rate. This feature is active only in Asynchronous mode and while the WUE bit is clear.

The automatic baud rate measurement sequence (Figure 17-1) begins whenever a Start bit is received and the ABDEN bit is set. The calculation is self-averaging.

In the Auto-Baud Rate Detect (ABD) mode, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RX signal, the RX signal is timing the BRG. In ABD mode, the internal Baud Rate Generator is used as a counter to time the bit period of the incoming serial byte stream.

Once the ABDEN bit is set, the state machine will clear the BRG and look for a Start bit. The Auto-Baud Rate Detect must receive a byte with the value 55h (ASCII "U", which is also the LIN bus Sync character) in order to calculate the proper bit rate. The measurement is taken over both a low and a high bit time in order to minimize any effects caused by asymmetry of the incoming signal. After a Start bit, the SPBRG begins counting up, using the preselected clock source on the first rising edge of RX. After eight bits on the RX pin or the fifth rising edge, an accumulated value totalling the proper BRG period is left in the SPBRGH:SPBRG register pair. Once the 5th edge is seen (this should correspond to the Stop bit), the ABDEN bit is automatically cleared.

If a rollover of the BRG occurs (an overflow from FFFFh to 0000h), the event is trapped by the ABDOVF status bit (BAUDCON<7>). It is set in hardware by BRG rollovers and can be set or cleared by the user in software. ABD mode remains active after rollover events and the ABDEN bit remains set (Figure 17-2).

While calibrating the baud rate period, the BRG registers are clocked at 1/8th the preconfigured clock rate. Note that the BRG clock will be configured by the BRG16 and BRGH bits. Independent of the BRG16 bit setting, both the SPBRG and SPBRGH will be used as a 16-bit counter. This allows the user to verify that no carry occurred for 8-bit modes by checking for 00h in the SPBRGH register. Refer to Table 17-4 for counter clock rates to the BRG.

While the ABD sequence takes place, the EUSART state machine is held in Idle. The RCIF interrupt is set once the fifth rising edge on RX is detected. The value in the RCREG needs to be read to clear the RCIF interrupt. The contents of RCREG should be discarded.

- Note 1: If the WUE bit is set with the ABDEN bit, Auto-Baud Rate Detection will occur on the byte *following* the Break character.
  - 2: It is up to the user to determine that the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and EUSART baud rates are not possible due to bit error rates. Overall system timing and communication baud rates must be taken into consideration when using the Auto-Baud Rate Detection feature.

TABLE 17-4: BRG COUNTER CLOCK RATES


| BRG16 | BRGH | BRG Counter Clock |
|-------|------|-------------------|
| 0     | 0    | Fosc/512          |
| 0     | 1    | Fosc/128          |
| 1     | 0    | Fosc/128          |
| 1     | 1    | Fosc/32           |

**Note:** During the ABD sequence, SPBRG and SPBRGH are both used as a 16-bit counter, independent of BRG16 setting.


## 17.1.3.1 ABD and EUSART Transmission

Since the BRG clock is reversed during ABD acquisition, the EUSART transmitter cannot be used during ABD. This means that whenever the ABDEN bit is set, TXREG cannot be written to. Users should also ensure that ABDEN does not become set during a transmit sequence. Failing to do this may result in unpredictable EUSART operation.

## FIGURE 17-1: AUTOMATIC BAUD RATE CALCULATION



## FIGURE 17-2: BRG OVERFLOW SEQUENCE



## 17.2 EUSART Asynchronous Mode

The Asynchronous mode of operation is selected by clearing the SYNC bit (TXSTA<4>). In this mode, the EUSART uses standard Non-Return-to-Zero (NRZ) format (one Start bit, eight or nine data bits and one Stop bit). The most common data format is 8 bits. An on-chip dedicated 8-bit/16-bit Baud Rate Generator can be used to derive standard baud rate frequencies from the oscillator.

The EUSART transmits and receives the LSb first. The EUSART's transmitter and receiver are functionally independent but use the same data format and baud rate. The Baud Rate Generator produces a clock, either x16 or x64 of the bit shift rate depending on the BRGH and BRG16 bits (TXSTA<2> and BAUDCON<3>). Parity is not supported by the hardware but can be implemented in software and stored as the 9th data bit.

When operating in Asynchronous mode, the EUSART module consists of the following important elements:

- · Baud Rate Generator
- · Sampling Circuit
- · Asynchronous Transmitter
- · Asynchronous Receiver
- · Auto-Wake-up on Sync Break Character
- 12-bit Break Character Transmit
- · Auto-Baud Rate Detection

## 17.2.1 EUSART ASYNCHRONOUS TRANSMITTER

The EUSART transmitter block diagram is shown in Figure 17-3. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The Shift register obtains its data from the Read/Write Transmit Buffer register, TXREG. The TXREG register is loaded with data in software. The TSR register is not loaded until the Stop bit has been transmitted from the previous load. As soon as the Stop bit is transmitted, the TSR is loaded with new data from the TXREG register (if available).

Once the TXREG register transfers the data to the TSR register (occurs in one TCY), the TXREG register is empty and the TXIF flag bit (PIR1<4>) is set. This interrupt can be enabled or disabled by setting or clearing the interrupt enable bit, TXIE (PIE1<4>). TXIF will be set regardless of the state of TXIE; it cannot be cleared in software. TXIF is also not cleared immediately upon loading TXREG, but becomes valid in the second instruction cycle following the load instruction. Polling TXIF immediately following a load of TXREG will return invalid results.

While TXIF indicates the status of the TXREG register, another bit, TRMT (TXSTA<1>), shows the status of the TSR register. TRMT is a read-only bit which is set when the TSR register is empty. No interrupt logic is tied to this bit so the user has to poll this bit in order to determine if the TSR register is empty.

- **Note 1:** The TSR register is not mapped in data memory so it is not available to the user.
  - **2:** Flag bit TXIF is set when enable bit TXEN is set.

To set up an Asynchronous Transmission:

- Initialize the SPBRGH:SPBRG registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2. Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- If interrupts are desired, set enable bit TXIE.
- If 9-bit transmission is desired, set transmit bit TX9. Can be used as address/data bit.
- 5. Enable the transmission by setting bit TXEN which will also set bit TXIF.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Load data to the TXREG register (starts transmission).
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set

FIGURE 17-3: EUSART TRANSMIT BLOCK DIAGRAM




FIGURE 17-4: ASYNCHRONOUS TRANSMISSION




FIGURE 17-5: ASYNCHRONOUS TRANSMISSION (BACK TO BACK)




TABLE 17-5: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

| Name    | Bit 7                | Bit 6  | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|----------------------|--|--------|--------|-------|--------|--------|--------|----------------------------|--|
| INTCON  | GIE/GIEH             | PEIE/GIEL                                      | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 49                         |  |
| PIR1    | PSPIF <sup>(1)</sup> | ADIF   | RCIF   | TXIF   | SSPIF | CCP1IF | TMR2IF | TMR1IF | 52                         |  |
| PIE1    | PSPIE <sup>(1)</sup> | ADIE   | RCIE   | TXIE   | SSPIE | CCP1IE | TMR2IE | TMR1IE | 52                         |  |
| IPR1    | PSPIP <sup>(1)</sup> | ADIP   | RCIP   | TXIP   | SSPIP | CCP1IP | TMR2IP | TMR1IP | 52                         |  |
| RCSTA   | SPEN                 | RX9  | SREN   | CREN   | ADDEN | FERR   | OERR   | RX9D   | 51                         |  |
| TXREG   | EUSART T             | ransmit Reg                                    | jister |        |       |        |        |        | 51                         |  |
| TXSTA   | CSRC                 | TX9  | TXEN   | SYNC   | SENDB | BRGH   | TRMT   | TX9D   | 51                         |  |
| BAUDCON | ABDOVF               | RCIDL  | _      | SCKP   | BRG16 | _      | WUE    | ABDEN  | 51                         |  |
| SPBRGH  | EUSART E             | EUSART Baud Rate Generator Register, High Byte |        |        |       |        |        |        |                            |  |
| SPBRG   | EUSART B             | JSART Baud Rate Generator Register, Low Byte   |        |        |       |        |        |        |                            |  |

**Legend:** — = unimplemented locations read as '0'. Shaded cells are not used for asynchronous transmission.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

## 17.2.2 EUSART ASYNCHRONOUS RECEIVER

The receiver block diagram is shown in Figure 17-6. The data is received on the RX pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc. This mode would typically be used in RS-232 systems.

To set up an Asynchronous Reception:

- Initialize the SPBRGH:SPBRG registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit RCIE.
- 4. If 9-bit reception is desired, set bit RX9.
- 5. Enable the reception by setting bit CREN.
- Flag bit RCIF will be set when reception is complete and an interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the 9th bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing enable bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

# 17.2.3 SETTING UP 9-BIT MODE WITH ADDRESS DETECT

This mode would typically be used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRGH:SPBRG registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2. Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If interrupts are required, set the RCEN bit and select the desired priority level with the RCIP bit.
- 4. Set the RX9 bit to enable 9-bit reception.
- 5. Set the ADDEN bit to enable address detect.
- 6. Enable reception by setting the CREN bit.
- The RCIF bit will be set when reception is complete. The interrupt will be Acknowledged if the RCIE and GIE bits are set.
- 8. Read the RCSTA register to determine if any error occurred during reception, as well as read bit 9 of data (if applicable).
- Read RCREG to determine if the device is being addressed.
- 10. If any error occurred, clear the CREN bit.
- 11. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and interrupt the CPU.

## FIGURE 17-6: EUSART RECEIVE BLOCK DIAGRAM




FIGURE 17-7: ASYNCHRONOUS RECEPTION




TABLE 17-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

| Name    | Bit 7                | Bit 6  | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|----------------------|--|--------|--------|-------|--------|--------|--------|----------------------------|--|
| INTCON  | GIE/GIEH             | PEIE/GIEL                                      | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 49                         |  |
| PIR1    | PSPIF <sup>(1)</sup> | ADIF   | RCIF   | TXIF   | SSPIF | CCP1IF | TMR2IF | TMR1IF | 52                         |  |
| PIE1    | PSPIE <sup>(1)</sup> | ADIE   | RCIE   | TXIE   | SSPIE | CCP1IE | TMR2IE | TMR1IE | 52                         |  |
| IPR1    | PSPIP <sup>(1)</sup> | ADIP   | RCIP   | TXIP   | SSPIP | CCP1IP | TMR2IP | TMR1IP | 52                         |  |
| RCSTA   | SPEN                 | RX9  | SREN   | CREN   | ADDEN | FERR   | OERR   | RX9D   | 51                         |  |
| RCREG   | EUSART R             | Receive Regi                                   | ster   |        |       |        |        |        | 51                         |  |
| TXSTA   | CSRC                 | TX9  | TXEN   | SYNC   | SENDB | BRGH   | TRMT   | TX9D   | 51                         |  |
| BAUDCON | ABDOVF               | RCIDL  |        | SCKP   | BRG16 | _      | WUE    | ABDEN  | 51                         |  |
| SPBRGH  | EUSART B             | EUSART Baud Rate Generator Register, High Byte |        |        |       |        |        |        |                            |  |
| SPBRG   | EUSART B             | USART Baud Rate Generator Register, Low Byte   |        |        |       |        |        |        |                            |  |

**Legend:** — = unimplemented locations read as '0'. Shaded cells are not used for asynchronous reception.

**Note 1:** These bits are unimplemented on 28-pin devices and read as '0'.

## 17.2.4 AUTO-WAKE-UP ON SYNC BREAK CHARACTER

During Sleep mode, all clocks to the EUSART are suspended. Because of this, the Baud Rate Generator is inactive and a proper byte reception cannot be performed. The auto-wake-up feature allows the controller to wake-up due to activity on the RX/DT line while the EUSART is operating in Asynchronous mode.

The auto-wake-up feature is enabled by setting the WUE bit (BAUDCON<1>). Once set, the typical receive sequence on RX/DT is disabled and the EUSART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a high-to-low transition on the RX/DT line. (This coincides with the start of a Sync Break or a Wake-up Signal character for the LIN protocol.)

Following a wake-up event, the module generates an RCIF interrupt. The interrupt is generated synchronously to the Q clocks in normal operating modes (Figure 17-8) and asynchronously, if the device is in Sleep mode (Figure 17-9). The interrupt condition is cleared by reading the RCREG register.

The WUE bit is automatically cleared once a low-to-high transition is observed on the RX line following the wake-up event. At this point, the EUSART module is in Idle mode and returns to normal operation. This signals to the user that the Sync Break event is over.

# 17.2.4.1 Special Considerations Using Auto-Wake-up

Since auto-wake-up functions by sensing rising edge transitions on RX/DT, information with any state changes before the Stop bit may signal a false end-of-

character and cause data or framing errors. To work properly, therefore, the initial character in the transmission must be all '0's. This can be 00h (8 bytes) for standard RS-232 devices or 000h (12 bits) for LIN bus.

Oscillator start-up time must also be considered, especially in applications using oscillators with longer start-up intervals (i.e., XT or HS mode). The Sync Break (or Wake-up Signal) character must be of sufficient length and be followed by a sufficient interval to allow enough time for the selected oscillator to start and provide proper initialization of the EUSART.


## 17.2.4.2 Special Considerations Using the WUE Bit

The timing of WUE and RCIF events may cause some confusion when it comes to determining the validity of received data. As noted, setting the WUE bit places the EUSART in an Idle mode. The wake-up event causes a receive interrupt by setting the RCIF bit. The WUE bit is cleared after this when a rising edge is seen on RX/DT. The interrupt condition is then cleared by reading the RCREG register. Ordinarily, the data in RCREG will be dummy data and should be discarded.


The fact that the WUE bit has been cleared (or is still set) and the RCIF flag is set should not be used as an indicator of the integrity of the data in RCREG. Users should consider implementing a parallel method in firmware to verify received data integrity.

To assure that no actual data is lost, check the RCIDL bit to verify that a receive operation is not in process. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.

### FIGURE 17-8: AUTO-WAKE-UP BIT (WUE) TIMINGS DURING NORMAL OPERATION



## FIGURE 17-9: AUTO-WAKE-UP BIT (WUE) TIMINGS DURING SLEEP



#### 17.2.5 BREAK CHARACTER SEQUENCE

The EUSART module has the capability of sending the special Break character sequences that are required by the LIN bus standard. The Break character transmit consists of a Start bit, followed by twelve '0' bits and a Stop bit. The frame Break character is sent whenever the SENDB and TXEN bits (TXSTA<3> and TXSTA<5>) are set while the Transmit Shift register is loaded with data. Note that the value of data written to TXREG will be ignored and all '0's will be transmitted.

The SENDB bit is automatically reset by hardware after the corresponding Stop bit is sent. This allows the user to preload the transmit FIFO with the next transmit byte following the Break character (typically, the Sync character in the LIN specification).

Note that the data value written to the TXREG for the Break character is ignored. The write simply serves the purpose of initiating the proper sequence.

The TRMT bit indicates when the transmit operation is active or Idle, just as it does during normal transmission. See Figure 17-10 for the timing of the Break character sequence.

### 17.2.5.1 Break and Sync Transmit Sequence

The following sequence will send a message frame header made up of a Break, followed by an Auto-Baud Sync byte. This sequence is typical of a LIN bus master.

- Configure the EUSART for the desired mode.
- Set the TXEN and SENDB bits to set up the Break character.
- 3. Load the TXREG with a dummy character to initiate transmission (the value is ignored).
- Write '55h' to TXREG to load the Sync character into the transmit FIFO buffer.
- After the Break has been sent, the SENDB bit is reset by hardware. The Sync character now transmits in the preconfigured mode.

When the TXREG becomes empty, as indicated by the TXIF, the next data byte can be written to TXREG.

### 17.2.6 RECEIVING A BREAK CHARACTER


The Enhanced USART module can receive a Break character in two ways.

The first method forces configuration of the baud rate at a frequency of 9/13 the typical speed. This allows for the Stop bit transition to be at the correct sampling location (13 bits for Break versus Start bit and 8 data bits for typical data).

The second method uses the auto-wake-up feature described in **Section 17.2.4** "Auto-Wake-up on Sync Break Character". By enabling this feature, the EUSART will sample the next two transitions on RX/DT, cause an RCIF interrupt and receive the next data byte followed by another interrupt.

Note that following a Break character, the user will typically want to enable the Auto-Baud Rate Detect feature. For both methods, the user can set the ABD bit once the TXIF interrupt is observed.

FIGURE 17-10: SEND BREAK CHARACTER SEQUENCE



## 17.3 EUSART Synchronous Master Mode

The Synchronous Master mode is entered by setting the CSRC bit (TXSTA<7>). In this mode, the data is transmitted in a half-duplex manner (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit SYNC (TXSTA<4>). In addition, enable bit SPEN (RCSTA<7>) is set in order to configure the TX and RX pins to CK (clock) and DT (data) lines, respectively.

The Master mode indicates that the processor transmits the master clock on the CK line. Clock polarity is selected with the SCKP bit (BAUDCON<4>); setting SCKP sets the Idle state on CK as high, while clearing the bit sets the Idle state as low. This option is provided to support Microwire devices with this module.

## 17.3.1 EUSART SYNCHRONOUS MASTER TRANSMISSION

The EUSART transmitter block diagram is shown in Figure 17-3. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The Shift register obtains its data from the Read/Write Transmit Buffer register, TXREG. The TXREG register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREG (if available).


Once the TXREG register transfers the data to the TSR register (occurs in one TCY), the TXREG is empty and the TXIF flag bit (PIR1<4>) is set. The interrupt can be enabled or disabled by setting or clearing the interrupt enable bit, TXIE (PIE1<4>). TXIF is set regardless of the state of enable bit TXIE; it cannot be cleared in software. It will reset only when new data is loaded into the TXREG register.

While flag bit TXIF indicates the status of the TXREG register, another bit, TRMT (TXSTA<1>), shows the status of the TSR register. TRMT is a read-only bit which is set when the TSR is empty. No interrupt logic is tied to this bit so the user has to poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory so it is not available to the user.

To set up a Synchronous Master Transmission:

- Initialize the SPBRGH:SPBRG registers for the appropriate baud rate. Set or clear the BRG16 bit, as required, to achieve the desired baud rate.
- 2. Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- 5. Enable the transmission by setting bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Start transmission by loading data to the TXREG register.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set

## FIGURE 17-11: SYNCHRONOUS TRANSMISSION



RC7/RX/DT pin bit 0 bit 1 bit 2 bit 6 bit 7

RC6/TX/CK pin Write to TXREG reg

TXIF bit

TXEN bit

FIGURE 17-12: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)

TABLE 17-7: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

| Name    | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|--|--|--------|--------|-------|--------|--------|--------|----------------------------|--|
| INTCON  | GIE/GIEH                                       | PEIE/GIEL                                    | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 49                         |  |
| PIR1    | PSPIF <sup>(1)</sup>                           | ADIF   | RCIF   | TXIF   | SSPIF | CCP1IF | TMR2IF | TMR1IF | 52                         |  |
| PIE1    | PSPIE <sup>(1)</sup>                           | ADIE   | RCIE   | TXIE   | SSPIE | CCP1IE | TMR2IE | TMR1IE | 52                         |  |
| IPR1    | PSPIP <sup>(1)</sup>                           | ADIP   | RCIP   | TXIP   | SSPIP | CCP1IP | TMR2IP | TMR1IP | 52                         |  |
| RCSTA   | SPEN   | RX9  | SREN   | CREN   | ADDEN | FERR   | OERR   | RX9D   | 51                         |  |
| TXREG   | EUSART T                                       | ransmit Reg                                  | ister  |        |       |        |        |        | 51                         |  |
| TXSTA   | CSRC   | TX9  | TXEN   | SYNC   | SENDB | BRGH   | TRMT   | TX9D   | 51                         |  |
| BAUDCON | ABDOVF   | RCIDL  | -      | SCKP   | BRG16 | _      | WUE    | ABDEN  | 51                         |  |
| SPBRGH  | EUSART Baud Rate Generator Register, High Byte |  |        |        |       |        |        |        |                            |  |
| SPBRG   | EUSART E                                       | USART Baud Rate Generator Register, Low Byte |        |        |       |        |        |        |                            |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for synchronous master transmission.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

## 17.3.2 EUSART SYNCHRONOUS MASTER RECEPTION

Once Synchronous mode is selected, reception is enabled by setting either the Single Receive Enable bit, SREN (RCSTA<5>), or the Continuous Receive Enable bit, CREN (RCSTA<4>). Data is sampled on the RX pin on the falling edge of the clock.


If enable bit SREN is set, only a single word is received. If enable bit CREN is set, the reception is continuous until CREN is cleared. If both bits are set, then CREN takes precedence.

To set up a Synchronous Master Reception:

- Initialize the SPBRGH:SPBRG registers for the appropriate baud rate. Set or clear the BRG16 bit, as required, to achieve the desired baud rate.
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.

- 3. Ensure bits CREN and SREN are clear.
- 4. If interrupts are desired, set enable bit RCIE.
- 5. If 9-bit reception is desired, set bit RX9.
- 6. If a single reception is required, set bit SREN. For continuous reception, set bit CREN.
- Interrupt flag bit RCIF will be set when reception is complete and an interrupt will be generated if the enable bit RCIE was set.
- Read the RCSTA register to get the 9th bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set

## FIGURE 17-13: SYNCHRONOUS RECEPTION (MASTER MODE, SREN)



## TABLE 17-8: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

| Name    | Bit 7  | Bit 6         | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values on<br>page |
|---------|--|---------------|--------|--------|-------|--------|--------|--------|----------------------------|
| INTCON  | GIE/GIEH                                       | PEIE/GIEL     | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 49                         |
| PIR1    | PSPIF <sup>(1)</sup>                           | ADIF          | RCIF   | TXIF   | SSPIF | CCP1IF | TMR2IF | TMR1IF | 52                         |
| PIE1    | PSPIE <sup>(1)</sup>                           | ADIE          | RCIE   | TXIE   | SSPIE | CCP1IE | TMR2IE | TMR1IE | 52                         |
| IPR1    | PSPIP <sup>(1)</sup>                           | ADIP          | RCIP   | TXIP   | SSPIP | CCP1IP | TMR2IP | TMR1IP | 52                         |
| RCSTA   | SPEN   | RX9           | SREN   | CREN   | ADDEN | FERR   | OERR   | RX9D   | 51                         |
| RCREG   | EUSART Re                                      | ceive Registe | r      |        |       |        |        |        | 51                         |
| TXSTA   | CSRC   | TX9           | TXEN   | SYNC   | SENDB | BRGH   | TRMT   | TX9D   | 51                         |
| BAUDCON | ABDOVF   | RCIDL         | _      | SCKP   | BRG16 | _      | WUE    | ABDEN  | 51                         |
| SPBRGH  | EUSART Baud Rate Generator Register, High Byte |               |        |        |       |        |        |        |                            |
| SPBRG   | EUSART Baud Rate Generator Register, Low Byte  |               |        |        |       |        |        |        |                            |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for synchronous master reception.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

# 17.4 EUSART Synchronous Slave Mode

Synchronous Slave mode is entered by clearing bit, CSRC (TXSTA<7>). This mode differs from the Synchronous Master mode in that the shift clock is supplied externally at the CK pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in any low-power mode.

## 17.4.1 EUSART SYNCHRONOUS SLAVE TRANSMIT

The operation of the Synchronous Master and Slave modes are identical, except in the case of the Sleep mode.

If two words are written to the TXREG and then the SLEEP instruction is executed, the following will occur:

- The first word will immediately transfer to the TSR register and transmit.
- The second word will remain in the TXREG register.
- c) Flag bit TXIF will not be set.
- d) When the first word has been shifted out of TSR, the TXREG register will transfer the second word to the TSR and flag bit TXIF will now be set.
- If enable bit TXIE is set, the interrupt will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Transmission:

- Enable the synchronous slave serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- Clear bits CREN and SREN.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- Enable the transmission by setting enable bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- Start transmission by loading data to the TXREGx register.
- 8. If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

TABLE 17-9: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

| Name    | Bit 7                | Bit 6   | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|----------------------|---|--------|--------|-------|--------|--------|--------|----------------------------|--|
| INTCON  | GIE/GIEH             | PEIE/GIEL                                     | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 49                         |  |
| PIR1    | PSPIF <sup>(1)</sup> | ADIF  | RCIF   | TXIF   | SSPIF | CCP1IF | TMR2IF | TMR1IF | 52                         |  |
| PIE1    | PSPIE <sup>(1)</sup> | ADIE  | RCIE   | TXIE   | SSPIE | CCP1IE | TMR2IE | TMR1IE | 52                         |  |
| IPR1    | PSPIP <sup>(1)</sup> | ADIP  | RCIP   | TXIP   | SSPIP | CCP1IP | TMR2IP | TMR1IP | 52                         |  |
| RCSTA   | SPEN                 | RX9   | SREN   | CREN   | ADDEN | FERR   | OERR   | RX9D   | 51                         |  |
| TXREG   | EUSART T             | ransmit Regi                                  | ister  |        |       |        |        |        | 51                         |  |
| TXSTA   | CSRC                 | TX9   | TXEN   | SYNC   | SENDB | BRGH   | TRMT   | TX9D   | 51                         |  |
| BAUDCON | ABDOVF               | RCIDL   |        | SCKP   | BRG16 | _      | WUE    | ABDEN  | 51                         |  |
| SPBRGH  | EUSART B             | USART Baud Rate Generator Register, High Byte |        |        |       |        |        |        |                            |  |
| SPBRG   | EUSART B             | USART Baud Rate Generator Register, Low Byte  |        |        |       |        |        |        |                            |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for synchronous slave transmission.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

## 17.4.2 EUSART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Slave modes is identical, except in the case of Sleep, or any Idle mode and bit SREN, which is a "don't care" in Slave mode.

If receive is enabled by setting the CREN bit prior to entering Sleep or any Idle mode, then a word may be received while in this low-power mode. Once the word is received, the RSR register will transfer the data to the RCREG register; if the RCIE enable bit is set, the interrupt generated will wake the chip from the low-power mode. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Reception:

- Enable the synchronous master serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. If interrupts are desired, set enable bit RCIE.
- 3. If 9-bit reception is desired, set bit RX9.
- 4. To enable reception, set enable bit CREN.
- Flag bit RCIF will be set when reception is complete. An interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the 9th bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- 8. If any error occurred, clear the error by clearing bit CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set

TABLE 17-10: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

| Name    | Bit 7                | Bit 6  | Bit 5  | Bit 4  | Bit 3 | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |  |
|---------|----------------------|--|--------|--------|-------|--------|--------|--------|----------------------------|--|
| INTCON  | GIE/GIEH             | PEIE/GIEL                                      | TMR0IE | INT0IE | RBIE  | TMR0IF | INT0IF | RBIF   | 49                         |  |
| PIR1    | PSPIF <sup>(1)</sup> | ADIF   | RCIF   | TXIF   | SSPIF | CCP1IF | TMR2IF | TMR1IF | 52                         |  |
| PIE1    | PSPIE <sup>(1)</sup> | ADIE   | RCIE   | TXIE   | SSPIE | CCP1IE | TMR2IE | TMR1IE | 52                         |  |
| IPR1    | PSPIP <sup>(1)</sup> | ADIP   | RCIP   | TXIP   | SSPIP | CCP1IP | TMR2IP | TMR1IP | 52                         |  |
| RCSTA   | SPEN                 | RX9  | SREN   | CREN   | ADDEN | FERR   | OERR   | RX9D   | 51                         |  |
| RCREG   | EUSART F             | Receive Regi                                   | ster   |        |       |        |        |        | 51                         |  |
| TXSTA   | CSRC                 | TX9  | TXEN   | SYNC   | SENDB | BRGH   | TRMT   | TX9D   | 51                         |  |
| BAUDCON | ABDOVF               | RCIDL  | _      | SCKP   | BRG16 | _      | WUE    | ABDEN  | 51                         |  |
| SPBRGH  | EUSART E             | EUSART Baud Rate Generator Register, High Byte |        |        |       |        |        |        |                            |  |
| SPBRG   | EUSART E             | EUSART Baud Rate Generator Register, Low Byte  |        |        |       |        |        |        |                            |  |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for synchronous slave reception.

Note 1: These bits are unimplemented on 28-pin devices and read as '0'.

# 18.0 10-BIT ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

The Analog-to-Digital (A/D) converter module has 10 inputs for the 28-pin devices and 13 for the 40/44-pin devices. This module allows conversion of an analog input signal to a corresponding 10-bit digital number.

The module has five registers:

- A/D Result High Register (ADRESH)
- A/D Result Low Register (ADRESL)
- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)
- A/D Control Register 2 (ADCON2)

The ADCON0 register, shown in Register 18-1, controls the operation of the A/D module. The ADCON1 register, shown in Register 18-2, configures the functions of the port pins. The ADCON2 register, shown in Register 18-3, configures the A/D clock source, programmed acquisition time and justification.

## REGISTER 18-1: ADCON0: A/D CONTROL REGISTER 0

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0   | R/W-0 |
|-------|-----|-------|-------|-------|-------|---------|-------|
| _     | _   | CHS3  | CHS2  | CHS1  | CHS0  | GO/DONE | ADON  |
| bit 7 |     |       |       |       |       |         | bit 0 |

bit 7-6 Unimplemented: Read as '0'

bit 5-2 CHS3:CHS0: Analog Channel Select bits

0000 = Channel 0 (AN0)

0001 = Channel 1 (AN1)

0010 = Channel 2 (AN2)

0011 = Channel 3 (AN3)

0100 = Channel 4 (AN4)

0101 = Channel 5 (AN5)(1,2)

0110 = Channel 6 (AN6)(1,2)

0111 = Channel 7 (AN7) $^{(1,2)}$ 

1000 = Channel 8 (AN8)

1001 = Channel 9 (AN9)

1010 = Channel 10 (AN10)

1011 = Channel 11 (AN11)

1100 = Channel 12 (AN12

1101 = Unimplemented<sup>(2)</sup>

1110 = Unimplemented<sup>(2)</sup>

1111 = Unimplemented<sup>(2)</sup>

Note 1: These channels are not implemented on 28-pin devices.

2: Performing a conversion on unimplemented channels will return a floating input measurement.

bit 1 GO/DONE: A/D Conversion Status bit

When ADON = 1:

1 = A/D conversion in progress

0 = A/D Idle

bit 0 ADON: A/D On bit

1 = A/D converter module is enabled 0 = A/D converter module is disabled

## Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### **ADCON1: A/D CONTROL REGISTER 1 REGISTER 18-2:**

| U-0   | U-0 | R/W-0 | R/W-0 | R/W-0 <sup>(1)</sup> | R/W <sup>(1)</sup> | R/W <sup>(1)</sup> | R/W <sup>(1)</sup> |
|-------|-----|-------|-------|----------------------|--------------------|--------------------|--------------------|
| _     | _   | VCFG1 | VCFG0 | PCFG3                | PCFG2              | PCFG1              | PCFG0              |
| bit 7 |     |       |       |                      |                    |                    | bit 0              |

bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5 VCFG1: Voltage Reference Configuration bit (VREF- source)

1 = VREF- (AN2)

0 = Vss

bit 4 **VCFG0:** Voltage Reference Configuration bit (VREF+ source)

1 = VREF+ (AN3)

0 = VDD

bit 3-0 **PCFG3:PCFG0:** A/D Port Configuration Control bits:

| PCFG3:<br>PCFG0 | AN12 | AN11 | AN10 | 6NA | AN8 | AN7 <sup>(2)</sup> | AN6 <sup>(2)</sup> | AN5 <sup>(2)</sup> | AN4 | AN3 | AN2 | AN1 | ANO |
|-----------------|------|------|------|-----|-----|--------------------|--------------------|--------------------|-----|-----|-----|-----|-----|
| 0000(1)         | Α    | Α    | Α    | Α   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0001            | Α    | Α    | Α    | Α   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0010            | Α    | Α    | Α    | Α   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0011            | D    | Α    | Α    | Α   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0100            | D    | D    | Α    | Α   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0101            | D    | D    | D    | Α   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0110            | D    | D    | D    | D   | Α   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 0111(1)         | D    | D    | D    | D   | D   | Α                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 1000            | D    | D    | D    | D   | D   | D                  | Α                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 1001            | D    | D    | D    | D   | D   | D                  | D                  | Α                  | Α   | Α   | Α   | Α   | Α   |
| 1010            | D    | D    | D    | D   | D   | D                  | D                  | D                  | Α   | Α   | Α   | Α   | Α   |
| 1011            | D    | D    | D    | D   | D   | D                  | D                  | D                  | D   | Α   | Α   | Α   | Α   |
| 1100            | D    | D    | D    | D   | D   | D                  | D                  | D                  | D   | D   | Α   | Α   | Α   |
| 1101            | D    | D    | D    | D   | D   | D                  | D                  | D                  | D   | D   | D   | Α   | Α   |
| 1110            | D    | D    | D    | D   | D   | D                  | D                  | D                  | D   | D   | D   | D   | Α   |
| 1111            | D    | D    | D    | D   | D   | D                  | D                  | D                  | D   | D   | D   | D   | D   |

A = Analog input

D = Digital I/O

- Note 1: The POR value of the PCFG bits depends on the value of the PBADEN configuration bit. When PBADEN = 1, PCFG<3:0> = 0000; when PBADEN = 0, PCFG<3:0> = 0111.
  - 2: AN5 through AN7 are available only on 40/44-pin devices.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

## REGISTER 18-3: ADCON2: A/D CONTROL REGISTER 2

| R/W-0 | U-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-------|-----|-------|-------|-------|-------|-------|-------|
| ADFM  | _   | ACQT2 | ACQT1 | ACQT0 | ADCS2 | ADCS1 | ADCS0 |

bit 7 bit 0

bit 7 ADFM: A/D Result Format Select bit

1 = Right justified0 = Left justified

bit 6 Unimplemented: Read as '0'

bit 5-3 ACQT2:ACQT0: A/D Acquisition Time Select bits

111 = 20 TAD 110 = 16 TAD 101 = 12 TAD 100 = 8 TAD 011 = 6 TAD 010 = 4 TAD 001 = 2 TAD 000 = 0 TAD<sup>(1)</sup>

bit 2-0 ADCS2:ADCS0: A/D Conversion Clock Select bits

111 = FRC (clock derived from A/D RC oscillator)(1)

110 = Fosc/64 101 = Fosc/16

101 = FOSC/10

100 = Fosc/4

011 = FRC (clock derived from A/D RC oscillator)(1)

010 = Fosc/32

001 = Fosc/8

000 = Fosc/2

**Note 1:** If the A/D FRC clock source is selected, a delay of one TCY (instruction cycle) is added before the A/D clock starts. This allows the SLEEP instruction to be executed before starting a conversion.

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

The analog reference voltage is software selectable to either the device's positive and negative supply voltage (VDD and VSS), or the voltage level on the RA3/AN3/VREF+ and RA2/AN2/VREF-/CVREF pins.


The A/D converter has a unique feature of being able to operate while the device is in Sleep mode. To operate in Sleep, the A/D conversion clock must be derived from the A/D's internal RC oscillator.

The output of the sample and hold is the input into the converter, which generates the result via successive approximation.

A device Reset forces all registers to their Reset state. This forces the A/D module to be turned off and any conversion in progress is aborted.

Each port pin associated with the A/D converter can be configured as an analog input, or as a digital I/O. The ADRESH and ADRESL registers contain the result of the A/D conversion. When the A/D conversion is complete, the result is loaded into the ADRESH: ADRESL register pair, the GO/DONE bit (ADCON0 register) is cleared and A/D Interrupt Flag bit ADIF is set. The block diagram of the A/D module is shown in Figure 18-1.

**FIGURE 18-1:** A/D BLOCK DIAGRAM



The value in the ADRESH:ADRESL registers is not modified for a Power-on Reset. The ADRESH:ADRESL registers will contain unknown data after a Power-on Reset.


After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see **Section 18.1** "A/D Acquisition Requirements". After this acquisition time has elapsed, the A/D conversion can be started. An acquisition time can be programmed to occur between setting the GO/DONE bit and the actual start of the conversion.

To perform an A/D conversion, do the following steps:


- 1. Configure the A/D module:
  - Configure analog pins, voltage reference and digital I/O (ADCON1)
  - Select A/D input channel (ADCON0)
  - Select A/D acquisition time (ADCON2)
  - Select A/D conversion clock (ADCON2)
  - Turn on A/D module (ADCON0)
- 2. Configure A/D interrupt (if desired):
  - · Clear ADIF bit
  - · Set ADIE bit
  - · Set GIE bit
- 3. Wait the required acquisition time (if required).
- 4. Start conversion:
  - Set GO/DONE bit (ADCON0 register)

- 5. Wait for A/D conversion to complete, by either:
  - Polling for the GO/DONE bit to be cleared OR
  - Waiting for the A/D interrupt
- Read A/D Result registers (ADRESH:ADRESL); clear bit ADIF, if required.
- 7. For next conversion, go to step 1 or step 2, as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2 TAD is required before the next acquisition starts.









# 18.1 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (Chold) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 18-3. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor Chold. The sampling switch (Rss) impedance varies over the device voltage (VDD). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is 2.5 k $\Omega$ . After the analog input channel is selected (changed), the channel must be sampled for at least the minimum acquisition time before starting a conversion.

**Note:** When the conversion is started, the holding capacitor is disconnected from the input pin.

To calculate the minimum acquisition time, Equation 18-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

Example 18-3 shows the calculation of the minimum required acquisition time TACQ. This calculation is based on the following application system assumptions:

 $\begin{array}{lll} \text{CHOLD} & = & 25 \text{ pF} \\ \text{Rs} & = & 2.5 \text{ k}\Omega \\ \text{Conversion Error} & \leq & 1/2 \text{ LSb} \\ \end{array}$ 

VDD =  $5V \rightarrow Rss = 2 k\Omega$ Temperature =  $85^{\circ}C$  (system max.)

#### **EQUATION 18-1: ACQUISITION TIME**

TACQ = Amplifier Settling Time + Holding Capacitor Charging Time + Temperature Coefficient

= TAMP + TC + TCOFF

#### **EQUATION 18-2: A/D MINIMUM CHARGING TIME**

```
\begin{array}{lll} V_{HOLD} & = & (V_{REF} - (V_{REF}/2048)) \bullet (1 - e^{(-T_{C}/C_{HOLD}(R_{IC} + R_{SS} + R_{S}))}) \\ \text{or} \\ T_{C} & = & -(C_{HOLD})(R_{IC} + R_{SS} + R_{S}) \ln(1/2048) \end{array}
```

#### **EQUATION 18-3: CALCULATING THE MINIMUM REQUIRED ACQUISITION TIME**

```
TACO
                    TAMP + TC + TCOFF
TAMP
                    0.2 \mu s
TCOFF
                    (Temp - 25^{\circ}C)(0.02 \mu s/^{\circ}C)
                    (85^{\circ}C - 25^{\circ}C)(0.02 \,\mu\text{s}/^{\circ}C)
                    1.2 \mu s
Temperature coefficient is only required for temperatures > 25°C. Below 25°C, TCOFF = 0 ms.
TC
                    -(CHOLD)(RIC + RSS + RS) ln(1/2047)
                    -(25 \text{ pF}) (1 \text{ k}\Omega + 2 \text{ k}\Omega + 2.5 \text{ k}\Omega) \ln(0.0004883)
                     1.05 \mu s
TACQ
                    0.2 \mu s + 1 \mu s + 1.2 \mu s
                    2.4 \mu s
```

# 18.2 Selecting and Configuring Acquisition Time

The ADCON2 register allows the user to select an acquisition time that occurs each time the GO/DONE bit is set. It also gives users the option to use an automatically determined acquisition time.

Acquisition time may be set with the ACQT2:ACQT0 bits (ADCON2<5:3>), which provides a range of 2 to 20 TAD. When the GO/DONE bit is set, the A/D module continues to sample the input for the selected acquisition time, then automatically begins a conversion. Since the acquisition time is programmed, there may be no need to wait for an acquisition time between selecting a channel and setting the GO/DONE bit.

Manual acquisition is selected when ACQT2:ACQT0 = 000. When the GO/DONE bit is set, sampling is stopped and a conversion begins. The user is responsible for ensuring the required acquisition time has passed between selecting the desired input channel and setting the GO/DONE bit. This option is also the default Reset state of the ACQT2:ACQT0 bits and is compatible with devices that do not offer programmable acquisition times.

In either case, when the conversion is completed, the GO/DONE bit is cleared, the ADIF flag is set and the A/D begins sampling the currently selected channel again. If an acquisition time is programmed, there is nothing to indicate if the acquisition time has ended or if the conversion has begun.

# 18.3 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 11 TAD per 10-bit conversion. The source of the A/D conversion clock is software selectable. There are seven possible options for TAD:

- 2 Tosc
- 4 Tosc
- 8 Tosc
- 16 Tosc
- 32 Tosc
- 64 Tosc
- · Internal RC Oscillator

For correct A/D conversions, the A/D conversion clock (TAD) must be as short as possible, but greater than the minimum TAD (see parameter 130 for more information).

Table 18-1 shows the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

TABLE 18-1: TAD vs. DEVICE OPERATING FREQUENCIES

| AD Clock S        | ource (TAD) | Maximum Device Frequency |                            |  |  |
|-------------------|-------------|--------------------------|----------------------------|--|--|
| Operation         | ADCS2:ADCS0 | PIC18FXXXX               | PIC18LFXXXX <sup>(4)</sup> |  |  |
| 2 Tosc            | 000         | 2.86 MHz                 | 1.43 kHz                   |  |  |
| 4 Tosc            | 100         | 5.71 MHz                 | 2.86 MHz                   |  |  |
| 8 Tosc            | 001         | 11.43 MHz                | 5.72 MHz                   |  |  |
| 16 Tosc           | 101         | 22.86 MHz                | 11.43 MHz                  |  |  |
| 32 Tosc           | 010         | 40.0 MHz                 | 22.86 MHz                  |  |  |
| 64 Tosc           | 110         | 40.0 MHz                 | 22.86 MHz                  |  |  |
| RC <sup>(3)</sup> | x11         | 1.00 MHz <sup>(1)</sup>  | 1.00 MHz <sup>(2)</sup>    |  |  |

- Note 1: The RC source has a typical TAD time of  $0.9 \, \mu s$ .
  - 2: The RC source has a typical TAD time of 1.2  $\mu$ s.
  - 3: For device frequencies above 1 MHz, the device must be in Sleep for the entire conversion or the A/D accuracy may be out of specification.
  - 4: Low-power (PIC18LFXXXX) devices only.

# 18.4 Operation in Power Managed Modes

The selection of the automatic acquisition time and A/D conversion clock is determined in part by the clock source and frequency while in a power managed mode.

If the A/D is expected to operate while the device is in a power managed mode, the ACQT2:ACQT0 and ADCS2:ADCS0 bits in ADCON2 should be updated in accordance with the clock source to be used in that mode. After entering the mode, an A/D acquisition or conversion may be started. Once started, the device should continue to be clocked by the same clock source until the conversion has been completed.

If desired, the device may be placed into the corresponding Idle mode during the conversion. If the device clock frequency is less than 1 MHz, the A/D RC clock source should be selected.

Operation in the Sleep mode requires the A/D FRC clock to be selected. If bits ACQT2:ACQT0 are set to '000' and a conversion is started, the conversion will be delayed one instruction cycle to allow execution of the SLEEP instruction and entry to Sleep mode. The IDLEN bit (OSCCON<7>) must have already been cleared prior to starting the conversion.

# 18.5 Configuring Analog Port Pins

The ADCON1, TRISA, TRISB and TRISE registers all configure the A/D port pins. The port pins needed as analog inputs must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS3:CHS0 bits and the TRIS bits.

- Note 1: When reading the Port register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as digital inputs will convert as analog inputs. Analog levels on a digitally configured input will be accurately converted.
  - 2: Analog levels on any pin defined as a digital input may cause the digital input buffer to consume current out of the device's specification limits.
  - **3:** The PBADEN bit in Configuration Register 3H configures PORTB pins to reset as analog or digital pins by controlling how the PCFG0 bits in ADCON1 are reset.

#### 18.6 A/D Conversions

Figure 18-4 shows the operation of the A/D converter after the GO bit has been set and the ACQT2:ACQT0 bits are cleared. A conversion is started after the following instruction to allow entry into Sleep mode before the conversion begins.

Figure 18-5 shows the operation of the A/D converter after the GO bit has been set and the ACQT2:ACQT0 bits are set to '010' and selecting a 4 TAD acquisition time before the conversion starts.

Clearing the GO/DONE bit during a conversion will abort the current conversion. The A/D Result register pair will NOT be updated with the partially completed A/D conversion sample. This means the ADRESH:ADRESL registers will continue to contain the value of the last completed conversion (or the last value written to the ADRESH:ADRESL registers).


After the A/D conversion is completed or aborted, a 2 TAD wait is required before the next acquisition can be started. After this wait, acquisition on the selected channel is automatically started.

**Note:** The GO/DONE bit should **NOT** be set in the same instruction that turns on the A/D.


# 18.7 Discharge

The discharge phase is used to initialize the value of the capacitor array. The array is discharged before every sample. This feature helps to optimize the unitygain amplifier, as the circuit always needs to charge the capacitor array, rather than charge/discharge based on previous measure values.





# FIGURE 18-5: A/D CONVERSION TAD CYCLES (ACQT<2:0> = 010, TACQ = 4 TAD)



© 2004 Microchip Technology Inc. Preliminary DS39636A-page 219

# 18.8 Use of the CCP2 Trigger

An A/D conversion can be started by the special event trigger of the CCP2 module. This requires that the CCP2M3:CCP2M0 bits (CCP2CON<3:0>) be programmed as '1011' and that the A/D module is enabled (ADON bit is set). When the trigger occurs, the GO/DONE bit will be set, starting the A/D acquisition and conversion and the Timer1 (or Timer3) counter will be reset to zero. Timer1 (or Timer3) is reset to automatically repeat the A/D acquisition period with minimal

software overhead (moving ADRESH:ADRESL to the desired location). The appropriate analog input channel must be selected and the minimum acquisition period is either timed by the user, or an appropriate TACQ time selected before the special event trigger sets the GO/DONE bit (starts a conversion).

If the A/D module is not enabled (ADON is cleared), the special event trigger will be ignored by the A/D module but will still reset the Timer1 (or Timer3) counter.

TABLE 18-2: REGISTERS ASSOCIATED WITH A/D OPERATION

| Name                 | Bit 7                 | Bit 6   | Bit 5    | Bit 4          | Bit 3              | Bit 2    | Bit 1        | Bit 0  | Reset<br>Values<br>on page |
|----------------------|-----------------------|---|----------|----------------|--------------------|----------|--------------|--------|----------------------------|
| INTCON               | GIE/GIEH              | PEIE/GIEL   | TMR0IE   | INT0IE         | RBIE               | TMR0IF   | INT0IF       | RBIF   | 49                         |
| PIR1                 | PSPIF <sup>(1)</sup>  | ADIF  | RCIF     | TXIF           | SSPIF              | CCP1IF   | TMR2IF       | TMR1IF | 52                         |
| PIE1                 | PSPIE <sup>(1)</sup>  | ADIE  | RCIE     | TXIE           | SSPIE              | CCP1IE   | TMR2IE       | TMR1IE | 52                         |
| IPR1                 | PSPIP <sup>(1)</sup>  | ADIP  | RCIP     | TXIP           | SSPIP              | CCP1IP   | TMR2IP       | TMR1IP | 52                         |
| PIR2                 | OSCFIF                | CMIF  | _        | _              | BCLIF              | HLVDIF   | TMR3IF       | CCP2IF | 52                         |
| PIE2                 | OSCFIE                | CMIE  | _        | _              | BCLIE              | HLVDIE   | TMR3IE       | CCP2IE | 52                         |
| IPR2                 | OSCFIP                | CMIP  | -        |                | BCLIP              | HLVDIP   | TMR3IP       | CCP2IP | 52                         |
| ADRESH               | A/D Result            | A/D Result Register, High Byte                          |          |                |                    |          |              |        | 51                         |
| ADRESL               | A/D Result            | Register, Lo  | w Byte   |                |                    |          |              |        | 51                         |
| ADCON0               | _                     | _   | CHS3     | CHS2           | CHS1               | CHS0     | GO/DONE      | ADON   | 51                         |
| ADCON1               | _                     | _   | VCFG1    | VCFG0          | PCFG3              | PCFG2    | PCFG1        | PCFG0  | 51                         |
| ADCON2               | ADFM                  | _   | ACQT2    | ACQT1          | ACQT0              | ADCS2    | ADCS1        | ADCS0  | 51                         |
| PORTA                | RA7 <sup>(1)</sup>    | RA6 <sup>(1)</sup>                                      | RA5      | RA4            | RA3                | RA2      | RA1          | RA0    | 52                         |
| TRISA                | TRISA7 <sup>(2)</sup> | TRISA6 <sup>(2)</sup>                                   | PORTA Da | ta Direction ( | Control Reg        | ister    |              |        | 52                         |
| PORTB                | RB7                   | RB6   | RB5      | RB4            | RB3                | RB2      | RB1          | RB0    | 52                         |
| TRISB                | PORTB Dat             | PORTB Data Direction Control Register                   |          |                |                    |          |              |        | 52                         |
| LATB                 | PORTB Dat             | ORTB Data Latch Register (Read and Write to Data Latch) |          |                |                    |          |              |        |                            |
| PORTE <sup>(4)</sup> | _                     | _   | _        | _              | RE3 <sup>(3)</sup> | RE2      | RE1          | RE0    | 52                         |
| TRISE <sup>(4)</sup> | IBF                   | OBF   | IBOV     | PSPMODE        | _                  | TRISE2   | TRISE1       | TRISE0 | 52                         |
| LATE <sup>(4)</sup>  | _                     | _   | _        | _              | _                  | PORTE Da | ita Latch Re | gister | 52                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for A/D conversion.

Note 1: These bits are unimplemented on 28-pin devices; always maintain these bits clear.

- 2: PORTA<7:6> and their direction bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.
- 3: RE3 port bit is available only as an input pin when the MCLRE configuration bit is '0'.
- 4: These registers are not implemented on 28-pin devices.

# 19.0 COMPARATOR MODULE

The analog comparator module contains two comparators that can be configured in a variety of ways. The inputs can be selected from the analog inputs multiplexed with pins RAO through RA5, as well as the on-chip voltage reference (see **Section 20.0 "Comparator Voltage Reference Module"**). The digital outputs (normal or inverted) are available at the pin level and can also be read through the control register.

The CMCON register (Register 19-1) selects the comparator input and output configuration. Block diagrams of the various comparator configurations are shown in Figure 19-1.

#### REGISTER 19-1: CMCON: COMPARATOR CONTROL REGISTER

| R-0   | R-0   | R/W-0 | R/W-0 | R/W-0 | R/W-1 | R/W-1 | R/W-1 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| C2OUT | C1OUT | C2INV | C1INV | CIS   | CM2   | CM1   | CM0   |
| bit 7 |       |       |       |       |       |       | bit 0 |

bit 7 C2OUT: Comparator 2 Output bit

When C2INV = 0:

1 = C2 VIN+ > C2 VIN-

0 = C2 VIN+ < C2 VIN-

When C2INV =  $\underline{1}$ :

1 = C2 VIN+ < C2 VIN-

0 = C2 VIN+ > C2 VIN-

bit 6 C10UT: Comparator 1 Output bit

When C1INV = 0:

1 = C1 VIN+ > C1 VIN-

0 = C1 VIN+ < C1 VIN-

When C1INV =  $\underline{1}$ :

1 = C1 VIN+ < C1 VIN-

0 = C1 VIN+ > C1 VIN-

bit 5 C2INV: Comparator 2 Output Inversion bit

1 = C2 output inverted

0 = C2 output not inverted

bit 4 C1INV: Comparator 1 Output Inversion bit

1 = C1 output inverted

0 = C1 output not inverted

bit 3 CIS: Comparator Input Switch bit

When CM2:CM0 = 110:

1 = C1 VIN+ connects to RA3/AN3/VREF+

C2 VIN+ connects to RA2/AN2/VREF-/CVREF

0 = C1 VIN- connects to RA0/AN0

C2 VIN- connects to RA1/AN1

bit 2-0 CM2:CM0: Comparator Mode bits

Figure 19-1 shows the Comparator modes and the CM2:CM0 bit settings.

| Legend:           |                  |   |  |
|-------------------|------------------|---|--|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read as '0'        |  |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared $x = Bit$ is unknown |  |


# 19.1 Comparator Configuration

There are eight modes of operation for the comparators, shown in Figure 19-1. Bits CM2:CM0 of the CMCON register are used to select these modes. The TRISA register controls the data direction of the comparator pins for each mode. If the Comparator mode is

changed, the comparator output level may not be valid for the specified mode change delay shown in **Section 25.0 "Electrical Characteristics"**.

**Note:** Comparator interrupts should be disabled during a Comparator mode change; otherwise, a false interrupt may occur.

#### FIGURE 19-1: COMPARATOR I/O OPERATING MODES




# 19.2 Comparator Operation

A single comparator is shown in Figure 19-2, along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 19-2 represent the uncertainty, due to input offsets and response time.

# 19.3 Comparator Reference

Depending on the comparator operating mode, either an external or internal voltage reference may be used. The analog signal present at VIN- is compared to the signal at VIN+ and the digital output of the comparator is adjusted accordingly (Figure 19-2).

FIGURE 19-2: SINGLE COMPARATOR



#### 19.3.1 EXTERNAL REFERENCE SIGNAL

When external voltage references are used, the comparator module can be configured to have the comparators operate from the same or different reference sources. However, threshold detector applications may require the same reference. The reference signal must be between VSS and VDD and can be applied to either pin of the comparator(s).

#### 19.3.2 INTERNAL REFERENCE SIGNAL

The comparator module also allows the selection of an internally generated voltage reference from the comparator voltage reference module. This module is described in more detail in **Section 20.0 "Comparator Voltage Reference Module"**.

The internal reference is only available in the mode where four inputs are multiplexed to two comparators (CM2:CM0 = 110). In this mode, the internal voltage reference is applied to the Vin+ pin of both comparators.

# 19.4 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output has a valid level. If the internal reference is changed, the maximum delay of the internal voltage reference must be considered when using the comparator outputs. Otherwise, the maximum delay of the comparators should be used (see Section 25.0 "Electrical Characteristics").

# 19.5 Comparator Outputs


The comparator outputs are read through the CMCON register. These bits are read-only. The comparator outputs may also be directly output to the RA4 and RA5 I/O pins. When enabled, multiplexors in the output path of the RA4 and RA5 pins will switch and the output of each pin will be the unsynchronized output of the comparator. The uncertainty of each of the comparators is related to the input offset voltage and the response time given in the specifications. Figure 19-3 shows the comparator output block diagram.

The TRISA bits will still function as an output enable/ disable for the RA4 and RA5 pins while in this mode.

The polarity of the comparator outputs can be changed using the C2INV and C1INV bits (CMCON<4:5>).

- Note 1: When reading the Port register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert an analog input according to the Schmitt Trigger input specification.
  - **2:** Analog levels on any pin defined as a digital input may cause the input buffer to consume more current than is specified.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 223



#### FIGURE 19-3: COMPARATOR OUTPUT BLOCK DIAGRAM

# 19.6 Comparator Interrupts

The comparator interrupt flag is set whenever there is a change in the output value of either comparator. Software will need to maintain information about the status of the output bits, as read from CMCON<7:6>, to determine the actual change that occurred. The CMIF bit (PIR2<6>) is the Comparator Interrupt Flag. The CMIF bit must be reset by clearing it. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

Both the CMIE bit (PIE2<6>) and the PEIE bit (INTCON<6>) must be set to enable the interrupt. In addition, the GIE bit (INTCON<7>) must also be set. If any of these bits are clear, the interrupt is not enabled, though the CMIF bit will still be set if an interrupt condition occurs.

Note: If a change in the CMCON register (C1OUT or C2OUT) should occur when a read operation is being executed (start of the Q2 cycle), then the CMIF (PIR registers) interrupt flag may not get set.

The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- Any read or write of CMCON will end the mismatch condition.
- b) Clear flag bit CMIF.

A mismatch condition will continue to set flag bit CMIF. Reading CMCON will end the mismatch condition and allow flag bit CMIF to be cleared.

# 19.7 Comparator Operation During Sleep

When a comparator is active and the device is placed in Sleep mode, the comparator remains active and the interrupt is functional if enabled. This interrupt will wake-up the device from Sleep mode, when enabled. Each operational comparator will consume additional current, as shown in the comparator specifications. To minimize power consumption while in Sleep mode, turn off the comparators (CM2:CM0 = 111) before entering Sleep. If the device wakes up from Sleep, the contents of the CMCON register are not affected.

### 19.8 Effects of a Reset

A device Reset forces the CMCON register to its Reset state, causing the comparator modules to be turned off (CM2:CM0 = 111). However, the input pins (RA0 through RA3) are configured as analog inputs by default on device Reset. The I/O configuration for these pins is determined by the setting of the PCFG3:PCFG0 bits (ADCON1<3:0>). Therefore, device current is minimized when analog inputs are present at Reset time

# 19.9 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 19-4. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this

range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up condition may occur. A maximum source impedance of 10  $k\Omega$  is recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.

FIGURE 19-4: COMPARATOR ANALOG INPUT MODEL




TABLE 19-1: REGISTERS ASSOCIATED WITH COMPARATOR MODULE

| Name   | Bit 7                 | Bit 6                 | Bit 5  | Bit 4        | Bit 3      | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on page |
|--------|-----------------------|-----------------------|--|--------------|------------|--------|--------|--------|----------------------------|
| CMCON  | C2OUT                 | C10UT                 | C2INV  | C1INV        | CIS        | CM2    | CM1    | CM0    | 51                         |
| CVRCON | CVREN                 | CVROE                 | CVRR   | CVRSS        | CVR3       | CVR2   | CVR1   | CVR0   | 51                         |
| INTCON | GIE/GIEH              | PEIE/GIEL             | TMR0IE   | INT0IE       | RBIE       | TMR0IF | INT0IF | RBIF   | 52                         |
| PIR2   | OSCFIF                | CMIF                  | _  | _            | BCLIF      | HLVDIF | TMR3IF | CCP2IF | 52                         |
| PIE2   | OCSFIE                | CMIE                  | _  | _            | BCLIE      | HLVDIE | TMR3IE | CCP2IE | 52                         |
| IPR2   | OSCFIP                | CMIP                  | _  | _            | BCLIP      | HLVDIP | TMR3IP | CCP2IP | 52                         |
| PORTA  | RA7 <sup>(1)</sup>    | RA6 <sup>(1)</sup>    | RA5  | RA4          | RA3        | RA2    | RA1    | RA0    | 52                         |
| LATA   | LATA7 <sup>(1)</sup>  | LATA6 <sup>(1)</sup>  | PORTA Data Latch Register (Read and Write to Data Latch) |              |            |        |        |        | 52                         |
| TRISA  | TRISA7 <sup>(1)</sup> | TRISA6 <sup>(1)</sup> | PORTA Da   | ta Direction | Control Re | gister |        |        | 52                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are unused by the comparator module.

**Note 1:** PORTA<7:6> and their direction and latch bits are individually configured as port pins based on various primary oscillator modes. When disabled, these bits read as '0'.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 225

NOTES:

# 20.0 COMPARATOR VOLTAGE REFERENCE MODULE

The comparator voltage reference is a 16-tap resistor ladder network that provides a selectable reference voltage. Although its primary purpose is to provide a reference for the analog comparators, it may also be used independently of them.

A block diagram of the module is shown in Figure 20-1. The resistor ladder is segmented to provide two ranges of CVREF values and has a power-down function to conserve power when the reference is not being used. The module's supply reference can be provided from either device VDD/VSS or an external voltage reference.

# 20.1 Configuring the Comparator Voltage Reference

The voltage reference module is controlled through the CVRCON register (Register 20-1). The comparator voltage reference provides two ranges of output voltage, each with 16 distinct levels. The range to be

used is selected by the CVRR bit (CVRCON<5>). The primary difference between the ranges is the size of the steps selected by the CVREF selection bits (CVR3:CVR0), with one range offering finer resolution. The equations used to calculate the output of the comparator voltage reference are as follows:

If CVRR = 1:

CVREF = ((CVR3:CVR0)/24) x CVRSRC

If CVRR = 0:

CVREF = (CVRSRC x 1/4) + (((CVR3:CVR0)/32) x CVRSRC)

The comparator reference supply voltage can come from either VDD and Vss, or the external VREF+ and VREF+ that are multiplexed with RA2 and RA3. The voltage source is selected by the CVRSS bit (CVRCON<4>).

The settling time of the comparator voltage reference must be considered when changing the CVREF output (see Table 25-3 in **Section 25.0 "Electrical Characteristics"**).

# REGISTER 20-1: CVRCON: COMPARATOR VOLTAGE REFERENCE CONTROL REGISTER

| R/W-0 | R/W-0                | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 | R/W-0 |
|-------|----------------------|-------|-------|-------|-------|-------|-------|
| CVREN | CVROE <sup>(1)</sup> | CVRR  | CVRSS | CVR3  | CVR2  | CVR1  | CVR0  |
| bit 7 |                      |       |       |       |       |       | bit 0 |

bit 7 CVREN: Comparator Voltage Reference Enable bit

1 = CVREF circuit powered on

0 = CVREF circuit powered down

bit 6 **CVROE**: Comparator VREF Output Enable bit<sup>(1)</sup>

1 = CVREF voltage level is also output on the RA2/AN2/VREF-/CVREF pin

0 = CVREF voltage is disconnected from the RA2/AN2/VREF-/CVREF pin

Note 1: CVROE overrides the TRISA<2> bit setting.

bit 5 CVRR: Comparator VREF Range Selection bit

1 = 0 to 0.667 CVRSRC, with CVRSRC/24 step size (low range)

0 = 0.25 CVRSRC to 0.75 CVRSRC, with CVRSRC/32 step size (high range)

bit 4 CVRSS: Comparator VREF Source Selection bit

1 = Comparator reference source, CVRSRC = (VREF+) - (VREF-)

0 = Comparator reference source, CVRSRC = VDD - VSS

bit 3-0 **CVR3:CVR0:** Comparator VREF Value Selection bits  $(0 \le (CVR3:CVR0) \le 15)$ 

When CVRR = 1:

CVREF = ((CVR3:CVR0)/24) • (CVRSRC)

When CVRR = 0:

CVREF = (CVRSRC/4) + ((CVR3:CVR0)/32) • (CVRSRC)

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | l bit, read as '0' |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |




FIGURE 20-1: COMPARATOR VOLTAGE REFERENCE BLOCK DIAGRAM

# 20.2 Voltage Reference Accuracy/Error

The full range of voltage reference cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (Figure 20-1) keep CVREF from approaching the reference source rails. The voltage reference is derived from the reference source; therefore, the CVREF output changes with fluctuations in that source. The tested absolute accuracy of the voltage reference can be found in **Section 25.0** "Electrical Characteristics".

# 20.3 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the CVRCON register are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

#### 20.4 Effects of a Reset

A device Reset disables the voltage reference by clearing bit CVREN (CVRCON<7>). This Reset also disconnects the reference from the RA2 pin by clearing bit CVROE (CVRCON<6>) and selects the high-voltage range by clearing bit CVRR (CVRCON<5>). The CVR value select bits are also cleared.

#### 20.5 Connection Considerations

The voltage reference module operates independently of the comparator module. The output of the reference generator may be connected to the RA2 pin if the CVROE bit is set. Enabling the voltage reference output onto RA2 when it is configured as a digital input will increase current consumption. Connecting RA2 as a digital output with CVRSS enabled will also increase current consumption.

The RA2 pin can be used as a simple D/A output with limited drive capability. Due to the limited current drive capability, a buffer must be used on the voltage reference output for external connections to VREF. Figure 20-2 shows an example buffering technique.

# FIGURE 20-2: COMPARATOR VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE




TABLE 20-1: REGISTERS ASSOCIATED WITH COMPARATOR VOLTAGE REFERENCE

| Name   | Bit 7                 | Bit 6                 | Bit 5   | Bit 4                                | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Reset<br>Values<br>on page |  |
|--------|-----------------------|-----------------------|---------|--------------------------------------|-------|-------|-------|-------|----------------------------|--|
| CVRCON | CVREN                 | CVROE                 | CVRR    | CVRSS                                | CVR3  | CVR2  | CVR1  | CVR0  | 51                         |  |
| CMCON  | C2OUT                 | C1OUT                 | C2INV   | C1INV                                | CIS   | CM2   | CM1   | CM0   | 51                         |  |
| TRISA  | TRISA7 <sup>(1)</sup> | TRISA6 <sup>(1)</sup> | PORTA D | ORTA Data Direction Control Register |       |       |       |       |                            |  |

Legend: Shaded cells are not used with the comparator voltage reference.

Note 1: PORTA pins are enabled based on oscillator configuration.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 229

NOTES:

# 21.0 HIGH/LOW-VOLTAGE DETECT (HLVD)

PIC18F2X1X/4X1X devices have a High/Low-Voltage Detect module (HLVD). This is a programmable circuit that allows the user to specify both a device voltage trip point and the direction of change from that point. If the device experiences an excursion past the trip point in that direction, an interrupt flag is set. If the interrupt is enabled, the program execution will branch to the interrupt vector address and the software can then respond to the interrupt.

The High/Low-Voltage Detect Control register (Register 21-1) completely controls the operation of the HLVD module. This allows the circuitry to be "turned off" by the user under software control, which minimizes the current consumption for the device.

The block diagram for the HLVD module is shown in Figure 21-1.

### REGISTER 21-1: HLVDCON: HIGH/LOW-VOLTAGE DETECT CONTROL REGISTER

| R/W-0   | U-0 | R-0   | R/W-0  | R/W-0  | R/W-1  | R/W-0  | R/W-1  |
|---------|-----|-------|--------|--------|--------|--------|--------|
| VDIRMAG | _   | IRVST | HLVDEN | HLVDL3 | HLVDL2 | HLVDL1 | HLVDL0 |
| hit 7   |     |       |        |        |        |        | hit 0  |

- bit 7 VDIRMAG: Voltage Direction Magnitude Select bit
  - 1 = Event occurs when voltage equals or exceeds trip point (HLVDL3:HLDVL0)
  - 0 = Event occurs when voltage equals or falls below trip point (HLVDL3:HLVDL0)
- bit 6 Unimplemented: Read as '0'
- bit 5 IRVST: Internal Reference Voltage Stable Flag bit
  - 1 = Indicates that the voltage detect logic will generate the interrupt flag at the specified voltage range
  - 0 = Indicates that the voltage detect logic will not generate the interrupt flag at the specified voltage range and the HLVD interrupt should not be enabled
- bit 4 **HLVDEN:** High/Low-Voltage Detect Power Enable bit
  - 1 = HLVD enabled
  - 0 = HLVD disabled
- bit 3-0 HLVDL3:HLVDL0: Voltage Detection Limit bits
  - 1111 = External analog input is used (input comes from the HLVDIN pin)
  - 1110 = Maximum setting

•

•

0000 = Minimum setting

Note: See Table 25-4 in Section 25.0 "Electrical Characteristics" for the specifications.

| Legend:           |                  |                      |                    |
|-------------------|------------------|----------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented    | bit, read as '0'   |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared | x = Bit is unknown |

The module is enabled by setting the HLVDEN bit. Each time that the HLVD module is enabled, the circuitry requires some time to stabilize. The IRVST bit is a read-only bit and is used to indicate when the circuit is stable. The module can only generate an interrupt after the circuit is stable and IRVST is set.

The VDIRMAG bit determines the overall operation of the module. When VDIRMAG is cleared, the module monitors for drops in VDD below a predetermined set point. When the bit is set, the module monitors for rises in VDD above the set point.

# 21.1 Operation


When the HLVD module is enabled, a comparator uses an internally generated reference voltage as the set point. The set point is compared with the trip point, where each node in the resistor divider represents a trip point voltage. The "trip point" voltage is the voltage level at which the device detects a high or low-voltage

event, depending on the configuration of the module. When the supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal by setting the HLVDIF bit.

The trip point voltage is software programmable to any one of 16 values. The trip point is selected by programming the HLVDL3:HLVDL0 bits (HLVDCON<3:0>).

The HLVD module has an additional feature that allows the user to supply the trip voltage to the module from an external source. This mode is enabled when bits HLVDL3:HLVDL0 are set to '1111'. In this state, the comparator input is multiplexed from the external input pin, HLVDIN. This gives users flexibility because it allows them to configure the High/Low-Voltage Detect interrupt to occur at any voltage in the valid operating range.

FIGURE 21-1: HLVD MODULE BLOCK DIAGRAM (WITH EXTERNAL INPUT)



### 21.2 HLVD Setup

The following steps are needed to set up the HLVD module:

- 1. Disable the module by clearing the HLVDEN bit (HLVDCON<4>).
- 2. Write the value to the HLVDL3:HLVDL0 bits that selects the desired HLVD trip point.
- Set the VDIRMAG bit to detect high voltage (VDIRMAG = 1) or low voltage (VDIRMAG = 0).
- 4. Enable the HLVD module by setting the HLVDEN bit.
- 5. Clear the HLVD interrupt flag (PIR2<2>), which may have been set from a previous interrupt.
- 6. Enable the HLVD interrupt if interrupts are desired by setting the HLVDIE and GIE bits (PIE<2> and INTCON<7>). An interrupt will not be generated until the IRVST bit is set.

#### **Current Consumption** 21.3

When the module is enabled, the HLVD comparator and voltage divider are enabled and will consume static current. The total current consumption, when enabled, is specified in electrical specification parameter D022B.

Depending on the application, the HLVD module does not need to be operating constantly. To decrease the current requirements, the HLVD circuitry may only need to be enabled for short periods where the voltage is checked. After doing the check, the HLVD module may be disabled.

#### 21.4 **HLVD Start-up Time**

The internal reference voltage of the HLVD module, specified in electrical specification parameter D420. may be used by other internal circuitry, such as the Programmable Brown-out Reset. If the HLVD or other circuits using the voltage reference are disabled to lower the device's current consumption, the reference voltage circuit will require time to become stable before a low or high-voltage condition can be reliably detected. This start-up time, TIRVST, is an interval that is independent of device clock speed. It is specified in electrical specification parameter 36.


The HLVD interrupt flag is not enabled until TIRVST has expired and a stable reference voltage is reached. For this reason, brief excursions beyond the set point may not be detected during this interval. Refer to Figure 21-2 or Figure 21-3.

**FIGURE 21-2: LOW-VOLTAGE DETECT OPERATION (VDIRMAG = 0)** CASE 1: HLVDIF may not be set Vpp -HLVDIF Enable HLVD IRVST ----HI VDIF cleared in software Internal Reference is stable CASE 2: HLVDIF \_\_ Enable HLVD TIVRST \_ IRVST \_ Internal Reference is stable -

HLVDIF cleared in software

HLVDIF remains set since HLVD condition still exists

HLVDIF cleared in software,




**FIGURE 21-3: HIGH-VOLTAGE DETECT OPERATION (VDIRMAG = 1)** 

#### 21.5 **Applications**

In many applications, the ability to detect a drop below or rise above a particular threshold is desirable. For example, the HLVD module could be periodically enabled to detect a Universal Serial Bus (USB) attach or detach. This assumes the device is powered by a lower voltage source than the USB when detached. An attach would indicate a high-voltage detect from, for example, 3.3V to 5V (the voltage on USB) and vice versa for a detach. This feature could save a design a few extra components and an attach signal (input pin).

For general battery applications, Figure 21-4 shows a possible voltage curve. Over time, the device voltage decreases. When the device voltage reaches voltage VA, the HLVD logic generates an interrupt at time TA. The interrupt could cause the execution of an ISR, which would allow the application to perform "housekeeping tasks" and perform a controlled shutdown before the device voltage exits the valid operating range at TB. The HLVD thus would give the application a time window, represented by the difference between TA and TB, to safely exit.

**TYPICAL FIGURE 21-4:** HIGH/LOW-VOLTAGE **DETECT APPLICATION** 



# 21.6 Operation During Sleep

When enabled, the HLVD circuitry continues to operate during Sleep. If the device voltage crosses the trip point, the HLVDIF bit will be set and the device will wake-up from Sleep. Device execution will continue from the interrupt vector address if interrupts have been globally enabled.

#### 21.7 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the HLVD module to be turned off.

TABLE 21-1: REGISTERS ASSOCIATED WITH HIGH/LOW-VOLTAGE DETECT MODULE

| Name    | Bit 7    | Bit 6     | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Reset<br>Values<br>on Page |
|---------|----------|-----------|--------|--------|--------|--------|--------|--------|----------------------------|
| HLVDCON | VDIRMAG  | _         | IRVST  | HLVDEN | HLVDL3 | HLVDL2 | HLVDL1 | HLVDL0 | 50                         |
| INTCON  | GIE/GIEH | PEIE/GIEL | TMR0IE | INT0IE | RBIE   | TMR0IF | INT0IF | RBIF   | 49                         |
| PIR2    | OSCFIF   | CMIF      | _      | _      | BCLIF  | HLVDIF | TMR3IF | CCP2IF | 52                         |
| PIE2    | OCSFIE   | CMIE      | -      | _      | BCLIE  | HLVDIE | TMR3IE | CCP2IE | 52                         |
| IPR2    | OSCFIP   | CMIP      | _      | _      | BCLIP  | HLVDIP | TMR3IP | CCP2IP | 52                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are unused by the HLVD module.

NOTES:

# 22.0 SPECIAL FEATURES OF THE CPU

PIC18F2X1X/4X1X devices include several features intended to maximize reliability and minimize cost through elimination of external components. These are:

- · Oscillator Selection
- Resets:
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Brown-out Reset (BOR)
- Interrupts
- · Watchdog Timer (WDT)
- · Fail-Safe Clock Monitor
- Two-Speed Start-up
- Code Protection
- ID Locations
- · In-Circuit Serial Programming

The oscillator can be configured for the application depending on frequency, power, accuracy and cost. All of the options are discussed in detail in **Section 2.0** "Oscillator Configurations".

A complete discussion of device Resets and interrupts is available in previous sections of this data sheet.

In addition to their Power-up and Oscillator Start-up Timers provided for Resets, PIC18F2X1X/4X1X devices have a Watchdog Timer, which is either permanently enabled via the configuration bits or software controlled (if configured as disabled).

The inclusion of an internal RC oscillator also provides the additional benefits of a Fail-Safe Clock Monitor (FSCM) and Two-Speed Start-up. FSCM provides for background monitoring of the peripheral clock and automatic switchover in the event of its failure. Two-Speed Start-up enables code to be executed almost immediately on start-up, while the primary clock source completes its start-up delays.

All of these features are enabled and configured by setting the appropriate configuration register bits.

# 22.1 Configuration Bits

The configuration bits can be programmed (read as '0') or left unprogrammed (read as '1') to select various device configurations. These bits are mapped starting at program memory location 300000h.

The user will note that address 300000h is beyond the user program memory space. In fact, it belongs to the configuration memory space (300000h-3FFFFFh), which can only be accessed using table reads.

TABLE 22-1: CONFIGURATION BITS AND DEVICE IDs

| File Name |                       | Bit 7 | Bit 6 | Bit 5 | Bit 4  | Bit 3                  | Bit 2                | Bit 1  | Bit 0  | Default/<br>Unprogrammed<br>Value |
|-----------|-----------------------|-------|-------|-------|--------|------------------------|----------------------|--------|--------|-----------------------------------|
| 300001h   | CONFIG1H              | IESO  | FCMEN | _     | _      | FOSC3                  | FOSC2                | FOSC1  | FOSC0  | 00 0111                           |
| 300002h   | CONFIG2L              | _     | _     | _     | BORV1  | BORV0                  | BOREN1               | BOREN0 | PWRTEN | 1 1111                            |
| 300003h   | CONFIG2H              | _     | _     | _     | WDTPS3 | WDTPS2                 | WDTPS1               | WDTPS0 | WDTEN  | 1 1111                            |
| 300005h   | CONFIG3H              | MCLRE | _     | _     | _      | _                      | LPT10SC              | PBADEN | CCP2MX | 1011                              |
| 300006h   | CONFIG4L              | DEBUG | XINST | _     | _      | _                      | LVP                  | _      | STVREN | 101-1                             |
| 300008h   | CONFIG5L              | _     | _     | _     | _      | CP3 <sup>(1,2)</sup>   | CP2 <sup>(1)</sup>   | CP1    | CP0    | 1111                              |
| 300009h   | CONFIG5H              | _     | СРВ   | _     | _      | _                      | _                    | _      | _      | -1                                |
| 30000Ah   | CONFIG6L              | _     | _     | _     | _      | WRT3 <sup>(1,2)</sup>  | WRT2 <sup>(1)</sup>  | WRT1   | WRT0   | 1111                              |
| 30000Bh   | CONFIG6H              | _     | WRTB  | WRTC  | _      | _                      | _                    | _      | _      | -11                               |
| 30000Ch   | CONFIG7L              | _     | _     | _     | _      | EBTR3 <sup>(1,2)</sup> | EBTR2 <sup>(1)</sup> | EBTR1  | EBTR0  | 1111                              |
| 30000Dh   | CONFIG7H              | _     | EBTRB | _     | _      | _                      | _                    | _      | _      | -1                                |
| 3FFFEh    | DEVID1 <sup>(3)</sup> | DEV2  | DEV1  | DEV0  | REV4   | REV3                   | REV2                 | REV1   | REV0   | xxxx xxxx(3)                      |
| 3FFFFFh   | DEVID2(3)             | DEV10 | DEV9  | DEV8  | DEV7   | DEV6                   | DEV5                 | DEV4   | DEV3   | 0000 1100                         |

**Legend:** x = unknown, u = unchanged, --= unimplemented, q = value depends on condition. Shaded cells are unimplemented, read as '0'.

- Note 1: Unimplemented in PIC18F2410/4410 devices; maintain this bit set.
  - 2: Unimplemented in PIC18F2515/4515 devices, maintain this bit set.
  - 3: See Register 22-14 for DEVID1 values. DEVID registers are read-only and cannot be programmed by the user.

## REGISTER 22-1: CONFIG1H: CONFIGURATION REGISTER 1 HIGH (BYTE ADDRESS 300001h)

| R/P-0 | R/P-0 | U-0 | U-0 | R/P-0 | R/P-1 | R/P-1 | R/P-1 |
|-------|-------|-----|-----|-------|-------|-------|-------|
| IESO  | FCMEN | _   | _   | FOSC3 | FOSC2 | FOSC1 | FOSC0 |
| bit 7 |       |     |     |       |       |       | bit 0 |

bit 7 IESO: Internal/External Oscillator Switchover bit

1 = Oscillator Switchover mode enabled

0 = Oscillator Switchover mode disabled

bit 6 FCMEN: Fail-Safe Clock Monitor Enable bit

1 = Fail-Safe Clock Monitor enabled

0 = Fail-Safe Clock Monitor disabled

bit 5-4 Unimplemented: Read as '0'

bit 3-0 FOSC3:FOSC0: Oscillator Selection bits

11xx = External RC oscillator, CLKO function on RA6

101x = External RC oscillator, CLKO function on RA6

1001 = Internal oscillator block, CLKO function on RA6, port function on RA7

1000 = Internal oscillator block, port function on RA6 and RA7

0111 = External RC oscillator, port function on RA6

0110 = HS oscillator, PLL enabled (Clock Frequency = 4 x FOSC1)

0101 = EC oscillator, port function on RA6

0100 = EC oscillator, CLKO function on RA6

0011 = External RC oscillator, CLKO function on RA6

0010 = HS oscillator

0001 = XT oscillator

0000 = LP oscillator

#### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'

-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 22-2: CONFIG2L: CONFIGURATION REGISTER 2 LOW (BYTE ADDRESS 300002h)

| U-0   | U-0 | U-0 | R/P-1                | R/P-1                | R/P-1                 | R/P-1                 | R/P-1                 |
|-------|-----|-----|----------------------|----------------------|-----------------------|-----------------------|-----------------------|
| _     | 1   | _   | BORV1 <sup>(1)</sup> | BORV0 <sup>(1)</sup> | BOREN1 <sup>(2)</sup> | BOREN0 <sup>(2)</sup> | PWRTEN <sup>(2)</sup> |
| bit 7 |     |     |                      |                      |                       |                       | bit 0                 |

bit 7-5 **Unimplemented:** Read as '0'

bit 4-3 BORV1:BORV0: Brown-out Reset Voltage bits<sup>(1)</sup>

11 = Minimum setting

.

00 = Maximum setting

bit 2-1 BOREN1:BOREN0: Brown-out Reset Enable bits<sup>(2)</sup>

- 11 = Brown-out Reset enabled in hardware only (SBOREN is disabled)
- 10 = Brown-out Reset enabled in hardware only and disabled in Sleep mode (SBOREN is disabled)
- 01 = Brown-out Reset enabled and controlled by software (SBOREN is enabled)
- 00 = Brown-out Reset disabled in hardware and software
- bit 0 **PWRTEN**: Power-up Timer Enable bit<sup>(2)</sup>
  - 1 = PWRT disabled
  - 0 = PWRT enabled

Note 1: See Section 25.1 "DC Characteristics" for the specifications.

**2:** The Power-up Timer is decoupled from Brown-out Reset, allowing these features to be independently controlled.

#### Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$  $-n = Value \ when \ device is unprogrammed <math>u = Unchanged \ from \ programmed \ state$ 

# REGISTER 22-3: CONFIG2H: CONFIGURATION REGISTER 2 HIGH (BYTE ADDRESS 300003h)

| U-0   | U-0 | U-0 | R/P-1  | R/P-1  | R/P-1  | R/P-1  | R/P-1 |
|-------|-----|-----|--------|--------|--------|--------|-------|
| _     | _   | _   | WDTPS3 | WDTPS2 | WDTPS1 | WDTPS0 | WDTEN |
| bit 7 |     |     |        |        |        |        | bit 0 |

#### bit 7-5 Unimplemented: Read as '0'

# bit 4-1 WDTPS3:WDTPS0: Watchdog Timer Postscale Select bits

```
1111 = 1:32,768
1110 = 1:16,384
1101 = 1:8,192
1100 = 1:4,096
1011 = 1:2,048
1010 = 1:1,024
1001 = 1:512
1000 = 1:256
0111 = 1:128
0110 = 1:64
0101 = 1:32
0100 = 1:16
0011 = 1:8
0010 = 1:4
0001 = 1:2
0000 = 1:1
```

#### bit 0 WDTEN: Watchdog Timer Enable bit

1 = WDT enabled

0 = WDT disabled (control is placed on the SWDTEN bit)

#### Legend:

 $R = Readable \ bit$   $P = Programmable \ bit$   $U = Unimplemented \ bit, read as '0'$   $-n = Value \ when \ device \ is \ unprogrammed$   $u = Unchanged \ from \ programmed \ state$ 

## REGISTER 22-4: CONFIG3H: CONFIGURATION REGISTER 3 HIGH (BYTE ADDRESS 300005h)

| R/P-1 | U-0 | U-0 | U-0 | U-0 | R/P-0   | R/P-1  | R/P-1  |
|-------|-----|-----|-----|-----|---------|--------|--------|
| MCLRE | _   | _   | _   | _   | LPT1OSC | PBADEN | CCP2MX |
| L:4.7 |     |     |     |     |         |        | L:4 O  |

bit 7 bit 0

- bit 7 MCLRE: MCLR Pin Enable bit
  - $1 = \overline{\text{MCLR}}$  pin enabled; RE3 input pin disabled
  - 0 = RE3 input pin enabled; MCLR disabled
- bit 6-3 Unimplemented: Read as '0'
- bit 2 LPT10SC: Low-Power Timer1 Oscillator Enable bit
  - 1 = Timer1 configured for low-power operation
  - 0 = Timer1 configured for higher power operation
- bit 1 PBADEN: PORTB A/D Enable bit

(Affects ADCON1 Reset state. ADCON1 controls PORTB<4:0> pin configuration.)

- 1 = PORTB<4:0> pins are configured as analog input channels on Reset
- 0 = PORTB<4:0> pins are configured as digital I/O on Reset
- bit 0 CCP2MX: CCP2 Mux bit
  - 1 = CCP2 input/output is multiplexed with RC1
  - 0 = CCP2 input/output is multiplexed with RB3

#### Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 22-5: CONFIG4L: CONFIGURATION REGISTER 4 LOW (BYTE ADDRESS 300006h)

| R/P-1 | R/P-0 | U-0 | U-0 | U-0 | R/P-1 | U-0 | R/P-1  |
|-------|-------|-----|-----|-----|-------|-----|--------|
| DEBUG | XINST | _   | _   | _   | LVP   | _   | STVREN |
| bit 7 |       |     |     |     |       |     | bit 0  |

bit 7 **DEBUG:** Background Debugger Enable bit

- 1 = Background debugger disabled, RB6 and RB7 configured as general purpose I/O pins
- 0 = Background debugger enabled, RB6 and RB7 are dedicated to In-Circuit Debug
- bit 6 XINST: Extended Instruction Set Enable bit
  - 1 = Instruction set extension and Indexed Addressing mode enabled
  - 0 = Instruction set extension and Indexed Addressing mode disabled (Legacy mode)
- bit 5-3 **Unimplemented:** Read as '0'
- bit 2 LVP: Single-Supply ICSP Enable bit
  - 1 = Single-Supply ICSP enabled
  - 0 = Single-Supply ICSP disabled
- bit 1 Unimplemented: Read as '0'
- bit 0 STVREN: Stack Full/Underflow Reset Enable bit
  - 1 = Stack full/underflow will cause Reset
  - 0 = Stack full/underflow will not cause Reset

# Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 22-6: CONFIG5L: CONFIGURATION REGISTER 5 LOW (BYTE ADDRESS 300008h)

| U-0   | U-0 | U-0 | U-0 | R/C-1                | R/C-1              | R/C-1 | R/C-1 |
|-------|-----|-----|-----|----------------------|--------------------|-------|-------|
| _     | _   | _   | _   | CP3 <sup>(1,2)</sup> | CP2 <sup>(1)</sup> | CP1   | CP0   |
| hit 7 |     |     |     |                      |                    |       | hit Ω |

#### bit 7-4 Unimplemented: Read as '0'

bit 3 **CP3:** Code Protection bit<sup>(1,2)</sup>

1 = Block 3 (006000-007FFFh) not code-protected<sup>(3)</sup> 0 = Block 3 (006000-007FFFh) code-protected<sup>(3)</sup> 1 = Block 3 (00C000-00FFFFh) not code-protected<sup>(4)</sup>

0 = Block 3 (00C000-00FFFFh) code-protected(4)

bit 2 **CP2:** Code Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not code-protected<sup>(3)</sup> 0 = Block 2 (004000-005FFFh) code-protected<sup>(3)</sup> 1 = Block 2 (008000-00BFFFh) not code-protected<sup>(4)</sup>

0 = Block 2 (008000-00BFFFh) code-protected<sup>(4)</sup>

bit 1 CP1: Code Protection bit

1 = Block 1 (002000-003FFFh) not code-protected<sup>(3)</sup> 0 = Block 1 (002000-003FFFh) code-protected<sup>(3)</sup> 1 = Block 1 (004000-007FFFh) not code-protected<sup>(4)</sup>

0 = Block 1 (004000-007FFFh) code-protected<sup>(4)</sup>

bit 0 **CP0:** Code Protection bit

1 = Block 0 (000800-001FFFh) not code-protected (3)

0 = Block 0 (000800-001FFFh) code-protected<sup>(3)</sup>

1 = Block 0 (000800-003FFFh) not code-protected<sup>(4)</sup>

0 = Block 0 (000800-003FFFh) code-protected<sup>(4)</sup>

Note 1: Unimplemented in PIC18F2410/4410 devices; maintain this bit set.

2: Unimplemented in PIC18F2515/4515 devices; maintain this bit set.

3: Address range for 16K and 32K devices.

4: Address range for 48K and 64K devices.

#### Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$ -n = Value when device is unprogrammed  $u = Unchanged \ from \ programmed \ state$ 

## REGISTER 22-7: CONFIG5H: CONFIGURATION REGISTER 5 HIGH (BYTE ADDRESS 300009h)

| U-0   | R/C-1 | U-0 | U-0 | U-0 | U-0 | U-0 | U-0   |
|-------|-------|-----|-----|-----|-----|-----|-------|
| _     | СРВ   | _   | _   | _   | _   | _   | _     |
| bit 7 |       |     |     |     |     |     | bit 0 |

#### bit 7 Unimplemented: Read as '0'

bit 6 CPB: Boot Block Code Protection bit

1 = Boot block (000000-0007FFh) not code-protected 0 = Boot block (000000-0007FFh) code-protected

bit 5-0 Unimplemented: Read as '0'

#### Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$   $u = Unchanged \ from \ programmed \ state$ 

# REGISTER 22-8: CONFIG6L: CONFIGURATION REGISTER 6 LOW (BYTE ADDRESS 30000Ah)

| U-0   | U-0 | U-0 | U-0 | R/C-1                 | R/C-1               | R/C-1 | R/C-1 |
|-------|-----|-----|-----|-----------------------|---------------------|-------|-------|
| _     | _   | _   | _   | WRT3 <sup>(1,2)</sup> | WRT2 <sup>(1)</sup> | WRT1  | WRT0  |
| bit 7 |     |     |     |                       |                     |       | bit 0 |

#### bit 7-4 Unimplemented: Read as '0'

# bit 3 WRT3: Write Protection bit (1,2)

1 = Block 3 (006000-007FFFh) not write-protected<sup>(3)</sup>

0 = Block 3 (006000-007FFFh) write-protected<sup>(3)</sup>

1 = Block 3 (00C000-00FFFFh) not write-protected (4)

0 = Block 3 (00C000-00FFFFh) write-protected(4)

### bit 2 WRT2: Write Protection bit<sup>(1)</sup>

1 = Block 2 (004000-005FFFh) not write-protected<sup>(3)</sup>

0 = Block 2 (004000-005FFFh) write-protected<sup>(3)</sup>

1 = Block 2 (008000-00BFFFh) not write-protected (4)

0 = Block 2 (008000-00BFFFh) write-protected<sup>(4)</sup>

#### bit 1 WRT1: Write Protection bit

1 = Block 1 (002000-003FFFh) not write-protected<sup>(3)</sup>

0 = Block 1 (002000-003FFFh) write-protected<sup>(3)</sup>

1 = Block 1 (004000-007FFFh) not write-protected (4)

0 = Block 1 (004000-007FFFh) write-protected<sup>(4)</sup>

#### bit 0 WRT0: Write Protection bit

1 = Block 0 (000800-001FFFh) not write-protected  $^{(3)}$ 

0 = Block 0 (000800-001FFFh) write-protected<sup>(3)</sup>

1 = Block 0 (000800-003FFFh) not write-protected<sup>(4)</sup>

0 = Block 0 (000800-003FFFh) write-protected<sup>(4)</sup>

Note 1: Unimplemented in PIC18F2410/4410 devices; maintain this bit set.

2: Unimplemented in PIC18F2515/4515 devices; maintain this bit set.

3: Address range for 16K and 32K devices.

4: Address range for 48K and 64K devices.

#### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

## REGISTER 22-9: CONFIG6H: CONFIGURATION REGISTER 6 HIGH (BYTE ADDRESS 30000Bh)

| U-0   | R/C-1 | R-1                 | U-0 | U-0 | U-0 | U-0 | U-0   |
|-------|-------|---------------------|-----|-----|-----|-----|-------|
| _     | WRTB  | WRTC <sup>(1)</sup> | _   | _   | _   | _   | _     |
| bit 7 |       |                     |     |     |     |     | bit 0 |

#### bit 7 Unimplemented: Read as '0'

bit 6 WRTB: Boot Block Write Protection bit

1 = Boot block (000000-0007FFh) not write-protected

0 = Boot block (000000-0007FFh) write-protected

bit 5 WRTC: Configuration Register Write Protection bit (1)

1 = Configuration registers (300000-3000FFh) not write-protected

0 = Configuration registers (300000-3000FFh) write-protected

Note 1: This bit is read-only in normal execution mode; it can be written only in Program mode.

bit 4-0 Unimplemented: Read as '0'

#### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

# REGISTER 22-10: CONFIG7L: CONFIGURATION REGISTER 7 LOW (BYTE ADDRESS 30000Ch)

| U-0   | U-0 | U-0 | U-0 | R/C-1                  | R/C-1                | R/C-1 | R/C-1 |
|-------|-----|-----|-----|------------------------|----------------------|-------|-------|
| _     | _   | _   | _   | EBTR3 <sup>(1,2)</sup> | EBTR2 <sup>(1)</sup> | EBTR1 | EBTR0 |
| bit 7 |     |     |     |                        |                      |       | bit 0 |

#### bit 7-4 Unimplemented: Read as '0'

- bit 3 **EBTR3:** Table Read Protection bit<sup>(1,2)</sup>
  - 1 = Block 3 (006000-007FFFh) not protected from table reads executed in other blocks<sup>(3)</sup>
  - 0 = Block 3 (006000-007FFFh) protected from table reads executed in other blocks<sup>(3)</sup>
  - 1 = Block 3 (00C000-00FFFFh) not protected from table reads executed in other blocks<sup>(4)</sup>
  - 0 = Block 3 (00C000-00FFFFh) protected from table reads executed in other blocks (4)
- bit 2 **EBTR2**: Table Read Protection bit<sup>(1)</sup>
  - 1 = Block 2 (004000-005FFFh) not protected from table reads executed in other blocks<sup>(3)</sup>
  - 0 = Block 2 (004000-005FFFh) protected from table reads executed in other blocks<sup>(3)</sup>
  - 1 = Block 2 (008000-00BFFFh) not protected from table reads executed in other blocks (4)
  - 0 = Block 2 (008000-00BFFFh) protected from table reads executed in other blocks (4)
- bit 1 **EBTR1:** Table Read Protection bit
  - 1 = Block 1 (002000-003FFFh) not protected from table reads executed in other blocks<sup>(3)</sup>
  - 0 = Block 1 (002000-003FFFh) protected from table reads executed in other blocks<sup>(3)</sup>
  - 1 = Block 1 (004000-007FFFh) not protected from table reads executed in other blocks<sup>(4)</sup>
  - 0 = Block 1 (004000-007FFFh) protected from table reads executed in other blocks<sup>(4)</sup>
- bit 0 **EBTR0**: Table Read Protection bit
  - 1 = Block 0 (000800-001FFFh) not protected from table reads executed in other blocks<sup>(3)</sup>
  - 0 = Block 0 (000800-001FFFh) protected from table reads executed in other blocks<sup>(3)</sup>
  - 1 = Block 0 (000800-003FFFh) not protected from table reads executed in other blocks<sup>(4)</sup>
  - 0 = Block 0 (000800-003FFFh) protected from table reads executed in other blocks<sup>(4)</sup>
    - Note 1: Unimplemented in PIC18F2410/4410 devices; maintain this bit set.
      - 2: Unimplemented in PIC18F2515/4515 devices; maintain this bit set.
      - 3: Address range for 16K and 32K devices.
      - 4: Address range for 48K and 64K devices.

#### Legend:

R = Readable bit C = Clearable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

#### REGISTER 22-11: CONFIG7H: CONFIGURATION REGISTER 7 HIGH (BYTE ADDRESS 30000Dh)

| U-0   | R/C-1 | U-0 | U-0 | U-0 | U-0 | U-0 | U-0   |
|-------|-------|-----|-----|-----|-----|-----|-------|
| _     | EBTRB | _   | _   | _   | _   | _   | _     |
| bit 7 |       |     |     |     |     |     | bit 0 |

#### bit 7 **Unimplemented:** Read as '0'

- bit 6 EBTRB: Boot Block Table Read Protection bit
  - 1 = Boot block (000000-0007FFh) not protected from table reads executed in other blocks
  - $_{0}$  = Boot block (000000-0007FFh) protected from table reads executed in other blocks
- bit 5-0 Unimplemented: Read as '0'

#### Legend:

 $R = Readable \ bit$   $C = Clearable \ bit$   $U = Unimplemented \ bit, read as '0'$   $-n = Value \ when \ device \ is \ unprogrammed$   $u = Unchanged \ from \ programmed \ state$ 

#### REGISTER 22-12: DEVICE ID REGISTER 1 FOR PIC18F2X1X/4X1X DEVICES

| R     | R    | R    | R    | R    | R    | R    | R     |
|-------|------|------|------|------|------|------|-------|
| DEV2  | DEV1 | DEV0 | REV4 | REV3 | REV2 | REV1 | REV0  |
| bit 7 |      |      |      |      |      |      | bit 0 |

bit 7-5 **DEV2:DEV0:** Device ID bits

011 = PIC18F2410

001 = PIC18F2510

111 = PIC18F2515

101 = PIC18F2610

111 = PIC18F4410

101 = PIC18F4510

011 = PIC18F4515

001 = PIC18F4610

#### bit 4-0 REV4:REV0: Revision ID bits

These bits are used to indicate the device revision.

#### Legend:

R = Read-only bit P = Programmable bit U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed u = Unchanged from programmed state

#### REGISTER 22-13: DEVICE ID REGISTER 2 FOR PIC18F2X1X/4X1X DEVICES

|       | R     | R    | R    | R    | R    | R    | R    | R    |
|-------|-------|------|------|------|------|------|------|------|
|       | DEV10 | DEV9 | DEV8 | DEV7 | DEV6 | DEV5 | DEV4 | DEV3 |
| bit 7 |       |      |      |      |      |      |      |      |

#### bit 7-0 DEV10:DEV3: Device ID bits

These bits are used with the DEV2:DEV0 bits in the Device ID Register 1 to identify the part number.

0000 1100 = PIC18F2X1X/4X1X devices

**Note:** These values for DEV10:DEV3 may be shared with other devices. The specific device is always identified by using the entire DEV10:DEV0 bit sequence.

# Legend:

R = Read-only bit P = Programmable bit U = Unimplemented bit, read as '0'-n = Value when device is unprogrammed <math>u = Unchanged from programmed state

# 22.2 Watchdog Timer (WDT)

For PIC18F2X1X/4X1X devices, the WDT is driven by the INTRC source. When the WDT is enabled, the clock source is also enabled. The nominal WDT period is 4 ms and has the same stability as the INTRC oscillator.


The 4 ms period of the WDT is multiplied by a 16-bit postscaler. Any output of the WDT postscaler is selected by a multiplexer, controlled by bits in Configuration Register 2H. Available periods range from 4 ms to 131.072 seconds (2.18 minutes). The WDT and postscaler are cleared when any of the following events occur: a SLEEP or CLRWDT instruction is executed, the IRCF bits (OSCCON<6:4>) are changed or a clock failure has occurred.

- **Note 1:** The CLRWDT and SLEEP instructions clear the WDT and postscaler counts when executed.
  - 2: Changing the setting of the IRCF bits (OSCCON<6:4>) clears the WDT and postscaler counts.
  - **3:** When a CLRWDT instruction is executed, the postscaler count will be cleared.

#### 22.2.1 CONTROL REGISTER

Register 22-14 shows the WDTCON register. This is a readable and writable register which contains a control bit that allows software to override the WDT enable configuration bit, but only if the configuration bit has disabled the WDT.

FIGURE 22-1: WDT BLOCK DIAGRAM



#### REGISTER 22-14: WDTCON: WATCHDOG TIMER CONTROL REGISTER

| U-0   | U-0 | U-0 | U-0 | U-0 | U-0 | U-0 | R/W-0                 |
|-------|-----|-----|-----|-----|-----|-----|-----------------------|
| _     | _   | _   | _   | _   | _   | _   | SWDTEN <sup>(1)</sup> |
| hit 7 |     |     |     |     |     |     | hit 0                 |

bit 7-1 Unimplemented: Read as '0'

bit 0 **SWDTEN:** Software Controlled Watchdog Timer Enable bit<sup>(1)</sup>

1 = Watchdog Timer is on0 = Watchdog Timer is off

Note 1: This bit has no effect if the configuration bit WDTEN is enabled.

Legend:

 $R = Readable \ bit$   $W = Writable \ bit$   $U = Unimplemented \ bit, \ read \ as \ '0'$   $-n = Value \ at \ POR$ 

#### TABLE 22-2: SUMMARY OF WATCHDOG TIMER REGISTERS

| Name   | Bit 7 | Bit 6                 | Bit 5 | Bit 4 | Bit 3 | Bit 2 | Bit 1 | Bit 0                 | Reset<br>Values<br>on page |
|--------|-------|-----------------------|-------|-------|-------|-------|-------|-----------------------|----------------------------|
| RCON   | IPEN  | SBOREN <sup>(1)</sup> | _     | RI    | TO    | PD    | POR   | BOR                   | 48                         |
| WDTCON | _     | _                     | _     | _     | _     | _     | _     | SWDTEN <sup>(2)</sup> | 50                         |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Watchdog Timer.

Note 1: The SBOREN bit is only available when the BOREN1:BOREN0 configuration bits = 01; otherwise, it is disabled and reads as '0'. See Section 4.4 "Brown-out Reset (BOR)".

2: This bit has no effect if the configuration bit WDTEN is enabled.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 247

### 22.3 Two-Speed Start-up

The Two-Speed Start-up feature helps to minimize the latency period from oscillator start-up to code execution by allowing the microcontroller to use the INTOSC oscillator as a clock source until the primary clock source is available. It is enabled by setting the IESO configuration bit.

Two-Speed Start-up should be enabled only if the primary oscillator mode is LP, XT, HS or HSPLL (crystal-based modes). Other sources do not require an OST start-up delay; for these, Two-Speed Start-up should be disabled.

When enabled, Resets and wake-ups from Sleep mode cause the device to configure itself to run from the internal oscillator block as the clock source, following the time-out of the Power-up Timer after a Power-on Reset is enabled. This allows almost immediate code execution while the primary oscillator starts and the OST is running. Once the OST times out, the device automatically switches to PRI\_RUN mode.


To use a higher clock speed on wake-up, the INTOSC or postscaler clock sources can be selected to provide a higher clock speed by setting bits IRCF2:IRCF0 immediately after Reset. For wake-ups from Sleep, the INTOSC or postscaler clock sources can be selected by setting the IRCF2:IRCF0 bits prior to entering Sleep mode.

In all other power managed modes, Two-Speed Startup is not used. The device will be clocked by the currently selected clock source until the primary clock source becomes available. The setting of the IESO bit is ignored.

# 22.3.1 SPECIAL CONSIDERATIONS FOR USING TWO-SPEED START-UP

While using the INTOSC oscillator in Two-Speed Start-up, the device still obeys the normal command sequences for entering power managed modes, including multiple SLEEP instructions (refer to Section 3.1.4 "Multiple Sleep Commands"). In practice, this means that user code can change the SCS1:SCSO bit settings or issue SLEEP instructions before the OST times out. This would allow an application to briefly wake-up, perform routine "housekeeping" tasks and return to Sleep before the device starts to operate from the primary oscillator.

User code can also check if the primary clock source is currently providing the device clocking by checking the status of the OSTS bit (OSCCON<3>). If the bit is set, the primary oscillator is providing the clock. Otherwise, the internal oscillator block is providing the clock during wake-up from Reset or Sleep mode.




#### 22.4 Fail-Safe Clock Monitor

The Fail-Safe Clock Monitor (FSCM) allows the microcontroller to continue operation in the event of an external oscillator failure by automatically switching the device clock to the internal oscillator block. The FSCM function is enabled by setting the FCMEN configuration bit.

When FSCM is enabled, the INTRC oscillator runs at all times to monitor clocks to peripherals and provide a backup clock in the event of a clock failure. Clock monitoring (shown in Figure 22-3) is accomplished by creating a sample clock signal, which is the INTRC output divided by 64. This allows ample time between FSCM sample clocks for a peripheral clock edge to occur. The peripheral device clock and the sample clock are presented as inputs to the Clock Monitor latch (CM). The CM is set on the falling edge of the device clock source, but cleared on the rising edge of the sample clock.

FIGURE 22-3: FSCM BLOCK DIAGRAM



Clock failure is tested for on the falling edge of the sample clock. If a sample clock falling edge occurs while CM is still set, a clock failure has been detected (Figure 22-4). This causes the following:

- the FSCM generates an oscillator fail interrupt by setting bit OSCFIF (PIR2<7>);
- the device clock source is switched to the internal oscillator block (OSCCON is not updated to show the current clock source – this is the fail-safe condition); and
- the WDT is reset.

During switchover, the postscaler frequency from the internal oscillator block may not be sufficiently stable for timing sensitive applications. In these cases, it may be desirable to select another clock configuration and enter an alternate power managed mode. This can be done to attempt a partial recovery or execute a controlled shutdown. See Section 3.1.4 "Multiple Sleep Commands" and Section 22.3.1 "Special Considerations for Using Two-Speed Start-up" for more details.

To use a higher clock speed on wake-up, the INTOSC or postscaler clock sources can be selected to provide a higher clock speed by setting bits, IRCF2:IRCF0, immediately after Reset. For wake-ups from Sleep, the INTOSC or postscaler clock sources can be selected by setting the IRCF2:IRCF0 bits prior to entering Sleep mode.

The FSCM will detect failures of the primary or secondary clock sources only. If the internal oscillator block fails, no failure would be detected, nor would any action be possible.

## 22.4.1 FSCM AND THE WATCHDOG TIMER

Both the FSCM and the WDT are clocked by the INTRC oscillator. Since the WDT operates with a separate divider and counter, disabling the WDT has no effect on the operation of the INTRC oscillator when the FSCM is enabled.


As already noted, the clock source is switched to the INTOSC clock when a clock failure is detected. Depending on the frequency selected by the IRCF2:IRCF0 bits, this may mean a substantial change in the speed of code execution. If the WDT is enabled with a small prescale value, a decrease in clock speed allows a WDT time-out to occur and a subsequent device Reset. For this reason, fail-safe clock events also reset the WDT and postscaler, allowing it to start timing from when execution speed was changed and decreasing the likelihood of an erroneous time-out.

# 22.4.2 EXITING FAIL-SAFE OPERATION

The fail-safe condition is terminated by either a device Reset or by entering a power managed mode. On Reset, the controller starts the primary clock source specified in Configuration Register 1H (with any required start-up delays that are required for the oscillator mode, such as OST or PLL timer). The INTOSC multiplexer provides the device clock until the primary clock source becomes ready (similar to a Two-Speed Start-up). The clock source is then switched to the primary clock (indicated by the OSTS bit in the OSCCON register becoming set). The Fail-Safe Clock Monitor then resumes monitoring the peripheral clock.

The primary clock source may never become ready during start-up. In this case, operation is clocked by the INTOSC multiplexer. The OSCCON register will remain in its Reset state until a power managed mode is entered.





# 22.4.3 FSCM INTERRUPTS IN POWER MANAGED MODES

By entering a power managed mode, the clock multiplexer selects the clock source selected by the OSCCON register. Fail-Safe Monitoring of the power managed clock source resumes in the power managed mode.

If an oscillator failure occurs during power managed operation, the subsequent events depend on whether or not the oscillator failure interrupt is enabled. If enabled (OSCFIF = 1), code execution will be clocked by the INTOSC multiplexer. An automatic transition back to the failed clock source will not occur.

If the interrupt is disabled, subsequent interrupts while in Idle mode will cause the CPU to begin executing instructions while being clocked by the INTOSC source.

#### 22.4.4 POR OR WAKE FROM SLEEP

The FSCM is designed to detect oscillator failure at any point after the device has exited Power-on Reset (POR) or low-power Sleep mode. When the primary device clock is EC, RC or INTRC modes, monitoring can begin immediately following these events.

For oscillator modes involving a crystal or resonator (HS, HSPLL, LP or XT), the situation is somewhat different. Since the oscillator may require a start-up time considerably longer than the FCSM sample clock time, a false clock failure may be detected. To prevent this, the internal oscillator block is automatically configured as the device clock and functions until the primary clock is stable (the OST and PLL timers have timed out). This is identical to Two-Speed Start-up mode. Once the primary clock is stable, the INTRC returns to its role as the FSCM source.

Note: The same logic that prevents false oscillator failure interrupts on POR or wake from Sleep, will also prevent the detection of the oscillator's failure to start at all following these events. This can be avoided by monitoring the OSTS bit and using a timing routine to determine if the oscillator is taking too long to start. Even so, no oscillator failure interrupt will be flagged.

As noted in Section 22.3.1 "Special Considerations for Using Two-Speed Start-up", it is also possible to select another clock configuration and enter an alternate power managed mode while waiting for the primary clock to become stable. When the new power managed mode is selected, the primary clock is disabled.

# 22.5 Program Verification and Code Protection

The overall structure of the code protection on the PIC18 Flash devices differs significantly from other PICmicro<sup>®</sup> devices.

The user program memory is divided into five blocks. One of these is a boot block of 2 Kbytes. The remainder of the memory is divided into four blocks on binary boundaries.

Each of the five blocks has three code protection bits associated with them. They are:

- Code-Protect bit (CPn)
- Write-Protect bit (WRTn)
- External Block Table Read bit (EBTRn)

Figure 22-5 shows the program memory organization for 16- and 32-Kbyte devices and the specific code protection bit associated with each block.

Figure 22-6 shows the program memory organization for 48 and 64-Kbyte devices and the specific code protection bit associated with each block. The actual locations of the bits are summarized in Table 22-3.

FIGURE 22-5: CODE-PROTECTED PROGRAM MEMORY FOR PIC18F2410/2510/4410/4510

| MEMORY S                       | IZE/DEVICE                     |                    | Block Code Protection        |
|--------------------------------|--------------------------------|--------------------|------------------------------|
| 16 Kbytes<br>(PIC18F2410/4410) | 32 Kbytes<br>(PIC18F2510/4510) | Address<br>Range   | Controlled By:               |
| Boot Block                     | Boot Block                     | 000000h<br>0007FFh | CPB, WRTB, EBTRB             |
| Block 0                        | Block 0                        | 000800h<br>001FFFh | CP0, WRT0, EBTR0             |
| Block 1                        | Block 1                        | 002000h<br>003FFFh | CP1, WRT1, EBTR1             |
|                                | Block 2                        | 004000h<br>005FFFh | CP2, WRT2, EBTR2             |
|                                | Block 3                        | 006000h<br>007FFFh | CP3, WRT3, EBTR3             |
| Unimplemented<br>Read '0's     | Unimplemented<br>Read '0's     |                    | (Unimplemented Memory Space) |
|                                |                                | 1FFFFFh            |                              |

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 251

FIGURE 22-6: CODE-PROTECTED PROGRAM MEMORY FOR PIC18F2515/2610/4515/4610

| MEMORY S                       | IZE/DEVICE                     |                    | Block Code Protection        |  |
|--------------------------------|--------------------------------|--------------------|------------------------------|--|
| 48 Kbytes<br>(PIC18F2515/4515) | 64 Kbytes<br>(PIC18F2610/4610) | Address<br>Range   | Controlled By:               |  |
| Boot Block                     | Boot Block                     | 000000h<br>0007FFh | CPB, WRTB, EBTRB             |  |
| Block 0                        | Block 0                        | 000800h<br>003FFFh | CP0, WRT0, EBTR0             |  |
| Block 1                        | Block 1                        | 004000h<br>007FFFh | CP1, WRT1, EBTR1             |  |
| Block 2                        | Block 2                        | 008000h<br>00BFFFh | CP2, WRT2, EBTR2             |  |
|                                | Block 3                        | 00C000h<br>00FFFFh | CP3, WRT3, EBTR3             |  |
| Unimplemented<br>Read '0's     | Unimplemented<br>Read '0's     | 010000h            | (Unimplemented Memory Space) |  |
|                                |                                | 1FFFFFh            |                              |  |

## TABLE 22-3: SUMMARY OF CODE PROTECTION REGISTERS

| File    | Name     | Bit 7 | Bit 6 | Bit 5 | Bit 4 | Bit 3                  | Bit 2                | Bit 1 | Bit 0 |
|---------|----------|-------|-------|-------|-------|------------------------|----------------------|-------|-------|
| 300008h | CONFIG5L | _     | _     | _     | _     | CP3 <sup>(1,2)</sup>   | CP2 <sup>(1)</sup>   | CP1   | CP0   |
| 300009h | CONFIG5H | _     | СРВ   | _     | _     | _                      | _                    | _     | _     |
| 30000Ah | CONFIG6L | _     | _     | _     | _     | WRT3 <sup>(1,2)</sup>  | WRT2 <sup>(1)</sup>  | WRT1  | WRT0  |
| 30000Bh | CONFIG6H | _     | WRTB  | WRTC  | _     | _                      | _                    | _     | _     |
| 30000Ch | CONFIG7L | _     | _     | _     | _     | EBTR3 <sup>(1,2)</sup> | EBTR2 <sup>(1)</sup> | EBTR1 | EBTR0 |
| 30000Dh | CONFIG7H | ı     | EBTRB | ı     | _     | _                      | -                    | -     | _     |

**Legend:** Shaded cells are unimplemented.

Note 1: Unimplemented in PIC18F2410/4410 devices; maintain this bit set.

2: Unimplemented in PIC18F2515/4515 devices; maintain this bit set.

# 22.5.1 PROGRAM MEMORY CODE PROTECTION


The program memory may be read to or written from any location using the table read and table write instructions. The device ID may be read with table reads. The configuration registers may be read and written with the table read and table write instructions.

In normal execution mode, the CPn bits have no direct effect. CPn bits inhibit external reads and writes. The EBTRn bits control table reads. For a block of user memory with the EBTRn bit set to '0', a table read instruction that executes from within that block is allowed to read. A table read instruction that executes

from a location outside of that block is not allowed to read and will result in reading '0's. Figures 22-7 through 22-10 illustrate table write and table read protection.

Note: Code protection bits may only be written to a '0' from a '1' state. It is not possible to write a '1' to a bit in the '0' state. Code protection bits are only set to '1' by a full chip erase or block erase function. The full chip erase and block erase functions can only be initiated via ICSP or an external programmer.

FIGURE 22-7: EXTERNAL BLOCK TABLE READ (EBTRn) DISALLOWED (16-KBYTE AND 32-KBYTE DEVICES)



© 2004 Microchip Technology Inc. Preliminary DS39636A-page 253

FIGURE 22-8: EXTERNAL BLOCK TABLE READ (EBTRn) ALLOWED (16-KBYTE AND 32-KBYTE DEVICES)




FIGURE 22-9: EXTERNAL BLOCK TABLE READ (EBTRn) DISALLOWED (48-KBYTE AND 64-KBYTE DEVICES)





FIGURE 22-10: EXTERNAL BLOCK TABLE READ (EBTRn) ALLOWED (48-KBYTE AND 64-KBYTE DEVICES)



# 22.5.2 CONFIGURATION REGISTER PROTECTION

The configuration registers can be write-protected. The WRTC bit controls protection of the configuration registers. In normal execution mode, the WRTC bit is readable only. WRTC can only be written via ICSP or an external programmer.

### 22.6 ID Locations

Eight memory locations (200000h-200007h) are designated as ID locations, where the user can store checksum or other code identification numbers. These locations are both readable and writable during normal execution through the TBLRD instruction; during program/verify these locations are readable and writable. The ID locations can be read when the device is code-protected.

### 22.7 In-Circuit Serial Programming

PIC18F2X1X/4X1X microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data and three other lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

## 22.8 In-Circuit Debugger

When the DEBUG configuration bit is programmed to a '0', the In-Circuit Debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB® IDE. When the microcontroller has this feature enabled, some resources are not available for general use. Table 22-4 shows which resources are required by the background debugger.

TABLE 22-4: DEBUGGER RESOURCES

| I/O pins:       | RB6, RB7  |
|-----------------|-----------|
| Stack:          | 2 levels  |
| Program Memory: | 512 bytes |
| Data Memory:    | 10 bytes  |

To use the In-Circuit Debugger function of the microcontroller, the design must implement In-Circuit Serial Programming connections to MCLR/VPP/RE3, VDD, Vss, RB7 and RB6. This will interface to the In-Circuit Debugger module available from Microchip or one of the third party development tool companies.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 255

## 22.9 Single-Supply ICSP Programming

The LVP configuration bit enables Single-Supply ICSP Programming (formerly known as Low-Voltage ICSP Programming or LVP). When Single-Supply Programming is enabled, the microcontroller can be programmed without requiring high voltage being applied to the MCLR/VPP/RE3 pin, but the RB5/KBI1/PGM pin is then dedicated to controlling Program mode entry and is not available as a general purpose I/O pin.

While programming, using Single-Supply Programming mode, VDD is applied to the MCLR/VPP/RE3 pin as in normal execution mode. To enter Programming mode, VDD is applied to the PGM pin.

- Note 1: High-voltage programming is always available, regardless of the state of the LVP bit or the PGM pin, by applying VIHH to the MCLR pin.
  - 2: By default, Single-Supply ICSP is enabled in unprogrammed devices (as supplied from Microchip) and erased devices.
  - **3:** When Single-Supply Programming is enabled, the RB5 pin can no longer be used as a general purpose I/O pin.
  - **4:** When LVP is enabled, externally pull the PGM pin to Vss to allow normal program execution.

If Single-Supply ICSP Programming mode will not be used, the LVP bit can be cleared. RB5/KBI1/PGM then becomes available as the digital I/O pin, RB5. The LVP bit may be set or cleared only when using standard high-voltage programming (VIHH applied to the MCLR/VPP/RE3 pin). Once LVP has been disabled, only the standard high-voltage programming is available and must be used to program the device.

Memory that is not code-protected can be erased using either a block erase, or erased row by row, then written at any specified VDD. If code-protected memory is to be erased, a block erase is required. If a block erase is to be performed when using Low-Voltage Programming, the device must be supplied with VDD of 4.5V to 5.5V.

### 23.0 INSTRUCTION SET SUMMARY

PIC18F2X1X/4X1X devices incorporate the standard set of 75 PIC18 core instructions, as well as an extended set of 8 new instructions for the optimization of code that is recursive or that utilizes a software stack. The extended set is discussed later in this section.

#### 23.1 Standard Instruction Set

The standard PIC18 instruction set adds many enhancements to the previous PICmicro® instruction sets, while maintaining an easy migration from these PICmicro instruction sets. Most instructions are a single program memory word (16 bits), but there are four instructions that require two program memory locations.

Each single-word instruction is a 16-bit word divided into an opcode, which specifies the instruction type and one or more operands, which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- Byte-oriented operations
- · Bit-oriented operations
- Literal operations
- · Control operations

The PIC18 instruction set summary in Table 23-2 lists byte-oriented, bit-oriented, literal and control operations. Table 23-1 shows the opcode field descriptions.

Most byte-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator 'f' specifies which file register is to be used by the instruction. The destination designator 'd' specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the WREG register. If 'd' is one, the result is placed in the file register specified in the instruction.

All bit-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator 'f' represents the number of the file in which the bit is located.

The **literal** instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The **control** instructions may use some of the following operands:

- A program memory address (specified by 'n')
- The mode of the CALL or RETURN instructions (specified by 's')
- The mode of the table read and table write instructions (specified by 'm')
- No operand required (specified by '—')

All instructions are a single word, except for four double-word instructions. These instructions were made double-word to contain the required information in 32 bits. In the second word, the 4 MSbs are '1's. If this second word is executed as an instruction (by itself), it will execute as a NOP.

All single-word instructions are executed in a single instruction cycle, unless a conditional test is true or the program counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles, with the additional instruction cycle(s) executed as a NOP.

The double-word instructions execute in two instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu$ s. If a conditional test is true, or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s. Two-word branch instructions (if true) would take 3  $\mu$ s.

Figure 23-1 shows the general formats that the instructions can have. All examples use the convention 'nnh' to represent a hexadecimal number.

The Instruction Set Summary, shown in Table 23-2, lists the standard instructions recognized by the Microchip MPASM™ Assembler.

**Section 23.1.1 "Standard Instruction Set"** provides a description of each instruction.

### TABLE 23-1: OPCODE FIELD DESCRIPTIONS

| Field                 | Description   |
|-----------------------|---|
| a                     | RAM access bit  |
| a                     | a = 0: RAM location in Access RAM (BSR register is ignored)   |
|                       | a = 1: RAM bank is specified by BSR register  |
| bbb                   | Bit address within an 8-bit file register (0 to 7).   |
| BSR                   | Bank Select Register. Used to select the current RAM bank.  |
| C, DC, Z, OV, N       | ALU status bits: Carry, Digit Carry, Zero, Overflow, Negative.  |
| d                     | Destination select bit  |
|                       | d = 0: store result in WREG   |
|                       | d = 1: store result in file register f  |
| dest                  | Destination: either the WREG register or the specified register file location.  |
| f                     | 8-bit Register file address (00h to FFh) or 2-bit FSR designator (0h to 3h).  |
| f <sub>s</sub>        | 12-bit Register file address (000h to FFFh). This is the source address.  |
| f <sub>d</sub>        | 12-bit Register file address (000h to FFFh). This is the destination address.   |
| GIE                   | Global Interrupt Enable bit.  |
| k                     | Literal field, constant data or label (may be either an 8-bit, 12-bit or a 20-bit value).   |
| label                 | Label name.   |
| mm                    | The mode of the TBLPTR register for the table read and table write instructions.  |
|                       | Only used with table read and table write instructions:   |
| *                     | No change to register (such as TBLPTR with table reads and writes)  |
| *+                    | Post-Increment register (such as TBLPTR with table reads and writes)  |
| * -                   | Post-Decrement register (such as TBLPTR with table reads and writes)  |
| +*                    | Pre-Increment register (such as TBLPTR with table reads and writes)   |
| n                     | The relative address (2's complement number) for relative branch instructions or the direct address for call/branch and return instructions.                    |
| PC                    | Program Counter.  |
| PCL                   | Program Counter Low Byte.   |
| PCH                   | Program Counter High Byte.  |
| PCLATH                | Program Counter High Byte Latch.  |
| PCLATU                | Program Counter Upper Byte Latch.   |
| PD                    | Power-down bit.   |
| PRODH                 | Product of Multiply High Byte.  |
| PRODL                 | Product of Multiply Low Byte.   |
| s                     | Fast Call/Return mode select bit  |
|                       | s = 0: do not update into/from shadow registers   |
|                       | s = 1: certain registers loaded into/from shadow registers (Fast mode)  |
| TBLPTR                | 21-bit Table Pointer (points to a Program Memory location).   |
| TABLAT                | 8-bit Table Latch.  |
| TO                    | Time-out bit.   |
| TOS                   | Top-of-Stack.   |
| u                     | Unused or unchanged.  |
| WDT                   | Watchdog Timer.   |
| WREG                  | Working register (accumulator).   |
| х                     | Don't care ('0' or '1'). The assembler will generate code with $x = 0$ . It is the recommended form of use for compatibility with all Microchip software tools. |
|                       | 7-bit offset value for indirect addressing of register files (source).  |
| Z <sub>S</sub>        | 7-bit offset value for indirect addressing of register files (source).  7-bit offset value for indirect addressing of register files (destination).             |
| z <sub>d</sub>        | Optional argument.  |
| [text]                | Indicates an indexed address.   |
|                       | The contents of text.   |
| (text) [expr] <n></n> | Specifies bit n of the register indicated by the pointer expr.  |
|                       |   |
| <i>→</i>              | Assigned to.  |
| < >                   | Register bit field.   |
| €                     | In the set of.  |
| italics               | User defined term (font is Courier).  |

## FIGURE 23-1: GENERAL FORMAT FOR INSTRUCTIONS

#### Byte-oriented file register operations **Example Instruction** OPCODE f (FILE #) ADDWF MYREG, W, B d а d = 0 for result destination to be WREG register d = 1 for result destination to be file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address Byte to Byte move operations (2-word) 12 11 OPCODE f (Source FILE #) MOVFF MYREG1, MYREG2 15 12 11 0 f (Destination FILE #) 1111 f = 12-bit file register address Bit-oriented file register operations OPCODE b (BIT #) a f (FILE #) BSF MYREG, bit, B b = 3-bit position of bit in file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address Literal operations 15 0 **OPCODE** k (literal) MOVLW 7Fh k = 8-bit immediate value **Control** operations CALL, GOTO and Branch operations 15 0 OPCODE n<7:0> (literal) GOTO Label 15 12 11 0 1111 n<19:8> (literal) n = 20-bit immediate value 15 CALL MYFUNC **OPCODE** n<7:0> (literal) 15 12 11 0 n<19:8> (literal) 1111 S = Fast bit 11 10 OPCODE BRA MYFUNC n<10:0> (literal) 15 8 7 OPCODE n<7:0> (literal) BC MYFUNC

TABLE 23-2: PIC18FXXXX INSTRUCTION SET

| Mnemonic, |                      | Description                              | Cycles     | 16-Bit Instruction Word |      |      | Vord | Status          | Notes      |
|-----------|----------------------|--|------------|-------------------------|------|------|------|-----------------|------------|
| Operai    | Operands Description |  | Cycles     | MSb                     |      |      | LSb  | Affected        | Notes      |
| BYTE-ORIE | ENTED (              | OPERATIONS                               |            |                         |      |      |      |                 |            |
| ADDWF     | f, d, a              | Add WREG and f                           | 1          | 0010                    | 01da | ffff | ffff | C, DC, Z, OV, N | 1, 2       |
| ADDWFC    | f, d, a              | Add WREG and Carry bit to f              | 1          | 0010                    | 00da | ffff | ffff | C, DC, Z, OV, N | 1, 2       |
| ANDWF     | f, d, a              | AND WREG with f                          | 1          | 0001                    | 01da | ffff | ffff | Z, N            | 1,2        |
| CLRF      | f, a                 | Clear f                                  | 1          | 0110                    | 101a | ffff | ffff | Z               | 2          |
| COMF      | f, d, a              | Complement f                             | 1          | 0001                    | 11da | ffff | ffff | Z, N            | 1, 2       |
| CPFSEQ    | f, a                 | Compare f with WREG, skip =              | 1 (2 or 3) | 0110                    | 001a | ffff | ffff | None            | 4          |
| CPFSGT    | f, a                 | Compare f with WREG, skip >              | 1 (2 or 3) | 0110                    | 010a | ffff | ffff | None            | 4          |
| CPFSLT    | f, a                 | Compare f with WREG, skip <              | 1 (2 or 3) | 0110                    | 000a | ffff | ffff | None            | 1, 2       |
| DECF      | f, d, a              | Decrement f                              | 1          | 0000                    | 01da | ffff | ffff | C, DC, Z, OV, N | 1, 2, 3, 4 |
| DECFSZ    | f, d, a              | Decrement f, Skip if 0                   | 1 (2 or 3) | 0010                    | 11da | ffff | ffff | None            | 1, 2, 3, 4 |
| DCFSNZ    | f, d, a              | Decrement f, Skip if Not 0               | 1 (2 or 3) | 0100                    | 11da | ffff | ffff | None            | 1, 2       |
| INCF      | f, d, a              | Increment f                              | 1          | 0010                    | 10da | ffff | ffff | C, DC, Z, OV, N | 1, 2, 3, 4 |
| INCFSZ    | f, d, a              | Increment f, Skip if 0                   | 1 (2 or 3) | 0011                    | 11da | ffff | ffff | None            | 4          |
| INFSNZ    | f, d, a              | Increment f, Skip if Not 0               | 1 (2 or 3) | 0100                    | 10da | ffff | ffff | None            | 1, 2       |
| IORWF     | f, d, a              | Inclusive OR WREG with f                 | 1          | 0001                    | 00da | ffff | ffff | Z, N            | 1, 2       |
| MOVF      | f, d, a              | Move f                                   | 1          | 0101                    | 00da | ffff | ffff | Z, N            | 1          |
| MOVFF     | $f_s, f_d$           | Move f <sub>s</sub> (source) to 1st word | 2          | 1100                    | ffff | ffff | ffff | None            |            |
|           | 0                    | f <sub>d</sub> (destination) 2nd word    |            | 1111                    | ffff | ffff | ffff |                 |            |
| MOVWF     | f, a                 | Move WREG to f                           | 1          | 0110                    | 111a | ffff | ffff | None            |            |
| MULWF     | f, a                 | Multiply WREG with f                     | 1          | 0000                    | 001a | ffff | ffff | None            | 1, 2       |
| NEGF      | f, a                 | Negate f                                 | 1          | 0110                    | 110a | ffff | ffff | C, DC, Z, OV, N |            |
| RLCF      | f, d, a              | Rotate Left f through Carry              | 1          | 0011                    | 01da | ffff | ffff | C, Z, N         | 1, 2       |
| RLNCF     | f, d, a              | Rotate Left f (No Carry)                 | 1          | 0100                    | 01da | ffff | ffff | Z, N            |            |
| RRCF      | f, d, a              | Rotate Right f through Carry             | 1          | 0011                    | 00da | ffff | ffff | C, Z, N         |            |
| RRNCF     | f, d, a              | Rotate Right f (No Carry)                | 1          | 0100                    | 00da | ffff | ffff | Z, N            |            |
| SETF      | f, a                 | Set f                                    | 1          | 0110                    | 100a | ffff | ffff | None            | 1, 2       |
| SUBFWB    | f, d, a              | Subtract f from WREG with                | 1          | 0101                    | 01da | ffff | ffff | C, DC, Z, OV, N |            |
|           |                      | borrow                                   |            |                         |      |      |      |                 |            |
| SUBWF     | f, d, a              | Subtract WREG from f                     | 1          | 0101                    | 11da | ffff | ffff | C, DC, Z, OV, N | 1, 2       |
| SUBWFB    | f, d, a              | Subtract WREG from f with                | 1          | 0101                    | 10da | ffff |      | C, DC, Z, OV, N |            |
|           |                      | borrow                                   |            |                         |      |      |      |                 |            |
| SWAPF     | f, d, a              | Swap nibbles in f                        | 1          | 0011                    | 10da | ffff | ffff | None            | 4          |
| TSTFSZ    | f, a                 | Test f, skip if 0                        | 1 (2 or 3) | 0110                    | 011a | ffff | ffff | None            | 1, 2       |
| XORWF     | f, d, a              | Exclusive OR WREG with f                 | 1 `        | 0001                    | 10da | ffff | ffff | Z, N            |            |

Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

<sup>2:</sup> If this instruction is executed on the TMR0 register (and where applicable, 'd' = 1), the prescaler will be cleared if assigned.

<sup>3:</sup> If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

**<sup>4:</sup>** Some instructions are two-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

TABLE 23-2: PIC18FXXXX INSTRUCTION SET (CONTINUED)

| Mnemo     | onic,   | Decembries                     | Cualas     | 16-E | Bit Instr | uction V | Vord | Status    | Natas |
|-----------|---------|--------------------------------|------------|------|-----------|----------|------|-----------|-------|
| Opera     | nds     | Description                    | Cycles     | MSb  |           |          | LSb  | Affected  | Notes |
| BIT-ORIEN | ITED OP | ERATIONS                       |            |      |           |          |      |           |       |
| BCF       | f, b, a | Bit Clear f                    | 1          | 1001 | bbba      | ffff     | ffff | None      | 1, 2  |
| BSF       | f, b, a | Bit Set f                      | 1          | 1000 | bbba      | ffff     | ffff | None      | 1, 2  |
| BTFSC     | f, b, a | Bit Test f, Skip if Clear      | 1 (2 or 3) | 1011 | bbba      | ffff     | ffff | None      | 3, 4  |
| BTFSS     | f, b, a | Bit Test f, Skip if Set        | 1 (2 or 3) | 1010 | bbba      | ffff     | ffff | None      | 3, 4  |
| BTG       | f, d, a | Bit Toggle f                   | 1          | 0111 | bbba      | ffff     | ffff | None      | 1, 2  |
| CONTROL   | OPERA   | TIONS                          |            | •    |           |          |      |           |       |
| ВС        | n       | Branch if Carry                | 1 (2)      | 1110 | 0010      | nnnn     | nnnn | None      |       |
| BN        | n       | Branch if Negative             | 1 (2)      | 1110 | 0110      | nnnn     | nnnn | None      |       |
| BNC       | n       | Branch if Not Carry            | 1 (2)      | 1110 | 0011      | nnnn     | nnnn | None      |       |
| BNN       | n       | Branch if Not Negative         | 1 (2)      | 1110 | 0111      | nnnn     | nnnn | None      |       |
| BNOV      | n       | Branch if Not Overflow         | 1 (2)      | 1110 | 0101      | nnnn     | nnnn | None      |       |
| BNZ       | n       | Branch if Not Zero             | 1 (2)      | 1110 | 0001      | nnnn     | nnnn | None      |       |
| BOV       | n       | Branch if Overflow             | 1 (2)      | 1110 | 0100      | nnnn     | nnnn | None      |       |
| BRA       | n       | Branch Unconditionally         | 2          | 1101 | 0nnn      | nnnn     | nnnn | None      |       |
| BZ        | n       | Branch if Zero                 | 1 (2)      | 1110 | 0000      | nnnn     | nnnn | None      |       |
| CALL      | n, s    | Call subroutine 1st word       | 2          | 1110 | 110s      | kkkk     | kkkk | None      |       |
|           |         | 2nd word                       |            | 1111 | kkkk      | kkkk     | kkkk |           |       |
| CLRWDT    | _       | Clear Watchdog Timer           | 1          | 0000 | 0000      | 0000     | 0100 | TO, PD    |       |
| DAW       | _       | Decimal Adjust WREG            | 1          | 0000 | 0000      | 0000     | 0111 | С         |       |
| GOTO      | n       | Go to address 1st word         | 2          | 1110 | 1111      | kkkk     | kkkk | None      |       |
|           |         | 2nd word                       |            | 1111 | kkkk      | kkkk     | kkkk |           |       |
| NOP       | _       | No Operation                   | 1          | 0000 | 0000      | 0000     | 0000 | None      |       |
| NOP       | _       | No Operation                   | 1          | 1111 | XXXX      | XXXX     | XXXX | None      | 4     |
| POP       | _       | Pop top of return stack (TOS)  | 1          | 0000 | 0000      | 0000     | 0110 | None      |       |
| PUSH      | _       | Push top of return stack (TOS) | 1          | 0000 | 0000      | 0000     | 0101 | None      |       |
| RCALL     | n       | Relative Call                  | 2          | 1101 | 1nnn      | nnnn     | nnnn | None      |       |
| RESET     |         | Software device Reset          | 1          | 0000 | 0000      | 1111     | 1111 | All       |       |
| RETFIE    | S       | Return from interrupt enable   | 2          | 0000 | 0000      | 0001     | 000s | GIE/GIEH, |       |
|           |         |                                |            |      |           |          |      | PEIE/GIEL |       |
| RETLW     | k       | Return with literal in WREG    | 2          | 0000 | 1100      | kkkk     | kkkk | None      |       |
| RETURN    | S       | Return from Subroutine         | 2          | 0000 | 0000      | 0001     | 001s | None_     |       |
| SLEEP     | _       | Go into Standby mode           | 1          | 0000 | 0000      | 0000     | 0011 | TO, PD    |       |

Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

- 2: If this instruction is executed on the TMR0 register (and where applicable, 'd' = 1), the prescaler will be cleared if assigned.
- **3:** If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
- 4: Some instructions are two-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 261

TABLE 23-2: PIC18FXXXX INSTRUCTION SET (CONTINUED)

| Mnemonic, |                        | Description                     | Cycles | 16-Bit Instruction V |      | Word | Status | Notes           |       |
|-----------|------------------------|---------------------------------|--------|----------------------|------|------|--------|-----------------|-------|
| Oper      | ands                   | Description                     | Cycles | MSb                  | LSb  |      | LSb    | Affected        | Notes |
| LITERAL   | OPERATI                | ONS                             |        |                      |      |      |        |                 |       |
| ADDLW     | k                      | Add literal and WREG            | 1      | 0000                 | 1111 | kkkk | kkkk   | C, DC, Z, OV, N |       |
| ANDLW     | k                      | AND literal with WREG           | 1      | 0000                 | 1011 | kkkk | kkkk   | Z, N            |       |
| IORLW     | k                      | Inclusive OR literal with WREG  | 1      | 0000                 | 1001 | kkkk | kkkk   | Z, N            |       |
| LFSR      | f, k                   | Move literal (12-bit) 2nd word  | 2      | 1110                 | 1110 | OOff | kkkk   | None            |       |
|           |                        | to FSR(f) 1st word              |        | 1111                 | 0000 | kkkk | kkkk   |                 |       |
| MOVLB     | k                      | Move literal to BSR<3:0>        | 1      | 0000                 | 0001 | 0000 | kkkk   | None            |       |
| MOVLW     | k                      | Move literal to WREG            | 1      | 0000                 | 1110 | kkkk | kkkk   | None            |       |
| MULLW     | k                      | Multiply literal with WREG      | 1      | 0000                 | 1101 | kkkk | kkkk   | None            |       |
| RETLW     | k                      | Return with literal in WREG     | 2      | 0000                 | 1100 | kkkk | kkkk   | None            |       |
| SUBLW     | k                      | Subtract WREG from literal      | 1      | 0000                 | 1000 | kkkk | kkkk   | C, DC, Z, OV, N |       |
| XORLW     | k                      | Exclusive OR literal with WREG  | 1      | 0000                 | 1010 | kkkk | kkkk   | Z, N            |       |
| DATA ME   | $MORY \leftrightarrow$ | PROGRAM MEMORY OPERATION        | ONS    |                      |      |      |        |                 |       |
| TBLRD*    |                        | Table Read                      | 2      | 0000                 | 0000 | 0000 | 1000   | None            |       |
| TBLRD*+   |                        | Table Read with post-increment  |        | 0000                 | 0000 | 0000 | 1001   | None            |       |
| TBLRD*-   |                        | Table Read with post-decrement  |        | 0000                 | 0000 | 0000 | 1010   | None            |       |
| TBLRD+*   |                        | Table Read with pre-increment   |        | 0000                 | 0000 | 0000 | 1011   | None            |       |
| TBLWT*    |                        | Table Write                     | 2      | 0000                 | 0000 | 0000 | 1100   | None            |       |
| TBLWT*+   |                        | Table Write with post-increment |        | 0000                 | 0000 | 0000 | 1101   | None            |       |
| TBLWT*-   |                        | Table Write with post-decrement |        | 0000                 | 0000 | 0000 | 1110   | None            |       |
| TBLWT+*   |                        | Table Write with pre-increment  |        | 0000                 | 0000 | 0000 | 1111   | None            |       |

Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

- 2: If this instruction is executed on the TMR0 register (and where applicable, 'd' = 1), the prescaler will be cleared if assigned.
- 3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
- **4:** Some instructions are two-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

### 23.1.1 STANDARD INSTRUCTION SET

| ADD   | DLW                        | ADD Lite  | ral to W                |   |            |  |  |  |  |
|-------|----------------------------|---|-------------------------|---|------------|--|--|--|--|
| Synta | ax:                        | ADDLW   | k                       |   |            |  |  |  |  |
| Oper  | ands:                      | $0 \le k \le 255$   | $0 \le k \le 255$       |   |            |  |  |  |  |
| Oper  | ation:                     | $(W) + k \rightarrow C$   | $(W) + k \rightarrow W$ |   |            |  |  |  |  |
| Statu | s Affected:                | N, OV, C, E   | )C, Z                   |   |            |  |  |  |  |
| Enco  | coding: 0000 1111 kkkk kkk |   |                         |   |            |  |  |  |  |
| Desc  | ription:                   | The contents of W are added to the 8-bit literal 'k' and the result is placed ir W. |                         |   |            |  |  |  |  |
| Word  | ls:                        | 1   |                         |   |            |  |  |  |  |
| Cycle | es:                        | 1   | 1                       |   |            |  |  |  |  |
| QC    | ycle Activity:             |   |                         |   |            |  |  |  |  |
|       | Q1                         | Q2  | Q3                      | 1 | Q4         |  |  |  |  |
|       | Decode                     | Read  | Proce                   |   | /rite to W |  |  |  |  |
|       |                            | literal 'k'   | Data                    | a |            |  |  |  |  |

Example: ADDLW 15h

Before Instruction W = 10h After Instruction W = 25h

| ADDWF            | ADD W to f  |  |  |  |  |  |
|------------------|---|--|--|--|--|--|
| Syntax:          | ADDWF f {,d {,a}}   |  |  |  |  |  |
| Operands:        | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |  |  |  |  |  |
| Operation:       | (W) + (f) $\rightarrow$ dest  |  |  |  |  |  |
| Status Affected: | N, OV, C, DC, Z   |  |  |  |  |  |
| Encoding:        | 0010 01da ffff ffff   |  |  |  |  |  |
| Description:     | Add W to register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default).  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See  Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |  |  |  |  |  |
| Words:           | 1   |  |  |  |  |  |

Q Cycle Activity:

Cycles:

|                               | Q1     | Q2                | Q3              | Q4                   |
|-------------------------------|--------|-------------------|-----------------|----------------------|
| register   Data   destination | Decode | Read register 'f' | Process<br>Data | Write to destination |

Example: ADDWF REG, 0, 0

1

Before Instruction

W = 17h REG = 0C2h

After Instruction

W = 0D9hREG = 0C2h

**Note:** All PIC18 instructions may take an optional label argument preceding the instruction mnemonic for use in symbolic addressing. If a label is used, the instruction format then becomes: {label} instruction argument(s).

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 263

| ADDWFC            | ADD W a  | nd Carr  | y bit to 1   | f   |  |  |
|-------------------|--|--|--|---|--|--|
| Syntax:           | ADDWFC   | f {,d {,   | a}}  |   |  |  |
| Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |  |  |   |  |  |
| Operation:        | (W) + (f) +  | $(C) \rightarrow de$   | st   |   |  |  |
| Status Affected:  | N,OV, C, D   | C, Z   |  |   |  |  |
| Encoding:         | 0010   | 00da   | ffff   | ffff  |  |  |
| Description:      | Add W, the location 'f'. placed in W placed in di If 'a' is 'o', t If 'a' is '1', t GPR bank If 'a' is '0' a set is enabl in Indexed mode wher Section 23 Bit-Oriente Literal Offs | If 'd' is 'o  If 'd' is ata memore he Acces he BSR i (default). and the exited, this in Literal Off never f ≤ 5.2.3 "By ded Instru | ', the resi<br>'1', the resi<br>'1', the resory locations<br>is Bank is<br>is used to<br>ktended in<br>instruction<br>ffset Addr<br>95 (5Fh).<br>ite-Orient<br>ctions in | ult is esult is esult is on 'f'. selected. select the nstruction operates essing See ed and Indexed |  |  |
| Words:            | 1  |  |  |   |  |  |
| Cycles:           | 1  |  |  |   |  |  |
| Q Cycle Activity: |  |  |  |   |  |  |
| Q1                | Q2   | Q3   |  | Q4  |  |  |
| Decode            | Read register 'f'  | Proce<br>Data  |  | Vrite to stination  |  |  |

ADDWFC

02h 4Dh

02h 50h REG, 0, 1

| Word  | S:                | 1    |           |         |            |
|-------|-------------------|------|-----------|---------|------------|
| Cycle | s:                | 1    |           |         |            |
| Q Cy  | cle Activity:     |      |           |         |            |
| _     | Q1                |      | Q2        | Q3      | Q4         |
|       | Decode            | Rea  | d literal | Process | Write to W |
| L     |                   |      | 'k'       | Data    |            |
|       |                   |      |           |         |            |
| Exam  | <u>iple:</u>      | Al   | NDLW      | 05Fh    |            |
| ı     | Before Instruc    | tion |           |         |            |
|       | W                 | =    | A3h       |         |            |
| ,     | After Instruction | n    |           |         |            |
|       | W                 | =    | 03h       |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |
|       |                   |      |           |         |            |

**AND Literal with W** 

ANDLW

N, Z

 $0 \le k \le 255$ 

0000

(W) .AND.  $k \rightarrow W$ 

1011

The contents of W are AND'ed with the 8-bit literal 'k'. The result is placed in W.

kkkk

kkkk

**ANDLW** 

Syntax:

Operands:

Operation: Status Affected:

Encoding:

Description:

Example:

Before Instruction

Carry bit =

REG =

W =

After Instruction

Carry bit = REG = W =

#### **ANDWF** AND W with f ANDWF Syntax: f {,d {,a}} Operands: $0 \le f \le 255$ $d\in \left[ 0,1\right]$ $a\in \left[ 0,1\right]$ Operation: (W) .AND. (f) $\rightarrow$ dest Status Affected: Encoding: 0001 01da ffff ffff The contents of W are AND'ed with Description: register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Section 23.2.3 "Byte-Oriented and **Bit-Oriented Instructions in Indexed** Literal Offset Mode" for details. Words: 1 Cycles: Q Cycle Activity: Q1 Q2 Q3 Q4

| Example:                    | Al           | NDWF       | REG, | 0, | 0 |  |
|-----------------------------|--------------|------------|------|----|---|--|
| Before Instruc              | ction        |            |      |    |   |  |
| W<br>REG<br>After Instructi | =<br>=<br>on | 17h<br>C2h |      |    |   |  |
| W                           | =            | 02h        |      |    |   |  |

C2h

Read

register 'f'

Decode

REG

**Process** 

Data

Write to

destination

| ВС           | BC Branch if Carry     |  |  |   |                        |
|--------------|------------------------|--|--|---|------------------------|
| Synta        | ax:                    | BC n   |  |   |                        |
| Oper         | ands:                  | -128 ≤ n ≤   | 127  |   |                        |
| Oper         | ation:                 | if Carry bit<br>(PC) + 2 +   |  | ;   |                        |
| Statu        | s Affected:            | None   |  |   |                        |
| Enco         | oding:                 | 1110   | 0010   | nnnn  | nnnn                   |
| Word         | ription:               | If the Carry will branch. The 2's cor added to the incremente instruction, PC + 2 + 2 two-cycle in 1 | mplemen<br>e PC. Sind to fetclenthe the new<br>the new<br>n. This in | t number<br>nce the PC<br>n the next<br>address v | '2n' is<br>C will have |
| Cycle        | es:                    | 1(2)   |  |   |                        |
| Q C<br>If Ju | ycle Activity:<br>imp: |  |  |   |                        |
|              | Q1                     | Q2   | Q3   | 3   | Q4                     |
|              | Decode                 | Read literal 'n'   | Proce<br>Data  |   | ite to PC              |
|              | No                     | No   | No   |   | No                     |
|              | operation              | operation  | operat   | ion or  | peration               |
| If No        | o Jump:                |  |  |   |                        |

| Example:                                | HERE             | вс      | 5           |
|---|------------------|---------|-------------|
| Before Instruction PC After Instruction | =                | address | (HERE)      |
| If Carry<br>PC<br>If Carry<br>PC        | =<br>=<br>=<br>= | 0;      | (HERE + 12) |

Q2

Read literal

'n'

Q3

**Process** 

Data

Q4

No

operation

Q1

Decode

| BCF              | Bit Clear f  |
|------------------|--|
| Syntax:          | BCF f, b {,a}  |
| Operands:        | $0 \le f \le 255$<br>$0 \le b \le 7$<br>$a \in [0,1]$  |
| Operation:       | $0 \rightarrow f < b >$  |
| Status Affected: | None   |
| Encoding:        | 1001 bbba ffff ffff  |
| Description:     | Bit 'b' in register 'f' is cleared. If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). |

If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever  $f \le 95$  (5Fh). See Section 23.2.3 "Byte-Oriented and **Bit-Oriented Instructions in Indexed** Literal Offset Mode" for details.

Words: Cycles:

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: FLAG REG, 7, 0 BCF

Before Instruction

FLAG\_REG = C7h

After Instruction

FLAG\_REG =

#### BN **Branch if Negative**

Syntax: BN n

Operands:  $-128 \le n \le 127$ 

Operation: if Negative bit is '1'  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0110 nnnn nnnn

If the Negative bit is '1', then the Description:

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next

instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity:

If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BN Jump

Before Instruction

PC address (HERE)

After Instruction

If Negative PC

address (Jump)

If Negative PC

address (HERE + 2)

| BNC              | Branch is   | f Not Ca       | rry  |      |
|------------------|---|----------------|------|------|
| Syntax:          | BNC n   |                |      |      |
| Operands:        | -128 ≤ n ≤  | -128 ≤ n ≤ 127 |      |      |
| Operation:       | if Carry bit is '0' $(PC) + 2 + 2n \rightarrow PC$  |                |      |      |
| Status Affected: | None  |                |      |      |
| Encoding:        | 1110  | 0011           | nnnn | nnnn |
| Description:     | If the Carry bit is '0', then the program will branch.  The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction. |                |      |      |

Words: 1 Cycles: 1(2)

Q Cycle Activity:

If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | ʻn'          | Data    | operation |

Example: HERE BNC Jump

Before Instruction

PC address (HERE)

After Instruction

If Carry PC

address (Jump)

address (HERE + 2)

| BNN     | Branch if Not Negative |
|---------|------------------------|
| Syntax: | BNN n                  |

Operands:  $\text{-}128 \leq n \leq 127$ Operation: if Negative bit is '0'  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0111 nnnn nnnn

n

Description: If the Negative bit is '0', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be

PC + 2 + 2n. This instruction is then a two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity:

If Jump:

Syntax:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |  |
|--------|--------------|---------|-----------|--|
| Decode | Read literal | Process | No        |  |
|        | 'n'          | Data    | operation |  |

Example: HERE BNN Jump

Before Instruction

PC address (HERE)

After Instruction

If Negative

address (Jump)

If Negative PC = address (HERE + 2)

| BNOV             | Branch i                                | f Not Ov  | erflow |      |  |
|------------------|---|---|--------|------|--|
| Syntax:          | BNOV n                                  | BNOV n  |        |      |  |
| Operands:        | -128 ≤ n ≤                              | -128 ≤ n ≤ 127  |        |      |  |
| Operation:       |   | if Overflow bit is '0' $(PC) + 2 + 2n \rightarrow PC$   |        |      |  |
| Status Affected: | None                                    |   |        |      |  |
| Encoding:        | 1110                                    | 0101  | nnnn   | nnnn |  |
| Description:     | program w<br>The 2's co<br>added to the | If the Overflow bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next |        |      |  |

instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |  |
|--------|--------------|---------|-----------|--|
| Decode | Read literal | Process | No        |  |
|        | 'n'          | Data    | operation |  |

Example: HERE BNOV Jump

Before Instruction

PC address (HERE)

After Instruction

If Overflow

address (Jump)

If Overflow PC address (HERE + 2) **BNZ Branch if Not Zero** 

BNZ n

Operands:  $-128 \le n \le 127$ Operation: if Zero bit is '0'

 $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0001 nnnn nnnn

Description: If the Zero bit is '0', then the program

will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next

instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity:

If Jump:

Syntax:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BNZ Jump

Before Instruction

PC address (HERE)

After Instruction

If Zero

address (Jump)

If Zero PC

address (HERE + 2)

#### **BRA Unconditional Branch**

Syntax: BRA

Operands:  $-1024 \le n \le 1023$ Operation:  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1101 0nnn nnnn nnnn

Description: Add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a two-cycle instruction.

Words: 2

Q Cycle Activity:

Cycles:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
| 'n'       |              | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

Example: HERE BRA Jump

Before Instruction

PC address (HERE)

After Instruction

PC address (Jump) **BSF** Bit Set f

BSF f, b {,a} Syntax: Operands:  $0 \le f \le 255$ 

 $0 \le b \le 7$ 

 $a \in [0,1]$ Operation:  $1 \rightarrow f < b >$ 

Status Affected: None

Encoding: 1000 bbba ffff ffff

Bit 'b' in register 'f' is set. Description:

If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the

GPR bank (default).

If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever  $f \le 95$  (5Fh). See Section 23.2.3 "Byte-Oriented and **Bit-Oriented Instructions in Indexed** 

Literal Offset Mode" for details.

Words: Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: BSF FLAG REG, 7, 1

Before Instruction

FLAG\_REG 0Ah

After Instruction

FLAG\_REG 8Ah

| BTFSC   | Bit Test Fi   | le, Skip if Cl  | ear  | BTF   | SS   | Bit Test Fi   | le, Skip if Se                        | t  |
|---|---|---|--|-------|--|---|---------------------------------------|--|
| Syntax:   | BTFSC f, b  | (,a)  |  | Synta | ax:  | BTFSS f, b  | {,a}                                  |  |
| Operands:   | $0 \le f \le 255$<br>$0 \le b \le 7$<br>$a \in [0,1]$   |   |  | Oper  | ands:  | $0 \le f \le 255$<br>$0 \le b < 7$<br>$a \in [0,1]$   |                                       |  |
| Operation:  | skip if (f <b>)</b>   | ) = 0   |  | Oper  | ation:   | skip if (f <b>)</b>   | = 1                                   |  |
| Status Affected:  | None  |   |  | Statu | s Affected:  | None  |                                       |  |
| Encoding:   | 1011  | bbba ff   | ff ffff  | Enco  | ding:  | 1010  | bbba ff                               | ff ffff  |
| Description:  | instruction is<br>the next instruction and a NOP is<br>this a two-cy<br>If 'a' is '0', the<br>GPR bank (or<br>If 'a' is '0' ar<br>set is enabled<br>Indexed Little<br>mode where<br>See Section<br>Bit-Oriented | s executed ins<br>cle instruction<br>the Access Banine BSR is used to<br>default).<br>In the extended<br>this instruct<br>that Offset Adding<br>ever f ≤ 95 (5F | "b' is 'o', then during the on is discarded tead, making .  k is selected. If o select the dinstruction ion operates in ressing h).  Oriented and in Indexed | Desc  | ription:   | instruction is<br>the next instruction instruction and a NOP in<br>this a two-cy<br>If 'a' is '0', the<br>'a' is '1', the<br>GPR bank (or<br>If 'a' is '0' ar<br>set is enable<br>in Indexed L<br>mode where<br>See Section<br>Bit-Orientee | BSR is used to                        | 'b' is '1', then I during the on is discarded tead, making it is selected. If it is select the id instruction ion operates diressing in).  Oriented and in Indexed |
| Words:  | 1   |   |  | Word  | s:   | 1   |                                       |  |
| Cycles:   |   | cles if skip and<br>2-word instruc  |  | Cycle | es:  |   | rcles if skip and<br>a 2-word instruc |  |
| Q Cycle Activity:   |   |   |  | Q C   | ycle Activity:   |   |                                       |  |
| Q1  | Q2  | Q3  | Q4   |       | Q1   | Q2  | Q3                                    | Q4   |
| Decode  | Read  | Process<br>Data   | No   |       | Decode   | Read  | Process<br>Data                       | No   |
| If skip:  | register 'f'  | Data  | operation  | lf sk | in:  | register 'f'  | Dala                                  | operation  |
| Q1  | Q2  | Q3  | Q4   |       | Q1   | Q2  | Q3                                    | Q4   |
| No  | No  | No  | No   |       | No   | No  | No                                    | No   |
| operation   | operation   | operation   | operation  |       | operation  | operation   | operation                             | operation  |
| If skip and followe   | ,   |   | _  | If sk | •  | d by 2-word ins   |                                       | _  |
| Q1  | Q2  | Q3  | Q4   |       | Q1   | Q2  | Q3                                    | Q4   |
| No operation  | No operation  | No operation  | No operation   |       | No operation   | No operation  | No operation                          | No operation   |
| No  | No  | No  | No   |       | No   | No  | No                                    | No   |
| operation   | operation   | operation   | operation  |       | operation  | operation   | operation                             | operation  |
| Example:  Before Instruction PC After Instruction If FLAG< PC | FALSE : TRUE : tion = add   |   | G, 1, 0  |       | Before Instruc<br>PC<br>After Instructic<br>If FLAG<<br>PC | FALSE : TRUE : tion = adc on 1> = 0; = adc  | rfss flag<br>dress (here)             | , 1, 0   |
| If FLAG<<br>PC  | :1> = 1;  | dress (FALSE  | )  |       | If FLAG<<br>PC   |   | lress (TRUE)                          |  |

| BTG              | Bit logg   | Bit Toggle f |      |      |  |
|------------------|--|--------------|------|------|--|
| Syntax:          | BTG f, b   | {,a}         |      |      |  |
| Operands:        | $0 \le f \le 255$<br>$0 \le b < 7$<br>$a \in [0,1]$  |              |      |      |  |
| Operation:       | $(\overline{f \mathord{<} b \mathord{>}}) \to f \mathord{<} b \mathord{>}$   |              |      |      |  |
| Status Affected: | None   |              |      |      |  |
| Encoding:        | 0111   | bbba         | ffff | ffff |  |
| Description:     | Bit 'b' in data memory location 'f' is inverted.  If 'a' is '0', the Access Bank is selected.  If 'a' is '1', the BSR is used to select the GPR bank (default).  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See  Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |              |      |      |  |
| Words:           | 1  |              |      |      |  |
| Cycles:          | 1  |              |      |      |  |

| Words:  | 1 |
|---------|---|
| Cycles: | 1 |
|         |   |

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: PORTC, 4, 0

Before Instruction:

PORTC = 0111 0101 [75h]

After Instruction:

PORTC = 0110 0101 **[65h]** 

#### **BOV Branch if Overflow**

BOV n

Operands:  $-128 \le n \le 127$ Operation: if Overflow bit is '1'

 $(PC) + 2 + 2n \rightarrow PC$ None

Encoding: 1110 0100 nnnn nnnn

Description: If the Overflow bit is '1', then the

program will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity:

If Jump:

Syntax:

Status Affected:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | 'n'          | Data    | operation |

Example: HERE BOV Jump

Before Instruction

PC address (HERE)

After Instruction

If Overflow

1; address (Jump) PC =

If Overflow PC =

address (HERE + 2)

| BZ | Branch if Zero |
|----|----------------|
|----|----------------|

BZ n Syntax: Operands:  $-128 \le n \le 127$ Operation: if Zero bit is '1'  $(PC) + 2 + 2n \rightarrow PC$ 

Status Affected: None

Encoding: 1110 0000 nnnn nnnn

Description: If the Zero bit is '1', then the program

will branch.

The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next

instruction, the new address will be PC + 2 + 2n. This instruction is then a

two-cycle instruction.

Words: 1 Cycles: 1(2)

Q Cycle Activity: If Jump:

| Q1        | Q2           | Q3        | Q4          |
|-----------|--------------|-----------|-------------|
| Decode    | Read literal | Process   | Write to PC |
|           | 'n'          | Data      |             |
| No        | No           | No        | No          |
| operation | operation    | operation | operation   |

If No Jump:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read literal | Process | No        |
|        | ʻn'          | Data    | operation |

Example: HERE BZJump

Before Instruction

PC address (HERE)

After Instruction

If Zero

address (Jump)

If Zero PC address (HERE + 2)

No operation operation

STATUSS = Status

| CALL  | Subroutine Call   |                             |                            |                   |
|---|---|-----------------------------|----------------------------|-------------------|
| Syntax:   | CALL k {  | ,s}                         |                            |                   |
| Operands:   | $0 \le k \le 10$ $s \in [0,1]$  | 48575                       |                            |                   |
| Operation:  | $ \begin{aligned} &(\text{PC}) + 4 \rightarrow \text{TOS}, \\ &k \rightarrow \text{PC} < 20:1 >, \\ &\text{if s} = 1 \\ &(\text{W}) \rightarrow \text{WS}, \\ &(\text{Status}) \rightarrow \text{STATUSS}, \\ &(\text{BSR}) \rightarrow \text{BSRS} \end{aligned} $ |                             |                            |                   |
| Status Affected:                                    | None  |                             |                            |                   |
| Encoding:<br>1st word (k<7:0>)<br>2nd word(k<19:8>) | 1110<br>1111  | 110s<br>k <sub>19</sub> kkk | k <sub>7</sub> kkk<br>kkkk | kkkk <sub>0</sub> |
| Description:  | Subroutine call of entire 2-Mbyte memory range. First, return address   |                             |                            |                   |

(PC + 4) is pushed onto the return stack. If 's' = 1, the W, Status and BSR registers are also pushed into their respective shadow registers, WS, STATUSS and BSRS. If 's' = 0, no update occurs (default). Then, the 20-bit value 'k' is loaded into PC<20:1>.

CALL is a two-cycle instruction.

Q3

Push PC to

stack

No

operation

Q4

Read literal

'k'<19:8>, Write to PC

No

operation

Words: 2 2 Cycles:

Q1

Decode

Q Cycle Activity:

| Example:          | HE   | RE      | CALL  | THERE,1 |
|-------------------|------|---------|-------|---------|
| Before Instruc    | tion |         |       |         |
| PC                | =    | address | (HERE | )       |
| After Instruction | n    |         |       |         |
| PC                | =    | address | (THER | E)      |
| TOS               | =    | address | (HERE | + 4)    |
| WS                | =    | W       |       |         |
| BSRS              | =    | BSR     |       |         |

Q2

Read literal

'k'<7:0>,

No

| CLRF             | Clear f   |  |  |   |
|------------------|---|--|--|---|
| Syntax:          | CLRF f {,a}   |  |  |   |
| Operands:        | $0 \le f \le 255$<br>$a \in [0,1]$  |  |  |   |
| Operation:       | $000h \rightarrow f$ $1 \rightarrow Z$  |  |  |   |
| Status Affected: | Z   |  |  |   |
| Encoding:        | 0110 10   | 1a   | ffff   | ffff  |
| Description:     | Clears the contregister.  If 'a' is '0', the A  If 'a' is '1', the B  GPR bank (def  If 'a' is '0' and t  set is enabled, in Indexed Lite mode wheneve  Section 23.2.3  Bit-Oriented In | Accestant). Sault). She exists in the exists of the exists | ss Bank is is used to set tended in instruction ffset Addres 95 (5Fh). | selected. select the struction operates essing See ed and |

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Literal Offset Mode" for details.

Example: CLRF FLAG\_REG, 1

Before Instruction

FLAG REG = 5Ah

After Instruction

 $FLAG_REG = 00h$ 

## CLRWDT Clear Watchdog Timer

Syntax: CLRWDT Operands: None

Operation:  $000h \rightarrow WDT$ ,

000h → WDT postscaler,

 $1 \to \overline{\frac{\text{TO}}{\text{PD}}}$ 

Status Affected:  $\overline{TO}$ ,  $\overline{PD}$ 

**Encoding:** 0000 0000 0000 0100

CLRWDT instruction resets the Watchdog Timer. It also resets the postscaler of the WDT. Status bits TO

and  $\overline{PD}$  are set.

Words: 1
Cycles: 1

Q Cycle Activity:

Description:

| Q1     | Q2        | Q3      | Q4        |
|--------|-----------|---------|-----------|
| Decode | No        | Process | No        |
|        | operation | Data    | operation |

Example: CLRWDT

Before Instruction

WDT Counter = ?

After Instruction

 $\begin{array}{lll} \text{WDT Counter} & = & 00\text{h} \\ \underline{\text{WDT Postscaler}} & = & 0 \\ \hline{\text{TO}} & = & 1 \end{array}$ 

PD = 1

| CO    | ИF             | Complement f   |               |      |                      |  |  |
|-------|----------------|--|---------------|------|----------------------|--|--|
| Synt  | ax:            | COMF f   | {,d {,a}}     |      |                      |  |  |
| Opei  | rands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |               |      |                      |  |  |
| Ope   | ration:        | $(\overline{f}) \hspace{0.1cm} 	o dest$  |               |      |                      |  |  |
| Statu | is Affected:   | N, Z   |               |      |                      |  |  |
| Enco  | oding:         | 0001   | 11da          | ffff | ffff                 |  |  |
| Desc  | pription:      | The contents of register 'f' are complemented. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |               |      |                      |  |  |
| Word  | ds:            | 1  |               |      |                      |  |  |
| Cycle | es:            | 1  | 1             |      |                      |  |  |
| QC    | ycle Activity: |  |               |      |                      |  |  |
|       | Q1             | Q2   | Q3            | 3    | Q4                   |  |  |
|       | Decode         | Read register 'f'  | Proce<br>Data |      | Write to destination |  |  |

| <u>Example:</u> | CC                 | OMF' | REG, | Ο, | 0 |
|-----------------|--------------------|------|------|----|---|
| Before Instru   | Before Instruction |      |      |    |   |
| REG             | =                  | 13h  |      |    |   |
| After Instruct  | tion               |      |      |    |   |
| REG             | =                  | 13h  |      |    |   |
| W               | =                  | ECh  |      |    |   |

| CPFSEQ             | -                                       | f with W,                                       | экір і   | rt = W            |
|--------------------|---|---|----------|-------------------|
| Syntax:            | CPFSEQ                                  | f {,a}  |          |                   |
| Operands:          | $0 \le f \le 255$<br>$a \in [0,1]$      |   |          |                   |
| Operation:         | (f) - (W),                              |   |          |                   |
| •                  | skip if $(f) =$                         | (W)<br>comparison)                              |          |                   |
| Status Affected:   | None                                    |   |          |                   |
| Encoding:          | 0110                                    | 001a f  | fff      | ffff              |
| Description:       | location 'f'                            | the contents<br>to the conter<br>an unsigned    | nts of V | V by              |
|                    | If 'f' = W, the discarded a instead, ma | nen the fetch<br>and a NOP is<br>aking this a t | ed inst  | ruction is<br>ted |
|                    | If 'a' is '1', t                        | he Access E<br>he BSR is u                      |          |                   |
|                    | GPR bank                                | (default).<br>Ind the exter                     | odod i∽  | ctruction         |
|                    |   | led, this inst                                  |          |                   |
|                    | in Indexed                              | Literal Offse                                   | t Addre  | essing            |
|                    |   | never f ≤ 95                                    |          |                   |
|                    |   | 3.2.3 "Byte-<br>ed Instruction                  |          |                   |
|                    |   | set Mode" f                                     |          |                   |
| Words:             | 1                                       |   |          |                   |
| Cycles:            | 1(2)                                    |   |          |                   |
| •                  |   | ycles if skip                                   | and fol  | lowed             |
|                    | by                                      | a 2-word ins                                    | tructio  | n.                |
| Q Cycle Activity:  |   |   |          |                   |
| Q1                 | Q2                                      | Q3  |          | Q4                |
| Decode             | Read                                    | Process   |          | No                |
| 16 -1 2-           | register 'f'                            | Data  | op       | eration           |
| If skip:           | 00                                      | 00  |          | 04                |
| Q1<br>No           | Q2<br>No                                | Q3<br>No  | 1        | Q4<br>No          |
| operation          | operation                               | operation                                       | or       | eration           |
| If skip and follow |   |   | 0        | oralion           |
| Q1                 | Q2                                      | Q3  |          | Q4                |
| No                 | No                                      | No  |          | No                |
| operation          | operation                               | operation                                       | op       | eration           |
| No                 | No                                      | No  |          | No                |
| operation          | operation                               | operation                                       | op       | eration           |
| Example:           | HERE<br>NEQUAL<br>EQUAL                 | CPFSEQ R:                                       | EG, 0    |                   |
| Before Instru      | ıction                                  |   |          |                   |
| PC Add             | dress = HE                              | RE  |          |                   |
| W                  | = ?                                     |   |          |                   |
| REG                | = ?                                     |   |          |                   |
| After Instruc      |   |   |          |                   |
| If REG             | = W<br>= Ac                             | ;<br>Idress (EQI                                |          |                   |
| PO                 |   |   | ΤΔ 1 . 1 |                   |

If REG

Address (NEQUAL)

#### **CPFSGT** Compare f with W, Skip if f > W Syntax: CPFSGT f {,a} Operands: $0 \le f \le 255$ $a \in [0,1]$ Operation: (f) - (W),skip if (f) > (W)(unsigned comparison) Status Affected: None Encodina: 0110 010a ffff ffff Compares the contents of data memory Description: location 'f' to the contents of the W by performing an unsigned subtraction. If the contents of 'f' are greater than the contents of WREG, then the fetched instruction is discarded and a NOP is executed instead, making this a two-cycle instruction.

GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever  $f \le 95$  (5Fh). See Section 23.2.3 "Byte-Oriented and

If 'a' is '0', the Access Bank is selected.

If 'a' is '1', the BSR is used to select the

**Bit-Oriented Instructions in Indexed** Literal Offset Mode" for details.

Words: Cycles: 1(2)

Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read         | Process | No        |
|        | register 'f' | Data    | operation |

If skip:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No        | No        | No        | No        |
| operation | operation | operation | operation |

If skip and followed by 2-word instruction:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No        | No        | No        | No        |
| operation | operation | operation | operation |
| No        | No        | No        | No        |
| operation | operation | operation | operation |

Example: HERE CPFSGT REG, 0

> NGREATER GREATER

Before Instruction

PC Address (HERE)

W ?

After Instruction

If REG W:

> Address (GREATER) PC =

If REG w. ≤

Address (NGREATER)

Syntax: CPFSLT f {,a} Operands:  $0 \le f \le 255$  $a \in [0,1]$ 

Operation: (f) - (W),skip if (f) < (W)

(unsigned comparison)

Status Affected: None

Encoding: ffff ffff 0110 000a

Description: Compares the contents of data memory location 'f' to the contents of W by performing an unsigned subtraction. If the contents of 'f' are less than the contents of W, then the fetched

instruction is discarded and a NOP is executed instead, making this a

two-cycle instruction.

If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the

GPR bank (default).

Words: 1

Cycles: 1(2)

> Note: 3 cycles if skip and followed

by a 2-word instruction.

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read         | Process | No        |
|        | register 'f' | Data    | operation |

If skip:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No        | No        | No        | No        |
| operation | operation | operation | operation |

If skip and followed by 2-word instruction:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No No     |           | No        | No        |
| operation | operation | operation | operation |
| No        | No        | No        | No        |
| operation | operation | operation | operation |

Example: HERE CPFSLT REG, 1

> NLESS LESS

Before Instruction

PC Address (HERE) =

After Instruction

If REG < W:

Address (LESS) PC =

If REG  $\geq$ W:

PC Address (NLESS)

| DAW               | Decimal A          | Adjust W R  | egist | ter        |  |
|-------------------|--------------------|---|-------|------------|--|
| Syntax:           | DAW                |   |       |            |  |
| Operands:         | None               |   |       |            |  |
| Operation:        | (W<3:0>) +<br>else | If [W<3:0> > 9] or [DC = 1] then (W<3:0>) + 6 $\rightarrow$ W<3:0>; else (W<3:0>) $\rightarrow$ W<3:0>;               |       |            |  |
|                   | (W<7:4>) +<br>else | If [W<7:4> + DC > 9] or [C = 1] then $(W<7:4>) + 6 + DC \rightarrow W<7:4>$ ; else $(W<7:4>) + DC \rightarrow W<7:4>$ |       |            |  |
| Status Affected:  | С                  |   |       |            |  |
| Encoding:         | 0000               | 0000 0  | 000   | 0111       |  |
|                   | variables (e       | om the earlie<br>each in pack<br>es a correct   | ed BC | D format)  |  |
| Words:            | 1                  |   |       |            |  |
| Cycles:           | 1                  |   |       |            |  |
| Q Cycle Activity: |                    |   |       |            |  |
| Q1                | Q2                 | Q3  | 1     | Q4         |  |
| Decode            | Read register W    | Process<br>Data   |       | Write<br>W |  |
| Example 1:        |                    | JI.   |       |            |  |
|                   | DAW                |   |       |            |  |
| Before Instruc    | tion               |   |       |            |  |
| W                 | = A5h              |   |       |            |  |
| C<br>DC           | = 0<br>= 0         |   |       |            |  |
| After Instruction | _ 0                |   |       |            |  |
| W                 | = 05h              |   |       |            |  |
| C<br>DC           | = 1                |   |       |            |  |
| Example 2:        | = 0                |   |       |            |  |
|                   | -                  |   |       |            |  |


Before Instruction W =

C = DC = After Instruction
W =

C DC CEh

34h

| DEC   | F              | Decrement f   |  |   |       |                     |  |  |
|-------|----------------|---|--|---|-------|---------------------|--|--|
| Synta | ax:            | DECF f {,d  | d {,a}}  |   |       |                     |  |  |
| Oper  | ands:          | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   | d ∈ [0,1]  |   |       |                     |  |  |
| Oper  | ation:         | $(f)-1 \to dest$  |  |   |       |                     |  |  |
| Statu | s Affected:    | C, DC, N, C   | C, DC, N, OV, Z  |   |       |                     |  |  |
| Enco  | ding:          | 0000  | 0000 01da ffff ffff  |   |       |                     |  |  |
| Desc  | ription:       | result is sto<br>result is sto<br>(default).<br>If 'a' is '0', t<br>If 'a' is '1', t<br>GPR bank<br>If 'a' is '0' a<br>set is enabl<br>in Indexed<br>mode wher<br>Section 23<br>Bit-Oriente | Decrement register 'f'. If 'd' is 'o', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' |   |       |                     |  |  |
| Word  | ls:            | 1   |  |   |       |                     |  |  |
| Cycle | es:            | 1   | 1  |   |       |                     |  |  |
| QC    | ycle Activity: |   |  |   |       |                     |  |  |
|       | Q1             | Q2  | Q3   | 3 |       | Q4                  |  |  |
|       | Decode         | Read register 'f'   | Proce<br>Data  |   | • • • | rite to<br>tination |  |  |



| DECFSZ   | Decrement f, Skip if 0                              |                                      | DCF               | SNZ  | Decrement f, Skip if not 0  |   |   |                      |  |
|--|---|--------------------------------------|-------------------|--|---|---|---|----------------------|--|
| Syntax:  | DECFSZ  | f {,d {,a}}                          |                   | Synt   | ax:   | DCFSNZ  | DCFSNZ f {,d {,a}}                                  |                      |  |
| Operands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$ |                                      |                   | Ope  | rands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$                 | $d \in [0,1]$                                       |                      |  |
| Operation:   | (f) $-1 \rightarrow de$ skip if result              | •                                    |                   | Ope  | ration:   | ` '   | (f) $-1 \rightarrow dest$ , skip if result $\neq 0$ |                      |  |
| Status Affected:   | None  |                                      |                   | Statu  | us Affected:  | None  |   |                      |  |
| Encoding:  | 0010  | 11da ff:                             | ff ffff           | Enco   | oding:  | 0100  | 0100 11da ffff f                                    |                      |  |
| Encoding:  Description:  The contents of register 'f' are decremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).  If the result is '0', the next instruction, which is already fetched, is discarded and a NOP is executed instead, making it a two-cycle instruction.  If 'a' is '0', the Access Bank is selected.  If 'a' is '1', the BSR is used to select the GPR bank (default).  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See  Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |   |                                      | cription:         | The contents of register 'f' are decremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If the result is not '0', the next instruction, which is already fetched, is discarded and a NOP is executed instead, making it a two-cycle instruction. If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |   |   |   |                      |  |
| Words:   | 1   |                                      |                   |  |   |   | set Mode" for                                       | details.             |  |
| Cycles:  Q Cycle Activity:   |   | cles if skip ar<br>2-word instru     |                   | Word<br>Cycl   |   | 1 1(2) Note: 3 cycles if skip and followed by a 2-word instruction. |   |                      |  |
| Q1   | Q2  | Q3                                   | Q4                | QC   | cycle Activity:   |   |   |                      |  |
| Decode   | Read  | Process                              | Write to          | ]  | Q1  | Q2  | Q3  | Q4                   |  |
|  | register 'f'  | Data                                 | destination       | ]  | Decode  | Read register 'f'   | Process<br>Data                                     | Write to destination |  |
| If skip:   |   |                                      | •                 | If sk  | (in:  | register i  | Dala  | uestination          |  |
| Q1   | Q2  | Q3                                   | Q4                | ]  | αρ.<br>Q1   | Q2  | Q3  | Q4                   |  |
| No operation   | No operation  | No operation                         | No operation      |  | No  | No.   | No  | No No                |  |
| If skip and follower   |   |                                      | operation         | I  | operation   | operation   | operation   | operation            |  |
| Q1   | Q2  | Q3                                   | Q4                | If sk  | ip and followe  | d by 2-word in  | struction:  |                      |  |
| No   | No  | No                                   | No                | ]  | Q1  | Q2  | Q3  | Q4                   |  |
| operation  | operation   | operation                            | operation         |  | No  | No  | No  | No                   |  |
| No   | No  | No                                   | No                |  | operation   | operation   | operation   | operation            |  |
| operation  | operation   | operation                            | operation         |  | No operation  | No operation  | No operation  | No operation         |  |
| Example:   | HERE<br>CONTINUE                                    | DECFSZ<br>GOTO                       | CNT, 1, 1<br>LOOP | <u>Exar</u>  | mple:   | HERE  |   | IP, 1, 0             |  |
| Before Instru  | ction   |                                      |                   |  |   |   | :   |                      |  |
| PC After Instructi CNT If CNT PC If CNT  | = Address on = CNT - 6 = 0; = Address ≠ 0;          | S (HERE)  1  S (CONTINUE S (HERE + 2 |                   |  | Before Instruction TEMP After Instruction TEMP If TEMP PC If TEMP | =   | ? TEMP - 1, 0; Address (:                           | ZERO)                |  |
| FC   | - Address   | • (11111/E + 2                       | · /               |  | PC  | =   | Address (1  | NZERO)               |  |

| GOTO  | Unconditional Branch   |                             |                            |  |
|---|--|-----------------------------|----------------------------|--|
| Syntax:   | GOTO k   |                             |                            |  |
| Operands:   | $0 \le k \le 10$   | 48575                       |                            |  |
| Operation:  | $k \rightarrow PC < 2$   | 20:1>                       |                            |  |
| Status Affected:                                    | None   |                             |                            |  |
| Encoding:<br>1st word (k<7:0>)<br>2nd word(k<19:8>) | 1110<br>1111   | 1111<br>k <sub>19</sub> kkk | k <sub>7</sub> kkk<br>kkkk | kkkk <sub>0</sub><br>kkkk <sub>8</sub> |
| Description:  | GOTO allows an unconditional branch anywhere within entire 2-Mbyte memory range. The 20-bit value 'k' is loaded into PC<20:1>. GOTO is always a two-cycle instruction. |                             |                            |  |
| Words:  | 2  |                             |                            |  |

Cycles: 2

Q Cycle Activity:

| Q1           | Q2                     | Q3              | Q4  |
|--------------|------------------------|-----------------|---|
| Decode       | Read literal 'k'<7:0>, | No<br>operation | Read literal<br>'k'<19:8>,<br>Write to PC |
| No operation | No<br>operation        | No operation    | No<br>operation                           |

Example: GOTO THERE

After Instruction

PC = Address (THERE)

| INCF   | ;             | Incremen  | t f           |     |   |                       |
|--------|---------------|---|---------------|-----|---|-----------------------|
| Synta  | X:            | INCF f {,d {,a}}  |               |     |   |                       |
| Opera  | ands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |               |     |   |                       |
| Opera  | ation:        | (f) + 1 $\rightarrow$ de  | est           |     |   |                       |
| Status | s Affected:   | C, DC, N,   | OV, Z         |     |   |                       |
| Encod  | ding:         | 0010  | 10da          | fff | f | ffff                  |
| Descr  | ription:      | The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |               |     |   |                       |
| Words  | S:            | 1   |               |     |   |                       |
| Cycle  | s:            | 1   |               |     |   |                       |
| Q Cy   | cle Activity: |   |               |     |   |                       |
| _      | Q1            | Q2  | Q3            |     |   | Q4                    |
|        | Decode        | Read register 'f'   | Proce<br>Data | -   |   | /rite to<br>stination |

| Example:  | II               | NCF                | CNT, | 1, | 0 |
|---|------------------|--------------------|------|----|---|
| Before Instru<br>CNT<br>Z<br>C<br>DC<br>After Instruc | =<br>=<br>=<br>= | FFh<br>0<br>?      |      |    |   |
| CNT<br>Z<br>C<br>DC                                   | = = =            | 00h<br>1<br>1<br>1 |      |    |   |

#### **INFSNZ** Increment f, Skip if not 0 **INCFSZ** Increment f, Skip if 0 Syntax: INFSNZ $f \{ d \{,a \} \}$ INCFSZ f {,d {,a}} Syntax: Operands: $0 \le f \le 255$ $0 \le f \le 255$ Operands: $d \in [0,1]$ $d \in [0,1]$ $a \in [0,1]$ $a \in [0,1]$ Operation: (f) + 1 $\rightarrow$ dest, (f) + 1 $\rightarrow$ dest, Operation: skip if result ≠ 0 skip if result = 0 Status Affected: None Status Affected: None Encoding: 0100 10da ffff ffff Encoding: 0011 11da ffff ffff Description: The contents of register 'f' are Description: The contents of register 'f' are incremented. If 'd' is '0', the result is incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). placed back in register 'f'. (default) If the result is not '0', the next If the result is '0', the next instruction, instruction, which is already fetched, is which is already fetched, is discarded discarded and a NOP is executed and a NOP is executed instead, making instead, making it a two-cycle it a two-cycle instruction. instruction. If 'a' is '0', the Access Bank is selected. If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the If 'a' is '1', the BSR is used to select the GPR bank (default). GPR bank (default). If 'a' is '0' and the extended instruction If 'a' is '0' and the extended instruction set is enabled, this instruction operates set is enabled, this instruction operates in Indexed Literal Offset Addressing in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See mode whenever $f \le 95$ (5Fh). See Section 23.2.3 "Byte-Oriented and Section 23.2.3 "Byte-Oriented and **Bit-Oriented Instructions in Indexed Bit-Oriented Instructions in Indexed** Literal Offset Mode" for details. Literal Offset Mode" for details. Words: Words: 1 Cycles: 1(2) 1(2) Cycles: Note: 3 cycles if skip and followed Note: 3 cycles if skip and followed by a 2-word instruction. by a 2-word instruction. Q Cycle Activity: Q Cycle Activity: Q1 Q2 Q3 Q4 Ω1 Q2 Q3 Q4 Write to Decode Read Process Decode Read **Process** Write to register 'f' Data destination register 'f' Data destination If skip: If skip: Q3 Q4 Q1 Q2 Q1 Q2 Q3 Ω4 Nο No No No No No No operation operation operation operation operation operation operation operation If skip and followed by 2-word instruction: If skip and followed by 2-word instruction: Q1 Q2 Q4 Q3 Q2 Q4 No No No No No Nο Nο Nο operation operation operation operation operation operation operation operation No No Nο Nο No No No operation operation operation operation operation operation operation operation Example: Example: HERE INCFSZ CNT, 1, 0 HERE INFSNZ REG, 1, 0 NZERO ZERO ZERO NZERO Before Instruction Before Instruction PC Address (HERE) PC Address (HERE) After Instruction After Instruction **CNT + 1** REG REG + 1 **CNT** If CNT If REG # 0: Address (ZERO) PC Address (NZERO) =

Address (NZERO)

If REG

PC

=

Address (ZERO)

| IORLW            | Inclusive OR Literal with W   |      |      |      |
|------------------|---|------|------|------|
| Syntax:          | IORLW k   |      |      |      |
| Operands:        | $0 \le k \le 255$   |      |      |      |
| Operation:       | (W) .OR. $k \rightarrow W$  |      |      |      |
| Status Affected: | N, Z  |      |      |      |
| Encoding:        | 0000  | 1001 | kkkk | kkkk |
| Description:     | The contents of W are ORed with the eight-bit literal 'k'. The result is placed in W. |      |      |      |
| Words:           | 1   |      |      |      |
| Cvcles:          | 1   |      |      |      |

Q Cycle Activity:

| Q1     | Q2          | Q3      | Q4         |
|--------|-------------|---------|------------|
| Decode | Read        | Process | Write to W |
|        | literal 'k' | Data    |            |

Example: IORLW 35h

Before Instruction

W 9Ah

After Instruction

W BFh

| IORWF            | Inclusive OR W with f  |
|------------------|--|
| Syntax:          | IORWF f {,d {,a}}  |
| Operands:        | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$  |
| Operation:       | (W) .OR. (f) $\rightarrow$ dest  |
| Status Affected: | N, Z   |
| Encoding:        | 0001 00da ffff ffff  |
|                  | '0', the result is placed in W. If 'd' is '1' the result is placed back in register 'f' (default).  If 'a' is '0', the Access Bank is selected if 'a' is '1', the BSR is used to select the GPR bank (default).  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See  Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |
| Words:           | 1  |
| Cycles:          | 1  |

Cycles:

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4          |
|--------|--------------|---------|-------------|
| Decode | Read         | Process | Write to    |
|        | register 'f' | Data    | destination |

Example: IORWF RESULT, 0, 1

Before Instruction

RESULT = 13h W 91h

After Instruction

13h RESULT = W 93h LFSR Load FSR

Syntax: LFSR f, k Operands:  $0 \le f \le 2$ 

 $\begin{array}{l} 0 \leq f \leq 2 \\ 0 \leq k \leq 4095 \end{array}$ 

Operation:  $k \to FSRf$ 

Status Affected: None

Description: The 12-bit literal 'k' is loaded into the File Select Register pointed to by 'f'.

Words: 2 Cycles: 2

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4            |
|--------|--------------|---------|---------------|
| Decode | Read literal | Process | Write         |
|        | 'k' MSB      | Data    | literal 'k'   |
|        |              |         | MSB to        |
|        |              |         | FSRfH         |
| Decode | Read literal | Process | Write literal |
|        | 'k' LSB      | Data    | 'k' to FSRfL  |

Example: LFSR 2, 3ABh

After Instruction

FSR2H = 03hFSR2L = ABh

| MOVF             | Move f   |      |      |      |
|------------------|--|------|------|------|
| Syntax:          | MOVF f {,d {,a}}   |      |      |      |
| Operands:        | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$                        |      |      |      |
| Operation:       | $f \to dest$   |      |      |      |
| Status Affected: | N, Z   |      |      |      |
| Encoding:        | 0101   | 00da | ffff | ffff |
| Description:     | The contents of register 'f' are moved to a destination dependent upon the |      |      |      |

a destination dependent upon the status of 'd'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). Location 'f' can be anywhere in the 256-byte bank.

If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the

GPR bank (default). If 'a' is '0' and the extended instruction

set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed

Literal Offset Mode" for details.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4      |
|--------|--------------|---------|---------|
| Decode | Read         | Process | Write W |
|        | register 'f' | Data    |         |

Example: MOVF REG, 0, 0

Before Instruction

REG = 22hW = FFh

After Instruction

REG = 22h W = 22h

| MOVFF  | Move f to  | o f              |              |                   |
|--|--|------------------|--------------|-------------------|
| Syntax:  | MOVFF f  | s,f <sub>d</sub> |              |                   |
| Operands:  | $0 \le f_s \le 4095$<br>$0 \le f_d \le 4095$   |                  |              |                   |
| Operation:   | $(f_s) \rightarrow f_d$  |                  |              |                   |
| Status Affected:                                     | None   |                  |              |                   |
| Encoding:<br>1st word (source)<br>2nd word (destin.) | 1100<br>1111   | ffff<br>ffff     | ffff<br>ffff | ffff <sub>s</sub> |
| Description:   | The contents of source register 'f <sub>s</sub> ' are moved to destination register 'f <sub>d</sub> '. |                  |              |                   |

Location of source ' $f_s$ ' can be anywhere in the 4096-byte data space (000h to FFFh) and location of destination 'fd' can also be anywhere from 000h to

Either source or destination can be W (a useful special situation). MOVFF is particularly useful for transferring a data memory location to a peripheral register (such as the transmit

buffer or an I/O port).

The MOVFF instruction cannot use the PCL, TOSU, TOSH or TOSL as the

destination register.

Words: 2 Cycles: 2 (3)

Q Cycle Activity:

| Q1     | Q2                                  | Q3              | Q4                              |
|--------|-------------------------------------|-----------------|---------------------------------|
| Decode | Read<br>register 'f'<br>(src)       | Process<br>Data | No<br>operation                 |
| Decode | No<br>operation<br>No dummy<br>read | No<br>operation | Write<br>register 'f'<br>(dest) |

Example: MOVFF REG1, REG2

Before Instruction

REG1 33h REG2 11h

After Instruction

REG1 REG2 33h 33h

| MOVLB             | Move Lite  | eral to Lo              | ow Nibbl                 | e in BSR  |  |
|-------------------|--|-------------------------|--------------------------|-----------|--|
| Syntax:           | MOVLW  | k                       |                          |           |  |
| Operands:         | $0 \le k \le 25$                                   | 5                       |                          |           |  |
| Operation:        | $k\to BSR$   |                         |                          |           |  |
| Status Affected:  | None   |                         |                          |           |  |
| Encoding:         | 0000   | 0001                    | kkkk                     | kkkk      |  |
| Description:      | The eight-<br>Bank Sele<br>of BSR<7:<br>regardless | ct Registe<br>4> always | er (BSR). 1<br>s remains | The value |  |
| Words:            | 1  |                         |                          |           |  |
| Cycles:           | 1  |                         |                          |           |  |
| Q Cycle Activity: |  |                         |                          |           |  |
| Q1                | Q2   | Q3                      | 3                        | Q4        |  |

| <u> </u> | Q2          | ŲЗ      | Q4            |
|----------|-------------|---------|---------------|
| Decode   | Read        | Process | Write literal |
|          | literal 'k' | Data    | 'k' to BSR    |

Example: MOVLB

Before Instruction

BSR Register = 02h After Instruction BSR Register = 05h

MOVLW Move Literal to W

Syntax: MOVLW k

Operands:  $0 \le k \le 255$ Operation:  $k \to W$ 

Status Affected: None

Encoding: 0000 1110 kkkk kkkk

Description: The eight-bit literal 'k' is loaded into W.

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2          | Q3      | Q4         |
|--------|-------------|---------|------------|
| Decode | Read        | Process | Write to W |
|        | literal 'k' | Data    |            |

Example: MOVLW 5Ah

After Instruction

W = 5Ah

MOVWF Move W to f

Syntax: MOVWF f {,a}

 $0 \le f \le 255$ a  $\in [0,1]$ 

Operation:  $(W) \rightarrow f$ Status Affected: None

Operands:

Encoding: 0110 111a ffff ffff

Description: Move data from W to register 'f'.

Location 'f' can be anywhere in the

256-byte bank.

If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the

GPR bank (default).

If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed

Literal Offset Mode" for details.

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: MOVWF REG, 0

Before Instruction

W = 4Fh REG = FFh

After Instruction

W = 4FhREG = 4Fh

| MULLW            | Multiply   | Literal v  | vith W   |   |
|------------------|--|--|--|---|
| Syntax:          | MULLW  | k  |  |   |
| Operands:        | $0 \le k \le 25$   | 5  |  |   |
| Operation:       | (W) $x k \rightarrow$  | PRODH:   | PRODL  |   |
| Status Affected: | None   |  |  |   |
| Encoding:        | 0000   | 1101   | kkkk   | kkkk  |
| Description:     | An unsign out betwee 8-bit litera placed in I PRODH of W is unch None of th Note that possible in is possible in the state of the state | en the cor<br>I 'k'. The 'PRODH:Pontains the<br>anged.<br>he status for neither over this open | ntents of V<br>16-bit resu<br>RODL reg<br>e high byt<br>lags are a<br>rerflow not<br>ration. A z | V and the alt is gister pair. te.  affected. r carry is |

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2                  | Q3              | Q4              |
|--------|---------------------|-----------------|-----------------|
| Decode | Read<br>literal 'k' | Process<br>Data | Write registers |
|        |                     |                 | PRODH:          |
|        |                     |                 | PRODL           |

Example: MULLW 0C4h

Before Instruction

W = E2h
PRODH = ?
PRODL = ?

After Instruction

W = E2h PRODH = ADh PRODL = 08h

**MULWF** Multiply W with f Svntax: MULWF f {,a}  $0 \le f \le 255$ Operands:  $a \in [0,1]$ (W)  $x(f) \rightarrow PRODH:PRODL$ Operation: Status Affected: None Encoding: 0000 001a ffff ffff An unsigned multiplication is carried Description: out between the contents of W and the

register file location 'f'. The 16-bit result is stored in the PRODH:PRODL register pair. PRODH contains the high byte. Both W and 'f' are unchanged.

None of the status flags are affected.

Note that neither overflow nor carry is possible in this operation. A zero result is possible but not detected.

result is possible but not detected. If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3

"Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4        |
|--------|--------------|---------|-----------|
| Decode | Read         | Process | Write     |
|        | register 'f' | Data    | registers |
|        |              |         | PRODH:    |
|        |              |         | PRODL     |

Example: MULWF REG, 1

Before Instruction

W = C4h REG = B5h PRODH = ? PRODL = ?

After Instruction

W = C4h REG = B5h PRODH = 8Ah PRODL = 94h

| NEGF             | Negate f  |
|------------------|---|
| Syntax:          | NEGF f {,a}   |
| Operands:        | $0 \le f \le 255$<br>$a \in [0,1]$  |
| Operation:       | $(\overline{f}) + 1 \rightarrow f$  |
| Status Affected: | N, OV, C, DC, Z   |
| Encoding:        | 0110 110a ffff ffff   |
| Description:     | Location 'f' is negated using two's complement. The result is placed in the data memory location 'f'. |

If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing

mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4           |
|--------|--------------|---------|--------------|
| Decode | Read         | Process | Write        |
|        | register 'f' | Data    | register 'f' |

Example: NEGF REG, 1

Before Instruction

REG = 0011 1010 [3Ah]

After Instruction

REG = 1100 0110 [C6h]

| NOF   | •                          | No Operation                               |              |   |    |               |  |
|-------|----------------------------|--|--------------|---|----|---------------|--|
| Synta | ax:                        | NOP  | NOP          |   |    |               |  |
| Oper  | ands:                      | None                                       |              |   |    |               |  |
| Oper  | ation:                     | No operat                                  | ion          |   |    |               |  |
| Statu | s Affected:                | None                                       |              |   |    |               |  |
| Enco  | ding:                      | 0000 0000 0000 0000<br>1111 xxxx xxxx xxxx |              |   |    |               |  |
| Desc  | Description: No operation. |  |              |   |    |               |  |
| Word  | ls:                        | 1  |              |   |    |               |  |
| Cycle | es:                        | 1  |              |   |    |               |  |
| QC    | ycle Activity:             |  |              |   |    |               |  |
|       | Q1                         | Q2   | Q            | 3 |    | Q4            |  |
|       | Decode                     | No<br>operation                            | No<br>operat |   | or | No<br>eration |  |

Example:

None.

| POP | Pop Top of Return Stack |
|-----|-------------------------|
|-----|-------------------------|

Syntax: POP
Operands: None

Operation:  $(TOS) \rightarrow bit bucket$ 

Status Affected: None

Encoding: 0000 0000 0000 0110

The TOS value is pulled off the return stack and is discarded. The TOS value then becomes the previous value that was pushed onto the return stack. This instruction is provided to enable the user to properly manage the return stack to incorporate a software stack.

Words: 1 Cycles: 1

Q Cycle Activity:

Description:

| Q1     | Q2        | Q3      | Q4        |
|--------|-----------|---------|-----------|
| Decode | No        | POP TOS | No        |
|        | operation | value   | operation |

Example: POP GOTO

GOTO NEW Before Instruction

TOS = 0031A2h

Stack (1 level down) = 014332h

After Instruction

TOS = 014332h PC = NEW PUSH Push Top of Return Stack

Syntax: PUSH Operands: None

Operation:  $(PC + 2) \rightarrow TOS$ 

Status Affected: None

**Encoding**: 0000 0000 0000 0101

Description:

The PC + 2 is pushed onto the top of the return stack. The previous TOS value is pushed down on the stack.

This instruction allows implementing a software stack by modifying TOS and then pushing it onto the return stack.

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3        | Q4        |
|--------|--------------|-----------|-----------|
| Decode | PUSH         | No        | No        |
|        | PC + 2 onto  | operation | operation |
|        | return stack |           |           |

Example: PUSH

Before Instruction

TOS = 345Ah PC = 0124h

After Instruction

PC = 0126h TOS = 0126h Stack (1 level down) = 345Ah

| RCALL            | Relative Call   |      |      |      |
|------------------|---|------|------|------|
| Syntax:          | RCALL n   |      |      |      |
| Operands:        | $-1024 \le n \le 1023$  |      |      |      |
| Operation:       | $ (PC) + 2 \rightarrow TOS, $ $ (PC) + 2 + 2n \rightarrow PC $  |      |      |      |
| Status Affected: | None  |      |      |      |
| Encoding:        | 1101  | 1nnn | nnnn | nnnn |
| Description:     | Subroutine call with a jump up to 1K from the current location. First, return address (PC+2) is pushed onto the |      |      |      |

from the current location. First, return address (PC+2) is pushed onto the stack. Then, add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC+2+2n. This instruction is a

two-cycle instruction.

Words: 1 Cycles: 2

Q Cycle Activity:

|   | Q1        | Q2               | Q3              | Q4          |
|---|-----------|------------------|-----------------|-------------|
|   | Decode    | Read literal 'n' | Process<br>Data | Write to PC |
|   |           | Push PC to stack |                 |             |
| ſ | No        | No               | No              | No          |
|   | operation | operation        | operation       | operation   |

Example: HERE RCALL Jump

Before Instruction

PC = Address (HERE)

After Instruction

PC = Address (Jump) TOS = Address (HERE + 2)

| RESET            | Reset  |      |      |      |
|------------------|--|------|------|------|
| Syntax:          | RESET  |      |      |      |
| Operands:        | None   |      |      |      |
| Operation:       | Reset all registers and flags that are affected by a MCLR Reset.     |      |      |      |
| Status Affected: | All  |      |      |      |
| Encoding:        | 0000   | 0000 | 1111 | 1111 |
| Description:     | This instruction provides a way to execute a MCLR Reset in software. |      |      |      |

Words: 1
Cycles: 1

Q Cycle Activity:

| Q1     | Q2    | Q3        | Q4        |
|--------|-------|-----------|-----------|
| Decode | Start | No        | No        |
|        | Reset | operation | operation |

Example: RESET

After Instruction

Registers = Reset Value Flags\* = Reset Value

#### **RETFIE Return from Interrupt**

Syntax: RETFIE {s} Operands:  $s \in [0,1]$ Operation:  $(TOS) \rightarrow PC$ ,

1 → GIE/GIEH or PEIE/GIEL,

if s = 1 $(WS) \rightarrow W$ ,

(STATUSS) → Status,  $(BSRS) \rightarrow BSR,$ 

PCLATU, PCLATH are unchanged.

Status Affected: GIE/GIEH, PEIE/GIEL.

Encoding: 0000 0000 0001 000s

Description: Return from Interrupt. Stack is popped and Top-of-Stack (TOS) is loaded into the PC. Interrupts are enabled by setting either the high or low priority global interrupt enable bit. If 's' = 1, the contents of the shadow registers WS,

STATUSS and BSRS are loaded into their corresponding registers, W, Status and BSR. If 's' = 0, no update of these registers occurs (default).

Words: 2 Cycles:

Q Cycle Activity:

| Q1        | Q2        | Q3        | Q4                  |
|-----------|-----------|-----------|---------------------|
| Decode    | No        | No        | POP PC              |
|           | operation | operation | from stack          |
|           |           |           | Set GIEH or<br>GIEL |
| No        | No        | No        | No                  |
| operation | operation | operation | operation           |

Example: RETFIE 1

After Interrupt

PC W TOS WS BSRS BSR **STATUSS** Status

GIE/GIEH, PEIE/GIEL

#### **RETLW** Return Literal to W

RETLW k Syntax: Operands:  $0 \le k \le 255$ Operation:  $k \rightarrow W$ ,  $(TOS) \rightarrow PC$ 

PCLATU, PCLATH are unchanged

Status Affected: None

Encoding: 0000 1100 kkkk kkkk W is loaded with the eight-bit literal 'k'. Description:

The program counter is loaded from the top of the stack (the return address). The high address latch (PCLATH)

remains unchanged.

Words: Cycles: 2

Q Cycle Activity:

| Q1           | Q2           | Q3           | Q4                        |
|--------------|--------------|--------------|---------------------------|
| Decode       | Read         | Process      | POP PC                    |
|              | literal 'k'  | Data         | from stack,<br>Write to W |
| No operation | No operation | No operation | No operation              |

#### Example:

```
CALL TABLE ; W contains table
           ; offset value
           ; W now has
           ; table value
```

TABLE

; W = offset ADDWF PCL RETLW k0 ; Begin table RETLW k1

RETLW kn ; End of table

Before Instruction

W 07h

After Instruction

W value of kn

# Syntax: RETURN $\{s\}$ Operands: $s \in [0,1]$ Operation: $(TOS) \rightarrow PC$ , if s = 1

 $\begin{aligned} & (\text{WS}) \to \text{W}, \\ & (\text{STATUSS}) \to \text{Status}, \\ & (\text{BSRS}) \to \text{BSR}, \end{aligned}$ 

**Return from Subroutine** 

PCLATU, PCLATH are unchanged

Status Affected: None

**RETURN** 

Encoding: 0000 0000 0001 001s

Description: Return from subroutine. The stack is

Return from subroutine. The stack is popped and the top of the stack (TOS) is loaded into the program counter. If 's'= 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers, W, Status and BSR. If 's' = 0, no update of these registers

occurs (default).

Words: 1 Cycles: 2

Q Cycle Activity:

| Q1        | Q2        | Q3        | Q4         |
|-----------|-----------|-----------|------------|
| Decode    | No        | Process   | POP PC     |
|           | operation | Data      | from stack |
| No        | No        | No        | No         |
| operation | operation | operation | operation  |

Example: RETURN

After Instruction: PC = TOS

| RLCF             | Rotate Left f through Carry   |  |  |
|------------------|---|--|--|
| Syntax:          | RLCF f {,d {,a}}  |  |  |
| Operands:        | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |  |  |
| Operation:       | $(f) \rightarrow dest,  (f<7>) \rightarrow C,  (C) \rightarrow dest<0>$   |  |  |
| Status Affected: | C, N, Z   |  |  |
| Encoding:        | 0011 01da ffff ffff   |  |  |
|                  | one bit to the left through the Carry flag. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |  |  |
| Words:           | 1   |  |  |

Q Cycle Activity:

Cycles:

| Q1     | Q2           | Q3      | Q4          |
|--------|--------------|---------|-------------|
| Decode | Read         | Process | Write to    |
|        | register 'f' | Data    | destination |

Example: RLCF REG, 0, 0

Before Instruction

REG = 1110 0110 C = 0

After Instruction

REG = 1110 0110 W = 1100 1100 C = 1

| RLNCF             | Rotate Left f (no   | carry)   | RRCF              | Rotate Ri   | ght f throug  | h Carry  |
|-------------------|---|--|-------------------|---|---|--|
| Syntax:           | RLNCF f {,d {,a}}   |  | Syntax:           | RRCF f {,   | d {,a}}   |  |
| Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |  | Operands:         | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |   |  |
| Operation:        | $(f) \rightarrow dest(f<7>) \rightarrow dest<0>$  | >,   | Operation:        | $ (f < n >) \rightarrow de $ $ (f < 0 >) \rightarrow C $  | ,   |  |
| Status Affected:  | N, Z  |  |                   | $(C) \rightarrow dest$  |   |  |
| Encoding:         | 0100 01da   | ffff ffff  | Status Affected:  | C, N, Z   |   |  |
| Description:      | The contents of regi  | ster 'f' are rotated   | Encoding:         | 0011  | 00da ff   | ff ffff  |
|                   | one bit to the left. If is placed in W. If 'd' stored back in regist If 'a' is '0', the Acces If 'a' is '1', the BSR is GPR bank (default). If 'a' is '0' and the exset is enabled, this in Indexed Literal Of mode whenever f < Section 23.2.3 "By Bit-Oriented Instru Literal Offset Mode | is '1', the result is<br>ter 'f' (default).<br>s Bank is selected.<br>s used to select the<br>ktended instruction<br>instruction operates<br>ifset Addressing<br>95 (5Fh). See<br>te-Oriented and<br>ctions in Indexed | Description:      | one bit to the flag. If 'd' is '1', the register 'f' (If 'a' is '0', the flag is '1', the GPR bank If 'a' is '0' at set is enable in Indexed mode where Section 23 Bit-Orientes | he result is pla<br>default).<br>he Access Ba<br>he BSR is use<br>(default).<br>nd the extend | h the Carry is placed in W. aced back in  nk is selected. d to select the ed instruction ction operates Addressing Fh). See iented and is in Indexed |
| Words:            | 1   |  |                   | C C   | → registe   | r f 🗡  |
| Cycles:           | 1   |  | VA/ I -           |   |   |  |
| Q Cycle Activity: |   |  | Words:            | 1   |   |  |
| Q1                | Q2 Q3   | Q4   | Cycles:           | 1   |   |  |
| Decode            | Read Proces   | ss Write to  | Q Cycle Activity: |   |   |  |
|                   | register 'f' Data   | destination  | Q1                | Q2  | Q3  | Q4   |
| Example:          | RLNCF REG,  | 1, 0   | Decode            | Read<br>register 'f'  | Process<br>Data   | Write to destination   |
| Before Instru     | ction   |  |                   |   |   |  |
| REG               | = 1010 1011   |  | Example:          | RRCF  | REG, 0,   | 0  |
| After Instruct    |   |  | Before Instruc    | tion  |   |  |
| REG               | = 0101 0111   |  | REG<br>C          | = 1110 0<br>= 0   | 0110  |  |
|                   |   |  | After Instruction |   | 1110  |  |
|                   |   |  | W<br>C            | = 1110 C<br>= 0111 C<br>= 0   |   |  |

Set f

**SETF** 

#### **RRNCF** Rotate Right f (no carry) Syntax: RRNCF f {,d {,a}} $0 \le f \le 255$ Operands: $d \in [0,1]$ $a\in \left[ 0,1\right]$ Operation: $(f < n >) \rightarrow dest < n - 1 >$ , $(f<0>) \rightarrow dest<7>$ Status Affected: N, Z Encoding: 0100 00da ffff ffff The contents of register 'f' are rotated Description: one bit to the right. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Section 23.2.3 "Byte-Oriented and **Bit-Oriented Instructions in Indexed** Literal Offset Mode" for details. register f Words: 1 Cycles: 1

Q3

**Process** 

Data

REG, 1, 0

Q4

Write to

destination

| Synta | ax:            | SETF f {,a}   |               |          |                     |
|-------|----------------|---|---------------|----------|---------------------|
| Oper  | ands:          | $0 \le f \le 255$ $a \in [0,1]$   |               |          |                     |
| Oper  | ation:         | $FFh \to f$   |               |          |                     |
| Statu | s Affected:    | None  |               |          |                     |
| Enco  | oding:         | 0110  | 100a          | ffff     | ffff                |
| Desc  | cription:      | The contents of the specified register are set to FFh.  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See  Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |               |          |                     |
| Word  | ds:            | 1   |               |          |                     |
| Cycle | es:            | 1   |               |          |                     |
| QC    | ycle Activity: |   |               |          |                     |
|       | Q1             | Q2  | Q3            | <u> </u> | Q4                  |
|       | Decode         | Read register 'f'   | Proce<br>Data |          | Write<br>gister 'f' |
| _     |                |   |               |          |                     |

Example: SETF REG, 1

Before Instruction

REG = 5Ah

 $\begin{array}{ccc} \text{After Instruction} & & \\ \text{REG} & = & \text{FFh} \end{array}$ 

REG = 1110 1011

Example 2: RRNCF REG, 0, 0

Before Instruction

Q2

Read

register 'f'

RRNCF

1101 0111

Q Cycle Activity:

Example 1:

Q1

Decode

Before Instruction REG =

After Instruction

W = ? REG = 1101 0111

After Instruction

W = 1110 1011 REG = 1101 0111

| SLE                     | EP   | Enter Sleep mode    |                       |                   |                |
|-------------------------|--|---------------------|-----------------------|-------------------|----------------|
| Synta                   | ax:  | SLEEP               |                       |                   |                |
| Oper                    | ands:  | None                |                       |                   |                |
| Oper                    | ation:   |                     | $0 \to \overline{PD}$ |                   |                |
| Status Affected: TO, PD |  |                     |                       |                   |                |
| Enco                    | ding:  | 0000 0000 0000 0011 |                       |                   | 0011           |
| Desc                    | Description:  The Power-down status bit (PD) is cleared. The Time-out status bit (T is set. Watchdog Timer and its postscaler are cleared.  The processor is put into Sleep mowith the oscillator stopped. |                     |                       | us bit (TO) d its |                |
| Word                    | ls:  | 1                   |                       |                   |                |
| Cycle                   | es:  | 1                   |                       |                   |                |
| QC                      | ycle Activity:   |                     |                       |                   |                |
|                         | Q1   | Q2                  | Q3                    |                   | Q4             |
|                         | Decode   | No operation        | Proces<br>Data        |                   | Go to<br>Sleep |

 $\begin{array}{lll} \underline{\text{Example:}} & & \text{SLEEP} \\ & & \underline{\text{Before Instruction}} \\ & \underline{\overline{\text{TO}}} & = & ? \\ & \underline{\text{PD}} & = & ? \\ & \\ & \underline{\text{After Instruction}} \\ & \underline{\overline{\text{TO}}} & = & 1 \uparrow \\ & \underline{\text{PD}} & = & 0 \\ \end{array}$ 

† If WDT causes wake-up, this bit is cleared.

| SUBFWB   | Subtract  | f from W wi                       | th Borrow            |  |
|--|---|-----------------------------------|----------------------|--|
| Syntax:  | SUBFWB  | f {,d {,a}}                       |                      |  |
| Operands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$ |                                   |                      |  |
| Operation:   | (W) - (f) -   | $(\overline{C}) \rightarrow dest$ |                      |  |
| Status Affected:   | N, OV, C,   | DC, Z                             |                      |  |
| Encoding:  | 0101  | 01da ffi                          | ff ffff              |  |
| Encoding:  0101  01da  ffff  ffff  Subtract register 'f' and Carry flag (borrow) from W (2's complement method). If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored in register 'f' (default).  If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).  If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3  "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details. |   |                                   |                      |  |
| Words:   | 1   |                                   |                      |  |
| Cycles:  | 1   |                                   |                      |  |
| Q Cycle Activity:  |   |                                   |                      |  |
| Q1   | Q2  | Q3                                | Q4                   |  |
| Decode   | Read register 'f'                                   | Process<br>Data                   | Write to destination |  |
| Example 1:  Before Instruction   | SUBFWB ction = 3                                    | REG, 1, 0                         |                      |  |
| W<br>C<br>After Instructi<br>REG<br>W<br>C<br>Z<br>N   | = FF<br>= 2<br>= 0<br>= 0                           | sult is negative                  | e                    |  |
| Example 2:   | SUBFWB  | REG, 0, 0                         |                      |  |
| Before Instruc<br>REG<br>W<br>C<br>After Instructi<br>REG<br>W<br>C<br>Z   | = 2<br>= 5<br>= 1                                   |                                   |                      |  |
| N  | -   | sult is positive                  |                      |  |
| Example 3:   | SUBFWB  | REG, 1, 0                         |                      |  |
| Before Instruct<br>REG<br>W<br>C<br>After Instructi<br>REG<br>W  | = 1<br>= 2<br>= 0<br>on<br>= 0<br>= 2               |                                   |                      |  |
| C<br>Z<br>N  | = 1<br>= 1 ; re<br>= 0                              | sult is zero                      |                      |  |

| SUBLW                      | Subtract W from Literal                             | SUBWF   | Subtract  | W from f                       |                             |
|----------------------------|---|---|---|--------------------------------|-----------------------------|
| Syntax:                    | SUBLW k   | Syntax:   | SUBWF   | f {,d {,a}}                    |                             |
| Operands:                  | $0 \le k \le 255$                                   | Operands:   | $0 \le f \le 255$   | 5                              |                             |
| Operation:                 | $k-(W)\to W$  |   | $d \in [0,1]$   |                                |                             |
| Status Affected:           | N, OV, C, DC, Z                                     | Operation:  | $a \in [0,1]$   | \ dost                         |                             |
| Encoding:                  | 0000 1000 kkkk kk                                   | Status Affected:  | (f) – (W) –<br>N, OV, C,  |                                |                             |
| Description                | W is subtracted from the eight-bit                  | Encoding:   | 0101  | 11da ff                        | ff ffff                     |
|                            | literal 'k'. The result is placed in V              | Description:  | <u> </u>  | V from registe                 |                             |
| Words:                     | 1   | Description.  |   | ent method). If                |                             |
| Cycles:                    | 1   |   |   | ored in W. If                  | •                           |
| Q Cycle Activity:          |   |   | result is st<br>(default).  | ored back in r                 | egister T                   |
| Q1                         | Q2 Q3 Q4  |   | Ìf 'a' is 'o',  | the Access B                   |                             |
| Decode                     | Read Process Write to literal 'k' Data              |   |   | If 'a' is '1', the he GPR bank |                             |
| Example 1:                 | SUBLW 02h   |   |   |                                | led instruction             |
| Before Instruc             |   |   |   | bled, this instr               |                             |
| W                          | = 01h   |   | •   | n Indexed Lite<br>g mode when  |                             |
| C<br>After Instruction     | = ?<br>on   |   |   | n). See Section                |                             |
| W<br>C                     | = 01h<br>= 1 ; result is positive                   |   |   | ented and Bit<br>ns in Indexed | -Oriented<br>Literal Offset |
| Z                          | = 0   |   | Mode" for   |                                | Zitorai Orioot              |
| N<br>Evennes 2:            | = 0   | Words:  | 1   |                                |                             |
| Example 2:                 | SUBLW 02h   | Cycles:   | 1   |                                |                             |
| Before Instruc             | = 02h   | Q Cycle Activity:   |   |                                |                             |
| C<br>After Instruction     | = ?<br>on   | Q1  | Q2  | Q3                             | Q4                          |
| W<br>C                     | = 00h   | Decode  | Read register 'f'   | Process<br>Data                | Write to destination        |
| Z                          | = 1   |   | <u> </u>  |                                | destination                 |
| N<br>Everyoria 2:          | = 0   | Example 1:<br>Before Instruc  | SUBWF   | REG, 1, 0                      |                             |
| Example 3:                 | SUBLW 02h   | REG   | = 3   |                                |                             |
| Before Instruc             | = 03h   | W<br>C  | = 2<br>= ?  |                                |                             |
| С                          |   | After Instructi   |   |                                |                             |
|                            | = ?   | REG   |   |                                |                             |
| After Instruction          | on<br>= FFh; (2's complement)                       | REG<br>W  | = 1<br>= 2  | anda ia manisino               |                             |
| After Instruction          | on  |   | = 1<br>= 2  | sult is positive               | )                           |
| After Instructio<br>W<br>C | on = FFh; (2's complement) = 0; result is negative  | W<br>C<br>Z<br>N  | = 1<br>= 2<br>= 1 ; re<br>= 0<br>= 0  | ·                              | )                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W<br>C<br>Z<br>N<br>Example 2:  | = 1<br>= 2<br>= 1 ; re<br>= 0<br>= 0  | REG, 0, 0                      | ÷                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W<br>C<br>Z<br>N<br><u>Example 2:</u><br>Before Instruc<br>REG  | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF  | ·                              | 3                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W<br>C<br>Z<br>N<br><u>Example 2:</u><br>Before Instruc   | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF  | ·                              | <del>)</del>                |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N Example 2: Before Instruction REG W C After Instruction   | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>Ction<br>= 2<br>= 2<br>= ?  | ·                              | 3                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N N Example 2: Before Instruct REG W C C After Instructi REG W  | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>Ction<br>= 2<br>= ?<br>on<br>= 2<br>= ?   | REG, 0, 0                      | 3                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N N Example 2: Before Instructi REG W C After Instructi REG   | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>Ction<br>= 2<br>= ?<br>on<br>= 2<br>= ?   | ·                              |                             |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N Example 2:  Before Instruct REG W C After Instructi REG W C Z N   | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>ction<br>= 2<br>= 2<br>= ?<br>on<br>= 2<br>= 0<br>= 1; re<br>= 1                            | REG, 0, 0                      | 3                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N N Example 2:  Before Instruct REG W C After Instructi REG W C Z N Example 3:  | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>Ction<br>= 2<br>= 2<br>= ?<br>on<br>= 2<br>= 0<br>= 1; re<br>= 1<br>= 0                     | REG, 0, 0                      |                             |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N Example 2:  Before Instruct REG W C After Instructi REG W C Z N Example 3:  Before Instruct REG   | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>ction<br>= 2<br>= 2<br>= ?<br>on<br>= 2<br>= 0<br>= 1; re<br>= 1<br>= 0<br>SUBWF            | REG, 0, 0                      |                             |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N Example 2:  Before Instruct REG W C After Instructi REG W C Z N Example 3:  Before Instruct   | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>ction<br>= 2<br>= 2<br>= ?<br>on<br>= 2<br>= 0<br>= 1; re<br>= 1<br>= 0<br>SUBWF            | REG, 0, 0                      | 3                           |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N  Example 2:  Before Instruct REG W C After Instructi REG W C Z N  Example 3:  Before Instruct REG W C After Instructi REG W C After Instructi REG A W C After Instructi REG W C After Instructi | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>Ction<br>= 2<br>= 2<br>= ?<br>on<br>= 1; re<br>= 1<br>= 0<br>SUBWF                          | REG, 0, 0                      |                             |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N Example 2:  Before Instruct REG W C After Instructi REG W C Z N  Example 3:  Before Instruct REG W C After Instructi REG W C Z N  | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>Ction<br>= 2<br>= 2<br>= ?<br>on<br>= 1; re<br>= 1<br>= 0<br>SUBWF                          | REG, 0, 0                      |                             |
| After Instruction W C Z    | FFh; (2's complement)  = 0; result is negative  = 0 | W C Z N Example 2:  Before Instruct REG W C After Instructi REG W C Z N Example 3:  Before Instruct REG W C After Instructi REG W C After Instructi REG W C After Instructi REG REG REG REG REG         | = 1<br>= 2<br>= 1; re<br>= 0<br>= 0<br>SUBWF<br>ction<br>= 2<br>= ?<br>on<br>= 1; re<br>= 1<br>= 0<br>SUBWF<br>ction<br>= 1<br>= 0<br>SUBWF | REG, 0, 0                      | t)                          |

| SUBWFB   | Subtract \  | W from f with  | n Borrow  | SWA         | <b>\PF</b>  | Swap f  |  |   |
|--|---|--|---|-------------|---|---|--|---|
| Syntax:  | SUBWFB  | f {,d {,a}}  |   | Synta       | ax:   | SWAPF f   | (,d {,a}}  |   |
| Operands:  | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |  |   | Oper        | ands:   | $0 \le f \le 255$<br>$d \in [0,1]$<br>$a \in [0,1]$   |  |   |
| Operation:   | (f) - (W) - (   | $\overline{\mathbb{C}}$ ) $\rightarrow$ dest   |   | Oper        | ation:  | (f<3:0>) →  | dest<7:4>,   |   |
| Status Affected:   | N, OV, C, D   | OC, Z  |   | ·           |   | (f<7:4>) →  | dest<3:0>  |   |
| Encoding:  | 0101  | 10da fff   |   | Statu       | s Affected:   | None  |  |   |
| Description:   |   | and the Carry<br>er 'f' (2's comple  | <b>O</b> ( ,  | Enco        | ding:   | 0011  | 10da ff  | ff ffff   |
| Monto  | method). If<br>in W. If 'd' is<br>in register 'I<br>If 'a' is '0', tl<br>If 'a' is '1', tl<br>GPR bank (<br>If 'a' is '0' a<br>set is enabl<br>in Indexed I<br>mode when<br>Section 23<br>Bit-Oriente<br>Literal Offs | 'd' is '0', the res<br>s '1', the result i<br>f' (default).<br>he Access Ban<br>he BSR is used | sult is stored<br>s stored back<br>k is selected.<br>I to select the<br>d instruction<br>tion operates<br>ddressing<br>h). See<br>ented and<br>s in Indexed | Desc        | ription:  | if are excha<br>is placed in re<br>lf 'a' is '0', the<br>lf 'a' is '1', the<br>GPR bank (<br>lf 'a' is '0' a<br>set is enable<br>in Indexed I<br>mode when<br>Section 23<br>Bit-Oriente | anged. If 'd' is 'U', If 'd' is 'L', Igister 'f' (defa he Access Barne BSR is use (default). | the result is ult).  nk is selected. d to select the ed instruction ction operates Addressing Fh). See iented and is in Indexed |
| Words:   | 1<br>1  |  |   | Word        | ls:   | 1   |  |   |
| Cycles:<br>Q Cycle Activity:                             | ı   |  |   | Cycle       | es:   | 1   |  |   |
| Q1   | Q2  | Q3   | Q4  | QC          | ycle Activity:  |   |  |   |
| Decode   | Read  | Process  | Write to  |             | Q1  | Q2  | Q3   | Q4  |
|  | register 'f'  | Data   | destination   |             | Decode  | Read  | Process  | Write to  |
| Example 1:   | SUBWFB  | REG, 1, 0  |   |             |   | register 'f'  | Data   | destination   |
| Before Instruction REG W C After Instruction REG W C C Z | = 19h<br>= 0Dh<br>= 1   | (0000 100<br>(0000 100<br>(0000 101<br>(0000 110   | .1)   | <u>Exar</u> | n <u>ple:</u><br>Before Instruc<br>REG<br>After Instructio<br>REG | etion<br>= 53h  | EG, 1, 0   |   |
| N  | = 0   | ; result is po   | sitive  |             |   |   |  |   |
| Example 2:   | SUBWFB  | REG, 0, 0  |   |             |   |   |  |   |
| Before Instruc<br>REG<br>W<br>C<br>After Instructi       | = 1Bh<br>= 1Ah<br>= 0   | (0001 101<br>(0001 101   |   |             |   |   |  |   |
| REG<br>W<br>C<br>Z                                       | = 1Bh<br>= 00h<br>= 1<br>= 1  | (0001 101  |   |             |   |   |  |   |
| N  | = 0   | ,  |   |             |   |   |  |   |
| Example 3:   | SUBWFB  | REG, 1, 0  |   |             |   |   |  |   |
| Before Instruc<br>REG<br>W<br>C                          | = 03h<br>= 0Eh<br>= 1   | (0000 001<br>(0000 110   |   |             |   |   |  |   |
| After Instructi<br>REG<br>W<br>C                         | on<br>= F5h<br>= 0Eh<br>= 0   | (1111 010; [2's comp]<br>(0000 110   |   |             |   |   |  |   |
| Z<br>N   | = 0<br>= 0<br>= 1   | ; result is ne   | egative   |             |   |   |  |   |

# Syntax: TBLRD (\*; \*+; \*-; +\*) Operands: None Operation: if TBLRD \*,

**Table Read** 

(Prog Mem (TBLPTR)) → TABLAT; TBLPTR – No Change;

if TBLRD \*+,

(Prog Mem (TBLPTR)) → TABLAT;

(TBLPTR) + 1  $\rightarrow$  TBLPTR;

if TBLRD \*-,

(Prog Mem (TBLPTR))  $\rightarrow$  TABLAT; (TBLPTR)  $-1 \rightarrow$  TBLPTR;

(IDLI III) - I -> I

if TBLRD +\*,

(TBLPTR) + 1  $\rightarrow$  TBLPTR; (Prog Mem (TBLPTR))  $\rightarrow$  TABLAT;

Status Affected: None

Encoding:

**TBLRD** 

| 1   | 10nr | 0000 | 0000 | 0000 |
|-----|------|------|------|------|
| *   | nn=0 |      |      |      |
| *+  | =1   |      |      |      |
| * - | =2   |      |      |      |
| +*  | =3   |      |      |      |
|     |      |      |      |      |

Description: This instruction is used to read the contents

of Program Memory (P.M.). To address the program memory, a pointer called Table Pointer (TBLPTR) is used.

The TRI DTD (a 21 bit pair

The TBLPTR (a 21-bit pointer) points to each byte in the program memory. TBLPTR has a 2-Mbyte address range.

TBLPTR[0] = 0: Least Significant Byte of Program Memory

Word `

TBLPTR[0] = 1: Most Significant Byte

of Program Memory

Word

The TBLRD instruction can modify the value

of TBLPTR as follows:

no change

post-increment

post-decrement

pre-increment

Words: 1 Cycles: 2

Q Cycle Activity:

| Q1              | Q2                                       | Q3              | Q4                             |  |
|-----------------|--|-----------------|--------------------------------|--|
| Decode          | No operation                             | No operation    | No operation                   |  |
| No<br>operation | No operation<br>(Read Program<br>Memory) | No<br>operation | No operation<br>(Write TABLAT) |  |

#### TBLRD Table Read (Continued)

Example 1: TBLRD Before Instruction TABLAT 55h 00A356h **TBLPTR** MEMORY (00A356h) 34h After Instruction **TABLAT** 34h 00A357h **TBLPTR** Example 2: TBLRD +\*

Before Instruction

TABLAT = AAh TBLPTR = 01A357h MEMORY (01A357h) = 12h MEMORY (01A358h) = 34h

After Instruction

TABLAT = 34h TBLPTR = 01A358h

| TBLWT             | Table Write   | TBLWT      | Table Write (Continued)                      |
|-------------------|---|------------|--|
| Syntax:           | TBLWT ( *; *+; *-; +*)  | Example 1: | TBLWT *+;                                    |
| Operands:         | None  | Before In  | struction                                    |
| Operation:        | if TBLWT*,  |            | ELAT = 55h                                   |
|                   | (TABLAT) → Holding Register;  |            | .PTR = 00A356h<br>.DING REGISTER             |
|                   | TBLPTR – No Change; if TBLWT*+,   | (00        | (A356h) = FFh                                |
|                   | (TABLAT) → Holding Register;  |            | ructions (table write completion) SLAT = 55h |
|                   | $(TBLPTR) + 1 \rightarrow TBLPTR;$  |            | SLAT = 55h<br>.PTR = 00A357h                 |
|                   | if TBLWT*-,   |            | LDING REGISTER<br>DA356h) = 55h              |
|                   | (TABLAT) → Holding Register;<br>(TBLPTR) – 1 → TBLPTR;                      | ·          | ,  |
|                   | if TBLWT+*,   | Example 2: | TBLWT +*;                                    |
|                   | $(TBLPTR) + 1 \rightarrow TBLPTR;$  | Before In  |  |
|                   | (TABLAT) → Holding Register;  |            | SLAT = 34h<br>.PTR = 01389Ah                 |
| Status Affected:  | None  |            | _DING REGISTER<br>I389Ah) = FFh              |
| Encoding:         | 0000 0000 0000 11r  |            | LDING REGISTER                               |
|                   | nn=0  | `          | (389Bh) = FFh                                |
|                   | =1 =2   |            | ruction (table write completion) SLAT = 34h  |
|                   | =3  | +* TBL     | .PTR = 01389Bh                               |
| Description:      | This instruction uses the 3 LSBs of   |            | _DING REGISTER<br>I389Ah) = FFh              |
| ·                 | TBLPTR to determine which of the  | IÓH        | LDING REGISTER                               |
|                   | 8 holding registers the TABLAT is writ                                      | ten (01    | (389Bh) = 34h                                |
|                   | to. The holding registers are used to                                       |            |  |
|                   | program the contents of Program Memory (P.M.). (Refer to <b>Section 6.0</b> |            |  |
|                   | "Flash Program Memory" for addition   |            |  |
|                   | details on programming Flash memor  | • /        |  |
|                   | The TBLPTR (a 21-bit pointer) points  | to         |  |
|                   | each byte in the program memory.  TBLPTR has a 2-MByte address range.       | 10         |  |
|                   | The LSb of the TBLPTR selects which   |            |  |
|                   | byte of the program memory location   |            |  |
|                   | access.   |            |  |
|                   | TBLPTR[0] = 0: Least Significa<br>Byte of Progra                            |            |  |
|                   | Memory Word   |            |  |
|                   | TBLPTR[0] = 1: Most Significal Byte of Progra                               | nt<br>M    |  |
|                   | Memory Word   |            |  |
|                   | The TBLWT instruction can modify the value of TBLPTR as follows:            | е          |  |
|                   | no change   |            |  |
|                   | • post-increment  |            |  |
|                   | post-decrement  |            |  |
|                   | pre-increment   |            |  |
| Words:            | 1   |            |  |
| Cycles:           | 2   |            |  |
| Q Cycle Activity: |   |            |  |
|                   | Q1 Q2 Q3 Q4   |            |  |
|                   | Decode No No No   |            |  |
|                   | operation operation operation   |            |  |
|                   | No No No No   |            |  |
|                   | operation operation operation   |            |  |
|                   | (Read (Write  |            |  |
|                   | TABLAT) Holdi   | ng         |  |
|                   | Regist  | or \       |  |

#### **TSTFSZ** Test f, Skip if 0

Syntax: TSTFSZ f {,a} Operands:  $0 \le f \le 255$  $a\in \left[ 0,1\right]$ 

Operation: skip if f = 0Status Affected: None

Encoding: 0110

Description: If 'f' = 0, the next instruction fetched during the current instruction execution is discarded and a NOP is executed, making this a two-cycle instruction. If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the

011a

ffff

ffff

GPR bank (default).

If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever  $f \le 95$  (5Fh). See Section 23.2.3 "Byte-Oriented and **Bit-Oriented Instructions in Indexed** 

Literal Offset Mode" for details.

Words: Cycles: 1(2)

Note: 3 cycles if skip and followed

by a 2-word instruction.

#### Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4        |  |
|--------|--------------|---------|-----------|--|
| Decode | Read         | Process | No        |  |
|        | register 'f' | Data    | operation |  |

#### If skip:

| Q1        | Q1 Q2     |           | Q4        |  |
|-----------|-----------|-----------|-----------|--|
| No No     |           | No        | No        |  |
| operation | operation | operation | operation |  |

If skip and followed by 2-word instruction:

| Q1        | Q2        | Q3        | Q4        |
|-----------|-----------|-----------|-----------|
| No        | No No     |           | No        |
| operation | operation | operation | operation |
| No        | No        | No        | No        |
| operation | operation | operation | operation |

Example: HERE TSTFSZ CNT, 1

NZERO ZERO

Before Instruction

PC Address (HERE)

After Instruction

If CNT 00h.

PC If CNT Address (ZERO) = # 00h.

Address (NZERO)

#### **XORLW Exclusive OR Literal with W**

XORLW k Syntax: Operands:  $0 \le k \le 255$ Operation: (W) .XOR.  $k \rightarrow W$ Status Affected: N, Z

Encoding: 0000 1010 kkkk kkkk

The contents of W are XORed with Description: the 8-bit literal 'k'. The result is placed

in W.

Words: Cycles:

Q Cycle Activity:

| Q1     | Q2          | Q3      | Q4         |  |
|--------|-------------|---------|------------|--|
| Decode | Read        | Process | Write to W |  |
|        | literal 'k' | Data    |            |  |

XORLW Example: 0AFh

Before Instruction

W B5h

After Instruction

W 1Ah

#### XORWF Exclusive OR W with f

Syntax: XORWF  $f \{ d \{,a\} \}$ 

Operands:  $0 \leq f \leq 255 \\ d \in [0,1]$ 

 $a \in [0,1]$   $a \in [0,1]$ 

Operation: (W) .XOR. (f)  $\rightarrow$  dest

Status Affected: N, Z

Encoding: 0001 10da fffff ffff

Description: Exclusive OR the contents of W with register 'f'. If 'd' is '0', the result is stored

in W. If 'd' is '1', the result is stored back in the register 'f' (default).

If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the

GPR bank (default).

If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 23.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed

**Literal Offset Mode**" for details.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4          |  |  |
|--------|--------------|---------|-------------|--|--|
| Decode | Read         | Process | Write to    |  |  |
|        | register 'f' | Data    | destination |  |  |

Example: XORWF REG, 1, 0

Before Instruction

 $\begin{array}{ccc} \mathsf{REG} & = & \mathsf{AFh} \\ \mathsf{W} & = & \mathsf{B5h} \end{array}$ 

After Instruction

 $\begin{array}{lll} \mathsf{REG} & = & \mathsf{1Ah} \\ \mathsf{W} & = & \mathsf{B5h} \end{array}$ 

#### 23.2 Extended Instruction Set

In addition to the standard 75 instructions of the PIC18 instruction set, PIC18F2X1X/4X1X devices also provide an optional extension to the core CPU functionality. The added features include eight additional instructions that augment indirect and indexed addressing operations and the implementation of Indexed Literal Offset Addressing mode for many of the standard PIC18 instructions.

The additional features of the extended instruction set are disabled by default. To enable them, users must set the XINST configuration bit.

The instructions in the extended set (with the exception of CALLW, MOVSF and MOVSS) can all be classified as literal operations, which either manipulate the File Select Registers, or use them for indexed addressing. Two of the instructions, ADDFSR and SUBFSR, each have an additional special instantiation for using FSR2. These versions (ADDULNK and SUBULNK) allow for automatic return after execution.

The extended instructions are specifically implemented to optimize re-entrant program code (that is, code that is recursive or that uses a software stack) written in high-level languages, particularly C. Among other things, they allow users working in high-level languages to perform certain operations on data structures more efficiently. These include:

- dynamic allocation and deallocation of software stack space when entering and leaving subroutines
- · function pointer invocation
- software Stack Pointer manipulation
- manipulation of variables located in a software stack

A summary of the instructions in the extended instruction set is provided in Table 23-3. Detailed descriptions are provided in **Section 23.2.2 "Extended Instruction Set"**. The opcode field descriptions in Table 23-1 (page 258) apply to both the standard and extended PIC18 instruction sets.

Note: The instruction set extension and the Indexed Literal Offset Addressing mode were designed for optimizing applications written in C. The user may likely never use these instructions directly in assembler. The syntax for these commands is provided as a reference for users who may be reviewing code that has been generated by a compiler.

#### 23.2.1 EXTENDED INSTRUCTION SYNTAX

Most of the extended instructions use indexed arguments, using one of the File Select Registers and some offset to specify a source or destination register. When an argument for an instruction serves as part of indexed addressing, it is enclosed in square brackets ("[]"). This is done to indicate that the argument is used as an index or offset. The MPASM<sup>TM</sup> Assembler will flag an error if it determines that an index or offset value is not bracketed.

When the extended instruction set is enabled, brackets are also used to indicate index arguments in byte-oriented and bit-oriented instructions. This is in addition to other changes in their syntax. For more details, see Section 23.2.3.1 "Extended Instruction Syntax with Standard PIC18 Commands".

Note: In the past, square brackets have been used to denote optional arguments in the PIC18 and earlier instruction sets. In this text and going forward, optional arguments are denoted by braces ("{ }").

TABLE 23-3: EXTENSIONS TO THE PIC18 INSTRUCTION SET

| Mnemonic,<br>Operands |               | Description                              | Cycles | 16-Bit Instruction Word |      |      |      | Status   |  |
|-----------------------|---------------|--|--------|-------------------------|------|------|------|----------|--|
|                       |               | Description                              | Cycles | MSb                     |      |      | LSb  | Affected |  |
| ADDFSR                | f, k          | Add literal to FSR                       | 1      | 1110                    | 1000 | ffkk | kkkk | None     |  |
| ADDULNK               | k             | Add literal to FSR2 and return           | 2      | 1110                    | 1000 | 11kk | kkkk | None     |  |
| CALLW                 |               | Call subroutine using WREG               | 2      | 0000                    | 0000 | 0001 | 0100 | None     |  |
| MOVSF                 | $z_s$ , $f_d$ | Move z <sub>s</sub> (source) to 1st word | 2      | 1110                    | 1011 | 0zzz | zzzz | None     |  |
|                       |               | f <sub>d</sub> (destination) 2nd word    |        | 1111                    | ffff | ffff | ffff |          |  |
| MOVSS                 | $z_s, z_d$    | Move z <sub>s</sub> (source) to 1st word | 2      | 1110                    | 1011 | 1zzz | ZZZZ | None     |  |
|                       |               | z <sub>d</sub> (destination) 2nd word    |        | 1111                    | xxxx | XZZZ | ZZZZ |          |  |
| PUSHL                 | k             | Store literal at FSR2,                   | 1      | 1110                    | 1010 | kkkk | kkkk | None     |  |
|                       |               | decrement FSR2                           |        |                         |      |      |      |          |  |
| SUBFSR                | f, k          | Subtract literal from FSR                | 1      | 1110                    | 1001 | ffkk | kkkk | None     |  |
| SUBULNK               | k             | Subtract literal from FSR2 and           | 2      | 1110                    | 1001 | 11kk | kkkk | None     |  |
|                       |               | return                                   |        |                         |      |      |      |          |  |

#### 23.2.2 EXTENDED INSTRUCTION SET

ADDFSR Add Literal to FSR

Syntax: ADDFSR f, k Operands:  $0 \le k \le 63$   $f \in [0, 1, 2]$ 

 $\label{eq:final_problem} \text{Operation:} \qquad \qquad \text{FSR(f)} + k \rightarrow \text{FSR(f)}$ 

Status Affected: None

Encoding: 1110 1000 ffkk kkkk

Description: The 6-bit literal 'k' is added to the contents of the FSR specified by 'f'.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2          | Q3      | Q4       |
|--------|-------------|---------|----------|
| Decode | Read        | Process | Write to |
|        | literal 'k' | Data    | FSR      |

Example: ADDFSR 2, 23h

Before Instruction

FSR2 = 03FFh

After Instruction

FSR2 = 0422h

| ADDULNK          | Add Literal to FSR2 and Return  |                      |      |   |  |
|------------------|---|----------------------|------|---|--|
| Syntax:          | ADDULNK k   |                      |      |   |  |
| Operands:        | $0 \le k \le 63$  |                      |      |   |  |
| Operation:       | FSR2 + k  | $c \rightarrow FSR2$ | ,    |   |  |
|                  | $(TOS) \to$   | PC                   |      |   |  |
| Status Affected: | None  |                      |      |   |  |
| Encoding:        | 1110  | 1000                 | 11kk | kkkk  |  |
| Description:     | The 6-bit literal 'k' is added to the contents of FSR2. A RETURN is then executed by loading the PC with the TOS.  The instruction takes two cycles to execute; a NOP is performed during the second cycle.  This may be thought of as a special case of the ADDFSR instruction, where f = 3 (binary '11'); it operates only on FSR2. |                      |      | is then with the cles to during special on, |  |

Words: 1 Cycles: 2

Q Cycle Activity:

| Q1        | Q2          | Q3        | Q4        |
|-----------|-------------|-----------|-----------|
| Decode    | Read        | Process   | Write to  |
|           | literal 'k' | Data      | FSR       |
| No        | No          | No        | No        |
| Operation | Operation   | Operation | Operation |

Example: ADDULNK 23h

Before Instruction

FSR2 = 03FFhPC = 0100h

After Instruction

FSR2 = 0422hPC = (TOS)

**Note:** All PIC18 instructions may take an optional label argument preceding the instruction mnemonic for use in symbolic addressing. If a label is used, the instruction syntax then becomes: {label} instruction argument(s).

#### **CALLW Subroutine Call Using WREG**

Svntax: **CALLW** 

Operands: None

Operation:  $(PC + 2) \rightarrow TOS$ ,

 $(W) \rightarrow PCL$ ,  $(PCLATH) \rightarrow PCH$ ,  $(PCLATU) \rightarrow PCU$ 

None Status Affected:

Encoding:

0000 0000 0001 0100 First, the return address (PC + 2) is

Description pushed onto the return stack. Next, the

contents of W are written to PCL; the existing value is discarded. Then the contents of PCLATH and PCLATU are

latched into PCH and PCU, respectively. The second cycle is executed as a NOP instruction while the new next instruction is fetched. Unlike CALL, there is no option to

update W, Status or BSR.

Words: 1 2 Cycles:

Q Cycle Activity:

| Q1        | Q2        | Q3         | Q4        |
|-----------|-----------|------------|-----------|
| Decode    | Read      | Push PC to | No        |
|           | WREG      | stack      | operation |
| No        | No        | No         | No        |
| operation | operation | operation  | operation |

Example: HERE CALLW

Before Instruction

address (HERE)

PCLATH 10h **PCLATU** 00h 06h

After Instruction

001006h

TOS address (HERE + 2) PCLATH =

PCLATU =

#### **MOVSF** Move Indexed to f

Syntax: MOVSF  $[z_s]$ ,  $f_d$ Operands:  $0 \le z_{s} \le 127$  $0 \le f_d \le 4095$ 

 $((FSR2) + z_s) \rightarrow f_d$ Operation:

Status Affected: None

Encodina: 1st word (source)

2nd word (destin.)

| 1110 | 1011 | 0zzz | ZZZZs |
|------|------|------|-------|
| 1111 | ffff | ffff | ffffd |
|      |      |      | _     |

Description: The contents of the source register are moved to destination register 'f<sub>d</sub>'. The actual address of the source register is determined by adding the 7-bit literal offset 'zs' in the first word to the value of FSR2. The address of the destination register is specified by the 12-bit literal

> 'f<sub>d</sub>' in the second word. Both addresses can be anywhere in the 4096-byte data

space (000h to FFFh).

The MOVSF instruction cannot use the PCL, TOSU, TOSH or TOSL as the

destination register.

If the resultant source address points to an indirect addressing register, the

value returned will be 00h.

Words: 2 2 Cycles:

Q Cycle Activity:

| Q1     | Q2          | Q3          | Q4           |
|--------|-------------|-------------|--------------|
| Decode | Determine   | Determine   | Read         |
|        | source addr | source addr | source reg   |
| Decode | No          | No          | Write        |
|        | operation   | operation   | register 'f' |
|        | No dummy    |             | (dest)       |
|        | read        |             |              |

Example: MOVSF [05h], REG2

Before Instruction

80h FSR2 Contents

33h of 85h

REG2 11h

After Instruction

FSR2 80h Contents of 85h 33h REG2 33h

#### MOVSS Move Indexed to Indexed

Syntax: MOVSS  $[z_s]$ ,  $[z_d]$ Operands:  $0 \le z_s \le 127$  $0 \le z_d \le 127$ 

Operation:  $((FSR2) + z_S) \rightarrow ((FSR2) + z_d)$ 

Status Affected: None

Encoding: 1st word (source) 2nd word (dest.)

| 1110 | 1011 | 1zzz | ZZZZs |
|------|------|------|-------|
| 1111 | xxxx | XZZZ | zzzzd |

Description The contents of the source register are moved to the destination register. The addresses of the source and destination registers are determined by adding the

7-bit literal offsets 'z<sub>s</sub>' or 'z<sub>d</sub>', respectively, to the value of FSR2. Both registers can be located anywhere in the 4096-byte data memory space

(000h to FFFh).

The  ${\tt MOVSS}$  instruction cannot use the PCL, TOSU, TOSH or TOSL as the

destination register.

If the resultant source address points to an indirect addressing register, the value returned will be 00h. If the resultant destination address points to an indirect addressing register, the instruction will execute as a NOP.

Words: 2 Cycles: 2

Q Cycle Activity:

| Q1     | Q2          | Q3          | Q4          |
|--------|-------------|-------------|-------------|
| Decode | Determine   | Determine   | Read        |
|        | source addr | source addr | source reg  |
| Decode | Determine   | Determine   | Write       |
|        | dest addr   | dest addr   | to dest reg |

Example: MOVSS [05h], [06h]

Before Instruction

FSR2 = 80h
Contents
of 85h = 33h
Contents
of 86h = 11h
After Instruction

FSR2 = 80h Contents of 85h = 33h Contents of 86h = 33h

| PUSHL | Store Literal at FSR2. Decrement FSR | 2 |
|-------|--------------------------------------|---|
| FUSHL | Store Literal at FSRZ, Decrement FSR | ~ |

Syntax: PUSHL k
Operands:  $0 \le k \le 255$ Operation:  $k \rightarrow (FSR2)$ ,

 $FSR2-1 \rightarrow FSR2$ 

Status Affected: None

Description:

Encoding: 1111 1010 kkkk kkkk

memory address specified by FSR2. FSR2 is decremented by 1 after the operation. This instruction allows users to push values

The 8-bit literal 'k' is written to the data

onto a software stack.

Words: 1
Cycles: 1
Q Cycle Activity:

| Q1     | Q2       | Q3      | Q4          |
|--------|----------|---------|-------------|
| Decode | Read 'k' | Process | Write to    |
|        |          | data    | destination |

Example: PUSHL 08h

Before Instruction

 $\begin{array}{lll} \text{FSR2H:FSR2L} & = & \text{01ECh} \\ \text{Memory (01ECh)} & = & \text{00h} \end{array}$ 

After Instruction

 $\begin{array}{lll} \text{FSR2H:FSR2L} & = & \text{01EBh} \\ \text{Memory (01ECh)} & = & \text{08h} \end{array}$ 

SUBFSR Subtract Literal from FSR

Syntax: SUBFSR f, k Operands:  $0 \le k \le 63$ 

 $f \in [0, 1, 2]$ 

Operation:  $FSR(f) - k \rightarrow FSRf$ 

Status Affected: None

Encoding: 1110 1001 ffkk kkkk

Description: The 6-bit literal 'k' is subtracted from

the contents of the FSR specified by  $% \left\{ \mathbf{r}^{\prime}\right\} =\mathbf{r}^{\prime}$ 

ʻf'.

Words: 1 Cycles: 1

Q Cycle Activity:

| Q1     | Q2           | Q3      | Q4          |
|--------|--------------|---------|-------------|
| Decode | Read         | Process | Write to    |
|        | register 'f' | Data    | destination |

Example: SUBFSR 2, 23h

Before Instruction

FSR2 = 03FFh

After Instruction

FSR2 = 03DCh

SUBULNK Subtract Literal from FSR2 and Return

Syntax: SUBULNK k
Operands:  $0 \le k \le 63$ 

Operation:  $FSR2 - k \rightarrow FSR2$ 

 $(TOS) \rightarrow PC$ 

Status Affected: None

**Encoding:** 1110 1001 11kk kkkk

Description: The 6-bit literal 'k' is subtracted from the contents of the FSR2. A RETURN is then executed by loading the PC with the TOS.

The instruction takes two cycles to execute; a NOP is performed during the

second cycle.

This may be thought of as a special case of the  $\mathtt{SUBFSR}$  instruction, where f=3 (binary

'11'); it operates only on FSR2.

Words: 1
Cycles: 2
Q Cycle Activity:

| Q1        | Q2                | Q3              | Q4                   |
|-----------|-------------------|-----------------|----------------------|
| Decode    | Read register 'f' | Process<br>Data | Write to destination |
| No        | No                | No              | No                   |
| Operation | Operation         | Operation       | Operation            |

Example: SUBULNK 23h

Before Instruction

FSR2 = 03FFhPC = 0100h

After Instruction

FSR2 = 03DCh PC = (TOS)

## 23.2.3 BYTE-ORIENTED AND BIT-ORIENTED INSTRUCTIONS IN INDEXED LITERAL OFFSET MODE

**Note:** Enabling the PIC18 instruction set extension may cause legacy applications to behave erratically or fail entirely.

In addition to eight new commands in the extended set, enabling the extended instruction set also enables Indexed Literal Offset Addressing mode (Section 5.5.1 "Indexed Addressing with Literal Offset"). This has a significant impact on the way that many commands of the standard PIC18 instruction set are interpreted.

When the extended set is disabled, addresses embedded in opcodes are treated as literal memory locations: either as a location in the Access Bank ('a' = 0) or in a GPR bank designated by the BSR ('a' = 1). When the extended instruction set is enabled and 'a' = 0, however, a file register argument of 5Fh or less is interpreted as an offset from the pointer value in FSR2 and not as a literal address. For practical purposes, this means that all instructions that use the Access RAM bit as an argument – that is, all byte-oriented and bitoriented instructions, or almost half of the core PIC18 instructions – may behave differently when the extended instruction set is enabled.

When the content of FSR2 is 00h, the boundaries of the Access RAM are essentially remapped to their original values. This may be useful in creating backward compatible code. If this technique is used, it may be necessary to save the value of FSR2 and restore it when moving back and forth between C and assembly routines in order to preserve the Stack Pointer. Users must also keep in mind the syntax requirements of the extended instruction set (see Section 23.2.3.1 "Extended Instruction Syntax with Standard PIC18 Commands").

Although the Indexed Literal Offset Addressing mode can be very useful for dynamic stack and pointer manipulation, it can also be very annoying if a simple arithmetic operation is carried out on the wrong register. Users who are accustomed to the PIC18 programming must keep in mind that when the extended instruction set is enabled, register addresses of 5Fh or less are used for Indexed Literal Offset Addressing.

Representative examples of typical byte-oriented and bit-oriented instructions in the Indexed Literal Offset Addressing mode are provided on the following page to show how execution is affected. The operand conditions shown in the examples are applicable to all instructions of these types.

### 23.2.3.1 Extended Instruction Syntax with Standard PIC18 Commands

When the extended instruction set is enabled, the file register argument, 'f', in the standard byte-oriented and bit-oriented commands is replaced with the literal offset value, 'k'. As already noted, this occurs only when 'f' is less than or equal to 5Fh. When an offset value is used, it must be indicated by square brackets ("[]"). As with the extended instructions, the use of brackets indicates to the compiler that the value is to be interpreted as an index or an offset. Omitting the brackets, or using a value greater than 5Fh within brackets, will generate an error in the MPASM Assembler.

If the index argument is properly bracketed for Indexed Literal Offset Addressing, the Access RAM argument is never specified; it will automatically be assumed to be '0'. This is in contrast to standard operation (extended instruction set disabled) when 'a' is set on the basis of the target address. Declaring the Access RAM bit in this mode will also generate an error in the MPASM Assembler.

The destination argument, 'd', functions as before.

In the latest versions of the MPASM Assembler, language support for the extended instruction set must be explicitly invoked. This is done with either the command line option, /y, or the PE directive in the source listing.

## 23.2.4 CONSIDERATIONS WHEN ENABLING THE EXTENDED INSTRUCTION SET

It is important to note that the extensions to the instruction set may not be beneficial to all users. In particular, users who are not writing code that uses a software stack may not benefit from using the extensions to the instruction set.

Additionally, the Indexed Literal Offset Addressing mode may create issues with legacy applications written to the PIC18 assembler. This is because instructions in the legacy code may attempt to address registers in the Access Bank below 5Fh. Since these addresses are interpreted as literal offsets to FSR2 when the instruction set extension is enabled, the application may read or write to the wrong data addresses.

When porting an application to the PIC18F2X1X/4X1X, it is very important to consider the type of code. A large, re-entrant application that is written in 'C' and would benefit from efficient compilation will do well when using the instruction set extensions. Legacy applications that heavily use the Access Bank will most likely not benefit from using the extended instruction set.

ADDWF Add W to Indexed

(Indexed Literal Offset mode)

Syntax: ADDWF  $[k] \{,d\}$ 

 $0 \le k \le 95$  $d \in [0,1]$ 

Operation:  $(W) + ((FSR2) + k) \rightarrow dest$ 

Status Affected: N, OV, C, DC, Z

Encoding: 0010 01d0 kkkk kkkk

Description: The contents of W are added to the

contents of the register indicated by FSR2, offset by the value 'k'.

If 'd' is '0', the result is stored in W. If 'd'

is '1', the result is stored back in

register 'f' (default).

Words: 1
Cycles: 1

Q Cycle Activity:

Operands:

Q1 Q2 Q3 Q4

Decode Read 'k' Process Write to Data destination

Example: ADDWF [OFST],0

Before Instruction

W = 17h OFST = 2Ch FSR2 = 0A00h

Contents of 0A2Ch = 20h

After Instruction

W = 37h Contents

of 0A2Ch = 20h

BSF Bit Set Indexed (Indexed Literal Offset mode)

Syntax: BSF [k], b Operands:  $0 \le f \le 95$ 

 $0 \le f \le 95$  $0 \le b \le 7$ 

Operation:  $1 \rightarrow ((FSR2) + k) < b >$ 

Status Affected: None

Encoding: 1000 bbb0 kkkk kkkk

Description: Bit 'b' of the register indicated by FSR2,

offset by the value 'k', is set.

Words: 1
Cycles: 1

Q Cycle Activity:

Q1 Q2 Q3 Q4

| Decode | Read | Process | Write to register 'f' | Data | destination

Example: BSF [FLAG\_OFST], 7

Before Instruction

FLAG\_OFST = 0Ah FSR2 = 0A00h Contents of 0A0Ah = 55h

After Instruction

Contents of 0A0Ah = D5h

SETF Set Indexed (Indexed Literal Offset mode)

Syntax: SETF [k]

Operands:  $0 \le k \le 95$ 

Operation: FFh  $\rightarrow$  ((FSR2) + k)

Status Affected: None

Encoding: 0110 1000 kkkk kkkk

Description: The contents of the register indicated by

FSR2, offset by 'k', are set to FFh.

Words: 1
Cycles: 1

Q Cycle Activity:

 Q1
 Q2
 Q3
 Q4

 Decode
 Read 'k'
 Process
 Write register

Example: SETF [OFST]

Before Instruction

OFST = 2Ch FSR2 = 0A00h Contents of 0A2Ch = 00h

After Instruction

Contents of 0A2Ch = FFh

### 23.2.5 SPECIAL CONSIDERATIONS WITH MICROCHIP MPLAB® IDE TOOLS

The latest versions of Microchip's software tools have been designed to fully support the extended instruction set of the PIC18F2X1X/4X1X family of devices. This includes the MPLAB C18 C compiler, MPASM assembly language and MPLAB Integrated Development Environment (IDE).

When selecting a target device for software development, MPLAB IDE will automatically set default configuration bits for that device. The default setting for the XINST configuration bit is '0', disabling the extended instruction set and Indexed Literal Offset Addressing mode. For proper execution of applications developed to take advantage of the extended instruction set, XINST must be set during programming.

To develop software for the extended instruction set, the user must enable support for the instructions and the Indexed Addressing mode in their language tool(s). Depending on the environment being used, this may be done in several ways:

- A menu option, or dialog box within the environment, that allows the user to configure the language tool and its settings for the project
- A command line option
- · A directive in the source code

These options vary between different compilers, assemblers and development environments. Users are encouraged to review the documentation accompanying their development systems for the appropriate information.

#### 24.0 DEVELOPMENT SUPPORT

The PICmicro<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Assemblers/Compilers/Linkers
  - MPASM™ Assembler
  - MPLAB C17 and MPLAB C18 C Compilers
  - MPLINK<sup>™</sup> Object Linker/ MPLIB<sup>™</sup> Object Librarian
  - MPLAB C30 C Compiler
  - MPLAB ASM30 Assembler/Linker/Library
- Simulators
  - MPLAB SIM Software Simulator
  - MPLAB dsPIC30 Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - MPLAB ICE 4000 In-Circuit Emulator
- In-Circuit Debugger
  - MPLAB ICD 2
- Device Programmers
  - PRO MATE® II Universal Device Programmer
  - PICSTART® Plus Development Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration Boards
  - PICDEM™ 1 Demonstration Board
  - PICDEM.net™ Demonstration Board
  - PICDEM 2 Plus Demonstration Board
  - PICDEM 3 Demonstration Board
  - PICDEM 4 Demonstration Board
  - PICDEM 17 Demonstration Board
  - PICDEM 18R Demonstration Board
  - PICDEM LIN Demonstration Board
  - PICDEM USB Demonstration Board
- Evaluation Kits
  - KEELOQ® Evaluation and Programming Tools
  - PICDEM MSC
  - microID® Developer Kits
  - CAN
  - PowerSmart® Developer Kits
  - Analog

### 24.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16-bit microcontroller market. The MPLAB IDE is a Windows® based application that contains:

- · An interface to debugging tools
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
  - in-circuit debugger (sold separately)
- · A full-featured editor with color coded context
- · A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- · Mouse over variable inspection
- · Extensive on-line help

The MPLAB IDE allows you to:

- Edit your source files (either assembly or C)
- One touch assemble (or compile) and download to PICmicro emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - source files (assembly or C)
  - mixed assembly and C
  - machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increasing flexibility and power.

#### 24.2 MPASM Assembler

The MPASM assembler is a full-featured, universal macro assembler for all PICmicro MCUs.

The MPASM assembler generates relocatable object files for the MPLINK object linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM assembler features include:

- · Integration into MPLAB IDE projects
- User defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

### 24.3 MPLAB C17 and MPLAB C18 C Compilers

The MPLAB C17 and MPLAB C18 Code Development Systems are complete ANSI C compilers for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers. These compilers provide powerful integration capabilities, superior code optimization and ease of use not found with other compilers.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

#### 24.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK object linker combines relocatable objects created by the MPASM assembler and the MPLAB C17 and MPLAB C18 C compilers. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB object librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

#### 24.5 MPLAB C30 C Compiler

The MPLAB C30 C compiler is a full-featured, ANSI compliant, optimizing compiler that translates standard ANSI C programs into dsPIC30F assembly language source. The compiler also supports many command line options and language extensions to take full advantage of the dsPIC30F device hardware capabilities and afford fine control of the compiler code generator.

MPLAB C30 is distributed with a complete ANSI C standard library. All library functions have been validated and conform to the ANSI C library standard. The library includes functions for string manipulation, dynamic memory allocation, data conversion, time-keeping and math functions (trigonometric, exponential and hyperbolic). The compiler provides symbolic information for high-level source debugging with the MPLAB IDE.

### 24.6 MPLAB ASM30 Assembler, Linker and Librarian

MPLAB ASM30 assembler produces relocatable machine code from symbolic assembly language for dsPIC30F devices. MPLAB C30 compiler uses the assembler to produce it's object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- Support for the entire dsPIC30F instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- Rich directive set
- · Flexible macro language
- MPLAB IDE compatibility

#### 24.7 MPLAB SIM Software Simulator

The MPLAB SIM software simulator allows code development in a PC hosted environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any pin. The execution can be performed in Single-Step, Execute Until Break or Trace mode.

The MPLAB SIM simulator fully supports symbolic debugging using the MPLAB C17 and MPLAB C18 C Compilers, as well as the MPASM assembler. The software simulator offers the flexibility to develop and debug code outside of the laboratory environment, making it an excellent, economical software development tool.

#### 24.8 MPLAB SIM30 Software Simulator

The MPLAB SIM30 software simulator allows code development in a PC hosted environment by simulating the dsPIC30F series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any of the pins.

The MPLAB SIM30 simulator fully supports symbolic debugging using the MPLAB C30 C Compiler and MPLAB ASM30 assembler. The simulator runs in either a Command Line mode for automated tasks, or from MPLAB IDE. This high-speed simulator is designed to debug, analyze and optimize time intensive DSP routines.

# 24.9 MPLAB ICE 2000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 2000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers. Software control of the MPLAB ICE 2000 in-circuit emulator is advanced by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB ICE in-circuit emulator allows expansion to support new PICmicro microcontrollers.

The MPLAB ICE 2000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft® Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

# 24.10 MPLAB ICE 4000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 4000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for highend PICmicro microcontrollers. Software control of the MPLAB ICE in-circuit emulator is provided by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICD 4000 is a premium emulator system, providing the features of MPLAB ICE 2000, but with increased emulation memory and high-speed performance for dsPIC30F and PIC18XXXX devices. Its advanced emulator features include complex triggering and timing, up to 2 Mb of emulation memory and the ability to view variables in real-time.

The MPLAB ICE 4000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

#### 24.11 MPLAB ICD 2 In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD 2, is a powerful, low-cost, run-time development tool, connecting to the host PC via an RS-232 or high-speed USB interface. This tool is based on the Flash PICmicro MCUs and can be used to develop for these and other PICmicro microcontrollers. The MPLAB ICD 2 utilizes the in-circuit debugging capability built into the Flash devices. This feature, along with Microchip's In-Circuit Serial Programming™ (ICSP™) protocol, offers cost effective in-circuit Flash debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by setting breakpoints, single-stepping and watching variables, CPU status and peripheral registers. Running at full speed enables testing hardware and applications in real-time. MPLAB ICD 2 also serves as a development programmer for selected PICmicro devices.

### 24.12 PRO MATE II Universal Device Programmer

The PRO MATE II is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features an LCD display for instructions and error messages and a modular detachable socket assembly to support various package types. In Stand-Alone mode, the PRO MATE II device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode.

#### 24.13 MPLAB PM3 Device Programmer

The MPLAB PM3 is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode. MPLAB PM3 connects to the host PC via an RS-232 or USB cable. MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an SD/MMC card for file storage and secure data applications.

### 24.14 PICSTART Plus Development Programmer

The PICSTART Plus development programmer is an easy-to-use, low-cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient. The PICSTART Plus development programmer supports most PICmicro devices up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus development programmer is CE compliant.

### 24.15 PICDEM 1 PICmicro Demonstration Board

The PICDEM 1 demonstration board demonstrates the capabilities of the PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The sample microcontrollers provided with the PICDEM 1 demonstration board can be programmed with a PRO MATE II device programmer or a PICSTART Plus development programmer. The PICDEM 1 demonstration board can be connected to the MPLAB ICE in-circuit emulator for testing. A prototype area extends the circuitry for additional application components. Features include an RS-232 interface, a potentiometer for simulated analog input, push button switches and eight LEDs.

### 24.16 PICDEM.net Internet/Ethernet Demonstration Board

The PICDEM.net demonstration board is an Internet/ Ethernet demonstration board using the PIC18F452 microcontroller and TCP/IP firmware. The board supports any 40-pin DIP device that conforms to the standard pinout used by the PIC16F877 or PIC18C452. This kit features a user friendly TCP/IP stack, web server with HTML, a 24L256 Serial EEPROM for Xmodem download to web pages into Serial EEPROM, ICSP/MPLAB ICD 2 interface connector, an Ethernet interface, RS-232 interface and a 16 x 2 LCD display. Also included is the book and CD-ROM "TCP/IP Lean, Web Servers for Embedded Systems," by Jeremy Bentham

### 24.17 PICDEM 2 Plus Demonstration Board

The PICDEM 2 Plus demonstration board supports many 18, 28 and 40-pin microcontrollers, including PIC16F87X and PIC18FXX2 devices. All the necessary hardware and software is included to run the demonstration programs. The sample microcontrollers provided with the PICDEM 2 demonstration board can be programmed with a PRO MATE II device programmer, PICSTART Plus development programmer, or MPLAB ICD 2 with a Universal Programmer Adapter. The MPLAB ICD 2 and MPLAB ICE in-circuit emulators may also be used with the PICDEM 2 demonstration board to test firmware. A prototype area extends the circuitry for additional application components. Some of the features include an RS-232 interface, a 2 x 16 LCD display, a piezo speaker, an on-board temperature sensor, four LEDs and sample PIC18F452 and PIC16F877 Flash microcontrollers.

#### 24.18 PICDEM 3 PIC16C92X Demonstration Board

The PICDEM 3 demonstration board supports the PIC16C923 and PIC16C924 in the PLCC package. All the necessary hardware and software is included to run the demonstration programs.

### 24.19 PICDEM 4 8/14/18-Pin Demonstration Board

The PICDEM 4 can be used to demonstrate the capabilities of the 8, 14 and 18-pin PIC16XXXX and PIC18XXXX MCUs, including the PIC16F818/819, PIC16F87/88, PIC16F62XA and the PIC18F1320 family of microcontrollers. PICDEM 4 is intended to showcase the many features of these low pin count parts, including LIN and Motor Control using ECCP. Special provisions are made for low-power operation with the supercapacitor circuit and jumpers allow onboard hardware to be disabled to eliminate current draw in this mode. Included on the demo board are provisions for Crystal, RC or Canned Oscillator modes, a five volt regulator for use with a nine volt wall adapter or battery, DB-9 RS-232 interface, ICD connector for programming via ICSP and development with MPLAB ICD 2, 2 x 16 liquid crystal display, PCB footprints for H-Bridge motor driver, LIN transceiver and EEPROM. Also included are: header for expansion, eight LEDs, four potentiometers, three push buttons and a prototyping area. Included with the kit is a PIC16F627A and a PIC18F1320. Tutorial firmware is included along with the User's Guide.

#### 24.20 PICDEM 17 Demonstration Board

The PICDEM 17 demonstration board is an evaluation board that demonstrates the capabilities of several Microchip microcontrollers, including PIC17C752, PIC17C756A, PIC17C762 and PIC17C766. A programmed sample is included. The PRO MATE II device programmer, or the PICSTART Plus development programmer, can be used to reprogram the device for user tailored application development. The PICDEM 17 demonstration board supports program download and execution from external on-board Flash memory. A generous prototype area is available for user hardware expansion.

### 24.21 PICDEM 18R PIC18C601/801 Demonstration Board

The PICDEM 18R demonstration board serves to assist development of the PIC18C601/801 family of Microchip microcontrollers. It provides hardware implementation of both 8-bit Multiplexed/Demultiplexed and 16-bit Memory modes. The board includes 2 Mb external Flash memory and 128 Kb SRAM memory, as well as serial EEPROM, allowing access to the wide range of memory types supported by the PIC18C601/801.

#### 24.22 PICDEM LIN PIC16C43X Demonstration Board

The powerful LIN hardware and software kit includes a series of boards and three PICmicro microcontrollers. The small footprint PIC16C432 and PIC16C433 are used as slaves in the LIN communication and feature on-board LIN transceivers. A PIC16F874 Flash microcontroller serves as the master. All three microcontrollers are programmed with firmware to provide LIN bus communication.

#### 24.23 PICkit<sup>™</sup> 1 Flash Starter Kit

A complete "development system in a box", the PICkit™ Flash Starter Kit includes a convenient multi-section board for programming, evaluation and development of 8/14-pin Flash PIC® microcontrollers. Powered via USB, the board operates under a simple Windows GUI. The PICkit 1 Starter Kit includes the User's Guide (on CD ROM), PICkit 1 tutorial software and code for various applications. Also included are MPLAB® IDE (Integrated Development Environment) software, software and hardware "Tips 'n Tricks for 8-pin Flash PIC® Microcontrollers" Handbook and a USB interface cable. Supports all current 8/14-pin Flash PIC microcontrollers, as well as many future planned devices.

### 24.24 PICDEM USB PIC16C7X5 Demonstration Board

The PICDEM USB Demonstration Board shows off the capabilities of the PIC16C745 and PIC16C765 USB microcontrollers. This board provides the basis for future USB products.

### 24.25 Evaluation and Programming Tools

In addition to the PICDEM series of circuits, Microchip has a line of evaluation kits and demonstration software for these products.

- KEELOQ evaluation and programming tools for Microchip's HCS Secure Data Products
- CAN developers kit for automotive network applications
- Analog design boards and filter design software
- PowerSmart battery charging evaluation/ calibration kits
- IrDA® development kit
- microID development and rfLab<sup>TM</sup> development software
- SEEVAL® designer kit for memory evaluation and endurance calculations
- PICDEM MSC demo boards for Switching mode power supply, high-power IR driver, delta sigma ADC and flow rate sensor

Check the Microchip web page and the latest Product Selector Guide for the complete list of demonstration and evaluation kits.

NOTES:

#### 25.0 ELECTRICAL CHARACTERISTICS

#### Absolute Maximum Ratings(†)

| Ambient temperature under bias                               | 40°C to +125°C       |
|--|----------------------|
| Storage temperature  | 65°C to +150°C       |
| Voltage on any pin with respect to Vss (except VDD and MCLR) | 0.3V to (VDD + 0.3V) |
| Voltage on VDD with respect to Vss                           | 0.3V to +7.5V        |
| Voltage on MCLR with respect to Vss (Note 2)                 | 0V to +13.25V        |
| Total power dissipation (Note 1)                             | 1.0W                 |
| Maximum current out of Vss pin                               | 300 mA               |
| Maximum current into VDD pin                                 | 250 mA               |
| Input clamp current, IiK (VI < 0 or VI > VDD)                | ±20 mA               |
| Output clamp current, lok (Vo < 0 or Vo > VDD)               | ±20 mA               |
| Maximum output current sunk by any I/O pin                   | 25 mA                |
| Maximum output current sourced by any I/O pin                | 25 mA                |
| Maximum current sunk by all ports                            | 200 mA               |
| Maximum current sourced by all ports                         | 200 mA               |

- **Note 1:** Power dissipation is calculated as follows: Pdis = VDD x {IDD  $\Sigma$  IOH} +  $\Sigma$  {(VDD VOH) x IOH} +  $\Sigma$ (VOL x IOL)
  - 2: Voltage spikes below Vss at the  $\overline{MCLR}/VPP/RE3$  pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100 $\Omega$  should be used when applying a "low" level to the  $\overline{MCLR}/VPP/RE3$  pin, rather than pulling this pin directly to Vss.

† **NOTICE:** Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 313

FIGURE 25-1: PIC18F2X1X/4X1X VOLTAGE-FREQUENCY GRAPH (INDUSTRIAL)






FIGURE 25-2: PIC18F2X1X/4X1X VOLTAGE-FREQUENCY GRAPH (EXTENDED)





**FIGURE 25-3:** PIC18LF2X1X/4X1X VOLTAGE-FREQUENCY GRAPH (INDUSTRIAL)

**Preliminary** © 2004 Microchip Technology Inc. DS39636A-page 315

25.1 DC Characteristics: Supply Voltage

PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial)

| PIC18LF2X1X/4X1X<br>(Industrial)          |      |  |   | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial |      |       |   |  |  |  |
|---|------|--|---|--|------|-------|---|--|--|--|
| PIC18F2X1X/4X1X<br>(Industrial, Extended) |      |  | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |  |      |       |   |  |  |  |
| Param No. Characteristic                  |      |  |   | Тур  | Max  | Units | Conditions                                |  |  |  |
| D001                                      | VDD  | Supply Voltage   |   |  |      |       |   |  |  |  |
|   |      | PIC18LF2X1X/4X1X   | 2.0   | -  | 5.5  | ٧     | HS, XT, RC and LP Oscillator mode         |  |  |  |
|   |      | PIC18F2X1X/4X1X  | 4.2   | _  | 5.5  | V     |   |  |  |  |
| D002                                      | VDR  | RAM Data Retention<br>Voltage <sup>(1)</sup>                     | 1.5   | _  | _    | V     |   |  |  |  |
| D003                                      | VPOR | VDD Start Voltage<br>to ensure internal<br>Power-on Reset signal |   |  | 0.7  | V     | See section on Power-on Reset for details |  |  |  |
| D004                                      | SVDD | VDD Rise Rate<br>to ensure internal<br>Power-on Reset signal     | 0.05  | _  | _    | V/ms  | See section on Power-on Reset for details |  |  |  |
|   | VBOR | Brown-out Reset Voltag   | е   |  | •    |       |   |  |  |  |
| D005                                      |      | PIC18LF2X1X/4X1X   |   |  |      |       |   |  |  |  |
|   |      | BORV1:BORV0 = 11   | NA  | 2.05   | 2.16 | V     |   |  |  |  |
| BORV1:BORV0 = 10                          |      |  |   | 2.79   | 2.93 | V     |   |  |  |  |
| D005                                      |      | All devices  |   |  | •    |       | •   |  |  |  |
|   |      | BORV1:BORV0 = 01   | 4.11  | 4.33   | 4.55 | V     |   |  |  |  |
|   |      | BORV1:BORV0 = 00   | 4.36  | 4.59   | 4.82 | V     |   |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

### 25.2 DC Characteristics: Power-Down and Supply Current PIC18F2X1X/4X1X (Industrial)

PIC18LF2X1X/4X1X (Industrial)

| PIC18LF22<br>(Indust | -                          | Standard Operating Conditions (unless otherwise stated)<br>Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial |   |       |                               |                                     |  |  |  |  |
|----------------------|----------------------------|---|---|-------|-------------------------------|-------------------------------------|--|--|--|--|
| PIC18F2X             | 1X/4X1X<br>rial, Extended) |   | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |       |                               |                                     |  |  |  |  |
| ParamNo.             | Device                     | Тур   | Max   | Units | Condit                        | ons                                 |  |  |  |  |
|                      | Power-down Current (IPD)   | ower-down Current (IPD) <sup>(1)</sup>  |   |       |                               |                                     |  |  |  |  |
|                      | PIC18LF2X1X/4X1X           | 0.1   | 950   | nA    | -40°C                         | \/pp                                |  |  |  |  |
|                      |                            | 0.1   | 1.0   | μΑ    | +25°C                         | VDD = 2.0V,<br>( <b>Sleep</b> mode) |  |  |  |  |
|                      |                            | 0.2   | 5   | μΑ    | +85°C                         | (Sieep mode)                        |  |  |  |  |
|                      | PIC18LF2X1X/4X1X           | 0.1   | 1.4   | μΑ    | -40°C                         | \/pp 2.0\/                          |  |  |  |  |
|                      |                            | 0.1   | 2   | μΑ    | +25°C                         | VDD = 3.0V,<br>( <b>Sleep</b> mode) |  |  |  |  |
|                      |                            | 0.3   | 8   | μΑ    | +85°C                         | (Gleep mode)                        |  |  |  |  |
|                      | All devices                | 0.1   | 1.9   | μΑ    | -40°C                         |                                     |  |  |  |  |
|                      |                            |   | 2.0   | μΑ    | +25°C                         | VDD = 5.0V,                         |  |  |  |  |
|                      |                            | 0.4   | 15  | μΑ    | μA +85°C ( <b>Sleep</b> mode) |                                     |  |  |  |  |
|                      | Extended devices only      | 10  | 120   | μΑ    | +125°C                        | +125°C                              |  |  |  |  |

Legend: Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 317

25.2 DC Characteristics: Power-Down and Supply Current

PIC18F2X1X/4X1X (Industrial)

PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF2 |   | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial |      |       |            |             |   |  |  |  |  |
|----------|---|--|------|-------|------------|-------------|---|--|--|--|--|
| PIC18F2X | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |  |      |       |            |             |   |  |  |  |  |
| ParamNo. | Device  | Тур  | Max  | Units | Conditions |             |   |  |  |  |  |
|          | Supply Current (IDD) <sup>(2,3)</sup>   |  |      |       |            |             |   |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 15   | 31.5 | μΑ    | -40°C      |             |   |  |  |  |  |
|          |   | 15   | 30   | μΑ    | +25°C      | VDD = 2.0V  |   |  |  |  |  |
|          |   | 15   | 28.5 | μΑ    | +85°C      |             | Fosc = 31 kHz<br>( <b>RC_RUN</b> mode,<br>INTRC source) |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 40   | 63   | μΑ    | -40°C      |             |   |  |  |  |  |
|          |   | 35   | 60   | μΑ    | +25°C      | VDD = 3.0V  |   |  |  |  |  |
|          |   | 30   | 57   | μΑ    | +85°C      |             |   |  |  |  |  |
|          | All devices   | 105  | 168  | μΑ    | -40°C      |             |   |  |  |  |  |
|          |   | 90   | 160  | μΑ    | +25°C      | VDD = 5.0V  |   |  |  |  |  |
|          |   | 80   | 152  | μΑ    | +85°C      | VDD = 3.0 V |   |  |  |  |  |
|          | Extended devices only   | 80   | 250  | μΑ    | +125°C     |             |   |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 0.32   | 1    | mA    | -40°C      |             |   |  |  |  |  |
|          |   | 0.33   | 1    | mA    | +25°C      | VDD = 2.0V  |   |  |  |  |  |
|          |   | 0.33   | 1    | mA    | +85°C      |             |   |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 0.6  | 1.3  | mA    | -40°C      |             | 5000 4 MH-  |  |  |  |  |
|          |   | 0.55   | 1.2  | mA    | +25°C      | VDD = 3.0V  | Fosc = 1 MHz<br>( <b>RC_RUN</b> mode,                   |  |  |  |  |
|          |   | 0.6  | 1.1  | mA    | +85°C      | VDD = 5.0V  | INTOSC source)  |  |  |  |  |
|          | All devices   | 1.1  | 2.3  | mA    | -40°C      |             |   |  |  |  |  |
|          |   | 1.1  | 2.2  | mA    | +25°C      |             |   |  |  |  |  |
|          |   | 1.0  | 2.1  | mA    | +85°C      |             |   |  |  |  |  |
|          | Extended devices only   | 1  | 3.3  | mA    | +125°C     |             |   |  |  |  |  |

Legend:

Shading of rows is to assist in readability of the table.

- Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).
  - 2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in k $\Omega$ .
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

# 25.2 DC Characteristics: Power-Down and Supply Current PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF2            |                                       | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial  |     |       |        |                          |   |  |  |
|---------------------|---------------------------------------|---|-----|-------|--------|--------------------------|---|--|--|
| PIC18F2X<br>(Indust | 1X/4X1X<br>rial, Extended)            | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended |     |       |        |                          |   |  |  |
| ParamNo.            | Device                                | Тур   | Max | Units |        | Conditio                 | ns  |  |  |
|                     | Supply Current (IDD) <sup>(2,3)</sup> |   |     |       |        |                          |   |  |  |
|                     | PIC18LF2X1X/4X1X                      | 0.8   | 2.1 | μΑ    | -40°C  |                          |   |  |  |
|                     |                                       | 8.0   | 2.0 | μΑ    | +25°C  | VDD = 2.0V               |   |  |  |
|                     |                                       | 0.8   | 1.9 | μΑ    | +85°C  |                          | Fosc = 4 MHz<br>( <b>RC_RUN</b> mode,<br>INTOSC source) |  |  |
|                     | PIC18LF2X1X/4X1X                      | 1.3   | 3.0 | mA    | -40°C  |                          |   |  |  |
|                     |                                       | 1.3   | 3.0 | mA    | +25°C  | VDD = 3.0V               |   |  |  |
|                     |                                       | 1.3   | 3.0 | mA    | +85°C  |                          |   |  |  |
|                     | All devices                           | 2.5   | 5.3 | mA    | -40°C  |                          |   |  |  |
|                     |                                       | 2.5   | 5.0 | mA    | +25°C  | VDD = 5.0V               |   |  |  |
|                     |                                       | 2.5   | 4.8 | mA    | +85°C  | VDD = 3.0 V              |   |  |  |
|                     | Extended devices only                 | 2.5   | 10  | mA    | +125°C |                          |   |  |  |
|                     | PIC18LF2X1X/4X1X                      | 2.9   | 8   | μΑ    | -40°C  |                          |   |  |  |
|                     |                                       | 3.1   | 8   | μΑ    | +25°C  | VDD = 2.0V               |   |  |  |
|                     |                                       | 3.6   | 11  | μΑ    | +85°C  |                          |   |  |  |
|                     | PIC18LF2X1X/4X1X                      | 4.5   | 11  | μΑ    | -40°C  | _                        | F000 24 kH=   |  |  |
|                     |                                       | 4.8   | 11  | μΑ    | +25°C  | VDD = 3.0V<br>VDD = 5.0V | Fosc = 31 kHz<br>( <b>RC_IDLE</b> mode,                 |  |  |
|                     |                                       | 5.8   | 15  | μΑ    | +85°C  |                          | INTRC source)   |  |  |
|                     | All devices                           | 9.2   | 16  | μΑ    | -40°C  |                          | ivino soulce)   |  |  |
|                     |                                       | 9.8   | 16  | μΑ    | +25°C  |                          |   |  |  |
|                     |                                       | 11.4  | 36  | μΑ    | +85°C  | V DD = 3.0 V             |   |  |  |
|                     | Extended devices only                 | 21  | 180 | μΑ    | +125°C |                          |   |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- **3:** For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 319

25.2 DC Characteristics: Power-Down and Supply Current

PIC18F2X1X/4X1X (Industrial)

PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF2 |   | Standard Operating Conditions (unless otherwise stated)  Operating temperature -40°C ≤ TA ≤ +85°C for industrial |     |       |            |                          |  |  |  |  |  |
|----------|---|--|-----|-------|------------|--------------------------|--|--|--|--|--|
| PIC18F2X | Standard Operating Conditions (unless otherwise stated)<br>Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended |  |     |       |            |                          |  |  |  |  |  |
| ParamNo. | Device  | Тур  | Max | Units | Conditions |                          |  |  |  |  |  |
|          | Supply Current (IDD) <sup>(2,3)</sup>   |  |     |       |            |                          |  |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 165  | 350 | μΑ    | -40°C      |                          |  |  |  |  |  |
|          |   | 175  | 350 | μΑ    | +25°C      | VDD = 2.0V               |  |  |  |  |  |
|          |   | 190  | 350 | μΑ    | +85°C      |                          | Fosc = 1 MHz<br>( <b>RC_IDLE</b> mode,<br>INTOSC source) |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 250  | 500 | μΑ    | -40°C      |                          |  |  |  |  |  |
|          |   | 270  | 500 | μΑ    | +25°C      | VDD = 3.0V               |  |  |  |  |  |
|          |   | 290  | 500 | μΑ    | +85°C      |                          |  |  |  |  |  |
|          | All devices   | 500  | 1   | mA    | -40°C      |                          |  |  |  |  |  |
|          |   | 520  | 1   | mA    | +25°C      | VDD = 5.0V               |  |  |  |  |  |
|          |   | 550  | 1   | mA    | +85°C      | VDD = 3.0V               |  |  |  |  |  |
|          | Extended devices only   | 0.6  | 2.9 | mA    | +125°C     |                          |  |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 340  | 500 | μΑ    | -40°C      |                          |  |  |  |  |  |
|          |   | 350  | 500 | μΑ    | +25°C      | VDD = 2.0V               |  |  |  |  |  |
|          |   | 360  | 500 | μΑ    | +85°C      |                          |  |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 520  | 900 | μΑ    | -40°C      |                          |  |  |  |  |  |
|          |   | 540  | 900 | μΑ    | +25°C      | VDD = 3.0V<br>VDD = 5.0V | FOSC = 4 MHz   |  |  |  |  |
|          |   | 580  | 900 | μΑ    | +85°C      |                          | (RC_IDLE mode,<br>INTOSC source)                         |  |  |  |  |
|          | All devices   | 1.0  | 1.6 | mA    | -40°C      |                          |  |  |  |  |  |
|          |   | 1.1  | 1.5 | mA    | +25°C      |                          |  |  |  |  |  |
|          |   | 1.1  | 1.4 | mA    | +85°C      | 3.0V = 0.0V              |  |  |  |  |  |
|          | Extended devices only   | 1.1  | 5.0 | mA    | +125°C     |                          |  |  |  |  |  |

Legend:

Shading of rows is to assist in readability of the table.

- Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).
  - 2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

# 25.2 DC Characteristics: Power-Down and Supply Current PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial) (Continued)

Operating temperature

PIC18LF2X1X/4X1X

(Industrial)

| (Indust  | Operating temperature -40°C ≤ TA ≤ +85°C for industrial |   |                          |    |        |            |  |  |  |  |
|----------|---|---|--------------------------|----|--------|------------|--|--|--|--|
| PIC18F2X | 1X/4X1X<br>rial, Extended)                              | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |                          |    |        |            |  |  |  |  |
| ParamNo. | No. Device  |   | Typ Max Units Conditions |    |        |            |  |  |  |  |
|          | Supply Current (IDD)(2,3)                               |   |                          |    |        |            |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 250   | 500                      | μΑ | -40°C  |            |  |  |  |  |
|          |   | 260   | 500                      | μΑ | +25°C  | VDD = 2.0V |  |  |  |  |
|          |   | 250   | 500                      | μΑ | +85°C  |            |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 550   | 650                      | μΑ | -40°C  |            |  |  |  |  |
|          |   | 480   | 650                      | μΑ | +25°C  | VDD = 3.0V | FOSC = 1 MHz   |  |  |  |
|          |   | 460   | 650                      | μΑ | +85°C  |            | (PRI_RUN,<br>EC oscillator)                          |  |  |  |
|          | All devices   | 1.2   | 1.6                      | mA | -40°C  |            |  |  |  |  |
|          |   | 1.1   | 1.5                      | mA | +25°C  | VDD = 5.0V |  |  |  |  |
|          |   | 1.0   | 1.4                      | mA | +85°C  |            |  |  |  |  |
|          | Extended devices only                                   | 1.0   | 3.5                      | mA | +125°C |            |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 0.72  | 2.0                      | mA | -40°C  |            | Fosc = 4 MHz<br>( <b>PRI_RUN</b> ,<br>EC oscillator) |  |  |  |
|          |   | 0.74  | 2.0                      | mA | +25°C  | VDD = 2.0V |  |  |  |  |
|          |   | 0.74  | 2.0                      | mA | +85°C  |            |  |  |  |  |
|          | PIC18LF2X1X/4X1X  | 1.3   | 3.0                      | mA | -40°C  |            |  |  |  |  |
|          |   | 1.3   | 3.0                      | mA | +25°C  | VDD = 3.0V |  |  |  |  |
|          |   | 1.3   | 3.0                      | mA | +85°C  |            |  |  |  |  |
|          | All devices   | 2.7   | 6.0                      | mA | -40°C  |            |  |  |  |  |
|          |   | 2.6   | 6.0                      | mA | +25°C  | VDD = 5.0V |  |  |  |  |
|          |   | 2.5   | 6.0                      | mA | +85°C  |            |  |  |  |  |
|          | Extended devices only                                   | 2.6   | 7.0                      | mA | +125°C |            |  |  |  |  |
|          | Extended devices only                                   | 8.4   | 21                       | mA | +125°C | VDD = 4.2V | Fosc = 25 MHz  |  |  |  |
|          |   | 11  | 28                       | mA | +125°C | VDD = 5.0V | ( <b>PRI_RUN</b> ,<br>EC oscillator)                 |  |  |  |
|          | All devices   | 15  | 35                       | mA | -40°C  | VDD = 4.2V |  |  |  |  |
|          |   | 16  | 35                       | mA | +25°C  |            | F 40 MI  |  |  |  |
|          |   | 16  | 35                       | mA | +85°C  |            | Fosc = 40 MHz<br>( <b>PRI_RUN</b> ,                  |  |  |  |
|          | All devices   | 21  | 40                       | mA | -40°C  | _          | EC oscillator)                                       |  |  |  |
|          |   | 21  | 40                       | mA | +25°C  | VDD = 5.0V | ,  |  |  |  |
|          |   | 21  | 40                       | mA | +85°C  |            |  |  |  |  |

Standard Operating Conditions (unless otherwise stated)

 $-40^{\circ}$ C < T<sub>A</sub> <  $\pm 85^{\circ}$ C for industrial

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all  $\ensuremath{\mathsf{IDD}}$  measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through RexT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

25.2 DC Characteristics: Power-Down and Supply Current

PIC18F2X1X/4X1X (Industrial)

PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF2            |                                       |   | andard Operating Conditions (unless otherwise stated) perating temperature -40°C ≤ TA ≤ +85°C for industrial |       |        |             |                                   |  |  |  |
|---------------------|---------------------------------------|---|--|-------|--------|-------------|-----------------------------------|--|--|--|
| PIC18F2X<br>(Indust | 1X/4X1X<br>rial, Extended)            | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |  |       |        |             |                                   |  |  |  |
| ParamNo.            | Device                                | Тур   | Max  | Units |        | Conditio    | ns                                |  |  |  |
|                     | Supply Current (IDD) <sup>(2,3)</sup> |   |  |       |        |             |                                   |  |  |  |
|                     | All devices                           | 7.5   | 16   | mA    | -40°C  |             |                                   |  |  |  |
|                     |                                       | 7.4   | 15   | mA    | +25°C  | VDD = 4.2V  | FOSC = 4 MHZ<br>(PRI_RUN HS+PLL)  |  |  |  |
|                     |                                       | 7.3   | 14   | mA    | +85°C  |             |                                   |  |  |  |
|                     | Extended devices only                 | 8.0   | 25   | mA    | +125°C |             |                                   |  |  |  |
|                     | All devices                           | 10  | 21   | mA    | -40°C  |             | Fosc = 4 MHz                      |  |  |  |
|                     |                                       | 10  | 20   | mA    | +25°C  | VDD = 5.0V  |                                   |  |  |  |
|                     |                                       | 9.7   | 19   | mA    | +85°C  | VDD = 3.0 V | (PRI_RUN HS+PLL)                  |  |  |  |
|                     | Extended devices only                 | 10  | 35   | mA    | +125°C |             |                                   |  |  |  |
|                     | All devices                           | 17  | 35   | mA    | -40°C  |             | F 40 MH-                          |  |  |  |
|                     |                                       | 17  | 35   | mA    | +25°C  | VDD = 4.2V  | Fosc = 10 MHz<br>(PRI_RUN HS+PLL) |  |  |  |
|                     |                                       | 17  | 35   | mA    | +85°C  |             | (i iii_iioii iio+i EE)            |  |  |  |
|                     | All devices                           | 23  | 40   | mA    | -40°C  | F000 40 MUZ |                                   |  |  |  |
|                     |                                       | 23  | 40   | mA    | +25°C  | VDD = 5.0V  | Fosc = 10 MHz<br>(PRI_RUN HS+PLL) |  |  |  |
|                     |                                       | 23  | 40   | mA    | +85°C  |             |                                   |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in  $k\Omega$ .
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

# 25.2 DC Characteristics: Power-Down and Supply Current PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF2<br>(Indust | X1X/4X1X<br>trial)          | Standard Operating Conditions (unless otherwise stated)  Operating temperature -40°C ≤ TA ≤ +85°C for industrial |         |       |            |   |  |  |  |
|---------------------|-----------------------------|--|---------|-------|------------|---|--|--|--|
| PIC18F2X<br>(Indust | 1X/4X1X<br>trial, Extended) |  | ard Ope |       | -40°C ≤ TA | ess otherwise states $A \le +85^{\circ}$ C for industant $A \le +125^{\circ}$ C for extension | strial                                   |  |  |
| ParamNo.            | Device                      | Тур  | Max     | Units |            | Conditio  | ns                                       |  |  |
|                     | Supply Current (IDD)(2,3)   |  |         |       |            |   |  |  |  |
|                     | PIC18LF2X1X/4X1X            | 65   | 130     | μΑ    | -40°C      |   |  |  |  |
|                     |                             | 65   | 120     | μΑ    | +25°C      | VDD = 2.0V  |  |  |  |
|                     |                             | 70   | 115     | μΑ    | +85°C      | ]   |  |  |  |
|                     | PIC18LF2X1X/4X1X            | 120  | 270     | μΑ    | -40°C      |   | <b>5 4.1</b> 11                          |  |  |
|                     |                             | 120  | 250     | μΑ    | +25°C      | VDD = 3.0V  | Fosc = 1 MHz<br>( <b>PRI_IDLE</b> mode,  |  |  |
|                     |                             | 130  | 240     | μΑ    | +85°C      |   | EC oscillator)                           |  |  |
|                     | All devices                 | 300  | 480     | μΑ    | -40°C      |   |  |  |  |
|                     |                             | 240  | 450     | μΑ    | +25°C      | VDD = 5.0V  |  |  |  |
|                     |                             | 300  | 430     | μΑ    | +85°C      | VDD = 3.0 V   |  |  |  |
|                     | Extended devices only       | 320  | 900     | μΑ    | +125°C     |   |  |  |  |
|                     | PIC18LF2X1X/4X1X            | 260  | 475     | μΑ    | -40°C      |   |  |  |  |
|                     |                             | 255  | 450     | μΑ    | +25°C      | VDD = 2.0V  |  |  |  |
|                     |                             | 270  | 430     | μΑ    | +85°C      |   |  |  |  |
|                     | PIC18LF2X1X/4X1X            | 420  | 900     | μΑ    | -40°C      |   |  |  |  |
|                     |                             | 430  | 850     | μΑ    | +25°C      | VDD = 3.0V  | FOSC = 4 MHz<br>( <b>PRI_IDLE</b> mode,  |  |  |
|                     |                             | 450  | 810     | μΑ    | +85°C      |   | EC oscillator)                           |  |  |
|                     | All devices                 | 0.9  | 1.5     | mA    | -40°C      |   | ,  |  |  |
|                     |                             | 0.9  | 1.4     | mA    | +25°C      | VDD = 5.0V  |  |  |  |
|                     |                             | 0.9  | 1.3     | mA    | +85°C      | VDD = 3.0 V   |  |  |  |
|                     | Extended devices only       | 1  | 1.2     | mA    | +125°C     |   |  |  |  |
|                     | Extended devices only       | 2.8  | 7.0     | mA    | +125°C     | VDD = 4.2V  | Fosc = 25 MHz                            |  |  |
|                     |                             | 4.3  | 11      | mA    | +125°C     | VDD = 5.0V  | (PRI_IDLE mode,<br>EC oscillator)        |  |  |
|                     | All devices                 | 6.0  | 16      | mA    | -40°C      | _   |  |  |  |
|                     |                             | 6.2  | 16      | mA    | +25°C      | VDD = 4.2V  | F000 40 MH-                              |  |  |
|                     |                             | 6.6  | 16      | mA    | +85°C      |   | Fosc = 40 MHz<br>( <b>PRI_IDLE</b> mode, |  |  |
|                     | All devices                 | 8.1  | 18      | mA    | -40°C      |   | EC oscillator)                           |  |  |
|                     |                             | 9.1  | 18      | mA    | +25°C      | VDD = 5.0V  | ,  |  |  |
|                     |                             | 8.3  | 18      | mA    | +85°C      |   |  |  |  |

Legend: Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

## PIC18F2X1X/4X1X

25.2 DC Characteristics: Power-Down and Supply Current PIC18F2X1X/4X1X (Industrial)

PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF22<br>(Indust |                                       |      | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial  |       |       |            |                              |  |  |  |  |
|----------------------|---------------------------------------|------|---|-------|-------|------------|------------------------------|--|--|--|--|
| PIC18F2X             | 1X/4X1X<br>rial, Extended)            |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |       |       |            |                              |  |  |  |  |
| ParamNo.             | Device                                | Тур  | Max   | Units |       | Conditio   | ns                           |  |  |  |  |
|                      | Supply Current (IDD) <sup>(2,3)</sup> |      |   |       |       |            |                              |  |  |  |  |
|                      | PIC18LF2X1X/4X1X                      | 14   | 40  | μΑ    | -40°C |            |                              |  |  |  |  |
|                      |                                       | 15   | 40  | μΑ    | +25°C | VDD = 2.0V |                              |  |  |  |  |
|                      |                                       | 16   | 40  | μΑ    | +85°C |            |                              |  |  |  |  |
|                      | PIC18LF2X1X/4X1X                      | 40   | 74  | μΑ    | -40°C |            | Fosc = 32 kHz <sup>(4)</sup> |  |  |  |  |
|                      |                                       | 35   | 70  | μΑ    | +25°C | VDD = 3.0V | (SEC_RUN mode,               |  |  |  |  |
|                      |                                       | 31   | 67  | μΑ    | +85°C |            | Timer1 as clock)             |  |  |  |  |
|                      | All devices                           | 99   | 150   | μΑ    | -40°C |            |                              |  |  |  |  |
|                      |                                       | 81   | 150   | μΑ    | +25°C | VDD = 5.0V |                              |  |  |  |  |
|                      |                                       | 75   | 150   | μΑ    | +85°C |            |                              |  |  |  |  |
|                      | PIC18LF2X1X/4X1X                      | 2.5  | 12  | μΑ    | -40°C |            |                              |  |  |  |  |
|                      |                                       | 3.7  | 12  | μΑ    | +25°C | VDD = 2.0V |                              |  |  |  |  |
|                      |                                       | 4.5  | 12  | μΑ    | +85°C |            |                              |  |  |  |  |
|                      | PIC18LF2X1X/4X1X                      | 5.0  | 15  | μΑ    | -40°C |            | Fosc = 32 kHz <sup>(4)</sup> |  |  |  |  |
|                      |                                       | 5.4  | 15  | μΑ    | +25°C | VDD = 3.0V | (SEC_IDLE mode,              |  |  |  |  |
|                      |                                       | 6.3  | 15  | μΑ    | +85°C |            | Timer1 as clock)             |  |  |  |  |
|                      | All devices                           | 8.5  | 25  | μΑ    | -40°C |            |                              |  |  |  |  |
|                      |                                       | 9.0  | 25  | μΑ    | +25°C | VDD = 5.0V |                              |  |  |  |  |
|                      |                                       | 10.5 | 36  | μΑ    | +85°C |            |                              |  |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD;

MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- 4: Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

# 25.2 DC Characteristics: Power-Down and Supply Current PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial) (Continued)

| PIC18LF2X<br>(Indust | -                              |          | •        | erating (            | Conditions (unlese -40°C ≤ TA | ss otherwise sta<br>≤ +85°C for indu                      | •                                 |
|----------------------|--------------------------------|----------|----------|----------------------|-------------------------------|---|-----------------------------------|
| PIC18F2X             | IX/4X1X<br>rial, Extended)     |          | -        | rating (<br>perature |                               | ss otherwise sta<br>≤ +85°C for indu:<br>≤ +125°C for ext | strial                            |
| ParamNo.             | Device                         | Тур      | Max      | Units                |                               | Conditio  | ns                                |
|                      | Module Differential Currer     | ıts (∆lw | DT, ∆lBo | or, ∆ <b>i</b> lv    |                               |   |                                   |
| D022                 | Watchdog Timer                 | 1.3      | 3.8      | μΑ                   | -40°C                         |   |                                   |
| (∆lwdt)              |                                | 1.4      | 3.8      | μΑ                   | +25°C                         | VDD = 2.0V  |                                   |
|                      |                                | 2.0      | 3.8      | μΑ                   | +85°C                         |   |                                   |
|                      |                                | 1.9      | 4.6      | μΑ                   | -40°C                         |   |                                   |
|                      |                                | 2.0      | 4.6      | μΑ                   | +25°C                         | VDD = 3.0V  |                                   |
|                      |                                | 2.8      | 4.6      | μΑ                   | +85°C                         |   |                                   |
|                      |                                | 4.0      | 10       | μΑ                   | -40°C                         |   |                                   |
|                      |                                | 5.5      | 10       | μΑ                   | +25°C                         | VDD = 5.0V  |                                   |
|                      |                                | 5.6      | 10       | μΑ                   | +85°C                         | VDD = 0.0 V   |                                   |
|                      |                                | 13       | 13       | μΑ                   | +125°C                        |   |                                   |
| D022A                | Brown-out Reset <sup>(5)</sup> | 35       | 40       | μΑ                   | -40°C to +85°C                | VDD = 3.0V  |                                   |
| (∆lbor)              |                                | 40       | 45       | μΑ                   | -40°C to +85°C                |   |                                   |
|                      |                                | 55       | 45       | μΑ                   | -40°C to +125°C               | VDD = 5.0V  |                                   |
|                      |                                | 0        | 5        | μА                   | -40°C to +125°C               |   | Sleep mode,<br>BOREN1:BOREN0 = 10 |
| D022B                | High/Low-Voltage               | 22       | 38       | μΑ                   | -40°C to +85°C                | VDD = 2.0V  |                                   |
| (∆llvd)              | Detect <sup>(5)</sup>          | 25       | 40       | μΑ                   | -40°C to +85°C                | VDD = 3.0V  |                                   |
|                      |                                | 29       | 45       | μΑ                   | -40°C to +85°C                | VDD = 5.0V  |                                   |
|                      |                                | 30       | 45       | μΑ                   | -40°C to +125°C               | VDD = 3.0 V   |                                   |
| D025                 | Timer1 Oscillator              | 2.1      | 4.5      | μΑ                   | -40°C                         |   | 40                                |
| (∆loscb)             |                                | 1.8      | 4.5      | μΑ                   | +25°C                         | VDD = 2.0V  | 32 kHz on Timer1 <sup>(4)</sup>   |
|                      |                                | 2.1      | 4.5      | μΑ                   | +85°C                         |   |                                   |
|                      |                                | 2.2      | 6.0      | μΑ                   | -40°C                         |   |                                   |
|                      |                                | 2.6      | 6.0      | μΑ                   | +25°C                         | VDD = 3.0V  | 32 kHz on Timer1 <sup>(4)</sup>   |
|                      |                                | 2.9      | 6.0      | μΑ                   | +85°C                         |   |                                   |
|                      |                                | 3.0      | 8.0      | μΑ                   | -40°C                         |   | 40                                |
|                      |                                | 3.2      | 8.0      | μΑ                   | +25°C                         | VDD = 5.0V  | 32 kHz on Timer1 <sup>(4)</sup>   |
|                      |                                | 3.4      | 8.0      | μΑ                   | +85°C                         |   |                                   |
| D026                 | A/D Converter                  | 1.0      | 2.0      | μΑ                   | -40°C to +85°C                | VDD = 2.0V  |                                   |
| (∆IAD)               |                                | 1.0      | 2.0      | μΑ                   | -40°C to +85°C                | VDD = 3.0V  | A/D on, not converting            |
|                      |                                | 1.0      | 2.0      | μΑ                   | -40°C to +85°C                | VDD = 5.0V  | TAND OII, HOL CONVERTING          |
|                      |                                | 2.0      | 8.0      | μΑ                   | -40°C to +125°C               |   |                                   |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT enabled/disabled as specified.

- 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2REXT (mA) with REXT in kΩ.
- Low-power Timer1 oscillator selected.
- 5: BOR and HLVD enable internal band gap reference. With both modules enabled, current consumption will be less than the sum of both specifications.

# 25.3 DC Characteristics: PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial)

| DC CHA                          | RACTE  | RISTICS                                 |                                  |                               |             | unless otherwise stated)<br>≤ +85°C for industrial |
|---------------------------------|--------|---|----------------------------------|-------------------------------|-------------|--|
| Param<br>No.                    | Symbol | Characteristic                          | Min                              | Max                           | Units       | Conditions   |
|                                 | VIL    | Input Low Voltage                       |                                  |                               |             |  |
|                                 |        | I/O ports:                              |                                  |                               |             |  |
| D030                            |        | with TTL buffer                         | Vss                              | 0.15 VDD                      | V           | VDD < 4.5V   |
| D030A                           |        |   | _                                | 0.8                           | V           | $4.5V \le VDD \le 5.5V$                            |
| D031                            |        | with Schmitt Trigger buffer RC3 and RC4 | Vss<br>Vss                       | 0.2 VDD<br>0.3 VDD            | V<br>V      |  |
| D032                            |        | MCLR                                    | Vss                              | 0.2 VDD                       | V           |  |
| D033                            |        | OSC1                                    | Vss                              | 0.3 VDD                       | V           | HS, HSPLL modes                                    |
| D033A<br>D033B<br>D034          |        | OSC1<br>OSC1<br>T13CKI                  | Vss<br>Vss<br>Vss                | 0.2 VDD<br>0.3 VDD<br>0.3 VDD | V<br>V<br>V | RC, EC modes <sup>(1)</sup><br>XT, LP modes        |
| D034                            | ViH    | Input High Voltage                      | V 55                             | 0.3 VDD                       | V           |  |
|                                 | VIII   | I/O ports:                              |                                  |                               |             |  |
| D040                            |        | with TTL buffer                         | 0.25 Vpp + 0.8V                  | VDD                           | V           | VDD < 4.5V   |
| D040A                           |        |   | 2.0                              | VDD                           | V           | 4.5V ≤ VDD ≤ 5.5V                                  |
| D041                            |        | with Schmitt Trigger buffer RC3 and RC4 | 0.8 VDD<br>0.7 VDD               | VDD<br>VDD                    | V           |  |
| D042                            |        | MCLR                                    | 0.8 VDD                          | VDD                           | V           |  |
| D043                            |        | OSC1                                    | 0.7 VDD                          | VDD                           | V           | HS, HSPLL modes                                    |
| D043A<br>D043B<br>D043C<br>D044 |        | OSC1<br>OSC1<br>OSC1<br>T13CKI          | 0.8 VDD<br>0.9 VDD<br>1.6<br>1.6 | VDD<br>VDD<br>VDD<br>VDD      | V<br>V<br>V | EC mode<br>RC mode <sup>(1)</sup><br>XT, LP modes  |
|                                 | lı∟    | Input Leakage Current <sup>(2,3)</sup>  |                                  |                               |             |  |
| D060                            |        | I/O ports                               | _                                | ±1                            | μΑ          | Vss ≤ VPIN ≤ VDD,<br>Pin at high-impedance         |
| D061                            |        | MCLR                                    | _                                | ±5                            | μΑ          | Vss ≤ Vpin ≤ Vdd                                   |
| D063                            |        | OSC1                                    | _                                | ±5                            | μA          | Vss ≤ Vpin ≤ Vdd                                   |
|                                 | IPU    | Weak Pull-up Current                    |                                  |                               |             |  |
| D070                            | IPURB  | PORTB weak pull-up current              | 50                               | 400                           | μΑ          | VDD = 5V, VPIN = VSS                               |

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro<sup>®</sup> device be driven with an external clock while in RC mode.

- **3:** Negative current is defined as current sourced by the pin.
- 4: Parameter is characterized but not tested.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

# 25.3 DC Characteristics: PIC18F2X1X/4X1X (Industrial) PIC18LF2X1X/4X1X (Industrial) (Continued)

| DC CHA              | RACTE             | RISTICS                                 | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial |     |       |  |  |
|---------------------|-------------------|---|--|-----|-------|--|--|
| Param<br>No.        | Symbol            | Characteristic                          | Min  | Max | Units | Conditions   |  |
|                     | Vol               | Output Low Voltage                      |  |     |       |  |  |
| D080                |                   | I/O ports                               | _  | 0.6 | V     | IOL = $8.5 \text{ mA}$ , VDD = $4.5 \text{V}$ , $-40^{\circ}\text{C}$ to $+85^{\circ}\text{C}$ |  |
| D083                |                   | OSC2/CLKO<br>(RC, RCIO, EC, ECIO modes) | _  | 0.6 | V     | IOL = $1.6 \text{ mA}$ , VDD = $4.5 \text{V}$ , $-40^{\circ}\text{C}$ to $+85^{\circ}\text{C}$ |  |
|                     | Vон               | Output High Voltage <sup>(3)</sup>      |  |     |       |  |  |
| D090                |                   | I/O ports                               | VDD - 0.7  | _   | V     | IOH = $-3.0$ mA, VDD = $4.5$ V, $-40$ °C to $+85$ °C   |  |
| D092                |                   | OSC2/CLKO<br>(RC, RCIO, EC, ECIO modes) | VDD - 0.7  | _   | V     | IOH = -1.3 mA, $VDD = 4.5V$ , $-40^{\circ}C$ to $+85^{\circ}C$                                 |  |
|                     |                   | Capacitive Loading Specs on Output Pins |  |     |       |  |  |
| D100 <sup>(4)</sup> | Cosc <sub>2</sub> | OSC2 pin                                | _  | 15  | pF    | In XT, HS and LP modes when external clock is used to drive OSC1                               |  |
| D101                | Сю                | All I/O pins and OSC2<br>(in RC mode)   | _  | 50  | pF    | To meet the AC Timing Specifications   |  |
| D102                | Св                | SCL, SDA                                | _  | 400 | pF    | I <sup>2</sup> C™ Specification  |  |

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro<sup>®</sup> device be driven with an external clock while in RC mode.

- 2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
- 3: Negative current is defined as current sourced by the pin.
- 4: Parameter is characterized but not tested.

## **PIC18F2X1X/4X1X**

TABLE 25-1: MEMORY PROGRAMMING REQUIREMENTS

| DC Cha       | racteris | stics  | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial |      |      |       |   |  |
|--------------|----------|--|--|------|------|-------|---|--|
| Param<br>No. | Sym      | Characteristic   | Min  | Тур† | Max  | Units | Conditions                                    |  |
|              |          | Internal Program Memory<br>Programming Specifications <sup>(1)</sup> |  |      |      |       |   |  |
| D110         | VPP      | Voltage on MCLR/VPP/RE3 pin  | VDD + 4  | _    | 12.5 | V     | (Note 2)                                      |  |
| D113         | IDDP     | Supply Current during<br>Programming                                 | _  | 10   | _    | mA    |   |  |
|              |          | Program Flash Memory   |  |      |      |       |   |  |
| D130         | EР       | Cell Endurance   | 10K  | 100K | _    | E/W   | -40°C to +85°C                                |  |
| D131         | VPR      | VDD for Read   | VMIN   | _    | 5.5  | V     | VMIN = Minimum operating voltage              |  |
| D132         | VIE      | VDD for Block Erase  | 4.5  | _    | 5.5  | V     | Using ICSP™ port                              |  |
| D132A        | Viw      | VDD for Externally Timed Erase or Write                              | 4.5  | _    | 5.5  | V     | Using ICSP port                               |  |
| D133         | TIE      | ICSP Block Erase Cycle Time  | _  | 4    | _    | ms    | VDD > 4.5V                                    |  |
| D133A        | Tıw      | ICSP Erase or Write Cycle Time (externally timed)                    | 1  | _    | _    | ms    | VDD > 4.5V                                    |  |
| D134         | TRETD    | Characteristic Retention   | 40   | 100  | _    | Year  | Provided no other specifications are violated |  |

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

**Note 1:** These specifications are for programming the on-chip program memory through the use of table write instructions.

**<sup>2:</sup>** Required only if Single-Supply programming is disabled.

ns

μs

10

VDD = 2.0V

#### TABLE 25-2: **COMPARATOR SPECIFICATIONS**

301

TMC2OV

**Operating Conditions:** 3.0V < VDD < 5.5V,  $-40^{\circ}C < TA < +85^{\circ}C$  (unless otherwise stated). **Param** Characteristics Min Max Units Comments Sym Тур No. D300 VIOFF Input Offset Voltage  $\pm 5.0$ ± 10 m۷ D301 VICM Input Common Mode Voltage\* 0 VDD - 1.5V D302 CMRR Common Mode Rejection Ratio\* 55 dΒ Response Time(1)\* 300 TRESP 150 400 PIC18FXXXX ns 300A 150 600 PIC18LFXXXX,

Output Valid\*

Comparator Mode Change to

Note 1: Response time measured with one comparator input at (VDD - 1.5)/2, while the other input transitions from Vss to VDD.

#### **VOLTAGE REFERENCE SPECIFICATIONS TABLE 25-3:**

| Operating    | Operating Conditions: 3.0V < VDD < 5.5V, -40°C < TA < +85°C (unless otherwise stated). |                               |        |     |        |       |          |  |  |  |  |
|--------------|--|-------------------------------|--------|-----|--------|-------|----------|--|--|--|--|
| Param<br>No. | Sym  | Characteristics               | Min    | Тур | Max    | Units | Comments |  |  |  |  |
| D310         | VRES   | Resolution                    | VDD/24 | _   | VDD/32 | LSb   |          |  |  |  |  |
| D311         | VRAA   | Absolute Accuracy             | _      | _   | 1/2    | LSb   |          |  |  |  |  |
| D312         | VRur   | Unit Resistor Value (R)*      | _      | 2k  | _      | Ω     |          |  |  |  |  |
| 310          | TSET   | Settling Time <sup>(1)*</sup> | _      | _   | 10     | μs    |          |  |  |  |  |

These parameters are characterized but not tested.

Note 1: Settling time measured while CVRR = 1 and CVR3:CVR0 transitions from '0000' to '1111'.

**Preliminary** © 2004 Microchip Technology Inc. DS39636A-page 329

These parameters are characterized but not tested.

FIGURE 25-4: HIGH/LOW-VOLTAGE DETECT CHARACTERISTICS




TABLE 25-4: HIGH/LOW-VOLTAGE DETECT CHARACTERISTICS

Standard Operating Conditions (unless otherwise stated)

| Param<br>No. | Symbol | Characteristic         |            | Min  | Тур† | Max      | Units | Conditions |
|--------------|--------|------------------------|------------|------|------|----------|-------|------------|
| D420         |        | HLVD Voltage on VDD    | LVV = 0000 | 2.06 | 2.17 | 2.28     | V     |            |
|              |        | Transition High to Low | LVV = 0001 | 2.12 | 2.23 | 2.34     | V     |            |
|              |        |                        | LVV = 0010 | 2.24 | 2.36 | 2.48     | V     |            |
|              |        |                        | LVV = 0011 | 2.32 | 2.44 | 2.56     | V     |            |
|              |        |                        | LVV = 0100 | 2.47 | 2.60 | 2.73     | >     |            |
|              |        | LVV = 0101             | 2.65       | 2.79 | 2.93 | V        |       |            |
|              |        | LVV = 0110             | 2.74       | 2.89 | 3.04 | V        |       |            |
|              |        | LVV = 0111             | 2.96       | 3.12 | 3.28 | V        |       |            |
|              |        |                        | LVV = 1000 | 3.22 | 3.39 | 3.56     | V     |            |
|              |        |                        | LVV = 1001 | 3.37 | 3.55 | 3.73     | V     |            |
|              |        |                        | LVV = 1010 | 3.52 | 3.71 | 3.90     | V     |            |
|              |        |                        | LVV = 1011 | 3.70 | 3.90 | 4.10     | V     |            |
|              |        | LVV = 1100             | 3.90       | 4.11 | 4.32 | <b>V</b> |       |            |
|              |        |                        | LVV = 1101 | 4.11 | 4.33 | 4.55     | V     |            |
|              |        |                        | LVV = 1110 | 4.36 | 4.59 | 4.82     | V     |            |

 $<sup>\</sup>dagger$  Production tested at TAMB = 25°C. Specifications over temperature limits ensured by characterization.

### 25.4 AC (Timing) Characteristics

#### 25.4.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created using one of the following formats:

| 1. TppS2pp               | S                               | 3. Tcc:st | (I <sup>2</sup> C specifications only) |
|--------------------------|---------------------------------|-----------|--|
| 2. TppS                  |                                 | 4. Ts     | (I <sup>2</sup> C specifications only) |
| Т                        |                                 |           |  |
| F                        | Frequency                       | Т         | Time                                   |
| Lowercase I              | etters (pp) and their meanings: |           |  |
| рр                       |                                 |           |  |
| CC                       | CCP1                            | osc       | OSC1                                   |
| ck                       | CLKO                            | rd        | RD                                     |
| cs                       | <del>CS</del>                   | rw        | RD or WR                               |
| di                       | SDI                             | sc        | SCK                                    |
| do                       | SDO                             | SS        | SS                                     |
| dt                       | Data in                         | t0        | TOCKI                                  |
| io                       | I/O port                        | t1        | T13CKI                                 |
| mc                       | MCLR                            | wr        | WR                                     |
| Uppercase I              | etters and their meanings:      |           |  |
| S                        |                                 |           |  |
| F                        | Fall                            | Р         | Period                                 |
| Н                        | High                            | R         | Rise                                   |
| 1                        | Invalid (High-impedance)        | V         | Valid                                  |
| L                        | Low                             | Z         | High-impedance                         |
| I <sup>2</sup> C only    |                                 |           |  |
| AA                       | output access                   | High      | High                                   |
| BUF                      | Bus free                        | Low       | Low                                    |
| Tcc:st (I <sup>2</sup> C | specifications only)            |           |  |
| CC                       |                                 |           |  |
| HD                       | Hold                            | SU        | Setup                                  |
| ST                       |                                 |           |  |
| DAT                      | DATA input hold                 | STO       | Stop condition                         |
| STA                      | Start condition                 |           |  |

#### 25.4.2 TIMING CONDITIONS

The temperature and voltages specified in Table 25-5 apply to all timing specifications unless otherwise noted. Figure 25-5 specifies the load conditions for the timing specifications.


Because of space limitations, the generic terms "PIC18FXXXX" and "PIC18LFXXXX" are used throughout this section to refer to the PIC18F2X1X/4X1X and PIC18LF2X1X/4X1X families of devices specifically and only those devices.

#### TABLE 25-5: TEMPERATURE AND VOLTAGE SPECIFICATIONS – AC

Standard Operating Conditions (unless otherwise stated)
Operating temperature -40°C ≤ TA ≤ +85°C for industrial
Operating voltage VDD range as described in DC spec Section 25.1 and
Section 25.3.
LF parts operate for industrial temperatures only.

Note:

#### FIGURE 25-5: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



#### 25.4.3 TIMING DIAGRAMS AND SPECIFICATIONS

FIGURE 25-6: EXTERNAL CLOCK TIMING (ALL MODES EXCEPT PLL)




TABLE 25-6: EXTERNAL CLOCK TIMING REQUIREMENTS

| Param.<br>No. | Symbol | Characteristic                        | Min  | Max   | Units | Conditions               |
|---------------|--------|---------------------------------------|------|-------|-------|--------------------------|
| 1A            | Fosc   | External CLKI Frequency(1)            | DC   | 1     | MHz   | XT, RC Oscillator mode   |
|               |        |                                       | DC   | 20    | MHz   | HS Oscillator mode       |
|               |        |                                       | DC   | 31.25 | kHz   | LP Oscillator mode       |
|               |        | Oscillator Frequency <sup>(1)</sup>   | DC   | 4     | MHz   | RC Oscillator mode       |
|               |        |                                       | 0.1  | 4     | MHz   | XT Oscillator mode       |
|               |        |                                       | 4    | 20    | MHz   | HS Oscillator mode       |
|               |        |                                       | 5    | 200   | kHz   | LP Oscillator mode       |
| 1             | Tosc   | External CLKI Period <sup>(1)</sup>   | 1000 | _     | ns    | XT, RC Oscillator mode   |
|               |        |                                       | 50   | _     | ns    | HS Oscillator mode       |
|               |        |                                       | 32   | _     | μs    | LP Oscillator mode       |
|               |        | Oscillator Period <sup>(1)</sup>      | 250  | _     | ns    | RC Oscillator mode       |
|               |        |                                       | 250  | 1     | μs    | XT Oscillator mode       |
|               |        |                                       | 100  | 250   | ns    | HS Oscillator mode       |
|               |        |                                       | 50   | 250   | ns    | HS Oscillator mode       |
|               |        |                                       | 5    |       | μs    | LP Oscillator mode       |
| 2             | TCY    | Instruction Cycle Time <sup>(1)</sup> | 100  | _     | ns    | Tcy = 4/Fosc, Industrial |
|               |        |                                       | 160  |       | ns    | Tcy = 4/Fosc, Extended   |
| 3             | TosL,  | External Clock in (OSC1)              | 30   |       | ns    | XT Oscillator mode       |
|               | TosH   | High or Low Time                      | 2.5  | _     | μs    | LP Oscillator mode       |
|               |        |                                       | 10   |       | ns    | HS Oscillator mode       |
| 4             | TosR,  | External Clock in (OSC1)              | _    | 20    | ns    | XT Oscillator mode       |
|               | TosF   | Rise or Fall Time                     | _    | 50    | ns    | LP Oscillator mode       |
|               |        |                                       | _    | 7.5   | ns    | HS Oscillator mode       |

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period for all configurations except PLL. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "max." cycle time limit is "DC" (no clock) for all devices.

TABLE 25-7: PLL CLOCK TIMING SPECIFICATIONS (VDD = 4.2V TO 5.5V)

| Param<br>No. | Sym             | Characteristic                | Min | Тур† | Max | Units | Conditions   |
|--------------|-----------------|-------------------------------|-----|------|-----|-------|--------------|
| F10          | Fosc            | Oscillator Frequency Range    | 4   |      | 10  | MHz   | HS mode only |
| F11          | Fsys            | On-Chip VCO System Frequency  | 16  |      | 40  | MHz   | HS mode only |
| F12          | t <sub>rc</sub> | PLL Start-up Time (Lock Time) | _   | _    | 2   | ms    |              |
| F13          | $\Delta$ CLK    | CLKO Stability (Jitter)       | -2  | _    | +2  | %     |              |

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 25-8: AC CHARACTERISTICS: INTERNAL RC ACCURACY
PIC18F2X1X/4X1X (INDUSTRIAL)
PIC18LF2X1X/4X1X (INDUSTRIAL)

|              | I8LF2X1X/4X1X       Standard Operating Conditions (unless otherwise stated)         Industrial)       Operating temperature       -40°C ≤ TA ≤ +85°C for industrial |          |   |        |       |                |                |  |  |  |
|--------------|---|----------|---|--------|-------|----------------|----------------|--|--|--|
|              | 2X1X/4X1X<br>ustrial)   |          | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial |        |       |                |                |  |  |  |
| Param<br>No. | Device  | Min      | Тур   | Max    | Units | Conditions     |                |  |  |  |
|              | INTOSC Accuracy @ Freq = 8 MHz  | , 4 MHz, | 4 MHz, 2 MHz, 1 MHz, 500 kHz, 250 kHz, 125 kHz, 31 kHz <sup>(1)</sup>   |        |       |                |                |  |  |  |
|              | PIC18LF2X1X/4X1X  | -2       | +/-1  | 2      | %     | +25°C          | VDD = 2.7-3.3V |  |  |  |
|              |   | -5       | _   | 5      | %     | -10°C to +85°C | VDD = 2.7-3.3V |  |  |  |
|              |   | -10      | +/-1  | 10     | %     | -40°C to +85°C | VDD = 2.7-3.3V |  |  |  |
|              | PIC18F2X1X/4X1X   | -2       | +/-1  | 2      | %     | +25°C          | VDD = 4.5-5.5V |  |  |  |
|              |   | -5       | _   | 5      | %     | -10°C to +85°C | VDD = 4.5-5.5V |  |  |  |
|              |   | -10      | +/-1  | 10     | %     | -40°C to +85°C | VDD = 4.5-5.5V |  |  |  |
|              | INTRC Accuracy @ Freq = 31 kHz <sup>(2)</sup>   |          |   |        |       |                |                |  |  |  |
|              | PIC18LF2X1X/4X1X  | 26.562   | _   | 35.938 | kHz   | -40°C to +85°C | VDD = 2.7-3.3V |  |  |  |
|              | PIC18F2X1X/4X1X   | 26.562   |   | 35.938 | kHz   | -40°C to +85°C | VDD = 4.5-5.5V |  |  |  |

**Legend:** Shading of rows is to assist in readability of the table.

Note 1: Frequency calibrated at 25°C. OSCTUNE register can be used to compensate for temperature drift.

- 2: INTRC frequency after calibration.
- 3: Change of INTRC frequency as VDD changes.

FIGURE 25-7: CLKO AND I/O TIMING

TABLE 25-9: CLKO AND I/O TIMING REQUIREMENTS

| Param<br>No. | Symbol   | Characteris                           | stic                   | Min           | Тур | Max          | Units | Conditions |
|--------------|----------|---------------------------------------|------------------------|---------------|-----|--------------|-------|------------|
| 10           | TosH2ckL | OSC1 ↑ to CLKO ↓                      |                        | _             | 75  | 200          | ns    | (Note 1)   |
| 11           | TosH2ckH | OSC1 ↑ to CLKO ↑                      | SC1 ↑ to CLKO ↑        |               | 75  | 200          | ns    | (Note 1)   |
| 12           | TckR     | CLKO Rise Time                        |                        | _             | 35  | 100          | ns    | (Note 1)   |
| 13           | TckF     | CLKO Fall Time                        |                        | _             | 35  | 100          | ns    | (Note 1)   |
| 14           | TckL2ioV | CLKO ↓ to Port Out Valid              |                        | _             | _   | 0.5 Tcy + 20 | ns    | (Note 1)   |
| 15           | TioV2ckH | Port In Valid before CLKC             | <b>)</b> ↑             | 0.25 TcY + 25 | _   | _            | ns    | (Note 1)   |
| 16           | TckH2iol | Port In Hold after CLKO 1             | `                      | 0             | _   | _            | ns    | (Note 1)   |
| 17           | TosH2ioV | OSC1 ↑ (Q1 cycle) to Po               | rt Out Valid           | _             | 50  | 150          | ns    |            |
| 18           | TosH2iol | OSC1 ↑ (Q2 cycle) to                  | PIC18FXXXX             | 100           | _   | _            | ns    |            |
| 18A          |          | Port Input Invalid (I/O in hold time) | PIC18 <b>LF</b> XXXX   | 200           | _   | _            | ns    | VDD = 2.0V |
| 19           | TioV2osH | Port Input Valid to OSC1 1            | (I/O in setup time)    | 0             | _   | _            | ns    |            |
| 20           | TioR     | Port Output Rise Time                 | PIC18FXXXX             | _             | 10  | 25           | ns    |            |
| 20A          |          |                                       | PIC18 <b>LF</b> XXXX   | _             | _   | 60           | ns    | VDD = 2.0V |
| 21           | TioF     | Port Output Fall Time                 | PIC18FXXXX             | _             | 10  | 25           | ns    |            |
| 21A          |          |                                       | PIC18 <b>LF</b> XXXX   | _             | _   | 60           | ns    | VDD = 2.0V |
| 22†          | TINP     | INT pin High or Low Time              | T pin High or Low Time |               | _   | _            | ns    |            |
| 23†          | TRBP     | RB7:RB4 Change INT Hi                 | gh or Low Time         | Tcy           | _   | _            | ns    |            |

<sup>†</sup> These parameters are asynchronous events not related to any internal clock edges.

**Note 1:** Measurements are taken in RC mode, where CLKO output is 4 x Tosc.

FIGURE 25-8: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING




FIGURE 25-9: BROWN-OUT RESET TIMING




TABLE 25-10: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER AND BROWN-OUT RESET REQUIREMENTS

| Param.<br>No. | Symbol | Characteristic   | Min       | Тур  | Max       | Units | Conditions            |
|---------------|--------|--|-----------|------|-----------|-------|-----------------------|
| 30            | TmcL   | MCLR Pulse Width (low)                                   | 2         | _    | _         | μs    |                       |
| 31            | TWDT   | Watchdog Timer Time-out Period (no postscaler)           | 3.4       | 4.0  | 4.6       | ms    |                       |
| 32            | Tost   | Oscillation Start-up Timer Period                        | 1024 Tosc | _    | 1024 Tosc | _     | Tosc = OSC1 period    |
| 33            | TPWRT  | Power-up Timer Period                                    | 55.6      | 65.5 | 75        | ms    |                       |
| 34            | Tioz   | I/O High-Impedance from MCLR Low or Watchdog Timer Reset |           | 2    | _         | μs    |                       |
| 35            | TBOR   | Brown-out Reset Pulse Width                              | 200       | _    | _         | μs    | VDD ≤ BVDD (see D005) |
| 36            | TIVRST | Time for Internal Reference<br>Voltage to become Stable  | _         | 20   | 50        | μs    |                       |
| 37            | TLVD   | High/Low-Voltage Detect Pulse Width                      | 200       | _    | _         | μs    | VDD ≤ VLVD            |
| 38            | TCSD   | CPU Start-up Time  | _         | 10   | _         | μs    |                       |
| 39            | TIOBST | Time for INTOSC to Stabilize                             | _         | 1    | _         | μs    |                       |

T0CKI T1OSO/T13CKI 48 TMR0 or -TMR1. Refer to Figure 25-5 for load conditions. Note:

FIGURE 25-10: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS

TABLE 25-11: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS

| Param<br>No. | Symbol    |                           | Characteristic       | C                             | Min                                     | Max    | Units | Conditions                               |
|--------------|-----------|---------------------------|----------------------|-------------------------------|---|--------|-------|--|
| 40           | Tt0H      | T0CKI High                | n Pulse Width        | No prescaler                  | 0.5 Tcy + 20                            | _      | ns    |  |
|              |           |                           |                      | With prescaler                | 10                                      | _      | ns    |  |
| 41           | Tt0L      | T0CKI Low                 | Pulse Width          | No prescaler                  | 0.5 Tcy + 20                            | _      | ns    |  |
|              |           |                           |                      | With prescaler                | 10                                      | _      | ns    |  |
| 42           | Tt0P      | T0CKI Peri                | od                   | No prescaler                  | Tcy + 10                                | _      | ns    |  |
|              |           |                           |                      | With prescaler                | Greater of:<br>20 ns or<br>(Tcy + 40)/N | _      | ns    | N = prescale<br>value<br>(1, 2, 4,, 256) |
| 45           | Tt1H      | T13CKI                    | Synchronous, no      | prescaler                     | 0.5 Tcy + 20                            | _      | ns    |  |
|              |           | High Time                 | Synchronous,         | PIC18FXXXX                    | 10                                      | _      | ns    |  |
|              |           |                           | with prescaler       | PIC18 <b>LF</b> XXXX          | 25                                      | _      | ns    | VDD = 2.0V                               |
|              |           |                           | Asynchronous         | PIC18FXXXX                    | 30                                      | _      | ns    |  |
|              |           |                           |                      | PIC18 <b>LF</b> XXXX          | 50                                      |        | ns    | VDD = 2.0V                               |
| 46           | Tt1L      | T13CKI                    | Synchronous, no      | prescaler                     | 0.5 Tcy + 5                             |        | ns    |  |
|              |           | Low Time                  | Synchronous,         | PIC18FXXXX                    | 10                                      |        | ns    |  |
|              |           |                           | with prescaler       | PIC18 <b>LF</b> XXXX          | 25                                      |        | ns    | VDD = 2.0V                               |
|              |           |                           | Asynchronous         | PIC18FXXXX                    | 30                                      |        | ns    |  |
|              |           |                           |                      | PIC18 <b>LF</b> XXXX          | 50                                      | _      | ns    | VDD = 2.0V                               |
| 47           | Tt1P      | T13CKI<br>Input<br>Period | Synchronous          |                               | Greater of:<br>20 ns or<br>(TcY + 40)/N | _      | ns    | N = prescale<br>value (1, 2, 4, 8)       |
|              |           |                           | Asynchronous         |                               | 60                                      |        | ns    |  |
|              | Ft1       | T13CKI Os                 | cillator Input Frequ | illator Input Frequency Range |   | 50     | kHz   |  |
| 48           | Tcke2tmrl | Delay from<br>Timer Incre |                      | xternal T13CKI Clock Edge to  |   | 7 Tosc |       |  |

**Preliminary** © 2004 Microchip Technology Inc. DS39636A-page 337

FIGURE 25-11: CAPTURE/COMPARE/PWM TIMINGS (ALL CCP MODULES)




TABLE 25-12: CAPTURE/COMPARE/PWM REQUIREMENTS (ALL CCP MODULES)

| Param<br>No. | Symbol      | С                | haracteristi | С                    | Min                    | Max | Units | Conditions                         |
|--------------|-------------|------------------|--------------|----------------------|------------------------|-----|-------|------------------------------------|
| 50           | TccL        | CCPx Input Low   | No prescale  | er                   | 0.5 Tcy + 20           |     | ns    |                                    |
|              |             | Time             | With         | PIC18FXXXX           | 10                     | _   | ns    |                                    |
|              |             |                  | prescaler    | PIC18 <b>LF</b> XXXX | 20                     | -   | ns    | VDD = 2.0V                         |
| 51           | TccH        | CCPx Input       | No prescale  | er                   | 0.5 Tcy + 20           | _   | ns    |                                    |
|              | High Time V |                  | With         | PIC18FXXXX           | 10                     | _   | ns    |                                    |
|              |             |                  | prescaler    | PIC18 <b>LF</b> XXXX | 20                     | _   | ns    | VDD = 2.0V                         |
| 52           | TccP        | CCPx Input Perio | od           |                      | <u>3 Tcy + 40</u><br>N | _   | ns    | N = prescale<br>value (1, 4 or 16) |
| 53           | TccR        | CCPx Output Fal  | I Time       | PIC18FXXXX           |                        | 25  | ns    |                                    |
|              |             |                  |              | PIC18 <b>LF</b> XXXX | _                      | 45  | ns    | VDD = 2.0V                         |
| 54           | TccF        | CCPx Output Fal  | I Time       | PIC18FXXXX           |                        | 25  | ns    |                                    |
|              |             |                  |              | PIC18 <b>LF</b> XXXX |                        | 45  | ns    | VDD = 2.0V                         |

FIGURE 25-12: PARALLEL SLAVE PORT TIMING (PIC18F4410/4510/4515/4610)

**TABLE 25-13: PARALLEL SLAVE PORT REQUIREMENTS (PIC18F4410/4510/4515/4610)** 

| Param.<br>No. | Symbol   | Characteristic   | Characteristic                                 |    |       | Units | Conditions |
|---------------|----------|--|--|----|-------|-------|------------|
| 62            | TdtV2wrH | Data In Valid before WR ↑ or CS  | Data In Valid before WR ↑ or CS ↑ (setup time) |    |       | ns    |            |
| 63            | TwrH2dtl | WR ↑ or CS ↑ to Data-In  | PIC18FXXXX                                     | 20 | _     | ns    |            |
|               |          | Invalid (hold time)  | PIC18 <b>LF</b> XXXX                           | 35 | _     | ns    | VDD = 2.0V |
| 64            | TrdL2dtV | $\overline{RD} \downarrow and \ \overline{CS} \downarrow to \ Data-Out \ Val$  | lid  | _  | 80    | ns    |            |
| 65            | TrdH2dtl | RD ↑ or CS ↓ to Data–Out Inval   | id   | 10 | 30    | ns    |            |
| 66            | TibfINH  | Inhibit of the IBF Flag bit being $\stackrel{\square}{\mathbb{WR}}$ $\uparrow$ or $\stackrel{\square}{\mathbb{CS}}$ $\uparrow$ | Cleared from                                   | _  | 3 Tcy |       |            |




FIGURE 25-13: EXAMPLE SPI™ MASTER MODE TIMING (CKE = 0)

TABLE 25-14: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 0)

| Param<br>No. | Symbol                | Characteristi                              | С                                  | Min           | Max | Units | Conditions |
|--------------|-----------------------|--|------------------------------------|---------------|-----|-------|------------|
| 70           | TssL2scH,<br>TssL2scL | SS ↓ to SCK ↓ or SCK ↑ Input               |                                    | Tcy           | _   | ns    |            |
| 71           | TscH                  | SCK Input High Time                        | Input High Time Continuous         |               | _   | ns    |            |
| 71A          |                       | (Slave mode)                               | Single Byte                        | 40            | _   | ns    | (Note 1)   |
| 72           | TscL                  | SCK Input Low Time                         | Continuous                         | 1.25 Tcy + 30 | _   | ns    |            |
| 72A          |                       | (Slave mode)                               | Single Byte                        | 40            | _   | ns    | (Note 1)   |
| 73           | TdiV2scH,<br>TdiV2scL | Setup Time of SDI Data Input               | to SCK Edge                        | 100           | _   | ns    |            |
| 73A          | Tb2b                  | Last Clock Edge of Byte 1 to the of Byte 2 | e 1st Clock Edge                   | 1.5 Tcy + 40  | _   | ns    | (Note 2)   |
| 74           | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to             | SCK Edge                           | 100           | _   | ns    |            |
| 75           | TdoR                  | SDO Data Output Rise Time                  | PIC18FXXXX                         | _             | 25  | ns    |            |
|              |                       |  | PIC18 <b>LF</b> XXXX               | _             | 45  | ns    | VDD = 2.0V |
| 76           | TdoF                  | SDO Data Output Fall Time                  | •                                  | _             | 25  | ns    |            |
| 78           | TscR                  | SCK Output Rise Time                       | PIC18FXXXX                         | _             | 25  | ns    |            |
|              |                       | (Master mode)                              | de) PIC18 <b>LF</b> XXXX           |               | 45  | ns    | VDD = 2.0V |
| 79           | TscF                  | SCK Output Fall Time (Master mode)         |                                    |               | 25  | ns    |            |
| 80           | TscH2doV,             | SDO Data Output Valid after                | Data Output Valid after PIC18FXXXX |               | 50  | ns    |            |
|              | TscL2doV              | SCK Edge                                   | PIC18 <b>LF</b> XXXX               |               | 100 | ns    | VDD = 2.0V |

Note 1: Requires the use of Parameter #73A.

2: Only if Parameter #71A and #72A are used.




FIGURE 25-14: EXAMPLE SPI™ MASTER MODE TIMING (CKE = 1)

TABLE 25-15: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 1)

| Param.<br>No. | Symbol                | Characterist                             | ic                                 | Min           | Max | Units | Conditions |
|---------------|-----------------------|--|------------------------------------|---------------|-----|-------|------------|
| 71            | TscH                  | SCK Input High Time                      | Continuous                         | 1.25 Tcy + 30 | _   | ns    |            |
| 71A           |                       | (Slave mode)                             | Single Byte                        | 40            | _   | ns    | (Note 1)   |
| 72            | TscL                  | SCK Input Low Time                       | Continuous                         | 1.25 Tcy + 30 | _   | ns    |            |
| 72A           |                       | (Slave mode)                             | Single Byte                        | 40            | _   | ns    | (Note 1)   |
| 73            | TdiV2scH,<br>TdiV2scL | Setup Time of SDI Data Input             | to SCK Edge                        | 100           | _   | ns    |            |
| 73A           | Tb2b                  | Last Clock Edge of Byte 1 to to f Byte 2 | he 1st Clock Edge                  | 1.5 TCY + 40  | _   | ns    | (Note 2)   |
| 74            | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input t            | o SCK Edge                         | 100           | _   | ns    |            |
| 75            | TdoR                  | SDO Data Output Rise Time                | PIC18FXXXX                         | _             | 25  | ns    |            |
|               |                       |  | PIC18 <b>LF</b> XXXX               |               | 45  | ns    | VDD = 2.0V |
| 76            | TdoF                  | SDO Data Output Fall Time                |                                    | _             | 25  | ns    |            |
| 78            | TscR                  | SCK Output Rise Time                     | PIC18FXXXX                         | _             | 25  | ns    |            |
|               |                       | (Master mode)                            | PIC18 <b>LF</b> XXXX               |               | 45  | ns    | VDD = 2.0V |
| 79            | TscF                  | SCK Output Fall Time (Maste              | r mode)                            | _             | 25  | ns    |            |
| 80            | TscH2doV,             | <u>.</u>                                 | Data Output Valid after PIC18FXXXX |               | 50  | ns    |            |
|               | TscL2doV              | SCK Edge                                 | PIC18 <b>LF</b> XXXX               |               | 100 | ns    | VDD = 2.0V |
| 81            | TdoV2scH,<br>TdoV2scL | SDO Data Output Setup to SO              | CK Edge                            | Tcy           | _   | ns    |            |

**Note 1:** Requires the use of Parameter #73A.

2: Only if Parameter #71A and #72A are used.





FIGURE 25-15: **EXAMPLE SPI™ SLAVE MODE TIMING (CKE = 0)** 

TABLE 25-16: EXAMPLE SPI™ MODE REQUIREMENTS (SLAVE MODE TIMING, CKE = 0)

| Param<br>No. | Symbol                | Characteristic                              |                                  | Min           | Max | Units | Conditions |
|--------------|-----------------------|---|----------------------------------|---------------|-----|-------|------------|
| 70           | TssL2scH,<br>TssL2scL | SS ↓ to SCK ↓ or SCK ↑ Input                | SS ↓ to SCK ↓ or SCK ↑ Input     |               |     | ns    |            |
| 71           | TscH                  | SCK Input High Time                         | Continuous                       | 1.25 Tcy + 30 | _   | ns    |            |
| 71A          |                       | (Slave mode)                                | Single Byte                      | 40            | 1   | ns    | (Note 1)   |
| 72           | TscL                  | SCK Input Low Time                          | Continuous                       | 1.25 Tcy + 30 | _   | ns    |            |
| 72A          |                       | (Slave mode)                                | Single Byte                      | 40            | _   | ns    | (Note 1)   |
| 73           | TdiV2scH,<br>TdiV2scL | Setup Time of SDI Data Input to SCK Ed      | dge                              | 100           | _   | ns    |            |
| 73A          | Tb2b                  | Last Clock Edge of Byte 1 to the First Cloc | k Edge of Byte 2                 | 1.5 Tcy + 40  | _   | ns    | (Note 2)   |
| 74           | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to SCK Ed       | је                               | 100           | _   | ns    |            |
| 75           | TdoR                  | SDO Data Output Rise Time                   | PIC18FXXXX                       | _             | 25  | ns    |            |
|              |                       |   | PIC18 <b>LF</b> XXXX             |               | 45  | ns    | VDD = 2.0V |
| 76           | TdoF                  | SDO Data Output Fall Time                   |                                  | _             | 25  | ns    |            |
| 77           | TssH2doZ              | SS↑ to SDO Output High-Impedance            |                                  | 10            | 50  | ns    |            |
| 78           | TscR                  | SCK Output Rise Time (Master mode)          | PIC18FXXXX                       | _             | 25  | ns    |            |
|              |                       |   | PIC18 <b>LF</b> XXXX             |               | 45  | ns    | VDD = 2.0V |
| 79           | TscF                  | SCK Output Fall Time (Master mode)          | K Output Fall Time (Master mode) |               | 25  | ns    |            |
| 80           | TscH2doV,             | SDO Data Output Valid after SCK Edge        | PIC18FXXXX                       | _             | 50  | ns    |            |
|              | TscL2doV              |   | PIC18 <b>LF</b> XXXX             |               | 100 | ns    | VDD = 2.0V |
| 83           | TscH2ssH,<br>TscL2ssH | SS ↑ after SCK edge                         |                                  | 1.5 Tcy + 40  | 1   | ns    |            |

Note 1: Requires the use of Parameter #73A.

Only if Parameter #71A and #72A are used.



**EXAMPLE SPI™ SLAVE MODE TIMING (CKE = 1)** FIGURE 25-16:

TABLE 25-17: EXAMPLE SPI™ SLAVE MODE REQUIREMENTS (CKE = 1)

| Param<br>No. | Symbol                | Characteristic                              |                      | Min           | Max | Units | Conditions |
|--------------|-----------------------|---|----------------------|---------------|-----|-------|------------|
| 70           | TssL2scH,<br>TssL2scL | SS ↓ to SCK ↓ or SCK ↑ Input                |                      | Tcy           | _   | ns    |            |
| 71           | TscH                  | SCK Input High Time                         | Continuous           | 1.25 Tcy + 30 | _   | ns    |            |
| 71A          |                       | (Slave mode)                                | Single Byte          | 40            | _   | ns    | (Note 1)   |
| 72           | TscL                  | SCK Input Low Time                          | Continuous           | 1.25 Tcy + 30 | _   | ns    |            |
| 72A          |                       | (Slave mode)                                | Single Byte          | 40            | _   | ns    | (Note 1)   |
| 73A          | Tb2b                  | Last Clock Edge of Byte 1 to the First      | Clock Edge of Byte 2 | 1.5 Tcy + 40  | _   | ns    | (Note 2)   |
| 74           | TscH2diL,<br>TscL2diL | Hold Time of SDI Data Input to SCK          | Edge                 | 100           | _   | ns    |            |
| 75           | TdoR                  | SDO Data Output Rise Time                   | PIC18FXXXX           | _             | 25  | ns    |            |
|              |                       |   | PIC18 <b>LF</b> XXXX |               | 45  | ns    | VDD = 2.0V |
| 76           | TdoF                  | SDO Data Output Fall Time                   |                      | _             | 25  | ns    |            |
| 77           | TssH2doZ              | SS↑ to SDO Output High-Impedanc             | е                    | 10            | 50  | ns    |            |
| 78           | TscR                  | SCK Output Rise Time                        | PIC18FXXXX           | _             | 25  | ns    |            |
|              |                       | (Master mode)                               | PIC18 <b>LF</b> XXXX | _             | 45  | ns    | VDD = 2.0V |
| 79           | TscF                  | SCK Output Fall Time (Master mode           | e)                   | _             | 25  | ns    |            |
| 80           | TscH2doV,             | SDO Data Output Valid after SCK             | PIC18FXXXX           | _             | 50  | ns    |            |
|              | TscL2doV              | Edge  | PIC18LFXXXX          | _             | 100 | ns    | VDD = 2.0V |
| 82           | TssL2doV              | SDO Data Output Valid after <del>SS</del> ↓ | PIC18FXXXX           | _             | 50  | ns    |            |
|              |                       | Edge  | PIC18 <b>LF</b> XXXX | _             | 100 | ns    | VDD = 2.0V |
| 83           | TscH2ssH,<br>TscL2ssH | SS ↑ after SCK Edge                         |                      | 1.5 Tcy + 40  | _   | ns    |            |

Requires the use of Parameter #73A. Note 1:

2: Only if Parameter #71A and #72A are used.

# **PIC18F2X1X/4X1X**

FIGURE 25-17: I<sup>2</sup>C™ BUS START/STOP BITS TIMING




TABLE 25-18: I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS (SLAVE MODE)

| Param.<br>No. | Symbol  | Characte        | ristic       | Min  | Max | Units | Conditions                   |
|---------------|---------|-----------------|--------------|------|-----|-------|------------------------------|
| 90            | Tsu:sta | Start Condition | 100 kHz mode | 4700 | _   | ns    | Only relevant for Repeated   |
|               |         | Setup Time      | 400 kHz mode | 600  | _   |       | Start condition              |
| 91            | THD:STA | Start Condition | 100 kHz mode | 4000 | _   | ns    | After this period, the first |
|               |         | Hold Time       | 400 kHz mode | 600  | _   |       | clock pulse is generated     |
| 92            | Tsu:sto | Stop Condition  | 100 kHz mode | 4700 | _   | ns    |                              |
|               |         | Setup Time      | 400 kHz mode | 600  | _   |       |                              |
| 93            | THD:STO | Stop Condition  | 100 kHz mode | 4000 | _   | ns    |                              |
|               |         | Hold Time       | 400 kHz mode | 600  | _   |       |                              |

FIGURE 25-18: I<sup>2</sup>C™ BUS DATA TIMING




TABLE 25-19: I<sup>2</sup>C™ BUS DATA REQUIREMENTS (SLAVE MODE)

| Param.<br>No. | Symbol  | Characte            | eristic      | Min         | Max  | Units | Conditions                              |
|---------------|---------|---------------------|--------------|-------------|------|-------|---|
| 100           | THIGH   | Clock High Time     | 100 kHz mode | 4.0         | _    | μs    |   |
|               |         |                     | 400 kHz mode | 0.6         | _    | μs    |   |
|               |         |                     | SSP Module   | 1.5 TcY     | _    |       |   |
| 101           | TLOW    | Clock Low Time      | 100 kHz mode | 4.7         | _    | μs    |   |
|               |         |                     | 400 kHz mode | 1.3         | _    | μs    |   |
|               |         |                     | SSP Module   | 1.5 TcY     | _    |       |   |
| 102           | Tr      | SDA and SCL Rise    | 100 kHz mode | _           | 1000 | ns    |   |
|               |         | Time                | 400 kHz mode | 20 + 0.1 CB | 300  | ns    | CB is specified to be from 10 to 400 pF |
| 103           | TF      | SDA and SCL Fall    | 100 kHz mode | _           | 300  | ns    |   |
|               |         | Time                | 400 kHz mode | 20 + 0.1 CB | 300  | ns    | CB is specified to be from 10 to 400 pF |
| 90            | Tsu:sta | Start Condition     | 100 kHz mode | 4.7         | _    | μs    | Only relevant for Repeated              |
|               |         | Setup Time          | 400 kHz mode | 0.6         | _    | μs    | Start condition                         |
| 91            | THD:STA | Start Condition     | 100 kHz mode | 4.0         | _    | μs    | After this period, the first            |
|               |         | Hold Time           | 400 kHz mode | 0.6         | _    | μs    | clock pulse is generated                |
| 106           | THD:DAT | Data Input Hold     | 100 kHz mode | 0           | _    | ns    |   |
|               |         | Time                | 400 kHz mode | 0           | 0.9  | μs    |   |
| 107           | TSU:DAT |                     | 100 kHz mode | 250         | _    | ns    | (Note 2)                                |
|               |         | Time                | 400 kHz mode | 100         | _    | ns    |   |
| 92            | Tsu:sto |                     | 100 kHz mode | 4.7         | _    | μs    |   |
|               |         | Setup Time          | 400 kHz mode | 0.6         | _    | μs    |   |
| 109           | TAA     | Output Valid from   | 100 kHz mode | _           | 3500 | ns    | (Note 1)                                |
|               |         | Clock               | 400 kHz mode | _           | _    | ns    |   |
| 110           | TBUF    | Bus Free Time       | 100 kHz mode | 4.7         | _    | μs    | Time the bus must be free               |
|               |         |                     | 400 kHz mode | 1.3         | _    | μs    | before a new transmission can start     |
| D102          | Св      | Bus Capacitive Load | ding         |             | 400  | pF    |   |

**Note 1:** As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.

2: A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system, but the requirement TSU:DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCL signal. If such a device does stretch the LOW period of the SCL signal, it must output the next data bit to the SDA line, TR max. + TSU:DAT = 1000 + 250 = 1250 ns (according to the standard mode I<sup>2</sup>C bus specification), before the SCL line is released.

FIGURE 25-19: MASTER SSP I<sup>2</sup>C™ BUS START/STOP BITS TIMING WAVEFORMS




TABLE 25-20: MASTER SSP I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS

| Param.<br>No. | Symbol  | Characte        | ristic Min                |                  | Max | Units | Conditions             |
|---------------|---------|-----------------|---------------------------|------------------|-----|-------|------------------------|
| 90            | Tsu:sta | Start Condition | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    | Only relevant for      |
|               |         | Setup Time      | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       | Repeated Start         |
|               |         |                 | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       | condition              |
| 91            | THD:STA | Start Condition | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    | After this period, the |
|               |         | Hold Time       | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       | first clock pulse is   |
|               |         |                 | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       | generated              |
| 92            | Tsu:sto | Stop Condition  | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    |                        |
|               |         | Setup Time      | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       |                        |
|               |         |                 | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       |                        |
| 93            | THD:STO | Stop Condition  | 100 kHz mode              | 2(Tosc)(BRG + 1) | _   | ns    |                        |
|               |         | Hold Time       | 400 kHz mode              | 2(Tosc)(BRG + 1) | _   |       |                        |
|               |         |                 | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _   |       |                        |

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2$ C pins.

FIGURE 25-20: MASTER SSP I<sup>2</sup>C™ BUS DATA TIMING





TABLE 25-21: MASTER SSP I<sup>2</sup>C™ BUS DATA REQUIREMENTS

| Param.<br>No. | Symbol  | Characteristic                |                           | Min              | Max  | Units | Conditions                          |
|---------------|---------|-------------------------------|---------------------------|------------------|------|-------|-------------------------------------|
| 100           | THIGH   | Clock High Time               | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
|               |         |                               | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
| 101           | TLOW    | Clock Low Time                | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
|               |         |                               | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
| 102           | TR      | SDA and SCL                   | 100 kHz mode              | _                | 1000 | ns    | CB is specified to be from          |
|               |         | Rise Time                     | 400 kHz mode              | 20 + 0.1 CB      | 300  | ns    | 10 to 400 pF                        |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | _                | 300  | ns    |                                     |
| 103           | TF      | SDA and SCL                   | 100 kHz mode              | _                | 300  | ns    | CB is specified to be from          |
|               |         | Fall Time                     | 400 kHz mode              | 20 + 0.1 CB      | 300  | ns    | 10 to 400 pF                        |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | _                | 100  | ns    |                                     |
| 90            | Tsu:sta | Start Condition<br>Setup Time | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | Only relevant for                   |
|               |         |                               | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | Repeated Start                      |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    | condition                           |
| 91            | THD:STA | Start Condition<br>Hold Time  | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | After this period, the first        |
|               |         |                               | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    | clock pulse is generated            |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
| 106           | THD:DAT | Data Input                    | 100 kHz mode              | 0                | _    | ns    |                                     |
|               |         | Hold Time                     | 400 kHz mode              | 0                | 0.9  | ms    |                                     |
| 107           | Tsu:dat | Data Input                    | 100 kHz mode              | 250              | _    | ns    | (Note 2)                            |
|               |         | Setup Time                    | 400 kHz mode              | 100              | _    | ns    |                                     |
| 92            | Tsu:sto | Stop Condition                | 100 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
|               |         | Setup Time                    | 400 kHz mode              | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | 2(Tosc)(BRG + 1) | _    | ms    |                                     |
| 109           | TAA     | Output Valid                  | 100 kHz mode              | _                | 3500 | ns    |                                     |
|               |         | from Clock                    | 400 kHz mode              | _                | 1000 | ns    |                                     |
|               |         |                               | 1 MHz mode <sup>(1)</sup> | _                | _    | ns    |                                     |
| 110           | TBUF    | Bus Free Time                 | 100 kHz mode              | 4.7              | _    | ms    | Time the bus must be free           |
|               |         |                               | 400 kHz mode              | 1.3              | _    | ms    | before a new transmission can start |
| D102          | Св      | Bus Capacitive Lo             | oading                    | _                | 400  | pF    |                                     |

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2\text{C}$  pins.

2: A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system, but parameter 107 ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCL signal. If such a device does stretch the LOW period of the SCL signal, it must output the next data bit to the SDA line, parameter 102 + parameter 107 = 1000 + 250 = 1250 ns (for 100 kHz mode), before the SCL line is released.


#### FIGURE 25-21: USART SYNCHRONOUS TRANSMISSION (MASTER/SLAVE) TIMING



#### TABLE 25-22: USART SYNCHRONOUS TRANSMISSION REQUIREMENTS

| Param<br>No. | Symbol   | Characteristic                    | Min                  | Max | Units | Conditions |            |
|--------------|----------|-----------------------------------|----------------------|-----|-------|------------|------------|
| 120          | TckH2dtV | SYNC XMIT (MASTER & SLAVE)        |                      |     |       |            |            |
|              |          | Clock High to Data Out Valid      | PIC18FXXXX           | _   | 40    | ns         |            |
|              |          |                                   | PIC18 <b>LF</b> XXXX | _   | 100   | ns         | VDD = 2.0V |
| 121          | Tckrf    | Clock Out Rise Time and Fall Time | PIC18FXXXX           | _   | 20    | ns         |            |
|              |          | (Master mode)                     | PIC18 <b>LF</b> XXXX | _   | 50    | ns         | VDD = 2.0V |
| 122          | Tdtrf    | Data Out Rise Time and Fall Time  | PIC18FXXXX           | _   | 20    | ns         |            |
|              |          |                                   | PIC18 <b>LF</b> XXXX | _   | 50    | ns         | VDD = 2.0V |

#### FIGURE 25-22: USART SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING



#### TABLE 25-23: USART SYNCHRONOUS RECEIVE REQUIREMENTS

| Param.<br>No. | Symbol   | Characteristic   | Min | Max | Units | Conditions |
|---------------|----------|--|-----|-----|-------|------------|
| 125           | TdtV2ckl | SYNC RCV (MASTER & SLAVE) Data Hold before CK ↓ (DT hold time) | 10  |     | ns    |            |
| 126           | TckL2dtl | Data Hold after CK ↓ (DT hold time)                            | 15  |     | ns    |            |

TABLE 25-24: A/D CONVERTER CHARACTERISTICS: PIC18F2X1X/4X1X (INDUSTRIAL)
PIC18LF2X1X/4X1X (INDUSTRIAL)


| Param<br>No. | Symbol        | Characteristic                                    | Min        | Тур                       | Max        | Units    | Conditions  |
|--------------|---------------|---|------------|---------------------------|------------|----------|---|
| A01          | NR            | Resolution  | _          |                           | 10         | bit      | ΔVREF ≥ 3.0V  |
| A03          | EIL           | Integral Linearity Error                          | _          | _                         | <±1        | LSb      | $\Delta VREF \ge 3.0V$                                      |
| A04          | EDL           | Differential Linearity Error                      | _          | _                         | <±1        | LSb      | ΔVREF ≥ 3.0V  |
| A06          | Eoff          | Offset Error                                      | _          | _                         | <±1        | LSb      | $\Delta VREF \ge 3.0V$                                      |
| A07          | Egn           | Gain Error  | _          | _                         | <±1        | LSb      | $\Delta VREF \ge 3.0V$                                      |
| A10          | _             | Monotonicity                                      | Gı         | Guaranteed <sup>(1)</sup> |            |          | VSS ≤ VAIN ≤ VREF   |
| A20          | $\Delta VREF$ | Reference Voltage Range<br>(VREFH – VREFL)        | 1.8<br>3   | _                         |            | V        | VDD < 3.0V<br>VDD ≥ 3.0V                                    |
| A21          | VREFH         | Reference Voltage High                            | Vss        |                           | VREFH      | V        |   |
| A22          | VREFL         | Reference Voltage Low                             | Vss - 0.3V |                           | VDD - 3.0V | V        |   |
| A25          | VAIN          | Analog Input Voltage                              | VREFL      | _                         | VREFH      | V        |   |
| A30          | ZAIN          | Recommended Impedance of<br>Analog Voltage Source | _          |                           | 2.5        | kΩ       |   |
| A50          | IREF          | VREF Input Current <sup>(2)</sup>                 |            | _<br>_                    | 5<br>150   | μA<br>μA | During VAIN acquisition.<br>During A/D conversion<br>cycle. |

Note 1: The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.

<sup>2:</sup> VREFH current is from RA3/AN3/VREF+ pin or VDD, whichever is selected as the VREFH source. VREFL current is from RA2/AN2/VREF-/CVREF pin or VSS, whichever is selected as the VREFL source.

## **PIC18F2X1X/4X1X**

#### FIGURE 25-23: A/D CONVERSION TIMING



#### **TABLE 25-25: A/D CONVERSION REQUIREMENTS**

| Param<br>No. | Symbol | Characteristic                             |                         | Min        | Max                 | Units    | Conditions                                 |
|--------------|--------|--|-------------------------|------------|---------------------|----------|--|
| 130          | TAD    | A/D Clock Period                           | Clock Period PIC18FXXXX |            | 25.0 <sup>(1)</sup> | μs       | Tosc based, VREF ≥ 3.0V                    |
|              |        |  | PIC18 <b>LF</b> XXXX    | 1.4        | 25.0 <sup>(1)</sup> | μs       | VDD = 2.0V;<br>Tosc based, VREF full range |
|              |        |  | PIC18FXXXX              | TBD        | 1                   | μs       | A/D RC mode                                |
|              |        |  | PIC18 <b>LF</b> XXXX    | TBD        | 3                   | μs       | VDD = 2.0V; A/D RC mode                    |
| 131          | TCNV   | Conversion Time (not including acquisition | on time) (Note 2)       | 11         | 12                  | TAD      |  |
| 132          | TACQ   | Acquisition Time (Note 3)                  |                         | 1.4<br>TBD | _                   | μs<br>μs | -40°C to +85°C<br>0°C ≤ to ≤ +85°C         |
| 135          | Tswc   | Switching Time from Convert → Sample       |                         |            | (Note 4)            |          |  |
| TBD          | TDIS   | Discharge Time                             | _                       | 0.2        | _                   | μs       |  |

**Legend:** TBD = To Be Determined

Note 1: The time of the A/D clock period is dependent on the device frequency and the TAD clock divider.

- 2: ADRES register may be read on the following TcY cycle.
- 3: The time for the holding capacitor to acquire the "New" input voltage when the voltage changes full scale after the conversion (VDD to Vss or Vss to VDD). The source impedance (Rs) on the input channels is  $50\Omega$ .
- 4: On the following cycle of the device clock.

# 26.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES

Graphs and tables are not available at this time.

# **PIC18F2X1X/4X1X**

NOTES:


#### 27.0 PACKAGING INFORMATION

### 27.1 Package Marking Information

#### 28-Lead SPDIP




### Example



#### 28-Lead SOIC



#### Example



#### 28-Lead QFN



#### Example



Legend: XX...X Customer specific information\*
Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')


NNN Alphanumeric traceability code

**Note**: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line thus limiting the number of available characters for customer specific information.

Standard PICmicro device marking consists of Microchip part number, year code, week code and traceability code. For PICmicro device marking beyond this, certain price adders apply. Please check with your Microchip Sales Office. For QTP devices, any special marking adders are included in QTP price.

### 27.1 Package Marking Information (Continued)

40-Lead PDIP



Example




44-Lead QFN



Example



44-Lead TQFP




Example



#### **Package Details** 27.2

The following sections give the technical details of the packages.

### 28-Lead Skinny Plastic Dual In-line (SP) – 300 mil Body (PDIP)



|                            | Units |       |       |       | MILLIMETERS |       |       |
|----------------------------|-------|-------|-------|-------|-------------|-------|-------|
| Dimension                  | MIN   | NOM   | MAX   | MIN   | NOM         | MAX   |       |
| Number of Pins             | n     |       | 28    |       |             | 28    |       |
| Pitch                      | р     |       | .100  |       |             | 2.54  |       |
| Top to Seating Plane       | Α     | .140  | .150  | .160  | 3.56        | 3.81  | 4.06  |
| Molded Package Thickness   | A2    | .125  | .130  | .135  | 3.18        | 3.30  | 3.43  |
| Base to Seating Plane      | A1    | .015  |       |       | 0.38        |       |       |
| Shoulder to Shoulder Width | Е     | .300  | .310  | .325  | 7.62        | 7.87  | 8.26  |
| Molded Package Width       | E1    | .275  | .285  | .295  | 6.99        | 7.24  | 7.49  |
| Overall Length             | D     | 1.345 | 1.365 | 1.385 | 34.16       | 34.67 | 35.18 |
| Tip to Seating Plane       | L     | .125  | .130  | .135  | 3.18        | 3.30  | 3.43  |
| Lead Thickness             | С     | .008  | .012  | .015  | 0.20        | 0.29  | 0.38  |
| Upper Lead Width           | B1    | .040  | .053  | .065  | 1.02        | 1.33  | 1.65  |
| Lower Lead Width           | В     | .016  | .019  | .022  | 0.41        | 0.48  | 0.56  |
| Overall Row Spacing §      | eВ    | .320  | .350  | .430  | 8.13        | 8.89  | 10.92 |
| Mold Draft Angle Top       | α     | 5     | 10    | 15    | 5           | 10    | 15    |
| Mold Draft Angle Bottom    | β     | 5     | 10    | 15    | 5           | 10    | 15    |


Notes:

Dimension D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side.
JEDEC Equivalent: MO-095
Drawing No. C04-070

<sup>\*</sup> Controlling Parameter § Significant Characteristic

### 28-Lead Plastic Small Outline (SO) - Wide, 300 mil Body (SOIC)




|                          |     | INCHES* |      | MILLIMETERS |       |       |       |
|--------------------------|-----|---------|------|-------------|-------|-------|-------|
| Dimensio                 | MIN | NOM     | MAX  | MIN         | NOM   | MAX   |       |
| Number of Pins           | n   |         | 28   |             |       | 28    |       |
| Pitch                    | р   |         | .050 |             |       | 1.27  |       |
| Overall Height           | Α   | .093    | .099 | .104        | 2.36  | 2.50  | 2.64  |
| Molded Package Thickness | A2  | .088    | .091 | .094        | 2.24  | 2.31  | 2.39  |
| Standoff §               | A1  | .004    | .008 | .012        | 0.10  | 0.20  | 0.30  |
| Overall Width            | Е   | .394    | .407 | .420        | 10.01 | 10.34 | 10.67 |
| Molded Package Width     | E1  | .288    | .295 | .299        | 7.32  | 7.49  | 7.59  |
| Overall Length           | D   | .695    | .704 | .712        | 17.65 | 17.87 | 18.08 |
| Chamfer Distance         | h   | .010    | .020 | .029        | 0.25  | 0.50  | 0.74  |
| Foot Length              | L   | .016    | .033 | .050        | 0.41  | 0.84  | 1.27  |
| Foot Angle Top           | φ   | 0       | 4    | 8           | 0     | 4     | 8     |
| Lead Thickness           | С   | .009    | .011 | .013        | 0.23  | 0.28  | 0.33  |
| Lead Width               | В   | .014    | .017 | .020        | 0.36  | 0.42  | 0.51  |
| Mold Draft Angle Top     | α   | 0       | 12   | 15          | 0     | 12    | 15    |
| Mold Draft Angle Bottom  | β   | 0       | 12   | 15          | 0     | 12    | 15    |

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MS-013 Drawing No. C04-052

<sup>\*</sup> Controlling Parameter § Significant Characteristic

# 28-Lead Plastic Quad Flat No Lead Package (ML) 6x6 mm Body (QFN) – With 0.55 mm Contact Length (Saw Singulated)



|                    | Units | nits INCHES |          |      | MILLIMETERS* |          |      |  |  |
|--------------------|-------|-------------|----------|------|--------------|----------|------|--|--|
| Dimension Limi     | ts    | MIN         | NOM      | MAX  | MIN          | NOM      | MAX  |  |  |
| Number of Pins     | n     |             | 28       |      |              | 28       |      |  |  |
| Pitch              | е     |             | .026 BSC |      |              | 0.65 BSC |      |  |  |
| Overall Height     | Α     | .031        | .035     | .039 | 0.80         | 0.90     | 1.00 |  |  |
| Standoff           | A1    | .000        | .001     | .002 | 0.00         | 0.02     | 0.05 |  |  |
| Contact Thickness  | А3    |             | .008 REF |      |              | 0.20 REF |      |  |  |
| Overall Width      | Е     | .232        | .236     | .240 | 5.90         | 6.00     | 6.10 |  |  |
| Exposed Pad Width  | E2    | .140        | .146     | .152 | 3.55         | 3.70     | 3.85 |  |  |
| Overall Length     | D     | .232        | .236     | .240 | 5.90         | 6.00     | 6.10 |  |  |
| Exposed Pad Length | D2    | .140        | .146     | .152 | 3.55         | 3.70     | 3.85 |  |  |
| Contact Width      | b     | .009        | .011     | .013 | 0.23         | 0.28     | 0.33 |  |  |
| Contact Length     | L     | .020        | .024     | .028 | 0.50         | 0.60     | 0.70 |  |  |

\*Controlling Parameter


Notes:

JEDEC equivalent: MO-220

Drawing No. C04-105

Revised 05-24-04

### 40-Lead Plastic Dual In-line (P) – 600 mil Body (PDIP)



|                            |     | INCHES* |       | MILLIMETERS |       |       |       |
|----------------------------|-----|---------|-------|-------------|-------|-------|-------|
| Dimension                  | MIN | NOM     | MAX   | MIN         | NOM   | MAX   |       |
| Number of Pins             | n   |         | 40    |             |       | 40    |       |
| Pitch                      | р   |         | .100  |             |       | 2.54  |       |
| Top to Seating Plane       | Α   | .160    | .175  | .190        | 4.06  | 4.45  | 4.83  |
| Molded Package Thickness   | A2  | .140    | .150  | .160        | 3.56  | 3.81  | 4.06  |
| Base to Seating Plane      | A1  | .015    |       |             | 0.38  |       |       |
| Shoulder to Shoulder Width | Е   | .595    | .600  | .625        | 15.11 | 15.24 | 15.88 |
| Molded Package Width       | E1  | .530    | .545  | .560        | 13.46 | 13.84 | 14.22 |
| Overall Length             | D   | 2.045   | 2.058 | 2.065       | 51.94 | 52.26 | 52.45 |
| Tip to Seating Plane       | L   | .120    | .130  | .135        | 3.05  | 3.30  | 3.43  |
| Lead Thickness             | С   | .008    | .012  | .015        | 0.20  | 0.29  | 0.38  |
| Upper Lead Width           | B1  | .030    | .050  | .070        | 0.76  | 1.27  | 1.78  |
| Lower Lead Width           | В   | .014    | .018  | .022        | 0.36  | 0.46  | 0.56  |
| Overall Row Spacing §      | eВ  | .620    | .650  | .680        | 15.75 | 16.51 | 17.27 |
| Mold Draft Angle Top       | α   | 5       | 10    | 15          | 5     | 10    | 15    |
| Mold Draft Angle Bottom    | β   | 5       | 10    | 15          | 5     | 10    | 15    |


Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MO-011 Drawing No. C04-016

<sup>\*</sup> Controlling Parameter § Significant Characteristic

#### 44-Lead Plastic Quad Flat No Lead Package (ML) 8x8 mm Body (QFN)



|                    | Units | INCHES     |          |            |      | MILLIMETERS* |      |
|--------------------|-------|------------|----------|------------|------|--------------|------|
| Dimension Limi     | ts    | MIN        | NOM      | MAX        | MIN  | NOM          | MAX  |
| Number of Contacts | n     |            | 44       | •          | 44   |              |      |
| Pitch              | р     |            | .026 BSC | 1          |      | 0.65 BSC     | ı    |
| Overall Height     | Α     | .031       | .035     | .039       | 0.80 | 0.90         | 1.00 |
| Standoff           | A1    | .000       | .001     | .002       | 0    | 0.02         | 0.05 |
| Base Thickness     | (A3)  | .010 REF 2 |          | 0.25 REF 2 |      |              |      |
| Overall Width      | E     | .309       | .315     | .321       | 7.85 | 8.00         | 8.15 |
| Exposed Pad Width  | E2    | .246       | .268     | .274       | 6.25 | 6.80         | 6.95 |
| Overall Length     | D     | .309       | .315     | .321       | 7.85 | 8.00         | 8.15 |
| Exposed Pad Length | D2    | .246       | .268     | .274       | 6.25 | 6.80         | 6.95 |
| Contact Width      | В     | .008       | .013     | .013       | 0.20 | 0.33         | 0.35 |
| Contact Length     | L     | .014       | .016     | .019       | 0.35 | 0.40         | 0.48 |


<sup>\*</sup>Controlling Parameter

#### Notes:

- 1. BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- See ASME Y14.5M
- 2. REF: Reference Dimension, usually without tolerance, for information purposes only. See ASME Y14.5M
- 3. Contact profiles may vary.

JEDEC equivalent: M0-220 Drawing No. C04-103

#### 44-Lead Plastic Thin Quad Flatpack (PT) 10x10x1 mm Body, 1.0/0.10 mm Lead Form (TQFP)



|                          | Units    |      | INCHES |      | MILLIMETERS* |       |       |
|--------------------------|----------|------|--------|------|--------------|-------|-------|
| Dimension                | n Limits | MIN  | NOM    | MAX  | MIN          | NOM   | MAX   |
| Number of Pins           | n        |      | 44     |      |              | 44    |       |
| Pitch                    | р        |      | .031   |      |              | 0.80  |       |
| Pins per Side            | n1       |      | 11     |      |              | 11    |       |
| Overall Height           | Α        | .039 | .043   | .047 | 1.00         | 1.10  | 1.20  |
| Molded Package Thickness | A2       | .037 | .039   | .041 | 0.95         | 1.00  | 1.05  |
| Standoff §               | A1       | .002 | .004   | .006 | 0.05         | 0.10  | 0.15  |
| Foot Length              | L        | .018 | .024   | .030 | 0.45         | 0.60  | 0.75  |
| Footprint (Reference)    | (F)      |      | .039   |      | 1.00         |       |       |
| Foot Angle               | ф        | 0    | 3.5    | 7    | 0            | 3.5   | 7     |
| Overall Width            | Е        | .463 | .472   | .482 | 11.75        | 12.00 | 12.25 |
| Overall Length           | D        | .463 | .472   | .482 | 11.75        | 12.00 | 12.25 |
| Molded Package Width     | E1       | .390 | .394   | .398 | 9.90         | 10.00 | 10.10 |
| Molded Package Length    | D1       | .390 | .394   | .398 | 9.90         | 10.00 | 10.10 |
| Lead Thickness           | С        | .004 | .006   | .008 | 0.09         | 0.15  | 0.20  |
| Lead Width               | В        | .012 | .015   | .017 | 0.30         | 0.38  | 0.44  |
| Pin 1 Corner Chamfer     | CH       | .025 | .035   | .045 | 0.64         | 0.89  | 1.14  |
| Mold Draft Angle Top     | α        | 5    | 10     | 15   | 5            | 10    | 15    |
| Mold Draft Angle Bottom  | β        | 5    | 10     | 15   | 5            | 10    | 15    |

Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MS-026 Drawing No. C04-076

<sup>\*</sup> Controlling Parameter § Significant Characteristic

#### APPENDIX A: REVISION HISTORY

Revision A (June 2004)

Original data sheet for PIC18F2X1X/4X1X devices.

**APPENDIX B: DEVICE** 

**DIFFERENCES** 

The differences between the devices listed in this data sheet are shown in Table B-1 and Table B-2.

**TABLE B-1: DEVICE DIFFERENCES (PIC18F2410/2510/2515/2610)** 

| Features                                | PIC18F2410                                | PIC18F2510                                | PIC18F2515                  | PIC18F2610                  |
|---|---|---|-----------------------------|-----------------------------|
| Program Memory (Bytes)                  | 16384                                     | 32768                                     | 49152                       | 65536                       |
| Program Memory (Instructions)           | 8192                                      | 16384                                     | 24576                       | 32768                       |
| Interrupt Sources                       | 18  | 18  | 18                          | 18                          |
| I/O Ports                               | Ports A, B, C, (E)                        | Ports A, B, C, (E)                        | Ports A, B, C, (E)          | Ports A, B, C, (E)          |
| Capture/Compare/PWM Modules             | 2   | 2   | 2                           | 2                           |
| Enhanced<br>Capture/Compare/PWM Modules | 0   | 0   | 0                           | 0                           |
| Parallel<br>Communications (PSP)        | No  | No  | No                          | No                          |
| 10-bit Analog-to-Digital Module         | 10 input channels                         | 10 input channels                         | 10 input channels           | 10 input channels           |
| Packages                                | 28-pin SPDIP<br>28-pin SOIC<br>28-pin QFN | 28-pin SPDIP<br>28-pin SOIC<br>28-pin QFN | 28-pin SPDIP<br>28-pin SOIC | 28-pin SPDIP<br>28-pin SOIC |

TABLE B-2: DEVICE DIFFERENCES (PIC18F4410/4510/4515/4610)

| Features                                | PIC18F4410                               | PIC18F4510                               | PIC18F4515                               | PIC18F4610                               |
|---|--|--|--|--|
| Program Memory (Bytes)                  | 16384                                    | 32768                                    | 49152                                    | 65536                                    |
| Program Memory (Instructions)           | 8192                                     | 16384                                    | 24576                                    | 32768                                    |
| Interrupt Sources                       | 19                                       | 19                                       | 19                                       | 19                                       |
| I/O Ports                               | Ports A, B, C, D, E                      |
| Capture/Compare/PWM Modules             | 2  | 2  | 2  | 2  |
| Enhanced<br>Capture/Compare/PWM Modules | 0  | 0  | 0  | 0  |
| Parallel<br>Communications (PSP)        | Yes                                      | Yes                                      | Yes                                      | Yes                                      |
| 10-bit Analog-to-Digital Module         | 13 input channels                        | 13 input channels                        | 13 input channels                        | 13 input channels                        |
| Packages                                | 40-pin PDIP<br>44-pin QFN<br>44-pin TQFP |

# APPENDIX C: CONVERSION CONSIDERATIONS

This appendix discusses the considerations for converting from previous versions of a device to the ones listed in this data sheet. Typically, these changes are due to the differences in the process technology used. An example of this type of conversion is from a PIC16C74A to a PIC16C74B.

**Not Applicable** 

# APPENDIX D: MIGRATION FROM BASELINE TO ENHANCED DEVICES

This section discusses how to migrate from a Baseline device (i.e., PIC16C5X) to an Enhanced MCU device (i.e., PIC18FXXX).

The following are the list of modifications over the PIC16C5X microcontroller family:

**Not Currently Available** 

# APPENDIX E: MIGRATION FROM MID-RANGE TO ENHANCED DEVICES

A detailed discussion of the differences between the mid-range MCU devices (i.e., PIC16CXXX) and the enhanced devices (i.e., PIC18FXXX) is provided in AN716, "Migrating Designs from PIC16C74A/74B to PIC18C442." The changes discussed, while device specific, are generally applicable to all mid-range to enhanced device migrations.

This Application Note is available as Literature Number DS00716.

# APPENDIX F: MIGRATION FROM HIGH-END TO ENHANCED DEVICES

A detailed discussion of the migration pathway and differences between the high-end MCU devices (i.e., PIC17CXXX) and the enhanced devices (i.e., PIC18FXXX) is provided in *AN726*, "*PIC17CXXX to PIC18CXXX Migration*." This Application Note is available as Literature Number DS00726.

NOTES:

#### **INDEX**

| A                                      |          | Block Diagrams                              |     |
|--|----------|---|-----|
| A/D                                    | 211      | A/D   |     |
| A/D Converter Interrupt, Configuring   | 215      | Analog Input Model                          |     |
| Acquisition Requirements               |          | Baud Rate Generator                         |     |
| ADCON0 Register                        |          | Capture Mode Operation                      |     |
| ADCON1 Register                        |          | Comparator Analog Input Model               |     |
| ADCON2 Register                        |          | Comparator I/O Operating Modes (Diagram)    |     |
| ADRESH Register                        |          | Comparator Output                           |     |
| ADRESL Register                        |          | Comparator Voltage Reference                | 228 |
| Analog Port Pins, Configuring          |          | Comparator Voltage Reference                |     |
| Associated Registers                   |          | Output Buffer Example                       | 229 |
| Calculating the Minimum Required       |          | Compare Mode Operation                      |     |
| Acquisition Time                       | 216      | Device Clock                                | 28  |
| Configuring the Module                 |          | Enhanced PWM                                | 139 |
| Conversion Clock (TAD)                 |          | EUSART Receive                              | 202 |
| Conversion Status (GO/DONE Bit)        |          | EUSART Transmit                             | 200 |
| Conversions                            |          | External Power-on Reset Circuit             |     |
| Converter Characteristics              |          | (Slow VDD Power-up)                         | 43  |
| Operation in Power Managed Modes       |          | Fail-Safe Clock Monitor                     | 249 |
| Selecting and Configuring              | 210      | Generic I/O Port                            | 95  |
| Acquisition Time                       | 217      | High/Low-Voltage Detect with External Input | 232 |
| •                                      |          | Interrupt Logic                             | 82  |
| Special Event Trigger (CCP)            |          | MSSP (I <sup>2</sup> C Master Mode)         |     |
| Special Event Trigger (ECCP)           |          | MSSP (I <sup>2</sup> C Mode)                |     |
| Use of the CCP2 Trigger                |          | MSSP (SPI Mode)                             |     |
| Absolute Maximum Ratings               |          | On-Chip Reset Circuit                       |     |
| AC (Timing) Characteristics            | 331      | PIC18F2410/2510/2515/2610                   |     |
| Load Conditions for Device             | 000      | PIC18F4410/4510/4515/4610                   |     |
| Timing Specifications                  |          | PLL (HS Mode)                               | 25  |
| Parameter Symbology                    |          | PORTD and PORTE                             |     |
| Temperature and Voltage Specifications |          | (Parallel Slave Port)                       | 110 |
| Timing Conditions                      | 332      | PWM Operation (Simplified)                  |     |
| AC Characteristics                     | 004      | Reads from Flash Program Memory             |     |
| Internal RC Accuracy                   | 334      | Single Comparator                           |     |
| Access Bank                            |          | Table Read Operation                        |     |
| Mapping with Indexed Literal Offset    | 70       | Timer0 in 16-Bit Mode                       |     |
| Addressing Mode                        |          | Timer0 in 8-Bit Mode                        |     |
| ACKSTAT                                |          | Timer1                                      |     |
| ACKSTAT Status Flag                    |          | Timer1 (16-Bit Read/Write Mode)             |     |
| ADCON0 Register                        |          | Timer2                                      |     |
| GO/DONE Bit                            |          | Timer3                                      |     |
| ADCON1 Register                        |          | Timer3 (16-Bit Read/Write Mode)             |     |
| ADCON2 Register                        |          | Watchdog Timer                              |     |
| ADDFSR                                 |          | BN  |     |
| ADDLW                                  |          | BNC   |     |
| ADDULNK                                |          | BNN   |     |
| ADDWF                                  |          | BNOV  |     |
| ADDWFC                                 |          | BNZ   |     |
| ADRESH Register                        |          | BOR. See Brown-out Reset.                   | 200 |
| ADRESL Register                        | 211, 214 | BOV   | 271 |
| Analog-to-Digital Converter. See A/D.  |          | BRA   |     |
| ANDLW                                  | -        | Break Character (12-Bit) Transmit           | 208 |
| ANDWF                                  | 265      | and Receive                                 | 205 |
| Assembler                              |          | BRG. See Baud Rate Generator.               | 200 |
| MPASM Assembler                        |          |   | 4.  |
| Auto-Wake-up on Sync Break Character   | 204      | Brown-out Reset (BOR)                       |     |
|  |          | Detecting                                   |     |
| В                                      |          | Disabling in Sleep Mode                     |     |
| Bank Select Register (BSR)             |          | Software Enabled                            |     |
| Baud Rate Generator                    | 177      | BSF   |     |
| BC                                     | 265      | BTFSC                                       |     |
| BCF                                    | 266      | BTFSS                                       |     |
| BF                                     |          | BTG   |     |
| BF Status Flag                         | 181      | BZ  | 2/2 |

| С  |     | Comparator Voltage Reference  |     |
|--|-----|---|-----|
| C Compilers  |     | Accuracy and Error  |     |
| MPLAB C17  | 308 | Associated Registers  |     |
| MPLAB C18  |     | Configuring   |     |
| MPLAB C30  |     | Connection Considerations   |     |
| CALL   |     | Effects of a Reset  |     |
| CALLW  |     | Operation During Sleep  |     |
| Capture (CCP Module)                               |     | Compare (CCP Module)  |     |
| Associated Registers                               |     | Associated Registers  |     |
| CCP Pin Configuration                              |     | CCPRx Register  |     |
| CCPRxH:CCPRxL Registers                            |     | Pin Configuration   |     |
| Prescaler  | 131 | Software Interrupt  |     |
| Software Interrupt                                 | 131 | Special Event Trigger   |     |
| Timer1/Timer3 Mode Selection                       |     | Timer1/Timer3 Mode Selection  |     |
| Capture (ECCP Module)                              | 138 | Compare (ECCP Module)   |     |
| Capture/Compare/PWM (CCP)                          |     | Special Event Trigger   |     |
| Capture Mode. See Capture.                         |     | Computed GOTO   |     |
| CCP Mode and Timer Resources                       | 130 | Configuration Bits  |     |
| CCPRxH Register                                    | 130 | Configuration Register Protection                                       |     |
| CCPRxL Register                                    | 130 | Context Saving During Interrupts  |     |
| Compare Mode. See Compare.                         |     | Conversion Considerations   |     |
| Interaction of Two CCP Modules                     | 130 | CPFSEQ  |     |
| Module Configuration                               | 130 | CPFSGT  |     |
| Clock Sources                                      | 28  | CPFSLT  |     |
| Selecting the 31 kHz Source                        | 29  | Crystal Oscillator/Ceramic Resonator                                    | 23  |
| Selection Using OSCCON Register                    | 29  | D   |     |
| CLRF   | 273 | Data Addressing Modes   | ec  |
| CLRWDT   | 273 |   | 08  |
| Code Examples                                      |     | Comparing Addressing Modes with<br>the Extended Instruction Set Enabled | 70  |
| 16 x 16 Signed Multiply Routine                    | 80  | Direct  |     |
| 16 x 16 Unsigned Multiply Routine                  | 80  | Indexed Literal Offset  |     |
| 8 x 8 Signed Multiply Routine                      | 79  | Indirect  |     |
| 8 x 8 Unsigned Multiply Routine                    | 79  | Inherent and Literal  |     |
| Changing Between Capture Prescalers                | 131 | Data Memory   |     |
| Computed GOTO Using an Offset Value                | 56  | Access Bank   |     |
| Fast Register Stack                                | 56  | and the Extended Instruction Set  |     |
| How to Clear RAM (Bank 1)                          |     | Bank Select Register (BSR)  |     |
| Using Indirect Addressing                          | 69  | General Purpose Registers   |     |
| Implementing a Real-Time Clock                     |     | Map for PIC18F2410/4410   |     |
| Using a Timer1 Interrupt Service                   |     | Map for PIC18F2510/4510   |     |
| Initializing PORTA                                 |     | Map for PIC18F2515/2610/4515/4610                                       |     |
| Initializing PORTB                                 |     | Special Function Registers  |     |
| Initializing PORTC                                 |     | DAW   |     |
| Initializing PORTD                                 |     | DC and AC Characteristics   |     |
| Initializing PORTE                                 |     | Graphs and Tables   | 351 |
| Loading the SSPBUF (SSPSR) Register                |     | DC Characteristics  |     |
| Reading a Flash Program Memory Word                |     | Power-Down and Supply Current   |     |
| Saving Status, WREG and                            | 00  | Supply Voltage  |     |
| BSR Registers in RAM                               |     | DCFSNZ  |     |
| Code Protection                                    |     | DECF  | 276 |
| COMF   |     | DECFSZ  | 277 |
| Comparator  Analog Input Connection Considerations |     | Demonstration Boards  |     |
| Associated Registers                               |     | PICDEM 1  | 310 |
| Configuration                                      |     | PICDEM 17   | 311 |
| Effects of a Reset                                 |     | PICDEM 18R  | 311 |
| Interrupts   |     | PICDEM 2 Plus   | 310 |
| Operation  |     | PICDEM 3  |     |
| Operation During Sleep                             |     | PICDEM 4  |     |
| Outputs  |     | PICDEM LIN  | 311 |
| Reference  |     | PICDEM USB  |     |
| External Signal                                    |     | PICDEM.net Internet/Ethernet  |     |
| Internal Signal                                    |     | Development Support   |     |
| Response Time                                      |     | Device Differences  | 361 |
| Comparator Specifications                          |     |   |     |

| Device Overview                             |       | Evaluation and Programming Tools                 | 31 <sup>2</sup> |
|---|-------|--|-----------------|
| Details on Individual Family Members        |       | Extended Instruction Set                         | 299             |
| New Core Features                           |       | ADDFSR   | 300             |
| Other Special Features                      | 8     | ADDULNK  |                 |
| Device Overview (PIC18F2410/2510/2515/2610) |       | and Using MPLAB Tools                            |                 |
| Features (table)                            | 9     | CALLW  |                 |
| Device Overview (PIC18F4410/4510/4515/4610) |       | Considerations for Use                           |                 |
| Features (table)                            |       | MOVSF  |                 |
| Device Reset Timers                         |       | MOVSS  |                 |
| Oscillator Start-up Timer (OST)             |       | PUSHL  |                 |
| PLL Lock Time-out                           |       | SUBFSR   |                 |
| Power-up Timer (PWRT)                       |       | SUBULNK  |                 |
| Direct Addressing                           | 70    | Syntax   |                 |
| E   |       | External Clock Input                             | 24              |
| Effect on Standard PIC Instructions71       | , 304 | F  |                 |
| Effects of Power Managed Modes on           |       | Fail-Safe Clock Monitor                          | . 237, 249      |
| Various Clock Sources                       | 31    | Interrupts in Power Managed Modes                | 250             |
| Electrical Characteristics                  | . 313 | POR or Wake from Sleep                           | 250             |
| Enhanced Capture/Compare/PWM (ECCP)         | . 137 | WDT During Oscillator Failure                    | 249             |
| Capture and Compare Modes                   | . 138 | Fast Register Stack                              | 56              |
| Capture Mode. See Capture (ECCP Module).    |       | Flash Program Memory                             | 7               |
| Outputs and Configuration                   | . 138 | Associated Registers                             | 7               |
| Pin Configurations for ECCP1                | . 138 | Control Registers                                | 76              |
| PWM Mode. See PWM (ECCP Module).            |       | Reading  | 76              |
| Standard PWM Mode                           | . 138 | TABLAT (Table Latch) Register                    | 76              |
| Timer Resources                             | . 138 | Table Reads and Table Writes                     | 7               |
| Enhanced PWM Mode. See PWM (ECCP Module).   |       | TBLPTR (Table Pointer) Register                  | 76              |
| Enhanced Universal Synchronous              |       | FSCM. See Fail-Safe Clock Monitor.               |                 |
| Asynchronous Receiver Transmitter           |       | 0  |                 |
| (EUSART). See EUSART.                       |       | G  |                 |
| Equations                                   |       | General Call Address Support                     |                 |
| A/D Acquisition Time                        | . 216 | GOTO   | 278             |
| A/D Minimum Charging Time                   | . 216 | н  |                 |
| Errata                                      | 6     |  |                 |
| EUSART                                      |       | Hardware Multiplier                              |                 |
| Asynchronous Mode                           | . 200 | Introduction                                     |                 |
| 12-Bit Break Transmit and Receive           |       | Operation  |                 |
| Associated Registers, Receive               |       | Performance Comparison                           |                 |
| Associated Registers, Transmit              |       | High/Low-Voltage Detect                          |                 |
| Auto-Wake-up on Sync Break                  |       | Applications                                     |                 |
| Receiver                                    | . 202 | Associated Registers                             |                 |
| Setting up 9-bit Mode with                  |       | Characteristics                                  |                 |
| Address Detect                              |       | Current Consumption                              |                 |
| Transmitter                                 | . 200 | Effects of a Reset                               |                 |
| Baud Rate Generator                         |       | Operation  |                 |
| Operation in Power Managed Mode             |       | During Sleep                                     |                 |
| Baud Rate Generator (BRG)                   | . 195 | Setup  |                 |
| Associated Registers                        |       | Start-up Time                                    |                 |
| Auto-Baud Rate Detect                       |       | Typical Application                              | 234             |
| Baud Rate Error, Calculating                |       | HLVD. See High/Low-Voltage Detect.               |                 |
| Baud Rates, Asynchronous Modes              |       | 1  |                 |
| High Baud Rate Select (BRGH Bit)            |       | -<br>L/O Dorto                                   | 0.1             |
| Sampling                                    |       | I/O Ports  | 9:              |
| Synchronous Master Mode                     |       | I <sup>2</sup> C Mode (MSSP)                     | 10              |
| Associated Registers, Receive               | . 208 | Acknowledge Sequence Timing                      |                 |
| Associated Registers, Transmit              |       | Baud Rate Generator                              | 17              |
| Reception                                   |       | Bus Collision  During a Repeated Start Condition | 404             |
| Transmission                                |       | During a Stan Condition                          |                 |
| Synchronous Slave Mode                      | . 209 | During a Stop Condition                          |                 |
| Associated Registers, Receive               |       | Clock Arbitration                                |                 |
| Associated Registers, Transmit              | . 209 | Clock Stretching                                 |                 |
| Reception                                   | . 210 | 10-Bit Slave Receive Mode (SEN = 1)              |                 |
| Transmission                                | . 209 | 10-Bit Slave Transmit Mode                       |                 |
|   |       | 7-Bit Slave Receive Mode (SEN = 1)               |                 |
|   |       | 7-Bit Slave Transmit Mode                        | 170             |

| Clock Synchronization and the               |           | COMF  | 274             |
|---|-----------|---|-----------------|
| CKP bit (SEN = 1)                           | 171       | CPFSEQ  | 274             |
| Effects of a Reset                          |           | CPFSGT  | 27              |
| General Call Address Support                | 174       | CPFSLT  | 27              |
| I <sup>2</sup> C Clock Rate w/BRG           | 177       | DAW   | 276             |
| Master Mode                                 | 175       | DCFSNZ  | 277             |
| Operation                                   | 176       | DECF  | 276             |
| Reception                                   | 181       | DECFSZ  | 277             |
| Repeated Start Timing                       | 180       | Firmware Instructions                           | 257             |
| Start Condition Timing                      | 179       | General Format                                  | 259             |
| Transmission                                | 181       | GOTO  | 278             |
| Multi-Master Communication, Bus Collision   | 1         | INCF  | 278             |
| and Arbitration                             | 185       | INCFSZ  | 279             |
| Multi-Master Mode                           | 185       | INFSNZ  | 279             |
| Operation                                   | 164       | IORLW   | 280             |
| Read/Write Bit Information (R/W Bit)        | 164, 165  | IORWF   | 280             |
| Registers                                   |           | LFSR  | 28 <sup>2</sup> |
| Serial Clock (RC3/SCK/SCL)                  |           | MOVF  | 28 <sup>2</sup> |
| Slave Mode                                  | 164       | MOVFF   | 282             |
| Addressing                                  | 164       | MOVLB   | 282             |
| Reception                                   |           | MOVLW   | 283             |
| Transmission                                |           | MOVWF   | 283             |
| Sleep Operation                             |           | MULLW   | 284             |
| Stop Condition Timing                       |           | MULWF   | _               |
| ID Locations                                |           | NEGF  |                 |
| INCF  |           | NOP   |                 |
| INCFSZ                                      |           | Opcode Field Descriptions                       |                 |
| In-Circuit Debugger                         |           | POP   |                 |
| In-Circuit Serial Programming (ICSP)        |           | PUSH  | _               |
| Indexed Literal Offset Addressing           | 201 , 200 | RCALL   |                 |
| and Standard PIC18 Instructions             | 304       | RESET   |                 |
| Indexed Literal Offset Mode                 |           | RETFIE  | _               |
| Indirect Addressing                         | ,         | RETLW   |                 |
| INFSNZ                                      |           | RETURN  |                 |
| Initialization Conditions for all Registers |           | RLCF  | _               |
| Instruction Cycle                           |           | RLNCF   | _               |
| Clocking Scheme                             |           | RRCF  |                 |
| Instruction Flow/Pipelining                 |           | RRNCF   | _               |
| Instruction Set                             |           | SETF  | _               |
| ADDLW                                       | 263       | SETF (Indexed Literal Offset mode)              |                 |
| ADDWF                                       |           | SLEEP   |                 |
| ADDWF (Indexed Literal Offset mode)         |           | Standard Instructions                           |                 |
| ADDWFC                                      |           | SUBFWB  |                 |
| ANDLW                                       | _         | SUBLW   | -               |
| ANDWF                                       | ·····     | SUBWF   |                 |
| BC  |           | SUBWFB  |                 |
| BCF   |           | SWAPF   | _               |
| BN  |           | TBLRD   |                 |
| BNC   |           | TBLWT   |                 |
| BNN   |           | TSTFSZ  |                 |
| BNOV  | _         | XORLW   | -               |
| BNZ   |           | XORWF   |                 |
| BOV   |           | INTCON Registers                                | -               |
| BRA   |           | Inter-Integrated Circuit. See I <sup>2</sup> C. | 03–00           |
| BSF   |           | Internal Oscillator Block                       | 20              |
|   |           |   |                 |
| BSF (Indexed Literal Offset mode)           |           | Adjustment                                      |                 |
| BTFSCBTFSS                                  |           | INTOSC Fraguency Drift                          |                 |
|   | -         | INTOSC Prequency Drift                          |                 |
| BTG   |           | INTOSC Output Frequency                         |                 |
| BZ  |           | OSCTUNE Register                                |                 |
| CALL  |           | PLL in INTOSC Modes                             | 20              |
| CLRF  |           | Internal RC Oscillator                          | 6.4             |
| CLRWDT                                      | 273       | Use with WDT                                    | 246             |

| nterrupt Sources                                  | 237 | MULLW                                | 284    |
|---|-----|--------------------------------------|--------|
| A/D Conversion Complete                           |     | MULWF                                |        |
| Capture Complete (CCP)                            |     |                                      |        |
| Compare Complete (CCP)                            |     | N                                    |        |
| Interrupt-on-Change (RB7:RB4)                     |     | NEGF                                 | 285    |
| INTn Pin  |     | NOP                                  |        |
| PORTB, Interrupt-on-Change                        |     |                                      |        |
| TMR0  |     | 0                                    |        |
| TMR0 Overflow                                     |     | OPTION_REG Register                  |        |
|   |     | PSA Bit                              | 115    |
| TMR1 Overflow                                     |     | TOCS Bit                             |        |
| TMR2 to PR2 Match (PWM)                           |     | T0PS2:T0PS0 Bits                     |        |
| TMR3 Overflow                                     |     | TOSE Bit                             |        |
| nterrupts   | 81  | Oscillator Configuration             |        |
| nterrupts, Flag Bits                              |     | 8                                    |        |
| Interrupt-on-Change (RB7:RB4)                     |     | EC                                   |        |
| Flag (RBIF Bit)                                   | 98  | ECIO                                 |        |
| NTOSC, INTRC. See Internal Oscillator Block.      |     | HS                                   |        |
| ORLW  | 280 | HSPLL                                |        |
| ORWF  | 280 | Internal Oscillator Block            |        |
| PR Registers                                      | 90  | INTIO1                               |        |
|   |     | INTIO2                               | 23     |
| <b>L</b>  |     | LP                                   | 23     |
| _FSR  | 281 | RC                                   | 23     |
| _ow-Voltage ICSP Programming.                     |     | RCIO                                 | 23     |
| See Single-Supply ICSP Programming.               |     | XT                                   | 23     |
| 222 2g. 2pp. y 222 2g.                            |     | Oscillator Selection                 | 237    |
| M   |     | Oscillator Start-up Timer (OST)      |        |
| Master Clear (MCLR)                               | 43  | Oscillator Switching                 |        |
| Master Synchronous Serial Port (MSSP). See MS     |     | Oscillator Transitions               |        |
| Memory Organization                               |     | Oscillator, Timer1                   |        |
| Data Memory                                       |     | Oscillator, Timer3                   |        |
| Program Memory                                    |     | Oscillator, Timers                   | 120    |
|   |     | P                                    |        |
| Memory Programming Requirements                   | 328 | Packaging Information                | 253    |
| Migration from Baseline to                        | 200 | Details (Diagrams)                   |        |
| Enhanced Devices                                  | 302 | Marking                              |        |
| Migration from High-End to                        |     |                                      |        |
| Enhanced Devices                                  | 363 | Parallel Slave Port (PSP)            |        |
| Migration from Mid-Range to                       |     | Associated Registers                 |        |
| Enhanced Devices                                  |     | CS (Chip Select)                     |        |
| MOVF  | -   | PORTD                                |        |
| MOVFF   | 282 | RD (Read Input)                      |        |
| MOVLB   | 282 | Select (PSPMODE Bit)                 |        |
| MOVLW   | 283 | WR (Write Input)                     |        |
| MOVSF   | 301 | PICkit 1 Flash Starter Kit           |        |
| MOVSS   | 302 | PICSTART Plus Development Programmer | 310    |
| MOVWF   | 283 | PIE Registers                        | 88     |
| MPLAB ASM30 Assembler, Linker, Librarian          | 308 | Pin Functions                        |        |
| MPLAB ICD 2 In-Circuit Debugger                   |     | MCLR/VPP/RE3                         | 13, 17 |
| MPLAB ICE 2000 High-Performance                   |     | OSC1/CLKI/RA7                        |        |
| Universal In-Circuit Emulator                     | 309 | OSC2/CLKO/RA6                        | ,      |
| MPLAB ICE 4000 High-Performance                   |     | RA0/AN0                              | ,      |
| Universal In-Circuit Emulator                     | 300 | RA1/AN1                              |        |
|   | 309 | RA2/AN2/VREF-/CVREF                  | ,      |
| MPLAB Integrated Development                      | 207 | RA3/AN3/VREF+                        |        |
| Environment Software                              |     |                                      | •      |
| MPLAB PM3 Device Programmer                       |     | RA4/T0CKI/C1OUT                      | •      |
| MPLINK Object Linker/MPLIB Object Librarian       | 308 | RA5/AN4/SS/HLVDIN/C2OUT              |        |
| MSS <u>P</u>                                      |     | RB0/INT0/FLT0/AN12                   | •      |
| ACK Pulse   |     | RB1/INT1/AN10                        | •      |
| Control Registers (general)                       | 151 | RB2/INT2/AN8                         | ,      |
| I <sup>2</sup> C Mode. See I <sup>2</sup> C Mode. |     | RB3/AN9/CCP2                         |        |
| Module Overview                                   | 151 | RB4/KBI0/AN11                        | 15, 19 |
| SPI Master/Slave Connection                       | 155 | RB5/KBI1/PGM                         | 15, 19 |
| SPI Mode. See SPI Mode.                           |     | RB6/KBI2/PGC                         |        |
| SSPBUF  | 156 | RB7/KBI3/PGD                         |        |
| SSPSR   |     | RC0/T10S0/T13CKI                     |        |
| - · · · · · · · · · · · · · · · · · · ·           |     |                                      |        |

| RC1/T1OSI/CCP2                     | 16, 20 | Power Managed Modes                      | 33  |
|------------------------------------|--------|--|-----|
| RC2/CCP1                           | 16     | and A/D Operation                        | 218 |
| RC2/CCP1/P1A                       | 20     | and EUSART Operation                     | 195 |
| RC3/SCK/SCL                        | 16, 20 | and Multiple Sleep Commands              |     |
| RC4/SDI/SDA                        | 16, 20 | and PWM Operation                        |     |
| RC5/SDO                            | -      | and SPI Operation                        |     |
| RC6/TX/CK                          | ,      | Clock Sources                            |     |
| RC7/RX/DT                          | ,      | Clock Transitions and Status Indicators  |     |
| RD0/PSP0                           | •      | Effects on Clock Sources                 |     |
| RD1/PSP1                           |        | Entering                                 |     |
| RD2/PSP2                           |        | Exiting Idle and Sleep Modes             |     |
| RD3/PSP3                           |        | by Interrupt                             |     |
| RD4/PSP4                           |        |  |     |
|                                    |        | by Reset                                 |     |
| RD5/PSP5/P1B                       |        | by WDT Time-out                          |     |
| RD6/PSP6/P1C                       |        | Without a Start-up Delay                 |     |
| RD7/PSP7/P1D                       |        | Idle Modes                               |     |
| RE0/RD/AN5                         |        | PRI_IDLE                                 |     |
| RE1/WR/AN6                         |        | RC_IDLE                                  |     |
| RE2/CS/AN7                         |        | SEC_IDLE                                 |     |
| VDD                                | •      | Run Modes                                |     |
| Vss                                | 16, 22 | PRI_RUN                                  |     |
| Pinout I/O Descriptions            |        | RC_RUN                                   |     |
| PIC18F2410/2510/2515/2610          | 13     | SEC_RUN                                  |     |
| PIC18F4410/4510/4515/4610          | 17     | Selecting                                |     |
| PIR Registers                      | 86     | Sleep Mode                               | 37  |
| PLL Frequency Multiplier           | 25     | Summary (table)                          |     |
| HSPLL Oscillator Mode              | 25     | Power-on Reset (POR)                     | 43  |
| Use with INTOSC                    | 25     | Power-up Timer (PWRT)                    | 45  |
| POP                                | 286    | Time-out Sequence                        | 45  |
| POR. See Power-on Reset.           |        | Power-up Delays                          |     |
| PORTA                              |        | Power-up Timer (PWRT)                    |     |
| Associated Registers               | 97     | Prescaler                                |     |
| LATA Register                      |        | Timer2                                   | 140 |
| PORTA Register                     |        | Prescaler, Timer0                        |     |
| TRISA Register                     |        | Assignment (PSA Bit)                     |     |
| PORTB                              |        | Rate Select (T0PS2:T0PS0 Bits)           |     |
| Associated Registers               | 100    | Switching Between Timer0 and WDT         |     |
| LATB Register                      |        | Prescaler, Timer2                        |     |
| PORTB Register                     |        | PRI_IDLE Mode                            |     |
| RB7:RB4 Interrupt-on-Change Flag   |        | PRI_RUN Mode                             |     |
| (RBIF Bit)                         | 98     | PRO MATE II Universal Device Programmer  |     |
| TRISB Register                     |        | Program Counter                          |     |
| PORTC                              |        | PCL, PCH and PCU Registers               |     |
| Associated Registers               | 102    | PCLATH and PCLATU Registers              |     |
| LATC Register                      |        | Program Memory                           | 54  |
|                                    |        | and Extended Instruction Set             | 72  |
| PORTC Register                     |        |  |     |
| RC3/SCK/SCL Pin                    |        | Code Protection                          |     |
| TRISC Register                     | 101    | Instructions                             |     |
| PORTD                              | 400    | Two-Word                                 |     |
| Associated Registers               |        | Interrupt Vector                         |     |
| LATD Register                      |        | Look-up Tables                           |     |
| Parallel Slave Port (PSP) Function |        | Map and Stack (diagram)                  |     |
| PORTD Register                     |        | Reset Vector                             |     |
| TRISD Register                     | 104    | Program Verification and Code Protection |     |
| PORTE                              |        | Associated Registers                     | 252 |
| Associated Registers               | 109    | Programming, Device Instructions         | 257 |
| LATE Register                      | 107    | PSP. See Parallel Slave Port.            |     |
| PORTE Register                     | 107    | Pulse-Width Modulation. See PWM (        |     |
| PSP Mode Select (PSPMODE Bit)      |        | CCP Module) and PWM (ECCP Module).       |     |
| TRISE Register                     | 107    | PUSH                                     | 286 |
| Postscaler, WDT                    |        | PUSH and POP Instructions                | 55  |
| Assignment (PSA Bit)               | 115    | PUSHL                                    | 302 |
| Rate Select (T0PS2:T0PS0 Bits)     |        |  |     |
| Switching Between Timer0 and WDT   |        |  |     |

| PWM (CCP Module)   |                                 | Device ID Register 1  | 245                    |
|--|---------------------------------|---|------------------------|
| Associated Registers   | 136                             | Device ID Register 2  |                        |
| Auto-Shutdown (CCP1 only)  | 135                             | ECCP1AS (ECCP Auto-Shutdown   |                        |
| CCPR1H:CCPR1L Registers  |                                 | Control)  | 147                    |
| Duty Cycle   | 134, 140                        | HLVDCON (HLVD Control)  | 231                    |
| Example Frequencies/Resolutions  | 135, 140                        | INTCON (Interrupt Control)  | 83                     |
| Period   |                                 | INTCON2 (Interrupt Control 2)   | 84                     |
| Setup for PWM Operation  | 135                             | INTCON3 (Interrupt Control 3)   |                        |
| TMR2 to PR2 Match  |                                 | IPR1 (Peripheral Interrupt Priority 1)  | 90                     |
| PWM (ECCP Module)  | 139                             | IPR2 (Peripheral Interrupt Priority 2)  |                        |
| Associated Registers   |                                 | OSCCON (Oscillator Control)   |                        |
| Direction Change in Full-Bridge  |                                 | OSCTUNE (Oscillator Tuning)   |                        |
| Output Mode  | 144                             | PIE1 (Peripheral Interrupt Enable 1)  |                        |
| Effects of a Reset   |                                 | PIE2 (Peripheral Interrupt Enable 2)  |                        |
| Enhanced PWM Auto-Shutdown   | -                               | PIR1 (Peripheral Interrupt  |                        |
| Full-Bridge Application Example  |                                 | Request (Flag) 1)   | 86                     |
| Full-Bridge Mode   |                                 | PIR2 (Peripheral Interrupt  |                        |
| Half-Bridge Mode   |                                 | Request (Flag) 2)   | 87                     |
| Half-Bridge Output Mode  |                                 | PWM1CON (PWM Configuration)   |                        |
| Applications Example   | 142                             | RCON (Reset Control)  |                        |
| Operation in Power Managed Modes   |                                 | RCSTA (Receive Status and Control)  |                        |
| Operation with Fail-Safe Clock Monitor   |                                 | SSPCON1 (MSSP Control 1, I <sup>2</sup> C Mode)   |                        |
|  |                                 | SSPCON1 (MSSP Control 1, 1 C Mode)  |                        |
| Output Politicaphine (Active High)   |                                 | SSPCON1 (MSSP Control 2, I <sup>2</sup> C Mode)   |                        |
| Output Relationships (Active-High)   |                                 | SSPSTAT (MSSP Status, I <sup>2</sup> C Mode)  |                        |
| Output Relationships (Active-Low)  |                                 |   |                        |
| Programmable Dead-Band Delay   |                                 | SSPSTAT (MSSP Status, SPI Mode)   |                        |
| Setup for PWM Operation  |                                 | Status  |                        |
| Start-up Considerations  | 148                             | STKPTR (Stack Pointer)  |                        |
| Q  |                                 | T0CON (Timer0 Control)  |                        |
|  |                                 | T1CON (Timer1 Control)  |                        |
| Q Clock  | 135, 140                        | T2CON (Timer 2 Control)   |                        |
| R  |                                 | T3CON (Timer3 Control)  |                        |
|  |                                 | TRISE (PORTE/PSP Control)   |                        |
| RAM. See Data Memory.  |                                 | TXSTA (Transmit Status and Control)   | 192                    |
| RBIF Bit   |                                 | WDTCON (Watchdog Timer Control)   |                        |
| RC Oscillator  |                                 | RESET   |                        |
| RCIO Oscillator Mode   |                                 | Reset State of Registers  | 48                     |
| RC_IDLE Mode   |                                 | Resets  |                        |
| RC_RUN Mode  |                                 | Brown-out Reset (BOR)   | 237                    |
| RCALL  | 287                             | Oscillator Start-up Timer (OST)   | 237                    |
| RCON Register  |                                 | Power-on Reset (POR)  | 237                    |
| Bit Status During Initialization   |                                 | Power-up Timer (PWRT)   | 237                    |
| Register File  | 63                              | RETFIE  | 288                    |
| Registers  |                                 | RETLW   | 288                    |
| ADCON0 (A/D Control 0)   | 211                             | RETURN  | 289                    |
| ADCON1 (A/D Control 1)   |                                 | Return Address Stack  | 54                     |
| ADCON2 (A/D Control 2)   | 213                             | Return Stack Pointer (STKPTR)   | 55                     |
| BAUDCON (Baud Rate Control)  | 194                             | Revision History  |                        |
| CCP1CON (Enhanced  |                                 | RLCF  |                        |
| Capture/Compare/PWM Control 1)   | 137                             | RLNCF   |                        |
| CCPxCON (Standard  |                                 | RRCF  |                        |
| Capture/Compare/PWM Control)   |                                 |   |                        |
| CMCON (Comparator Control)   | 129                             | RRNCE   |                        |
| CIVICON (Comparator Control)   |                                 | RRNCF   | 23                     |
| , ,  | 221                             | RRNCF   | 29                     |
| CONFIG1H (Configuration 1 High)  | 221<br>238                      | S   |                        |
| CONFIG1H (Configuration 1 High)CONFIG2H (Configuration 2 High)   | 221<br>238<br>240               | <b>S</b><br>SCK   | 151                    |
| CONFIG1H (Configuration 1 High)  | 221<br>238<br>240<br>239        | SCKSDI  | 151<br>151             |
| CONFIG1H (Configuration 1 High)  | 221<br>238<br>240<br>239<br>241 | <b>S</b> SCKSDISDO  | 151<br>151<br>151      |
| CONFIG1H (Configuration 1 High)  | 221<br>238<br>240<br>239<br>241 | \$ SCKSDISDOSDOSEC_IDLE Mode  | 151<br>151<br>153      |
| CONFIG1H (Configuration 1 High)  |                                 | \$ SCK  | 151<br>151<br>38<br>34 |
| CONFIG1H (Configuration 1 High)  |                                 | \$  \$CK  \$DI  \$DO  \$EC_IDLE Mode  \$EC_RUN Mode  \$erial Clock, SCK   |                        |
| CONFIG1H (Configuration 1 High)  |                                 | \$  \$CK  \$DI  \$DO  \$EC_IDLE Mode  \$EC_RUN Mode  Serial Clock, SCK  Serial Data In (SDI)  |                        |
| CONFIG1H (Configuration 1 High)  |                                 | \$  \$CK  \$DI  \$DO  \$EC_IDLE Mode  \$EC_RUN Mode  \$erial Clock, SCK  \$erial Data In (SDI)  \$erial Data Out (SDO)                                |                        |
| CONFIG1H (Configuration 1 High)  CONFIG2H (Configuration 2 High)  CONFIG2L (Configuration 2 Low)  CONFIG3H (Configuration 3 High)  CONFIG4L (Configuration 4 Low)  CONFIG5H (Configuration 5 High)  CONFIG5L (Configuration 5 Low)  CONFIG6H (Configuration 6 High)  CONFIG6H (Configuration 6 Low)  CONFIG6H (Configuration 7 High)                                 |                                 | S SCK SDI SDO SEC_IDLE Mode SEC_RUN Mode Serial Clock, SCK Serial Data In (SDI) Serial Peripheral Interface. See SPI Mode.                            |                        |
| CONFIG1H (Configuration 1 High)  CONFIG2H (Configuration 2 High)  CONFIG2L (Configuration 2 Low)  CONFIG3H (Configuration 3 High)  CONFIG4L (Configuration 4 Low)  CONFIG5H (Configuration 5 High)  CONFIG5L (Configuration 5 Low)  CONFIG6H (Configuration 6 High)  CONFIG6H (Configuration 6 Low)  CONFIG7H (Configuration 7 High)  CONFIG7L (Configuration 7 Low) |                                 | S SCK SDI SDO SEC_IDLE Mode SEC_RUN Mode Serial Clock, SCK Serial Data In (SDI) Serial Data Out (SDO) Serial Peripheral Interface. See SPI Mode. SETF |                        |
| CONFIG1H (Configuration 1 High)  CONFIG2H (Configuration 2 High)  CONFIG2L (Configuration 2 Low)  CONFIG3H (Configuration 3 High)  CONFIG4L (Configuration 4 Low)  CONFIG5H (Configuration 5 High)  CONFIG5L (Configuration 5 Low)  CONFIG6H (Configuration 6 High)  CONFIG6H (Configuration 6 Low)  CONFIG6H (Configuration 7 High)                                 |                                 | S SCK SDI SDO SEC_IDLE Mode SEC_RUN Mode Serial Clock, SCK Serial Data In (SDI) Serial Peripheral Interface. See SPI Mode.                            |                        |

| SLEEP                                  | 292      | Timer1                                     | 117      |
|--|----------|--|----------|
| Sleep                                  |          | 16-Bit Read/Write Mode                     |          |
| OSC1 and OSC2 Pin States               | 31       | Associated Registers                       |          |
| Software Simulator (MPLAB SIM)         |          | Interrupt                                  |          |
| Software Simulator (MPLAB SIM30)       |          | Operation                                  |          |
| Special Event Trigger.                 |          | Oscillator                                 |          |
| See Compare (ECCP Mode).               |          | Oscillator Layout Considerations           |          |
| Special Event Trigger.                 |          | Overflow Interrupt                         |          |
| See Compare (ECCP Module).             |          | Resetting, Using the CCP                   |          |
| Special Features of the CPU            | 237      | Special Event Trigger                      | 120      |
| Special Function Registers             |          | Special Event Trigger (ECCP)               |          |
| Map                                    | 64       | TMR1H Register                             |          |
| SPI Mode (MSSP)                        |          | TMR1L Register                             | 117      |
| Associated Registers                   | 159      | Use as a Real-Time Clock                   | 120      |
| Bus Mode Compatibility                 | 159      | Timer2                                     | 123      |
| Effects of a Reset                     | 159      | Associated Registers                       | 124      |
| Enabling SPI I/O                       | 155      | Interrupt                                  | 124      |
| Master Mode                            | 156      | Operation                                  | 123      |
| Master/Slave Connection                | 155      | Output                                     | 124      |
| Operation                              | 154      | PR2 Register                               | 134, 139 |
| Operation in Power                     |          | TMR2 to PR2 Match Interrupt                | 134, 139 |
| Managed Modes                          | 159      | Timer3                                     | 125      |
| Serial Clock                           | 151      | 16-Bit Read/Write Mode                     | 127      |
| Serial Data In                         | 151      | Associated Registers                       | 127      |
| Serial Data Out                        | 151      | Operation                                  | 126      |
| Slave Mode                             | 157      | Oscillator                                 | 125, 127 |
| Slave Select                           | 151      | Overflow Interrupt                         | 125, 127 |
| Slave Select Synchronization           | 157      | Special Event Trigger (CCP)                | 127      |
| SPI Clock                              | 156      | TMR3H Register                             | 125      |
| Typical Connection                     | 155      | TMR3L Register                             | 125      |
| SS                                     | 151      | Timing Diagrams                            |          |
| SSPOV                                  | 181      | A/D Conversion                             |          |
| SSPOV Status Flag                      | 181      | Acknowledge Sequence                       | 184      |
| SSPSTAT Register                       |          | Asynchronous Reception                     |          |
| R/W Bit                                | 164, 165 | Asynchronous Transmission                  | 201      |
| Stack Full/Underflow Resets            | 56       | Asynchronous Transmission                  |          |
| SUBFSR                                 | 303      | (Back to Back)                             | 201      |
| SUBFWB                                 | 292      | Automatic Baud Rate Calculation            | 199      |
| SUBLW                                  | 293      | Auto-Wake-up Bit (WUE) During              |          |
| SUBULNK                                | 303      | Normal Operation                           | 204      |
| SUBWF                                  | 293      | Auto-Wake-up Bit (WUE) During Sleep        |          |
| SUBWFB                                 | 294      | Baud Rate Generator with Clock Arbitration | 178      |
| SWAPF                                  | 294      | BRG Overflow Sequence                      | 199      |
| т                                      |          | BRG Reset Due to SDA Arbitration           |          |
|  |          | During Start Condition                     |          |
| Table Pointer Operations (table)       |          | Brown-out Reset (BOR)                      | 336      |
| Table Reads/Table Writes               |          | Bus Collision During a Repeated            |          |
| TBLRD                                  |          | Start Condition (Case 1)                   | 188      |
| TBLWT                                  |          | Bus Collision During a Repeated            |          |
| Time-out in Various Situations (table) |          | Start Condition (Case 2)                   | 188      |
| Timer0                                 |          | Bus Collision During a Start Condition     |          |
| 16-Bit Mode Timer Reads and Writes     |          | (SCL = 0)                                  | 187      |
| Associated Registers                   | 115      | Bus Collision During a Start Condition     |          |
| Clock Source Edge Select               |          | (SDA only)                                 | 186      |
| (TOSE Bit)                             |          | Bus Collision During a Stop Condition      |          |
| Clock Source Select (T0CS Bit)         |          | (Case 1)                                   | 189      |
| Operation                              |          | Bus Collision During a Stop Condition      |          |
| Overflow Interrupt                     |          | (Case 2)                                   |          |
| Prescaler                              | 115      | Bus Collision for Transmit and Acknowledge |          |
| Prescaler. See Prescaler, Timer0.      |          | Capture/Compare/PWM (CCP)                  | 338      |

| CLKO and I/O                                      | 335  | Synchronous Transmission                          | 206  |
|---|------|---|------|
| Clock Synchronization                             |      | Synchronous Transmission                          |      |
| Clock/Instruction Cycle                           | 57   | (Through TXEN)                                    | 207  |
| Example SPI Master Mode (CKE = 0)                 | 340  | Time-out Sequence on POR w/PLL                    |      |
| Example SPI Master Mode (CKE = 1)                 |      | Enabled (MCLR Tied to VDD)                        | 47   |
| Example SPI Slave Mode (CKE = 0)                  |      | Time-out Sequence on Power-up                     |      |
| Example SPI Slave Mode (CKE = 1)                  |      | (MCLR Not Tied to VDD, Case 1)                    | 46   |
| External Clock (All Modes except PLL)             |      | Time-out Sequence on Power-up                     |      |
| Fail-Safe Clock Monitor                           |      | (MCLR Not Tied to VDD, Case 2)                    | 46   |
| First Start Bit Timing                            |      | Time-out Sequence on Power-up                     |      |
| Full-Bridge PWM Output                            |      | (MCLR Tied to VDD, VDD Rise < TPWRT)              | 46   |
| Half-Bridge PWM Output                            |      | Timer0 and Timer1 External Clock                  |      |
| High/Low-Voltage Detect Characteristics           |      | Transition for Entry to Idle Mode                 | 38   |
| High-Voltage Detect (VDIRMAG = 1)                 |      | Transition for Entry to SEC_RUN Mode              |      |
| I <sup>2</sup> C Bus Data                         |      | Transition for Entry to Sleep Mode                |      |
| I <sup>2</sup> C Bus Start/Stop Bits              |      | Transition for Two-Speed Start-up                 |      |
| I <sup>2</sup> C Master Mode (7 or                |      | (INTOSC to HSPLL)                                 | 248  |
| 10-Bit Transmission)                              | 182  | Transition for Wake from Idle to                  |      |
| I <sup>2</sup> C Master Mode (7-Bit Reception)    |      | Run Mode  | 38   |
| I <sup>2</sup> C Slave Mode (10-Bit Reception,    |      | Transition for Wake from Sleep (HSPLL)            |      |
| SEN = 0)  | 168  | Transition from RC_RUN Mode to                    |      |
| I <sup>2</sup> C Slave Mode (10-Bit Reception,    |      | PRI_RUN Mode                                      | 36   |
| SEN = 1)  | 173  | Transition from SEC_RUN Mode to                   |      |
| I <sup>2</sup> C Slave Mode (10-Bit Transmission) |      | PRI_RUN Mode (HSPLL)                              | 35   |
| I <sup>2</sup> C Slave Mode (7-Bit Reception,     |      | Transition to RC_RUN Mode                         |      |
| SEN = 0)  | 166  | USART Synchronous Receive                         |      |
| I <sup>2</sup> C Slave Mode (7-Bit Reception,     |      | (Master/Slave)                                    | 348  |
| SEN = 1)  | 172  | USART Synchronous Transmission                    | 0 10 |
| I <sup>2</sup> C Slave Mode (7-Bit Transmission)  |      | (Master/Slave)                                    | 348  |
| I <sup>2</sup> C Slave Mode General Call Address  |      | Timing Diagrams and Specifications                |      |
| Sequence (7 or 10-Bit Address Mode)               | 174  | A/D Conversion Requirements                       |      |
| I <sup>2</sup> C Stop Condition Receive or        |      | Capture/Compare/PWM (CCP)                         | 550  |
| Transmit Mode                                     | 184  | Requirements                                      | 338  |
| Low-Voltage Detect (VDIRMAG = 0)                  |      | CLKO and I/O Requirements                         |      |
| Master SSP I <sup>2</sup> C Bus Data              | 346  | Example SPI Mode Requirements                     | 550  |
| Master SSP I <sup>2</sup> C Bus Start/Stop Bits   | 346  | (Master Mode, CKE = 0)                            | 340  |
| Parallel Slave Port                               |      | Example SPI Mode Requirements                     | 040  |
| (PIC18F4410/4510/4515/4610)                       | 330  | (Master Mode, CKE = 1)                            | 3/11 |
| Parallel Slave Port (PSP) Read                    |      | Example SPI Mode Requirements                     | 571  |
| Parallel Slave Port (PSP) Write                   |      | (Slave Mode, CKE = 0)                             | 342  |
| PWM Auto-Shutdown (PRSEN = 0,                     |      | Example SPI Mode Requirements                     | 0-12 |
| Auto-Restart Disabled)                            | 148  | (Slave Mode, CKE = 1)                             | 3/13 |
| PWM Auto-Shutdown (PRSEN = 1,                     | 140  | External Clock Requirements                       |      |
| Auto-Restart Enabled)                             | 1/18 | I <sup>2</sup> C Bus Data Requirements            | 550  |
| PWM Direction Change                              |      | (Slave Mode)                                      | 345  |
| PWM Direction Change at Near                      | 140  | Master SSP I <sup>2</sup> C Bus Data Requirements |      |
| 100% Duty Cycle                                   | 1/15 | Master SSP I <sup>2</sup> C Bus Start/Stop Bits   | 547  |
| PWM Output  |      | Requirements                                      | 3/6  |
| Repeat Start Condition                            |      | Parallel Slave Port Requirements                  | 540  |
| Reset, Watchdog Timer (WDT),                      | 100  | (PIC18F4410/4510/4515/4610)                       | 330  |
| Oscillator Start-up Timer (OST),                  |      | PLL Clock   |      |
| Power-up Timer (PWRT)                             | 226  | Reset, Watchdog Timer,                            | 554  |
| Send Break Character Sequence                     |      | Oscillator Start-up Timer,                        |      |
| Slave Synchronization                             |      | Power-up Timer and                                |      |
| Slow Rise Time (MCLR Tied to VDD,                 | 101  | Brown-out Reset Requirements                      | 226  |
|   | 17   |   | 330  |
| VDD Rise > TPWRT)                                 |      | Timer0 and Timer1 External                        | 207  |
| SPI Mode (Master Mode)                            |      | Clock Requirements                                | 331  |
| SPI Mode (Slave Mode, CKE = 0)                    |      | USART Synchronous                                 | 240  |
| SPI Mode (Slave Mode, CKE = 1)                    | 100  | Receive Requirements                              | 348  |
| Synchronous Reception (Master Mode, SREN)         | 200  | USART Synchronous  Transmission Requirements      | 240  |
| (Master Mode, SREN)                               | ∠∪ŏ  | riansmission Requirements                         | 348  |

| Top-of-Stack Access              | 54       |
|----------------------------------|----------|
| TRISE Register                   |          |
| PSPMODE Bit                      | 104      |
| TSTFSZ                           | 297      |
| Two-Speed Start-up               | 237, 248 |
| Two-Word Instructions            |          |
| Example Cases                    | 58       |
| TXSTA Register                   |          |
| BRGH Bit                         | 195      |
| V                                |          |
| Voltage Reference Specifications | 329      |

| W                          |                      |
|----------------------------|----------------------|
| Watchdog Timer (WDT)       | 237, 246             |
| Associated Registers       | 247                  |
| Control Register           | 246                  |
| During Oscillator Failure  | 249                  |
| Programming Considerations | 246                  |
| WCOL                       | . 179, 180, 181, 184 |
| WCOL Status Flag           | . 179, 180, 181, 184 |
| WWW, On-Line Support       | 6                    |
| X                          |                      |
| XORLW                      | 297                  |
| XORWF                      | 298                  |

#### **ON-LINE SUPPORT**

Microchip provides on-line support on the Microchip World Wide Web site.

The web site is used by Microchip as a means to make files and information easily available to customers. To view the site, the user must have access to the Internet and a web browser, such as Netscape® or Microsoft® Internet Explorer. Files are also available for FTP download from our FTP site.

### **Connecting to the Microchip Internet Web Site**

The Microchip web site is available at the following URL:

#### www.microchip.com

The file transfer site is available by using an FTP service to connect to:

#### ftp://ftp.microchip.com

The web site and file transfer site provide a variety of services. Users may download files for the latest Development Tools, Data Sheets, Application Notes, User's Guides, Articles and Sample Programs. A variety of Microchip specific business information is also available, including listings of Microchip sales offices, distributors and factory representatives. Other data available for consideration is:

- Latest Microchip Press Releases
- Technical Support Section with Frequently Asked Questions
- · Design Tips
- · Device Errata
- Job Postings
- Microchip Consultant Program Member Listing
- Links to other useful web sites related to Microchip Products
- Conferences for products, Development Systems, technical information and more
- · Listing of seminars and events

### SYSTEMS INFORMATION AND UPGRADE HOT LINE

The Systems Information and Upgrade Line provides system users a listing of the latest versions of all of Microchip's development systems software products. Plus, this line provides information on how customers can receive the most current upgrade kits. The Hot Line Numbers are:

1-800-755-2345 for U.S. and most of Canada and 1-480-792-7302 for the rest of the world.

042003

#### **READER RESPONSE**

то.

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information and use this outline to provide us with your comments about this document.

| RE:  | Reader Response                                      | Total Pages Sent                                       |
|------|--|--|
|      | m: Name Company Address City / State / ZIP / Country |  |
| Appl | Telephone: ()<br>lication (optional):                | FAX: ()  |
|      | uld you like a reply?YN                              |  |
| Devi | rice: PIC18F2X1X/4X1X                                | Literature Number: DS39636A                            |
| Que  | estions:   |  |
| 1.   | What are the best features of this do                | ocument?   |
| 2.   | How does this document meet your                     | hardware and software development needs?               |
| 3.   | Do you find the organization of this o               | document easy to follow? If not, why?                  |
| 4.   | What additions to the document do y                  | you think would enhance the structure and subject?     |
| 5.   | What deletions from the document of                  | ould be made without affecting the overall usefulness? |
| 6.   | Is there any incorrect or misleading                 | information (what and where)?                          |
| 7.   | How would you improve this docume                    | ent?   |
| -    |  |  |
| •    |  |  |

#### PIC18F2X1X/4X1X PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

| PART NO.             | x /xx xxx   | Examples:   |
|----------------------|---|---|
| <b>Device</b> Device | Temperature Package Pattern Range  PIC18F2410/2510/2515/2610 <sup>(1)</sup> , PIC18F2410/4510/4515/4610 <sup>(1)</sup> , PIC18F2410/2510/2515/2610T <sup>(2)</sup> , PIC18F2410/4510/4515/4610 T <sup>(2)</sup> ;   | <ul> <li>a) PIC18LF4510-I/P 301 = Industrial temp., PDIP package, Extended VDD limits, QTP pattern #301.</li> <li>b) PIC18LF2410-I/SO = Industrial temp., SOIC package, Extended VDD limits.</li> <li>c) PIC18F4410-I/P = Industrial temp., PDIP package, normal VDD limits.</li> </ul> |
| Temperature Range    | VDD range 4.2V to 5.5V  PIC18LF2410/2510/2515/2610 <sup>(1)</sup> , PIC18LF2410/4510/4515/4610 <sup>(1)</sup> , PIC18LF2410/2510/2515/2610T <sup>(2)</sup> , PIC18LF2410/2510/2515/4610T <sup>(2)</sup> ; VDD range 2.0V to 5.5V  I = -40°C to +85°C (Industrial) |   |
|                      | $E = -40^{\circ}C \text{ to } +125^{\circ}C \text{ (Extended)}$   | Note 1: F = Standard Voltage Range LF = Wide Voltage Range 2: T = in tape and reel TQFP   |
| Package              | PT = TQFP (Thin Quad Flatpack) SO = SOIC SP = Skinny Plastic DIP P = PDIP ML = QFN  | packages only.  |
| Pattern              | QTP, SQTP, Code or Special Requirements (blank otherwise)   |   |

© 2004 Microchip Technology Inc. Preliminary DS39636A-page 377



#### Worldwide Sales and Service

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277

Technical Support: 480-792-7627 Web Address: www.microchip.com

Atlanta

3780 Mansell Road, Suite 130 Alpharetta, GA 30022 Tel: 770-640-0034 Fax: 770-640-0307

**Boston** 

2 Lan Drive, Suite 120 Westford, MA 01886 Tel: 978-692-3848 Fax: 978-692-3821

Chicago

333 Pierce Road, Suite 180 Itasca, IL 60143 Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** 

4570 Westgrove Drive, Suite 160 Addison, TX 75001 Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Tri-Atria Office Building 32255 Northwestern Highway, Suite 190 Farmington Hills, MI 48334

Tel: 248-538-2250 Fax: 248-538-2260 **Kokomo** 

2767 S. Albright Road Kokomo, IN 46902 Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles

18201 Von Karman, Suite 1090 Irvine, CA 92612 Tel: 949-263-1888 Fax: 949-263-1338

San Jose

1300 Terra Bella Avenue Mountain View, CA 94043 Tel: 650-215-1444 Fax: 650-961-0286

**Toronto** 

6285 Northam Drive, Suite 108 Mississauga, Ontario L4V 1X5, Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Australia

Suite 22, 41 Rawson Street Epping 2121, NSW Australia

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755 China - Beijing

Unit 706B Wan Tai Bei Hai Bldg. No. 6 Chaoyangmen Bei Str. Beijing, 100027, China Tel: 86-10-85282100 Fax: 86-10-85282104

China - Chengdu

Rm. 2401-2402, 24th Floor, Ming Xing Financial Tower No. 88 TIDU Street Chengdu 610016, China Tel: 86-28-86766200 Fax: 86-28-86766599

China - Fuzhou

Unit 28F, World Trade Plaza No. 71 Wusi Road Fuzhou 350001, China Tel: 86-591-7503506 Fax: 86-591-7503521

China - Hong Kong SAR

Unit 901-6, Tower 2, Metroplaza 223 Hing Fong Road Kwai Fong, N.T., Hong Kong Tel: 852-2401-1200 Fax: 852-2401-3431

China - Shanghai

Room 701, Bldg. B Far East International Plaza No. 317 Xian Xia Road Shanghai, 200051 Tel: 86-21-6275-5700 Fax: 86-21-6275-5060

China - Shenzhen

Rm. 1812, 18/F, Building A, United Plaza No. 5022 Binhe Road, Futian District

Shenzhen 518033, China Tel: 86-755-82901380 Fax: 86-755-8295-1393

China - Shunde

Room 401, Hongjian Building, No. 2 Fengxiangnan Road, Ronggui Town, Shunde District, Foshan City, Guangdong 528303, China Tel: 86-757-28395507 Fax: 86-757-28395571

China - Qingdao

Rm. B505A, Fullhope Plaza, No. 12 Hong Kong Central Rd. Qingdao 266071, China

Tel: 86-532-5027355 Fax: 86-532-5027205

India

Divyasree Chambers 1 Floor, Wing A (A3/A4) No. 11, O'Shaugnessey Road Bangalore, 560 025, India Tel: 91-80-22290061 Fax: 91-80-22290062

Japan

Benex S-1 6F 3-18-20, Shinyokohama Kohoku-Ku, Yokohama-shi Kanagawa, 222-0033, Japan Tel: 81-45-471- 6166 Fax: 81-45-471-6122 Korea

168-1, Youngbo Bldg. 3 Floor Samsung-Dong, Kangnam-Ku Seoul, Korea 135-882 Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Singapore

200 Middle Road #07-02 Prime Centre Singapore, 188980

Tel: 65-6334-8870 Fax: 65-6334-8850

Taiwan

Kaohsiung Branch 30F - 1 No. 8 Min Chuan 2nd Road Kaohsiung 806, Taiwan Tel: 886-7-536-4818 Fax: 886-7-536-4803

Taiwan

Taiwan Branch 11F-3, No. 207 Tung Hua North Road Taipei, 105, Taiwan

Tel: 886-2-2717-7175 Fax: 886-2-2545-0139

#### **EUROPE**

Austria

Durisolstrasse 2 A-4600 Wels Austria Tel: 43-7242-2244-399

Fax: 43-7242-2244-399

Fax: 43-7242-2244-393

Denmark

Regus Business Centre Lautrup hoj 1-3 Ballerup DK-2750 Denmark

Tel: 45-4420-9895 Fax: 45-4420-9910

France

Parc d'Activite du Moulin de Massy 43 Rue du Saule Trapu Batiment A - ler Etage 91300 Massy, France Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

Germany

Steinheilstrasse 10 D-85737 Ismaning, Germany Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy

Via Quasimodo, 12 20025 Legnano (MI) Milan, Italy Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands

Waegenburghtplein 4 NL-5152 JR, Drunen, Netherlands Tel: 31-416-690399

Fax: 31-416-690340 United Kingdom

505 Eskdale Road Winnersh Triangle Wokingham Berkshire England

Berkshire, England RG41 5TU Tel: 44-118-921-5869 Fax: 44-118-921-5820

05/28/04

### **Mouser Electronics**

**Authorized Distributor** 

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

#### Microchip:

PIC18F4515-E/P PIC18F2610T-I/SO PIC18F2410T-I/ML PIC18F2410T-I/SO PIC18F4510-E/ML PIC18F4410-E/ML PIC18F4610-E/ML PIC18F2515T-I/SO PIC18LF4510-I/P PIC18LF4610-I/P PIC18F4515-E/PT PIC18F4410T-I/ML PIC18LF2515T-I/SO PIC18F2515-I/SO PIC18LF2410T-I/SO PIC18F2515-I/SP PIC18F4510-I/PT PIC18F4410-I/P PIC18F4510-I/P PIC18F4510-I/ML PIC18F2510-E/ML PIC18F2510-E/SO PIC18LF4510-I/ML PIC18F2510-E/ML PIC18LF4610-I/ML PIC18F2510-I/ML PIC18F4510-I/ML PIC18F4510-I/P PIC18F4510-I/P PIC18F4510-I/ML PIC18F4510-I/P PIC18F4510-I/ML PIC18F4510-I/P PIC18F4510-I/ML PIC18F4510-I/P PIC18F4510-I/ML PIC18F4510-I/ML PIC18F4510-I/P PIC18F4510-I/P PIC18F4515-I/P PIC18F4515-I/P PIC18F4410-I/ML PIC18F2510-I/ML PIC18F2510-I/ML PIC18F4510-I/P PIC18F45