

# PIC18F46J50 Family Data Sheet

28/44-Pin, Low-Power, High-Performance USB Microcontrollers with nanoWatt XLP Technology

© 2009 Microchip Technology Inc.

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION. QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### Trademarks

The Microchip name and logo, the Microchip logo, dsPIC, KEELOQ, KEELOQ logo, MPLAB, PIC, PICmicro, PICSTART, rfPIC and UNI/O are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

FilterLab, Hampshire, HI-TECH C, Linear Active Thermistor, MXDEV, MXLAB, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, dsSPEAK, ECAN, ECONOMONITOR, FanSense, HI-TIDE, In-Circuit Serial Programming, ICSP, Mindi, MiWi, MPASM, MPLAB Certified logo, MPLIB, MPLINK, mTouch, Octopus, Omniscient Code Generation, PICC, PICC-18, PICDEM, PICDEM.net, PICkit, PICtail, PIC<sup>32</sup> logo, REAL ICE, rfLAB, Select Mode, Total Endurance, TSHARC, UniWinDriver, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2009, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.



# QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV ISO/TS 16949:2002

Microchip received ISO/TS-16949:2002 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

# MICROCHIP PIC18F46J50 FAMILY

# 28/44-Pin, Low-Power, High-Performance USB Microcontrollers

# Power Management Features with nanoWatt XLP™ for Extreme Low-Power:

- Deep Sleep mode: CPU off, Peripherals off, Currents Down to 13 nA and 850 nA with RTCC
  - Able to wake-up on external triggers, programmable WDT or RTCC alarm
     Ultra Low-Power Wake-up (ULPWU)
- Sleep mode: CPU off, Peripherals off, SRAM on, Fast Wake-up, Currents Down to 105 nA Typical
- Idle: CPU off, Peripherals on, Currents Down to 2.3 μA Typical
- Run: CPU on, Peripherals on, Currents Down to 6.2 μA Typical
- Timer1 Oscillator w/RTCC: 1 μA, 32 kHz Typical
- Watchdog Timer: 1.3 μA Typical

#### **Special Microcontroller Features:**

- 5.5V Tolerant Inputs (digital only pins)
- · Low-Power, High-Speed CMOS Flash Technology
- · C Compiler Optimized Architecture for Re-Entrant Code
- · Priority Levels for Interrupts
- Self-Programmable under Software Control
- 8 x 8 Single-Cycle Hardware Multiplier
- Extended Watchdog Timer (WDT):
- Programmable period from 4 ms to 131s
- Single-Supply In-Circuit Serial Programming™ (ICSP™) via two pins
- In-Circuit Debug (ICD) with Three Breakpoints via Two Pins
- Operating Voltage Range of 2.0V to 3.6V
- On-Chip 2.5V Regulator
- Flash Program Memory of 10,000 Erase/Write Cycles Minimum and 20-Year Data Retention

### **Universal Serial Bus (USB) Features**

- USB V2.0 Compliant
- Full Speed (12 Mbps) and Low Speed (1.5 Mbps)
- Supports Control, Interrupt, Isochronous and Bulk Transfers
- Supports up to 32 Endpoints (16 bidirectional)
- USB module can use any RAM Location on the Device as USB Endpoint Buffers
- On-Chip USB Transceiver with Crystal-less operation

#### Flexible Oscillator Structure:

- High-Precision Internal Oscillator (±0.15% typ.) for USB
- Two External Clock modes, up to 48 MHz (12 MIPS)
- Internal 31 kHz Oscillator, Internal Oscillators Tunable at 31 kHz and 8 MHz or 48 MHz with PLL
- Secondary Oscillator using Timer1 @ 32 kHz
- Fail-Safe Clock Monitor:
- Allows for safe shutdown if any clock stops
- Two-Speed Oscillator Start-up
- Programmable Reference Clock Output Generator

#### **Peripheral Highlights:**

- · Peripheral Pin Select:
  - Allows independent I/O mapping of many peripherals
  - Continuous hardware integrity checking and safety interlocks prevent unintentional configuration changes
- Hardware Real-Time Clock and Calendar (RTCC):
   Provides clock, calendar and alarm functions
- High-Current Sink/Source 25 mA/25 mA (PORTB and PORTC)
- Four Programmable External Interrupts
- Four Input Change Interrupts
- Two Enhanced Capture/Compare/PWM (ECCP) modules:
  - One, two or four PWM outputs
  - Selectable polarity
  - Programmable dead time
  - Auto-shutdown and auto-restart
  - Pulse steering control
- Two Master Synchronous Serial Port (MSSP) modules Supporting Three-Wire SPI (all four modes) and I<sup>2</sup>C<sup>™</sup> Master and Slave modes
- Full-Duplex Master/Slave SPI DMA Engine
- 8-Bit Parallel Master Port/Enhanced Parallel Slave Port
- Two-Rail Rail Analog Comparators with Input Multiplexing
- 10-Bit, up to 13-Channel Analog-to-Digital (A/D) Converter module:
  - Auto-acquisition capability
  - Conversion available during Sleep
  - Self-calibration
- · High/Low-Voltage Detect module
- Charge Time Measurement Unit (CTMU):
  - Supports capacitive touch sensing for touch screens and capacitive switches
  - Provides a precise resolution time measurement for both flow measurement and simple temperature sensing
- Two Enhanced USART modules:
  - Supports RS-485, RS-232 and LIN/J2602
  - Auto-Wake-up on Start bit
- Auto-Baud Detect


# PIC18F46J50 FAMILY

		(se	()	۵		(			MSSF	2	Ê	s	•				
PIC18F/LF <sup>(1)</sup> Device	Pins	Program Memory (bytes)	SRAM (bytes)	Remappable Pins	Timers 8/16-Bit	ECCP/(PWM)	EUSART		SPI w/DMA	I²C™	10-Bit A/D (ch)	Comparators	Deep Sleep	dSd/dWd	CTMU	RTCC	USB
PIC18F24J50	28	16K	3776	16	2/3	2	2	2	Y	Y	10	2	Y	Ν	Y	Y	Y
PIC18F25J50	28	32K	3776	16	2/3	2	2	2	Y	Υ	10	2	Y	Ν	Y	Y	Y
PIC18F26J50	28	64K	3776	16	2/3	2	2	2	Υ	Υ	10	2	Y	Ν	Y	Y	Y
PIC18F44J50	44	16K	3776	22	2/3	2	2	2	Υ	Υ	13	2	Y	Υ	Y	Y	Y
PIC18F45J50	44	32K	3776	22	2/3	2	2	2	Y	Υ	13	2	Y	Y	Y	Y	Y
PIC18F46J50	44	64K	3776	22	2/3	2	2	2	Y	Y	13	2	Y	Y	Y	Y	Y
PIC18LF24J50	28	16K	3776	16	2/3	2	2	2	Υ	Υ	10	2	Ν	Ν	Y	Y	Y
PIC18LF25J50	28	32K	3776	16	2/3	2	2	2	Y	Υ	10	2	Ν	Ν	Y	Y	Y
PIC18LF26J50	28	64K	3776	16	2/3	2	2	2	Y	Y	10	2	Ν	Ν	Y	Y	Y
PIC18LF44J50	44	16K	3776	22	2/3	2	2	2	Y	Y	13	2	Ν	Y	Y	Y	Y
PIC18LF45J50	44	32K	3776	22	2/3	2	2	2	Υ	Y	13	2	Ν	Y	Y	Y	Y
PIC18LF46J50	44	64K	3776	22	2/3	2	2	2	Y	Y	13	2	Ν	Y	Y	Y	Y


Note 1: See Section 1.3 "Details on Individual Family Devices", Section 3.6 "Deep Sleep Mode" and Section 26.3 "On-Chip Voltage Regulator" for details describing the functional differences between PIC18F and PIC18LF variants in this device family.

# PIC18F46J50 FAMILY

#### **Pin Diagrams**




### **Pin Diagrams (Continued)**



# PIC18F46J50 FAMILY

#### **Pin Diagrams (Continued)**



# **Table of Contents**

1.0	Device Overview	11
2.0	Oscillator Configurations	
3.0	Low-Power Modes	
4.0	Reset	
5.0	Memory Organization	
6.0	Flash Program Memory	
7.0	8 x 8 Hardware Multiplier	107
8.0	Interrupts	109
9.0	I/O Ports	125
10.0	Parallel Master Port (PMP)	163
11.0	Timer0 Module	
12.0	Timer1 Module	193
13.0	Timer2 Module	
14.0	Timer3 Module	
	Timer4 Module	
16.0	Real-Time Clock and Calendar (RTCC)	
17.0		
18.0	Master Synchronous Serial Port (MSSP) Module	
19.0	Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART)	
20.0	10-bit Analog-to-Digital Converter (A/D) Module	
21.0		
22.0	Comparator Module	
23.0	Comparator Voltage Reference Module	
24.0	High/Low Voltage Detect (HLVD)	
25.0		
26.0		
27.0	Instruction Set Summary	
28.0	Development Support	
29.0	Electrical Characteristics	
30.0	Packaging Information	
	endix A: Revision History	
	endix B: Device Differences	
	Microchip Web Site	
	omer Change Notification Service	
	omer Support	
	ler Response	
Prod	uct Identification System	553

# TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### Most Current Data Sheet

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### Errata

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

# PIC18F46J50 FAMILY

NOTES:

# 1.0 DEVICE OVERVIEW

This document contains device-specific information for the following devices:

- PIC18F24J50 PIC18LF24J50
- PIC18F25J50 PIC18LF25J50
- PIC18F26J50
   PIC18LF26J50
- PIC18F44J50 PIC18LF44J50
- PIC18F45J50 PIC18LF45J50
- PIC18F46J50 PIC18LF46J50
- This family introduces a new line of low-voltage Universal Serial Bus (USB) microcontrollers with the main traditional advantage of all PIC18 microcontrollers,

namely, high computational performance and a rich feature set at an extremely competitive price point. These features make the PIC18F46J50 Family a logical choice for many high-performance applications, where cost is a primary consideration.

### 1.1 Core Features

#### 1.1.1 nanoWatt TECHNOLOGY

All of the devices in the PIC18F46J50 Family incorporate a range of features that can significantly reduce power consumption during operation. Key features are:

- Alternate Run Modes: By clocking the controller from the Timer1 source or the internal RC oscillator, power consumption during code execution can be reduced by as much as 90%.
- Multiple Idle Modes: The controller can also run with its CPU core disabled but the peripherals still active. In these states, power consumption can be reduced even further, to as little as 4% of normal operational requirements.
- On-the-Fly Mode Switching: The power-managed modes are invoked by user code during operation, allowing the users to incorporate power-saving ideas into their application's software design.

### 1.1.2 UNIVERSAL SERIAL BUS (USB)

Devices in the PIC18F46J50 Family incorporate a fully-featured USB communications module with a built-in transceiver that is compliant with the USB Specification Revision 2.0. The module supports both low-speed and full-speed communication for all supported data transfer types.

# 1.1.3 OSCILLATOR OPTIONS AND FEATURES

All of the devices in the PIC18F46J50 Family offer five different oscillator options, allowing users a range of choices in developing application hardware. These include:

- Two Crystal modes, using crystals or ceramic resonators.
- Two External Clock modes, offering the option of a divide-by-4 clock output.
- An internal oscillator block, which provides an 8 MHz clock and an INTRC source (approximately 31 kHz, stable over temperature and VDD), as well as a range of six user-selectable clock frequencies, between 125 kHz to 4 MHz, for a total of eight clock frequencies. This option frees an oscillator pin for use as an additional general purpose I/O.
- A Phase Lock Loop (PLL) frequency multiplier, available to the high-speed crystal, and external and internal oscillators, providing a clock speed up to 48 MHz.
- Dual clock operation, allowing the USB module to run from a high-frequency oscillator while the rest of the microcontroller is clocked at a different frequency.

The internal oscillator block provides a stable reference source that gives the PIC18F46J50 Family additional features for robust operation:

- Fail-Safe Clock Monitor: This option constantly monitors the main clock source against a reference signal provided by the internal oscillator. If a clock failure occurs, the controller is switched to the internal oscillator, allowing for continued low-speed operation or a safe application shutdown.
- **Two-Speed Start-up:** This option allows the internal oscillator to serve as the clock source from Power-on Reset (POR), or wake-up from Sleep mode, until the primary clock source is available.

### 1.1.4 EXPANDED MEMORY

The PIC18F46J50 Family provides ample room for application code, from 16 Kbytes to 64 Kbytes of code space. The Flash cells for program memory are rated to last in excess of 10000 erase/write cycles. Data retention without refresh is conservatively estimated to be greater than 20 years.

The Flash program memory is readable and writable during normal operation. The PIC18F46J50 Family also provides plenty of room for dynamic application data with up to 3.8 Kbytes of data RAM.

### 1.1.5 EXTENDED INSTRUCTION SET

The PIC18F46J50 Family implements the optional extension to the PIC18 instruction set, adding eight new instructions and an Indexed Addressing mode. Enabled as a device configuration option, the extension has been specifically designed to optimize re-entrant application code originally developed in high-level languages, such as C.

#### 1.1.6 EASY MIGRATION

Regardless of the memory size, all devices share the same rich set of peripherals, allowing for a smooth migration path as applications grow and evolve.

The consistent pinout scheme used throughout the entire family also aids in migrating to the next larger device.

The PIC18F46J50 Family is also pin compatible with other PIC18 families, such as the PIC18F4550, PIC18F2450 and PIC18F45J10. This allows a new dimension to the evolution of applications, allowing developers to select different price points within Microchip's PIC18 portfolio, while maintaining the same feature set.

# 1.2 Other Special Features

- Communications: The PIC18F46J50 Family incorporates a range of serial and parallel communication peripherals, including a fully featured USB communications module that is compliant with the USB Specification Revision 2.0. This device also includes two independent Enhanced USARTs and two Master Synchronous Serial Port (MSSP) modules, capable of both Serial Peripheral Interface (SPI) and I<sup>2</sup>C<sup>™</sup> (Master and Slave) modes of operation. The device also has a parallel port and can be configured to serve as either a Parallel Master Port (PMP) or as a Parallel Slave Port (PSP).
- ECCP Modules: All devices in the family incorporate three Enhanced Capture/Compare/PWM (ECCP) modules to maximize flexibility in control applications. Up to four different time bases may be used to perform several different operations at once. Each of the ECCPs offers up to four PWM outputs, allowing for a total of eight PWMs. The ECCPs also offer many beneficial features, including polarity selection, programmable dead time, auto-shutdown and restart and Half-Bridge and Full-Bridge Output modes.

- **10-Bit A/D Converter:** This module incorporates programmable acquisition time, allowing for a channel to be selected and a conversion to be initiated without waiting for a sampling period, and thus, reducing code overhead.
- Extended Watchdog Timer (WDT): This enhanced version incorporates a 16-bit prescaler, allowing an extended time-out range that is stable across operating voltage and temperature. See Section 29.0 "Electrical Characteristics" for time-out periods.

#### 1.3 Details on Individual Family Devices

Devices in the PIC18F46J50 Family are available in 28-pin and 44-pin packages. Block diagrams for the two groups are shown in Figure 1-1 and Figure 1-2. The devices are differentiated from each other in two ways:

- Flash program memory (three sizes: 16 Kbytes for the PIC18FX4J50, 32 Kbytes for PIC18FX5J50 devices and 64 Kbytes for PIC18FX6J50)
- I/O ports (three bidirectional ports on 28-pin devices, five bidirectional ports on 44-pin devices)

All other features for devices in this family are identical. These are summarized in Table 1-1 and Table 1-2.

The pinouts for the PIC18F2XJ50 devices are listed in Table 1-3. The pinouts for the PIC18F4XJ50 devices are shown in Table 1-4.

The PIC18F46J50 Family of devices provides an on-chip voltage regulator to supply the correct voltage levels to the core. Parts designated with an "F" part number (such as PIC18F46J50) have the voltage regulator enabled.

These parts can run from 2.15V-3.6V on VDD, but should have the VDDCORE pin connected to VSs through a low-ESR capacitor. Parts designated with an "LF" part number (such as PIC18**LF**46J50) do not enable the voltage regulator. For "LF" parts, an external supply of 2.0V-2.7V has to be supplied to the VDDCORE pin while 2.0V-3.6V can be supplied to VDD (VDDCORE should never exceed VDD).

For more details about the internal voltage regulator, see **Section 26.3 "On-Chip Voltage Regulator"**.

Features	PIC18F24J50	PIC18F25J50	PIC18F26J50				
Operating Frequency	DC – 48 MHz	DC – 48 MHz	DC – 48 MHz				
Program Memory (Bytes)	16K	32K	64K				
Program Memory (Instructions)	8,192	16,384	32,768				
Data Memory (Bytes)	3.8K	3.8K	3.8K				
Interrupt Sources		30					
I/O Ports	Ports A, B, C						
Timers	5						
Enhanced Capture/Compare/PWM Modules	2						
Serial Communications	MSSP	(2), Enhanced USART (2	2), USB				
Parallel Communications (PMP/PSP)		No					
10-Bit Analog-to-Digital Module		10 Input Channels					
Resets (and Delays)	POR, BOR, RESET Instruction, Stack Full, Stack Underflow, MCLR, WDT (PWRT, OST)						
Instruction Set	75 Instructions, 83 with Extended Instruction Set Enabled						
Packages	28-Pin QFN, SOIC, SSOP and SPDIP (300 mil)						


### TABLE 1-1:DEVICE FEATURES FOR THE PIC18F2XJ50 (28-PIN DEVICES)


#### TABLE 1-2: DEVICE FEATURES FOR THE PIC18F4XJ50 (44-PIN DEVICES)

Features	PIC18F44J50	PIC18F45J50	PIC18F46J50			
Operating Frequency	DC – 48 MHz	DC – 48 MHz	DC – 48 MHz			
Program Memory (Bytes)	16K	32K	64K			
Program Memory (Instructions)	8,192	16,384	32,768			
Data Memory (Bytes)	3.8K	3.8K	3.8K			
Interrupt Sources		30				
I/O Ports	Ports A, B, C, D, E					
Timers	5					
Enhanced Capture/Compare/PWM Modules	2					
Serial Communications	MSSP	(2), Enhanced USART (2	), USB			
Parallel Communications (PMP/PSP)		Yes				
10-Bit Analog-to-Digital Module		13 Input Channels				
Resets (and Delays)	POR, BOR, RESET Instruction, Stack Full, Stack Underflow, MCLR, WDT (PWRT, OST)					
Instruction Set	75 Instructions, 83 with Extended Instruction Set Enabled					
Packages	44-Pin QFN and TQFP					

# PIC18F46J50 FAMILY

FIGURE 1-1: PIC18F2XJ50 (28-PIN) BLOCK DIAGRAM





	Pin N	umber						
Pin Name	28-SPDIP/ SSOP/ SOIC	28-QFN	Pin Type	Buffer Type	Description			
MCLR	1	26	I	ST	Master Clear (Reset) input. This pin is an active-low Reset to the device.			
OSC1/CLKI/RA7 OSC1	9	6	I	ST	Oscillator crystal or external clock input. Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; CMOS otherwise. Main oscillator input connection.			
CLKI			I	CMOS	External clock source input; always associated with pin function OSC1 (see related OSC1/CLK pins).			
RA7 <sup>(1)</sup>			I/O	TTL	Digital I/O.			
OSC2/CLKO/RA6 OSC2	10	7	0	_	Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or			
			•		resonator in Crystal Oscillator mode.			
CLKO			0	—	Main oscillator feedback output connection.			
					In RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes			
RA6 <sup>(1)</sup>			I/O	TTL	the instruction cycle rate. Digital I/O.			
Legend: TTL = TTL compa					MOS = CMOS compatible input or output			
ST = Schmitt Trig I = Input	Jger input Wi		eveis	Ar O	nalog = Analog input = Output			
P = Power DIG = Digital outp	ut			Ö	•			
DIG = Digital output I-C I = Open-Drain, I-C specific								

#### TABLE 1-3:PIC18F2XJ50 PINOUT I/O DESCRIPTIONS

	Pin Number				
Pin Name	28-SPDIP/ SSOP/ SOIC	28-QFN	Pin Type	Buffer Type	Description
					PORTA is a bidirectional I/O port.
RA0/AN0/C1INA/ULPWU/RP0 RA0 AN0 C1INA ULPWU RP0	2	27	I/O I I I/O	DIG Analog Analog Analog DIG	Digital I/O. Analog input 0. Comparator 1 input A. Ultra low-power wake-up input. Remappable peripheral pin 0 input/output.
RA1/AN1/C2INA/RP1 RA1 AN1 C2INA RP1	3	28	 0    /0	DIG Analog Analog DIG	Digital I/O. Analog input 1. Comparator 2 input A. Remappable peripheral pin 1 input/output.
RA2/AN2/VREF-/CVREF/C2INB RA2 AN2 VREF- CVREF C2INB	4	1	I/O I O I I	DIG Analog Analog Analog Analog	Digital I/O. Analog input 2. A/D reference voltage (low) input. Comparator reference voltage output. Comparator 2 input B.
RA3/AN3/VREF+/C1INB RA3 AN3 VREF+ C1INB	5	2	I/O I I	DIG Analog Analog Analog	Digital I/O. Analog input 3. A/D reference voltage (high) input. Comparator 1 input B.
RA5/AN4/SS1/HLVDIN/ RCV/RP2 RA5 <u>AN4</u> SS1 HLVDIN RCV RP2	7	4	I/O I I I I/O	DIG Analog TTL Analog Analog DIG	Digital I/O. Analog input 4. SPI slave select input. Low-voltage detect input. External USB transceiver RCV input. Remappable peripheral pin 2 input/output.
RA6 <sup>(1)</sup> RA7 <sup>(1)</sup>					See the OSC2/CLKO/RA6 pin. See the OSC1/CLKI/RA7 pin.
Legend: TTL = TTL compati ST = Schmitt Trigg I = Input P = Power DIG = Digital outpu	ger input wit			Ar O OI I <sup>2</sup> (	MOS = CMOS compatible input or output nalog = Analog input = Output

	Pin Nu	umber					
Pin Name	28-SPDIP/ SSOP/ SOIC	28-QFN	Pin Type	Buffer Type	Description		
					PORTB is a bidirectional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs.		
RB0/AN12/INT0/RP3 RB0 AN12 INT0 RP3	21	18	I/O I I I/O	DIG Analog ST DIG	Digital I/O. Analog input 12. External interrupt 0. Remappable peripheral pin 3 input/output.		
RB1/AN10/RTCC/RP4 RB1 AN10 RTCC RP4	22	19	I/O I O I/O	DIG Analog DIG DIG	Digital I/O. Analog input 10. Asynchronous serial transmit data output. Remappable peripheral pin 4 input/output.		
RB2/AN8/CTEDG1/VMO/ REFO/RP5 RB2 AN8 CTEDG1 VMO REFO RP5	23	20	I/O I I O I/O	DIG Analog ST DIG DIG DIG DIG	Digital I/O. Analog input 8. CTMU edge 1 input. External USB transceiver D- data output. Reference output clock. Remappable peripheral pin 5 input/output.		
RB3/AN9/CTEDG2/VPO/RP6 RB3 AN9 CTEDG2 VPO RP6	24	21	I/O I I/O O I	DIG Analog ST DIG DIG	Digital I/O.		
Legend:       TTL = TTL compatible input       CMOS       = CMOS compatible input or output         ST = Schmitt Trigger input with CMOS levels       Analog       = Analog input         I = Input       O       = Output         P = Power       OD       = Open-Drain (no P diode to VDD)         DIG = Digital output       If CS       = Open-Drain, I <sup>2</sup> C specific         Note 1:       RA7 and RA6 will be disabled if OSC1 and OSC2 are used for the clock function.							

	Pin Nu	umber			
Pin Name	28-SPDIP/ SSOP/ SOIC	28-QFN	Pin Type	Buffer Type	Description
					PORTB (continued)
RB4/KBI0/SCK1/SCL1/RP7 RB4 KBI0 SCK1 SCL1 RP7	25	22	I/O I I/O I/O I/O	DIG TTL DIG I <sup>2</sup> C DIG	Digital I/O. Interrupt-on-change pin. Synchronous serial clock input/output. I <sup>2</sup> C clock input/output. Remappable peripheral pin 7 input/output.
RB5/KBI1/SDI1/SDA1/RP8 RB5 KBI1 SDI1 SDA1 RP8	26	23	I/O I/O I I/O I/O	DIG DIG ST I <sup>2</sup> C DIG	Digital I/O. Parallel Master Port address. SPI data input. I <sup>2</sup> C™ data input/output. Remappable peripheral pin 8 input/output.
RB6/KBI2/PGC/RP9 RB6 KBI2 PGC RP9	27	24	I/O I I I/O	DIG TTL ST DIG	Digital I/O. Interrupt-on-change pin. ICSP™ clock input. Remappable peripheral pin 9 input/output.
RB7/KBI3/PGD/RP10 RB7 KBI3 PGD	28	25	I/O I I/O	DIG TTL ST	Digital I/O. Interrupt-on-change pin. In-Circuit Debugger and ICSP programming data pin.
RP10			I/O	DIG	Remappable peripheral pin 10 input/output.
Legend: TTL = TTL compat ST = Schmitt Trig I = Input P = Power DIG = Digital output Note 1: RA7 and RA6 will b	ger input wi			Ar O OI I <sup>2</sup> (	MOS = CMOS compatible input or output nalog = Analog input = Output

TABLE 1-3: PIC18F2XJ50 PINOUT I/O DESCRIPTIONS	(CONTINUED)
------------------------------------------------	-------------

	Pin Nu						
Pin Name	28-SPDIP/ SSOP/ SOIC	28-QFN	Pin Type	Buffer Type	Description		
					PORTC is a bidirectional I/O port.		
RC0/T1OSO/T1CKI/RP11 RC0 T1OSO T1CKI RP11	11	8	I/O O I I/O	ST Analog ST DIG	Digital I/O. Timer1 oscillator output. Timer1 external digital clock input. Remappable peripheral pin 11 input/output.		
RC1/T1OSI/UOE/RP12 RC1 T1OSI UOE RP12	12	9	I/O I O I/O	ST Analog DIG DIG	Digital I/O. Timer1 oscillator input. External USB transceiver NOE output. Remappable peripheral pin 12 input/output.		
RC2/AN11/CTPLS/RP13 RC2 AN11 CTPLS RP13	13	10	I/O I O I/O	ST Analog DIG DIG	Digital I/O. Analog input 11. CTMU pulse generator output. Remappable peripheral pin 13 input/output.		
RC4/D-/VM RC4 D- VM	15	12	  /O 	TTL — TTL	Digital I. USB bus minus line input/output. External USB transceiver FM input.		
RC5/D+/VP RC5 D+ VP	16	13	  /O 	TTL DIG TTL	Digital I. USB bus plus line input/output. External USB transceiver VP input.		
RC6/TX1/CK1/RP17 RC6 TX1 CK1	17	14	I/O O I/O	ST DIG ST	Digital I/O. EUSART1 asynchronous transmit. EUSART1 synchronous clock (see related RX1/DT1).		
RP17 RC7/RX1/DT1/SDO1/RP18 RC7 RX1 DT1 SDO1 RP18	18	15	I/O I/O I/O I/O	DIG ST ST DIG DIG	Remappable peripheral pin 17 input/output. Digital I/O. Asynchronous serial receive data input. Synchronous serial data output/input. SPI data output. Remappable peripheral pin 18 input/output.		
Legend:TTL = TTL compatible inputICDIGRemappable peripheral pin to input output.ST = Schmitt Trigger input with CMOS levelsCMOS = CMOS compatible input or outputI = InputO= OutputP = PowerOD= OutputDIG = Digital output $I^2C$ TM= Open-Drain, I^2C specificNote 1:PA5 will be disabled if OSC1 and OSC2 are used for the clock function.							

	Pin Nu	umber			
Pin Name	28-SPDIP/ SSOP/ SOIC	28-QFN	Pin Type	Buffer Type	Description
Vss1	8	5	Р	-	Ground reference for logic and I/O pins.
Vss2	19	16	—	—	
Vdd	20	17	Р	_	Positive supply for peripheral digital logic and I/O pins.
VDDCORE/VCAP	6	3	-	—	Core logic power or external filter capacitor connection.
VDDCORE			Р	—	Positive supply for microcontroller core logic (regulator disabled).
VCAP			Р	-	External filter capacitor connection (regulator enabled).
VUSB	14	11	Р	_	USB voltage input pin.
Legend: TTL = TTL compat ST = Schmitt Trig I = Input P = Power DIG = Digital output	ger input wi	th CMOS I	evels	Ar O Ol	MOS = CMOS compatible input or output nalog = Analog input = Output D = Open-Drain (no P diode to VDD) C <sup>™</sup> = Open-Drain, I <sup>2</sup> C specific

	Pin N	Pin Number		Buffer	
Pin Name	44- QFN	44- TQFP	Pin Type	витег Туре	Description
MCLR	18	18	I	ST	Master Clear (Reset) input; this is an active-low Reset to the device.
OSC1/CLKI/RA7 OSC1	32	30	I	ST	Oscillator crystal or external clock input. Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; otherwise CMOS. Main oscillator input connection.
CLKI			I	CMOS	
RA7 <sup>(1)</sup>			I/O	TTL	Digital I/O.
OSC2/CLKO/RA6 OSC2	33	31	ο	_	Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.
CLKO			0	_	Main oscillator feedback output connection in RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes the instruction cycle rate.
RA6 <sup>(1)</sup>			I/O	TTL	Digital I/O.
Legend: TTL = TTL compatible i ST = Schmitt Trigger i I = Input P = Power DIG = Digital output	•	n CMOS	levels	A () ()	CMOS= CMOS compatible input or outputAnalog= Analog inputD= OutputDD= Open-Drain (no P diode to VDD) $^2$ CTM= Open-Drain, I^2C specific

# TABLE 1-4: PIC18F4XJ50 PINOUT I/O DESCRIPTIONS

	Pin Number		Pin Type	Buffer Type	Description	
Pin Name	44- 44- QFN TQFP					
					PORTA is a bidirectional I/O port.	
RA0/AN0/C1INA/ULPWU/PMA6/	19	19				
RP0						
RA0			I/O	DIG	Digital I/O.	
ANO				Analog	Analog input 0.	
C1INA				Analog		
ULPWU				Analog		
PMA6			I/O	DIG	Parallel Master Port digital I/O.	
RP0			I/O	DIG	Remappable peripheral pin 0 input/output.	
RA1/AN1/C2INA/PMA7/RP1	20	20				
RA1			I	DIG	Digital I/O.	
AN1			0	Analog		
C2INA			I	Analog		
PMA7			I/O	DIG	Parallel Master Port digital I/O.	
RP1			I/O	DIG	Remappable peripheral pin 1 input/output.	
RA2/AN2/VREF-/CVREF/C2INB	21	21				
RA2			I/O	DIG	Digital I/O.	
AN2			I	Analog		
VREF-			0	Analog	A/D reference voltage (low) input.	
CVREF			I	Analog	Comparator reference voltage output.	
C2INB			I	Analog	Comparator 2 input B.	
RA3/AN3/VREF+/C1INB	22	22				
RA3			I/O	DIG	Digital I/O.	
AN3			I	Analog	•	
VREF+			I	Analog	A/D reference voltage (high) input.	
C1INB			Ι	Analog	Comparator 1 input B.	
RA5/AN4/SS1/HLVDIN/RCV/RP2	24	24				
RA5	27	2 <del>4</del>	I/O	DIG	Digital I/O.	
AN4			"O	Analog	•	
SS1			i i	TTL	SPI slave select input.	
HLVDIN			·	Analog	•	
RCV			Ì	Analog	External USB transceiver RCV input.	
RP2			I/O	DIG	Remappable peripheral pin 2 input/output.	
RA6 <sup>(1)</sup>					See the OSC2/CLKO/RA6 pin.	
RA0 <sup>(1)</sup>					See the OSC2/CLKO/RA6 pin.	
				L		
Legend: TTL = TTL compatible in ST = Schmitt Trigger in			lovala		CMOS = CMOS compatible input or output	
si = scrimit inggerir I = Input	iput with		ieveis		Analog = Analog input D = Output	
P = Power					DD = Open-Drain (no P diode to VDD)	
DIG = Digital output					$^{2}C^{TM}$ = Open-Drain, I <sup>2</sup> C specific	
- ·	obled if	0801 -			ised for the clock function.	

	Pin N	umber	Din	Din Duffer	
Pin Name	44- QFN	44- TQFP	Pin Type	Buffer Type	Description
					PORTB is a bidirectional I/O port. PORTB can be software programmed for internal weak pull-ups on all inputs.
RB0/AN12/INT0/RP3 RB0 AN12 INT0 RP3	9	8	I/O I I I/O	DIG Analog ST DIG	Digital I/O. Analog input 12. External interrupt 0. Remappable peripheral pin 3 input/output.
RB1/AN10/PMBE/RTCC/RP4 RB1 AN10 PMBE RTCC RP4	10	9	I/O I O I/O	DIG Analog DIG DIG DIG	Digital I/O. Analog input 10. Parallel Master Port byte enable. Asynchronous serial transmit data output. Remappable peripheral pin 4 input/output.
RB2/AN8/CTEDG1/PMA3/VMO/ REFO/RP5 RB2 AN8 CTEDG1 PMA3 VMO REFO RP5	11	10	I/O I I O O I/O	DIG Analog ST DIG DIG DIG DIG DIG	Digital I/O. Analog input 8. CTMU edge 1 input. Parallel Master Port address. External USB transceiver D- data output. Reference output clock. Remappable peripheral pin 5 input/output.
RB3/AN9/CTEDG2/PMA2/VPO/ RP6 RB3 AN9 CTEDG2 PMA2 VPO RP6	12	11	I/O I I O I/O	DIG Analog ST DIG DIG DIG	Digital I/O. Analog input 9. CTMU edge 2 input. Parallel Master Port address. External USB transceiver D+ data output. Remappable peripheral pin 6 input/output.
Legend: TTL = TTL compatible in ST = Schmitt Trigger in I = Input P = Power DIG = Digital output Note 1: RA7 and RA6 will be dis	put with			A C I	CMOS = CMOS compatible input or output Analog = Analog input D = Output DD = Open-Drain (no P diode to VDD) <sup>2</sup> C™ = Open-Drain, I <sup>2</sup> C specific used for the clock function.

	Pin Number		Pin	Buffer		
Pin Name	44- QFN	44- TQFP	Туре	Туре	Description	
					PORTB (continued)	
RB4/PMA1/KBI0/SCK1/SCL1/RP7	14	14				
RB4			I/O	DIG	Digital I/O.	
PMA1			I/O	DIG	Parallel Master Port address.	
KBI0			1	TTL	Interrupt-on-change pin.	
SCK1			I/O	DIG	Synchronous serial clock input/output.	
SCL1			I/O	l <sup>2</sup> C	I <sup>2</sup> C clock input/output.	
RP7			I/O	DIG	Remappable peripheral pin 7 input/output.	
RB5/PMA0/KBI1/SDI1/SDA1/RP8	15	15				
RB5	10	10	I/O	DIG	Digital I/O.	
PMA0			1/O	DIG	Parallel Master Port address.	
KBI1				TTL	Interrupt-on-change pin.	
SDI1			i	ST	SPI data input.	
SDA1			I/O	l <sup>2</sup> C	I <sup>2</sup> C™ data input/output.	
RP8			I/O	DIG	Remappable peripheral pin 8 input/output.	
RB6/KBI2/PGC/RP9	16	16				
RB6		10	I/O	DIG	Digital I/O.	
KBI2			I	TTL	Interrupt-on-change pin.	
PGC			I	ST	ICSP™ clock input.	
RP9			I/O	DIG	Remappable peripheral pin 9 input/output.	
RB7/KBI3/PGD/RP10	17	17				
RB7		17	I/O	DIG	Digital I/O.	
KBI3			<i>"</i> 0	TTL	Interrupt-on-change pin.	
PGD			I/O	ST	In-Circuit Debugger and ICSP programming	
1.02				0.	data pin.	
RP10			I/O	DIG	Remappable peripheral pin 10 input/output.	
Legend: TTL = TTL compatible in		•		(	CMOS = CMOS compatible input or output	
ST = Schmitt Trigger ir	nput with	n CMOS	levels		Analog = Analog input	
I = Input					O = Output	
P = Power					OD = Open-Drain (no P diode to VDD)	
DIG = Digital output				I	l <sup>2</sup> C™ = Open-Drain, l <sup>2</sup> C specific	

	Pin N	umber	<b>D!</b>	Duff-	
Pin Name	44- QFN	44- TQFP	Pin Type	Buffer Type	Description
					PORTC is a bidirectional I/O port.
RC0/T1OSO/T1CKI/RP11 RC0 T1OSO T1CKI RP11	34	32	I/O O I I/O	ST Analog ST DIG	Digital I/O. Timer1 oscillator output. Timer1/Timer3 external clock input. Remappable peripheral pin 11 input/output.
RC1/T1OSI/UOE/RP12 RC1 T1OSI UOE RP12	35	35	I/O I O I/O	ST Analog DIG DIG	Digital I/O. Timer1 oscillator input. External USB transceiver NOE output. Remappable peripheral pin 12 input/output.
RC2/AN11/CTPLS/RP13 RC2 AN11 CTPLS RP13	36	36	I/O I 0 I/O	ST Analog DIG DIG	Digital I/O. Analog input 11. CTMU pulse generator output. Remappable peripheral pin 13 input/output.
RC4/D-/VM RC4 D- VM	42	42	 0 	TTL — TTL	Digital I. USB bus minus line input/output. External USB transceiver FM input.
RC5/D+/VP RC5 D+ VP	43	43	  /O 	TTL DIG TTL	Digital I. USB bus plus line input/output. External USB transceiver VP input.
RC6/PMA5/TX1/CK1/RP17 RC6 PMA5 TX1 CK1 RP17	44	44	I/O I/O I/O I/O	ST DIG DIG ST DIG	Digital I/O. Parallel Master Port address. EUSART1 asynchronous transmit. EUSART1 synchronous clock (see related RX1/DT1). Remappable peripheral pin 17 input/output.
RC7/PMA4/RX1/DT1/SDO1/RP18 RC7 PMA4 RX1	1	1	I/O I/O I	ST DIG ST	EUSART1 asynchronous receive. Parallel Master Port address. EUSART1 synchronous data (see related
DT1 SDO1 RP18			I/O O I/O	ST DIG DIG	TX1/CK1). Synchronous serial data output/input. SPI data output. Remappable peripheral pin 18 input/output.
Legend: TTL = TTL compatible in ST = Schmitt Trigger in I = Input P = Power DIG = Digital output Note 1: RA7 and RA6 will be disa	put with			A C I	CMOS = CMOS compatible input or output  Analog = Analog input

	Pin N	Pin Number 44- QFN TQFP		Buffer	
Pin Name				Туре	Description
					PORTD is a bidirectional I/O port.
RD0/PMD0/SCL2 RD0 PMD0 SCL2	38	38	1/0 1/0 1/0	ST DIG DIG	Digital I/O. Parallel Master Port data. I <sup>2</sup> C™ data input/output.
RD1/PMD1/SDA2 RD1 PMD1 SDA2	39	39	1/0 1/0 1/0	ST DIG DIG	Digital I/O. Parallel Master Port data. I <sup>2</sup> C data input/output.
RD2/PMD2/RP19 RD2 PMD2 RP19	40	40	1/0 1/0 1/0	ST DIG DIG	Digital I/O. Parallel Master Port data. Remappable peripheral pin 19 input/output.
RD3/PMD3/RP20 RD3 PMD3 RP20	41	41	1/0 1/0 1/0	ST DIG DIG	Digital I/O. Parallel Master Port data. Remappable peripheral pin 20 input/output.
RD4/PMD4/RP21 RD4 PMD4 RP21	2	2	I/O I/O I/O	ST DIG DIG	Digital I/O. Parallel Master Port data. Remappable peripheral pin 21 input/output.
RD5/PMD5/RP22 RD5 PMD5 RP22	3	3	I/O I/O I/O	ST DIG DIG	Digital I/O. Parallel Master Port data. Remappable peripheral pin 22 input/output.
RD6/PMD6/RP23 RD6 PMD6 RP23	4	4	1/0 1/0 1/0	ST DIG DIG	Digital I/O. Parallel Master Port data. Remappable peripheral pin 23 input/output.
RD7/PMD7/RP24 RD7 PMD7 RP24	5	5	I/O I/O I/O	ST DIG DIG	Digital I/O. Parallel Master Port data. Remappable peripheral pin 24 input/output.
Legend: TTL = TTL compatibl ST = Schmitt Trigge I = Input P = Power DIG = Digital output Note 1: BA7 and BA6 will be	er input with			A C I	CMOS = CMOS compatible input or output Analog = Analog input D = Output DD = Open-Drain (no P diode to VDD) $^{2}$ C <sup>™</sup> = Open-Drain, 1 <sup>2</sup> C specific

Note 1: RA7 and RA6 will be disabled if OSC1 and OSC2 are used for the clock function.

	Pin Number		Pin	Buffer	
Pin Name	44- QFN	44- TQFP	Ріп Туре	Туре	Description
					PORTE is a bidirectional I/O port.
RE0/AN5/PMRD RE0 AN5 PMRD	25	25	I/O I I/O	ST Analog DIG	Digital I/O. Analog input 5. Parallel Master Port input/output.
RE1/AN6/PMWR RE1 AN6 PMWR	26	26	I/O I I/O	ST Analog DIG	Digital I/O. Analog input 6. Parallel Master Port write strobe.
RE2/AN7/PMCS RE2 AN7 PMCS	27	27	I/O I O	ST Analog —	Digital I/O. Analog input 7. Parallel Master Port byte enable.
Vss1	6	6	Р	_	Ground reference for logic and I/O pins.
Vss2	31	29	—	—	
AVss1	30		Р	—	Ground reference for analog modules.
VDD1	8	7	Р	—	Positive supply for peripheral digital logic and
Vdd2	29	28	Р	—	I/O pins.
VDDCORE/VCAP	23	23			Core logic power or external filter capacitor connection.
VDDCORE			Р	-	Positive supply for microcontroller core logic (regulator disabled).
VCAP			Ρ	_	External filter capacitor connection (regulator enabled).
AVDD1	7		Р	—	Positive supply for analog modules.
AVDD2	28	—	—	-	Positive supply for analog modules.
Vusb	37	37	Р		USB voltage input pin.
Legend: TTL = TTL compatible in ST = Schmitt Trigger in I = Input P = Power DIG = Digital output Note 1: RA7 and RA6 will be dis	put with			4 ( ( 	CMOS = CMOS compatible input or output Analog = Analog input D = Output D = Open-Drain (no P diode to VDD) <sup>2</sup> C <sup>™</sup> = Open-Drain, 1 <sup>2</sup> C specific

# 2.0 OSCILLATOR CONFIGURATIONS

### 2.1 Overview

Devices in the PIC18F46J50 Family incorporate a different oscillator and microcontroller clock system than general purpose PIC18F devices. Besides the USB module, with its unique requirements for a stable clock source, make it necessary to provide a separate clock source that is compliant with both USB low-speed and full-speed specifications.

The PIC18F46J50 Family has additional prescalers and postscalers, which have been added to accommodate a wide range of oscillator frequencies. Figure 2-1 provides an overview of the oscillator structure.

Other oscillator features used in PIC18 enhanced microcontrollers, such as the internal oscillator block and clock switching, remain the same. They are discussed later in this chapter.

#### 2.1.1 OSCILLATOR CONTROL

The operation of the oscillator in PIC18F46J50 Family devices is controlled through three Configuration registers and two control registers. Configuration registers, CONFIG1L, CONFIG1H and CONFIG2L, select the oscillator mode, PLL prescaler and CPU divider options. As Configuration bits, these are set when the device is programmed and left in that configuration until the device is reprogrammed.

The OSCCON register (Register 2-2) selects the Active Clock mode; it is primarily used in controlling clock switching in power-managed modes. Its use is discussed in **Section 2.5.1** "Oscillator Control **Register**".

The OSCTUNE register (Register 2-1) is used to trim the INTOSC frequency source, and select the low-frequency clock source that drives several special features. The OSCTUNE register is also used to activate or disable the Phase Locked Loop (PLL). Its use is described in **Section 2.2.5.1** "OSCTUNE Register".

# 2.2 Oscillator Types

PIC18F46J50 Family devices can be operated in eight distinct oscillator modes. Users can program the FOSC<2:0> Configuration bits to select one of the modes listed in Table 2-1. For oscillator modes which produce a clock output (CLKO) on pin RA6, the output frequency will be one fourth of the peripheral clock frequency. The clock output stops when in Sleep mode, but will continue during Idle mode (see Figure 2-1).


#### TABLE 2-1: OSCILLATOR MODES

TABLE 2-1:	OSCILLATOR MODES
Mode	Description
ECPLL	External Clock Input mode, the PLL can be enabled or disabled in software, CLKO on RA6, apply external clock signal to RA7.
EC	External Clock Input mode, the PLL is always disabled, CLKO on RA6, apply external clock signal to RA7.
HSPLL	High-Speed Crystal/Resonator mode, PLL can be enabled or disabled in software, crystal/resonator connected between RA6 and RA7.
HS	High-Speed Crystal/Resonator mode, PLL always disabled, crystal/resonator connected between RA6 and RA7.
INTOSCPLLO	Internal Oscillator mode, PLL can be enabled or disabled in software, CLKO on RA6, port function on RA7, the internal oscillator block is used to derive both the primary clock source and the postscaled internal clock.
INTOSCPLL	Internal Oscillator mode, PLL can be enabled or disabled in software, port function on RA6 and RA7, the internal oscillator block is used to derive both the primary clock source and the postscaled internal clock.
INTOSCO	Internal Oscillator mode, PLL is always disabled, CLKO on RA6, port function on RA7, the output of the INTOSC postscaler serves as both the postscaled internal clock and the primary clock source.
INTOSC	Internal Oscillator mode, PLL is always disabled, port function on RA6 and RA7, the output of the INTOSC postscaler serves as both the postscaled internal clock and the primary clock source.

# 2.2.1 OSCILLATOR MODES AND USB OPERATION

Because of the unique requirements of the USB module, a different approach to clock operation is necessary. In order to use the USB module, a fixed 6 MHz or 48 MHz clock must be internally provided to the USB module for operation in either Low-Speed or Full-Speed mode, respectively. The microcontroller core need not be clocked at the same frequency as the USB module. A network of MUXes, clock dividers and a fixed 96 MHz output PLL have been provided, which can be used to derive various microcontroller core and USB module frequencies. Figure 2-1 helps in understanding the oscillator structure of the PIC18F46J50 Family of devices.





- **Note 1:** The PLL requires a 4 MHz input and it produces a 96 MHz output. The PLL will not be available until the PLLEN bit in the OSCTUNE register is set. Once the PLLEN bit is set, the PLL requires up to t<sub>rc</sub> to lock. During this time, the device continues to be clocked at the PLL bypassed frequency.
  - 2: In order to use the USB module in Full-Speed mode, this node must be run at 48 MHz. For Low-Speed mode, this node may be run at either 48 MHz or 24 MHz, but the CPDIV bits must be set such that the USB module is clocked at 6 MHz.
  - 3: Selecting the Timer1 clock or postscaled internal clock will turn off the primary oscillator (unless required by the reference clock of Section 2.6 "Reference Clock Output") and PLL.
  - 4: The USB module cannot be used to communicate unless the primary clock source is selected.


# 2.2.2 CRYSTAL OSCILLATOR/CERAMIC RESONATORS

In HS and HSPLL Oscillator modes, a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation. Figure 2-2 displays the pin connections.

The oscillator design requires the use of a parallel cut crystal.

Note:	Use of a series cut crystal may give a fre- quency out of the crystal manufacturer's
	specifications.

#### FIGURE 2-2: CRYSTAL/CERAMIC RESONATOR OPERATION (HS OR HSPLL CONFIGURATION)



# TABLE 2-2:CAPACITOR SELECTION FOR<br/>CERAMIC RESONATORS

Typical Capacitor Values Used:						
Mode	Freq	OSC1	OSC2			
HS	8.0 MHz 16.0 MHz	27 pF 22 pF	27 pF 22 pF			
• •						

Capacitor values are for design guidance only.

These capacitors were tested with the resonators listed below for basic start-up and operation. **These values are not optimized**.

Different capacitor values may be required to produce acceptable oscillator operation. The user should test the performance of the oscillator over the expected VDD and temperature range for the application.

See the notes following Table 2-3 for additional information.

Resonators Used:
4.0 MHz
8.0 MHz
16.0 MHz

# TABLE 2-3:CAPACITOR SELECTION FOR<br/>CRYSTAL OSCILLATOR

Osc Type	Crystal Freq	Typical Capacitor Values Tested:				
_	Freq	C1	C2			
HS	4 MHz	27 pF	27 pF			
	8 MHz	22 pF	22 pF			
	16 MHz	18 pF	18 pF			

Capacitor values are for design guidance only.

These capacitors were tested with the crystals listed below for basic start-up and operation. **These values are not optimized.** 

Different capacitor values may be required to produce acceptable oscillator operation. The user should test the performance of the oscillator over the expected VDD and temperature range for the application.

See the notes following this table for additional information.

Crystals Used:	
4 MHz	
8 MHz	
16 MHz	

- Note 1: Higher capacitance not only increases the stability of oscillator, but also increases the start-up time.
  - 2: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **3:** Rs may be required to avoid overdriving crystals with low drive level specification.
  - **4:** Always verify oscillator performance over the VDD and temperature range that is expected for the application.


An internal postscaler allows users to select a clock frequency other than that of the crystal or resonator. Frequency division is determined by the CPDIV Configuration bits. Users may select a clock frequency of the oscillator frequency, or 1/2, 1/3 or 1/6 of the frequency.

### 2.2.3 EXTERNAL CLOCK INPUT

The EC and ECPLL Oscillator modes require an external clock source to be connected to the OSC1 pin. There is no oscillator start-up time required after a Power-on Reset (POR) or after an exit from Sleep mode.

In the EC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. In the ECPLL Oscillator mode, the PLL output divided by 4 is available on the OSC2 pin This signal may be used for test purposes or to synchronize other logic. Figure 2-3 displays the pin connections for the EC Oscillator mode.

#### FIGURE 2-3: EXTERNAL CLOCK INPUT OPERATION (EC AND ECPLL CONFIGURATION)



#### 2.2.4 PLL FREQUENCY MULTIPLIER

PIC18F46J50 Family devices include a PLL circuit. This is provided specifically for USB applications with lower speed oscillators and can also be used as a microcontroller clock source.

The PLL can be enabled in HSPLL, ECPLL, INTOSCPLL and INTOSCPLLO Oscillator modes by setting the PLLEN bit (OSCTUNE<6>). It is designed to produce a fixed 96 MHz reference clock from a fixed 4 MHz input. The output can then be divided and used for both the USB and the microcontroller core clock. Because the PLL has a fixed frequency input and output, there are eight prescaling options to match the oscillator input frequency to the PLL. This prescaler allows the PLL to be used with crystals, resonators and external clocks, which are integer multiple frequencies of 4 MHz. For example, a 12 MHz crystal could be used in a prescaler divide by three mode to drive the PLL.

There is also a CPU divider, which can be used to derive the microcontroller clock from the PLL. This allows the USB peripheral and microcontroller to use the same oscillator input and still operate at different clock speeds. The CPU divider can reduce the incoming frequency by a factor of 1, 2, 3 or 6.

#### 2.2.5 INTERNAL OSCILLATOR BLOCK

The PIC18F46J50 Family devices include an internal oscillator block which generates two different clock signals; either can be used as the microcontroller's clock source. The internal oscillator may eliminate the need for external oscillator circuits on the OSC1 and/or OSC2 pins.

The main output (INTOSC) is an 8 MHz clock source which can be used to directly drive the device clock. It also drives the INTOSC postscaler which can provide a range of clock frequencies from 31 kHz to 8 MHz. Additionally, the INTOSC may be used in conjunction with the PLL to generate clock frequencies up to 48 MHz.

The other clock source is the internal RC oscillator (INTRC) which provides a nominal 31 kHz output. INTRC is enabled if it is selected as the device clock source. It is also enabled automatically when any of the following are enabled:

- · Power-up Timer
- Fail-Safe Clock Monitor
- · Watchdog Timer
- Two-Speed Start-up

These features are discussed in larger detail in **Section 26.0 "Special Features of the CPU"**.

The clock source frequency (INTOSC direct, INTRC direct or INTOSC postscaler) is selected by configuring the IRCF bits of the OSCCON register (page 37).

#### 2.2.5.1 OSCTUNE Register

The internal oscillator's output has been calibrated at the factory but can be adjusted in the user's application. This is done by writing to the OSCTUNE register (Register 2-1). The tuning sensitivity is constant throughout the tuning range.

When the OSCTUNE register is modified, the INTOSC frequency will begin shifting to the new frequency. The INTOSC clock will stabilize typically within 1  $\mu$ s. Code execution continues during this shift. There is no indication that the shift has occurred.

The OSCTUNE register also contains the INTSRC bit. The INTSRC bit allows users to select which internal oscillator provides the clock source when the 31 kHz frequency option is selected. This is covered in larger detail in **Section 2.5.1 "Oscillator Control Register"**.

The PLLEN bit, contained in the OSCTUNE register, can be used to enable or disable the internal 96 MHz PLL when running in one of the PLL type oscillator modes (e.g., INTOSCPLL). Oscillator modes that do not contain "PLL" in their name cannot be used with the PLL. In these modes, the PLL is always disabled regardless of the setting of the PLLEN bit.

When configured for one of the PLL enabled modes, setting the PLLEN bit does not immediately switch the device clock to the PLL output. The PLL requires up to electrical parameter,  $t_{rc}$ , to start-up and lock, during which time, the device continues to be clocked. Once the PLL output is ready, the microcontroller core will automatically switch to the PLL derived frequency.

#### 2.2.5.2 Internal Oscillator Output Frequency and Drift

The internal oscillator block is calibrated at the factory to produce an INTOSC output frequency of 8.0 MHz. However, this frequency may drift as VDD or temperature changes, which can affect the controller operation in a variety of ways.

The low-frequency INTRC oscillator operates independently of the INTOSC source. Any changes in INTOSC across voltage and temperature are not necessarily reflected by changes in INTRC and vice versa.

#### 2.2.5.3 Compensating for INTOSC Drift

It is possible to adjust the INTOSC frequency by modifying the value in the OSCTUNE register. This has no effect on the INTRC clock source frequency.

Tuning the INTOSC source requires knowing when to make the adjustment, in which direction it should be made and in some cases, how large a change is needed. When using the EUSART, for example, an adjustment may be required when it begins to generate framing errors or receives data with errors while in Asynchronous mode. Framing errors indicate that the device clock frequency is too high; to adjust for this, decrement the value in OSCTUNE to reduce the clock frequency. On the other hand, errors in data may suggest that the clock speed is too low; to compensate, increment OSCTUNE to increase the clock frequency.

It is also possible to verify device clock speed against a reference clock. Two timers may be used: one timer is clocked by the peripheral clock, while the other is clocked by a fixed reference source, such as the Timer1 oscillator. Both timers are cleared, but the timer clocked by the reference generates interrupts. When an interrupt occurs, the internally clocked timer is read and both timers are cleared. If the internally clocked timer value is greater than expected, then the internal oscillator block is running too fast. To adjust for this, decrement the OSCTUNE register.

Finally, an ECCP module can use free-running Timer1 (or Timer3), clocked by the internal oscillator block and an external event with a known period (i.e., AC power frequency). The time of the first event is captured in the CCPRxH:CCPRxL registers and is recorded for use later. When the second event causes a capture, the time of the first event is subtracted from the time of the second event. Since the period of the external event is known, the time difference between events can be calculated.

If the measured time is greater than the calculated time, the internal oscillator block is running too fast; to compensate, decrement the OSCTUNE register. If the measured time is less than the calculated time, the internal oscillator block is running too slow; to compensate, increment the OSCTUNE register.

# PIC18F46J50 FAMILY

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
INTSRC	PLLEN	TUN5	TUN4	TUN3	TUN2	TUN1	TUN0	
bit 7							bit 0	
Legend:								
R = Readable	e bit	W = Writable	bit	U = Unimpler	nented bit, read	d as '0'		
-n = Value at POR		'1' = Bit is set		'0' = Bit is cleared		x = Bit is unkr	x = Bit is unknown	
bit 7	1 = 31.25 kHz	z device clock	derived from 8	cy Source Sele 3 MHz INTOSC rom INTRC inte	source (divide	-by-256 enable	d)	
bit 6	PLLEN: Frequency Multiplier Enable bit 1 = 96 MHz PLL is enabled 0 = 96 MHz PLL is disabled							
bit 5-0	TUN<5:0>: Frequency Tuning bits 011111 = Maximum frequency 011110 • • 000001 000000 = Center frequency; oscillator module is running at the calibrated frequency 111111							
	• 100000 = Minimum frequency							

#### REGISTER 2-1: OSCTUNE: OSCILLATOR TUNING REGISTER (ACCESS F9Bh)

#### 2.3 Oscillator Settings for USB

When the PIC18F46J50 Family devices are used for USB connectivity, a 6 MHz or 48 MHz clock must be provided to the USB module for operation in either Low-Speed or Full-Speed modes, respectively. This may require some forethought in selecting an oscillator frequency and programming the device.

The full range of possible oscillator configurations compatible with USB operation is shown in Table 2-5.

#### 2.3.1 LOW-SPEED OPERATION

The USB clock for Low-Speed mode is derived from the primary oscillator or from the 96 MHz PLL. In order to operate the USB module in Low-Speed mode, a 6 MHz clock must be provided to the USB module. Due to the way the clock dividers have been implemented in the

PIC18F46J50 Family, the microcontroller core must run at 24 MHz in order for the USB module to get the 6 MHz clock needed for low-speed USB operation. Several clocking schemes could be used to meet these two required conditions. See Table 2-4 and Table 2-5 for possible combinations which can be used for low-speed USB operation.

TABLE 2-4: CLOCK FOR LOW-SPEED USB

Clock Input	CPU Clock	CPDIV<1:0>	USB Clock
48	24	'10'	48/8 = 6 MHz
24	24	'11'	24/4 = 6 MHz

Input Oscillator Frequency	PLL Division (PLLDIV<2:0>)	Clock Mode (FOSC<2:0>)	MCU Clock Division (CPDIV<1:0>)	Microcontroller Clock Frequency
			None (11)	48 MHz
48 MHz	N/A	EC	÷2 (10)	24 MHz
			÷3(01)	16 MHz
			÷6 (00)	8 MHz
	÷ <b>12 (</b> 000)	ECPLL	None (11)	48 MHz
48 MHz			÷2(10)	24 MHz
			÷3(01)	16 MHz
			÷6 (00)	8 MHz
	÷ <b>10 (</b> 001)	ECPLL	None (11)	48 MHz
			÷2(10)	24 MHz
40 MHz			÷3(01)	16 MHz
			÷6 (00)	8 MHz
		HSPLL, ECPLL	None (11)	48 MHz
	÷6 (010)		÷2(10)	24 MHz
24 MHz			÷3(01)	16 MHz
			÷6 (00)	8 MHz
			None (11)	24 MHz
	N/A	EC, HS	÷2(10)	12 MHz
24 MHz			÷3(01)	8 MHz
			÷6 (00)	4 MHz
	÷ <b>5 (</b> 011 <b>)</b>	HSPLL, ECPLL	None (11)	48 MHz
00 MU-			÷2(10)	24 MHz
20 MHz			÷3(01)	16 MHz
			÷6 (00)	8 MHz
	÷ <b>4 (</b> 100)	HSPLL, ECPLL	None (11)	48 MHz
			÷2(10)	24 MHz
16 MHz			÷3(01)	16 MHz
			÷6 (00)	8 MHz
	÷ <b>3 (</b> 101)	HSPLL, ECPLL	None (11)	48 MHz
10 MI -			÷2 (10)	24 MHz
12 MHz			÷3(01)	16 MHz
			÷6 (00)	8 MHz
	÷2 (110)	HSPLL, ECPLL, INTOSCPLL/ INTOSCPLLO	None (11)	48 MHz
8 MHz			÷2(10)	24 MHz
			÷3(01)	16 MHz
			÷6 (00)	8 MHz
	÷1 (111)	HSPLL, ECPLL	None (11)	48 MHz
4 M⊔→			÷2 (10)	24 MHz
4 MHz			÷3(01)	16 MHz
			÷6 (00)	8 MHz

#### TABLE 2-5: OSCILLATOR CONFIGURATION OPTIONS FOR USB OPERATION

Legend: All clock frequencies, except 24 MHz, are exclusively associated with full-speed USB operation (USB clock of 48 MHz). Bold text highlights the clock selections that are compatible with low-speed USB operation (system clock of 24 MHz, USB clock of 6 MHz).

### 2.4 USB From INTOSC

The 8 MHz INTOSC included in all PIC18F46J50 Family devices is extremely accurate. When the 8 MHz INTOSC is used with the 96 MHz PLL, it may be used to derive the USB module clock. The high accuracy of the INTOSC will allow the application to meet low-speed USB signal rate specifications.

#### 2.5 Clock Sources and Oscillator Switching

Like previous PIC18 enhanced devices, the PIC18F46J50 Family includes a feature that allows the device clock source to be switched from the main oscillator to an alternate, low-frequency clock source. PIC18F46J50 Family devices offer two alternate clock sources. When an alternate clock source is enabled, the various power-managed operating modes are available.

Essentially, there are three clock sources for these devices:

- Primary Oscillators
- · Secondary Oscillators
- Internal Oscillator Block

The **Primary Oscillators** include the External Crystal and Resonator modes, the External Clock modes and the internal oscillator block. The particular mode is defined by the FOSC<2:0> Configuration bits. The details of these modes are covered earlier in this chapter.

The **Secondary Oscillators** are external sources that are not connected to the OSC1 or OSC2 pins. These sources may continue to operate even after the controller is placed in a power-managed mode.

PIC18F46J50 Family devices offer the Timer1 oscillator as a secondary oscillator. This oscillator, in all power-managed modes, is often the time base for functions such as a Real-Time Clock (RTC). Most often, a 32.768 kHz watch crystal is connected between the RC0/T1OSO/T1CKI/RP11 and RC1/T1OSI/UOE/RP12 pins. Like the HS Oscillator mode circuits, loading capacitors are also connected from each pin to ground. The Timer1 oscillator is discussed in larger detail in **Section 12.5 "Timer1 Oscillator**".

In addition to being a primary clock source, the **postscaled internal clock** is available as a power-managed mode clock source. The INTRC source is also used as the clock source for several special features, such as the WDT and Fail-Safe Clock Monitor (FSCM).

#### 2.5.1 OSCILLATOR CONTROL REGISTER

The OSCCON register (Register 2-2) controls several aspects of the device clock's operation, both in full-power operation and in power-managed modes.

The System Clock Select bits, SCS<1:0>, select the clock source. The available clock sources are the primary clock (defined by the FOSC<2:0> Configuration bits), the secondary clock (Timer1 oscillator) and the postscaled internal clock. The clock source changes immediately, after one or more of the bits is written to, following a brief clock transition interval. The SCS bits are cleared on all forms of Reset.

The Internal Oscillator Frequency Select bits, IRCF<2:0>, select the frequency output provided on the postscaled internal clock line. The choices are the INTRC source, the INTOSC source (8 MHz) or one of the frequencies derived from the INTOSC postscaler (31 kHz to 4 MHz). If the postscaled internal clock is supplying the device clock, changing the states of these bits will have an immediate change on the internal oscillator's output. On device Resets, the default output frequency of the INTOSC postscaler is set at 4 MHz.

When an output frequency of 31 kHz is selected (IRCF<2:0> = 000), users may choose the internal oscillator, which acts as the source. This is done with the INTSRC bit in the OSCTUNE register (OSCTUNE<7>). Setting this bit selects INTOSC as a 31.25 kHz clock source by enabling the divide-by-256 output of the INTOSC postscaler. Clearing INTSRC selects INTRC (nominally 31 kHz) as the clock source.

This option allows users to select the tunable and more precise INTOSC as a clock source, while maintaining power savings with a very low clock speed. Regardless of the setting of INTSRC, INTRC always remains the clock source for features such as the WDT and the FSCM.

The OSTS and T1RUN bits indicate which clock source is currently providing the device clock. The OSTS bit indicates that the Oscillator Start-up Timer (OST) has timed out and the primary clock is providing the device clock in primary clock modes. The T1RUN bit (T1CON<6>) indicates when the Timer1 oscillator is providing the device clock in secondary clock modes. In power-managed modes, only one of these bits will be set at any time. If none of these bits are set, the INTRC is providing the clock or the internal oscillator block has just started and is not yet stable.

The IDLEN bit determines if the device goes into Sleep mode, or one of the Idle modes, when the SLEEP instruction is executed.

The use of the flag and control bits in the OSCCON register is discussed in more detail in **Section 3.0** "Low-Power Modes".

- Note 1: The Timer1 crystal driver is enabled by setting the T1OSCEN bit in the Timer1 Control register (T1CON<3>). If the Timer1 oscillator is not enabled, then any attempt to select the Timer1 clock source will be ignored, unless the CONFIG2L register's T1DIG bit is set.
  - 2: If Timer1 is driving a crystal, it is recommended that the Timer1 oscillator be operating and stable prior to switching to it as the clock source; otherwise, a very long delay may occur while the Timer1 oscillator starts.

## 2.5.2 OSCILLATOR TRANSITIONS

PIC18F46J50 Family devices contain circuitry to prevent clock "glitches" when switching between clock sources. A short pause in the device clock occurs during the clock switch. The length of this pause is the sum of two cycles of the old clock source and three to four cycles of the new clock source. This formula assumes that the new clock source is stable.

Clock transitions are discussed in more detail in **Section 3.1.2 "Entering Power-Managed Modes"**.

### REGISTER 2-2: OSCCON: OSCILLATOR CONTROL REGISTER (ACCESS FD3h)

R/W-0	R/W-1	R/W-1	R/W-0	R-1 <sup>(1)</sup>	U-1	R/W-0	R/W-0
IDLEN	IRCF2	IRCF1	IRCF0	OSTS		SCS1	SCS0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	read as `0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	IDLEN: Idle Enable bit
	1 = Device enters Idle mode on SLEEP instruction
	0 = Device enters Sleep mode on SLEEP instruction
bit 6-4	IRCF<2:0>: Internal Oscillator Frequency Select bits
	111 = 8 MHz (INTOSC drives clock directly)
	110 = 4 MHz <sup>(2)</sup>
	101 = 2 MHz
	100 = 1 MHz 011 = 500 kHz
	010 = 250  kHz
	001 = <b>125</b> kHz
	000 = 31 kHz (from either INTOSC/256 or INTRC directly) <sup>(3)</sup>
bit 3	<b>OSTS</b> : Oscillator Start-up Time-out Status bit <sup>(1)</sup>
	1 = Oscillator Start-up Timer time-out has expired; primary oscillator is running
	0 = Oscillator Start-up Timer time-out is running; primary oscillator is not ready
bit 2	Unimplemented: Read as '1'
bit 1-0	SCS<1:0>: System Clock Select bits
	11 = Postscaled internal clock (INTRC/INTOSC derived)
	10 = Reserved
	01 = Timer1 oscillator
	00 = Primary clock source (INTOSC postscaler output when FOSC<2:0> = 001 or 000) 00 = Primary clock source (CPU divider output for other values of FOSC<2:0>)
Note 1:	Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.
2:	Default output frequency of INTOSC on Reset (4 MHz).

3: Source selected by the INTSRC bit (OSCTUNE<7>).

#### 2.6 **Reference Clock Output**

In addition to the peripheral clock/4 output in certain oscillator modes, the device clock in the PIC18F46J50 Family can also be configured to provide a reference clock output signal to a port pin. This feature is available in all oscillator configurations and allows the user to select a greater range of clock submultiples to drive external devices in the application.

This reference clock output is controlled by the REFOCON register (Register 2-3). Setting the ROON bit (REFOCON<7>) makes the clock signal available on the REFO (RB2) pin. The RODIV<3:0> bits enable the selection of 16 different clock divider options.

The ROSSLP and ROSEL bits (REFOCON<5:4>) control the availability of the reference output during Sleep mode. The ROSEL bit determines if the oscillator is on OSC1 and OSC2, or the current system clock source is used for the reference clock output. The ROSSLP bit determines if the reference source is available on RB2 when the device is in Sleep mode.

To use the reference clock output in Sleep mode, both the ROSSLP and ROSEL bits must be set. The device clock must also be configured for an EC or HS mode; otherwise, the oscillator on OSC1 and OSC2 will be powered down when the device enters Sleep mode. Clearing the ROSEL bit allows the reference output frequency to change as the system clock changes during any clock switches.

#### **REGISTER 2-3: REFOCON: REFERENCE OSCILLATOR CONTROL REGISTER (BANKED F3Dh)**

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
ROON		ROSSLP	ROSEL	RODIV3	RODIV2	RODIV1	RODIV0
bit 7							bit 0
Legend:			,				
R = Readable bit		W = Writable		•	nented bit, rea		
-n = Value at POR		'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unki	nown
bit 7	ROON: Refer	ence Oscillator	Output Enat	ole bit			
		e oscillator ena	•				
	0 = Reference	e oscillator disa	bled				
bit 6	Unimplemen	ted: Read as '	) <b>'</b>				
bit 5	ROSSLP: Re	ference Oscilla	tor Output St	op in Sleep bit			
	1 = Reference	e oscillator con	tinues to run	in Sleep			
	0 = Reference	e oscillator is di	sabled in Sle	ер			
bit 4	ROSEL: Refe	erence Oscillato	or Source Sel	ect bit			
				sed as the base			
	0 = System c	lock (Fosc) us	ed as the bas	e clock; base cl	ock reflects any	y clock switchin	g of the device
bit 3-0		Reference Os					
		clock value div					
		clock value div					
		clock value div					
		clock value div clock value div	•				
		clock value div					
		clock value div		T			
		clock value div	-				
		clock value div					
	0110 <b>= Base</b>	clock value div	ided by 64				
		clock value div					
		clock value div					
		clock value div					
		clock value div					
		clock value div	ided by 2				
	0000 <b>= Base</b>	clock value					
Note 1.	The crystal oscillat	or must be ena	bled using th	e EOSC<2.0>	hits: the crystal	maintains the	operation in

The crystal oscillator must be enabled using the FOSC<2:0> bits; the crystal maintains the operation in Note 1: Sleep mode.

## 2.7 Effects of Power-Managed Modes on Various Clock Sources

When the PRI\_IDLE mode is selected, the designated primary oscillator continues to run without interruption. For all other power-managed modes, the oscillator using the OSC1 pin is disabled. Unless the USB module is enabled, the OSC1 pin (and OSC2 pin if used by the oscillator) will stop oscillating.

In secondary clock modes (SEC\_RUN and SEC\_IDLE), the Timer1 oscillator is operating and providing the device clock. The Timer1 oscillator may also run in all power-managed modes if required to clock Timer1 or Timer3.

In internal oscillator modes (RC\_RUN and RC\_IDLE), the internal oscillator block provides the device clock source. The 31 kHz INTRC output can be used directly to provide the clock and may be enabled to support various special features regardless of the power-managed mode (see Section 26.2 "Watchdog Timer (WDT)", Section 26.4 "Two-Speed Start-up" and Section 26.5 "Fail-Safe Clock Monitor" for more information on WDT, FSCM and Two-Speed Start-up). The INTOSC output at 8 MHz may be used directly to clock the device or may be divided down by the postscaler. The INTOSC output is disabled if the clock is provided directly from the INTRC output.

If Sleep mode is selected, all clock sources which are no longer required are stopped. Since all the transistor switching currents have been stopped, Sleep mode achieves the lowest current consumption of the device (only leakage currents) outside of Deep Sleep. Sleep mode should not be invoked while the USB module is enabled and operating in Full-Power mode. Before Sleep mode is selected, the USB module should be put in the suspend state. This is accomplished by setting the SUSPND bit in the UCON register.

Enabling any on-chip feature that will operate during Sleep mode increases the current consumed during Sleep mode. The INTRC is required to support WDT operation. The Timer1 oscillator may be operating to support a RTC. Other features may be operating that do not require a device clock source (i.e., MSSP slave, PMP, INTx pins, etc.). Peripherals that may add significant current consumption are listed in Section 29.2 "DC Characteristics: Power-Down and Supply Current PIC18F46J50 Family (Industrial)".

## 2.8 Power-up Delays

Power-up delays are controlled by two timers so that no external Reset circuitry is required for most applications. The delays ensure that the device is kept in Reset until the device power supply is stable under normal circumstances and the primary clock is operating and stable. For additional information on power-up delays, see **Section 4.6 "Power-up Timer (PWRT)**".

The first timer is the Power-up Timer (PWRT), which provides a fixed delay on power-up (parameter 33, Table 29-14).

The second timer is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable (HS mode). The OST does this by counting 1024 oscillator cycles before allowing the oscillator to clock the device.

There is a delay of interval, TCSD (parameter 38, Table 29-14), following POR, while the controller becomes ready to execute instructions. This delay runs concurrently with any other delays. This may be the only delay that occurs when any of the internal oscillator or EC modes are used as the primary clock source.

NOTES:

## 3.0 LOW-POWER MODES

The PIC18F46J50 Family devices can manage power consumption through clocking to the CPU and the peripherals. In general, reducing the clock frequency and number of circuits being clocked reduce power consumption.

For managing power in an application, the primary modes of operation are:

- Run Mode
- Idle Mode
- Sleep Mode
- Deep Sleep Mode

Additionally, there is an Ultra Low-Power Wake-up (ULPWU) mode for generating an interrupt-on-change on RA0.

These modes define which portions of the device are clocked and at what speed.

- The Run and Idle modes can use any of the three available clock sources (primary, secondary or internal oscillator blocks).
- The Sleep mode does not use a clock source.

The ULPWU mode on RA0 allows a slow falling voltage to generate an interrupt-on-change on RA0 without excess current consumption. See **Section 3.7 "Ultra Low-Power Wake-up"**.

The power-managed modes include several power-saving features offered on previous PIC<sup>®</sup> devices, such as clock switching, ULPWU and Sleep mode. In addition, the PIC18F46J50 family devices add a new power-managed Deep Sleep mode.

## 3.1 Selecting Power-Managed Modes

Selecting a power-managed mode requires these decisions:

- Will the CPU be clocked?
- If so, which clock source will be used?

The IDLEN bit (OSCCON<7>) controls CPU clocking and the SCS<1:0> bits (OSCCON<1:0>) select the clock source. The individual modes, bit settings, clock sources and affected modules are summarized in Table 3-1.

## 3.1.1 CLOCK SOURCES

The SCS<1:0> bits allow the selection of one of three clock sources for power-managed modes. They are:

- Primary clock source Defined by the FOSC<2:0> Configuration bits
- Timer1 clock Provided by the secondary oscillator
- Postscaled internal clock Derived from the internal oscillator block

#### 3.1.2 ENTERING POWER-MANAGED MODES

Switching from one clock source to another begins by loading the OSCCON register. The SCS<1:0> bits select the clock source.

Changing these bits causes an immediate switch to the new clock source, assuming that it is running. The switch also may be subject to clock transition delays. These delays are discussed in **Section 3.1.3 "Clock Transitions and Status Indicators"** and subsequent sections.

Entry to the power-managed Idle or Sleep modes is triggered by the execution of a SLEEP instruction. The actual mode that results depends on the status of the IDLEN bit.

Depending on the current mode and the mode being switched to, a change to a power-managed mode does not always require setting all of these bits. Many transitions may be done by changing the oscillator select bits, the IDLEN bit, or the DSEN bit prior to issuing a SLEEP instruction.

If the IDLEN and DSEN bits are already configured correctly, it only may be necessary to perform a SLEEP instruction to switch to the desired mode.

	DSCONH<7>	oscco	ON<7,1:0>	Modul	e Clocking	
Mode	DSEN <sup>(1)</sup>	IDLEN <sup>(1)</sup>	SCS<1:0>	CPU Peripherals		Available Clock and Oscillator Source
Sleep	0	0	N/A	Off	Off	Timer1 oscillator and/or RTCC may optionally be enabled
Deep Sleep	1	0	N/A	Off <sup>(2)</sup>	Off	RTCC can run uninterrupted using the Timer1 or internal low-power RC oscillator
PRI_RUN	0	N/A	00	Clocked	Clocked	The normal, full-power execution mode; primary clock source (defined by FOSC<2:0>)
SEC_RUN	0	N/A	01	Clocked	Clocked	Secondary – Timer1 oscillator
RC_RUN	0	N/A	11	Clocked	Clocked	Postscaled internal clock
PRI_IDLE	0	1	00	Off	Clocked	Primary clock source (defined by FOSC<2:0>)
SEC_IDLE	0	1	01	Off	Clocked	Secondary – Timer1 oscillator
RC_IDLE	0	1	11	Off	Clocked	Postscaled internal clock

## TABLE 3-1: LOW-POWER MODES

Note 1: IDLEN and DSEN reflect their values when the **SLEEP** instruction is executed.

2: Deep Sleep turns off the voltage regulator for ultra low-power consumption. See Section 3.6 "Deep Sleep Mode" for more information.

## 3.1.3 CLOCK TRANSITIONS AND STATUS INDICATORS

The length of the transition between clock sources is the sum of two cycles of the old clock source and three to four cycles of the new clock source. This formula assumes that the new clock source is stable.

Two bits indicate the current clock source and its status: OSTS (OSCCON<3>) and T1RUN (T1CON<6>). In general, only one of these bits will be set in a given power-managed mode. When the OSTS bit is set, the primary clock would be providing the device clock. When the T1RUN bit is set, the Timer1 oscillator would be providing the clock. If neither of these bits is set, INTRC would be clocking the device.

**Note:** Executing a SLEEP instruction does not necessarily place the device into Sleep mode. It acts as the trigger to place the controller into either the Sleep or Deep Sleep mode, or one of the Idle modes, depending on the setting of the IDLEN bit.

### 3.1.4 MULTIPLE SLEEP COMMANDS

The power-managed mode that is invoked with the SLEEP instruction is determined by the setting of the IDLEN and DSEN bits at the time the instruction is executed. If another SLEEP instruction is executed, the device will enter the power-managed mode specified by IDLEN and DSEN at that time. If IDLEN or DSEN have changed, the device will enter the new power-managed mode specified by the new setting.

## 3.2 Run Modes

In the Run modes, clocks to both the core and peripherals are active. The difference between these modes is the clock source.

## 3.2.1 PRI\_RUN MODE

The PRI\_RUN mode is the normal, full-power execution mode of the microcontroller. This is also the default mode upon a device Reset unless Two-Speed Start-up is enabled (see **Section 26.4 "Two-Speed Start-up"** for details). In this mode, the OSTS bit is set (see **Section 2.5.1 "Oscillator Control Register"**).


## 3.2.2 SEC\_RUN MODE


The SEC\_RUN mode is the compatible mode to the "clock switching" feature offered in other PIC18 devices. In this mode, the CPU and peripherals are clocked from the Timer1 oscillator. This gives users the option of low-power consumption while still using a high-accuracy clock source.

SEC\_RUN mode is entered by setting the SCS<1:0> bits to '01'. The device clock source is switched to the Timer1 oscillator (see Figure 3-1), the primary oscillator is shut down, the T1RUN bit (T1CON<6>) is set and the OSTS bit is cleared.

Note: The Timer1 oscillator should already be running prior to entering SEC\_RUN mode. If the T1OSCEN bit is not set when the SCS<1:0> bits are set to '01', entry to SEC\_RUN mode will not occur. If the Timer1 oscillator is enabled, but not yet running, device clocks will be delayed until the oscillator has started. In such situations, initial oscillator operation is far from stable and unpredictable operation may result. On transitions from SEC\_RUN mode to PRI\_RUN mode, the peripherals and CPU continue to be clocked from the Timer1 oscillator while the primary clock is started. When the primary clock becomes ready, a clock switch back to the primary clock occurs (see

Figure 3-2). When the clock switch is complete, the T1RUN bit is cleared, the OSTS bit is set and the primary clock would be providing the clock. The IDLEN and SCS bits are not affected by the wake-up; the Timer1 oscillator continues to run.






## 3.2.3 RC\_RUN MODE

In RC\_RUN mode, the CPU and peripherals are clocked from the internal oscillator; the primary clock is shutdown. This mode provides the best power conservation of all the Run modes while still executing code. It works well for user applications, which are not highly timing sensitive or do not require high-speed clocks at all times.


This mode is entered by setting the SCS<1:0> bits (OSCCON<1:0>) to '11'. When the clock source is switched to the internal oscillator block (see Figure 3-3), the primary oscillator is shutdown and the OSTS bit is cleared.

On transitions from RC\_RUN mode to PRI\_RUN mode, the device continues to be clocked from the INTOSC block while the primary clock is started. When the primary clock becomes ready, a clock switch to the primary clock occurs (see Figure 3-4). When the clock switch is complete, the OSTS bit is set and the primary clock is providing the device clock. The IDLEN and SCS bits are not affected by the switch. The INTRC clock source will continue to run if either the WDT or the FSCM is enabled.

## FIGURE 3-3: TRANSITION TIMING TO RC\_RUN MODE



### FIGURE 3-4: TRANSITION TIMING FROM RC\_RUN MODE TO PRI\_RUN MODE





## 3.3 Sleep Mode

The power-managed Sleep mode is identical to the legacy Sleep mode offered in all other PIC devices. It is entered by clearing the IDLEN bit (the default state on device Reset) and executing the SLEEP instruction. This shuts down the selected oscillator (Figure 3-5). All clock source status bits are cleared.

Entering the Sleep mode from any other mode does not require a clock switch. This is because no clocks are needed once the controller has entered Sleep mode. If the WDT is selected, the INTRC source will continue to operate. If the Timer1 oscillator is enabled, it will also continue to run. When a wake event occurs in Sleep mode (by interrupt, Reset or WDT time-out), the device will not be clocked until the clock source selected by the SCS<1:0> bits becomes ready (see Figure 3-6), or it will be clocked from the internal oscillator if either the Two-Speed Start-up or the FSCM are enabled (see Section 26.0 "Special Features of the CPU"). In either case, the OSTS bit is set when the primary clock is providing the device clocks. The IDLEN and SCS bits are not affected by the wake-up.







## 3.4 Idle Modes

The Idle modes allow the controller's CPU to be selectively shut down while the peripherals continue to operate. Selecting a particular Idle mode allows users to further manage power consumption.

If the IDLEN bit is set to '1' when a SLEEP instruction is executed, the peripherals will be clocked from the clock source selected using the SCS<1:0> bits; however, the CPU will not be clocked. The clock source status bits are not affected. Setting IDLEN and executing a SLEEP instruction provides a quick method of switching from a given Run mode to its corresponding Idle mode.

If the WDT is selected, the INTRC source will continue to operate. If the Timer1 oscillator is enabled, it will also continue to run.

Since the CPU is not executing instructions, the only exits from any of the Idle modes are by interrupt, WDT time-out or a Reset. When a wake event occurs, CPU execution is delayed by an interval of TCsD (parameter 38, Table 29-14) while it becomes ready to execute code. When the CPU begins executing code, it resumes with the same clock source for the current Idle mode. For example, when waking from RC\_IDLE mode, the internal oscillator block will clock the CPU and peripherals (in other words, RC\_RUN mode). The IDLEN and SCS bits are not affected by the wake-up.

While in any Idle or Sleep mode, a WDT time-out will result in a WDT wake-up to the Run mode currently specified by the SCS<1:0> bits.

### 3.4.1 PRI\_IDLE MODE

This mode is unique among the three low-power Idle modes, in that it does not disable the primary device clock. For timing-sensitive applications, this allows for the fastest resumption of device operation with its more accurate primary clock source, since the clock source does not have to "warm up" or transition from another oscillator.

PRI\_IDLE mode is entered from PRI\_RUN mode by setting the IDLEN bit and executing a SLEEP instruction. If the device is in another Run mode, set IDLEN

first, then set the SCS bits to '00' and execute SLEEP. Although the CPU is disabled, the peripherals continue to be clocked from the primary clock source specified by the FOSC<1:0> Configuration bits. The OSTS bit remains set (see Figure 3-7).

When a wake event occurs, the CPU is clocked from the primary clock source. A delay of interval, TCSD, is required between the wake event and when code execution starts. This is required to allow the CPU to become ready to execute instructions. After the wake-up, the OSTS bit remains set. The IDLEN and SCS bits are not affected by the wake-up (see Figure 3-8).


## 3.4.2 SEC\_IDLE MODE


In SEC\_IDLE mode, the CPU is disabled but the peripherals continue to be clocked from the Timer1 oscillator. This mode is entered from SEC\_RUN by setting the IDLEN bit and executing a SLEEP instruction. If the device is in another Run mode, set IDLEN first, then set SCS<1:0> to '01' and execute SLEEP. When the clock source is switched to the Timer1 oscillator, the primary oscillator is shutdown, the OSTS bit is cleared and the T1RUN bit is set.

When a wake event occurs, the peripherals continue to be clocked from the Timer1 oscillator. After an interval of TCSD following the wake event, the CPU begins executing code being clocked by the Timer1 oscillator. The IDLEN and SCS bits are not affected by the wake-up; the Timer1 oscillator continues to run (see Figure 3-8).

Note: The Timer1 oscillator should already be running prior to entering SEC\_IDLE mode. If the T1OSCEN bit is not set when the SLEEP instruction is executed, the SLEEP instruction will be ignored and entry to SEC\_IDLE mode will not occur. If the Timer1 oscillator is enabled, but not yet running, peripheral clocks will be delayed until the oscillator has started. In such situations, initial oscillator operation is far from stable and unpredictable operation may result.

## FIGURE 3-7: TRANSITION TIMING FOR ENTRY TO IDLE MODE





## 3.4.3 RC\_IDLE MODE

In RC\_IDLE mode, the CPU is disabled but the peripherals continue to be clocked from the internal oscillator block. This mode allows for controllable power conservation during Idle periods.

From RC\_RUN, this mode is entered by setting the IDLEN bit and executing a SLEEP instruction. If the device is in another Run mode, first set IDLEN, then clear the SCS bits and execute SLEEP. When the clock source is switched to the INTOSC block, the primary oscillator is shutdown and the OSTS bit is cleared.

When a wake event occurs, the peripherals continue to be clocked from the internal oscillator block. After a delay of TCSD following the wake event, the CPU begins executing code being clocked by the INTRC. The IDLEN and SCS bits are not affected by the wake-up. The INTRC source will continue to run if either the WDT or the FSCM is enabled.

## 3.5 Exiting Idle and Sleep Modes

An exit from Sleep mode, or any of the Idle modes, is triggered by an interrupt, a Reset or a WDT time-out. This section discusses the triggers that cause exits from power-managed modes. The clocking subsystem actions are discussed in each of the power-managed modes sections (see Section 3.2 "Run Modes", Section 3.3 "Sleep Mode" and Section 3.4 "Idle Modes").

## 3.5.1 EXIT BY INTERRUPT

Any of the available interrupt sources can cause the device to exit from an Idle mode, or the Sleep mode, to a Run mode. To enable this functionality, an interrupt source must be enabled by setting its enable bit in one of the INTCON or PIE registers. The exit sequence is initiated when the corresponding interrupt flag bit is set.

On all exits from Idle or Sleep modes by interrupt, code execution branches to the interrupt vector if the GIE/GIEH bit (INTCON<7>) is set. Otherwise, code execution continues or resumes without branching (see **Section 8.0 "Interrupts"**).

A fixed delay of interval, TCSD, following the wake event, is required when leaving Sleep and Idle modes. This delay is required for the CPU to prepare for execution. Instruction execution resumes on the first clock cycle following this delay.

## 3.5.2 EXIT BY WDT TIME-OUT

A WDT time-out will cause different actions depending on which power-managed mode the device is, when the time-out occurs.

If the device is not executing code (all Idle modes and Sleep mode), the time-out will result in an exit from the power-managed mode (see Section 3.2 "Run Modes" and Section 3.3 "Sleep Mode"). If the device is executing code (all Run modes), the time-out will result in a WDT Reset (see Section 26.2 "Watchdog Timer (WDT)").

The WDT and postscaler are cleared by one of the following events:

- Executing a SLEEP or CLRWDT instruction
- The loss of a currently selected clock source (if the FSCM is enabled)

## 3.5.3 EXIT BY RESET

Exiting an Idle or Sleep mode by Reset automatically forces the device to run from the INTRC.

#### 3.5.4 EXIT WITHOUT AN OSCILLATOR START-UP DELAY

Certain exits from power-managed modes do not invoke the OST at all. There are two cases:

- PRI\_IDLE mode (where the primary clock source is not stopped) and the primary clock source is the EC mode
- PRI\_IDLE mode and the primary clock source is the ECPLL mode

In these instances, the primary clock source either does not require an oscillator start-up delay, since it is already running (PRI\_IDLE), or normally does not require an oscillator start-up delay (EC). However, a fixed delay of interval, TCSD, following the wake event, is still required when leaving Sleep and Idle modes to allow the CPU to prepare for execution. Instruction execution resumes on the first clock cycle following this delay.

## 3.6 Deep Sleep Mode

Deep Sleep mode brings the device into its lowest power consumption state without requiring the use of external switches to remove power from the device. During deep sleep, the on-chip VDDCORE voltage regulator is powered down, effectively disconnecting power to the core logic of the microcontroller.

Note:	Since Deep Sleep mode powers down the microcontroller by turning off the on-chip VDDCORE voltage regulator, Deep sleep capability is available only on PIC18FXXJ members in the device family. The on-chip voltage regulator is not available in PIC18LFXXJ members of the device family, and therefore they do not support Deep Sleep.
-------	-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

On devices that support it, the Deep Sleep mode is entered by:

- Setting the REGSLP (WDTCON<7>) bit
- Clearing the IDLEN bit
- · Clearing the GIE bit
- Setting the DSEN bit (DSCONH<7>)
- Executing the SLEEP instruction immediately after setting DSEN (no delay or interrupts in between)

In order to minimize the possibility of inadvertently entering Deep Sleep, the DSEN bit is cleared in hardware two instruction cycles after having been set. Therefore, in order to enter Deep Sleep, the SLEEP instruction must be executed in the immediate instruction cycle after setting DSEN. If DSEN is not set when Sleep is executed, the device will enter conventional Sleep mode instead.

During Deep Sleep, the core logic circuitry of the microcontroller is powered down to reduce leakage current. Therefore, most peripherals and functions of the microcontroller become unavailable during Deep Sleep. However, a few specific peripherals and functions are powered directly from the VDD supply rail of the microcontroller, and therefore, can continue to function in Deep Sleep.

Entering Deep Sleep mode clears the DSWAKEL register. However, if the Real-Time Clock and Calendar (RTCC) is enabled prior to entering Deep Sleep, it will continue to operate uninterrupted.

The device has a dedicated Brown-out Reset (DSBOR) and Watchdog Timer Reset (DSWDT) for monitoring voltage and time-out events in Deep Sleep. The DSBOR and DSWDT are independent of the standard BOR and WDT used with other power-managed modes (Run, Idle and Sleep).

When a wake event occurs in Deep Sleep mode (by MCLR Reset, RTCC alarm, INT0 interrupt, ULPWU or DSWDT), the device will exit Deep Sleep mode and perform a Power-on Reset (POR). When the device is released from Reset, code execution will resume at the device's Reset vector.

### 3.6.1 PREPARING FOR DEEP SLEEP

Because VDDCORE could fall below the SRAM retention voltage while in Deep Sleep mode, SRAM data could be lost in Deep Sleep. Exiting Deep Sleep mode causes a POR; as a result, most Special Function Registers will reset to their default POR values.

Applications needing to save a small amount of data throughout a Deep Sleep cycle can save the data to the general purpose DSGPR0 and DSGPR1 registers. The contents of these registers are preserved while the device is in Deep Sleep, and will remain valid throughout an entire Deep Sleep entry and wake-up sequence.

### 3.6.2 I/O PINS DURING DEEP SLEEP

During Deep Sleep, the general purpose I/O pins will retain their previous states.

Pins that are configured as inputs (TRIS bit set) prior to entry into Deep Sleep will remain high impedance during Deep Sleep.

Pins that are configured as outputs (TRIS bit clear) prior to entry into Deep Sleep will remain as output pins during Deep Sleep. While in this mode, they will drive the output level determined by their corresponding LAT bit at the time of entry into Deep Sleep.

When the device wakes back up, the I/O pin behavior depends on the type of wake up source.

If the device wakes back up by an RTCC alarm, INT0 interrupt, DSWDT or ULPWU event, all I/O pins will continue to maintain their previous states, even after the device has finished the POR sequence and is executing application code again. Pins configured as inputs during Deep Sleep will remain high impedance, and pins configured as outputs will continue to drive their previous value.

After waking up, the TRIS and LAT registers will be reset, but the I/O pins will still maintain their previous states. If firmware modifies the TRIS and LAT values for the I/O pins, they will not immediately go to the newly configured states. Once the firmware clears the RELEASE bit (DSCONL<0>), the I/O pins will be "released". This causes the I/O pins to take the states configured by their respective TRIS and LAT bit values.

If the Deep Sleep BOR (DSBOR) circuit is enabled, and VDD drops below the DSBOR and VDD rail POR thresholds, the I/O pins will be immediately released similar to clearing the RELEASE bit. All previous state information will be lost, including the general purpose DSGPR0 and DSGPR1 contents. See **Section 3.6.5 "Deep Sleep Brown-Out Reset (DSBOR)"** for additional details regarding this scenario

If a MCLR Reset event occurs during Deep Sleep, the I/O pins will also be released automatically, but in this case, the DSGPR0 and DSGPR1 contents will remain valid.

In all other Deep Sleep wake-up cases, application firmware needs to clear the RELEASE bit in order to reconfigure the I/O pins.

## 3.6.3 DEEP SLEEP WAKE-UP SOURCES

The device can be awakened from Deep Sleep mode by a MCLR, POR, RTCC, INTO I/O pin interrupt, DSWDT or ULPWU event. After waking, the device performs a POR. When the device is released from Reset, code execution will begin at the device's Reset vector.

The software can determine if the wake-up was caused from an exit from Deep Sleep mode by reading the DS bit (WDTCON<3>). If this bit is set, the POR was caused by a Deep Sleep exit. The DS bit must be manually cleared by the software.

The software can determine the wake event source by reading the DSWAKEH and DSWAKEL registers. When the application firmware is done using the DSWAKEH and DSWAKEL status registers, individual bits do not need to be manually cleared before entering Deep Sleep again. When entering Deep Sleep mode, these registers are automatically cleared.

#### 3.6.3.1 Wake-up Event Considerations

Deep Sleep wake-up events are only monitored while the processor is fully in Deep Sleep mode. If a wake-up event occurs before Deep Sleep mode is entered, the event status will not be reflected in the DSWAKE registers. If the wake-up source asserts prior to entering Deep Sleep, the CPU will either go to the interrupt vector (if the wake source has an interrupt bit and the interrupt is fully enabled) or will abort the Deep Sleep entry sequence by executing past the SLEEP instruction if the interrupt was not enabled. In this case, a wake-up event handler should be placed after the SLEEP instruction to process the event and re-attempt entry into Deep Sleep, if desired.

When the device is in Deep Sleep with more than one wake-up source simultaneously enabled, only the first wake-up source to assert will be detected and logged in the DSWAKEH/DSWAKEL status registers.

#### 3.6.4 DEEP SLEEP WATCHDOG TIMER (DSWDT)

Deep Sleep has its own dedicated WDT (DSWDT) with a postscaler for time-outs of 2.1 ms to 25.7 days, configurable through the bits, DSWDTPS<3:0>.

The DSWDT can be clocked from either the INTRC or the T1OSC/T1CKI input. If the T1OSC/T1CKI source will be used with a crystal, the T1OSCEN bit in the T1CON register needs to be set prior to entering Deep Sleep. The reference clock source is configured through the DSWDTOSC bit.

DSWDT is enabled through the DSWDTEN bit. Entering Deep Sleep mode automatically clears the DSWDT. See **Section 26.0 "Special Features of the CPU"** for more information.

#### 3.6.5 DEEP SLEEP BROWN-OUT RESET (DSBOR)

The Deep Sleep module contains a dedicated Deep Sleep BOR (DSBOR) circuit. This circuit may be optionally enabled through the DSBOREN Configuration bit.

The DSBOR circuit monitors the VDD supply rail voltage. The behavior of the DSBOR circuit is described in **Section 4.4 "Brown-out Reset (BOR)"**.

## 3.6.6 RTCC PERIPHERAL AND DEEP SLEEP

The RTCC can operate uninterrupted during Deep Sleep mode. It can wake the device from Deep Sleep by configuring an alarm.

The RTCC clock source is configured with the RTCOSC bit (CONFIG3L<1>). The available reference clock sources are the INTRC and T1OSC/T1CKI. If the INTRC is used, the RTCC accuracy will directly depend on the INTRC tolerance.For more information on configuring the RTCC peripheral, see Section 16.0 "Real-Time Clock and Calendar (RTCC)".

## 3.6.7 TYPICAL DEEP SLEEP SEQUENCE

This section gives the typical sequence for using the Deep Sleep mode. Optional steps are indicated, and additional information is given in notes at the end of the procedure.

- 1. Enable DSWDT (optional).<sup>(1)</sup>
- 2. Configure DSWDT clock source (optional).<sup>(2)</sup>
- 3. Enable DSBOR (optional).<sup>(1)</sup>
- 4. Enable RTCC (optional).<sup>(3)</sup>
- 5. Configure the RTCC peripheral (optional).<sup>(3)</sup>
- 6. Configure the ULPWU peripheral (optional).<sup>(4)</sup>
- 7. Enable the INT0 Interrupt (optional).
- 8. Context save SRAM data by writing to the DSGPR0 and DSGPR1 registers (optional).
- 9. Set the REGSLP bit (WDTCON<7>) and clear the IDLEN bit (OSCCON<7>).
- 10. If using an RTCC alarm for wake-up, wait until the RTCSYNC bit (RTCCFG<4>) is clear.
- Enter Deep Sleep mode by setting the DSEN bit (DSCONH<7>) and issuing a SLEEP instruction. These two instructions must be executed back to back.
- 12. Once a wake-up event occurs, the device will perform a POR Reset sequence. Code execution resumes at the device's Reset vector.
- Determine if the device exited Deep Sleep by reading the Deep Sleep bit, DS (WDTCON<3>). This bit will be set if there was an exit from Deep Sleep mode.

- 14. Clear the Deep Sleep bit, DS (WDTCON<3>).
- 15. Determine the wake-up source by reading the DSWAKEH and DSWAKEL registers.
- Determine if a DSBOR event occurred during Deep Sleep mode by reading the DSBOR bit (DSCONL<1>).
- 17. Read the DSGPR0 and DSGPR1 context save registers (optional).
- 18. Clear the RELEASE bit (DSCONL<0>).
  - Note 1: DSWDT and DSBOR are enabled through the devices' Configuration bits. For more information, see Section 26.1 "Configuration Bits".
    - 2: The DSWDT and RTCC clock sources are selected through the devices' Configuration bits. For more information, see Section 26.1 "Configuration Bits".
    - 3: For more information, see Section 16.0 "Real-Time Clock and Calendar (RTCC)".
    - 4: For more information on configuring this peripheral, see Section 3.7 "Ultra Low-Power Wake-up".

## 3.6.8 DEEP SLEEP FAULT DETECTION

If during Deep Sleep, the device is subjected to unusual operating conditions, such as an Electrostatic Discharge (ESD) event, it is possible that internal circuit states used by the Deep Sleep module could become corrupted. If this were to happen, the device may exhibit unexpected behavior, such as a failure to wake back up.

In order to prevent this type of scenario from occurring, the Deep Sleep module includes automatic self-monitoring capability. During Deep Sleep, critical internal nodes are continuously monitored in order to detect possible Fault conditions (which would not ordinarily occur). If a Fault condition is detected, the circuitry will set the DSFLT status bit (DSWAKEL<7>) and automatically wake the microcontroller from Deep Sleep, causing a POR Reset.

During Deep Sleep, the Fault detection circuitry is always enabled and does not require any specific configuration prior to entering Deep Sleep.

#### 3.6.9 DEEP SLEEP MODE REGISTERS

Deep Sleep mode registers are provided in Register 3-1 through Register 3-6.

#### REGISTER 3-1: DSCONH: DEEP SLEEP CONTROL HIGH BYTE REGISTER (BANKED F4Dh)

R/W-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
DSEN <sup>(1)</sup>	—	—	_	—	(Reserved)	DSULPEN	RTCWDIS
bit 7							bit 0

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

- 1 = Deep Sleep mode is entered on a SLEEP command
- 0 = Sleep mode is entered on a SLEEP command
- bit 6-3 Unimplemented: Read as '0'
- bit 2 (Reserved): Always write '0' to this bit
- bit 1 DSULPEN: Ultra Low-Power Wake-up Module Enable bit
  - 1 = ULPWU module is enabled in Deep Sleep
    - 0 = ULPWU module is disabled in Deep Sleep
- bit 0 RTCWDIS: RTCC Wake-up Disable bit
  - 1 = Wake-up from RTCC is disabled
  - 0 = Wake-up from RTCC is enabled
- Note 1: In order to enter Deep Sleep, Sleep must be executed immediately after setting DSEN.

#### **REGISTER 3-2:** DSCONL: DEEP SLEEP LOW BYTE CONTROL REGISTER (BANKED F4Ch)

U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0 <sup>(1)</sup>	R/W-0 <sup>(1)</sup>
—	—		-	—	ULPWDIS	DSBOR	RELEASE
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-3	Unimplemented: Read as '0'
bit 2	ULPWDIS: Ultra Low-Power Wake-up Disable bit
	<ul> <li>1 = ULPWU wake-up source is disabled</li> <li>0 = ULPWU wake-up source is enabled (must also set DSULPEN = 1)</li> </ul>
bit 1	DSBOR: Deep Sleep BOR Event Status bit
	<ul> <li>1 = DSBOREN was enabled and VDD dropped below the DSBOR arming voltage during Deep Sleep, but did not fall below VDSBOR</li> <li>0 = DSBOREN was disabled, or VDD did not drop below the DSBOR arming voltage during Deep Sleep</li> </ul>
bit 0	RELEASE: I/O Pin State Release bit
	Upon waking from Deep Sleep, the I/O pins maintain their previous states. Clearing this bit will release the I/O pins and allow their respective TRIS and LAT bits to control their states.

**Note 1:** This is the value when VDD is initially applied.

#### REGISTER 3-3: DSGPR0: DEEP SLEEP PERSISTENT GENERAL PURPOSE REGISTER 0 (BANKED F4Eh)

	R/W-xxxx <sup>(1)</sup>		
Deep Sleep Per	sistent General Purpose bits		
			bit 0
W = Writable bit	U = Unimplemented bit,	read as '0'	
'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	
	Deep Sleep Per W = Writable bit	•	Deep Sleep Persistent General Purpose bits W = Writable bit U = Unimplemented bit, read as '0'

bit 7-0 Deep Sleep Persistent General Purpose bits Contents are retained even in Deep Sleep mode.

### REGISTER 3-4: DSGPR1: DEEP SLEEP PERSISTENT GENERAL PURPOSE REGISTER 1 (BANKED F4Fh)

	R/W-xxxx <sup>(1)</sup>		
Deep Sleep Per	sistent General Purpose bits		
			bit 0
W = Writable bit	U = Unimplemented bit,	read as '0'	
'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	
	Deep Sleep Per W = Writable bit	-	Deep Sleep Persistent General Purpose bits W = Writable bit U = Unimplemented bit, read as '0'

bit 7-0 Deep Sleep Persistent General Purpose bits Contents are retained even in Deep Sleep mode.

**Note 1:** All register bits are maintained unless: VDDCORE drops below the normal BOR threshold outside of Deep Sleep or the device is in Deep Sleep and the dedicated DSBOR is enabled and VDD drops below the DSBOR threshold, or DSBOR is enabled or disabled, but VDD is hard cycled to near VSS.

**Note 1:** All register bits are maintained unless: VDDCORE drops below the normal BOR threshold outside of Deep Sleep or the device is in Deep Sleep and the dedicated DSBOR is enabled and VDD drops below the DSBOR threshold, or DSBOR is enabled or disabled, but VDD is hard cycled to near VSS.

#### REGISTER 3-5: DSWAKEH: DEEP SLEEP WAKE HIGH BYTE REGISTER (BANKED F4Bh)

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0
—	—	—	—	—	—	—	DSINT0
bit 7							bit 0

Legend:					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-1 Unimplemented: Read as '	0'
----------------------------------	----

bit 0

DSINT0: Interrupt-on-Change bit

1 = Interrupt-on-change was asserted during Deep Sleep

0 = Interrupt-on-change was not asserted during Deep Sleep

#### REGISTER 3-6: DSWAKEL: DEEP SLEEP WAKE LOW BYTE REGISTER (BANKED F4Ah)

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-1
DSFLT	—	DSULP	DSWDT	DSRTC	DSMCLR	—	DSPOR
bit 7							bit 0

Legend:					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7	DSFLT: Deep Sleep Fault Detected bit
	<ul> <li>1 = A Deep Sleep Fault was detected during Deep Sleep</li> <li>0 = A Deep Sleep Fault was not detected during Deep Sleep</li> </ul>
bit 6	Unimplemented: Read as '0'
bit 5	DSULP: Ultra Low-Power Wake-up Status bit
	<ul> <li>1 = An ultra low-power wake-up event occurred during Deep Sleep</li> <li>0 = An ultra low-power wake-up event did not occur during Deep Sleep</li> </ul>
bit 4	DSWDT: Deep Sleep Watchdog Timer Time-out bit
	<ul> <li>1 = The Deep Sleep Watchdog Timer timed out during Deep Sleep</li> <li>0 = The Deep Sleep Watchdog Timer did not time out during Deep Sleep</li> </ul>
bit 3	DSRTC: Real-Time Clock and Calendar Alarm bit
	1 = The Real-Time Clock/Calendar triggered an alarm during Deep Sleep
	0 = The Real-Time Clock /Calendar did not trigger an alarm during Deep Sleep
bit 2	DSMCLR: MCLR Event bit
	1 = The $\overline{MCLR}$ pin was asserted during Deep Sleep
	0 = The MCLR pin was not asserted during Deep Sleep
bit 1	Unimplemented: Read as '0'
bit 0	DSPOR: Power-on Reset Event bit
	1 = The VDD supply POR circuit was active and a POR event was detected <sup>(1)</sup>
	0 = The VDD supply POR circuit was not active, or was active, but did not detect a POR event

Note 1: Unlike the other bits in this register, this bit can be set outside of Deep Sleep.

## 3.7 Ultra Low-Power Wake-up

The Ultra Low-Power Wake-up (ULPWU) on RA0 allows a slow falling voltage to generate an interrupt-on-change without excess current consumption.

Follow these steps to use this feature:

- 1. Configure a remappable output pin to output the ULPOUT signal.
- 2. Map an INTx interrupt-on-change input function to the same pin as used for the ULPOUT output function. Alternatively, in step 1, configure ULPOUT to output onto a PORTB interrupt-on-change pin.
- 3. Charge the capacitor on RA0 by configuring the RA0 pin to an output and setting it to '1'.
- 4. Enable interrupt-on-change (PIE bit) for the corresponding pin selected in step 2.
- 5. Stop charging the capacitor by configuring RA0 as an input.
- 6. Discharge the capacitor by setting the ULPEN and ULPSINK bits in the WDTCON register.
- 7. Configure Sleep mode.
- 8. Enter Sleep mode.

When the voltage on RA0 drops below VIL, an interrupt will be generated, which will cause the device to wake-up and execute the next instruction.

This feature provides a low-power technique for periodically waking up the device from Sleep mode. The time-out is dependent on the discharge time of the RC circuit on RA0.


When the ULPWU module causes the device to wake-up from Sleep mode, the WDTCON<ULPLVL> bit is set. When the ULPWU module causes the device to wake-up from Deep Sleep, the DSULP (DSWAKEL<5>) bit is set. Software can check these bits upon wake-up to determine the wake-up source. Also in Sleep mode, only the remappable output function, ULPWU, will output this bit value to an RPn pin for externally detecting wake-up events.

See Example 3-1 for initializing the ULPWU module.

Note:	For module-related bit definitions, see the									
	WDTCON register in Section 26.2									
	"Watchdog Timer (WDT)" and the									
	DSWAKEL register (Register 3-6).									

A series resistor between RA0 and the external capacitor provides overcurrent protection for the RA0/AN0/C1INA/ULPWU/RP0 pin and can allow for software calibration of the time-out (see Figure 3-9).

FIGURE 3-9: SERIAL RESISTOR



A timer can be used to measure the charge time and discharge time of the capacitor. The charge time can then be adjusted to provide the desired interrupt delay. This technique will compensate for the affects of temperature, voltage and component accuracy. The ULPWU peripheral can also be configured as a simple Programmable Low-Voltage Detect (LVD) or temperature sensor.

Note:	For more information, refer to AN879,
	"Using the Microchip Ultra Low-Power
	Wake-up Module" application note
	(DS00879).

#### EXAMPLE 3-1: ULTRA LOW-POWER WAKE-UP INITIALIZATION

```
//Configure a remappable output pin with interrupt capability
     //for ULPWU function (RP21 => RD4/INT1 in this example)
     *****
     RPOR21 = 13;// ULPWU function mapped to RP21/RD4
     RPINR1 = 21;// INT1 mapped to RP21 (RD4)
     //***********************
     //Charge the capacitor on RAO
     //****************************
     TRISAbits.TRISA0 = 0;
     PORTAbits.RA0 = 1;
     for(i = 0; i < 10000; i++) Nop();
     //Stop Charging the capacitor on RAO
     TRISAbits.TRISA0 = 1;
     //Enable the Ultra Low Power Wakeup module
     //and allow capacitor discharge
     WDTCONbits.ULPEN = 1;
     WDTCONbits.ULPSINK = 1;
     //Enable Interrupt for ULPW
     //For Sleep
     //(assign the ULPOUT signal in the PPS module to a pin
     //which has also been assigned an interrupt capability,
     //such as INT1)
     INTCON3bits.INT1IF = 0;
     INTCON3bits.INT1IE = 1;
     //***************
     //Configure Sleep Mode
     //For Sleep
     OSCCONDits.IDLEN = 0;
     //For Deep Sleep
     OSCCONbits.IDLEN = 0; // enable deep sleep
     DSCONHbits.DSEN = 1; // Note: must be set just before executing Sleep();
     //**********
     //Enter Sleep Mode
     //************
     Sleep();
     // for sleep, execution will resume here
     // for deep sleep, execution will restart at reset vector (use WDTCONbits.DS to detect)
```

NOTES:

## 4.0 RESET

The PIC18F46J50 Family of devices differentiate among various kinds of Reset:

- a) Power-on Reset (POR)
- b) MCLR Reset during normal operation
- c) MCLR Reset during power-managed modes
- d) Watchdog Timer (WDT) Reset (during execution)
- e) Configuration Mismatch (CM)
- f) Brown-out Reset (BOR)
- g) RESET Instruction
- h) Stack Full Reset
- i) Stack Underflow Reset
- j) Deep Sleep Reset

This section discusses Resets generated by  $\overline{\text{MCLR}}$ , POR and BOR, and covers the operation of the various start-up timers.


For information on WDT Resets, see Section 26.2 "Watchdog Timer (WDT)". For Stack Reset events, see Section 5.1.4.4 "Stack Full and Underflow Resets" and for Deep Sleep mode, see Section 3.6 "Deep Sleep Mode".

Figure 4-1 provides a simplified block diagram of the on-chip Reset circuit.

## 4.1 RCON Register

Device Reset events are tracked through the RCON register (Register 4-1). The lower five bits of the register indicate that a specific Reset event has occurred. In most cases, these bits can only be set by the event and must be cleared by the application after the event. The state of these flag bits, taken together, can be read to indicate the type of Reset that just occurred. This is described in more detail in **Section 4.7 "Reset State of Registers"**.





R/W-0	U-0	R/W-1	R/W-1	R-1	R-1	R/W-0	R/W-0
IPEN	_	CM	RI	TO	PD	POR	BOR
bit 7							bit C
Legend:							
R = Reada		W = Writable		-	mented bit, rea		
-n = Value	at POR	'1' = Bit is set		'0' = Bit is cl	eared	x = Bit is unkr	nown
bit 7	IPEN. Interru	pt Priority Enal	ole hit				
bit i		priority levels or					
		priority levels o		PIC16CXXX C	ompatibility mo	de)	
bit 6	Unimplemer	nted: Read as '	0'				
bit 5	CM: Configu	ration Mismatcl	n Flag bit				
	-	uration Mismat					
		guration Misma h Reset occurs		is occurred (m	nust be set in a	software after a	Configuratio
bit 4		struction Flag b					
Sit 1		ET instruction		uted (set by firi	mware onlv)		
	0 = The RES	SET instruction	was execute			nust be set in so	oftware after a
		ut Reset occurs	,				
bit 3		og Time-out Fla	-				
		ower-up, CLRW		OF SLEEP INST	ruction		
bit 2	PD: Power-D	own Detection	Flag bit				
		ower-up or by t	•	struction			
	0 = Set by e	xecution of the	SLEEP instru	ction			
bit 1		-on Reset Statu					
		-on Reset has				r on Dooot oogu	ro)
bit 0		-on Reset occu	•	e set in soltwar	e aller a Powe	r-on Reset occu	is)
DILU		n-out Reset Stat		l (set by firmw	are only)		
						vn-out Reset occ	curs)
			•				
Note 1:	It is recommende Power-on Resets			er a Power-on	Reset has beer	n detected, so th	at subsequer
2:	If the on-chip vol <b>BOR</b> " for more ir	• •	is disabled, $\overline{B}$	OR remains '	)' at all times. S	See Section 4.4	.1 "Detectin
3:	Brown-out Reset '1' by software in				and $\overline{POR}$ is '1' (	assuming that $\overline{P}$	OR was set t

## REGISTER 4-1: RCON: RESET CONTROL REGISTER (ACCESS FD0h)

## 4.2 Master Clear (MCLR)

The Master Clear Reset (MCLR) pin provides a method for triggering a hard external Reset of the device. A Reset is generated by holding the pin low. PIC18 extended microcontroller devices have a noise filter in the MCLR Reset path, which detects and ignores small pulses.

The  $\overline{\text{MCLR}}$  pin is not driven low by any internal Resets, including the WDT.

## 4.3 Power-on Reset (POR)

A POR condition is generated on-chip whenever VDD rises above a certain threshold. This allows the device to start in the initialized state when VDD is adequate for operation.

To take advantage of the POR circuitry, tie the  $\overline{\text{MCLR}}$  pin through a resistor (1 k $\Omega$  to 10 k $\Omega$ ) to VDD. This will eliminate external RC components usually needed to create a POR delay.

When the device starts normal operation (i.e., exits the Reset condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met.

POR events are captured by the  $\overrightarrow{POR}$  bit (RCON<1>). The state of the bit is set to '0' whenever a Power-on Reset occurs; it does not change for any other Reset event.  $\overrightarrow{POR}$  is not reset to '1' by any hardware event. To capture multiple events, the user manually resets the bit to '1' in software following any POR.

## 4.4 Brown-out Reset (BOR)

The "F" devices in the PIC18F46J50 Family incorporate two types of BOR circuits: one which monitors VDDCORE and one which monitors VDD. Only one BOR circuit can be active at a time. When in normal Run mode, Idle or normal Sleep modes, the BOR circuit that monitors VDDCORE is active and will cause the device to be held in BOR if VDDCORE drops below VBOR (parameter D005). Once VDDCORE rises back above VBOR, the device will be held in Reset until the expiration of the Power-up Timer, with period, TPWRT (parameter 33).

During Deep Sleep operation, the on-chip core voltage regulator is disabled and VDDCORE is allowed to drop to Vss. If the Deep Sleep BOR circuit is enabled by the DSBOREN bit (CONFIG3L<2> = 1), it will monitor VDD. If VDD drops below the VDSBOR threshold, the device will be held in a Reset state similar to POR. All registers

will be set back to their POR Reset values and the contents of the DSGPR0 and DSGPR1 holding registers will be lost. Additionally, if any I/O pins had been configured as outputs during Deep Sleep, these pins will be tri-stated and the device will no longer be held in Deep Sleep. Once the VDD voltage recovers back above the VDSBOR threshold, and once the core voltage regulator achieves a VDDCORE voltage above VBOR, the device will begin executing code again normally, but the DS bit in the WDTCON register will not be set. The device behavior will be similar to hard cycling all power to the device.

On "LF" devices (ex: PIC18LF46J50), the VDDCORE BOR circuit is always disabled because the internal core voltage regulator is disabled. Instead of monitoring VDDCORE, PIC18LF devices in this family can still use the VDD BOR circuit to monitor VDD excursions below the VDSBOR threshold. The VDD BOR circuit can be disabled by setting the DSBOREN bit = 0.

The VDD BOR circuit is enabled when DSBOREN = 1 on "LF" devices, or on "F" devices while in Deep Sleep with DSBOREN = 1. When enabled, the VDD BOR circuit is extremely low power (typ. 200nA) during normal operation above ~2.3V on VDD. If VDD drops below this DSBOR arming level when the VDD BOR circuit is enabled, the device may begin to consume additional current (typ. 50  $\mu$ A) as internal features of the circuit power-up. The higher current is necessary to achieve more accurate sensing of the VDD level. However, the device will not enter Reset until VDD falls below the VDSBOR threshold.

## 4.4.1 DETECTING BOR

The BOR bit always resets to '0' on any VDDCORE BOR or POR event. This makes it difficult to determine if a Brown-out Reset event has occurred just by reading the state of BOR alone. A more reliable method is to simultaneously check the state of both POR and BOR. This assumes that the POR bit is reset to '1' in software immediately after any Power-on Reset event. If BOR is '0' while POR is '1', it can be reliably assumed that a Brown-out Reset event has occurred.

If the voltage regulator is disabled (LF device), the VDDCORE BOR functionality is disabled. In this case, the BOR bit cannot be used to determine a Brown-out Reset event. The BOR bit is still cleared by a Power-on Reset event.

## 4.5 Configuration Mismatch (CM)

The Configuration Mismatch (CM) Reset is designed to detect, and attempt to recover from, random memory corrupting events. These include Electrostatic Discharge (ESD) events, which can cause widespread single-bit changes throughout the device, and result in catastrophic failure.

In PIC18FXXJ Flash devices, the device Configuration registers (located in the configuration memory space) are continuously monitored during operation by comparing their values to complimentary shadow registers. If a mismatch is detected between the two sets of registers, a CM Reset automatically occurs. These events are captured by the CM bit (RCON<5>). The state of the bit is set to '0' whenever a CM event occurs; it does not change for any other Reset event.

A CM Reset behaves similarly to a MCLR, RESET instruction, WDT time-out or Stack Event Resets. As with all hard and power Reset events, the device Configuration Words are reloaded from the Flash Configuration Words in program memory as the device restarts.

## 4.6 **Power-up Timer (PWRT)**

PIC18F46J50 Family devices incorporate an on-chip PWRT to help regulate the POR process. The PWRT is always enabled. The main function is to ensure that the device voltage is stable before code is executed.

The Power-up Timer (PWRT) of the PIC18F46J50 Family devices is a 5-bit counter which uses the INTRC source as the clock input. This yields an approximate time interval of  $32 \times 32 \ \mu s = 1 \ ms$ . While the PWRT is counting, the device is held in Reset.


The power-up time delay depends on the INTRC clock and will vary from chip-to-chip due to temperature and process variation. See DC parameter 33 (TPWRT) for details.


#### 4.6.1 TIME-OUT SEQUENCE

The PWRT time-out is invoked after the POR pulse has cleared. The total time-out will vary based on the status of the PWRT. Figure 4-2, Figure 4-3, Figure 4-4 and Figure 4-5 all depict time-out sequences on power-up with the PWRT.

Since the time-outs occur from the POR pulse, if  $\overline{\text{MCLR}}$ is kept low long enough, the PWRT will expire. Bringing  $\overline{\text{MCLR}}$  high will begin execution immediately if a clock source is available (Figure 4-4). This is useful for testing purposes, or to synchronize more than one PIC18F device operating in parallel.

## FIGURE 4-2: TIME-OUT SEQUENCE ON POWER-UP (MCLR TIED TO VDD, VDD RISE < TPWRT)





### FIGURE 4-4: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2





FIGURE 4-5: SLOW RISE TIME (MCLR TIED TO VDD, VDD RISE > TPWRT)



## 4.7 Reset State of Registers

Most registers are unaffected by a Reset. Their status is unknown on POR and unchanged by all other Resets. The other registers are forced to a "Reset state" depending on the type of Reset that occurred.

Most registers are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. Status bits from the RCON register (CM, RI,

TO, PD, POR and BOR) are set or cleared differently in different Reset situations, as indicated in Table 4-1. These bits are used in software to determine the nature of the Reset.

Table 4-2 describes the Reset states for all of the Special Function Registers. These are categorized by POR and BOR, MCLR and WDT Resets and WDT wake-ups.

TABLE 4-1:	STATUS BITS, THEIR SIGNIFICANCE AND THE INITIALIZATION CONDITION FOR
	RCON REGISTER

O an althin in	Program			RCON	Register			STKPTR Register	
Condition	Counter <sup>(1)</sup>	CM	RI	ТО	PD	POR	BOR	STKFUL	STKUNF
Power-on Reset	0000h	1	1	1	1	0	0	0	0
RESET instruction	0000h	u	0	u	u	u	u	u	u
Brown-out Reset	0000h	1	1	1	1	u	0	u	u
Configuration Mismatch Reset	0000h	0	u	u	u	u	u	u	u
MCLR Reset during power-managed Run modes	0000h	u	u	1	u	u	u	u	u
MCLR Reset during power-managed Idle modes and Sleep mode	0000h	u	u	1	0	u	u	u	u
MCLR Reset during full-power execution	0000h	u	u	u	u	u	u	u	u
Stack Full Reset (STVREN = 1)	0000h	u	u	u	u	u	u	1	u
Stack Underflow Reset (STVREN = 1)	0000h	u	u	u	u	u	u	u	1
Stack Underflow Error (not an actual Reset, STVREN = 0)	0000h	u	u	u	u	u	u	u	1
WDT time-out during full-power or power-managed Run modes	0000h	u	u	0	u	u	u	u	u
WDT time-out during power-managed Idle or Sleep modes	PC + 2	u	u	0	0	u	u	u	u
Interrupt exit from power-managed modes	PC + 2	u	u	u	0	u	u	u	u

Legend: u = unchanged

**Note 1:** When the wake-up is due to an interrupt and the GIEH or GIEL bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

Register		e Devices	NS FOR ALL REGI Power-on Reset, Brown-out Reset, Wake From Deep Sleep	MCLR Resets WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt
TOSU	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	0 0000 <b>(1)</b>
тоѕн	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu <b>(1)</b>
TOSL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu <b>(1)</b>
STKPTR	PIC18F2XJ50	PIC18F4XJ50	00-0 0000	uu-0 0000	uu-u uuuu <b>(1)</b>
PCLATU	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PCLATH	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	นนนน นนนน
PCL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	PC + 2 <sup>(2)</sup>
TBLPTRU	PIC18F2XJ50	PIC18F4XJ50	00 0000	00 0000	uu uuuu
TBLPTRH	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
TBLPTRL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
TABLAT	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PRODH	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu
PRODL	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	սսսս սսսս	uuuu uuuu
INTCON	PIC18F2XJ50	PIC18F4XJ50	0000 000x	0000 000u	uuuu uuuu <sup>(3)</sup>
INTCON2	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu <sup>(3)</sup>
INTCON3	PIC18F2XJ50	PIC18F4XJ50	1100 0000	1100 0000	uuuu uuuu <sup>(3)</sup>
INDF0	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
POSTINC0	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
POSTDEC0	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
PREINC0	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
PLUSW0	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
FSR0H	PIC18F2XJ50	PIC18F4XJ50	xxxx	uuuu	uuuu
FSR0L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu
WREG	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu
INDF1	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
POSTINC1	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
POSTDEC1	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
PREINC1	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
PLUSW1	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A
FSR1H	PIC18F2XJ50	PIC18F4XJ50	xxxx	uuuu	uuuu
FSR1L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	นนนน นนนน	นนนน นนนน
BSR	PIC18F2XJ50	PIC18F4XJ50	0000	0000	uuuu
INDF2	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A

### TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

- 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
- 3: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).
- **4**: See Table 4-1 for Reset value for specific condition.
- **5**: Not implemented for PIC18F2XJ50 devices.

TABLE 4-2:	INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)					
Register	Applicabl	e Devices	Power-on Reset, Brown-out Reset, Wake From Deep Sleep	MCLR Resets WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt	
POSTINC2	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A	
POSTDEC2	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A	
PREINC2	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A	
PLUSW2	PIC18F2XJ50	PIC18F4XJ50	N/A	N/A	N/A	
FSR2H	PIC18F2XJ50	PIC18F4XJ50	xxxx	uuuu	uuuu	
FSR2L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	นนนน นนนน	սսսս սսսս	
STATUS	PIC18F2XJ50	PIC18F4XJ50	x xxxx	u uuuu	u uuuu	
TMR0H	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս	
TMR0L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	นนนน นนนน	սսսս սսսս	
T0CON	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu	
OSCCON	PIC18F2XJ50	PIC18F4XJ50	0110 q000	0110 q000	0110 q00u	
CM1CON	PIC18F2XJ50	PIC18F4XJ50	0001 1111	uuuu uuuu	uuuu uuuu	
CM2CON	PIC18F2XJ50	PIC18F4XJ50	0001 1111	uuuu uuuu	uuuu uuuu	
RCON <sup>(4)</sup>	PIC18F2XJ50	PIC18F4XJ50	0-11 1100	0-qq qquu	u-qq qquu	
TMR1H	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu	
TMR1L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu	
T1CON	PIC18F2XJ50	PIC18F4XJ50	0000 0000	u0uu uuuu	uuuu uuuu	
TMR2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	
PR2	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu	
T2CON	PIC18F2XJ50	PIC18F4XJ50	-000 0000	-000 0000	-uuu uuuu	
SSP1BUF	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu	
SSP1ADD	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	
SSP1MSK	PIC18F2XJ50	PIC18F4XJ50	1111 1111	uuuu uuuu	uuuu uuuu	
SSP1STAT	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	
SSP1CON1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	
SSP1CON2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս	
ADRESH	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	սսսս սսսս	սսսս սսսս	
ADRESL	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	นนนน นนนน	սսսս սսսս	
ADCON0	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	
ADCON1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	
WDTCON	PIC18F2XJ50	PIC18F4XJ50	1qq- 0000	0qq- 0000	uqq- uuuu	
PSTR1CON	PIC18F2XJ50	PIC18F4XJ50	00-0 0001	00-0 0001	uu-u uuuu	
ECCP1AS	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu	

## TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

**2:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- **4:** See Table 4-1 for Reset value for specific condition.
- **5:** Not implemented for PIC18F2XJ50 devices.

TABLE 4-2: Register		e Devices	Power-on Reset, Brown-out Reset, Wake From Deep Sleep	STERS (CONTINUED MCLR Resets WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
		1	Oleeh	CM Resets	
ECCP1DEL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
CCPR1H	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	սսսս սսսս	սսսս սսսս
CCPR1L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	սսսս սսսս	սսսս սսսս
CCP1CON	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
PSTR2CON	PIC18F2XJ50	PIC18F4XJ50	00-0 0001	00-0 0001	uu-u uuuu
ECCP2AS	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
ECCP2DEL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
CCPR2H	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	սսսս սսսս	սսսս սսսս
CCPR2L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	սսսս սսսս	սսսս սսսս
CCP2CON	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
CTMUCONH	PIC18F2XJ50	PIC18F4XJ50	0-00 000-	0-00 000-	u-uu uuu-
CTMUCONL	PIC18F2XJ50	PIC18F4XJ50	0000 00xx	0000 00xx	uuuu uuuu
CTMUICON	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
SPBRG1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
RCREG1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
TXREG1	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXSTA1	PIC18F2XJ50	PIC18F4XJ50	0000 0010	0000 0010	սսսս սսսս
RCSTA1	PIC18F2XJ50	PIC18F4XJ50	0000 000x	0000 000x	սսսս սսսս
SPBRG2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
RCREG2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
TXREG2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
TXSTA2	PIC18F2XJ50	PIC18F4XJ50	0000 0010	0000 0010	սսսս սսսս
EECON2	PIC18F2XJ50	PIC18F4XJ50			
EECON1	PIC18F2XJ50	PIC18F4XJ50	00 x00-	00 u00-	00 u00-
IPR3	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	սսսս սսսս
PIR3	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu <sup>(3)</sup>
PIE3	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
IPR2	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu
PIR2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu <sup>(3)</sup>
PIE2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
IPR1	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu
PIR1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu <sup>(3)</sup>
PIE1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս

### TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, – = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- 4: See Table 4-1 for Reset value for specific condition.
- 5: Not implemented for PIC18F2XJ50 devices.

TABLE 4-2:	INITIALIZAT	ALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)					
Register	Applicable Devices		eter Applicable Devices Power-on Reset, Wake From Deep Sleep	MCLR Resets WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt		
RCSTA2	PIC18F2XJ50	PIC18F4XJ50	0000 000x	0000 000x	uuuu uuuu		
OSCTUNE	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	นนนน นนนน		
T1GCON	PIC18F2XJ50	PIC18F4XJ50	0000 0x00	0000 0x00	นนนน นนนน		
RTCVALH	PIC18F2XJ50	PIC18F4XJ50	0xxx xxxx	0uuu uuuu	0uuu uuuu		
RTCVALL	PIC18F2XJ50	PIC18F4XJ50	0xxx xxxx	Ouuu uuuu	Ouuu uuuu		
T3GCON	PIC18F2XJ50	PIC18F4XJ50	00x0 0x00	uuuu uxuu	uuuu uxuu		
TRISE <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	111	111	uuu		
TRISD <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu		
TRISC	PIC18F2XJ50	PIC18F4XJ50	11111	11111	uuuuu		
TRISB	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	uuuu uuuu		
TRISA	PIC18F2XJ50	PIC18F4XJ50	111- 1111	111- 1111	uuu- uuuu		
ALRMCFG	PIC18F2XJ50	PIC18F4XJ50	0000 0000	uuuu uuuu	uuuu uuuu		
ALRMRPT	PIC18F2XJ50	PIC18F4XJ50	0000 0000	uuuu uuuu	uuuu uuuu		
ALRMVALH	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu		
ALRMVALL	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu		
LATE <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	xxx	uuu	uuu		
LATD <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu		
LATC	PIC18F2XJ50	PIC18F4XJ50	XXXXX	uuuuu	uuuuu		
LATB	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu		
LATA	PIC18F2XJ50	PIC18F4XJ50	XXX- XXXX	uuu- uuuu	uuu- uuuu		
DMACON1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu		
DMACON2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu		
HLVDCON	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu		
PORTE <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	00xxx	uuuuu	uuuuu		
PORTD <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu		
PORTC	PIC18F2XJ50	PIC18F4XJ50	XXXX -XXX	uuuu -uuu	uuuu -uuu		
PORTB	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu		
PORTA	PIC18F2XJ50	PIC18F4XJ50	xxx- xxxx	uuu- uuuu	uuu- uuuu		
SPBRGH1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu		
BAUDCON1	PIC18F2XJ50	PIC18F4XJ50	0100 0-00	0100 0-00	uuuu u-uu		
SPBRGH2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu		
BAUDCON2	PIC18F2XJ50	PIC18F4XJ50	0100 0-00	0100 0-00	uuuu u-uu		

### TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- **4:** See Table 4-1 for Reset value for specific condition.
- **5**: Not implemented for PIC18F2XJ50 devices.

TABLE 4-2:       INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)         Power-on Reset,       MCLR Resets					') 
Register	Applicabl	e Devices	Brown-out Reset, Brown-out Reset, Wake From Deep Sleep	WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt
TMR3H	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	นนนน นนนน	սսսս սսսս
TMR3L	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	นนนน นนนน	นนนน นนนน
T3CON	PIC18F2XJ50	PIC18F4XJ50	0000 0000	นนนน นนนน	นนนน นนนน
TMR4	PIC18F2XJ50	PIC18F4XJ50	0000 0000	นนนน นนนน	սսսս սսսս
PR4	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	սսսս սսսս
T4CON	PIC18F2XJ50	PIC18F4XJ50	-000 0000	-000 0000	-uuu uuuu
SSP2BUF	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	uuuu uuuu	uuuu uuuu
SSP2ADD	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
SSP2MASK	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
SSP2STAT	PIC18F2XJ50	PIC18F4XJ50	1111 1111	1111 1111	սսսս սսսս
SSP2CON1	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
SSP2CON2	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
CMSTAT	PIC18F2XJ50	PIC18F4XJ50	11	11	uu
PMADDRH <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	-000 0000	-000 0000	-uuu uuuu
PMDOUT1H <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMADDRL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
PMDOUT1L	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
PMDIN1H	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMDIN1L	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
TXADDRL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
TXADDRH	PIC18F2XJ50	PIC18F4XJ50	0000	0000	uuuu
RXADDRL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
RXADDRH	PIC18F2XJ50	PIC18F4XJ50	0000	0000	uuuu
DMABCL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	սսսս սսսս
DMABCH	PIC18F2XJ50	PIC18F4XJ50	00	00	uu
UCON	PIC18F2XJ50	PIC18F4XJ50	-0x0 000-	-0x0 0x0-	-uuu uuu-
USTAT	PIC18F2XJ50	PIC18F4XJ50	-xxx xxx-	-XXX XXX-	-uuu uuu-
UEIR	PIC18F2XJ50	PIC18F4XJ50	00 0000	00 0000	uu uuuu
UIR	PIC18F2XJ50	PIC18F4XJ50	-000 0000	-000 0000	-uuu uuuu
UFRMH	PIC18F2XJ50	PIC18F4XJ50	xxx	xxx	uuu
UFRML	PIC18F2XJ50	PIC18F4XJ50	XXXX XXXX	XXXXX XXXX	սսսս սսսս
PMCONH	PIC18F2XJ50	PIC18F4XJ50	0-00 0000	0-00 0000	u-uu uuuu
PMCONL	PIC18F2XJ50	PIC18F4XJ50	000- 0000	000- 0000	uuu- uuuu

## TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- 4: See Table 4-1 for Reset value for specific condition.
- 5: Not implemented for PIC18F2XJ50 devices.

TABLE 4-2:	2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)				
Register	Applicabl	e Devices	Power-on Reset, Brown-out Reset, Wake From Deep Sleep	MCLR Resets WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt
PMMODEH	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMMODEL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMDOUT2H	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMDOUT2L	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	นนนน นนนน
PMDIN2H	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	นนนน นนนน
PMDIN2L	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	นนนน นนนน
PMEH	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMEL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
PMSTATH	PIC18F2XJ50	PIC18F4XJ50	00 0000	00 0000	uu uuuu
PMSTATL	PIC18F2XJ50	PIC18F4XJ50	10 1111	10 1111	uu uuuu
CVRCON <sup>(5)</sup>	PIC18F2XJ50	PIC18F4XJ50	0000 0000	0000 0000	uuuu uuuu
ANCON1	PIC18F2XJ50	PIC18F4XJ50	00-0 0000	uu-u uuuu	uu-u uuuu
ANCON0	PIC18F2XJ50	PIC18F4XJ50	0000 0000	uuuu uuuu	սսսս սսսս
ODCON1	PIC18F2XJ50	PIC18F4XJ50	00	uu	uu
ODCON2	PIC18F2XJ50	PIC18F4XJ50	00	uu	uu
ODCON3	PIC18F2XJ50	PIC18F4XJ50	00	uu	uu
RTCCFG	PIC18F2XJ50	PIC18F4XJ50	0-00 0000	u-uu uuuu	u-uu uuuu
RTCCAL	PIC18F2XJ50	PIC18F4XJ50	0000 0000	uuuu uuuu	uuuu uuuu
REFOCON	PIC18F2XJ50	PIC18F4XJ50	0-00 0000	u-uu uuuu	u-uu uuuu
PADCFG1	PIC18F2XJ50	PIC18F4XJ50	000	uuu	uuu
UCFG	PIC18F2XJ50	PIC18F4XJ50	00-0 0000	00-0 0000	uu-u uuuu
UADDR	PIC18F2XJ50	PIC18F4XJ50	-000 0000	-uuu uuuu	-uuu uuuu
UEIE	PIC18F2XJ50	PIC18F4XJ50	00 0000	00 0000	uu uuuu
UIE	PIC18F2XJ50	PIC18F4XJ50	-000 0000	-000 0000	-uuu uuuu
UEP15	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP14	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP13	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP12	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP11	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP10	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP9	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP8	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
UEP7	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu

### TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

**2:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- **4:** See Table 4-1 for Reset value for specific condition.
- **5:** Not implemented for PIC18F2XJ50 devices.

TABLE 4-2:       INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)				
Applicabl	e Devices	Power-on Reset, Brown-out Reset, Wake From Deep Sleep	MCLR Resets WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	1 1111	1 1111	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
	Applicabl           PIC18F2XJ50           PIC18F2XJ	Applicable Devices           PIC18F2XJ50         PIC18F4XJ50           PIC18F2XJ50         PIC18F4XJ50 <td>Applicable Devices         Power-on Reset, Brown-out Reset, Wake From Deep Sleep           PIC18F2XJ50         PIC18F4XJ50        0         0000           PIC18F2XJ50         PIC18F4XJ50        1         1111           PIC18F2XJ50         PIC18F4XJ50        1<td>Applicable Devices         Power-on Reset, Brown-out Reset, Wake From Deep Sleep         MCLR Resets WDT Reset RESET Instruction Stack Resets           PIC18F2XJ50         PIC18F4XJ50        0         0000        0         0000           PIC18F2XJ50         PIC18F4XJ50        1         1111        1         1111           PIC18F2XJ50         PIC18F4XJ50        1         1111        1         1111</td></td>	Applicable Devices         Power-on Reset, Brown-out Reset, Wake From Deep Sleep           PIC18F2XJ50         PIC18F4XJ50        0         0000           PIC18F2XJ50         PIC18F4XJ50        1         1111           PIC18F2XJ50         PIC18F4XJ50        1 <td>Applicable Devices         Power-on Reset, Brown-out Reset, Wake From Deep Sleep         MCLR Resets WDT Reset RESET Instruction Stack Resets           PIC18F2XJ50         PIC18F4XJ50        0         0000        0         0000           PIC18F2XJ50         PIC18F4XJ50        1         1111        1         1111           PIC18F2XJ50         PIC18F4XJ50        1         1111        1         1111</td>	Applicable Devices         Power-on Reset, Brown-out Reset, Wake From Deep Sleep         MCLR Resets WDT Reset RESET Instruction Stack Resets           PIC18F2XJ50         PIC18F4XJ50        0         0000        0         0000           PIC18F2XJ50         PIC18F4XJ50        1         1111        1         1111           PIC18F2XJ50         PIC18F4XJ50        1         1111        1         1111

## TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- 4: See Table 4-1 for Reset value for specific condition.
- 5: Not implemented for PIC18F2XJ50 devices.

Register	Applicable Devices		Power-on Reset, Brown-out Reset, Wake From Deep Sleep	MCLR Resets WDT Reset RESET Instruction Stack Resets CM Resets	Wake-up via WDT or Interrupt
RPOR10	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR9	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR8	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR7	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR6	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR5	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR4	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR3	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR2	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR1	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu
RPOR0	PIC18F2XJ50	PIC18F4XJ50	0 0000	0 0000	u uuuu

### TABLE 4-2: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition.

**Note 1:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

**2:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

3: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

4: See Table 4-1 for Reset value for specific condition.

5: Not implemented for PIC18F2XJ50 devices.

## 5.0 MEMORY ORGANIZATION

There are two types of memory in PIC18 Flash microcontrollers:

- Program Memory
- Data RAM

As Harvard architecture devices, the data and program memories use separate busses; this allows for concurrent access of the two memory spaces.

Section 6.0 "Flash Program Memory" provides additional information on the operation of the Flash program memory.


### 5.1 Program Memory Organization

PIC18 microcontrollers implement a 21-bit program counter, which is capable of addressing a 2-Mbyte program memory space. Accessing a location between the upper boundary of the physically implemented memory and the 2-Mbyte address returns all '0's (a NOP instruction).

The PIC18F46J50 Family offers a range of on-chip Flash program memory sizes, from 16 Kbytes (up to 8,192 single-word instructions) to 64 Kbytes (32,768 single-word instructions).

Figure 5-1 provides the program memory maps for individual family devices.






### 5.1.1 HARD MEMORY VECTORS

All PIC18 devices have a total of three hard-coded return vectors in their program memory space. The Reset vector address is the default value to which the program counter returns on all device Resets; it is located at 0000h.

PIC18 devices also have two interrupt vector addresses for handling high-priority and low-priority interrupts. The high-priority interrupt vector is located at 0008h and the low-priority interrupt vector at 0018h. Figure 5-2 provides their locations in relation to the program memory map.

#### FIGURE 5-2: HARD VECTOR AND CONFIGURATION WORD LOCATIONS FOR PIC18F46J50 FAMILY DEVICES



## 5.1.2 FLASH CONFIGURATION WORDS

Because PIC18F46J50 Family devices do not have persistent configuration memory, the top four words of on-chip program memory are reserved for configuration information. On Reset, the configuration information is copied into the Configuration registers.

The Configuration Words are stored in their program memory location in numerical order, starting with the lower byte of CONFIG1 at the lowest address and ending with the upper byte of CONFIG4.

Table 5-1 provides the actual addresses of the Flash Configuration Word for devices in the PIC18F46J50 Family. Figure 5-2 displays their location in the memory map with other memory vectors.

Additional details on the device Configuration Words are provided in **Section 26.1** "**Configuration Bits**".

TABLE 5-1:	FLASH CONFIGURATION WORD FOR PIC18F46J50 FAMILY DEVICES

Device	Program Memory (Kbytes)	Configuration Word Addresses	
PIC18F24J50	16	3FF8h to 3FFFh	
PIC18F44J50	10		
PIC18F25J50	32	7FF8h to 7FFFh	
PIC18F45J50	32		
PIC18F26J50	64	FFF8h to FFFFh	
PIC18F46J50	04		

### 5.1.3 PROGRAM COUNTER

The Program Counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21 bits wide and is contained in three separate 8-bit registers. The low byte, known as the PCL register, is both readable and writable. The high byte, or PCH register, contains the PC<15:8> bits; it is not directly readable or writable. Updates to the PCH register are performed through the PCLATH register. The upper byte is called PCU. This register contains the PC<20:16> bits; it is also not directly readable or writable. Updates to the PCH register. Updates to the PCU register are performed through the PCLATH register contains the PC<20:16> bits; it is also not directly readable or writable. Updates to the PCU register are performed through the PCLATU register.

The contents of PCLATH and PCLATU are transferred to the program counter by any operation that writes to PCL. Similarly, the upper 2 bytes of the program counter are transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see **Section 5.1.6.1 "Computed GOTO"**).

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the Least Significant bit (LSb) of PCL is fixed to a value of '0'. The PC increments by two to address sequential instructions in the program memory.

The CALL, RCALL, GOTO and program branch instructions write to the program counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the program counter.

### 5.1.4 RETURN ADDRESS STACK

The return address stack allows any combination of up to 31 program calls and interrupts to occur. The PC is pushed onto the stack when a CALL or RCALL instruction is executed, or an interrupt is Acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction (and on ADDULNK and SUBULNK instructions if the extended instruction set is enabled). PCLATU and PCLATH are not affected by any of the RETURN or CALL instructions. The stack operates as a 31-word by 21-bit RAM and a 5-bit Stack Pointer (SP), STKPTR. The stack space is not part of either program or data space. The Stack Pointer is readable and writable and the address on the top of the stack is readable and writable through the Top-of-Stack Special Function Registers (SFRs). Data can also be pushed to, or popped from the stack, using these registers.

A CALL type instruction causes a push onto the stack. The Stack Pointer is first incremented and the location pointed to by the Stack Pointer is written with the contents of the PC (already pointing to the instruction following the CALL). A RETURN type instruction causes a pop from the stack. The contents of the location pointed to by the STKPTR are transferred to the PC and then the Stack Pointer is decremented.


The Stack Pointer is initialized to '00000' after all Resets. There is no RAM associated with the location corresponding to a Stack Pointer value of '00000'; this is only a Reset value. Status bits indicate if the stack is full, has overflowed or has underflowed.

### 5.1.4.1 Top-of-Stack Access

Only the top of the return address stack (TOS) is readable and writable. A set of three registers, TOSU:TOSH:TOSL, holds the contents of the stack location pointed to by the STKPTR register (Figure 5-3). This allows users to implement a software stack if necessary. After a CALL, RCALL or interrupt (and ADDULNK and SUBULNK instructions if the extended instruction set is enabled), the software can read the pushed value by reading the TOSU:TOSH:TOSL registers. These values can be placed on a user-defined software stack. At return time, the software can return these values to TOSU:TOSH:TOSL and do a return.

The user must disable the global interrupt enable bits while accessing the stack to prevent inadvertent stack corruption.





### 5.1.4.2 Return Stack Pointer (STKPTR)

The STKPTR register (Register 5-1) contains the Stack Pointer value, the STKFUL (Stack Full) and the STKUNF (Stack Underflow) status bits. The value of the Stack Pointer can be 0 through 31. The Stack Pointer increments before values are pushed onto the stack and decrements after values are popped off the stack. On Reset, the Stack Pointer value will be zero. The user may read and write the Stack Pointer value. This feature can be used by a Real-Time Operating System (RTOS) for return stack maintenance.

After the PC is pushed onto the stack 31 times (without popping any values off the stack), the STKFUL bit is set. The STKFUL bit is cleared by software or by a Power-on Reset (POR).

The action that takes place when the stack becomes full depends on the state of the Stack Overflow Reset Enable (STVREN) Configuration bit.

Refer to **Section 26.1 "Configuration Bits"** for device Configuration bits' description.

If STVREN is set (default), the  $31^{st}$  push will push the (PC + 2) value onto the stack, set the STKFUL bit and reset the device. The STKFUL bit will remain set and the Stack Pointer will be set to zero.

If STVREN is cleared, the STKFUL bit will be set on the 31<sup>st</sup> push and the Stack Pointer will increment to 31. Any additional pushes will not overwrite the 31<sup>st</sup> push and the STKPTR will remain at 31.

When the stack has been popped enough times to unload the stack, the next pop will return zero to the PC and set the STKUNF bit, while the Stack Pointer remains at zero. The STKUNF bit will remain set until cleared by software or until a POR occurs.

Note:	Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the Reset vector, where the stack conditions can be verified and appropriate actions can be taken. This is not the same as a Reset as the contents
	not the same as a Reset, as the contents of the SFRs are not affected.

### 5.1.4.3 PUSH and POP Instructions

Since the Top-of-Stack is readable and writable, the ability to push values onto the stack and pull values off the stack, without disturbing normal program execution is necessary. The PIC18 instruction set includes two instructions, PUSH and POP, that permit the TOS to be manipulated under software control. TOSU, TOSH and TOSL can be modified to place data or a return address on the stack.

The PUSH instruction places the current PC value onto the stack. This increments the Stack Pointer and loads the current PC value onto the stack.

The POP instruction discards the current TOS by decrementing the Stack Pointer. The previous value pushed onto the stack then becomes the TOS value.

### REGISTER 5-1: STKPTR: STACK POINTER REGISTER (ACCESS FFCh)

R/C-0	R/C-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
STKFUL <sup>(1)</sup>	STKUNF <sup>(1)</sup>	—	SP4	SP3	SP2	SP1	SP0		
bit 7 bit 0									

Legend:	C = Clearable bit		
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	STKFUL: Stack Full Flag bit <sup>(1)</sup>
	<ul> <li>1 = Stack became full or overflowed</li> <li>0 = Stack has not become full or overflowed</li> </ul>
bit 6	STKUNF: Stack Underflow Flag bit <sup>(1)</sup>
	1 = Stack underflow occurred
	0 = Stack underflow did not occur
bit 5	Unimplemented: Read as '0'
bit 4-0	SP<4:0>: Stack Pointer Location bits

Note 1: Bits 7 and 6 are cleared by user software or by a POR.

### 5.1.4.4 Stack Full and Underflow Resets

Device Resets on stack overflow and stack underflow conditions are enabled by setting the STVREN bit in Configuration register 1L. When STVREN is set, a full or underflow condition sets the appropriate STKFUL or STKUNF bit and then causes a device Reset. When STVREN is cleared, a full or underflow condition sets the appropriate STKFUL or STKUNF bit, but does not cause a device Reset. The STKFUL or STKUNF bits are cleared by the user software or a POR.

### 5.1.5 FAST REGISTER STACK (FRS)

A Fast Register Stack (FRS) is provided for the STATUS, WREG and BSR registers to provide a "fast return" option for interrupts. This stack is only one level deep and is neither readable nor writable. It is loaded with the current value of the corresponding register when the processor vectors for an interrupt. All interrupt sources push values into the Stack registers. The values in the registers are then loaded back into the working registers if the RETFIE, FAST instruction is used to return from the interrupt.

If both low-priority and high-priority interrupts are enabled, the Stack registers cannot be used reliably to return from low-priority interrupts. If a high-priority interrupt occurs while servicing a low-priority interrupt, the Stack register values stored by the low-priority interrupt will be overwritten. In these cases, users must save the key registers in software during a low-priority interrupt.

If interrupt priority is not used, all interrupts may use the FRS for returns from interrupt. If no interrupts are used, the FRS can be used to restore the STATUS, WREG and BSR registers at the end of a subroutine call. To use the Fast Register Stack for a subroutine call, a CALL label, FAST instruction must be executed to save the STATUS, WREG and BSR registers to the Fast Register Stack. A RETURN, FAST instruction is then executed to restore these registers from the FRS.

Example 5-1 provides a source code example that uses the FRS during a subroutine call and return.

#### EXAMPLE 5-1: FAST REGISTER STACK CODE EXAMPLE

CALL SUB1, FAST	;STATUS, WREG, BSR ;SAVED IN FAST REGISTER ;STACK
• SUB1 RETURN FAST	;RESTORE VALUES SAVED ;IN FAST REGISTER STACK

## 5.1.6 LOOK-UP TABLES IN PROGRAM MEMORY

There may be programming situations that require the creation of data structures or look-up tables in program memory. For PIC18 devices, look-up tables can be implemented in two ways:

- Computed GOTO
- Table Reads

### 5.1.6.1 Computed GOTO

A computed GOTO is accomplished by adding an offset to the PC. An example is shown in Example 5-2.

A look-up table can be formed with an ADDWF PCL instruction and a group of RETLW nn instructions. The W register is loaded with an offset into the table before executing a call to that table. The first instruction of the called routine is the ADDWF PCL instruction. The next executed instruction will be one of the RETLW nn instructions that returns the value 'nn' to the calling function.

The offset value (in WREG) specifies the number of bytes that the PC should advance and should be multiples of 2 (LSb = 0).

In this method, only one byte may be stored in each instruction location, room on the return address stack is required.

### EXAMPLE 5-2: COMPUTED GOTO USING AN OFFSET VALUE

	MOVF	OFFSET,	W
	CALL	TABLE	
ORG	nn00h		
TABLE	ADDWF	PCL	
	RETLW	nnh	
	RETLW	nnh	
	RETLW	nnh	

### 5.1.6.2 Table Reads

A better method of storing data in program memory allows two bytes to be stored in each instruction location.

Look-up table data may be stored two bytes per program word while programming. The Table Pointer (TBLPTR) specifies the byte address, and the Table Latch (TABLAT) contains the data that is read from the program memory. Data is transferred from program memory one byte at a time.

Table read operation is discussed further in **Section 6.1 "Table Reads and Table Writes"**.

### 5.2 PIC18 Instruction Cycle

### 5.2.1 CLOCKING SCHEME


The microcontroller clock input, whether from an internal or external source, is internally divided by '4' to generate four non-overlapping quadrature clocks (Q1, Q2, Q3 and Q4). Internally, the PC is incremented on every Q1; the instruction is fetched from the program memory and latched into the Instruction Register (IR) during Q4. The instruction is decoded and executed during the following Q1 through Q4. Figure 5-4 illustrates the clocks and instruction execution flow.

### 5.2.2 INSTRUCTION FLOW/PIPELINING


An "Instruction Cycle" consists of four Q cycles, Q1 through Q4. The instruction fetch and execute are pipelined in such a manner that a fetch takes one instruction cycle, while the decode and execute takes another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the PC to change (e.g., GOTO), then two cycles are required to complete the instruction (Example 5-3).

A fetch cycle begins with the PC incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the IR in cycle Q1. This instruction is then decoded and executed during the Q2, Q3 and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).



### EXAMPLE 5-3: INSTRUCTION PIPELINE FLOW



**Note:** All instructions are single-cycle, except for any program branches. These take two cycles since the fetch instruction is "flushed" from the pipeline while the new instruction is being fetched and then executed.

### FIGURE 5-4: CLOCK/INSTRUCTION CYCLE

### 5.2.3 INSTRUCTIONS IN PROGRAM MEMORY

The program memory is addressed in bytes. Instructions are stored as 2 bytes or 4 bytes in program memory. The Least Significant Byte (LSB) of an instruction word is always stored in a program memory location with an even address (LSB = 0). To maintain alignment with instruction boundaries, the PC increments in steps of 2 and the LSB will always read '0' (see Section 5.1.3 "Program Counter").

Figure 5-5 provides an example of how instruction words are stored in the program memory.

The CALL and GOTO instructions have the absolute program memory address embedded into the instruction. Since instructions are always stored on word boundaries, the data contained in the instruction is a word address. The word address is written to PC<20:1>, which accesses the desired byte address in program memory. Instruction #2 in Figure 5-5 displays how the instruction, GOTO 0006h, is encoded in the program memory. Program branch instructions, which encode a relative address offset, operate in the same manner. The offset value stored in a branch instruction represents the number of single-word instructions that the PC will be offset by. Section 27.0 "Instruction Set Summary" provides further details of the instruction set.

				LSB = 1	LSB = 0	Word Address $\downarrow$
	Program Memory Byte Locations $\rightarrow$					000000h
						000002h
						000004h
						000006h
Instruction 1:	MOVLW	055h		0Fh	55h	000008h
Instruction 2:	GOTO	0006h		EFh	03h	00000Ah
				F0h	00h	00000Ch
Instruction 3:	MOVFF	123h,	456h	C1h	23h	00000Eh
				F4h	56h	000010h
						000012h
						000014h

### FIGURE 5-5: INSTRUCTIONS IN PROGRAM MEMORY

### 5.2.4 TWO-WORD INSTRUCTIONS

The standard PIC18 instruction set has four two-word instructions: CALL, MOVFF, GOTO and LSFR. In all cases, the second word of the instructions always has '1111' as its four Most Significant bits (MSbs); the other 12 bits are literal data, usually a data memory address.

The use of '1111' in the 4 MSbs of an instruction specifies a special form of NOP. If the instruction is executed in proper sequence immediately after the first word, the data in the second word is accessed and

used by the instruction sequence. If the first word is skipped for some reason and the second word is executed by itself, a NOP is executed instead. This is necessary for cases when the two-word instruction is preceded by a conditional instruction that changes the PC. Example 5-4 illustrates how this works.

Note:	See Section 5.5 "Program Memory and the Extended Instruction Set" for infor-						
	mation on two-word instructions in the extended instruction set.						

EXAMPLE 5-4: TWO-WORD INSTRUCTIONS

CASE 1:							
Object Code Source Code							
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?					
1100 0001 0010 0011	MOVFF REG1, RE	G2 ; No, skip this word					
1111 0100 0101 0110		; Execute this word as a NOP					
0010 0100 0000 0000	ADDWF REG3	; continue code					
CASE 2:							
Object Code	Source Code						
0110 0110 0000 0000	TSTFSZ REG1	; is RAM location 0?					
1100 0001 0010 0011	MOVFF REG1, RE	G2 ; Yes, execute this word					
1111 0100 0101 0110		; 2nd word of instruction					
0010 0100 0000 0000	ADDWF REG3	; continue code					

### 5.3 Data Memory Organization

Note:	The operation of some aspects of data
	memory are changed when the PIC18
	extended instruction set is enabled. See
	Section 5.6 "Data Memory and the
	Extended Instruction Set" for more
	information.

The data memory in PIC18 devices is implemented as static RAM. Each register in the data memory has a 12-bit address, allowing up to 4096 bytes of data memory. The memory space is divided into as many as 16 banks that contain 256 bytes each. The PIC18F46J50 Family implements all available banks and provides 3.8 Kbytes of data memory available to the user. Figure 5-6 provides the data memory organization for the devices.

The data memory contains Special Function Registers (SFRs) and General Purpose Registers (GPRs). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratchpad operations in the user's application. Any read of an unimplemented location will read as '0's.

The instruction set and architecture allow operations across all banks. The entire data memory may be accessed by Direct, Indirect or Indexed Addressing modes. Addressing modes are discussed later in this section.

To ensure that commonly used registers (select SFRs and select GPRs) can be accessed in a single cycle, PIC18 devices implement an Access Bank. This is a 256-byte memory space that provides fast access to select SFRs and the lower portion of GPR Bank 0 without using the BSR. **Section 5.3.3 "Access Bank"** provides a detailed description of the Access RAM.

### 5.3.1 USB RAM

All 3.8 Kbytes of the GPRs implemented on the PIC18F46J50 Family devices can be accessed simultaneously by both the microcontroller core and the Serial Interface Engine (SIE) of the USB module. The SIE uses a dedicated USB DMA engine to store any incoming data packets (OUT/SETUP) directly into main system data memory.

For IN data packets, the SIE can directly read the contents of general purpose SRAM and use it to create USB data packets that are sent to the host.

Note:	IN and OUT are always from the USB
	host's perspective.

SRAM Bank 4 (400h-4FFh) is unique. In addition to being accessible by both the microcontroller core and the USB module, the SIE uses a portion of Bank 4 as Special Function Registers (SFRs). These SFRs compose the Buffer Descriptor Table (BDT). When the USB module is enabled, the BDT registers are used to control the behavior of the USB DMA operation for each of the enabled endpoints. The exact number of SRAM locations that are used for the BDT depends on how many endpoints are enabled and what USB Ping-Pong mode is used. For more details, see **Section 21.3 "USB RAM"**.

When the USB module is disabled, these SRAM locations behave like any other GPR location. When the USB module is disabled, these locations may be used for any general purpose.

### 5.3.2 BANK SELECT REGISTER

Large areas of data memory require an efficient addressing scheme to make rapid access to any address possible. Ideally, this means that an entire address does not need to be provided for each read or write operation. For PIC18 devices, this is accomplished with a RAM banking scheme. This divides the memory space into 16 contiguous banks of 256 bytes. Depending on the instruction, each location can be addressed directly by its full 12-bit address, or an 8-bit low-order address and a 4-bit Bank Pointer.


Most instructions in the PIC18 instruction set make use of the Bank Pointer, known as the Bank Select Register (BSR). This SFR holds the 4 MSbs of a location's address; the instruction itself includes the 8 LSbs. Only the four lower bits of the BSR are implemented (BSR<3:0>). The upper four bits are unused; they will always read '0' and cannot be written to. The BSR can be loaded directly by using the MOVLB instruction.


The value of the BSR indicates the bank in data memory. The 8 bits in the instruction show the location in the bank and can be thought of as an offset from the bank's lower boundary. The relationship between the BSR's value and the bank division in data memory is illustrated in Figure 5-7.

Since, up to 16 registers may share the same low-order address, the user must always be careful to ensure that the proper bank is selected before performing a data read or write. For example, writing what should be program data to an 8-bit address of F9h while the BSR is 0Fh, will end up resetting the PC.

While any bank can be selected, only those banks that are actually implemented can be read or written to. Writes to unimplemented banks are ignored, while reads from unimplemented banks will return '0's. Even so, the STATUS register will still be affected as if the operation was successful. The data memory map in Figure 5-6 indicates which banks are implemented.

In the core PIC18 instruction set, only the MOVFF instruction fully specifies the 12-bit address of the source and target registers. This instruction ignores the BSR completely when it executes. All other instructions include only the low-order address as an operand and must use either the BSR or the Access Bank to locate their target registers.





### 5.3.3 ACCESS BANK

While the use of the BSR with an embedded 8-bit address allows users to address the entire range of data memory, it also means that the user must always ensure that the correct bank is selected. Otherwise, data may be read from or written to the wrong location. This can be disastrous if a GPR is the intended target of an operation, but an SFR is written to instead. Verifying and/or changing the BSR for each read or write to data memory can become very inefficient.

To streamline access for the most commonly used data memory locations, the data memory is configured with an Access Bank, which allows users to access a mapped block of memory without specifying a BSR. The Access Bank consists of the first 96 bytes of memory (00h-5Fh) in Bank 0 and the last 160 bytes of memory (60h-FFh) in Bank 15. The lower half is known as the Access RAM and is composed of GPRs. The upper half is where the device's SFRs are mapped. These two areas are mapped contiguously in the Access Bank and can be addressed in a linear fashion by an 8-bit address (Figure 5-6).

The Access Bank is used by core PIC18 instructions that include the Access RAM bit (the 'a' parameter in the instruction). When 'a' is equal to '1', the instruction uses the BSR and the 8-bit address included in the opcode for the data memory address. When 'a' is '0', however, the instruction is forced to use the Access Bank address map; the current value of the BSR is ignored entirely.

Using this "forced" addressing allows the instruction to operate on a data address in a single cycle without updating the BSR first. For 8-bit addresses of 60h and above, this means that users can evaluate and operate on SFRs more efficiently. The Access RAM below 60h is a good place for data values that the user might need to access rapidly, such as immediate computational results or common program variables. Access RAM also allows for faster and more code efficient context saving and switching of variables.

The mapping of the Access Bank is slightly different when the extended instruction set is enabled (XINST Configuration bit = 1). This is discussed in more detail in Section 5.6.3 "Mapping the Access Bank in Indexed Literal Offset Mode".

### 5.3.4 GENERAL PURPOSE REGISTER FILE

PIC18 devices may have banked memory in the GPR area. This is data RAM, which is available for use by all instructions. GPRs start at the bottom of Bank 0 (address 000h) and grow upward toward the bottom of the SFR area. GPRs are not initialized by a POR and are unchanged on all other Resets.

### 5.3.5 SPECIAL FUNCTION REGISTERS

The SFRs are registers used by the CPU and peripheral modules for controlling the desired operation of the device. These registers are implemented as static RAM. SFRs start at the top of data memory (FFFh) and extend downward to occupy more than the top half of Bank 15 (F40h to FFFh). Table 5-2, Table 5-3 and Table 5-4 provide a list of these registers.

The SFRs can be classified into two sets: those associated with the "core" device functionality (ALU, Resets and interrupts) and those related to the peripheral functions. The Reset and Interrupt registers are described in their corresponding chapters, while the ALU's STATUS register is described later in this section. Registers related to the operation of the peripheral features are described in the chapter for that peripheral.

The SFRs are typically distributed among the peripherals whose functions they control. Unused SFR locations are unimplemented and read as '0's

Note: The SFRs located between EC0h and F5Fh are not part of the Access Bank. Either BANKED instructions (using BSR) or the MOVFF instruction should be used to access these locations. When programming in MPLAB C18, the compiler will automatically use the appropriate addressing mode.

### TABLE 5-2: ACCESS BANK SPECIAL FUNCTION REGISTER MAP

Address	Name	Address	Name	Address	Name	Address	Name	Address	Name
FFFh	TOSU	FDFh	INDF2 <sup>(1)</sup>	FBFh	PSTR1CON	F9Fh	IPR1	F7Fh	SPBRGH1
FFEh	TOSH	FDEh	POSTINC2 <sup>(1)</sup>	FBEh	ECCP1AS	F9Eh	PIR1	F7Eh	BAUDCON1
FFDh	TOSL	FDDh	POSTDEC2 <sup>(1)</sup>	FBDh	ECCP1DEL	F9Dh	PIE1	F7Dh	SPBRGH2
FFCh	STKPTR	FDCh	PREINC2 <sup>(1)</sup>	FBCh	CCPR1H	F9Ch	RCSTA2	F7Ch	BAUDCON2
FFBh	PCLATU	FDBh	PLUSW2 <sup>(1)</sup>	FBBh	CCPR1L	F9Bh	OSCTUNE	F7Bh	TMR3H
FFAh	PCLATH	FDAh	FSR2H	FBAh	CCP1CON	F9Ah	T1GCON	F7Ah	TMR3L
FF9h	PCL	FD9h	FSR2L	FB9h	PSTR2CON	F99h	RTCVALH	F79h	T3CON
FF8h	TBLPTRU	FD8h	STATUS	FB8h	ECCP2AS	F98h	RTCVALL	F78h	TMR4
FF7h	TBLPTRH	FD7h	TMR0H	FB7h	ECCP2DEL	F97h	T3GCON	F77h	PR4
FF6h	TBLPTRL	FD6h	TMR0L	FB6h	CCPR2H	F96h	TRISE	F76h	T4CON
FF5h	TABLAT	FD5h	T0CON	FB5h	CCPR2L	F95h	TRISD	F75h	SSP2BUF
FF4h	PRODH	FD4h	(5)	FB4h	CCP2CON	F94h	TRISC	F74h	SSP2ADD <sup>(3)</sup>
FF3h	PRODL	FD3h	OSCCON	FB3h	CTMUCONH	F93h	TRISB	F73h	SSP2STAT
FF2h	INTCON	FD2h	CM1CON	FB2h	CTMUCONL	F92h	TRISA	F72h	SSP2CON1
FF1h	INTCON2	FD1h	CM2CON	FB1h	CTMUICON	F91h	ALRMCFG	F71h	SSP2CON2
FF0h	INTCON3	FD0h	RCON	FB0h	SPBRG1	F90h	ALRMRPT	F70h	CMSTAT
FEFh	INDF0 <sup>(1)</sup>	FCFh	TMR1H	FAFh	RCREG1	F8Fh	ALRMVALH	F6Fh	PMADDRH <sup>(2,4)</sup>
FEEh	POSTINC0 <sup>(1)</sup>	FCEh	TMR1L	FAEh	TXREG1	F8Eh	ALRMVALL	F6Eh	PMADDRL <sup>(2,4)</sup>
FEDh	POSTDEC0 <sup>(1)</sup>	FCDh	T1CON	FADh	TXSTA1	F8Dh	LATE <sup>(2)</sup>	F6Dh	PMDIN1H <sup>(2)</sup>
FECh	PREINC0 <sup>(1)</sup>	FCCh	TMR2	FACh	RCSTA1	F8Ch	LATD <sup>(2)</sup>	F6Ch	PMDIN1L <sup>(2)</sup>
FEBh	PLUSW0 <sup>(1)</sup>	FCBh	PR2	FABh	SPBRG2	F8Bh	LATC	F6Bh	TXADDRL
FEAh	FSR0H	FCAh	T2CON	FAAh	RCREG2	F8Ah	LATB	F6Ah	TXADDRH
FE9h	FSR0L	FC9h	SSP1BUF	FA9h	TXREG2	F89h	LATA	F69h	RXADDRL
FE8h	WREG	FC8h	SSP1ADD <sup>(3)</sup>	FA8h	TXSTA2	F88h	DMACON1	F68h	RXADDRH
FE7h	INDF1 <sup>(1)</sup>	FC7h	SSP1STAT	FA7h	EECON2	F87h	(5)	F67h	DMABCL
FE6h	POSTINC1 <sup>(1)</sup>	FC6h	SSP1CON1	FA6h	EECON1	F86h	DMACON2	F66h	DMABCH
FE5h	POSTDEC1 <sup>(1)</sup>	FC5h	SSP1CON2	FA5h	IPR3	F85h	HLVDCON	F65h	UCON
FE4h	PREINC1 <sup>(1)</sup>	FC4h	ADRESH	FA4h	PIR3	F84h	PORTE <sup>(2)</sup>	F64h	USTAT
FE3h	PLUSW1 <sup>(1)</sup>	FC3h	ADRESL	FA3h	PIE3	F83h	PORTD <sup>(2)</sup>	F63h	UEIR
FE2h	FSR1H	FC2h	ADCON0	FA2h	IPR2	F82h	PORTC	F62h	UIR
FE1h	FSR1L	FC1h	ADCON1	FA1h	PIR2	F81h	PORTB	F61h	UFRMH
FE0h	BSR	FC0h	WDTCON	FA0h	PIE2	F80h	PORTA	F60h	UFRML

Note 1: This is not a physical register.

2: This register is not available on 28-pin devices.

3: SSPxADD and SSPxMSK share the same address.

4: PMADDRH and PMDOUTH share the same address and PMADDRL and PMDOUTL share the same address. PMADDRx is used in Master modes and PMDOUTx is used in Slave modes.

5: Reserved: Do not write to this location.

### TABLE 5-3: NON-ACCESS BANK SPECIAL FUNCTION REGISTER MAP

Address	Name	Address	Name	Address	Name	Address	Name	Address	Name
F5Fh	PMCONH	F3Fh	RTCCFG	F1Fh	—	EFFh	PPSCON	EDFh	_
F5Eh	PMCONL	F3Eh	RTCCAL	F1Eh	_	EFEh	RPINR24	EDEh	RPOR24 <sup>(1)</sup>
F5Dh	PMMODEH	F3Dh	REFOCON	F1Dh	_	EFDh	RPINR23	EDDh	RPOR23 <sup>(1)</sup>
F5Ch	PMMODEL	F3Ch	PADCFG1	F1Ch	_	EFCh	RPINR22	EDCh	RPOR22 <sup>(1)</sup>
F5Bh	PMDOUT2H	F3Bh	_	F1Bh	_	EFBh	RPINR21	EDBh	RPOR21 <sup>(1)</sup>
F5Ah	PMDOUT2L	F3Ah	_	F1Ah	_	EFAh	_	EDAh	RPOR20 <sup>(1)</sup>
F59h	PMDIN2H	F39h	UCFG	F19h	—	EF9h		ED9h	RPOR19 <sup>(1)</sup>
F58h	PMDIN2L	F38h	UADDR	F18h	—	EF8h		ED8h	RPOR18
F57h	PMEH	F37h	UEIE	F17h	—	EF7h	RPINR17	ED7h	RPOR17
F56h	PMEL	F36h	UIE	F16h	—	EF6h	RPINR16	ED6h	—
F55h	PMSTATH	F35h	UEP15	F15h	—	EF5h		ED5h	—
F54h	PMSTATL	F34h	UEP14	F14h	—	EF4h		ED4h	—
F53h	CVRCON	F33h	UEP13	F13h	—	EF3h	RPINR13	ED3h	RPOR13
F52h	TCLKCON	F32h	UEP12	F12h	—	EF2h	RPINR12	ED2h	RPOR12
F51h	_	F31h	UEP11	F11h	—	EF1h		ED1h	RPOR11
F50h	_	F30h	UEP10	F10h		EF0h	_	ED0h	RPOR10
F4Fh	DSGPR1	F2Fh	UEP9	F0Fh		EEFh	_	ECFh	RPOR9
F4Eh	DSGPR0	F2Eh	UEP8	F0Eh	_	EEEh	RPINR8	ECEh	RPOR8
F4Dh	DSCONH	F2Dh	UEP7	F0Dh		EEDh	RPINR7	ECDh	RPOR7
F4Ch	DSCONL	F2Ch	UEP6	F0Ch		EECh	RPINR6	ECCh	RPOR6
F4Bh	DSWAKEH	F2Bh	UEP5	F0Bh		EEBh	_	ECBh	RPOR5
F4Ah	DSWAKEL	F2Ah	UEP4	F0Ah		EEAh	RPINR4	ECAh	RPOR4
F49h	ANCON1	F29h	UEP3	F09h		EE9h	RPINR3	EC9h	RPOR3
F48h	ANCON0	F28h	UEP2	F08h		EE8h	RPINR2	EC8h	RPOR2
F47h	—	F27h	UEP1	F07h		EE7h	RPINR1	EC7h	RPOR1
F46h	_	F26h	UEP0	F06h		EE6h	_	EC6h	RPOR0
F45h	—	F25h	—	F05h	—	EE5h	—	EC5h	—
F44h	—	F24h	—	F04h	—	EE4h	—	EC4h	—
F43h	—	F23h	—	F03h	—	EE3h	—	EC3h	—
F42h	ODCON1	F22h	_	F02h	_	EE2h	_	EC2h	—
F41h	ODCON2	F21h	_	F01h	_	EE1h	_	EC1h	_
F40h	ODCON3	F20h	—	F00h	_	EE0h	—	EC0h	—

Note 1: This register is not available on 28-pin devices.

#### 5.3.5.1 Context Defined SFRs

There are several registers that share the same address in the SFR space. The register's definition and usage depends on the operating mode of its associated peripheral. These registers are:

- · SSPxADD and SSPxMSK: These are two separate hardware registers, accessed through a single SFR address. The operating mode of the MSSP modules determines which register is being accessed. See Section 18.5.3.4 "7-Bit Address Masking Mode" for additional details.
- PMADDRH/L and PMDOUT2H/L: In this case. these named buffer pairs are actually the same physical registers. The Parallel Master Port (PMP) module's operating mode determines what function the registers take on. See Section 10.1.2 "Data Registers" for additional details.

#### **TABLE 5-4**: REGISTER FILE SUMMARY (PIC18F46J50 FAMILY)

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
TOSU	_	_	_	Top-of-Stack		0 0000	63, 75			
TOSH	Top-of-Stack	High Byte (TO	DS<15:8>)	•					0000 0000	63, 73
TOSL	Top-of-Stack	Low Byte (TC	)S<7:0>)						0000 0000	63, 73
STKPTR	STKFUL	TKFUL STKUNF — SP4 SP3 SP2 SP1 SP								
PCLATU	-	_	bit 21 <sup>(1)</sup>	Holding Regi	ster for PC<20	:16>			0 0000	63, 73
PCLATH	Holding Reg	Iding Register for PC<15:8>								
PCL	PC Low Byte	e (PC<7:0>)							0000 0000	63, 73
TBLPTRU	_	bit 21 Program Memory Table Pointer Upper Byte (TBLPTR<20:16>)								63, 106
TBLPTRH	Program Me	Program Memory Table Pointer High Byte (TBLPTR<15:8>)							0000 0000	63, 106
TBLPTRL	Program Memory Table Pointer Low Byte (TBLPTR<7:0>)							0000 0000	63, 106	
TABLAT	Program Me	mory Table La	itch						0000 0000	63, 106
PRODH	Product Reg	ister High Byte	9						XXXX XXXX	63, 107
PRODL	Product Reg	ister Low Byte	;						XXXX XXXX	63, 107
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INTOIF	RBIF	0000 000x	63, 111
INTCON2	RBPU	INTEDG0	INTEDG1	INTEDG2	INTEDG3	TMR0IP	INT3IP	RBIP	1111 1111	63, 111
INTCON3	INT2IP	INT1IP	INT3IE	INT2IE	INT1IE	INT3IF	INT2IF	INT1IF	1100 0000	63, 111
INDF0	Uses conten	ts of FSR0 to	address data	memory – va	lue of FSR0 no	t changed (not	a physical regi	ster)	N/A	63, 92
POSTINC0	Uses conten	ts of FSR0 to	address data	memory - va	lue of FSR0 po	st-incremented	l (not a physica	l register)	N/A	63, 93
POSTDEC0	Uses conten	ts of FSR0 to	address data	memory - va	lue of FSR0 po	st-decremente	d (not a physica	al register)	N/A	63, 93
PREINC0	Uses conten	ts of FSR0 to	address data	memory - va	lue of FSR0 pro	e-incremented	(not a physical	register)	N/A	63, 93
PLUSW0		ts of FSR0 to to offset by W	address data	memory – va	lue of FSR0 pr	e-incremented	(not a physical	register) –	N/A	63, 93
FSR0H	_	_	_	_	Indirect Data I	Memory Addres	ss Pointer 0 Hig	h Byte	xxxx	63, 92
FSR0L	Indirect Data	Memory Add	ress Pointer (	D Low Byte					XXXX XXXX	63, 92
WREG	Working Reg	ister							XXXX XXXX	63, 75
INDF1	Uses conten	ts of FSR1 to	address data	memory – va	lue of FSR1 no	t changed (not	a physical regi	ster)	N/A	63, 92
POSTINC1	Uses conten	ts of FSR1 to	address data	memory – va	lue of FSR1 po	st-incremented	l (not a physica	l register)	N/A	63, 93
POSTDEC1	Uses conten	ts of FSR1 to	address data	memory – va	lue of FSR1 po	st-decremente	d (not a physica	al register)	N/A	63, 93
PREINC1	Uses conten	Uses contents of FSR1 to address data memory – value of FSR1 pre-incremented (not a physical registed							N/A	64, 93
PLUSW1		lses contents of FSR1 to address data memory – value of FSR1 pre-incremented (not a physical registral alue of FSR1 offset by W							N/A	63, 93

Note

Bit 21 of the PC is only available in Serial Programming (SP) modes. 1:

Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled. 2:

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

Alternate names and definitions for these bits when the MSSP module is operating in I<sup>2</sup>C<sup>™</sup> Slave mode. See Section 18.5.3.2 "Address 4: Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have 6: different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

TABLE 5-4:	REG	ISTER FI	LE SUMN	ARY (PIC	C18F46J50	FAMILY)	(CONTIN	UED)	

						••••••••••••••••••••••••••••••••••••••	(	<u>,</u>	1	1
File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
FSR1H	_	_	_	_	Indirect Data I	Memory Addres	s Pointer 1 Hig	h Byte	xxxx	63, 92
FSR1L	Indirect Data	Memory Add	ress Pointer '	1 Low Byte		,		, ,	XXXX XXXX	63, 92
BSR	_	— — — Bank Select Register								
INDF2	Uses content	ts of FSR2 to	address data	memory – va	lue of FSR2 no	t changed (not	a physical regi	ster)	N/A	63, 92
POSTINC2	Uses content	ts of FSR2 to	address data	memory – va	lue of FSR2 po	st-incremented	(not a physica	l register)	N/A	64, 93
POSTDEC2	Uses content	ts of FSR2 to	address data	memory – va	lue of FSR2 po	st-decremente	d (not a physica	al register)	N/A	64, 93
PREINC2	Uses content	ts of FSR2 to	address data	memory – va	lue of FSR2 pro	e-incremented	(not a physical	register)	N/A	64, 93
PLUSW2	Uses content	Uses contents of FSR2 to address data memory – value of FSR2 pre-incremented (not a physical register Uses contents of FSR2 to address data memory – value of FSR2 pre-incremented (not a physical register value of FSR2 offset by W								64, 93
FSR2H	_	_	_	_	Indirect Data I	Memory Addres	s Pointer 2 Hig	jh Byte	xxxx	64, 92
FSR2L	Indirect Data	Memory Add	ress Pointer 2	2 Low Byte			-		XXXX XXXX	64, 92
STATUS	_	_	_	N	OV	Z	DC	С	x xxxx	64, 90
TMR0H	Timer0 Regis	ster High Byte							0000 0000	64, 196
TMR0L	Timer0 Regis	ster Low Byte							XXXX XXXX	64, 196
TOCON	TMR00N	T08BIT	TOCS	T0SE	PSA	T0PS2	T0PS1	T0PS0	1111 1111	64, 190
OSCCON	IDLEN	IRCF2	IRCF1	IRCF0	OSTS <sup>(2)</sup>	_	SCS1	SCS0	0110 q-00	64, 37
CM1CON	CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	0001 1111	64, 387
CM2CON	CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	0001 1111	64, 387
RCON	IPEN	—	СМ	RI	TO	PD	POR	BOR	0-11 1100	62, 64, 123
TMR1H	Timer1 Regis	ster High Byte	•				•		XXXX XXXX	64, 196
TMR1L	Timer1 Regis	ster Low Byte							XXXX XXXX	64, 196
T1CON	TMR1CS1	TMR1CS0	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	RD16	TMR10N	0000 0000	64, 196
TMR2	Timer2 Regis	ster							0000 0000	64, 205
PR2	Timer2 Perio	d Register							1111 1111	64, 205
T2CON	_	T2OUTPS3	T2OUTPS2	T2OUTPS1	T2OUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	64, 205
SSP1BUF	MSSP1 Rece	eive Buffer/Tra	ansmit Regist	er			1		XXXX XXXX	64,282, 316
SSP1ADD	MSSP1 Addr	ess Register	(I <sup>2</sup> C <sup>™</sup> Slave	mode), MSSP	1 Baud Rate R	Reload Register	(I <sup>2</sup> C Master m	ode)	0000 0000	64, 287
SSP1MSK <sup>(4)</sup>	MSK7	MSK6	MSK5	MSK4	MSK3	MSK2	MSK1	MSK0	1111 1111	64, 289
SSP1STAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000 0000	64,264, 283
SSP1CON1	WCOL	SSPOV	SSPEN	СКР	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	64,264, 284
SSP1CON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000 0000	64,264,
	GCEN	ACKSTAT	ADMSK5(4)	ADMSK4(4)	ADMSK3(4)	ADMSK2(4)	ADMSK1 <sup>(4)</sup>	SEN		285
									XXXX XXXX	64, 350
ADRESH	A/D Result R	egister High I	Byte							
ADRESH ADRESL	-	egister High I egister Low E	,						XXXX XXXX	64, 350
	-	0 0	,	CHS2	CHS1	CHS0	GO/DONE	ADON	xxxx xxxx 0000 0000	
ADRESL	A/D Result R	egister Low E	Syte	CHS2 ACQT1	CHS1 ACQT0	CHS0 ADCS2	GO/DONE	ADON ADCS0		63, 341
ADRESL ADCON0 ADCON1	A/D Result R VCFG1	egister Low E VCFG0	Byte CHS3						0000 0000	63, 341 64, 341
ADRESL ADCON0	A/D Result R VCFG1 ADFM	egister Low E VCFG0 ADCAL	Byte CHS3 ACQT2		ACQT0	ADCS2	ADCS1	ADCS0	0000 0000	63, 341 64, 341 64, 423

Legend: Note 1

d: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition, r = reserved. Bold indicates shared access SFRs.

1: Bit 21 of the PC is only available in Serial Programming (SP) modes.

**2:** Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

4: Alternate names and definitions for these bits when the MSSP module is operating in I<sup>2</sup>C<sup>™</sup> Slave mode. See Section 18.5.3.2 "Address Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

6: The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOI	on
ECCP1DEL	P1RSEN	P1DC6	P1DC5	P1DC4	P1DC3	P1DC2	P1DC1	P1DC0	0000 000	0 65
CCPR1H	Capture/Com	npare/PWM R	egister 1 Hlgł	n Byte					XXXX XXX	x 65
CCPR1L	Capture/Com	npare/PWM R	egister 1 Low	Byte					XXXX XXX	x 65
CCP1CON	P1M1	P1M0	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	0000 000	0 65
PSTR2CON	CMPL1	CMPL0	—	STRSYNC	STRD	STRC	STRB	STRA	00-0 000	1 <b>65, 259</b>
ECCP2AS	ECCP2ASE	ECCP2AS2	ECCP2AS1	ECCP2AS0	PSS2AC1	PSS2AC0	PSS2BD1	PSS2BD0	0000 000	0 65
ECCP2DEL	P2RSEN	P2DC6	P2DC5	P2DC4	P2DC3	P2DC2	P2DC1	P2DC0	0000 000	0 65
CCPR2H	Capture/Com	apture/Compare/PWM Register 2 High Byte								x 65
CCPR2L	Capture/Com	apture/Compare/PWM Register 2 Low Byte								x 65
CCP2CON	P2M1	P2M0	DC2B1	DC2B0	CCP2M3	CCP2M2	CCP2M1	CCP2M0	0000 000	0 65
CTMUCONH	CTMUEN	_	CTMUSIDL	TGEN	EDGEN	EDGSEQEN	IDISSEN	—	0-00 000	- 65
CTMUCONL	EDG2POL	EDG2SEL1	EDG2SEL0	EDG1POL	EDG1SEL1	EDG1SEL0	EDG2STAT	EDG1STAT	0000 002	x 65
CTMUICON	ITRIM5	ITRIM4	ITRIM3	ITRIM2	ITRIM1	ITRIM0	IRNG1	IRNG0	0000 000	0 65
SPBRG1	EUSART1 B	aud Rate Ger	erator Regist	er Low Byte					0000 000	0 65, 321
RCREG1	EUSART1 R	eceive Regist	er						0000 000	0 65,329, 322
TXREG1	EUSART1 Tr	ransmit Regis	ter						XXXX XXX	x 65,329, 328
TXSTA1	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	0000 001	0 65, 327
RCSTA1	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000	x 65, 329
SPBRG2			EUSART2	Baud Rate G	enerator Regis	ster Low Byte			0000 000	0 65, 321
RCREG2	EUSART2 R	eceive Regist	er						0000 000	0 <b>65,329,</b> 330
TXREG2	EUSART2 Tr	ransmit Regis	ter						0000 000	0 65,327, 328
TXSTA2	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	0000 001	0 65, 327
EECON2	Program Mer	mory Control	Register 2 (no	ot a physical re	egister)					- 65, 98
EECON1	_	_	WPROG	FREE	WRERR	WREN	WR	_	00 x00	- 65, 98
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	1111 111	1 <b>65, 120</b>
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	0000 000	0 65, 114
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	0000 000	0 65, 117
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	1111 111	1 <b>65, 120</b>
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	0000 000	0 65, 114
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	0000 000	0 65, 117
IPR1	PMPIP <sup>(5)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	1111 111	1 <b>65, 120</b>
PIR1	PMPIF <sup>(5)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	0000 000	0 65, 114
PIE1	PMPIE <sup>(5)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	0000 000	0 65, 117
RCSTA2	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000	x 66, 329
OSCTUNE	INTSRC	PLLEN	TUN5	TUN4	TUN3	TUN2	TUN1	TUN0	0000 000	0 66, 33
T1GCON	TMR1GE	T1GPOL	T1GTM	T1GSPM	T1GGO/ T1DONE	T1GVAL	T1GSS1	T1GSS0	0000 0x0	0 194
RTCVALH	RTCC Value	Register Win	dow High Byte	e, Based on R	TCPTR<1:0>				0xxx xxx	x 66, 225
RTCVALL	RTCC Value	Register Win	dow Low Byte	, Based on R	TCPTR<1:0>				0xxx xxx	x 66, 225
Legend: x	= unknown, u	= unchanged,	– = unimpler	nented, q = va	alue depends o	n condition, r =	reserved. Bol	d indicates sh	nared acces	s SFRs.

TABLE 5-4:	REGISTER FILE SUMMARY	(PIC18F46J50 FAMILY)	(CONTINUED)

Note 1: Bit 21 of the PC is only available in Serial Programming (SP) modes.

2: Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

Alternate names and definitions for these bits when the MSSP module is operating in I<sup>2</sup>C<sup>TM</sup> Slave mode. See Section 18.5.3.2 "Address 4: Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

6: The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

### TABLE 5-4: REGISTER FILE SUMMARY (PIC18F46J50 FAMILY) (CONTINUED)

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
T3GCON	TMR3GE	T3GPOL	T3GTM	T3GSPM	T3GGO/ T3DONE	T3GVAL	T3GSS1	T3GSS0	0000 0x00	66, 208
TRISE	_	_	_	_	_	TRISE2	TRISE1	TRISE0	111	66
TRISD	TRISD7	TRISD6	TRISD5	TRISD4	TRISD3	TRISD2	TRISD1	TRISD0	1111 1111	66, 273
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	_	TRISC2	TRISC1	TRISC0	1111 -111	66, 136
TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	1111 1111	66, 132
TRISA	TRISA7	TRISA6	TRISA5	_	TRISA3	TRISA2	TRISA1	TRISA0	111- 1111	66, 129
ALRMCFG	ALRMEN	CHIME	AMASK3	AMASK2	AMASK1	AMASK0	ALRMPTR1	ALRMPTR0	0000 0000	66, 223
ALRMRPT	ARPT7	ARPT6	ARPT5	ARPT4	ARPT3	ARPT2	ARPT1	ARPT0	0000 0000	66, 224
ALRMVALH	Alarm Value	Register Wind	low High Byte	e, Based on A	LRMPTR<1:0>				XXXX XXXX	66, 228
ALRMVALL	Alarm Value	Register Wind	low Low Byte	, Based on Al	RMPTR<1:0>				XXXX XXXX	66, 228
LATE	—	—	_	_	—	LATE2	LATE1	LATE0	xxx	66, 142
LATD	LATD7	LATD6	LATD5	LATD4	LATD3	LATD2	LATD1	LATD0	XXXX XXXX	66, 140
LATC	LATC7	LATC6	LATC5	LATC4	_	LATC2	LATC1	LATC0	xxxx -xxx	66, 135
LATB	LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0	XXXX XXXX	66, 135
LATA	LATA7	LATA6	LATA5	_	LATA3	LATA2	LATA1	LATA0	xxx- xxxx	66, 135
DMACON1	SSCON1	SSCON0	TXINC	RXINC	DUPLEX1	DUPLEX0	DLYINTEN	DMAEN	0000 0000	66, 276
DMATXBUF	SPI DMA Tra	ansmit Buffer				•			XXXX XXXX	66
DMACON2	DLYCYC3	DLYCYC2	DLYCYC1	DLYCYC0	INTLVL3	INTLVL2	INTLVL1	INTLVL0	0000 0000	66, 277
HLVDCON	VDIRMAG	BGVST	IRVST	HLVDEN	HLVDL3	HLVDL2	HLVDL1	HLVDL0	0000 0000	66
PORTE	RDPU	REPU	_	_	_	RE2	RE1	RE0	00xxx	66, 125
PORTD	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	XXXX XXXX	66, 125
PORTC	RC7	RC6	RC5	RC4	_	RC2	RC1	RC0	xxxx -xxx	66, 125
PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	XXXX XXXX	66, 125
PORTA	RA7	RA6	RA5	_	RA3	RA2	RA1	RA0	xxx- xxxx	66, 350
SPBRGH1	EUSART1 B	aud Rate Ger	erator Regist	er High Byte					0000 0000	66, 321
BAUDCON1	ABDOVF	RCIDL	RXDTP	TXCKP	BRG16	_	WUE	ABDEN	0100 0-00	66, 321
SPBRGH2	EUSART2 B	aud Rate Ger	erator Regist	er High Byte					0000 0000	66, 321
BAUDCON2	ABDOVF	RCIDL	RXDTP	TXCKP	BRG16	_	WUE	ABDEN	0100 0-00	66, 321
TMR3H	Timer3 Regis	ster High Byte							XXXX XXXX	67, 191
TMR3L	Timer3 Regis	ster Low Byte							XXXX XXXX	67, 191
T3CON	TMR3CS1	TMR3CS0	T3CKPS1	T3CKPS0	T3OSCEN	T3SYNC	RD16	TMR3ON	0000 0000	67, 191
TMR4	Timer4 Regis	ster				•			0000 0000	67, 217
PR4	Timer4 Perio	d Register							1111 1111	67, 191
T4CON	_	T4OUTPS3	T4OUTPS2	T4OUTPS1	T4OUTPS0	TMR4ON	T4CKPS1	T4CKPS0	-000 0000	67, 217
SSP2BUF	MSSP2 Rece	eive Buffer/Tra	ansmit Regist	er					XXXX XXXX	67,282, 316
SSP2ADD/	MSSP2 Addr	ess Register	(I <sup>2</sup> C™ Slave	mode), MSSP	2 Baud Rate R	eload Register	(I <sup>2</sup> C Master me	ode)	0000 0000	67, 282
SSP2MSK <sup>(4)</sup>	MSK7	MSK6	MSK5	MSK4	MSK3	MSK2	MSK1	MSK0	0000 0000	67, 289
SSP2STAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	1111 1111	67,264, 304
SSP2CON1	WCOL	SSPOV	SSPEN	СКР	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	67,264, 316

Legend: Note 1

d: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition, r = reserved. Bold indicates shared access SFRs.

1: Bit 21 of the PC is only available in Serial Programming (SP) modes.

**2:** Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

4: Alternate names and definitions for these bits when the MSSP module is operating in I<sup>2</sup>C<sup>™</sup> Slave mode. See Section 18.5.3.2 "Address Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

6: The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
SSP2CON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000 0000	67,264,
	GCEN	ACKSTAT	ADMSK5(4)	ADMSK4(4)	ADMSK3(4)	ADMSK2(4)	ADMSK1 <sup>(4)</sup>	SEN		316
CMSTAT	—	—	_	_	—	—	COUT2	COUT1	11	67, 384
PMADDRH/	_	CS1	Parallel Mas	ter Port Addre	ss High Byte				-000 0000	67, 171
PMDOUT1H <sup>(5)</sup>	Parallel Port	Out Data Hig	n Byte (Buffer	<sup>.</sup> 1)					0000 0000	67, 174
PMADDRL/	Parallel Mast	ter Port Addre	ss Low Byte						0000 0000	67, 170
PMDOUT1L <sup>(5)</sup>	Parallel Port	Out Data Low	v Byte (Buffer	0)					0000 0000	67, 171
PMDIN1H <sup>(5)</sup>	Parallel Port	In Data High	Byte (Buffer 1	)					0000 0000	67, 171
PMDIN1L <sup>(5)</sup>	Parallel Port	In Data Low I	Byte (Buffer 0	)					0000 0000	67, 171
TXADDRL	SPI DMA Tra	ansit Data Poi	nter Low Byte	•					XXXX XXXX	67, 278
TXADDRH	_	_	_	_	SPI DMA Tran	isit Data Pointe	r High Byte		xxxx	67, 278
RXADDRL	SPI DMA Re	ceive Data Po	ointer Low By	te					XXXX XXXX	67, 278
RXADDRH	_	_	_	_	SPI DMA Rec	eive Data Point	er High Byte		xxxx	67, 278
DMABCL	SPI DMA By	te Count Low	Byte						XXXX XXXX	67, 278
DMABCH	-	—	_	_	-	_	SPI DMA Reco Pointer High B		xx	67, 278
UCON	_	PPBRST	SE0	PKTDIS	USBEN	RESUME	SUSPND	_	-0x0 000-	67, 353
USTAT	_	ENDP3	ENDP2	ENDP1	ENDP0	DIR	PPBI	_	-xxx xxx-	67, 357
UEIR	BTSEF	_	_	BTOEF	DFN8EF	CRC16EF	CRC5EF	PIDEF	00 0000	67, 370
UIR	_	SOFIF	STALLIF	IDLEIF	TRNIF	ACTVIF	UERRIF	URSTIF	-000 0000	67, 367
UFRMH	_	_	_	_	_	FRM10	FRM9	FRM8	xxx	67, 359
UFRML	FRM7	FRM6	FRM5	FRM4	FRM3	FRM2	FRM1	FRM0	XXXX XXXX	67, 359
PMCONH <sup>(5)</sup>	PMPEN	_	PSIDL	ADRMUX1	ADRMUX0	PTBEEN	PTWREN	PTRDEN	0-00 0000	67, 164
PMCONL <sup>(5)</sup>	CSF1	CSF0	ALP	_	CS1P	BEP	WRSP	RDSP	000- 0000	67, 165
PMMODEH <sup>(5)</sup>	BUSY	IRQM1	IRQM0	INCM1	INCM0	MODE16	MODE1	MODE0	0000 0000	68, 166
PMMODEL <sup>(5)</sup>	WAITB1	WAITB0	WAITM3	WAITM2	WAITM1	WAITM0	WAITE1	WAITE0	0000 0000	68, 167
PMDOUT2H <sup>(5)</sup>	Parallel Port	Out Data Hig	n Byte (Buffer	3)					0000 0000	68, 170
PMDOUT2L <sup>(5)</sup>	Parallel Port	Out Data Low	Byte (Buffer	2)					0000 0000	68, 170
PMDIN2H <sup>(5)</sup>	Parallel Port	In Data High	Byte (Buffer 3	5)					0000 0000	68, 170
PMDIN2L <sup>(5)</sup>	Parallel Port	In Data Low I	Byte (Buffer 2	)					0000 0000	68, 170
PMEH <sup>(5)</sup>	PTEN15	PTEN14	PTEN13	PTEN12	PTEN11	PTEN10	PTEN9	PTEN8	0000 0000	68, 168
PMEL <sup>(5)</sup>	PTEN7	PTEN6	PTEN5	PTEN4	PTEN3	PTEN2	PTEN1	PTEN0	0000 0000	68, 168
PMSTATH <sup>(5)</sup>	IBF	IBOV	_	_	IB3F	IB2F	IB1F	IB0F	00 0000	68, 169
PMSTATL <sup>(5)</sup>	OBE	OBUF	_	_	OB3E	OB2E	OB1E	OB0E	10 1111	68, 169
CVRCON <sup>(5)</sup>	CVREN	CVROE	CVRR	r	CVR3	CVR2	CVR1	CVR0	0000 0000	68, 388
TCLKCON	_	_	_	T1RUN	_	_	T3CCP2	T3CCP1	000	195
DSGPR1	Deep Sleep I	Persistent Ge	neral Purpose	e Register (co	ntents retained	even in Deep	Sleep)		XXXX XXXX	52
DSGPR0	Deep Sleep I	Persistent Ge	neral Purpose	e Register (co	ntents retained	even in Deep	Sleep)		XXXX XXXX	52
DSCONH	DSEN	—	_	_	_	(Reserved)	DSULPEN	RTCWDIS	0000	51
DSCONL	_	_	_	_	_	ULPWDIS	DSBOR	RELEASE	000	51
DSWAKEH	_	_	_	_	_	—	—	DSINT0	0	53

#### TABLE 5.4 REGISTER FILE SUMMARY (PIC18E46 150 EAMILY) (CONTINUED)

Legend: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition, r = reserved. Bold indicates shared access SFRs. Note 1:

Bit 21 of the PC is only available in Serial Programming (SP) modes.

2: Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

Alternate names and definitions for these bits when the MSSP module is operating in  $l^2C^{TM}$  Slave mode. See Section 18.5.3.2 "Address and the the MSSP module is operating in  $l^2C^{TM}$  Slave mode. 4: Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

6: The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

### TABLE 5-4: REGISTER FILE SUMMARY (PIC18F46J50 FAMILY) (CONTINUED)

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
ANCON1	VBGEN	r	—	PCFG12	PCFG11	PCFG10	PCFG9	PCFG8	00-0 0000	68, 342
ANCON0	PCFG7 <sup>(5)</sup>	PCFG6 <sup>(5)</sup>	PCFG5 <sup>(5)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	0000 0000	68, 341
ODCON1	_	_	_	_	—	—	ECCP20D	ECCP10D	00	68, 127
ODCON2	_	_	_	_	—	—	U2OD	U10D	00	68, 127
ODCON3	_	_	_	_	_	_	SPI2OD	SPI10D	00	68, 128
RTCCFG	RTCEN	_	RTCWREN	RTCSYNC	HALFSEC	RTCOE	RTCPTR1	RTCPTR0	0-00 0000	68, 221
RTCCAL	CAL7	CAL6	CAL5	CAL4	CAL3	CAL2	CAL1	CAL0	0000 0000	68, 222
REFOCON	ROON	—	ROSSLP	ROSEL	RODIV3	RODIV2	RODIV1	RODIV0	0-00 0000	68, 38
PADCFG1	—	—			_	RTSECSEL1	RTSECSEL0	PMPTTL	000	68, 128
UCFG	UTEYE	UOEMON		UPUEN	UTRDIS	FSEN	PPB1	PPB0	00-0 0000	68, 354
UADDR	—	ADDR6	ADDR5	ADDR4	ADDR3	ADDR2	ADDR1	ADDR0	-000 0000	68, 359
UEIE	BTSEE	—		BTOEE	DFN8EE	CRC16EE	CRC5EE	PIDEE	00 0000	68, 371
UIE	—	SOFIE	STALLIE	IDLEIE	TRNIE	ACTVIE	UERRIE	URSTIE	-000 0000	68, 369
UEP15	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP14	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP13	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP12	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP11	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP10	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP9	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP8	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP7	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	68, 358
UEP6	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
UEP5	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
UEP4	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
UEP3	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
UEP2	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
UEP1	—	—		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
UEP0	—	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	0 0000	69, 358
PPSCON	—	_	_	_	—	—	_	IOLOCK	0	148
RPINR24	—	_	_	-	nput Function I	LT0 to Input P	in Mapping Bits		1 1111	69, 153
RPINR23	_	_	_	I	nput Function	SS2 to Input Pi	n Mapping Bits		1 1111	69, 153
RPINR22	_	_	_	Ir	nput Function S	SCK2 to Input F	in Mapping Bits	6	1 1111	69, 153
RPINR21	_	_	_		nput Function S	SDI2 to Input P	in Mapping Bits		1 1111	69, 152
RPINR17	_	_	_				n Mapping Bits		1 1111	69, 152
RPINR16	_	_	_	Inp	ts	1 1111	69			
RPINR13	_	—	_	i		1 1111	69			
RPINR12	_	—	_	I	1 1111	69, 151				
RPINR8	_	_	_							69, 151
RPINR7	_	_	_							69, 150
RPINR6	_	_	_		-	· · · · · · · · · · · · · · · · · · ·	Pin Mapping Bits	3	1 1111	69, 150
	1					OCKI to Input F			1 1111	

Legend: Note 1

x = unknown, u = unchanged, - = unimplemented, q = value depends on condition, r = reserved. Bold indicates shared access SFRs.

1: Bit 21 of the PC is only available in Serial Programming (SP) modes.

**2:** Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

4: Alternate names and definitions for these bits when the MSSP module is operating in I<sup>2</sup>C<sup>™</sup> Slave mode. See Section 18.5.3.2 "Address Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

6: The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

IADLE 3-4:	I/LOI				C10F40J5					
File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
RPINR3	—		_		Input Function I	NT3 to Input P	in Mapping Bits		1 1111	69, 149
RPINR2	_	_	_		Input Function I	NT2 to Input P	in Mapping Bits		1 1111	69
RPINR1	_	_	_		Input Function I	NT1 to Input P	in Mapping Bits		1 1111	69, 149
RPOR24 <sup>(5)</sup>	—	_	_	R	emappable Pin	RP24 Output S	Signal Select Bi	ts	0 0000	69, 161
RPOR23 <sup>(5)</sup>	—	_	_	R	emappable Pin	RP23 Output S	Signal Select Bi	ts	0 0000	69, 160
RPOR22 <sup>(5)</sup>	_	_	_	R	emappable Pin	RP22 Output S	Signal Select Bi	ts	0 0000	69, 160
RPOR21 <sup>(5)</sup>		-		R	emappable Pin	RP21 Output S	Signal Select Bi	ts	0 0000	69, 160
RPOR20 <sup>(5)</sup>	_	_	_	R	emappable Pin	RP20 Output S	Signal Select Bi	ts	0 0000	69, 159
RPOR19 <sup>(5)</sup>	_	_	_	R	emappable Pin	RP19 Output 8	Signal Select Bi	ts	0 0000	69, 159
RPOR18	_	_	_	R	emappable Pin	RP18 Output 8	Signal Select Bi	ts	0 0000	69, 159
RPOR17	_	_	_	R	emappable Pin	RP17 Output S	Signal Select Bi	ts	0 0000	69, 158
RPOR13	_	_	_	R	emappable Pin	RP13 Output S	Signal Select Bi	ts	0 0000	69, 158
RPOR12	-	_	_	R	emappable Pin	RP12 Output S	Signal Select Bi	ts	0 0000	69, 158
RPOR11	_	_	_	R	emappable Pin	RP11 Output S	Signal Select Bit	s	0 0000	69, 157
RPOR10	_	_	_	R	emappable Pin	RP10 Output S	Signal Select Bi	ts	0 0000	70, 157
RPOR9	_	_	_	F	Remappable Pir	n RP9 Output S	ignal Select Bit	S	0 0000	70, 157
RPOR8	_	_	_	F	Remappable Pir	n RP8 Output S	ignal Select Bit	S	0 0000	70, 156
RPOR7	_	_	_	F	Remappable Pir	n RP7 Output S	ignal Select Bit	S	0 0000	70, 156
RPOR6	_	_	_	F	Remappable Pir	n RP6 Output S	ignal Select Bit	S	0 0000	70, 156
RPOR5	_	_	_	F	Remappable Pir	n RP5 Output S	ignal Select Bit	S	0 0000	70, 155
RPOR4	_	_	_	F	Remappable Pir	n RP4 Output S	ignal Select Bit	S	0 0000	70, 155
RPOR3	_	_	_	F	Remappable Pir	n RP3 Output S	ignal Select Bit	S	0 0000	70, 155
RPOR2	_	_	_	R	Remappable Pir	n RP2 Output S	ignal Select Bit	S	0 0000	70, 154
RPOR1	_	_	_	Remappable Pin RP1 Output Signal Select Bits					0 0000	70, 154
RPOR0	_	_	_				ignal Select Bits		0 0000	70, 154

### TABLE 5-4:REGISTER FILE SUMMARY (PIC18F46J50 FAMILY) (CONTINUED)

Legend: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition, r = reserved. Bold indicates shared access SFRs.

**Note** 1: Bit 21 of the PC is only available in Serial Programming (SP) modes.

2: Reset value is '0' when Two-Speed Start-up is enabled and '1' if disabled.

3: The SSPxMSK registers are only accessible when SSPxCON2<3:0> = 1001.

4: Alternate names and definitions for these bits when the MSSP module is operating in I<sup>2</sup>C<sup>™</sup> Slave mode. See Section 18.5.3.2 "Address Masking Modes" for details.

5: These bits and/or registers are only available in 44-pin devices; otherwise, they are unimplemented and read as '0'. Reset values are shown for 44-pin devices.

6: The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the same physical registers and addresses, but have different functions determined by the module's operating mode. See Section 10.1.2 "Data Registers" for more information.

### 5.3.6 STATUS REGISTER

The STATUS register in Register 5-2, contains the arithmetic status of the ALU. The STATUS register can be the operand for any instruction, as with any other register. If the STATUS register is the destination for an instruction that affects the Z, DC, C, OV or N bits, then the write to these five bits is disabled.

These bits are set or cleared according to the device logic. Therefore, the result of an instruction with the STATUS register as destination may be different than intended. For example, CLRF STATUS will set the Z bit but leave the other bits unchanged. The STATUS

register then reads back as '000u u1uu'. It is recommended, therefore, that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the STATUS register because these instructions do not affect the Z, C, DC, OV or N bits in the STATUS register.

For other instructions not affecting any Status bits, see the instruction set summary in Table 27-2 and Table 27-3.

Note: The C and DC bits operate as a borrow and digit borrow bits respectively, in subtraction.

### REGISTER 5-2: STATUS REGISTER (ACCESS FD8h)

U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x			
	_		Ν	OV	Z	DC <sup>(1)</sup>	C <sup>(2)</sup>			
bit 7							bit (			
Legend: R = Read		W = Writable	hit	II – Unimplon	contod hit roc	ad aa '0'				
	e at POR	'1' = Bit is se		U = Unimplen '0' = Bit is clea		x = Bit is unkr				
-11 – valu	e al FOR		L		areu		IOWIT			
bit 7-5	Unimpleme	ented: Read as	<b>'</b> 0'							
bit 4	N: Negative	N: Negative bit								
		This bit is used for signed arithmetic (2's complement). It indicates whether the result was negative ALU MSB = $1$ ).								
		= Result was negative = Result was positive								
bit 3	OV: Overflo	w bit								
		sed for signed a es the sign bit (b			ndicates an ov	verflow of the 7-I	oit magnitude			
		w occurred for si flow occurred	gned arithmeti	c (in this arithm	etic operation	)				
bit 2	Z: Zero bit									
		ult of an arithme ult of an arithme	• •		0					
bit 1	DC: Digit ca	arry/borrow bit <sup>(1)</sup>								
		ADDLW, SUBLW								
		out from the 4 <sup>th</sup> y-out from the 4 <sup>t</sup>			urred					
bit 0	C: Carry/bo	•								
		ADDLW, SUBLW	and SUBWF in	structions:						
	•	out from the MS								
	0 = No carr	y-out from the M	Sb of the resul	t occurred						
Note 1:	For borrow, the									
c	·					4 or bit 3 of the s	•			
2:	For borrow, the									
	operand. For ro	operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low-order bit of the								

source register.

### 5.4 Data Addressing Modes

Note: The execution of some instructions in the core PIC18 instruction set are changed when the PIC18 extended instruction set is enabled. See Section 5.6 "Data Memory and the Extended Instruction Set" for more information.

While the program memory can be addressed in only one way, through the PC, information in the data memory space can be addressed in several ways. For most instructions, the addressing mode is fixed. Other instructions may use up to three modes, depending on which operands are used and whether or not the extended instruction set is enabled.

The addressing modes are:

- Inherent
- Literal
- Direct
- Indirect

An additional addressing mode, Indexed Literal Offset, is available when the extended instruction set is enabled (XINST Configuration bit = 1). Its operation is discussed in more detail in **Section 5.6.1 "Indexed Addressing with Literal Offset**".

### 5.4.1 INHERENT AND LITERAL ADDRESSING

Many PIC18 control instructions do not need any argument at all; they either perform an operation that globally affects the device, or they operate implicitly on one register. This addressing mode is known as Inherent Addressing. Examples include SLEEP, RESET and DAW.

Other instructions work in a similar way, but require an additional explicit argument in the opcode. This is known as Literal Addressing mode, because they require some literal value as an argument. Examples include ADDLW and MOVLW, which respectively, add or move a literal value to the W register. Other examples include CALL and GOTO, which include a 20-bit program memory address.

### 5.4.2 DIRECT ADDRESSING

Direct Addressing specifies all or part of the source and/or destination address of the operation within the opcode itself. The options are specified by the arguments accompanying the instruction.

In the core PIC18 instruction set, bit-oriented and byte-oriented instructions use some version of Direct Addressing by default. All of these instructions include some 8-bit Literal Address as their LSB. This address specifies either a register address in one of the banks of data RAM (Section 5.3.4 "General Purpose **Register File**"), or a location in the Access Bank (Section 5.3.3 "Access Bank") as the data source for the instruction.

The Access RAM bit, 'a', determines how the address is interpreted. When 'a' is '1', the contents of the BSR (Section 5.3.2 "Bank Select Register") are used with the address to determine the complete 12-bit address of the register. When 'a' is '0', the address is interpreted as being a register in the Access Bank. Addressing that uses the Access RAM is sometimes also known as Direct Forced Addressing mode.

A few instructions, such as MOVFF, include the entire 12-bit address (either source or destination) in their opcodes. In these cases, the BSR is ignored entirely.

The destination of the operation's results is determined by the destination bit, 'd'. When 'd' is '1', the results are stored back in the source register, overwriting its original contents. When 'd' is '0', the results are stored in the W register. Instructions without the 'd' argument have a destination that is implicit in the instruction; their destination is either the target register being operated on or the W register.

### 5.4.3 INDIRECT ADDRESSING

Indirect Addressing allows the user to access a location in data memory without giving a fixed address in the instruction. This is done by using File Select Registers (FSRs) as pointers to the locations to be read or written to. Since the FSRs are themselves located in RAM as SFRs, they can also be directly manipulated under program control. This makes FSRs very useful in implementing data structures such as tables and arrays in data memory.

The registers for Indirect Addressing are also implemented with Indirect File Operands (INDFs) that permit automatic manipulation of the pointer value with auto-incrementing, auto-decrementing or offsetting with another value. This allows for efficient code using loops, such as the example of clearing an entire RAM bank in Example 5-5. It also enables users to perform Indexed Addressing and other Stack Pointer operations for program memory in data memory.

### EXAMPLE 5-5: HOW TO CLEAR RAM (BANK 1) USING INDIRECT ADDRESSING

	LFSR	FSR0, 100h	;
NEXT	CLRF	POSTINC0	; Clear INDF
			; register then
			; inc pointer
	BTFSS	FSROH, 1	; All done with
			; Bank1?
	BRA	NEXT	; NO, clear next
CONTINU	JE		; YES, continue

### 5.4.3.1 FSR Registers and the INDF Operand (INDF)


At the core of Indirect Addressing are three sets of registers: FSR0, FSR1 and FSR2. Each represents a pair of 8-bit registers, FSRnH and FSRnL. The four upper bits of the FSRnH register are not used, so each FSR pair holds a 12-bit value. This represents a value that can address the entire range of the data memory in a linear fashion. The FSR register pairs, then, serve as pointers to data memory locations.

Indirect Addressing is accomplished with a set of INDF operands, INDF0 through INDF2. These can be presumed as "virtual" registers: they are mapped in the

### FIGURE 5-8: INDIRECT ADDRESSING

SFR space but are not physically implemented. Reading or writing to a particular INDF register actually accesses its corresponding FSR register pair. A read from INDF1, for example, reads the data at the address indicated by FSR1H:FSR1L. Instructions that use the INDF registers as operands actually use the contents of their corresponding FSR as a pointer to the instruction's target. The INDF operand is just a convenient way of using the pointer.

Because Indirect Addressing uses a full 12-bit address, data RAM banking is not necessary. Thus, the current contents of the BSR and the Access RAM bit have no effect on determining the target address.



### 5.4.3.2 FSR Registers and POSTINC, POSTDEC, PREINC and PLUSW

In addition to the INDF operand, each FSR register pair also has four additional indirect operands. Like INDF, these are "virtual" registers that cannot be indirectly read or written to. Accessing these registers actually accesses the associated FSR register pair, but also performs a specific action on its stored value. They are:

- POSTDEC: accesses the FSR value, then automatically decrements it by '1' thereafter
- POSTINC: accesses the FSR value, then automatically increments it by '1' thereafter
- PREINC: increments the FSR value by '1', then uses it in the operation
- PLUSW: adds the signed value of the W register (range of 127 to 128) to that of the FSR and uses the new value in the operation

In this context, accessing an INDF register uses the value in the FSR registers without changing them. Similarly, accessing a PLUSW register gives the FSR value offset by the value in the W register; neither value is actually changed in the operation. Accessing the other virtual registers changes the value of the FSR registers.

Operations on the FSRs with POSTDEC, POSTINC and PREINC affect the entire register pair; that is, rollovers of the FSRnL register from FFh to 00h carry over to the FSRnH register. On the other hand, results of these operations do not change the value of any flags in the STATUS register (e.g., Z, N, OV, etc.).

The PLUSW register can be used to implement a form of Indexed Addressing in the data memory space. By manipulating the value in the W register, users can reach addresses that are fixed offsets from pointer addresses. In some applications, this can be used to implement some powerful program control structure, such as software stacks, inside of data memory.

### 5.4.3.3 Operations by FSRs on FSRs

Indirect Addressing operations that target other FSRs or virtual registers represent special cases. For example, using an FSR to point to one of the virtual registers will not result in successful operations. As a specific case, assume that FSR0H:FSR0L contains FE7h, the address of INDF1. Attempts to read the value of the INDF1, using INDF0 as an operand, will return 00h. Attempts to write to INDF1, using INDF0 as the operand, will result in a NOP.

On the other hand, using the virtual registers to write to an FSR pair may not occur as planned. In these cases, the value will be written to the FSR pair but without any incrementing or decrementing. Thus, writing to INDF2 or POSTDEC2 will write the same value to the FSR2H:FSR2L. Since the FSRs are physical registers mapped in the SFR space, they can be manipulated through all direct operations. Users should proceed cautiously when working on these registers, particularly if their code uses Indirect Addressing.

Similarly, operations by Indirect Addressing are generally permitted on all other SFRs. Users should exercise appropriate caution that they do not inadvertently change settings that might affect the operation of the device.

### 5.5 Program Memory and the Extended Instruction Set

The operation of program memory is unaffected by the use of the extended instruction set.

Enabling the extended instruction set adds five additional two-word commands to the existing PIC18 instruction set: ADDFSR, CALLW, MOVSF, MOVSS and SUBFSR. These instructions are executed as described in Section 5.2.4 "Two-Word Instructions".

# 5.6 Data Memory and the Extended Instruction Set

Enabling the PIC18 extended instruction set (XINST Configuration bit = 1) significantly changes certain aspects of data memory and its addressing. Specifically, the use of the Access Bank for many of the core PIC18 instructions is different. This is due to the introduction of a new addressing mode for the data memory space. This mode also alters the behavior of Indirect Addressing using FSR2 and its associated operands.

What does not change is just as important. The size of the data memory space is unchanged, as well as its linear addressing. The SFR map remains the same. Core PIC18 instructions can still operate in both Direct and Indirect Addressing mode; inherent and literal instructions do not change at all. Indirect Addressing with FSR0 and FSR1 also remains unchanged.

## 5.6.1 INDEXED ADDRESSING WITH LITERAL OFFSET

Enabling the PIC18 extended instruction set changes the behavior of Indirect Addressing using the FSR2 register pair and its associated file operands. Under proper conditions, instructions that use the Access Bank, that is, most bit and byte-oriented instructions, can invoke a form of Indexed Addressing using an offset specified in the instruction. This special addressing mode is known as Indexed Addressing with Literal Offset, or Indexed Literal Offset mode.

When using the extended instruction set, this addressing mode requires the following:

- The use of the Access Bank is forced ('a' = 0); and
- The file address argument is less than or equal to 5Fh.

Under these conditions, the file address of the instruction is not interpreted as the lower byte of an address (used with the BSR in Direct Addressing) or as an 8-bit address in the Access Bank. Instead, the value is interpreted as an offset value to an Address Pointer specified by FSR2. The offset and the contents of FSR2 are added to obtain the target address of the operation.


### 5.6.2 INSTRUCTIONS AFFECTED BY INDEXED LITERAL OFFSET MODE

Any of the core PIC18 instructions that can use Direct Addressing are potentially affected by the Indexed Literal Offset Addressing mode. This includes all byte and bit-oriented instructions, or almost one-half of the standard PIC18 instruction set. Instructions that only use Inherent or Literal Addressing modes are unaffected.

Additionally, byte and bit-oriented instructions are not affected if they use the Access Bank (Access RAM bit is '1') or include a file address of 60h or above. Instructions meeting these criteria will continue to execute as before. A comparison of the different possible addressing modes when the extended instruction set is enabled is provided in Figure 5-9.

Those who desire to use byte or bit-oriented instructions in the Indexed Literal Offset mode should note the changes to assembler syntax for this mode. This is described in more detail in **Section 27.2.1 "Extended Instruction Syntax"**.

## FIGURE 5-9: COMPARING ADDRESSING OPTIONS FOR BIT-ORIENTED AND BYTE-ORIENTED INSTRUCTIONS (EXTENDED INSTRUCTION SET ENABLED)



### 5.6.3 MAPPING THE ACCESS BANK IN INDEXED LITERAL OFFSET MODE

The use of Indexed Literal Offset Addressing mode effectively changes how the lower part of Access RAM (00h to 5Fh) is mapped. Rather than containing just the contents of the bottom part of Bank 0, this mode maps the contents from Bank 0 and a user-defined "window" that can be located anywhere in the data memory space. The value of FSR2 establishes the lower boundary of the addresses mapped to the window, while the upper boundary is defined by FSR2 plus 95 (5Fh). Addresses in the Access RAM above 5Fh are mapped as previously described (see **Section 5.3.3** "**Access Bank**"). Figure 5-10 provides an example of Access Bank remapping in this addressing mode.

Remapping of the Access Bank applies *only* to operations using the Indexed Literal Offset mode. Operations that use the BSR (Access RAM bit is '1') will continue to use Direct Addressing as before. Any Indirect or Indexed Addressing operation that explicitly uses any of the indirect file operands (including FSR2) will continue to operate as standard Indirect Addressing. Any instruction that uses the Access Bank, but includes a register address of greater than 05Fh, will use Direct Addressing and the normal Access Bank map.

### 5.6.4 BSR IN INDEXED LITERAL OFFSET MODE

Although the Access Bank is remapped when the extended instruction set is enabled, the operation of the BSR remains unchanged. Direct Addressing, using the BSR to select the data memory bank, operates in the same manner as previously described.

### FIGURE 5-10: REMAPPING THE ACCESS BANK WITH INDEXED LITERAL OFFSET ADDRESSING


#### Example Situation:

ADDWF f, d, a FSR2H:FSR2L = 120h

Locations in the region from the FSR2 Pointer (120h) to the pointer plus 05Fh (17Fh) are mapped to the bottom of the Access RAM (000h-05Fh).

Special Function Registers at F60h through FFFh are mapped to 60h through FFh, as usual.

Bank 0 addresses below 5Fh are not available in this mode. They can still be addressed by using the BSR.



### 6.0 FLASH PROGRAM MEMORY

The Flash program memory is readable, writable and erasable during normal operation over the entire  $\mathsf{V}\mathsf{D}\mathsf{D}$  range.

A read from program memory is executed on 1 byte at a time. A write to program memory is executed on blocks of 64 bytes at a time or 2 bytes at a time. Program memory is erased in blocks of 1024 bytes at a time. A bulk erase operation may not be issued from user code.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, therefore, code cannot execute. An internal programming timer terminates program memory writes and erases.

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP.

### 6.1 Table Reads and Table Writes

In order to read and write program memory, there are two operations that allow the processor to move bytes between the program memory space and the data RAM:

- Table Read (TBLRD)
- Table Write (TBLWT)

The program memory space is 16 bits wide, while the data RAM space is 8 bits wide. Table reads and table writes move data between these two memory spaces through an 8-bit register (TABLAT).


Table read operations retrieve data from program memory and place it into the data RAM space. Figure 6-1 illustrates the operation of a table read with program memory and data RAM.

Table write operations store data from the data memory space into holding registers in program memory. The procedure to write the contents of the holding registers into program memory is detailed in **Section 6.5** "**Writing to Flash Program Memory**". Figure 6-2 illustrates the operation of a table write with program memory and data RAM.


Table operations work with byte entities. A table block containing data, rather than program instructions, is not required to be word-aligned. Therefore, a table block can start and end at any byte address. If a table write is being used to write executable code into program memory, program instructions will need to be word-aligned.

FIGURE 6-1:

### TABLE READ OPERATION



### FIGURE 6-2: TABLE WRITE OPERATION



### 6.2 Control Registers

Several control registers are used in conjunction with the TBLRD and TBLWT instructions. Those are:

- EECON1 register
- · EECON2 register
- TABLAT register
- TBLPTR registers

### 6.2.1 EECON1 AND EECON2 REGISTERS

The EECON1 register (Register 6-1) is the control register for memory accesses. The EECON2 register is not a physical register; it is used exclusively in the memory write and erase sequences. Reading EECON2 will read all '0's.

The WPROG bit, when set, will allow programming two bytes per word on the execution of the WR command. If this bit is cleared, the WR command will result in programming on a block of 64 bytes. The FREE bit, when set, will allow a program memory erase operation. When FREE is set, the erase operation is initiated on the next WR command. When FREE is clear, only writes are enabled.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set in hardware when the WR bit is set and cleared when the internal programming timer expires and the write operation is complete.

Note:	During normal operation, the WRERR is
	read as '1'. This can indicate that a write
	operation was prematurely terminated by
	a Reset, or a write operation was
	attempted improperly.

The WR control bit initiates write operations. The bit cannot be cleared, only set, in software. It is cleared in hardware at the completion of the write operation.

### REGISTER 6-1: EECON1: EEPROM CONTROL REGISTER 1 (ACCESS FA6h)

U-0	U-0	R/W-0	R/W-0	R/W-x	R/W-0	R/S-0	U-0
—	—	WPROG	FREE	WRERR	WREN	WR	—
bit 7							bit 0

Legend:	S = Settable bit (cannot b	be cleared in software)	
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-6	Unimplemented: Read as '0'
bit 5	WPROG: One Word-Wide Program bit
	1 = Program 2 bytes on the next WR command
	0 = Program 64 bytes on the next WR command
bit 4	FREE: Flash Erase Enable bit
	<ul> <li>1 = Perform an erase operation on the next WR command (cleared by hardware after completion of erase)</li> <li>0 = Perform write only</li> </ul>
bit 3	WRERR: Flash Program Error Flag bit
	1 = A write operation is prematurely terminated (any Reset during self-timed programming in normal operation, or an improper write attempt)
	0 = The write operation completed
bit 2	WREN: Flash Program Write Enable bit
	<ul> <li>1 = Allows write cycles to Flash program memory</li> <li>0 = Inhibits write cycles to Flash program memory</li> </ul>
bit 1	WR: Write Control bit
bit i	
	<ul> <li>1 = Initiates a program memory erase cycle or write cycle</li> <li>(The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.)</li> </ul>
	0 = Write cycle is complete
bit 0	Unimplemented: Read as '0'

### 6.2.2 TABLE LATCH REGISTER (TABLAT)

The Table Latch (TABLAT) is an 8-bit register mapped into the Special Function Register (SFR) space. The Table Latch register is used to hold 8-bit data during data transfers between program memory and data RAM.

### 6.2.3 TABLE POINTER REGISTER (TBLPTR)

The Table Pointer (TBLPTR) register addresses a byte within the program memory. The TBLPTR comprises three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). These three registers join to form a 22-bit wide pointer. The low-order 21 bits allow the device to address up to 2 Mbytes of program memory space. The 22<sup>nd</sup> bit allows access to the device ID, the user ID and the Configuration bits.

The Table Pointer register, TBLPTR, is used by the TBLRD and TBLWT instructions. These instructions can update the TBLPTR in one of four ways based on the table operation.

Table 6-1 provides these operations. These operations on the TBLPTR only affect the low-order 21 bits.

### 6.2.4 TABLE POINTER BOUNDARIES

TBLPTR is used in reads, writes and erases of the Flash program memory.

When a TBLRD is executed, all 22 bits of the TBLPTR determine which byte is read from program memory into TABLAT.

When a TBLWT is executed, the seven Least Significant bits (LSbs) of the Table Pointer register (TBLPTR<6:0>) determine which of the 64 program memory holding registers is written to. When the timed write to program memory begins (via the WR bit), the 12 Most Significant bits (MSbs) of the TBLPTR (TBLPTR<21:10>) determine which program memory block of 1024 bytes is written to. For more information, see Section 6.5 "Writing to Flash Program Memory".

When an erase of program memory is executed, the 12 MSbs of the Table Pointer register point to the 1024-byte block that will be erased. The LSbs are ignored.


Figure 6-3 illustrates the relevant boundaries of TBLPTR based on Flash program memory operations.

Example	Operation on Table Pointer
TBLRD* TBLWT*	TBLPTR is not modified
TBLRD*+ TBLWT*+	TBLPTR is incremented after the read/write
TBLRD*- TBLWT*-	TBLPTR is decremented after the read/write
TBLRD+* TBLWT+*	TBLPTR is incremented before the read/write

### TABLE 6-1: TABLE POINTER OPERATIONS WITH TBLRD AND TBLWT INSTRUCTIONS

#### FIGURE 6-3:

#### TABLE POINTER BOUNDARIES BASED ON OPERATION



### 6.3 Reading the Flash Program Memory


The TBLRD instruction is used to retrieve data from program memory and places it into data RAM. Table reads from program memory are performed one byte at a time.

TBLPTR points to a byte address in program space. Executing TBLRD places the byte pointed to into TABLAT. In addition, TBLPTR can be modified automatically for the next table read operation.

The internal program memory is typically organized by words. The LSb of the address selects between the high and low bytes of the word.

Figure 6-4 illustrates the interface between the internal program memory and the TABLAT.

### FIGURE 6-4: READS FROM FLASH PROGRAM MEMORY



### EXAMPLE 6-1: READING A FLASH PROGRAM MEMORY WORD

MOVLW CODE_ADDR_LOW MOVWF TBLPTRL READ WORD	
TBLRD*+ ; read into TABLAT and increment MOVF TABLAT, W ; get data	
MOVWF WORD_EVEN TBLRD*+ ; read into TABLAT and increment MOVF TABLAT, W ; get data MOVWF WORD ODD	DVWF       WORD_EVEN         BLRD*+       ; read into TABLAT and increment         DVF       TABLAT, W       ; get data

### 6.4 Erasing Flash Program Memory

The minimum erase block is 512 words or 1024 bytes. Only through the use of an external programmer, or through ICSP control, can larger blocks of program memory be bulk erased. Word erase in the Flash array is not supported.

When initiating an erase sequence from the microcontroller itself, a block of 1024 bytes of program memory is erased. The Most Significant 12 bits of the TBLPTR<21:10> point to the block being erased; TBLPTR<9:0> are ignored.

The EECON1 register commands the erase operation. The WREN bit must be set to enable write operations. The FREE bit is set to select an erase operation. For protection, the write initiate sequence for EECON2 must be used.

A long write is necessary for erasing the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

### 6.4.1 FLASH PROGRAM MEMORY ERASE SEQUENCE

The sequence of events for erasing a block of internal program memory location is:

- 1. Load Table Pointer register with address of row being erased.
- 2. Set the WREN and FREE bits (EECON1<2,4>) to enable the erase operation.
- 3. Disable interrupts.
- 4. Write 55h to EECON2.
- 5. Write 0AAh to EECON2.
- 6. Set the WR bit; this will begin the erase cycle.
- The CPU will stall for the duration of the erase for TIE (see parameter D133B).
- 8. Re-enable interrupts.

### EXAMPLE 6-2: ERASING FLASH PROGRAM MEMORY

	MOVLW MOVWF MOVUW MOVWF MOVLW MOVWF	CODE_ADDR_UPPER TBLPTRU CODE_ADDR_HIGH TBLPTRH CODE_ADDR_LOW TBLPTRL	; load TBLPTR with the base ; address of the memory block
ERASE_ROW			
	BSF	EECON1, WREN	; enable write to memory
	BSF	EECON1, FREE	; enable Erase operation
	BCF	INTCON, GIE	; disable interrupts
Required	MOVLW	55h	
Sequence	MOVWF	EECON2	; write 55h
	MOVLW	0AAh	
	MOVWF	EECON2	; write OAAh
	BSF	EECON1, WR	; start erase (CPU stall)
	BSF	INTCON, GIE	; re-enable interrupts

### 6.5 Writing to Flash Program Memory

The programming block is 32 words or 64 bytes. Programming one word or 2 bytes at a time is also supported.

Table writes are used internally to load the holding registers needed to program the Flash memory. There are 64 holding registers used by the table writes for programming.


Since the Table Latch (TABLAT) is only a single byte, the TBLWT instruction may need to be executed 64 times for each programming operation (if WPROG = 0). All of the table write operations will essentially be short writes because only the holding registers are written. At the end of updating the 64 holding registers, the EECON1 register must be written to in order to start the programming operation with a long write.

The long write is necessary for programming the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

The on-chip timer controls the write time. The write/erase voltages are generated by an on-chip charge pump, rated to operate over the voltage range of the device.

- Note 1: Unlike previous PIC<sup>®</sup> devices, devices of the PIC18F46J50 Family do not reset the holding registers after a write occurs. The holding registers must be cleared or overwritten before a programming sequence.
  - 2: To maintain the endurance of the program memory cells, each Flash byte should not be programmed more than once between erase operations. Before attempting to modify the contents of the target cell a second time, an erase of the target page, or a bulk erase of the entire memory, must be performed.

### FIGURE 6-5: TABLE WRITES TO FLASH PROGRAM MEMORY



### 6.5.1 FLASH PROGRAM MEMORY WRITE SEQUENCE

The sequence of events for programming an internal program memory location should be:

- 1. Read 1024 bytes into RAM.
- 2. Update data values in RAM as necessary.
- 3. Load Table Pointer register with address being erased.
- 4. Execute the erase procedure.
- 5. Load Table Pointer register with address of first byte being written, minus 1.
- 6. Write the 64 bytes into the holding registers with auto-increment.
- Set the WREN bit (EECON1<2>) to enable byte writes.

- 8. Disable interrupts.
- 9. Write 55h to EECON2.
- 10. Write 0AAh to EECON2.
- 11. Set the WR bit. This will begin the write cycle.
- 12. The CPU will stall for the duration of the write for TIW (see parameter D133A).
- 13. Re-enable interrupts.
- 14. Repeat steps 6 through 13 until all 1024 bytes are written to program memory.
- 15. Verify the memory (table read).

An example of the required code is provided in Example 6-3 on the following page.

Note: Before setting the WR bit, the Table Pointer address needs to be within the intended address range of the 64 bytes in the holding register.

EXAMPLE 6-3:	WRITING	G TO FLASH PROGRA	M MEMORY
ERASE BLOCK	MOVLW MOVWF MOVLW MOVLW MOVLW	TBLPTRH	; Load TBLPTR with the base address ; of the memory block, minus 1
_	BSF		; enable write to memory
	BSF BCF MOVLW	INTCON, GIE	; enable Erase operation ; disable interrupts
	MOVWF	EECON2	; write 55h
	MOVWF	EECON2	; write OAAh
	BSF BSF	INTCON, GIE	; start erase (CPU stall) ; re-enable interrupts
	MOVLW MOVWF	D'16' WRITE_COUNTER	; Need to write 16 blocks of 64 to write ; one erase block of 1024
RESTART_BUFFER	NOTITE		
	MOVLW MOVWF MOVLW		; point to buffer
	MOVWF		
FILL_BUFFER	PIOVWE	FSRUL	
			; read the new data from I2C, SPI, ; PSP, USART, etc.
WRITE_BUFFER	MOVLW MOVWF		; number of bytes in holding register
WRITE_BYTE_TO_HRE		DOGETNOS UDEC	
	MOVFF MOVWF TBLWT+*	TABLAT	; get low byte of buffer data ; present data to table latch ; write data, perform a short write
		COUNTER	; to internal TBLWT holding register. ; loop until buffers are full
PROGRAM_MEMORY	BRA	WRITE_BYTE_TO_HREGS	
	BSF BCF	EECON1, WREN INTCON, GIE	; enable write to memory ; disable interrupts
Required Sequence	MOVLW MOVWF MOVLW	55h EECON2 0AAh	; write 55h
	MOVWF BSF	EECON2 EECON1, WR	; write OAAh ; start program (CPU stall)
	BSF BCF	INTCON, GIE EECON1, WREN	; re-enable interrupts ; disable write to memory
	DECFSZ BRA	WRITE_COUNTER RESTART BUFFER	; done with one write cycle ; if not done replacing the erase block

### EXAMPLE 6-3: WRITING TO FLASH PROGRAM MEMORY

## 6.5.2 FLASH PROGRAM MEMORY WRITE SEQUENCE (WORD PRORAMMING).

The PIC18F46J50 Family of devices has a feature that allows programming a single word (two bytes). This feature is enabled when the WPROG bit is set. If the memory location is already erased, the following sequence is required to enable this feature:

- 1. Load the Table Pointer register with the address of the data to be written. (It must be an even address.)
- 2. Write the 2 bytes into the holding registers by performing table writes. (Do not post-increment on the second table write.)

- Set the WREN bit (EECON1<2>) to enable writes and the WPROG bit (EECON1<5>) to select Word Write mode.
- 4. Disable interrupts.
- 5. Write 55h to EECON2.
- 6. Write 0AAh to EECON2.
- 7. Set the WR bit; this will begin the write cycle.
- The CPU will stall for the duration of the write for TIW (see parameter D133A).
- 9. Re-enable interrupts.

	MOVLW	CODE_ADDR_UPPER	; Load TBLPTR with the base address
	MOVWF	TBLPTRU	
	MOVLW	CODE_ADDR_HIGH	
	MOVWF	TBLPTRH	
	MOVLW	CODE_ADDR_LOW	; The table pointer must be loaded with an even address
	MOVWF	TBLPTRL	
	MOVLW	DATA0	; LSB of word to be written
	MOVWF	TABLAT	
	TBLWT*-		
	MOVLW	DATA1	; MSB of word to be written
	MOVWF	TABLAT	
	TBLWT*		; The last table write must not increment the table
			pointer! The table pointer needs to point to the
			MSB before starting the write operation.
PROGRAM MEMORY			
	BSF	EECON1, WPROG	; enable single word write
	BSF	EECON1, WREN	; enable write to memory
	BCF	INTCON, GIE	; disable interrupts
	MOVLW	55h	
Required	MOVWF	EECON2	; write 55h
Sequence	MOVLW	0AAh	
	MOVWF	EECON2	; write AAh
	BSF	EECON1, WR	; start program (CPU stall)
	BSF	INTCON, GIE	; re-enable interrupts
	BCF	EECON1, WPROG	; disable single word write
	BCF	EECON1, WREN	; disable write to memory

### EXAMPLE 6-4: SINGLE-WORD WRITE TO FLASH PROGRAM MEMORY

### 6.5.3 WRITE VERIFY

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

### 6.5.4 UNEXPECTED TERMINATION OF WRITE OPERATION

If a write is terminated by an unplanned event, such as loss of power or an unexpected Reset, the memory location just programmed should be verified and reprogrammed if needed. If the write operation is interrupted by a MCLR Reset or a WDT time-out Reset during normal operation, the user can check the WRERR bit and rewrite the location(s) as needed.

### 6.6 Flash Program Operation During Code Protection

See Section 26.6 "Program Verification and Code Protection" for details on code protection of Flash program memory.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
TBLPTRU	_	_	bit 21	Program Me	mory Table F	Pointer Upper	Byte (TBLP	TR<20:16>)	63
TBPLTRH	Program M	Program Memory Table Pointer High Byte (TBLPTR<15:8>)					63		
TBLPTRL	Program M	Program Memory Table Pointer Low Byte (TBLPTR<7:0>)					63		
TABLAT	Program M	Program Memory Table Latch					63		
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
EECON2	Program Memory Control Register 2 (not a physical register)					65			
EECON1	_	_	WPROG	FREE	WRERR	WREN	WR	—	65

Legend: — = unimplemented, read as '0'. Shaded cells are not used during Flash program memory access.

### 7.0 8 x 8 HARDWARE MULTIPLIER

### 7.1 Introduction

All PIC18 devices include an 8 x 8 hardware multiplier as part of the ALU. The multiplier performs an unsigned operation and yields a 16-bit result that is stored in the product register pair, PRODH:PRODL. The multiplier's operation does not affect any flags in the STATUS register.

Making multiplication a hardware operation allows it to be completed in a single instruction cycle. This has the advantages of higher computational throughput and reduced code size for multiplication algorithms and allows the PIC18 devices to be used in many applications previously reserved for digital signal processors. Table 7-1 provides a comparison of various hardware and software multiply operations, along with the savings in memory and execution time.

### 7.2 Operation

Example 7-1 provides the instruction sequence for an 8 x 8 unsigned multiplication. Only one instruction is required when one of the arguments is already loaded in the WREG register.

Example 7-2 provides the instruction sequence for an 8 x 8 signed multiplication. To account for the sign bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

EXAMPLE 7-1:	8 x 8 UNSIGNED MULTIPLY
	ROUTINE

; ; ARG1 * ARG2 -> ; PRODH:PRODL		W		MOVF MULWF
----------------------------------------	--	---	--	---------------

### EXAMPLE 7-2:

8 x 8 SIGNED MULTIPLY

MOVF	ARG1, W	
MULWF	ARG2	; ARG1 * ARG2 ->
		; PRODH:PRODL
BTFSC	ARG2, SB	; Test Sign Bit
SUBWF	PRODH, F	; PRODH = PRODH
		; – ARG1
MOVF	ARG2, W	
BTFSC	ARG1, SB	; Test Sign Bit
SUBWF	PRODH, F	; PRODH = PRODH
		; – ARG2

		Program	Cycles	Time		
Routine	Multiply Method	Memory (Words)	(Max)	@ 48 MHz	@ 10 MHz	@ 4 MHz
9 x 9 upsigned	Without hardware multiply	13	69	5.7 μs	27.6 μs	69 μs
8 x 8 unsigned	Hardware multiply	1	1	83.3 ns	400 ns	1 μs
	Without hardware multiply	33	91	7.5 μs	36.4 μs	91 μs
8 x 8 signed	Hardware multiply	6	6	500 ns	2.4 μs	6 μs
10 x 10 uppigned	Without hardware multiply	21	242	20.1 μs	96.8 μs	242 μs
16 x 16 unsigned	Hardware multiply	28	28	2.3 μs	11.2 μs	28 μs
10 × 10 signed	Without hardware multiply	52	254	21.6 μs	102.6 μs	254 μs
16 x 16 signed	Hardware multiply	35	40	3.3 μs	16.0 μs	40 μs

### TABLE 7-1: PERFORMANCE COMPARISON FOR VARIOUS MULTIPLY OPERATIONS

Example 7-3 provides the instruction sequence for a 16 x 16 unsigned multiplication. Equation 7-1 provides the algorithm that is used. The 32-bit result is stored in four registers (RES<3:0>).

### EQUATION 7-1: 16 x 16 UNSIGNED MULTIPLICATION ALGORITHM

RES3:RES0	=	ARG1H:ARG1L · ARG2H:ARG2L
	=	$(ARG1H \cdot ARG2H \cdot 2^{16}) +$
		$(ARG1H \cdot ARG2L \cdot 2^8) +$
		$(ARG1L \cdot ARG2H \cdot 2^8) +$
		(ARG1L · ARG2L)

### EXAMPLE 7-3:

#### 16 x 16 UNSIGNED MULTIPLY ROUTINE

MOVF	ARG1L, W	
MULWF		; ARG1L * ARG2L->
		; PRODH:PRODL
MOVEE	PRODH, RES1	;
	PRODL, RESO	
;	,	,
	ARG1H, W	
MULWF		; ARG1H * ARG2H->
		; PRODH:PRODL
MOVFF	PRODH, RES3	
	PRODL, RES2	
;	110000, 11000	,
	ARG1L, W	
		; ARG1L * ARG2H->
110 2011	11110211	; PRODH:PRODL
MOVE	PRODL, W	;
	-	; Add cross
		; products
	RES2, F	;
	WREG	;
-	RES3, F	;
;	1000, 1	,
	ARG1H, W	;
	-	; ARG1H * ARG2L->
110 2012		; PRODH:PRODL
MOVF	PRODL, W	;
	,	; Add cross
		; products
	RES2, F	;
	WREG	;
	RES3, F	;
nibbiii C	1.200, 1	,

Example 7-4 provides the sequence to do a 16 x 16 signed multiply. Equation 7-2 provides the algorithm used. The 32-bit result is stored in four registers (RES<3:0>). To account for the sign bits of the arguments, the MSb for each argument pair is tested and the appropriate subtractions are done.

### EQUATION 7-2: 16 x 16 SIGNED MULTIPLICATION ALGORITHM

RES3:RES0	=	$\begin{array}{l} ARG1H:ARG1L \cdot ARG2H:ARG2L\\ (ARG1H \cdot ARG2H \cdot 2^{16}) +\\ (ARG1H \cdot ARG2L \cdot 2^8) +\\ (ARG1L \cdot ARG2H \cdot 2^8) +\\ (ARG1L \cdot ARG2H \cdot 2^8) +\\ (-1 \cdot ARG2H < 7 > \cdot ARG1H:ARG1L \cdot 2^{16}) +\\ (-1 \cdot ARG1H < 7 > \cdot ARG2H:ARG2L \cdot 2^{16}) +\\ \end{array}$
		( )

### EXAMPLE 7-4: 16 x 7

16 x 16 SIGNED MULTIPLY ROUTINE

		KOUII			
	MOVF	ARG1L, W			
	MULWF		;	ARG1L * ARG2L ->	
				PRODH:PRODL	
	MOVFF	PRODH, RES1	;		
	MOVFF	PRODL, RESO	;		
;		,	,		
,	MOVF	ARG1H, W			
	MULWF			ARG1H * ARG2H ->	
	110 2012	111(0211	;	PRODH: PRODL	
	MOVFF	PRODH, RES3	;	1100011110001	
	MOVFF	PRODL, RES2	;		
;	110 1 1 1	110000, 1000	,		
'	MOVE	ARG1L, W			
		ARG2H		ARG1L * ARG2H ->	
	PIOLIMI	11(0211		PRODH:PRODL	
	MOVF	PRODL, W	;	IIIODII.IIIODE	
		RES1, F		Add cross	
	MOVF	PRODH, W		products	
		RES2, F		Produces	
		WREG	;		
		RES3, F	;		
	ADDWIC	RESS, F	;		
'	MOVE	ARG1H, W			
	MULWF	ARG11, W ARG2L	;	ARG1H * ARG2L ->	
	MOLWE	ARGZL		PRODH:PRODL	
	MOVF	PRODL, W	;	FRODH.FRODL	
		RES1, F	;	Add cross	
	MOVF	PRODH, W		products	
		RES2, F		produces	
		WREG	; ;		
		RES3, F			
	ADDWIC	RESS, F	;		
;	BWECC	ARG2H, 7		ARG2H:ARG2L neg?	
	BRA	SIGN ARG1		no, check ARG1	
	MOVF	ARG1L, W		no, check Argi	
	SUBWF	RES2	;		
	MOVF	ARG1H, W	;		
	SUBWFB	-	;		
	SODMED	1/1100			
; STG	N ARG1				
510	_	ARG1H, 7		ARG1H:ARG1L neg?	
	BRA	CONT CODE		no, done	
	MOVF	ARG2L, W		no, done	
	SUBWF	RES2	;		
	MOVF	ARG2H, W	;		
	SUBWFB		;		
	SUDWED	COUNT			
, Cont code					
:					
	•				

# 8.0 INTERRUPTS

Devices of the PIC18F46J50 Family have multiple interrupt sources and an interrupt priority feature that allows most interrupt sources to be assigned a high-priority level or a low-priority level. The high-priority interrupt vector is at 0008h and the low-priority interrupt vector is at 0018h. High-priority interrupt events will interrupt any low-priority interrupts that may be in progress.

There are 13 registers, which are used to control interrupt operation. These registers are:

- RCON
- INTCON
- INTCON2
- INTCON3
- PIR1, PIR2, PIR3
- PIE1, PIE2, PIE3
- IPR1, IPR2, IPR3

It is recommended that the Microchip header files supplied with MPLAB<sup>®</sup> IDE be used for the symbolic bit names in these registers. This allows the assembler/compiler to automatically take care of the placement of these bits within the specified register.

In general, interrupt sources have three bits to control their operation. They are:

- Flag bit to indicate that an interrupt event occurred
- Enable bit that allows program execution to branch to the interrupt vector address when the flag bit is set
- **Priority bit** to select high priority or low priority

The interrupt priority feature is enabled by setting the IPEN bit (RCON<7>). When interrupt priority is enabled, there are two bits which enable interrupts globally. Setting the GIEH bit (INTCON<7>) enables all interrupts that have the priority bit set (high priority). Setting the GIEL bit (INTCON<6>) enables all interrupts that have the priority bit cleared (low priority). When the interrupt flag, enable bit and appropriate global interrupt enable bit are set, the interrupt will vector immediately to address 0008h or 0018h, depending on the priority bit setting. Individual interrupts can be disabled through their corresponding enable bits.

When the IPEN bit is cleared (default state), the interrupt priority feature is disabled and interrupts are compatible with PIC<sup>®</sup> mid-range devices. In Compatibility mode, the interrupt priority bits for each source have no effect. INTCON<6> is the PEIE bit, which enables/disables all peripheral interrupt sources. INTCON<7> is the GIE bit, which enables/disables all interrupt sources. All interrupts branch to address 0008h in Compatibility mode.

When an interrupt is responded to, the global interrupt enable bit is cleared to disable further interrupts. If the IPEN bit is cleared, this is the GIE bit. If interrupt priority levels are used, this will be either the GIEH or GIEL bit. High-priority interrupt sources can interrupt a low-priority interrupt. Low-priority interrupts are not processed while high-priority interrupts are in progress.

The return address is pushed onto the stack and the PC is loaded with the interrupt vector address (0008h or 0018h). Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bits must be cleared in software before re-enabling interrupts to avoid recursive interrupts.


The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit (GIEH or GIEL if priority levels are used), which re-enables interrupts.

For external interrupt events, such as the INTx pins or the PORTB input change interrupt, the interrupt latency will be three to four instruction cycles. The exact latency is the same for one or two-cycle instructions. Individual interrupt flag bits are set regardless of the status of their corresponding enable bit or the GIE bit.

Note: Do not use the MOVFF instruction to modify any of the interrupt control registers while any interrupt is enabled. Doing so may cause erratic microcontroller behavior.

# PIC18F46J50 FAMILY





#### 8.1 INTCON Registers

The INTCON registers are readable and writable registers, which contain various enable, priority and flag bits.

Note: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

#### **REGISTER 8-1:** INTCON: INTERRUPT CONTROL REGISTER (ACCESS FF2h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x
GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF <sup>(1)</sup>
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	GIE/GIEH: Global Interrupt Enable bit
	When IPEN = $0$ :
	1 = Enables all unmasked interrupts
	0 = Disables all interrupts
	When IPEN = 1:
	1 = Enables all high-priority interrupts
	0 = Disables all interrupts
bit 6	PEIE/GIEL: Peripheral Interrupt Enable bit
	When IPEN = $0$ :
	<ul> <li>1 = Enables all unmasked peripheral interrupts</li> <li>0 = Disables all peripheral interrupts</li> </ul>
	When IPEN = 1:
	1 = Enables all low-priority peripheral interrupts
	0 = Disables all low-priority peripheral interrupts
bit 5	TMR0IE: TMR0 Overflow Interrupt Enable bit
	1 = Enables the TMR0 overflow interrupt
	0 = Disables the TMR0 overflow interrupt
bit 4	INTOIE: INTO External Interrupt Enable bit
	1 = Enables the INT0 external interrupt
	0 = Disables the INT0 external interrupt
bit 3	RBIE: RB Port Change Interrupt Enable bit
	1 = Enables the RB port change interrupt
	0 = Disables the RB port change interrupt
bit 2	TMR0IF: TMR0 Overflow Interrupt Flag bit
	1 = TMR0 register has overflowed (must be cleared in software)
	0 = TMR0 register did not overflow
bit 1	INTOIF: INTO External Interrupt Flag bit
	<ul> <li>1 = The INT0 external interrupt occurred (must be cleared in software)</li> <li>0 = The INT0 external interrupt did not occur</li> </ul>
L:1 0	•
bit 0	<b>RBIF:</b> RB Port Change Interrupt Flag bit <sup>(1)</sup>
	<ul> <li>1 = At least one of the RB&lt;7:4&gt; pins changed state (must be cleared in software)</li> <li>0 = None of the RB&lt;7:4&gt; pins have changed state</li> </ul>
NI - 4 -	A. A minimum table and differential and the net this bit. Dearding DODTD and writing 4 Tay will and the prime stal

**Note 1:** A mismatch condition will continue to set this bit. Reading PORTB and waiting 1 TCY will end the mismatch condition and allow the bit to be cleared.

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
RBPU	INTEDG0	INTEDG1	INTEDG2	INTEDG3	TMR0IP	INT3IP	RBIP
bit 7							bit 0
Legend:	abla hit	\\/ = \\/ritabla	h it		opted bit rea	d oo 'O'	
R = Read		W = Writable		U = Unimplem			
-n = Value	alPOR	'1' = Bit is set		'0' = Bit is clea	areu	x = Bit is unkr	IOWII
bit 7	<b>RBPU</b> : PORT	B Pull-up Enal	ole bit				
		B pull-ups are					
	0 = PORTB p	oull-ups are ena	abled by individ	dual port latch v	alues		
bit 6		ternal Interrupt	0 Edge Select	t bit			
		on rising edge					
bit 5	-	on falling edge tternal Interrupt	1 Edgo Soloci	t bit			
DIL 5		on rising edge	I Luge Select				
		on falling edge					
bit 4	INTEDG2: Ex	ternal Interrupt	2 Edge Select	t bit			
		on rising edge					
	•	on falling edge					
bit 3		ternal Interrupt	3 Edge Select	t bit			
		on rising edge on falling edge					
bit 2	•	R0 Overflow Int	errupt Priority	bit			
	1 = High prio		. ,				
	0 = Low prior	•					
bit 1		External Interr	upt Priority bit				
	1 = High prio 0 = Low prior	•					
bit 0	•	rt Change Inter	runt Priority hit				
bit o	1 = High prio	-	rupt i nonty on				
	0 = Low prior						
Note:	Interrupt flag bits	are set when	an interrupt co	ndition occurs	regardless of	the state of its	corresponding
	enable bit or the g	global interrupt	enable bit. Use	er software sho	uld ensure the	appropriate int	
	are clear prior to	enabling an int	errupt. This fea	ature allows for	software pollir	ng.	

#### INTCON2: INTERRUPT CONTROL REGISTER 2 (ACCESS FF1h) **REGISTER 8-2:**

#### REGISTER 8-3: INTCON3: INTERRUPT CONTROL REGISTER 3 (ACCESS FF0h)

R/W-1	R/W-1	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
INT2IP	INT1IP	INT3IE	INT2IE	INT1IE	INT3IF	INT2IF	INT1IF
bit 7		·					bit (
Legend: R = Read	ablo bit	W = Writable	hit	U = Unimplen	contod bit roa	d ac '0'	
-n = Value		'1' = Bit is set		'0' = Bit is clea		x = Bit is unkr	NOW/D
					urcu		
bit 7	INT2IP: INT2	External Interr	upt Priority bit				
	1 = High pric	•					
	0 = Low prio	rity					
bit 6		External Interr	upt Priority bit				
	1 = High pric 0 = Low prio						
bit 5	•	External Interr	unt Enable bit				
		the INT3 exteri	•				
		the INT3 exter	•				
bit 4	INT2IE: INT2	External Interr	upt Enable bit				
		the INT2 extern					
1.11.0		the INT2 exter	•				
bit 3		External Interr	•				
		the INT1 extern the INT1 extern					
bit 2		External Interr					
				must be cleared	d in software)		
		3 external inter	•	cur			
bit 1		External Interr					
		2 external interi 2 external interi		must be cleared	d in software)		
bit 0		External Interr	•	Sui			
				must be cleared	d in software)		
		1 external interi					
			· · ·				
Note:	Interrupt flag bits enable bit or the						
	are clear prior to						

### 8.2 PIR Registers

The PIR registers contain the individual flag bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Request (Flag) registers (PIR1, PIR2, PIR3).

- Note 1: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the Global Interrupt Enable bit, GIE (INTCON<7>).
  - 2: User software should ensure the appropriate interrupt flag bits are cleared prior to enabling an interrupt and after servicing that interrupt.

#### REGISTER 8-4: PIR1: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 1 (ACCESS F9Eh)

R/W-0	R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0
PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	PMPIF: Parallel Master Port Read/Write Interrupt Flag bit <sup>(1)</sup>
	<ul> <li>1 = A read or a write operation has taken place (must be cleared in software)</li> <li>0 = No read or write has occurred</li> </ul>
bit 6	ADIF: A/D Converter Interrupt Flag bit
	<ul> <li>1 = An A/D conversion completed (must be cleared in software)</li> <li>0 = The A/D conversion is not complete</li> </ul>
bit 5	RC1IF: EUSART1 Receive Interrupt Flag bit
	<ul> <li>1 = The EUSART1 receive buffer, RCREG1, is full (cleared when RCREG1 is read)</li> <li>0 = The EUSART1 receive buffer is empty</li> </ul>
bit 4	TX1IF: EUSART1 Transmit Interrupt Flag bit
	<ul> <li>1 = The EUSART1 transmit buffer, TXREG1, is empty (cleared when TXREG1 is written)</li> <li>0 = The EUSART1 transmit buffer is full</li> </ul>
bit 3	SSP1IF: Master Synchronous Serial Port 1 Interrupt Flag bit
	<ul> <li>1 = The transmission/reception is complete (must be cleared in software)</li> <li>0 = Waiting to transmit/receive</li> </ul>
bit 2	CCP1IF: ECCP1 Interrupt Flag bit
	<u>Capture mode:</u> 1 = A TMR1/TMR3 register capture occurred (must be cleared in software) 0 = No TMR1/TMR3 register capture occurred
	Capture mode: 1 = A TMR1/TMR3 register capture occurred (must be cleared in software) 0 = No TMR1/TMR3 register capture occurred Compare mode: 1 = A TMR1/TMR3 register compare match occurred (must be cleared in software) 0 = No TMR1/TMR3 register compare match occurred PWM mode:
hit 1	Capture mode: 1 = A TMR1/TMR3 register capture occurred (must be cleared in software) 0 = No TMR1/TMR3 register capture occurred Compare mode: 1 = A TMR1/TMR3 register compare match occurred (must be cleared in software) 0 = No TMR1/TMR3 register compare match occurred PWM mode: Unused in this mode.
bit 1	Capture mode: 1 = A TMR1/TMR3 register capture occurred (must be cleared in software) 0 = No TMR1/TMR3 register capture occurred Compare mode: 1 = A TMR1/TMR3 register compare match occurred (must be cleared in software) 0 = No TMR1/TMR3 register compare match occurred PWM mode:
bit 1 bit 0	Capture mode:         1 = A TMR1/TMR3 register capture occurred (must be cleared in software)         0 = No TMR1/TMR3 register capture occurred         Compare mode:         1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)         0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)         0 = No TMR1/TMR3 register compare match occurred         PWM mode:         Unused in this mode.         TMR2IF: TMR2 to PR2 Match Interrupt Flag bit         1 = TMR2 to PR2 match occurred (must be cleared in software)
	Capture mode:         1 = A TMR1/TMR3 register capture occurred (must be cleared in software)         0 = No TMR1/TMR3 register capture occurred         Compare mode:         1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)         0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)         0 = No TMR1/TMR3 register compare match occurred         PWM mode:         Unused in this mode.         TMR2IF: TMR2 to PR2 Match Interrupt Flag bit         1 = TMR2 to PR2 match occurred (must be cleared in software)         0 = No TMR2 to PR2 match occurred

Note 1: These bits are unimplemented on 28-pin devices.

## REGISTER 8-5: PIR2: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 2 (ACCESS FA1h)

<ul> <li>t7</li> <li>t7</li> <li>egend:</li> <li>= Readable bit W = Writable bit U = Unimplemented bit, read as '0'</li> <li>t7</li> <li>OSCFIF: Oscillator Fail Interrupt Flag bit</li> <li>1 = Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)</li> <li>0 = Device clock operating</li> <li>t6</li> <li>CM2IF: Comparator 1 Interrupt Flag bit</li> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>t4</li> <li>USBIF: USB Interrupt Flag bit</li> <li>1 = USB has requested an interrupt (must be cleared in software)</li> <li>0 = No USB interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision Interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No USB interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred</li> <li>t1</li> <li>TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> </ul>	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
agend:         = Readable bit       W = Writable bit       U = Unimplemented bit, read as '0'         = Value at POR       '1' = Bit is set       '0' = Bit is cleared       x = Bit is unknown         t7       OSCFIF: Oscillator Fail Interrupt Flag bit       1 = Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)         0 = Device clock operating       1 = Comparator 2 Interrupt Flag bit       1 = Comparator input has changed (must be cleared in software)         0 = Comparator input has changed (must be cleared in software)       0 = Comparator 1 Interrupt Flag bit       1 = Comparator input has not changed         t5       CM1F: Comparator 1 Interrupt Flag bit       1 = Comparator input has not changed       1 = USB has requested an interrupt (must be cleared in software)         0 = Comparator input has not changed       1 = USB has requested an interrupt (must be cleared in software)       0 = No USB interrupt Flag bit         1 = USB has requested an interrupt flag bit (MSSP1 module)       1 = A bus collision occurred (must be cleared in software)       0 = No USB interrupt Flag bit (MSSP1 module)         1 = A bigh/low-voltage condition occurred (must be cleared in software)       0 = No bus collision occurred (must be cleared in software)         1 = A high/low-voltage condition occurred       1 = TMR3 register overflowed (must be cleared in software)       0 = An HLVD event has not occurred         1 = TMR3 register overflowed (must be cleared in software) <t< td=""><td>OSCFIF</td><td>CM2IF</td><td>CM1IF</td><td>USBIF</td><td>BCL1IF</td><td>HLVDIF</td><td>TMR3IF</td><td>CCP2IF</td></t<>	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF
= Readable bit       W = Writable bit       U = Unimplemented bit, read as '0'         = Value at POR       '1' = Bit is set       '0' = Bit is cleared       x = Bit is unknown         t7       OSCFIF: Oscillator Fail Interrupt Flag bit       1 = Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)         0 = Device clock operating       1 = Comparator 1 Interrupt Flag bit       1 = Comparator input has changed (must be cleared in software)         0 = Comparator input has changed (must be cleared in software)       0 = Comparator input has changed (must be cleared in software)         0 = Comparator input has changed (must be cleared in software)       0 = Comparator input has changed (must be cleared in software)         0 = Comparator input has changed (must be cleared in software)       0 = Comparator input has changed (must be cleared in software)         0 = Comparator input has not changed       1 = USB has requested an interrupt (must be cleared in software)         0 = No USB Interrupt Flag bit       1 = USB has requested an interrupt (must be cleared in software)         0 = No USB interrupt request       1 = A bus collision occurred         t3       BCL1IF: Bus Collision interrupt Flag bit (MSSP1 module)         1 = A bus collision occurred (must be cleared in software)       0 = An HLVD event has not occurred (must be cleared in software)         0 = An HLVD event has not occurred (must be cleared in software)       0 = TMR3 register overflowed (must be cleared in so	bit 7							bit 0
1' = Bit is set       0' = Bit is cleared       x = Bit is unknown         t7       OSCFIF: Oscillator Failed, clock input has changed to INTOSC (must be cleared in software)         0 = Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)         0 = Device clock operating         t6       CM2IF: Comparator 2 Interrupt Flag bit         1 = Comparator input has changed (must be cleared in software)         0 = Comparator input has not changed         t5       CM1IF: Comparator 1 Interrupt Flag bit         1 = Comparator input has not changed         t4       USBIF: USB Interrupt Flag bit         1 = USB has requested an interrupt (must be cleared in software)         0 = No USB interrupt request         t3       BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)         1 = A bus collision occurred (must be cleared in software)         0 = No bus collision occurred (must be cleared in software)         0 = No bus collision occurred (must be cleared in software)         0 = A high/low-voltage condition occurred (must be cleared in software)         0 = A high/low-voltage condition occurred (must be cleared in software)         0 = TMR3 register overflowed (must be cleared in software)         0 = TMR3 register overflowed (must be cleared in software)         0 = TMR3 register capture occurred (must be cleared in software)         0 = TMR3 regi	Legend:							
<ul> <li>t7 OSCFIF: Oscillator Fail Interrupt Flag bit <ol> <li>= Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)</li> <li>= Device clock operating</li> </ol> </li> <li>t6 CM2IF: Comparator 2 Interrupt Flag bit <ol> <li>= Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> </ol> </li> <li>t5 CM1IF: Comparator 1 Interrupt Flag bit <ol> <li>= Comparator input has not changed</li> <li>t0 = Comparator input has not changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> </ol> </li> <li>t3 CM1F: USB Interrupt Flag bit <ol> <li>= USB has requested an interrupt (must be cleared in software)</li> <li>= No USB interrupt request</li> </ol> </li> <li>t3 BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module) <ol> <li>= A bus collision occurred (must be cleared in software)</li> <li>= No bus collision occurred (must be cleared in software)</li> <li>= A bus collision occurred (must be cleared in software)</li> <li>= A high/low-voltage condition occurred (must be cleared in software)</li> <li>= TMR3 register overflowed (must be cleared in software)</li> <li>= TMR3 register did not overflow</li> <li>t0 CCP2IF: ECCP2 Interrupt Flag bit</li> <li>I = TMR3 register capture occurred (must be cleared in software)</li> <li>= No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>= No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>= No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> </ol> </li> </ul>	R = Readab	le bit	W = Writable	bit	U = Unimpler	nented bit, read	d as '0'	
<ul> <li>1 = Device oscillator failed, clock input has changed to INTOSC (must be cleared in software)</li> <li>0 = Device clock operating</li> <li>CM2IF: Comparator 2 Interrupt Flag bit</li> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>CM1IF: Comparator 1 Interrupt Flag bit</li> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>Comparator input has not changed</li> <li>USBIF: USB Interrupt Flag bit</li> <li>1 = USB has requested an interrupt (must be cleared in software)</li> <li>0 = No USB Interrupt request</li> <li>BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred to cleared in software)</li> <li>0 = TMR3 register overflow unterrupt Flag bit</li> <li>1 = TMR3 register overflow unterrupt Flag bit</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = N TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = N TMR1/TMR3 register compare match occurred (must be cleared in software)</li> </ul>	-n = Value a	t POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown
<ul> <li>Device clock operating</li> <li>CM2IF: Comparator 2 Interrupt Flag bit</li> <li>Comparator input has changed (must be cleared in software)</li> <li>Comparator input has not changed</li> <li>CM1IF: Comparator 1 Interrupt Flag bit</li> <li>Comparator input has changed (must be cleared in software)</li> <li>Comparator input has not changed</li> <li>CM1IF: Comparator 1 Interrupt Flag bit</li> <li>Comparator input has not changed</li> <li>USB Interrupt Flag bit</li> <li>USB Interrupt Flag bit</li> <li>USB has requested an interrupt (must be cleared in software)</li> <li>No USB interrupt request</li> <li>BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)</li> <li>A bus collision occurred (must be cleared in software)</li> <li>No bus collision occurred (must be cleared in software)</li> <li>No bus collision occurred (must be cleared in software)</li> <li>No bus collision occurred (must be cleared in software)</li> <li>A hus collision occurred (must be cleared in software)</li> <li>A high/low-voltage Detect (HLVD) Interrupt Flag bit</li> <li>A high/low-voltage condition occurred (must be cleared in software)</li> <li>An HLVD event has not occurred</li> <li>TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>TMR3 register overflowed (must be cleared in software)</li> <li>TMR3 register overflowed (must be cleared in software)</li> <li>TMR3 register overflowed (must be cleared in software)</li> <li>TMR3 register capture occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register capture occurred</li> <li>A TMR1/TMR3 register compare match occurred</li> <li>No TMR1/TMR3 register compare match occurred</li> <li>No TMR1/TMR3 register compare match occurred</li> </ul>	bit 7	OSCFIF: Os	cillator Fail Inter	rupt Flag bit				
<ul> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>t5 CM1IF: Comparator 1 Interrupt Flag bit</li> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>t4 USBIF: USB Interrupt Flag bit</li> <li>1 = USB has requested an interrupt (must be cleared in software)</li> <li>0 = No USB interrupt request</li> <li>t3 BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register otherway Flag bit</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred</li> <li>Compare mode:</li> <li>1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred</li> <li>0 = No TMR1/TMR3 register compare match occurred</li> </ul>				clock input ha	s changed to IN	ITOSC (must b	e cleared in so	ftware)
<ul> <li>0 = Comparator input has not changed</li> <li>t 5 CM1IF: Comparator 1 Interrupt Flag bit         <ol> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> </ol> </li> <li>t 4 USBIF: USB Interrupt Flag bit         <ol> <li>1 = USB has requested an interrupt (must be cleared in software)</li> <li>0 = No USB interrupt request</li> </ol> </li> <li>t 3 BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)         <ol> <li>a A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (thust be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (thust be cleared in software)</li> <li>0 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = A high/low-voltage condition occurred</li> </ol> </li> <li>t 1 TMR3IF: TMR3 Overflow Interrupt Flag bit         <ol> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> </ol> </li> <li>t 0 CCP2IF: ECCP2 Interrupt Flag bit         <ol> <li>Capture mode:</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared</li></ol></li></ul>	bit 6	CM2IF: Com	nparator 2 Interr	upt Flag bit				
<ul> <li>t5 CM1IF: Comparator 1 Interrupt Flag bit</li> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>t4 USBIF: USB Interrupt Flag bit</li> <li>1 = USB has requested an interrupt (must be cleared in software)</li> <li>0 = No USB interrupt request</li> <li>t3 BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (thust be cleared in software)</li> <li>0 = No bus collision occurred (thust be cleared in software)</li> <li>0 = No bus collision occurred (thust be cleared in software)</li> <li>0 = No bus collision occurred (thust be cleared in software)</li> <li>0 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVDIF: High/low-Voltage condition occurred</li> <li>t1 TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register capture occurred (must be cleared in software)</li> <li>0 = TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> </ul>					be cleared in so	oftware)		
<ul> <li>1 = Comparator input has changed (must be cleared in software)</li> <li>0 = Comparator input has not changed</li> <li>t USBIF: USB Interrupt Flag bit</li> <li>1 = USB has requested an interrupt (must be cleared in software)</li> <li>0 = No USB interrupt request</li> <li>t BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)</li> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred</li> <li>t HLVDIF: High/Low-Voltage Detect (HLVD) Interrupt Flag bit</li> <li>1 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred</li> <li>t 1 TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> <li>t Capture mode:</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> </ul>	bit 5	•	•	•				
<ul> <li>USBIF: USB Interrupt Flag bit</li> <li>USB has requested an interrupt (must be cleared in software)</li> <li>No USB interrupt request</li> <li>BCL1IF: Bus Collision Interrupt Flag bit (MSSP1 module)</li> <li>A bus collision occurred (must be cleared in software)</li> <li>No bus collision occurred</li> <li>HLVDIF: High/Low-Voltage Detect (HLVD) Interrupt Flag bit</li> <li>A high/low-voltage condition occurred (must be cleared in software)</li> <li>An HLVD event has not occurred</li> <li>TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>TMR3 register overflowed (must be cleared in software)</li> <li>TMR3 register did not overflow</li> <li>CCP2IF: ECCP2 Interrupt Flag bit</li> <li>Capture mode:</li> <li>A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred</li> <li>PWM mode:</li> </ul>		1 = Compar	ator input has c	hanged (must	be cleared in so	oftware)		
<ul> <li>0 = No USB interrupt request</li> <li>t 3</li> <li><b>BCL1IF:</b> Bus Collision Interrupt Flag bit (MSSP1 module)         <ol> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred</li> </ol> </li> <li>t 2</li> <li><b>HLVDIF:</b> High/Low-Voltage Detect (HLVD) Interrupt Flag bit         <ol> <li>a A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred</li> </ol> </li> <li>t 1</li> <li><b>TMR3IF:</b> TMR3 Overflow Interrupt Flag bit         <ol> <li>a TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> </ol> </li> <li>t 0</li> <li><b>CCP2IF:</b> ECCP2 Interrupt Flag bit         <ol> <li>a TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred</li> <li>PWM mode:</li> </ol> </li> </ul>	bit 4	•	•	•				
<ul> <li>1 = A bus collision occurred (must be cleared in software)</li> <li>0 = No bus collision occurred</li> <li>t 2 HLVDIF: High/Low-Voltage Detect (HLVD) Interrupt Flag bit</li> <li>1 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred</li> <li>t 1 TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> <li>t 0 CCP2IF: ECCP2 Interrupt Flag bit</li> <li>Capture mode:</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred</li> <li>PWM mode:</li> </ul>					t be cleared in s	software)		
<ul> <li>0 = No bus collision occurred</li> <li>t 2 HLVDIF: High/Low-Voltage Detect (HLVD) Interrupt Flag bit</li> <li>1 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred</li> <li>t 1 TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> <li>t 0 CCP2IF: ECCP2 Interrupt Flag bit</li> <li>Capture mode:</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred</li> <li>PWM mode:</li> </ul>	bit 3	BCL1IF: Bus	s Collision Interr	upt Flag bit (N	ISSP1 module)			
<ul> <li>1 = A high/low-voltage condition occurred (must be cleared in software)</li> <li>0 = An HLVD event has not occurred</li> <li>1 TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> <li>t 0 CCP2IF: ECCP2 Interrupt Flag bit</li> <li>Capture mode:</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred</li> <li>Dompare mode:</li> <li>1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> </ul>				•	ared in software	)		
<ul> <li>0 = An HLVD event has not occurred</li> <li>TMR3IF: TMR3 Overflow Interrupt Flag bit</li> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> <li>CCP2IF: ECCP2 Interrupt Flag bit</li> <li>Capture mode:</li> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred</li> <li>Compare mode:</li> <li>1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> </ul>	bit 2	HLVDIF: Hig	h/Low-Voltage I	Detect (HLVD)	Interrupt Flag	oit		
<ul> <li>1 = TMR3 register overflowed (must be cleared in software)</li> <li>0 = TMR3 register did not overflow</li> <li>t 0 CCP2IF: ECCP2 Interrupt Flag bit Capture mode:         <ol> <li>A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register capture occurred</li> </ol> </li> <li>Compare mode:         <ol> <li>A TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>No TMR1/TMR3 register compare match occurred</li> </ol> </li> </ul>		•	•		(must be cleare	ed in software)		
<ul> <li>0 = TMR3 register did not overflow</li> <li>t 0 CCP2IF: ECCP2 Interrupt Flag bit <u>Capture mode:</u>         1 = A TMR1/TMR3 register capture occurred (must be cleared in software)         0 = No TMR1/TMR3 register capture occurred     <u>Compare mode:</u>         1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)         0 = No TMR1/TMR3 register compare match occurred     <u>PWM mode:</u> </li> </ul>	bit 1	TMR3IF: TM	IR3 Overflow Int	errupt Flag bit	:			
<u>Capture mode:</u> 1 = A TMR1/TMR3 register capture occurred (must be cleared in software) 0 = No TMR1/TMR3 register capture occurred <u>Compare mode:</u> 1 = A TMR1/TMR3 register compare match occurred (must be cleared in software) 0 = No TMR1/TMR3 register compare match occurred <u>PWM mode:</u>					eared in softwa	re)		
<ul> <li>1 = A TMR1/TMR3 register capture occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register capture occurred</li> <li><u>Compare mode:</u></li> <li>1 = A TMR1/TMR3 register compare match occurred (must be cleared in software)</li> <li>0 = No TMR1/TMR3 register compare match occurred</li> <li><u>PWM mode:</u></li> </ul>	bit 0	CCP2IF: EC	CP2 Interrupt F	lag bit				
<u>Compare mode:</u> 1 = A TMR1/TMR3 register compare match occurred (must be cleared in software) 0 = No TMR1/TMR3 register compare match occurred <u>PWM mode:</u>		1 = A TMR1	/TMR3 register			eared in softwa	re)	
PWM mode:		<u>Compare mo</u> 1 = A TMR1	<u>ode:</u> I/TMR3 register	compare mate	ch occurred (mu	ist be cleared i	n software)	
			_	·				

# PIC18F46J50 FAMILY

R/W-0	R/W-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF
bit 7							bit 0
Legend:							
R = Readab	le bit	W = Writable	bit	U = Unimplen	nented bit, read	d as '0'	
-n = Value a	t POR	'1' = Bit is set		'0' = Bit is cle		x = Bit is unkn	own
bit 7	SSD2IE: Mag	ter Synchronou	is Serial Port (	2 Interrupt Flag	bit		
		-		e (must be clea		<del>2</del> )	
		o transmit/rece				-)	
bit 6	BCL2IF: Bus	Collision Interr	upt Flag bit (N	ISSP2 module)			
				red in software	)		
		collision occurre					
bit 5		ART2 Receive I					
		SART2 receive		62, is full (cleare	ed when RCRE	G2 is read)	
bit 4		ART2 Transmit					
			1 0		eared when TX	REG2 is writter	1)
		SART2 transmit					')
bit 3	TMR4IF: TM	R4 to PR4 Mate	ch Interrupt Fla	ag bit			
	1 = TMR4 to	PR4 match oc	curred (must b	e cleared in sof	ftware)		
	0 = No TMR	4 to PR4 match	occurred				
bit 2		•		Interrupt Flag b			
			· ·	cleared in soft	ware)		
L:1 4		vent has not oc		l- :4			
bit 1		mer3 Gate Eve	•	be cleared in s	offwara		
		r3 gate event con	• •	be cleared in s	ollwale)		
bit 0		CC Interrupt Fla	•				
		•	•	ared in software	)		
		interrupt occu	•		,		

#### REGISTER 8-6: PIR3: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 3 (ACCESS FA4h)

# 8.3 PIE Registers

The PIE registers contain the individual enable bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Enable registers (PIE1, PIE2, PIE3). When IPEN = 0, the PEIE bit must be set to enable any of these peripheral interrupts.

#### REGISTER 8-7: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1 (ACCESS F9Dh)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	<b>PMPIE:</b> Parallel Master Port Read/Write Interrupt Enable bit <sup>(1)</sup> 1 = Enables the PMP read/write interrupt 0 = Disables the PMP read/write interrupt
bit 6	ADIE: A/D Converter Interrupt Enable bit 1 = Enables the A/D interrupt 0 = Disables the A/D interrupt
bit 5	<b>RC1IE:</b> EUSART1 Receive Interrupt Enable bit 1 = Enables the EUSART1 receive interrupt 0 = Disables the EUSART1 receive interrupt
bit 4	<b>TX1IE:</b> EUSART1 Transmit Interrupt Enable bit 1 = Enables the EUSART1 transmit interrupt 0 = Disables the EUSART1 transmit interrupt
bit 3	<b>SSP1IE:</b> Master Synchronous Serial Port 1 Interrupt Enable bit 1 = Enables the MSSP1 interrupt 0 = Disables the MSSP1 interrupt
bit 2	<b>CCP1IE:</b> ECCP1 Interrupt Enable bit 1 = Enables the ECCP1 interrupt 0 = Disables the ECCP1 interrupt
bit 1	<b>TMR2IE:</b> TMR2 to PR2 Match Interrupt Enable bit 1 = Enables the TMR2 to PR2 match interrupt 0 = Disables the TMR2 to PR2 match interrupt
bit 0	<b>TMR1IE:</b> TMR1 Overflow Interrupt Enable bit 1 = Enables the TMR1 overflow interrupt 0 = Disables the TMR1 overflow interrupt
Note 1:	These bits are unimplemented on 28-pin devices.

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE
bit 7							bit 0
Levendi							
Legend: R = Readabl	≏ hit	W = Writable	hit	I I = I Inimplen	nented bit, read	d as 'O'	
-n = Value at		'1' = Bit is set		'0' = Bit is cle		x = Bit is unkr	างพท
bit 7	OSCFIE: Osc	illator Fail Inter	rupt Enable b	it			
	1 = Enabled						
	0 = Disabled						
bit 6	•	parator 2 Interro	upt Enable bit				
	1 = Enabled 0 = Disabled						
bit 5		parator 1 Interro	int Enable bit				
bit 5	1 = Enabled						
	0 = Disabled						
bit 4	USBIE: USB	Interrupt Enabl	e bit				
	1 = Enabled						
	0 = Disabled						
bit 3		Collision Interr	upt Enable bit	(MSSP1 modu	le)		
	1 = Enabled 0 = Disabled						
bit 2		n/Low-Voltage I	Detect Interrur	ot Enable bit			
	1 = Enabled	0	·				
	0 = Disabled						
bit 1		R3 Overflow Int	errupt Enable	bit			
	1 = Enabled 0 = Disabled						
hit O			nahla hit				
bit 0	1 = Enabled	CP2 Interrupt E					
	0 = Disabled						

# REGISTER 8-8: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2 (ACCESS FA0h)

#### REGISTER 8-9: PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3 (ACCESS FA3h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE
bit 7					•		bit 0
Legend:							
R = Readab	le bit	W = Writable I	pit	U = Unimplem	nented bit, read	1 as '0'	
-n = Value a	t POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkn	own
bit 7	SSP2IE: Ma	aster Synchronou	s Serial Port 2	2 Interrupt Enab	le bit		
	1 = Enable 0 = Disable	d					
bit 6	BCL2IE: Bu	s Collision Interr	upt Enable bit	(MSSP2 modul	le)		
	1 = Enableo 0 = Disable						
bit 5	RC2IE: EUS	SART2 Receive I	nterrupt Enab	le bit			
	1 = Enableo 0 = Disable						
bit 4	TX2IE: EUS	SART2 Transmit I	nterrupt Enab	le bit			
	1 = Enableo 0 = Disable						
bit 3	TMR4IE: TN	/R4 to PR4 Matc	h Interrupt Er	able bit			
	1 = Enableo 0 = Disable						
bit 2	CTMUIE: CI	harge Time Meas	urement Unit	(CTMU) Interru	pt Enable bit		
	1 = Enableo 0 = Disable						
bit 1	TMR3GIE: 1	Timer3 Gate Inter	rupt Enable b	it			
	1 = Enableo 0 = Disable						
bit 0	RTCCIE: RT	CC Interrupt En	able bit				
	1 = Enabled						
	0 = Disable	d					

### 8.4 IPR Registers

The IPR registers contain the individual priority bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Priority registers (IPR1, IPR2, IPR3). Using the priority bits requires that the Interrupt Priority Enable (IPEN) bit be set.

#### REGISTER 8-10: IPR1: PERIPHERAL INTERRUPT PRIORITY REGISTER 1 (ACCESS F9Fh)

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	
PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	
bit 7							bit	
Legend:								
R = Readabl	e bit	W = Writable	bit	U = Unimplen	nented bit, read	l as '0'		
-n = Value at	POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkr	iown	
bit 7	<b>PMPIP:</b> Para	allel Master Port	Read/Write In	terrupt Priority	bit <sup>(1)</sup>			
	1 = High price							
	0 = Low pric	•						
bit 6	ADIP: A/D C	onverter Interru	pt Priority bit					
	1 = High prio	ority						
	0 = Low pric	ority						
bit 5	RC1IP: EUS	ART1 Receive I	nterrupt Priori	ty bit				
	1 = High price							
	0 = Low price	-						
bit 4	TX1IP: EUS	ART1 Transmit	Interrupt Priori	ty bit				
	1 = High prio	,						
	0 = Low pric	•						
bit 3	SSP1IP: Master Synchronous Serial Port Interrupt Priority bit (MSSP1 module)							
	1 = High price							
	0 = Low pric	•						
bit 2		CP1 Interrupt P	riority bit					
	1 = High priority							
	0 = Low price	•						
bit 1		R2IP: TMR2 to PR2 Match Interrupt Priority bit						
	1 = High pric 0 = Low pric							
bit 0	-	R1 Overflow Int	orrupt Priority	hit				
	1 = High price		enupt Friolity	DIL				
	1 = High phic0 = Low pric	JIILY						

Note 1: These bits are unimplemented on 28-pin devices.

						•	,	
R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	
OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	
bit 7							bit	
Legend:								
R = Readabl	e bit	W = Writable	bit	U = Unimplen	nented bit, rea	d as '0'		
-n = Value at	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown	
bit 7		cillator Fail Inte	rrupt Priority b	it				
	1 = High pric 0 = Low prio							
bit 6	•	parator 2 Interr	unt Priority hit					
	1 = High pric	•	aper noncy on					
	0 = Low prio							
bit 5	C12IP: Comp	parator 1 Interru	pt Priority bit					
	1 = High pric							
	0 = Low prio	•						
bit 4		Interrupt Priori	ty bit					
	1 = High price	•						
bit 3	0 = Low prio	-	unt Driarity hit					
DIL 3	1 = High pric	Collision Interr	upt Friority bit		ie)			
	0 = Low prio	•						
bit 2	•	h/Low-Voltage	Detect Interrup	ot Priority bit				
	1 = High pric	ority						
	0 = Low prio	ority						
bit 1	TMR3IP: TMR3 Overflow Interrupt Priority bit							
	1 = High price							
	0 = Low prio	-						
bit 0		CP2 Interrupt P	riority bit					
	1 = High pric 0 = Low prio	•						
		inty						

# REGISTER 8-11: IPR2: PERIPHERAL INTERRUPT PRIORITY REGISTER 2 (ACCESS FA2h)

# PIC18F46J50 FAMILY

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1		
SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP		
bit 7		·					bit C		
Legend:									
R = Readabl	e bit	W = Writable	bit	•	nented bit, rea	d as '0'			
-n = Value at	t POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkn	own		
L:1 7		- t 0 t							
bit 7		ster Synchronou	is Serial Port	2 Interrupt Prior	ity dit				
	1 = High prid0 = Low prid	•							
bit 6		s Collision Interr	upt Prioritv bit	: (MSSP2 modu	le)				
	1 = High prie		. ,	,	,				
	0 = Low pric	prity							
bit 5	RC2IP: EUS	ART2 Receive I	nterrupt Priori	ty bit					
	1 = High price	•							
	0 = Low pric	•							
bit 4		ART2 Transmit I	Interrupt Prior	ity bit					
	1 = High pric 0 = Low pric								
bit 3		IR4 to PR4 Inter	runt Priority h	it					
bit o	1 = High pri		rupt i nonty b	it.					
	0 = Low priority								
bit 2	CTMUIP: Ch	arge Time Meas	surement Unit	(CTMU) Interru	upt Priority bit				
	1 = High priority								
	0 = Low pric	•							
bit 1		ïmer3 Gate Inte	rrupt Priority b	bit					
	1 = High price								
h:4 0	0 = Low pric	-							
bit 0		CC Interrupt Pri	onty Dit						
	1 = High prid 0 = Low prid	•							
	0 = Low price	лцу							

# REGISTER 8-12: IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3 (ACCESS FA5h)

# 8.5 RCON Register

The RCON register contains bits used to determine the cause of the last Reset or wake-up from Idle or Sleep mode. RCON also contains the bit that enables interrupt priorities (IPEN).

#### REGISTER 8-13: RCON: RESET CONTROL REGISTER (ACCESS FD0h)

R/W-0	U-0	R/W-1	R/W-1	R-1	R-1	R/W-0	R/W-0
IPEN	—	CM	RI	TO	PD	POR	BOR
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	<ul> <li>IPEN: Interrupt Priority Enable bit</li> <li>1 = Enable priority levels on interrupts</li> <li>0 = Disable priority levels on interrupts (PIC16CXXX Compatibility mode)</li> </ul>
bit 6	Unimplemented: Read as '0'
bit 5	CM: Configuration Mismatch Flag bit
	For details on bit operation, see Register 4-1.
bit 4	RI: RESET Instruction Flag bit
	For details on bit operation, see Register 4-1.
bit 3	TO: Watchdog Timer Time-out Flag bit
	For details on bit operation, see Register 4-1.
bit 2	PD: Power-Down Detection Flag bit
	For details on bit operation, see Register 4-1.
bit 1	POR: Power-on Reset Status bit
	For details on bit operation, see Register 4-1.
bit 0	BOR: Brown-out Reset Status bit
	For details on bit operation, see Register 4-1.

# 8.6 INTx Pin Interrupts

External interrupts on the INT0, INT1, INT2 and INT3 pins are edge-triggered. If the corresponding INTEDGx bit in the INTCON2 register is set (= 1), the interrupt is triggered by a rising edge; if the bit is clear, the trigger is on the falling edge. When a valid edge appears on the INTx pin, the corresponding flag bit and INTxIF are set. This interrupt can be disabled by clearing the corresponding enable bit, INTxIE. Flag bit, INTxIF, must be cleared in software in the Interrupt Service Routine before re-enabling the interrupt.

All external interrupts (INT0, INT1, INT2 and INT3) can wake-up the processor from the power-managed modes if bit, INTxIE, was set prior to going into the power-managed modes. If the Global Interrupt Enable bit, GIE, is set, the processor will branch to the interrupt vector following wake-up.

Interrupt priority for INT1, INT2 and INT3 is determined by the value contained in the Interrupt Priority bits, INT1IP (INTCON3<6>), INT2IP (INTCON3<7>) and INT3IP (INTCON2<1>). There is no priority bit associated with INT0. It is always a high-priority interrupt source.

# 8.7 TMR0 Interrupt

In 8-bit mode (which is the default), an overflow in the TMR0 register (FFh  $\rightarrow$  00h) will set flag bit, TMR0IF. In 16-bit mode, an overflow in the TMR0H:TMR0L register

pair (FFFFh  $\rightarrow$  0000h) will set TMR0IF. The interrupt can be enabled/disabled by setting/clearing enable bit, TMR0IE (INTCON<5>). Interrupt priority for Timer0 is determined by the value contained in the interrupt priority bit, TMR0IP (INTCON2<2>). See **Section 11.0 "Timer0 Module"** for further details on the Timer0 module.

# 8.8 PORTB Interrupt-on-Change

An input change on PORTB<7:4> sets flag bit, RBIF (INTCON<0>). The interrupt can be enabled/disabled by setting/clearing enable bit, RBIE (INTCON<3>). Interrupt priority for PORTB interrupt-on-change is determined by the value contained in the interrupt priority bit, RBIP (INTCON2<0>).

# 8.9 Context Saving During Interrupts

During interrupts, the return PC address is saved on the stack. Additionally, the WREG, STATUS and BSR registers are saved on the Fast Return Stack. If a fast return from interrupt is not used (see **Section 5.3 "Data Memory Organization"**), the user may need to save the WREG, STATUS and BSR registers on entry to the Interrupt Service Routine. Depending on the user's application, other registers may also need to be saved. Example 8-1 saves and restores the WREG, STATUS and BSR registers during an Interrupt Service Routine.

EXAMPLE 8-1: SAVING STATUS, WREG AND BSR REGISTERS IN RAM

MOVWF	W_TEMP	; W_TEMP is in virtual bank
MOVFF	STATUS, STATUS_TEMP	; STATUS_TEMP located anywhere
MOVFF	BSR, BSR_TEMP	; BSR_TMEP located anywhere
; ; USER ;	ISR CODE	
MOVFF	BSR_TEMP, BSR	; Restore BSR
MOVF	W_TEMP, W	; Restore WREG
MOVFF	STATUS_TEMP, STATUS	; Restore STATUS

# 9.0 I/O PORTS

Depending on the device selected and features enabled, there are up to five ports available. Some pins of the I/O ports are multiplexed with an alternate function from the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.


Each port has three registers for its operation. These registers are:

- TRIS register (Data Direction register)
- PORT register (reads the levels on the pins of the device)
- · LAT register (Data Latch)

The Data Latch (LAT register) is useful for read-modifywrite operations on the value that the I/O pins are driving.

Figure 9-1 displays a simplified model of a generic I/O port, without the interfaces to other peripherals.

FIGURE 9-1: GENERIC I/O PORT



# 9.1 I/O Port Pin Capabilities

When developing an application, the capabilities of the port pins must be considered. Outputs on some pins have higher output drive strength than others. Similarly, some pins can tolerate higher than VDD input levels.

### 9.1.1 PIN OUTPUT DRIVE

The output pin drive strengths vary for groups of pins intended to meet the needs for a variety of applications. PORTB and PORTC are designed to drive higher loads, such as LEDs. All other ports are designed for small loads, typically indication only. Table 9-1 summarizes the output capabilities. Refer to **Section 29.0** "**Electrical Characteristics**" for more details.

TABLE 9-1: OUTPUT DRIVE LEVELS

Port	Drive	Description		
PORTA				
PORTD	Minimum	Intended for indication.		
PORTE				
PORTB	High	Suitable for direct LED drive		
PORTC	High	levels.		

# 9.1.2 INPUT PINS AND VOLTAGE CONSIDERATIONS

The voltage tolerance of pins used as device inputs is dependent on the pin's input function. Pins that are used as digital only inputs are able to handle DC voltages up to 5.5V; a level typical for digital logic circuits. In contrast, pins that also have analog input functions of any kind can only tolerate voltages up to VDD. Voltage excursions beyond VDD on these pins should be avoided. Table 9-2 summarizes the input capabilities. Refer to **Section 29.0 "Electrical Characteristics"** for more details.


TABLE 9-2: INPUT VOLTAGE LEVELS

Port or Pin	Tolerated Input	Description		
PORTA<7:0>				
PORTB<3:0>	Voo	Only VDD input levels		
PORTC<2:0>	VDD	tolerated.		
PORTE<2:0>				
PORTB<7:4>		Tolerates input levels		
PORTC<7:6>	5.5V	above VDD, useful for		
PORTD<7:0>		most standard logic.		
PORTC<5:4>	(USB)	Designed for USB specifications.		

### 9.1.3 INTERFACING TO A 5V SYSTEM

Though the VDDMAX of the PIC18F46J50 Family is 3.6V, these devices are still capable of interfacing with 5V systems, even if the VIH of the target system is above 3.6V. This is accomplished by adding a pull-up resistor to the port pin (Figure 9-2), clearing the LAT bit for that pin and manipulating the corresponding TRIS bit (Figure 9-1) to either allow the line to be pulled high or to drive the pin low. Only port pins that are tolerant of voltages up to 5.5V can be used for this type of interface (refer to Section 9.1.2 "Input Pins and Voltage Considerations").

FIGURE 9-2: +5V SYSTEM HARDWARE INTERFACE



#### EXAMPLE 9-1: COMMUNICATING WITH THE +5V SYSTEM


BCF LATD,	7	; set up LAT register so ; changing TRIS bit will ; drive line low
		; send a 0 to the 5V system ; send a 1 to the 5V system

#### 9.1.4 OPEN-DRAIN OUTPUTS

The output pins for several peripherals are also equipped with a configurable open-drain output option. This allows the peripherals to communicate with external digital logic operating at a higher voltage level, without the use of level translators. The open-drain option is implemented on port pins specifically associated with the data and clock outputs of the EUSARTs, the MSSP modules (in SPI mode) and the ECCP modules. It is selectively enabled by setting the open-drain control bit for the corresponding module in the ODCON registers (Register 9-1, Register 9-2 and Register 9-3). Their configuration is discussed in more detail with the individual port where these peripherals are multiplexed. Output functions that are routed through the PPS module may also use the open-drain option. The open-drain functionality will follow the I/O pin assignment in the PPS module.

When the open-drain option is required, the output pin must also be tied through an external pull-up resistor provided by the user to a higher voltage level, up to 5.5V (Figure 9-3). When a digital logic high signal is output, it is pulled up to the higher voltage level.

FIGURE 9-3: USING THE OPEN-DRAIN OUTPUT (USART SHOWN AS EXAMPLE)



## 9.1.5 TTL INPUT BUFFER OPTION

Many of the digital I/O ports use Schmitt Trigger (ST) input buffers. While this form of buffering works well with many types of input, some applications may require TTL level signals to interface with external logic devices. This is particularly true for the Parallel Master Port (PMP), which is likely to be interfaced to TTL level logic or memory devices.

The inputs for the PMP can be optionally configured for TTL buffers with the PMPTTL bit in the PADCFG1 register (Register 9-4). Setting this bit configures all data and control input pins for the PMP to use TTL buffers. By default, these PMP inputs use the port's ST buffers.

# PIC18F46J50 FAMILY

### REGISTER 9-1: ODCON1: PERIPHERAL OPEN-DRAIN CONTROL REGISTER 1 (BANKED F42h)

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0
—	—	_	_	—	—	ECCP2OD	ECCP10D
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-2	Unimplemented: Read as '0'
bit 1	ECCP2OD: ECCP2 Open-Drain Output Enable bit
	<ol> <li>1 = Open-drain capability enabled</li> <li>0 = Open-drain capability disabled</li> </ol>
bit 0	ECCP10D: ECCP1 Open-Drain Output Enable bit
	<ol> <li>1 = Open-drain capability enabled</li> <li>0 = Open-drain capability disabled</li> </ol>

#### REGISTER 9-2: ODCON2: PERIPHERAL OPEN-DRAIN CONTROL REGISTER 2 (BANKED F41h)

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0
—	—	_	_	—	—	U2OD	U10D
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-2	Unimplemented: Read as '0'
bit 1	U2OD: USART2 Open-Drain Output Enable bit
	<ul><li>1 = Open-drain capability enabled</li><li>0 = Open-drain capability disabled</li></ul>
bit 0	U10D: USART1 Open-Drain Output Enable bit
	<ul><li>1 = Open-drain capability enabled</li><li>0 = Open-drain capability disabled</li></ul>

# PIC18F46J50 FAMILY

#### REGISTER 9-3: ODCON3: PERIPHERAL OPEN-DRAIN CONTROL REGISTER 3 (BANKED F40h)

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0
_	_		_	_		SPI2OD	SPI10D
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	1 as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-2	Unimplemented: Read as '0'
bit 1	SPI2OD: SPI2 Open-Drain Output Enable bit
	<ol> <li>1 = Open-drain capability enabled</li> <li>0 = Open-drain capability disabled</li> </ol>
bit 0	SPI10D: SPI1 Open-Drain Output Enable bit
	<ul><li>1 = Open-drain capability enabled</li><li>0 = Open-drain capability disabled</li></ul>

#### REGISTER 9-4: PADCFG1: PAD CONFIGURATION CONTROL REGISTER 1 (BANKED F3Ch)

U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
—	—	—	—	—	RTSECSEL1 <sup>(1)</sup>	RTSECSEL0 <sup>(1)</sup>	PMPTTL
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-3	Unimplemented: Read as '0'
---------	----------------------------

bit 2-1	RTSECSEL<1:0>: RTCC Seconds Clock Output Select bits <sup>(1)</sup>

- 11 = Reserved; do not use
  - 10 = RTCC source clock is selected for the RTCC pin (can be INTRC, T1OSC or T1CKI depending upon the RTCOSC (CONFIG3L<1>) and T1OSCEN (T1CON<3>) bit settings)
  - 01 = RTCC seconds clock is selected for the RTCC pin
  - 00 = RTCC alarm pulse is selected for the RTCC pin

bit 0 PMPTTL: PMP Module TTL Input Buffer Select bit

- 1 = PMP module uses TTL input buffers
- 0 = PMP module uses Schmitt Trigger input buffers

Note 1: To enable the actual RTCC output, the RTCOE (RTCCFG<2>) bit needs to be set.

#### 9.2 PORTA, TRISA and LATA Registers

PORTA is a 7-bit wide, bidirectional port. It may function as a 5-bit port, depending on the oscillator mode selected. Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., put the contents of the output latch on the selected pin).

Reading the PORTA register reads the status of the pins, whereas writing to it, will write to the port latch.

The Data Latch (LATA) register is also memory mapped. Read-modify-write operations on the LATA register read and write the latched output value for PORTA.

The other PORTA pins are multiplexed with analog inputs, the analog VREF+ and VREF- inputs and the comparator voltage reference output. The operation of pins, RA<3:0> and RA5, as A/D converter inputs is selected by clearing or setting the control bits in the ADCON1 register (A/D Control Register 1).

Pins, RA0 and RA3, may also be used as comparator inputs and by setting the appropriate bits in the CMCON register. To use RA<3:0> as digital inputs, it is also necessary to turn off the comparators.

Note: On a Power-on Reset (POR), RA5 and RA<3:0> are configured as analog inputs and read as '0'.

All PORTA pins have TTL input levels and full CMOS output drivers.

The TRISA register controls the direction of the PORTA pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set when using them as analog inputs.

EXAMP	LE 9-2:	INITIALIZING PORTA
CLRF	PORTA	; Initialize PORTA by
		; clearing output
		; data latches
CLRF	LATA	; Alternate method
		; to clear output
		; data latches
MOVLW	07h	; Configure A/D
MOVWF	ADCON1	; for digital inputs
MOVWF	07h	; Configure comparators
MOVWF	CMCON	; for digital input
MOVLW	OCFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISA	; Set RA<3:0> as inputs
		; RA<5:4> as outputs

Pin	Function	TRIS Setting	I/O	l/O Type	Description
RA0/AN0/C1INA/	A/ RA0 1			DIG	PORTA<0> data input; disabled when analog input enabled.
ULPWU/RP0		0	I/O	TTL	LATA<0> data output; not affected by analog input.
	AN0	1	I	ANA	A/D input channel 0 and Comparator C1- input. Default input configuration on POR; does not affect digital output.
	C1INA	1	I	ANA	Comparator 1 input A.
	ULPWU	1	Ι	ANA	Ultra low-power wake-up input.
	RP0	1	10	ST	Remappable peripheral pin 0 input.
		0	1/0	DIG	Remappable peripheral pin 0 output.
RA1/AN1/C2INA/	RA1	1	Ι	DIG	PORTA<1> data input; disabled when analog input enabled.
PMA7/RP1		0	0	TTL	LATA<1> data output; not affected by analog input.
	AN1	1	I	ANA	A/D input channel 1 and Comparator C2- input. Default input configuration on POR; does not affect digital output.
	C2INA	1	I	ANA	Comparator 1 input A.
	PMA7 <sup>(1)</sup>	1	I/O	ST/ TTL	Parallel Master Port io_addr_in[7].
		0		DIG	Parallel Master Port address.
	RP1	1	1/0	ST	Remappable peripheral pin 1 input.
		0	1/0	DIG	Remappable peripheral pin 1 output
RA2/AN2/ Vref-/CVref/	RA2	0	0	DIG	LATA<2> data output; not affected by analog input. Disabled when CVREF output enabled.
C2INB		1	Ι	TTL	PORTA<2> data input. Disabled when analog functions enabled; disabled when CVREF output enabled.
	AN2	1	I	ANA	A/D input channel 2 and Comparator C2+ input. Default input configuration on POR; not affected by analog output.
	VREF-	1	Ι	ANA	A/D and comparator voltage reference low input.
	CVREF	х	0	ANA	Comparator voltage reference output. Enabling this feature disables digital I/O.
	C2INB	I	I	ANA	Comparator 2 input B.
		0	0	ANA	CTMU pulse generator charger for the C2INB comparator input.
RA3/AN3/VREF+/	RA3	0	0	DIG	LATA<3> data output; not affected by analog input.
C1INB		1	I	TTL	PORTA<3> data input; disabled when analog input enabled.
	AN3	1	I	ANA	A/D input channel 3 and Comparator C1+ input. Default input configuration on POR.
	VREF+	1	I	ANA	A/D and comparator voltage reference high input.
	C1INB	1	Ι	ANA	Comparator 1 input B

#### TABLE 9-3:PORTA I/O SUMMARY

Legend: DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option)

Note 1: This bit is only available on 44-pin devices.

Pin	Function	TRIS Setting	I/O	I/O Туре	Description			
RA5/AN4/SS1/	RA5	0	0	DIG	LATA<5> data output; not affected by analog input.			
HLVDIN/RCV/		1	I	TTL	PORTA<5> data input; disabled when analog input enabled.			
RP2	AN4	1	Ι	ANA	A/D input channel 4. Default configuration on POR.			
	SS1	1	Ι	TTL	Slave select input for MSSP1.			
	HLVDIN	1	I	ANA	High/Low-Voltage Detect external trip point reference input.			
	RCV	1	I	TTL	External USB transceiver RCV input.			
	RP2	1	Ι	ST	Remappable Peripheral pin 2 input.			
		0	0	DIG	Remappable Peripheral pin 2 output.			
OSC2/CLKO/	OSC2	х	0	ANA	Main oscillator feedback output connection (HS mode).			
RA6	CLKO	х	0	DIG	System cycle clock output (Fosc/4) in RC and EC Oscillator modes.			
	RA6	1	Ι	TTL	PORTA<6> data input.			
		0	0	DIG	LATA<6> data output.			
OSC1/CLKI/RA7	OSC1	1	Ι	ANA	Main oscillator input connection.			
	CLKI	1		ANA	Main clock input connection.			
	RA7	1	Ι	TTL	PORTA<6> data input.			
		0	0	DIG	LATA<6> data output.			

TABLE 9-3: PORTA I/O SUMMARY (CONTINUED)

Legend: DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option)

**Note 1:** This bit is only available on 44-pin devices.

IADEE 3-4.	001111									
Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page	
PORTA	RA7	RA6	RA5	_	RA3	RA2	RA1	RA0	81	
LATA	LAT7	LAT6	LAT5	_	LAT3	LAT2	LAT1	LAT0	86	
TRISA	TRIS7	TRIS6	TRISA5	_	TRISA3	TRISA2	TRISA1	TRISA0	86	
ANCON0	PCFG7 <sup>(1)</sup>	PCFG6 <sup>(1)</sup>	PCFG5 <sup>(1)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	84	
CMxCON	CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	84, 84	
CVRCON	CVREN	CVROE	CVRR	r	CVR3	CVR2	CVR1	CVR0	87	

#### TABLE 9-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

Legend: — = unimplemented, read as '0'. Shaded cells are not used by PORTA.

Note 1: These bits are only available in 44-pin devices.

### 9.3 PORTB, TRISB and LATB Registers

PORTB is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISB. Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATB) is also memory mapped. Read-modify-write operations on the LATB register read and write the latched output value for PORTB.

	-LE 3-3.	INITIALIZING FORTD
CLRF	PORTB	; Initialize PORTB by
		; clearing output
		; data latches
CLRF	LATB	; Alternate method
		; to clear output
		; data latches
MOVLW	0x3F	; Configure as digital I/O
MOVFF	WREG ADCON1	; pins in this example
MOVLW	0CFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISB	; Set RB<3:0> as inputs
		; RB<5:4> as outputs
		; RB<7:6> as inputs
1		

EXAMPLE 9-3: INITIALIZING PORTB

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn <u>on all</u> the pull-ups. This is performed by clearing bit, RBPU (INTCON2<7>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a POR. The integrated weak pull-ups consist of a semiconductor structure similar to, but somewhat different, from a discrete resistor. On an unloaded I/O pin, the weak pull-ups are intended to provide logic high indication, but will not necessarily pull the pin all the way to VDD levels.

Note:	On	а	POR,	the	RB<3:0>	bits	are
	read	configured as analog inputs by default and read as '0'; RB<7:4> bits are configured					
	as di	gita	al inputs	•			

Four of the PORTB pins (RB<7:4>) have an interrupton-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB<7:4> pin configured as an output is excluded from the interrupton-change comparison). The input pins (of RB<7:4>) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB<7:4> are ORed together to generate the RB Port Change Interrupt with Flag bit, RBIF (INTCON<0>).

This interrupt can wake the device from Sleep mode or any of the Idle modes. Application software can clear the interrupt flag by following these steps:

- 1. Any read or write of PORTB (except with the MOVFF (ANY), PORTB instruction).
- 2. Wait one instruction cycle (such as executing a NOP instruction).
- 3. Clear flag bit, RBIF.

A mismatch condition continues to set flag bit, RBIF. Reading PORTB will end the mismatch condition and allow flag bit, RBIF, to be cleared after one instruction cycle of delay.

The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.

The RB5 pin is multiplexed with the Timer0 module clock input and one of the comparator outputs to become the RB5/KBI1/SDI1/SDA1/RP8 pin.

# PIC18F46J50 FAMILY

TABLE 9-5:	-5: PORTBI/O SUMMARY						
Pin	Function	TRIS Setting	I/O	l/O Type	Description		
RB0/AN12/ INT0/RP3	RB0	1	1	TTL	PORTB<0> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled. <sup>(1)</sup>		
		0	0	DIG	LATB<0> data output; not affected by analog input.		
	AN12	1	Ι	ANA	A/D input channel 12. <sup>(1)</sup>		
	INT0	1	I	ST	External interrupt 0 input.		
	RP3	1	Ι	ST	Remappable peripheral pin 3 input.		
		0	0	DIG	Remappable peripheral pin 3 output.		
RB1/AN10/ RTCC/RP4	RB1	1	I	TTL	PORTB<1> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled. <sup>(1)</sup>		
		0	0	DIG	LATB<1> data output; not affected by analog input.		
	AN10	1	Ι	ANA	A/D input channel 10. <sup>(1)</sup>		
	RTCC	0	0	DIG	Asynchronous serial transmit data output (USART module).		
	RP4	1	Ι	ST	Remappable peripheral pin 4 input.		
		0	0	DIG	Remappable peripheral pin 4 output.		
RB2/AN8/ CTEDG1/VMO/	<b>RB2</b> 1		I	TTL	PORTB<2> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled. <sup>(1)</sup>		
REFO/RP5		0	0	DIG	LATB<2> data output; not affected by analog input.		
	AN8	1	Ι	ANA	A/D input channel 8. <sup>(1)</sup>		
	CTEDG1	1	Ι	ST	CTMU Edge 1 input.		
	VMO	0	0	DIG	External USB transceiver D – data output.		
	REFO	0	0	DIG	Reference output clock.		
	RP5	1	Ι	ST	Remappable peripheral pin 5 input.		
		0	0	DIG	Remappable peripheral pin 5 output.		
RB3/AN9/	RB3	0	0	DIG	LATB<3> data output; not affected by analog input.		
CTEDG2/ PMA2/VPO/ RP6		1	Ι	TTL	PORTB<3> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled. <sup>(1)</sup>		
KF0	AN9	1	I	ANA	A/D input channel 9. <sup>(1)</sup>		
	CTEDG2	1	I	ST	CTMU edge 2 input.		
	PMA2	0	0	DIG	Parallel Master Port address.		
	VPO	0	I	DIG	External USB transceiver D+ data output.		
	RP6	1	I	ST	Remappable peripheral pin 6 input.		
		0	0	DIG	Remappable peripheral pin 6 output.		

TABLE 9-5: PORTB I/O SUMMARY

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option)

**Note 1:** Configuration on POR is determined by the PBADEN Configuration bit. Pins are configured as analog inputs by default when PBADEN is set and digital inputs when PBADEN is cleared.

2: All other pin functions are disabled when ICSP™ or ICD are enabled.

TABLE 9-5:	PORTB I		SUMMARY		NUED)
Pin	Function	TRIS Setting	I/O	l/O Type	Description
RB4/KBI0/	RB4	0	0	DIG	LATB<4> data output; not affected by analog input.
AN11/RP7/ SCK1/SCL1		1	I	TTL	PORTB<4> data input; weak pull-up when RBPU bit is cleared. Disabled when analog input enabled. <sup>(1)</sup>
	KBI0	1	Ι	TTL	Interrupt-on-change pin.
	AN11	1	Ι	ANA	A/D input channel 11. <sup>(1)</sup>
	RP7	1	Ι	ST	Remappable peripheral pin 7 input.
		0	0	DIG	Remappable peripheral pin 7 output.
	SCK1	1	Ι	ST/TTL	Parallel Master Port io_addr_in<1>.
		0	0	DIG	Parallel Master Port address.
	SCL1	1	I	l <sup>2</sup> C/ SMBus	I <sup>2</sup> C™ clock input (MSSP1 module).
		0	0	DIG	I <sup>2</sup> C clock output (MSSP1 module).
RB5/KBI1/	RB5	0	0	DIG	LATB<5> data output.
SDI1/SDA1/ RP8		1	Ι	TTL	PORTB<5> data input; weak pull-up when RBPU bit is cleared.
	KBI1	1	Ι	TTL	Interrupt-on-change pin.
	SDI1	1	I	ST	SPI Data Input (MSSP1 module).
	SDA1	<b>SDA1</b> 1		l <sup>2</sup> C/ SMBus	I <sup>2</sup> C data input (MSSP1 module).
		0	0	DIG	l <sup>2</sup> C/SMBus.
	RP8	1	Ι	ST	Remappable peripheral pin 8 input.
		0	0	DIG	Remappable peripheral pin 8 output.
RB6/KBI2/	RB6	0	0	DIG	LATB<6> data output.
PGC/RP9		1	I	TTL	PORTB<6> data input; weak pull-up when RBPU bit is cleared.
	KBI2	1	I	TTL	Interrupt-on-change pin.
	PGC	х	Ι	ST	Serial execution (ICSP™) clock input for ICSP and ICD operation. <sup>(2)</sup>
	RP9	1	Ι	ST	Remappable peripheral pin 9 input.
		0	0	DIG	Remappable peripheral pin 9 output.
RB7/KBI3/	RB7	0	0	DIG	LATB<7> data output.
PGD/RP10		1	I	TTL	PORTB<7> data input; weak pull-up when RBPU bit is cleared.
	KBI3	1		TTL	Interrupt-on-change pin.
	PGD	Х	0	DIG	Serial execution data output for ICSP and ICD operation. <sup>(2)</sup>
		х	Ι	ST	Serial execution data input for ICSP and ICD operation. <sup>(2)</sup>
	RP10	1	Ι	ST	Remappable peripheral pin 10 input.
		0	0	ST	Remappable peripheral pin 10 output.

# TABLE 9-5: PORTB I/O SUMMARY (CONTINUED)

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; x = Don't care (TRIS bit does not affect port direction or is overridden for this option)

**Note 1:** Configuration on POR is determined by the PBADEN Configuration bit. Pins are configured as analog inputs by default when PBADEN is set and digital inputs when PBADEN is cleared.

**2:** All other pin functions are disabled when  $ICSP^{TM}$  or ICD are enabled.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	86
LATB	LATB7	LATB6	LATB5	LATB4	LATB3	LATB2	LATB1	LATB0	86
TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	86
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	83
INTCON2	RBPU	INTEDG0	INTEDG1	INTEDG2	INTEDG3	TMR0IP	INT3IP	RBIP	83
INTCON3	INT2IP	INT1IP	INT3IE	INT2IE	INT1IE	INT3IF	INT2IF	INT1IF	83
ADCON0	PCFG7	PCFG6	PCFG5	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	84

 TABLE 9-6:
 SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTB.

### 9.4 PORTC, TRISC and LATC Registers

PORTC is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISC. Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATC) is also memory mapped. Read-modify-write operations on the LATC register read and write the latched output value for PORTC.

PORTC is multiplexed with several peripheral functions (see Table ). The pins have Schmitt Trigger input buffers.

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for additional information.

Pins RC4 and RC5 are multiplexed with the USB module. Depending on the configuration of the module, they can serve as the differential data lines for the on-chip USB transceiver, or the data inputs from an external USB transceiver. When used as general purpose inputs, both RC4 and RC5 input buffers depend on the level of the voltage applied to the VUSB pin, instead of VDD like all other general purpose I/O pins. Therefore, if the RC4 or RC5 general purpose input capability will be used, the VUSB pin should not be left floating.

Unlike other PORTC pins, RC4 and RC5 do not have TRISC bits associated with them. As digital ports, they can only function as digital inputs. When configured for USB operation, the data direction is determined by the configuration and status of the USB module at a given time. If an external transceiver is used, RC4 and RC5 always function as inputs from the transceiver. If the onchip transceiver is used, the data direction is determined by the operation being performed by the module at that time. Note: On a Power-on Reset, PORTC pins (except RC2, RC4 and RC5) are configured as digital inputs. RC2 will default as an analog input (controlled by the ANCON1 register). To use pins RC4 and RC5 as digital inputs, the USB module must be disabled (UCON<3> = 0) and the on-chip USB transceiver must be disabled (UCFG<3> = 1). The internal USB transceiver has a POR value of enabled.

The contents of the TRISC register are affected by peripheral overrides. Reading TRISC always returns the current contents, even though a peripheral device may be overriding one or more of the pins.

EXAMPLE 9-4:	INITIALIZING PORTC

CLRF	PORTC	; Initialize PORTC by
		; clearing output
		; data latches
CLRF	LATC	; Alternate method
		; to clear output
		; data latches
MOVLW	0x3F	; Value used to
		; initialize data
		; direction
MOVWF	TRISC	; Set RC<5:0> as inputs
		; RC<7:6> as outputs
MOVLB	0x0F	; ANCON register is not in
		Access Bank
BSF	ANCON1, F	CFG11
		;Configure RC2/AN11 as
		digital input

Pin	Function	TRIS Setting	I/O	l/O Type	Description
RC0/T1OSO/ RC0 1 I		I	ST	PORTC<0> data input.	
T1CKI/RP11		0	0	DIG	LATC<0> data output.
	T1OSO	Х	0	ANA	Timer1 oscillator output; enabled when Timer1 oscillator enabled. Disables digital I/O.
	T1CKI	1	Ι	ST	Timer1 digital clock input.
	RP11	1	Ι	ST	Remappable peripheral pin 11 input.
		0	0	DIG	Remappable peripheral pin 11 output.
RC1/T1OSI/	RC1	1	Ι	ST	PORTC<1> data input.
UOE/RP12		0	0	DIG	LATC<1> data output.
	T10SI	х	I	ANA	Timer1 oscillator input; enabled when Timer1 oscillator enabled. Disables digital I/O.
	UOE	0	0	DIG	External USB transceiver NOE output.
	RP12	1	Ι	ST	Remappable peripheral pin 12 input.
		0	0	DIG	Remappable peripheral pin 12 output.
RC2/AN11/	RC2	1	I	ST	PORTC<2> data input.
CTPLS/RP13		0	0	DIG	PORTC<2> data output.
	AN11	1	I	ANA	A/D input channel 11.
	CTPLS	0	0	DIG	CTMU pulse generator output.
	RP13	1	Ι	ST	Remappable peripheral pin 13 input.
		0	0	DIG	Remappable peripheral pin 13 output.
RC4/D-/VM	RC4	х	Ι	TTL	PORTC<4> data input.
	D-	х	Ι	XCVR	USB bus minus line output.
		Х	0	XCVR	USB bus minus line input.
	VM	1	Ι	TTL	External USB transceiver VP input.
RC5/D+/VP	RC5	х	I	TTL	PORTC<5> data input.
	D+	Х	I	XCVR	USB bus plus line input.
		х	0	XCVR	USB bus plus line output.
	VP	1	I	TTL	External USB transceiver VP input.

TABLE 9-7: PORTC I/O SUMMARY<sup>(1)</sup>

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; I<sup>2</sup>C/SMB = I<sup>2</sup>C/SMBus input buffer; x = Don't care (TRIS bit does not affect port direction or is overridden for this option)

**Note 1:** Enhanced PWM output is available only on PIC18F4XJ50 devices.

2: This bit is only available on 44-pin devices.

Pin	Function	TRIS Setting	I/O	l/O Type	Description
		PORTC<6> data input.			
TX1/CK1/RP17		0	0	DIG	LATC<6> data output.
	PMA5 <sup>(2)</sup>	1	I	ST/TTL	Parallel Master Port io_addr_in<5>.
		0	0	DIG	Parallel Master Port address.
	TX1	0	0	DIG	Asynchronous serial transmit data output (EUSART module); takes priority over port data. User must configure as output.
	CK1	1	Ι	ST	Synchronous serial clock input (EUSART module).
		0	0	DIG	Synchronous serial clock output (EUSART module); takes priority over port data.
	RP17	1	I	ST	Remappable peripheral pin 17 input.
		0	0	DIG	Remappable peripheral pin 17 output.
RC7/RX1/DT1/	RC7	1	Ι	ST	PORTC<7> data input.
SDO1/RP18		0	0	DIG	LATC<7> data output.
	RX1	1	Ι	ST	Asynchronous serial receive data input (EUSART module).
	DT1	1	1	ST	Synchronous serial data input (EUSART module). User must configure as an input.
		0	0	DIG	Synchronous serial data output (EUSART module); takes priority over port data.
	SDO1	0	0	DIG	SPI data output (MSSP1 module).
	RP18	1	Ι	ST	Remappable peripheral pin 18 input.
		0	0	DIG	Remappable peripheral pin 18 output.

# TABLE 9-7: PORTC I/O SUMMARY<sup>(1)</sup> (CONTINUED)

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level input/output; I<sup>2</sup>C/SMB = I<sup>2</sup>C/SMBus input buffer; x = Don't care (TRIS bit does not affect port direction or is overridden for this option)

**Note 1:** Enhanced PWM output is available only on PIC18F4XJ50 devices.

**2:** This bit is only available on 44-pin devices.

#### TABLE 9-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page:
PORTC	RC7	RC6	RC5	RC4	_	RC2	RC1	RC0	86
LATC	LATC7	LATC6	LATC5	LATC4	_	LATC2	LATC1	LATC0	86
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	_	TRISC2	TRISC1	TRISC0	86

#### 9.5 PORTD, TRISD and LATD Registers

#### Note: PORTD is available only in 44-pin devices.

PORTD is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISD. Setting a TRISD bit (= 1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISD bit (= 0) will make the corresponding PORTD pin an output (i.e., put the contents of the output latch on the selected pin).

The Data Latch register (LATD) is also memory mapped. Read-modify-write operations on the LATD register read and write the latched output value for PORTD.

All pins on PORTD are implemented with Schmitt Trigger input buffers. Each pin is individually configurable as an input or output.

Note:	On a POR, these pins are configured as
	digital inputs.

#### EXAMPLE 9-5: INITIALIZING PORTD

CLRF	PORTD	; Initialize PORTD by ; clearing output
		, creating output
		; data latches
CLRF	LATD	; Alternate method
		; to clear output
		; data latches
MOVLW	OCFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISD	; Set RD<3:0> as inputs
		; RD<5:4> as outputs
		; RD<7:6> as inputs

Each of the PORTD pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by setting bit, RDPU (PORTE<7>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a POR. The integrated weak pull-ups consist of a semiconductor structure similar to, but somewhat different, from a discrete resistor. On an unloaded I/O pin, the weak pull-ups are intended to provide logic high indication, but will not necessarily pull the pin all the way to VDD levels.

Note that the pull-ups can be used for any set of features, similar to the pull-ups found on PORTB.

Pin	Function	TRIS Setting	I/O	l/O Type	Description
RD0/PMD0/	RD0	1	Ι	ST	PORTD<0> data input.
SCL2		0	0	DIG	LATD<0> data output.
	PMD0	1	Ι	ST/TTL	Parallel Master Port data in.
		0	0	DIG	Parallel Master Port data out.
	SCL2	1	I	I <sup>2</sup> C/ SMB	I <sup>2</sup> C <sup>™</sup> clock input (MSSP2 module); input type depends on module setting.
		0	0	DIG	I <sup>2</sup> C clock output (MSSP2 module); takes priority over port data.
RD1/PMD1/	RD1	1	I	ST	PORTD<1> data input.
SDA2		0	0	DIG	LATD<1> data output.
	PMD1	1	Ι	TTL	Parallel Master Port data in.
		0	0	DIG	Parallel Master Port data out.
	SDA2	1	I	I <sup>2</sup> C/ SMB	I <sup>2</sup> C data input (MSSP2 module); input type depends on module setting.
		0	0	DIG	I <sup>2</sup> C data output (MSSP2 module); takes priority over port data.
RD2/PMD2/	RD2	1	I	ST	PORTD<2> data input.
RP19		0	0	DIG	LATD<2> data output.
	PMD2	1	Ι	TTL	Parallel Master Port data in.
		0	0	DIG	Parallel Master Port data out.
	RP19	1	Ι	ST	Remappable peripheral pin 19 input.
		0	0	DIG	Remappable peripheral pin 19 output.

TABLE 9-9:PORTD I/O SUMMARY

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer;  $I^2C/SMB = I^2C/SMB$ us input buffer; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

Function	TRIS Setting	I/O	I/O Type	Description			
RD3	1	I	DIG	PORTD<3> data input.			
	0	0	DIG	LATD<3> data output.			
PMD3	1	I	ST/TTL	Parallel Master Port data in.			
	0	0	DIG	Parallel Master Port data out.			
RP20	1	Ι	ST	Remappable peripheral pin 20 input.			
	0	0	DIG	Remappable peripheral pin 20 output.			
RD4	1	Ι	ST	PORTD<4> data input.			
	0	0	DIG	LATD<4> data output.			
PMD4	1	Ι	TTL	Parallel Master Port data in.			
	0	0	DIG	Parallel Master Port data out.			
RP21	1	Ι	ST	Remappable peripheral pin 21 input.			
	0	0	DIG	Remappable peripheral pin 21 output.			
RD5	1	Ι	ST	PORTD<5> data input.			
	0	0	DIG	LATD<5> data output.			
PMD5	1	Ι	TTL	Parallel Master Port data in.			
	0	0	DIG	Parallel Master Port data out.			
RP22	1	Ι	ST	Remappable peripheral pin 22 input.			
	0	0	DIG	Remappable peripheral pin 22 output.			
RD6	1	I	ST	PORTD<6> data input.			
	0	0	DIG	LATD<6> data output.			
PMD6	1	Ι	TTL	Parallel Master Port data in.			
	0	0	DIG	Parallel Master Port data out.			
RP23	1	Ι	ST	Remappable peripheral pin 23 input.			
	0	0	DIG	Remappable peripheral pin 23 output.			
RD7	1	Ι	ST	PORTD<7> data input.			
	0	0	DIG	LATD<7> data output.			
PMD7	1	I	TTL	Parallel Master Port data in.			
	0	0	DIG	Parallel Master Port data out.			
RP24	1	I	ST	Remappable peripheral pin 24 input.			
	0	0	DIG	Remappable peripheral pin 24 output.			
	FunctionRD3PMD3RP20RD4PMD4PMD4RP21RD5PMD5RP22RD6PMD6RP23RD7PMD7	FunctionTRIS SettingRD3100PMD310100RP2010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101010101 <td< td=""><td>Function         TRIS Setting         I/O           RD3         1         I           0         0         0           PMD3         1         I           0         0         0           PMD3         1         I           0         0         0           RP20         1         I           0         0         0           RD4         1         I           0         0         0           RD4         1         I           0         0         0           RD4         1         I           0         0         0           RD5         1         I           0         0         0           RD5         1         I           0         0         0           RD5         1         I           0         0         0           RD6         1         I           0         0         0           RD6         1         I           0         0         0           RD7         1         I           <t< td=""><td>Function         TRIS Setting         I/O         I/O Type           RD3         1         I         DIG           0         0         DIG           PMD3         1         I         ST/TTL           0         0         DIG           PMD3         1         I         ST/TTL           0         0         DIG           RP20         1         I         ST           0         0         O         DIG           RP20         1         I         ST           0         0         O         DIG           RP4         1         I         ST           0         0         O         DIG           PMD4         1         I         ST           0         0         O         DIG           RP21         1         I         ST           0         0         DIG         DIG           PMD5         1         I         ST           0         0         DIG         DIG           RP22         1         I         ST           0         0         DIG         DIG      <t< td=""></t<></br></td></t<></td></td<>	Function         TRIS Setting         I/O           RD3         1         I           0         0         0           PMD3         1         I           0         0         0           PMD3         1         I           0         0         0           RP20         1         I           0         0         0           RD4         1         I           0         0         0           RD4         1         I           0         0         0           RD4         1         I           0         0         0           RD5         1         I           0         0         0           RD5         1         I           0         0         0           RD5         1         I           0         0         0           RD6         1         I           0         0         0           RD6         1         I           0         0         0           RD7         1         I <t< td=""><td>Function         TRIS Setting         I/O         I/O Type           RD3         1         I         DIG           0         0         DIG           PMD3         1         I         ST/TTL           0         0         DIG           PMD3         1         I         ST/TTL           0         0         DIG           RP20         1         I         ST           0         0         O         DIG           RP20         1         I         ST           0         0         O         DIG           RP4         1         I         ST           0         0         O         DIG           PMD4         1         I         ST           0         0         O         DIG           RP21         1         I         ST           0         0         DIG         DIG           PMD5         1         I         ST           0         0         DIG         DIG           RP22         1         I         ST           0         0         DIG         DIG      <t< td=""></t<></br></td></t<>	Function         TRIS Setting         I/O         I/O 			

### TABLE 9-9: PORTD I/O SUMMARY (CONTINUED)

**Legend:** DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer;  $l^2C/SMB = l^2C/SMB$ us input buffer; x = Don't care (TRIS bit does not affect port direction or is overridden for this option).

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
PORTD <sup>(1)</sup>	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	86
LATD <sup>(1)</sup>	LATD7	LATD6	LATD5	LATD4	LATD3	LATD2	LATD1	LATD0	86
TRISD <sup>(1)</sup>	TRISD7	TRISD6	TRISD5	TRISD4	TRISD3	TRISD2	TRISD1	TRISD0	86

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTD.

**Note 1:** These registers are not available in 28-pin devices.

### 9.6 PORTE, TRISE and LATE Registers

#### **Note:** PORTE is available only in 44-pin devices.

Depending on the particular PIC18F46J50 Family device selected, PORTE is implemented in two different ways.

For 44-pin devices, PORTE is a 3-bit wide port. Three pins (RE0/AN5/PMRD, RE1/AN6/PMWR and RE2/AN7/PMCS) are individually configurable as inputs or outputs. These pins have Schmitt Trigger input buffers. When selected as analog inputs, these pins will read as '0's.

The corresponding Data Direction register is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., put the contents of the output latch on the selected pin).

TRISE controls the direction of the RE pins, even when they are being used as analog inputs. The user must make sure to keep the pins configured as inputs when using them as analog inputs.

**Note:** On a POR, RE<2:0> are configured as analog inputs.

The Data Latch register (LATE) is also memory mapped. Read-modify-write operations on the LATE register read and write the latched output value for PORTE.

#### EXAMPLE 9-6: INITIALIZING PORTE

CLRF	PORTE	; Initialize PORTE by ; clearing output
CLRF	LATE	; data latches : Alternate method
CLKF	LAID	; to clear output
		; data latches
MOVLW	0Ah	; Configure A/D
MOVWF	ADCON1	; for digital inputs
MOVLW	03h	; Value used to
		; initialize data
		; direction
MOVWF	TRISE	; Set RE<0> as inputs
		; RE<1> as outputs
		; RE<2> as inputs

Each of the PORTE pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by setting bit, REPU (PORTE<6>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a POR. The integrated weak pull-ups consist of a semiconductor structure similar to, but somewhat different, from a discrete resistor. On an unloaded I/O pin, the weak pull-ups are intended to provide logic high indication, but will not necessarily pull the pin all the way to VDD levels.

Note that the pull-ups can be used for any set of features, similar to the pull-ups found on PORTB

TADLE 9-11:	PORTE I/O SUMMART							
Pin	Function	TRIS Setting	I/O	l/O Type	Description			
RE0/AN5/	RE0	1	Ι	ST	PORTE<0> data input; disabled when analog input enabled.			
PMRD		0	0	DIG	LATE<0> data output; not affected by analog input.			
	AN5	1	Ι	ANA	A/D input channel 5; default input configuration on POR.			
	PMRD	1	Ι	ST/TTL	Parallel Master Port io_rd_in.			
		0	0	DIG	Parallel Master Port read strobe.			
RE1/AN6/	RE1	1	Ι	ST	PORTE<1> data input; disabled when analog input enabled.			
PMWR		0	0	DIG	LATE<1> data output; not affected by analog input.			
	AN6	1	Ι	ANA	A/D input channel 6; default input configuration on POR.			
	PMWR	1	Ι	ST/TTL	Parallel Master Port io_wr_in.			
		0	0	DIG	Parallel Master Port write strobe.			
RE2/AN7/	RE2	1	-	ST	PORTE<2> data input; disabled when analog input enabled.			
PMCS		0	0	DIG	LATE<2> data output; not affected by analog input.			
	AN7	1	Ι	ANA	A/D input channel 7; default input configuration on POR.			
	PMCS	0	0	DIG	Parallel Master Port byte enable.			
Vss1			Р		Cround reference for legic and I/O pipe			
Vss2	_		Г		Ground reference for logic and I/O pins.			
AVss1	—	_	Р	—	Ground reference for analog modules.			
VDD1			Р		Positive supply for peripheral digital logic and I/O pins.			
Vdd2	_		Г		Positive supply for periprieral digital logic and 1/O pins.			
VDDCORE/VCAP	VDDCORE	—	Р	—	Positive supply for microcontroller core logic (regulator disabled).			
	VCAP	—	Р	—	External filter capacitor connection (regulator enabled).			
AVDD1			Р		Positive supply for analog modules.			
AVDD2			_					
VUSB	_	_	Р	_	USB voltage input pin.			

#### TABLE 9-11: PORTE I/O SUMMARY

Legend: DIG = Digital level output; TTL = TTL input buffer; ST = Schmitt Trigger input buffer; ANA = Analog level I = Input; O = Output; P = Power

#### TABLE 9-12: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
PORTE <sup>(1)</sup>	RDPU	REPU			_	RE2	RE1	RE0	86
LATE <sup>(1)</sup>	—	—	_	—	_	LATE2	LATE1	LATE0	86
TRISE <sup>(1)</sup>	_	_	_			TRISE2	TRISE1	TRISE0	86
ANCON0	PCFG7 <sup>(2)</sup>	PCFG6 <sup>(2)</sup>	PCFG5 <sup>(2)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	88

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PORTE.

Note 1: These registers are not available in 28-pin devices.

2: These bits are only available in 44-pin devices.

	Note:	bit 7	RDPU: PORTD Pull-up Enable bit
--	-------	-------	--------------------------------

- 0 = All PORTD pull-ups are disabled
- 1 = PORTD pull-ups are enabled for any input pad
- bit 6 **REPU:** PORTE Pull-up Enable bit
- 0 = All PORTE pull-ups are disabled
- 1 = PORTE pull-ups are enabled for any input pad

# 9.7 Peripheral Pin Select (PPS)

A major challenge in general purpose devices is providing the largest possible set of peripheral features while minimizing the conflict of features on I/O pins. The challenge is even greater on low pin count devices similar to the PIC18F46J50 Family. In an application that needs to use more than one peripheral multiplexed on single pin, inconvenient workarounds in application code or a complete redesign may be the only option.

The Peripheral Pin Select (PPS) feature provides an alternative to these choices by enabling the user's peripheral set selection and their placement on a wide range of I/O pins. By increasing the pinout options available on a particular device, users can better tailor the microcontroller to their entire application, rather than trimming the application to fit the device.

The PPS feature operates over a fixed subset of digital I/O pins. Users may independently map the input and/ or output of any one of the many digital peripherals to any one of these I/O pins. PPS is performed in software and generally does not require the device to be reprogrammed. Hardware safeguards are included that prevent accidental or spurious changes to the peripheral mapping once it has been established.

#### 9.7.1 AVAILABLE PINS

The PPS feature is used with a range of up to 22 pins; the number of available pins is dependent on the particular device and its pin count. Pins that support the PPS feature include the designation "RPn" in their full pin designation, where "RP" designates a remappable peripheral and "n" is the remappable pin number. See Table 1-2 for pinout options in each package offering.

### 9.7.2 AVAILABLE PERIPHERALS

The peripherals managed by the PPS are all digital only peripherals. These include general serial communications (UART and SPI), general purpose timer clock inputs, timer-related peripherals (input capture and output compare) and external interrupt inputs. Also included are the outputs of the comparator module, since these are discrete digital signals.

The PPS module is not applied to I<sup>2</sup>C, change notification inputs, RTCC alarm outputs or peripherals with analog inputs. Additionally, the MSSP1 and EUSART1 modules are not routed through the PPS module.

A key difference between pin select and non-pin select peripherals is that pin select peripherals are not associated with a default I/O pin. The peripheral must always be assigned to a specific I/O pin before it can be used. In contrast, non-pin select peripherals are always available on a default pin, assuming that the peripheral is active and not conflicting with another peripheral.

#### 9.7.2.1 Peripheral Pin Select Function Priority

When a pin selectable peripheral is active on a given I/O pin, it takes priority over all other digital I/O and digital communication peripherals associated with the pin. Priority is given regardless of the type of peripheral that is mapped. Pin select peripherals never take priority over any analog functions associated with the pin.

#### 9.7.3 CONTROLLING PERIPHERAL PIN SELECT

PPS features are controlled through two sets of Special Function Registers (SFRs): one to map peripheral inputs and the other to map outputs. Because they are separately controlled, a particular peripheral's input and output (if the peripheral has both) can be placed on any selectable function pin without constraint.

The association of a peripheral to a peripheral selectable pin is handled in two different ways, depending on whether an input or an output is being mapped.

#### 9.7.3.1 Input Mapping

The inputs of the PPS options are mapped on the basis of the peripheral; that is, a control register associated with a peripheral dictates the pin it will be mapped to. The RPINRx registers are used to configure peripheral input mapping (see Register 9-6 through Register 9-20). Each register contains a 5-bit field which is associated with one of the pin selectable peripherals. Programming a given peripheral's bit field with an appropriate 5-bit value maps the RPn pin with that value to that peripheral. For any given device, the valid range of values for any of the bit fields corresponds to the maximum number of peripheral pin selections supported by the device.

<b>TABLE 9-13</b> :	SELECTABLE INPUT SOURCES	(MAPS INPUT TO FUNCTION) <sup>(1)</sup>
IADLE 5-13.	SELECTABLE INFUT SOURCES	

Input Name	Function Name	Register	Configuration Bits
External Interrupt 1	INT1	RPINR1	INTR1R<4:0>
External Interrupt 2	INT2	RPINR2	INTR2R<4:0>
External Interrupt 3	INT3	RPINR3	INTR3R<4:0>
Timer0 External Clock Input	TOCKI	RPINR4	T0CKR<4:0>
Timer3 External Clock Input	T3CKI	RPINR6	T3CKR<4:0>
Input Capture 1	CCP1	RPINR7	IC1R<4:0>
Input Capture 2	CCP2	RPINR8	IC2R<4:0>
Timer1 Gate Input	T1G	RPINR12	T1GR<4:0>
Timer3 Gate Input	T3G	RPINR13	T3GR<4:0>
EUSART2 Asynchronous Receive/Synchronous Receive	RX2/DT2	RPINR16	RX2DT2R<4:0>
EUSART2 Asynchronous Clock Input	CK2	RPINR17	CK2R<4:0>
SPI2 Data Input	SDI2	RPINR21	SDI2R<4:0>
SPI2 Clock Input	SCK2IN	RPINR22	SCK2R<4:0>
SPI2 Slave Select Input	SS2IN	RPINR23	SS2R<4:0>
PWM Fault Input	FLT0	RPINR24	OCFAR<4:0>

**Note 1:** Unless otherwise noted, all inputs use the Schmitt Trigger input buffers.

## 9.7.3.2 Output Mapping

In contrast to inputs, the outputs of the PPS options are mapped on the basis of the pin. In this case, a control register associated with a particular pin dictates the peripheral output to be mapped. The RPORx registers are used to control output mapping. The value of the bit field corresponds to one of the peripherals and that peripheral's output is mapped to the pin (see Table 9-14). Because of the mapping technique, the list of peripherals for output mapping also includes a null value of '00000'. This permits any given pin to remain disconnected from the output of any of the pin selectable peripherals.

## TABLE 9-14: SELECTABLE OUTPUT SOURCES (MAPS FUNCTION TO OUTPUT)

Function	Output Function Number <sup>(1)</sup>	Output Name			
NULL	0	NULL <sup>(2)</sup>			
C1OUT	1	Comparator 1 Output			
C2OUT	2	Comparator 2 Output			
TX2/CK2	5	EUSART2 Asynchronous Transmit/Asynchronous Clock Output			
DT2	6	EUSART2 Synchronous Transmit			
SDO2	9	SPI2 Data Output			
SCK2	10	SPI2 Clock Output			
SSDMA	12	SPI DMA Slave Select			
ULPOUT	13	Ultra Low-Power Wake-up Event			
CCP1/P1A	14	ECCP1 Compare or PWM Output Channel A			
P1B	15	ECCP1 Enhanced PWM Output, Channel B			
P1C	16	ECCP1 Enhanced PWM Output, Channel C			
P1D	17	ECCP1 Enhanced PWM Output, Channel D			
CCP2/P2A	18	ECCP2 Compare or PWM Output			
P2B	19	ECCP2 Enhanced PWM Output, Channel B			
P2C	20	ECCP2 Enhanced PWM Output, Channel C			
P2D	21	ECCP2 Enhanced PWM Output, Channel D			

Note 1: Value assigned to the RP<4:0> pins corresponds to the peripheral output function number.

2: The NULL function is assigned to all RPn outputs at device Reset and disables the RPn output function.

## 9.7.3.3 Mapping Limitations

The control schema of the PPS is extremely flexible. Other than systematic blocks that prevent signal contention caused by two physical pins being configured as the same functional input or two functional outputs configured as the same pin, there are no hardware enforced lock outs. The flexibility extends to the point of allowing a single input to drive multiple peripherals or a single functional output to drive multiple output pins.

## 9.7.4 CONTROLLING CONFIGURATION CHANGES

Because peripheral remapping can be changed during run time, some restrictions on peripheral remapping are needed to prevent accidental configuration changes. PIC18F devices include three features to prevent alterations to the peripheral map:

- Control register lock sequence
- · Continuous state monitoring
- Configuration bit remapping lock

## 9.7.4.1 Control Register Lock

Under normal operation, writes to the RPINRx and RPORx registers are not allowed. Attempted writes will appear to execute normally, but the contents of the registers will remain unchanged. To change these registers, they must be unlocked in hardware. The register lock is controlled by the IOLOCK bit (PPSCON<0>). Setting IOLOCK prevents writes to the control registers; clearing IOLOCK allows writes.

To set or clear IOLOCK, a specific command sequence must be executed:

- 1. Write 55h to EECON2<7:0>.
- 2. Write AAh to EECON2<7:0>.
- 3. Clear (or set) IOLOCK as a single operation.

IOLOCK remains in one state until changed. This allows all of the PPS registers to be configured with a single unlock sequence followed by an update to all control registers, then locked with a second lock sequence.

#### 9.7.4.2 Continuous State Monitoring

In addition to being protected from direct writes, the contents of the RPINRx and RPORx registers are constantly monitored in hardware by shadow registers. If an unexpected change in any of the registers occurs (such as cell disturbances caused by ESD or other external events), a Configuration Mismatch Reset will be triggered.

## 9.7.4.3 Configuration Bit Pin Select Lock

As an additional level of safety, the device can be configured to prevent more than one write session to the RPINRx and RPORx registers. The IOL1WAY (CONFIG3H<0>) Configuration bit blocks the IOLOCK bit from being cleared after it has been set once. If IOLOCK remains set, the register unlock procedure will not execute and the PPS control registers cannot be written to. The only way to clear the bit and re-enable peripheral remapping is to perform a device Reset.

In the default (unprogrammed) state, IOL1WAY is set, restricting users to one write session. Programming IOL1WAY allows users unlimited access (with the proper use of the unlock sequence) to the PPS registers.

## 9.7.5 CONSIDERATIONS FOR PERIPHERAL PIN SELECTION

The ability to control peripheral pin selection introduces several considerations into application design that could be overlooked. This is particularly true for several common peripherals that are available only as remappable peripherals.

The main consideration is that the PPS is not available on default pins in the device's default (Reset) state. Since all RPINRx registers reset to '11111' and all RPORx registers reset to '00000', all PPS inputs are tied to RP31 and all PPS outputs are disconnected.

Note:	In tying PPS inputs to RP31, RP31 does					
	not have to exist on a device for the					
	registers to be reset to it.					

This situation requires the user to initialize the device with the proper peripheral configuration before any other application code is executed. Since the IOLOCK bit resets in the unlocked state, it is not necessary to execute the unlock sequence after the device has come out of Reset.

For application safety, however, it is best to set IOLOCK and lock the configuration after writing to the control registers.

The unlock sequence is timing critical. Therefore, it is recommended that the unlock sequence be executed as an assembly language routine with interrupts temporarily disabled. If the bulk of the application is written in C or another high-level language, the unlock sequence should be performed by writing in-line assembly. Choosing the configuration requires the review of all PPSs and their pin assignments, especially those that will not be used in the application. In all cases, unused pin selectable peripherals should be disabled completely. Unused peripherals should have their inputs assigned to an unused RPn pin function. I/O pins with unused RPn functions should be configured with the null peripheral output.

The assignment of a peripheral to a particular pin does not automatically perform any other configuration of the pin's I/O circuitry. In theory, this means adding a pin selectable output to a pin may mean inadvertently driving an existing peripheral input when the output is driven. Users must be familiar with the behavior of other fixed peripherals that share a remappable pin and know when to enable or disable them. To be safe, fixed digital peripherals that share the same pin should be disabled when not in use.

Along these lines, configuring a remappable pin for a specific peripheral does not automatically turn that feature on. The peripheral must be specifically configured for operation and enabled, as if it were tied to a fixed pin. Where this happens in the application code (immediately following device Reset and peripheral configuration or inside the main application routine) depends on the peripheral and its use in the application.

A final consideration is that the PPS functions neither override analog inputs nor reconfigure pins with analog functions for digital I/O. If a pin is configured as an analog input on device Reset, it must be explicitly reconfigured as digital I/O when used with a PPS.

Example 9-7 provides a configuration for bidirectional communication with flow control using EUSART2. The following input and output functions are used:

- Input Function RX2
- Output Function TX2

#### EXAMPLE 9-7: CONFIGURING EUSART2 INPUT AND OUTPUT FUNCTIONS

		Г		UN3
//****	*******	*******	******	****
	lock Regi			
//****	*******	*******	******	****
_asm				
MOVLB	0x0E			;PPS registers are
				in BANK 14
BCF	INTCON,	GIE		;Disable interrupts
				for unlock sequence
MOVLW		0		
MOVWF	EECON2,	0		
	EECON2,	0		
BCF			BANKED	;Write protect off
endas		,		,
-				
//****	*******	*******	******	
// Cor	nfigure l	Input Fur	nctions	
	ee Table			
	********			
	/******			****
	/ Assign /******			· • • • •
	/ ^ ^ ^ ^ ^ ^ ^ ^ ^			
_asm	03700			
MOVLW				
endas	RPINR16	, BANKED		
	5111			
//****	*******	*******	******	
// Cor	nfigure (	Dutput Fu	inctions	5
	ee Table	-		
//****	*******	*******	******	
1.	/******	******	******	* * * * *
	/ Assign			
	/******	* * * * * * * * *	******	* * * * *
_asm	01/05			
MOVLW	RPOR1,	DANKED		
endas		DANKED		
	2111			
//****	*******	*******	******	****
// Loc	ck Regist	ers		
asm				
BCF	INTCON,	GIE		;Disable interrupts
				for unlock sequence
MOVLW	0x55			±
	EECON2,	0		
MOVLW				
	EECON2,	0		
BSF			BANKED	;PPS Write
	,	,		Protected
endas	sm			
_				

Note: If the Configuration bit, IOL1WAY = 1, once the IOLOCK bit is set, it cannot be cleared, preventing any future RP register changes. The IOLOCK bit is cleared back to '0' on any device Reset.

## 9.7.6 PERIPHERAL PIN SELECT REGISTERS

The PIC18F46J50 Family of devices implements a total of 37 registers for remappable peripheral configuration of 44-pin devices. The 28-pin devices have 31 registers for remappable peripheral configuration.

# **Note:** Input and output register values can only be changed if PPS<IOLOCK> = 0. See Example 9-7 for a specific command sequence.

## REGISTER 9-5: PPSCON: PERIPHERAL PIN SELECT INPUT REGISTER 0 (BANKED EFFh)<sup>(1)</sup>

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0
—	—	—	—	—	—		IOLOCK
bit 7 bit 0							

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

## bit 7-1 Unimplemented: Read as '0'

bit 0

- IOLOCK: I/O Lock Enable bit
  - 1 = I/O lock is active, RPORx and RPINRx registers are write-protected 0 = I/O lock is not active, pin configurations can be changed

**Note 1:** Register values can only be changed if PPSCON<IOLOCK> = 0.

x = Bit is unknown

'0' = Bit is cleared

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
		—	INTR1R4	INTR1R3	INTR1R2	INTR1R1	INTR1R0
bit 7 bit 0							
Legend:		$R/\overline{W}$ = Readable, Writable if IOLOCK = 0					
R = Readable b	bit	W = Writable bit U = Unimplemented bit, read as '0'					

#### REGISTER 9-6: **RPINR1: PERIPHERAL PIN SELECT INPUT REGISTER 1 (BANKED EE7h)**

bit 7-5 Unimplemented: Read as '0'

-n = Value at POR

INTR1R<4:0>: Assign External Interrupt 1 (INT1) to the Corresponding RPn Pin bits bit 4-0

'1' = Bit is set

#### **REGISTER 9-7: RPINR2: PERIPHERAL PIN SELECT INPUT REGISTER 2 (BANKED EE8h)**

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	INTR2R4	INTR2R3	INTR2R2	INTR2R1	INTR2R0
bit 7							bit 0

Legend:	R/W = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 INTR2R<4:0>: Assign External Interrupt 2 (INT2) to the Corresponding RPn Pin bits

#### **REGISTER 9-8: RPINR3: PERIPHERAL PIN SELECT INPUT REGISTER 3 (BANKED EE9h)**

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	INTR3R4	INTR3R3	INTR3R2	INTR3R1	INTR3R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 INTR3R<4:0>: Assign External Interrupt 3 (INT3) to the Corresponding RPn Pin bits

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	T0CKR4	T0CKR3	T0CKR2	T0CKR1	T0CKR0
bit 7							bit 0
Legend: R/W = Readable, Writable if IOLOCK = 0							

### REGISTER 9-9: RPINR4: PERIPHERAL PIN SELECT INPUT REGISTER 4 (BANKED EEAh)

Legend:	R/W = Readable, Writa	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit,	, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 TOCKR<4:0>: Timer0 External Clock Input (TOCKI) to the Corresponding RPn Pin bits

## REGISTER 9-10: RPINR6: PERIPHERAL PIN SELECT INPUT REGISTER 6 (BANKED EECh)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	T3CKR4	T3CKR3	T3CKR2	T3CKR1	T3CKR0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable	R/W = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit U = Unimplemented bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 T3CKR<4:0>: Timer 3 External Clock Input (T3CKI) to the Corresponding RPn Pin bits

## REGISTER 9-11: RPINR7: PERIPHERAL PIN SELECT INPUT REGISTER 7 (BANKED EEDh)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	IC1R4	IC1R3	IC1R2	IC1R1	IC1R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 IC1R<4:0>: Assign Input Capture 1 (ECCP1) to the Corresponding RPn Pin bits

### REGISTER 9-12: RPINR8: PERIPHERAL PIN SELECT INPUT REGISTER 8 (BANKED EEEh)

-         -         IC2R4         IC2R3         IC2R2         IC2R1         IC2R0           bit 7             bit 0	U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
bit 7 bit 0	—	—	—	IC2R4	IC2R3	IC2R2	IC2R1	IC2R0
	bit 7							bit 0

Legend:	R/W = Readable, Writa	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	W = Writable bit U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'1' = Bit is set '0' = Bit is cleared x = Bit is unknown				

bit 7-5 Unimplemented: Read as '0'

bit 4-0 IC2R<4:0>: Assign Input Capture 2 (ECCP2) to the Corresponding RPn Pin bits

### REGISTER 9-13: RPINR12: PERIPHERAL PIN SELECT INPUT REGISTER 12 (BANKED EF2h)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	T1GR4	T1GR3	T1GR2	T1GR1	T1GR0
bit 7							bit 0

Legend:	R/W = Readable, Writable i	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit U = Unimplemented bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'1' = Bit is set '0' = Bit is cleared x = Bit is unknown				

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **T1GR<4:0>:** Timer1 Gate Input (T1G) to the Corresponding RPn Pin bits

#### REGISTER 9-14: RPINR13: PERIPHERAL PIN SELECT INPUT REGISTER 13 (BANKED EF3h)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	T3GR4	T3GR3	T3GR2	T3GR1	T3GR0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0					
R = Readable bit	W = Writable bit U = Unimplemented bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'1' = Bit is set '0' = Bit is cleared x = Bit is unknown				

bit 7-5 Unimplemented: Read as '0'

bit 4-0 T3GR<4:0>: Timer3 Gate Input (T3G) to the Corresponding RPn Pin bits

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	
—	—	—	RX2DT2R4	RX2DT2R3	RX2DT2R2	RX2DT2R1	RX2DT2R0	
bit 7		bi						
Legend:		R/W = Reada	ble, Writable if	FIOLOCK = 0				
R = Readable bi	t	W = Writable	/ = Writable bit		U = Unimplemented bit, read as '0'			
-n = Value at PC	R	'1' = Bit is set		0' = Bit is cleared x = Bit is unknown			nown	

#### REGISTER 9-15: RPINR16: PERIPHERAL PIN SELECT INPUT REGISTER 16 (BANKED EF6h)

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RX2DT2R<4:0>:** EUSART2 Synchronous/Asynchronous Receive (RX2/DT2) to the Corresponding RPn Pin bits

## REGISTER 9-16: RPINR17: PERIPHERAL PIN SELECT INPUT REGISTER 17 (BANKED EF7h)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	CK2R4	CK2R3	CK2R2	CK2R1	CK2R0
bit 7							bit 0

Legend:	R/W = Readable, Writ	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0			
R = Readable bit	W = Writable bit	U = Unimplemented bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 CK2R<4:0>: EUSART2 Clock Input (CK2) to the Corresponding RPn Pin bits

#### REGISTER 9-17: RPINR21: PERIPHERAL PIN SELECT INPUT REGISTER 21 (BANKED EFBh)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	SDI2R4	SDI2R3	SDI2R2	SDI2R1	SDI2R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

bit 7-5 Unimplemented: Read as '0'

bit 4-0 SDI2R<4:0>: Assign SPI2 Data Input (SDI2) to the Corresponding RPn Pin bits

## REGISTER 9-18: RPINR22: PERIPHERAL PIN SELECT INPUT REGISTER 22 (BANKED EFCh)

	R/W-1
hit 7	SCK2R0
bit 7	bit 0

Legend:	$R/\overline{W}$ = Readable, Writable	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 SCK2R<4:0>: Assign SPI2 Data Input (SDI2) to the Corresponding RPn Pin bits

#### REGISTER 9-19: RPINR23: PERIPHERAL PIN SELECT INPUT REGISTER 23 (BANKED EFDh)

U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
—	—	—	SS2R4	SS2R3	SS2R2	SS2R1	SS2R0
bit 7							bit 0

Legend:	R/W = Readable, Writable	R/W = Readable, Writable if IOLOCK = 0			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 SS2R<4:0>: Assign SPI2 Slave Select Input (SS2IN) to the Corresponding RPn Pin bits

## REGISTER 9-20: RPINR24: PERIPHERAL PIN SELECT INPUT REGISTER 24 (BANKED EFEh)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	OCFAR4	OCFAR3	OCFAR2	OCFAR1	OCFAR0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

bit 7-5 Unimplemented: Read as '0'

bit 4-0 OCFAR<4:0>: Assign PWM Fault Input (FLT0) to the Corresponding RPn Pin bits

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP0R4	RP0R3	RP0R2	RP0R1	RP0R0
bit 7							bit 0
Legend: $R/W$ = Readable. Writable if IOLOCK = 0							

Legena:	R/W = Readable, Willable II IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP0R<4:0>:** Peripheral Output Function is Assigned to RP0 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-22: RPOR1: PERIPHERAL PIN SELECT OUTPUT REGISTER 1 (BANKED EC7h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—		RP1R4	RP1R3	RP1R2	RP1R1	RP1R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP1R<4:0>:** Peripheral Output Function is Assigned to RP1 Output Pin bits (see Table 9-14 for peripheral function numbers)

### REGISTER 9-23: RPOR2: PERIPHERAL PIN SELECT OUTPUT REGISTER 2 (BANKED EC8h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	—	—	RP2R4	RP2R3	RP2R2	RP2R1	RP2R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP2R<4:0>:** Peripheral Output Function is Assigned to RP2 Output Pin bits (see Table 9-14 for peripheral function numbers)

x = Bit is unknown

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—		—	RP3R4	RP3R3	RP3R2	RP3R1	RP3R0
bit 7							bit 0
Legend: R/W = Readable, Writable if IOLOCK = 0							
R = Readable b	bit	W = Writable bit U = Unimplemented bit, read as '0'					

'0' = Bit is cleared

#### REGISTER 9-24: RPOR3: PERIPHERAL PIN SELECT OUTPUT REGISTER 3 (BANKED EC9h)

bit 7-5 Unimplemented: Read as '0'

-n = Value at POR

bit 4-0 **RP3R<4:0>:** Peripheral Output Function is Assigned to RP3 Output Pin bits (see Table 9-14 for peripheral function numbers)

'1' = Bit is set

#### REGISTER 9-25: RPOR4: PERIPHERAL PIN SELECT OUTPUT REGISTER 4 (BANKED ECAh)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—		RP4R4	RP4R3	RP4R2	RP4R1	RP4R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP4R<4:0>:** Peripheral Output Function is Assigned to RP4 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-26: RPOR5: PERIPHERAL PIN SELECT OUTPUT REGISTER 5 (BANKED ECBh)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP5R4	RP5R3	RP5R2	RP5R1	RP5R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP5R<4:0>:** Peripheral Output Function is Assigned to RP5 Output Pin bits (see Table 9-14 for peripheral function numbers)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP6R4	RP6R3	RP6R2	RP6R1	RP6R0
bit 7							bit 0

Legend:	R/W = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP6R<4:0>:** Peripheral Output Function is Assigned to RP6 Output Pin bits (see Table 9-14 for peripheral function numbers)

## REGISTER 9-28: RPOR7: PERIPHERAL PIN SELECT OUTPUT REGISTER 7 (BANKED ECDh)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—		RP7R4	RP7R3	RP7R2	RP7R1	RP7R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set '0' = Bit is cleared x = Bit is unknown				

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP7R<4:0>:** Peripheral Output Function is Assigned to RP7 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-29: RPOR8: PERIPHERAL PIN SELECT OUTPUT REGISTER 8 (BANKED ECEh)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—		—	RP8R4	RP8R3	RP8R2	RP8R1	RP8R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0			
R = Readable bit	W = Writable bit	/ = Writable bit U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP8R<4:0>:** Peripheral Output Function is Assigned to RP8 Output Pin bits (see Table 9-14 for peripheral function numbers)

## REGISTER 9-30: RPOR9: PERIPHERAL PIN SELECT OUTPUT REGISTER 9 (BANKED ECFh)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP9R4	RP9R3	RP9R2	RP9R1	RP9R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable	R/W = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit U = Unimplemented bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x = Bit is unknown				

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP9R<4:0>:** Peripheral Output Function is Assigned to RP9 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-31: RPOR10: PERIPHERAL PIN SELECT OUTPUT REGISTER 10 (BANKED ED0h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—		RP10R4	RP10R3	RP10R2	RP10R1	RP10R0
bit 7							bit 0

Legend:	R/W = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP10R<4:0>:** Peripheral Output Function is Assigned to RP10 Output Pin bits (see Table 9-14 for peripheral function numbers)

## REGISTER 9-32: RPOR11: PERIPHERAL PIN SELECT OUTPUT REGISTER 11 (BANKED ED1h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP11R4	RP11R3	RP11R2	RP11R1	RP11R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	/ = Writable bit U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP11R<4:0>:** Peripheral Output Function is Assigned to RP11 Output Pin bits (see Table 9-14 for peripheral function numbers)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	_	RP12R4	RP12R3	RP12R2	RP12R1	RP12R0
bit 7							bit 0
_							
Legend:		R/W = Reada	ble, Writable i	f IOLOCK = 0			
R = Readable I	bit	W = Writable	bit	U = Unimpler	mented bit, read	as '0'	

'0' = Bit is cleared

x = Bit is unknown

#### REGISTER 9-33: RPOR12: PERIPHERAL PIN SELECT OUTPUT REGISTER 12 (BANKED ED2h)

bit 7-5 Unimplemented: Read as '0'

-n = Value at POR

bit 4-0 **RP12R<4:0>:** Peripheral Output Function is Assigned to RP12 Output Pin bits (see Table 9-14 for peripheral function numbers)

'1' = Bit is set

## REGISTER 9-34: RPOR13: PERIPHERAL PIN SELECT OUTPUT REGISTER 13 (BANKED ED3h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—		RP13R4	RP13R3	RP13R2	RP13R1	RP13R0
bit 7							bit 0

Legend:	R/W = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP13R<4:0>:** Peripheral Output Function is Assigned to RP13 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-35: RPOR17: PERIPHERAL PIN SELECT OUTPUT REGISTER 17 (BANKED ED7h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	_	RP17R4	RP17R3	RP17R2	RP17R1	RP17R0
bit 7							bit 0

Legend:	R/W = Readable, Wri	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP17R<4:0>:** Peripheral Output Function is Assigned to RP17 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-36: RPOR18: PERIPHERAL PIN SELECT OUTPUT REGISTER 18 (BANKED ED8h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP18R4	RP18R3	RP18R2	RP18R1	RP18R0
bit 7							bit 0

Legend:	R/W = Readable, Writable if IOLOCK = 0					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP18R<4:0>:** Peripheral Output Function is Assigned to RP18 Output Pin bits (see Table 9-14 for peripheral function numbers)

#### REGISTER 9-37: RPOR19: PERIPHERAL PIN SELECT OUTPUT REGISTER 19 (BANKED ED9h)<sup>(1)</sup>

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP19R4	RP19R3	RP19R2	RP19R1	RP19R0
bit 7							bit 0

Legend:	R/W = Readable, Writable if IOLOCK = 0					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP19R<4:0>:** Peripheral Output Function is Assigned to RP19 Output Pin bits (see Table 9-14 for peripheral function numbers)

Note 1: RP19 pins are not available on 28-pin devices.

## REGISTER 9-38: RPOR20: PERIPHERAL PIN SELECT OUTPUT REGISTER 20 (BANKED EDAh)<sup>(1)</sup>

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP20R4	RP20R3	RP20R2	RP20R1	RP20R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP20R<4:0>:** Peripheral Output Function is Assigned to RP20 Output Pin bits (see Table 9-14 for peripheral function numbers)

Note 1: RP20 pins are not available on 28-pin devices.

Legend: R/W = Readable, Writable if IOLOCK = 0									
bit 7							bit 0		
—	—	—	RP21R4	RP21R3	RP21R2	RP21R1	RP21R0		
U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		

U = Unimplemented bit, read as '0'

'0' = Bit is cleared

x = Bit is unknown

## REGISTER 9-39: RPOR21: PERIPHERAL PIN SELECT OUTPUT REGISTER 21 (BANKED EDBh)<sup>(1)</sup>

bit 7-5 Unimplemented: Read as '0'

R = Readable bit

-n = Value at POR

bit 4-0 **RP21R<4:0>:** Peripheral Output Function is Assigned to RP21 Output Pin bits (see Table 9-14 for peripheral function numbers)

W = Writable bit

'1' = Bit is set

**Note 1:** RP21 pins are not available on 28-pin devices.

## REGISTER 9-40: RPOR22: PERIPHERAL PIN SELECT OUTPUT REGISTER 22 (BANKED EDCh)<sup>(1)</sup>

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	—	—	RP22R4	RP22R3	RP22R2	RP22R1	RP22R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP22R<4:0>:** Peripheral Output Function is Assigned to RP22 Output Pin bits (see Table 9-14 for peripheral function numbers)

Note 1: RP22 pins are not available on 28-pin devices.

## REGISTER 9-41: RPOR23: PERIPHERAL PIN SELECT OUTPUT REGISTER 23 (BANKED EDDh)<sup>(1)</sup>

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	—	—	RP23R4	RP23R3	RP23R2	RP23R1	RP23R0
bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable i	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP23R<4:0>:** Peripheral Output Function is Assigned to RP23 Output Pin bits (see Table 9-14 for peripheral function numbers)

Note 1: RP23 pins are not available on 28-pin devices.

## REGISTER 9-42: RPOR24: PERIPHERAL PIN SELECT OUTPUT REGISTER 24 (BANKED EDEh)<sup>(1)</sup>

—         —         RP24R4         RP24R3         RP24R2         RP24R1         RP24R0           bit 7	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
bit 7 bit 0	—	_		RP24R4	RP24R3	RP24R2	RP24R1	RP24R0
	bit 7							bit 0

Legend:	$R/\overline{W}$ = Readable, Writable if IOLOCK = 0				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7-5 Unimplemented: Read as '0'

bit 4-0 **RP24R<4:0>:** Peripheral Output Function is Assigned to RP24 Output Pin bits (see Table 9-14 for peripheral function numbers)

Note 1: RP24 pins are not available on 28-pin devices.


## PIC18F46J50 FAMILY

NOTES:

## 10.0 PARALLEL MASTER PORT (PMP)

The Parallel Master Port module (PMP) is an 8-bit parallel I/O module, specifically designed to communicate with a wide variety of parallel devices, such as communication peripherals, LCDs, external memory devices and microcontrollers. Because the interface to parallel peripherals varies significantly, the PMP is highly configurable. The PMP module can be configured to serve as either a PMP or as a Parallel Slave Port (PSP). Key features of the PMP module are:

- Up to 16 bits of addressing when using data/address multiplexing
- Up to 8 Programmable Address Lines
- One Chip Select Line
- Programmable Strobe Options:
  - Individual Read and Write Strobes or;
    Read/Write Strobe with Enable Strobe
- Address Auto-Increment/Auto-Decrement
- Programmable Address/Data Multiplexing
- Programmable Polarity on Control Signals
- Legacy Parallel Slave Port Support
- Enhanced Parallel Slave Support:
  - Address Support
  - 4-Byte Deep, Auto-Incrementing Buffer
- Programmable Wait States
- · Selectable Input Voltage Levels



## FIGURE 10-1: PMP MODULE OVERVIEW

## 10.1 Module Registers

The PMP module has a total of 14 Special Function Registers (SFRs) for its operation, plus one additional register to set configuration options. Of these, eight registers are used for control and six are used for PMP data transfer.

### 10.1.1 CONTROL REGISTERS

The eight PMP Control registers are:

- PMCONH and PMCONL
- PMMODEH and PMMODEL
- PMSTATL and PMSTATH
- PMEH and PMEL

The PMCON registers (Register 10-1 and Register 10-2) control basic module operations, including turning the module on or off. They also configure address multiplexing and control strobe configuration.

The PMMODE registers (Register 10-3 and Register 10-4) configure the various Master and Slave modes, the data width and interrupt generation.

The PMEH and PMEL registers (Register 10-5 and Register 10-6) configure the module's operation at the hardware (I/O pin) level.

The PMSTAT registers (Register 10-5 and Register 10-6) provide status flags for the module's input and output buffers, depending on the operating mode.

## REGISTER 10-1: PMCONH: PARALLEL PORT CONTROL REGISTER HIGH BYTE (BANKED F5Fh)<sup>(1)</sup>

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
PMPEN	—	PSIDL	ADRMUX1	ADRMUX0	PTBEEN	PTWREN	PTRDEN
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	PMPEN: Parallel Master Port Enable bit
	1 = PMP enabled
	0 = PMP disabled, no off-chip access performed
bit 6	Unimplemented: Read as '0'
bit 5	PSIDL: Stop in Idle Mode bit
	<ul> <li>1 = Discontinue module operation when device enters Idle mode</li> <li>0 = Continue module operation in Idle mode</li> </ul>
bit 4-3	ADRMUX<1:0>: Address/Data Multiplexing Selection bits
	11 = Reserved
	10 = All 16 bits of address are multiplexed on PMD<7:0> pins
	01 = Lower 8 bits of address are multiplexed on PMD<7:0> pins (only eight bits of address are available in this mode)
	00 = Address and data appear on separate pins (only eight bits of address are available in this mode)
bit 2	PTBEEN: Byte Enable Port Enable bit (16-Bit Master mode)
	1 = PMBE port enabled
	0 = PMBE port disabled
bit 1	PTWREN: Write Enable Strobe Port Enable bit
	1 = PMWR/PMENB port enabled
	0 = PMWR/PMENB port disabled
bit 0	PTRDEN: Read/Write Strobe Port Enable bit
	1 = PMRD/PMWR port enabled
	0 = PMRD/PMWR port disabled
Note 1:	This register is only available in 44-pin devices.

## REGISTER 10-2: PMCONL: PARALLEL PORT CONTROL REGISTER LOW BYTE (BANKED F5Eh)<sup>(1)</sup>

R/W-0	R/W-0	R/W-0 <sup>(2)</sup>	U-0	R/W-0 <sup>(2)</sup>	R/W-0	R/W-0	R/W-0
CSF1	CSF0	ALP	—	CS1P	BEP	WRSP	RDSP
bit 7							bit 0

R = Reada	ble bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value	n = Value at POR '1' = Bit is set		'0' = Bit is cleared	x = Bit is unknown
bit 7-6	CSF<1:(	>: Chip Select Function bits		
	13 01 = Re	hip select function is enabled address bits only can be gen eserved	and PMCS acts as chip select nerated. (in Master mode). All 16 addro	
bit 5	<b>ALP:</b> Ad 1 = Acti	dress Latch Polarity bit <sup>(2)</sup> ve-high <u>(PMALL</u> and <u>PMALH</u> ve-low (PMALL and PMALH)	)	J. J
bit 4	Unimple	mented: Maintain as '0'		
bit 3	CS1P: Chip Select Polarity bit <sup>(2)</sup> 1 = Active-high (PMCS) 0 = Active-low (PMCS)			
bit 2	1 = Byte	te Enable Polarity bit e enable active-high (PMBE) e enable active-low (PMBE)		
bit 1	<u>For Slav</u> 1 = Writ 0 = Writ <u>For Mas</u> 1 = Ena	Write Strobe Polarity bit e modes and Master Mode 2 e strobe active-high (PMWR) e strobe active-low (PMWR) ter Mode 1 (PMMODEH<1:0> ble strobe active-high (PMEN ble strobe active-low (PMEN	<u>&gt; = 11):</u> IB)	<u>10):</u>
bit 0	<b>RDSP:</b> F <u>For Slav</u> 1 = Rea 0 = Rea <u>For Mas</u> 1 = Rea	Read Strobe Polarity bit	<u>(PMMODEH&lt;1:0&gt; = 00,01,3</u> > <u>= 11):</u> MRD/PMWR)	<u>10):</u>

- **Note 1:** This register is only available in 44-pin devices.
  - 2: These bits have no effect when their corresponding pins are used as address lines.

R-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
BUSY	IRQM1	IRQM0	INCM1	INCM0	MODE16	MODE1	MODE0
bit 7							bit
Legend:							
R = Readal	ble bit	W = Writable	bit	U = Unimpler	mented bit, read	l as '0'	
-n = Value a	at POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown
bit 7	<b>BUSY:</b> Busy 1 = Port is b 0 = Port is n		le only)				
bit 6-5	11 = Interru or on 10 = No int 01 = Interru	Interrupt Reque upt generated wh a read or write o errupt generated upt generated at errupt generated	nen Read Buff peration when d, processor st the end of the	PMA<1:0> = 1 all activated	11 (Addressable		
bit 4-3	11 = PSP re 10 = Decren 01 = Increm	Increment Mod ad and write but nent ADDR<15, ent ADDR<15,1 rement or decrer	fers auto-incre 13:0> by 1 eve 3:0> by 1 ever	ry read/write cy y read/write cy	ycle	()	
bit 2	1 = 16-bit m	/16-Bit Mode bit node: Data regist ode: Data registe					
bit 1-0	MODE<1:0>	•: Parallel Port M Mode 1 (PMCS	lode Select bit , PMRD/PMW	s R, PMENB, PM	/IBE, PMA <x:0></x:0>	and PMD<7:0	

## REGISTER 10-3: PMMODEH: PARALLEL PORT MODE REGISTER HIGH BYTE (BANKED F5Dh)<sup>(1)</sup>

							-		
R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
WAITB1 <sup>(2)</sup>	WAITB0 <sup>(2)</sup>	WAITM3	WAITM2	WAITM1	WAITM0	WAITE1 <sup>(2)</sup>	WAITE0 <sup>(2)</sup>		
bit 7	·						bit		
Legend:									
R = Readab	ole bit	W = Writable	bit	U = Unimplem	nented bit, read	d as '0'			
-n = Value a	it POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkr	nown		
					(0)				
bit 7-6	WAITB<1:0>	: Data Setup to	Read/Write W	ait State Config	juration bits <sup>(2)</sup>				
		,	•	ss phase of 4 T					
		<ul> <li>Data wait of 3 TCY; multiplexed address phase of 3 TCY</li> <li>Data wait of 2 TCY; multiplexed address phase of 2 TCY</li> </ul>							
			•	ss phase of 2 10					
bit 5-2		2	1						
DIL 3-2		of additional 15		Wait State Cor	ingulation bits				
			ICY						
		of additional 1	• • •						
				n forced into or					
bit 1-0	WAITE<1:0>:	: Data Hold Afte	er Strobe Wait	State Configura	ation bits <sup>(2)</sup>				
	11 = Wait of 4	4 TCY							
	10 = Wait of 3								
	01 = Wait of 2								
	00 = Wait of 1								
Note 1. T	his register is or	nlv available in .	44-nin devices						

## REGISTER 10-4: PMMODEL: PARALLEL PORT MODE REGISTER LOW BYTE (BANKED F5Ch)<sup>(1)</sup>

**Note 1:** This register is only available in 44-pin devices.

2: WAITBx and WAITEx bits are ignored whenever WAITM<3:0> = 0000.

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
PTEN15 PTEN14		PTEN13	PTEN12	PTEN11	PTEN10	PTEN9	PTEN8		
bit 7							bit 0		
Legend:									
R = Readable	e bit	W = Writable	bit	U = Unimplemented bit, read as '0'					
-n = Value at POR '1' = Bit is set			'0' = Bit is cleared x = Bit is unknown			nown			
bit 7-6	1 = PMA<15	>: PMCS1 Port :14> function a: :14> function a:	s either PMA<	15:14> or PMC	S2 and PMCS1	I			
bit 5-0	<b>PTEN&lt;13:8&gt;:</b> PMP Address Port Enable bits 1 = PMA<13:8> function as PMP address lines								

## REGISTER 10-5: PMEH: PARALLEL PORT ENABLE REGISTER HIGH BYTE (BANKED F57h)<sup>(1)</sup>

**Note 1:** This register is only available in 44-pin devices.

0 = PMA<13:8> function as port I/O

## REGISTER 10-6: PMEL: PARALLEL PORT ENABLE REGISTER LOW BYTE (BANKED F56h)<sup>(1)</sup>

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| PTEN7 | PTEN6 | PTEN5 | PTEN4 | PTEN3 | PTEN2 | PTEN1 | PTEN0 |
| bit 7 |       |       |       |       |       |       | bit 0 |

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-2	PTEN<7:2>: PMP Address Port Enable bits
	1 = PMA<7:2> function as PMP address lines
	0 = PMA<7:2> function as port I/O
bit 1-0	PTEN<1:0>: PMALH/PMALL Strobe Enable bits
	1 = PMA<1:0> function as either PMA<1:0> or PMALH and PMALL
	0 = PMA<1:0> pads functions as port I/O

Note 1: This register is only available in 44-pin devices.

## REGISTER 10-7: PMSTATH: PARALLEL PORT STATUS REGISTER HIGH BYTE (BANKED F55h)<sup>(1)</sup>

R-0	R/W-0	U-0	U-0	R-0	R-0	R-0	R-0
IBF	IBOV		_	IB3F	IB2F	IB1F	IB0F
oit 7							bit
Legend:							
R = Readable	bit	W = Writable b	bit	U = Unimplem	nented bit, read	l as '0'	
-n = Value at F	POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkr	nown
	1 = All writab	ffer Full Status I le input buffer r all of the writab	egisters are fu		mpty		
bit 6		Buffer Overflow B ttempt to a full in ow occurred		ster occurred (n	nust be cleared	I in software)	
bit 5-4	Unimplemen	ted: Read as '0	,				
bit 3-0	IB3F:IB0F: In	put Buffer x Sta	itus Full bits				
	•	fer contains dat fer does not cor		•	ding buffer will	clear this bit)	

Note 1: This register is only available in 44-pin devices.

## REGISTER 10-8: PMSTATL: PARALLEL PORT STATUS REGISTER LOW BYTE (BANKED F54h)<sup>(1)</sup>

R-1	R/W-0	U-0	U-0	R-1	R-1	R-1	R-1
OBE	OBUF	—	—	OB3E	OB2E	OB1E	OB0E
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	OBE: Output Buffer Empty Status bit
	1 = All readable output buffer registers are empty
	0 = Some or all of the readable output buffer registers are full
bit 6	OBUF: Output Buffer Underflow Status bit
	<ul> <li>1 = A read occurred from an empty output byte register (must be cleared in software)</li> <li>0 = No underflow occurred</li> </ul>
bit 5-4	Unimplemented: Read as '0'
bit 3-0	OB3E:OB0E: Output Buffer x Status Empty bits
	1 = Output buffer is empty (writing data to the buffer will clear this bit)
	0 = Output buffer contains data that has not been transmitted

Note 1: This register is only available in 44-pin devices.

## 10.1.2 DATA REGISTERS

The PMP module uses eight registers for transferring data into and out of the microcontroller. They are arranged as four pairs to allow the option of 16-bit data operations:

- PMDIN1H and PMDIN1L
- PMDIN2H and PMDIN2L
- PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L
- PMDOUT2H and PMDOUT2L

The PMDIN1 register is used for incoming data in Slave modes, and both input and output data in Master modes. The PMDIN2 register is used for buffering input data in select Slave modes.

The PMADDR/PMDOUT1 registers are actually a single register pair; the name and function are dictated by the module's operating mode. In Master modes, the registers function as the PMADDRH and PMADDRL registers and contain the address of any incoming or outgoing data. In Slave modes, the registers function as PMDOUT1H and PMDOUT1L and are used for outgoing data.

PMADDRH differs from PMADDRL in that it can also have limited PMP control functions. When the module is operating in select Master mode configurations, the upper two bits of the register can be used to determine the operation of chip select signals. If these are not used, PMADDR simply functions to hold the upper 8 bits of the address. Register 10-9 provides the function of the individual bits in PMADDRH.

The PMDOUT2H and PMDOUT2L registers are only used in Buffered Slave modes and serve as a buffer for outgoing data.

#### 10.1.3 PAD CONFIGURATION CONTROL REGISTER

In addition to the module level configuration options, the PMP module can also be configured at the I/O pin for electrical operation. This option allows users to select either the normal Schmitt Trigger input buffer on digital I/O pins shared with the PMP, or use TTL level compatible buffers instead. Buffer configuration is controlled by the PMPTTL bit in the PADCFG1 register.

## REGISTER 10-9: PMADDRH: PARALLEL PORT ADDRESS REGISTER HIGH BYTE (MASTER MODES ONLY) (ACCESS F6Fh)<sup>(1)</sup>

U0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	CS1		Parallel	I Master Port Add	ress High Byt	te<13:8>	
bit 7	•						bit 0
Legend:							
R = Readable	bit	W = Writable bit		U = Unimpleme	nted bit, read	las '0' r = Re	eserved
-n = Value at I	POR	'1' = Bit is set		'0' = Bit is cleare	ed	x = Bit is unkr	nown
bit 7	Unimplemer	nted: Read as '0'					
bit 6	CS1: Chip Se	elect bit					
	If PMCON<7	:6> = 10:					
	1 = Chip sele	ect is active					
	0 = Chip sele	ect is inactive					
	If PMCON<7	:6> = 11 or 00:					
	Bit functions	as ADDR<14>.					
bit 5-0	Parallel Mas	ter Port Address	: High Byte	<13:8> bits			

Note 1: In Enhanced Slave mode, PMADDRH functions as PMDOUT1H, one of the Output Data Buffer registers.

## REGISTER 10-10: PMADDRL: PARALLEL PORT ADDRESS REGISTER LOW BYTE (MASTER MODES ONLY) (ACCESS F6Eh)<sup>(1)</sup>

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
		Parallel N	Master Port A	Address Low Byte	<7:0>		
bit 7							bit 0
Legend:							
R = Readable b	bit	W = Writable bi	t	U = Unimplemer	nted bit, read	las'0'r=F	Reserved
-n = Value at P	OR	'1' = Bit is set		'0' = Bit is cleare	ed	x = Bit is un	known

bit 7-0 Parallel Master Port Address: Low Byte<7:0> bits

**Note 1:** In Enhanced Slave mode, PMADDRL functions as PMDOUT1L, one of the Output Data Buffer registers.

## 10.2 Slave Port Modes

The primary mode of operation for the module is configured using the MODE<1:0> bits in the PMMODEH register. The setting affects whether the module acts as a slave or a master, and it determines the usage of the control pins.


## 10.2.1 LEGACY MODE (PSP)

In Legacy mode (PMMODEH<1:0> = 00 and PMPEN = 1), the module is configured as a Parallel Slave Port (PSP) with the associated enabled module

pins dedicated to the module. In this mode, an external device, such as another microcontroller or microprocessor, can asynchronously read and write data using the 8-bit data bus (PMD<7:0>), the read (PMRD), write (PMWR) and chip select (PMCS1) inputs. It acts as a slave on the bus and responds to the read/write control signals.

Figure 10-2 displays the connection of the PSP. When chip select is active and a write strobe occurs (PMCS = 1 and PMWR = 1), the data from PMD<7:0> is captured into the PMDIN1L register.

## FIGURE 10-2: LEGACY PARALLEL SLAVE PORT EXAMPLE




## 10.2.2 WRITE TO SLAVE PORT

When chip select is active and a write strobe occurs (PMCS = 1 and PMWR = 1), the data from PMD<7:0> is captured into the lower PMDIN1L register. The PMPIF and IBF flag bits are set when the write ends. The timing for the control signals in Write mode is displayed in Figure 10-3. The polarity of the control signals are configurable.


## 10.2.3 READ FROM SLAVE PORT

When chip select is active and a read strobe occurs (PMCS = 1 and PMRD = 1), the data from the PMDOUT1L register (PMDOUT1L<7:0>) is presented onto PMD<7:0>. Figure 10-4 provides the timing for the control signals in Read mode.









### 10.2.4 BUFFERED PARALLEL SLAVE PORT MODE

Buffered Parallel Slave Port mode is functionally identical to the legacy PSP mode with one exception, the implementation of 4-level read and write buffers. Buffered PSP mode is enabled by setting the INCM bits in the PMMODEH register. If the INCM<1:0> bits are set to '11', the PMP module will act as the Buffered PSP.

When the Buffered mode is active, the PMDIN1L, PMDIN1H, PMDIN2L and PMDIN2H registers become the write buffers and the PMDOUT1L, PMDOUT1H, PMDOUT2L and PMDOUT2H registers become the read buffers. Buffers are numbered 0 through 3, starting with the lower byte of PMDIN1L to PMDIN2H as the read buffers and PMDOUT1L to PMDOUT2H as the write buffers.

## 10.2.4.1 READ FROM SLAVE PORT

For read operations, the bytes will be sent out sequentially, starting with Buffer 0 (PMDOUT1L<7:0>) and ending with Buffer 3 (PMDOUT2H<7:0>) for every read strobe. The module maintains an internal pointer to keep track of which buffer is to be read. Each buffer has a corresponding read status bit, OBxE, in the PMSTATL register. This bit is cleared when a buffer contains data that has not been written to the bus, and is set when data is written to the bus. If the current buffer location being read from is empty, a buffer underflow is generated, and the Buffer Overflow flag bit OBUF is set. If all four OBxE status bits are set, then the Output Buffer Empty flag (OBE) will also be set.


## 10.2.4.2 WRITE TO SLAVE PORT

For write operations, the data has to be stored sequentially, starting with Buffer 0 (PMDIN1L<7:0>) and ending with Buffer 3 (PMDIN2H<7:0>). As with read operations, the module maintains an internal pointer to the buffer that is to be written next.

The input buffers have their own write status bits, IBxF in the PMSTATH register. The bit is set when the buffer contains unread incoming data, and cleared when the data has been read. The flag bit is set on the write strobe. If a write occurs on a buffer when its associated IBxF bit is set, the Buffer Overflow flag, IBOV, is set; any incoming data in the buffer will be lost. If all four IBxF flags are set, the Input Buffer Full Flag (IBF) is set.

In Buffered Slave mode, the module can be configured to generate an interrupt on every read or write strobe (IRQM<1:0> = 01). It can be configured to generate an interrupt on a read from Read Buffer 3 or a write to Write Buffer 3, which is essentially an interrupt every fourth read or write strobe (RQM<1:0> = 11). When interrupting every fourth byte for input data, all input buffer registers should be read to clear the IBxF flags. If these flags are not cleared, then there is a risk of hitting an overflow condition.

## FIGURE 10-5: PARALLEL MASTER/SLAVE CONNECTION BUFFERED EXAMPLE




## 10.2.5 ADDRESSABLE PARALLEL SLAVE PORT MODE

In the Addressable Parallel Slave Port mode (PMMODEH<1:0> = 01), the module is configured with two extra inputs, PMA<1:0>, which are the address lines 1 and 0. This makes the 4-byte buffer space directly addressable as fixed pairs of read and write buffers. As with Legacy Buffered mode, data is output from PMDOUT1L, PMDOUT1H, PMDOUT2L and PMDOUT2H, and is read in PMDIN1L, PMDIN1H, PMDIN2L and PMDIN2L and PMDIN2L. Table 10-1 provides the buffer addressing for the incoming address to the input and output registers.

## TABLE 10-1: SLAVE MODE BUFFER ADDRESSING

PMA<1:0>	Output Register (Buffer)	Input Register (Buffer)
00	PMDOUT1L (0)	PMDIN1L (0)
01	PMDOUT1H (1)	PMDIN1H (1)
10	PMDOUT2L (2)	PMDIN2L (2)
11	PMDOUT2H((3)	PMDIN2H (3)


#### FIGURE 10-6: PARALLEL MASTER/SLAVE CONNECTION ADDRESSED BUFFER EXAMPLE



## 10.2.5.1 READ FROM SLAVE PORT

When chip select is active and a read strobe occurs (PMCS = 1 and PMRD = 1), the data from one of the four output bytes is presented onto PMD<7:0>. Which byte is read depends on the 2-bit address placed on ADDR<1:0>. Table 10-1 provides the corresponding

output registers and their associated address. When an output buffer is read, the corresponding OBxE bit is set. The OBxE flag bit is set when all the buffers are empty. If any buffer is already empty, OBxE = 1, the next read to that buffer will generate an OBUF event.




## FIGURE 10-7: PARALLEL SLAVE PORT READ WAVEFORMS

## 10.2.5.2 WRITE TO SLAVE PORT

When chip select is active and a write strobe occurs (PMCS = 1 and PMWR = 1), the data from PMD<7:0> is captured into one of the four input buffer bytes. Which byte is written depends on the 2-bit address placed on ADDRL<1:0>.

Table 10-1 provides the corresponding input registers and their associated address.

When an input buffer is written, the corresponding IBxF bit is set. The IBF flag bit is set when all the buffers are written. If any buffer is already written (IBxF = 1), the next write strobe to that buffer will generate an OBUF event and the byte will be discarded.



### FIGURE 10-8: PARALLEL SLAVE PORT WRITE WAVEFORMS

## 10.3 MASTER PORT MODES

In its Master modes, the PMP module provides an 8-bit data bus, up to 16 bits of address, and all the necessary control signals to operate a variety of external parallel devices, such as memory devices, peripherals and slave microcontrollers. To use the PMP as a master, the module must be enabled (PMPEN = 1) and the mode must be set to one of the two possible Master modes (PMMODEH<1:0> = 10 or 11).

Because there are a number of parallel devices with a variety of control methods, the PMP module is designed to be extremely flexible to accommodate a range of configurations. Some of these features include:

- · 8-Bit and 16-Bit Data modes on an 8-bit data bus
- · Configurable address/data multiplexing
- · Up to two chip select lines
- Up to 16 selectable address lines
- · Address auto-increment and auto-decrement
- · Selectable polarity on all control lines
- Configurable Wait states at different stages of the read/write cycle

## 10.3.1 PMP AND I/O PIN CONTROL

Multiple control bits are used to configure the presence or absence of control and address signals in the module. These bits are PTBEEN, PTWREN, PTRDEN and PTEN<15:0>. They give the user the ability to conserve pins for other functions and allow flexibility to control the external address. When any one of these bits is set, the associated function is present on its associated pin; when clear, the associated pin reverts to its defined I/O port function.

Setting a PTENx bit will enable the associated pin as an address pin and drive the corresponding data contained in the PMADDR register. Clearing a PTENx bit will force the pin to revert to its original I/O function.

For the pins configured as chip select (PMCS1 or PMCS2) with the corresponding PTENx bit set, the PTEN0 and PTEN1 bits will also control the PMALL and PMALH signals. When multiplexing is used, the associated address latch signals should be enabled.

## 10.3.2 READ/WRITE CONTROL

The PMP module supports two distinct read/write signaling methods. In Master Mode 1, read and write strobes are combined into a single control line, PMRD/PMWR. A second control line, PMENB, determines when a read or write action is to be taken. In Master Mode 2, separate read and write strobes (PMRD and PMWR) are supplied on separate pins.

All control signals (PMRD, PMWR, PMBE, PMENB, PMAL and PMCSx) can be individually configured as either positive or negative polarity. Configuration is controlled by separate bits in the PMCONL register.

Note that the polarity of control signals that share the same output pin (for example, PMWR and PMENB) are controlled by the same bit; the configuration depends on which Master Port mode is being used.

## 10.3.3 DATA WIDTH

The PMP supports data widths of both 8 bits and 16 bits. The data width is selected by the MODE16 bit (PMMODEH<2>). Because the data path into and out of the module is only 8 bits wide, 16-bit operations are always handled in a multiplexed fashion, with the Least Significant Byte (LSB) of data being presented first. To differentiate data bytes, the byte enable control strobe, PMBE, is used to signal when the Most Significant Byte (MSB) of data is being presented on the data lines.

## 10.3.4 ADDRESS MULTIPLEXING

In either of the Master modes (PMMODEH<1:0> = 1x), the user can configure the address bus to be multiplexed together with the data bus. This is accomplished by using the ADRMUX<1:0> bits (PMCONH<4:3>). There are three address multiplexing modes available; typical pinout configurations for these modes are displayed in Figure 10-9, Figure 10-10 and Figure 10-11.


In Demultiplexed mode (PMCONH<4:3> = 00), data and address information are completely separated. Data bits are presented on PMD<7:0> and address bits are presented on PMADDRH<6:0> and PMADDRL<7:0>.

In Partially Multiplexed mode (PMCONH<4:3> = 01), the lower eight bits of the address are multiplexed with the data pins on PMD<7:0>. The upper eight bits of address are unaffected and are presented on PMADDRH<6:0>. The PMA0 pin is used as an address latch, and presents the Address Latch Low (PMALL) enable strobe. The read and write sequences are extended by a complete CPU cycle during which the address is presented on the PMD<7:0> pins.


In Fully Multiplexed mode (PMCONH<4:3> = 10), the entire 16 bits of the address are multiplexed with the data pins on PMD<7:0>. The PMA0 and PMA1 pins are used to present Address Latch Low (PMALL) enable and Address Latch High (PMALH) enable strobes, respectively. The read and write sequences are extended by two complete CPU cycles. During the first cycle, the lower eight bits of the address are presented on the PMD<7:0> pins with the PMALL strobe active. During the second cycle, the upper eight bits of the address are presented on the PMD<7:0> pins with the PMALH strobe active. In the event the upper address bits are configured as chip select pins, the corresponding address bits are automatically forced to '0'.

## PIC18F46J50 FAMILY


## FIGURE 10-9: DEMULTIPLEXED ADDRESSING MODE (SEPARATE READ AND WRITE STROBES WITH CHIP SELECT)



## FIGURE 10-10: PARTIALLY MULTIPLEXED ADDRESSING MODE (SEPARATE READ AND WRITE STROBES WITH CHIP SELECT)



## FIGURE 10-11: FULLY MULTIPLEXED ADDRESSING MODE (SEPARATE READ AND WRITE STROBES WITH CHIP SELECT)



## 10.3.5 CHIP SELECT FEATURES

Up to two chip select lines, PMCS1 and PMCS2, are available for the Master modes of the PMP. The two chip select lines are multiplexed with the Most Significant bit (MSb) of the address bus (PMADDRH<6>). When a pin is configured as a chip select, it is not included in any address auto-increment/decrement. The function of the chip select signals is configured using the chip select function bits (PMCONL<7:6>).

## 10.3.6 AUTO-INCREMENT/DECREMENT

While the module is operating in one of the Master modes, the INCMx bits (PMMODEH<4:3>) control the behavior of the address value. The address can be made to automatically increment or decrement after each read and write operation. The address increments once each operation is completed and the BUSY bit goes to '0'. If the chip select signals are disabled and configured as address bits, the bits will participate in the increment and decrement operations; otherwise, the CS1 bit values will be unaffected.

## 10.3.7 WAIT STATES

In Master mode, the user has control over the duration of the read, write and address cycles by configuring the module Wait states. Three portions of the cycle, the beginning, middle and end, are configured using the corresponding WAITBx, WAITMx and WAITEx bits in the PMMODEL register.

The WAITBx bits (PMMODEL<7:6>) set the number of Wait cycles for the data setup prior to the PMRD/PMWT strobe in Mode 10, or prior to the PMENB strobe in Mode 11. The WAITMx bits (PMMODEL<5:2>) set the number of Wait cycles for the PMRD/PMWT strobe in Mode 10, or for the PMENB strobe in Mode 11. When this Wait state setting is '0', then WAITB and WAITE have no effect. The WAITE bits (PMMODEL<1:0>) define the number of Wait cycles for the data hold time after the PMRD/PMWT strobe in Mode 10, or after the PMENB strobe in Mode 11.

## 10.3.8 READ OPERATION

To perform a read on the PMP, the user reads the PMDIN1L register. This causes the PMP to output the desired values on the chip select lines and the address bus. Then the read line (PMRD) is strobed. The read data is placed into the PMDIN1L register.

If the 16-bit mode is enabled (MODE16 = 1), the read of the low byte of the PMDIN1L register will initiate two bus reads. The first read data byte is placed into the PMDIN1L register, and the second read data is placed into the PMDIN1H. Note that the read data obtained from the PMDIN1L register is actually the read value from the previous read operation. Hence, the first user read will be a dummy read to initiate the first bus read and fill the read register. Also, the requested read value will not be ready until after the BUSY bit is observed low. Thus, in a back-to-back read operation, the data read from the register will be the same for both reads. The next read of the register will yield the new value.

## 10.3.9 WRITE OPERATION

To perform a write onto the parallel bus, the user writes to the PMDIN1L register. This causes the module to first output the desired values on the chip select lines and the address bus. The write data from the PMDIN1L register is placed onto the PMD<7:0> data bus. Then the write line (PMWR) is strobed. If the 16-bit mode is enabled (MODE16 = 1), the write to the PMDIN1L register will initiate two bus writes. First write will consist of the data contained in PMDIN1L and the second write will contain the PMDIN1H.

## 10.3.10 PARALLEL MASTER PORT STATUS

## 10.3.10.1 The BUSY Bit

In addition to the PMP interrupt, a BUSY bit is provided to indicate the status of the module. This bit is used only in Master mode. While any read or write operation is in progress, the BUSY bit is set for all but the very last CPU cycle of the operation. In effect, if a single-cycle read or write operation is requested, the BUSY bit will never be active. This allows back-to-back transfers. While the bit is set, any request by the user to initiate a new operation will be ignored (i.e., writing or reading the lower byte of the PMDIN1L register will neither initiate a read nor a write).

#### 10.3.10.2 Interrupts


When the PMP module interrupt is enabled for Master mode, the module will interrupt on every completed read or write cycle; otherwise, the BUSY bit is available to query the status of the module.

## 10.3.11 MASTER MODE TIMING


This section contains a number of timing examples that represent the common Master mode configuration options. These options vary from 8-bit to 16-bit data, fully demultiplexed to fully multiplexed address and Wait states.


## FIGURE 10-12: READ AND WRITE TIMING, 8-BIT DATA, DEMULTIPLEXED ADDRESS

Q1 Q2	Q3  Q4  Q1  Q2  Q3  Q4  Q1  Q2	Q3 Q4 Q1 Q2 Q3	Q4 Q1 Q2 Q3 Q4 Q1 Q2	2 Q3 Q4 Q1 Q2 Q3 Q4
				1
PMCS1				
PMD<7:0>				
PMA<7:0>				i
PMWR				1 1
PMRD				
PMPIF				
BUSY			1 1 1 1 1 1 1 1 1	




## FIGURE 10-14: READ TIMING, 8-BIT DATA, WAIT STATES ENABLED, PARTIALLY MULTIPLEXED ADDRESS







### FIGURE 10-16: WRITE TIMING, 8-BIT DATA, WAIT STATES ENABLED, PARTIALLY MULTIPLEXED ADDRESS



### FIGURE 10-17: READ TIMING, 8-BIT DATA, PARTIALLY MULTIPLEXED ADDRESS, ENABLE STROBE






#### FIGURE 10-19: READ TIMING, 8-BIT DATA, FULLY MULTIPLEXED 16-BIT ADDRESS

	Q1 Q2 Q3 Q4	Q1 Q2 Q	3 Q4	Q1	Q2 Q3 0	Q4 Q1	Q2	Q3 Q4	Q1 Q2 Q3 0	Q4   Q1   Q2   Q3   Q4
			1	· ·	ł			· ·		
PMCS1				  	<u> </u>		- - -	· · · · ·		
MD<7:0> -		Address<	7:0>	Ado	dress<13:8	>)—		Data		
PMWR			, , ,	· ·				I		
PMRD			1	· · ·						
PMALL				, , , ,	1	ı I	1	I 1		!
PMALH			1		<u>`</u>		1 1	· ·		
PMPIF			i I	 				1		
BUSY				<u>, ,</u> , ,	<u> </u>	_ <u>\</u>	-	1   1		

#### FIGURE 10-20: WRITE TIMING, 8-BIT DATA, FULLY MULTIPLEXED 16-BIT ADDRESS

			1 1	
PMCS1		· · · · · · · · · · · · · · · · · · ·		
PMD<7:0>	Address<7:0>	Address<13:8>	Data	<u> </u>
PMWR				1 1
PMRD		· · · · ·		
PMALL	i_/\			1 1
PMALH				1 1
PMPIF		1 1 1 1 <u>1 1 1 1</u>		
BUSY				




#### FIGURE 10-22: WRITE TIMING, 16-BIT DATA, DEMULTIPLEXED ADDRESS

	Q1 Q2 Q3 Q4	Q1	Q2 Q3	Q4	Q1	Q2 Q3	Q4	Q1 Q2 Q3 Q4	Q1 Q2 Q3 Q4 Q1 Q2 Q3 Q4
				1 1 1		   	1		I I I
PMCS1				; ;	- - -			<u>۲</u>	l I
PMD<7:0>		(	LSB	, , ,	X	MSB	   	)	ı 
PMA<7:0>				1		1	1	χ	
PMWR				\				1	 
PMRD									· ·
PMBE			l	1 1	<u> </u>			χ	r 1
PMPIF				1 1		I I	1	1 1	
BUSY				, , ,		1			1 1 1
				: :		1 1	1	1	1 1


#### FIGURE 10-23: READ TIMING, 16-BIT MULTIPLEXED DATA, PARTIALLY MULTIPLEXED ADDRESS

	Q1 Q2 Q3 Q4	Q1	Q2 Q3	Q4	Q1	Q2 Q3	Q4	Q1	Q2 Q3	Q4	Q1 Q2 Q3 Q4	Q1 Q2 Q3 Q4
			1	1	1 1 1 1	1 1	1	I I	l I	1	1	1 1
PMCS1			u Ç		1	1	1					1 1
PMD<7:0>		A	ddress<7:	0>	}	C	LSB		——(C	MSB		1 +
PMWR						, , ,						
PMRD			1	1	1 1 1 1							1 1
PMBE			 		λ	1 1 1			 		(	1 T 1
PMALL					1	1	1	1				:
PMPIF			 			ı I I						1
BUSY			   	1 1 1	<u> </u>	I <u></u> I	 			1		1 1 1
		, i	1	1		1 1	1 1	l I	1	1	1	1 1 -
			,				•		ļ.			•

### FIGURE 10-24: WRITE TIMING, 16-BIT MULTIPLEXED DATA, PARTIALLY MULTIPLEXED ADDRESS



#### FIGURE 10-25: READ TIMING, 16-BIT MULTIPLEXED DATA, FULLY MULTIPLEXED 16-BIT ADDRESS



#### FIGURE 10-26: WRITE TIMING, 16-BIT MULTIPLEXED DATA, FULLY MULTIPLEXED 16-BIT ADDRESS

	Q1 Q2 Q3 Q4	Q1 Q2 Q3	Q4 (	Q1 Q2 Q	3 Q4 C	01 Q2 Q3	Q4 Q	1 Q2 Q3	Q4	Q1 Q2 Q3 Q4	Q1 Q2 Q3 Q4
PMCS1				1 			<u> </u>		<u> </u>		1 1 1
PMD<7:0>		Address<7:	0>	Address<1	3:8>	LSB	÷χ	MSB	· )		· • •
PMWR		· ·		1 1	· ·		<u>\</u>			1	i
PMRD	·				<u> </u>	1			· ·		1 1 1
PMBE		1 1	1	1		1		1	<u> </u>		! !
PMALH					<u> </u>		<u> </u>	1 1	1 1 1 1		1 1
PMALL		· · ·	i			1			, , , ,		! !
PMPIF	i	1 I	1	1		1	1 I 1 I	1	1 1 1 1	1	<u></u>
BUSY				1 				1 1 1	· ·		1 1 1
		· ·		1						1	1


#### **10.4** Application Examples

This section introduces some potential applications for the PMP module.

#### 10.4.1 MULTIPLEXED MEMORY OR PERIPHERAL

Figure 10-27 demonstrates the hookup of a memory or another addressable peripheral in Full Multiplex mode. Consequently, this mode achieves the best pin saving from the microcontroller perspective. However, for this configuration, there needs to be some external latches to maintain the address.


#### FIGURE 10-27: MULTIPLEXED ADDRESSING APPLICATION EXAMPLE




#### 10.4.2 PARTIALLY MULTIPLEXED MEMORY OR PERIPHERAL

Partial multiplexing implies using more pins; however, for a few extra pins, some extra performance can be achieved. Figure 10-28 provides an example of a memory or peripheral that is partially multiplexed with an external latch. If the peripheral has internal latches, as displayed in Figure 10-29, then no extra circuitry is required except for the peripheral itself.

#### FIGURE 10-28: EXAMPLE OF A PARTIALLY MULTIPLEXED ADDRESSING APPLICATION




#### FIGURE 10-29: EXAMPLE OF AN 8-BIT MULTIPLEXED ADDRESS AND DATA APPLICATION




#### 10.4.3 PARALLEL EEPROM EXAMPLE

Figure 10-30 provides an example connecting parallel EEPROM to the PMP. Figure 10-31 demonstrates a slight variation to this, configuring the connection for 16-bit data from a single EEPROM.

#### FIGURE 10-30: PARALLEL EEPROM EXAMPLE (UP TO 15-BIT ADDRESS, 8-BIT DATA)




#### FIGURE 10-31: PARALLEL EEPROM EXAMPLE (UP TO 15-BIT ADDRESS, 16-BIT DATA)



#### 10.4.4 LCD CONTROLLER EXAMPLE

The PMP module can be configured to connect to a typical LCD controller interface, as displayed in Figure 10-32. In this case the PMP module is configured for active-high control signals since common LCD displays require active-high control.

#### FIGURE 10-32: LCD CONTROL EXAMPLE (BYTE MODE OPERATION)



Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
PIR1	PMPIF <sup>(2)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65
PIE1	PMPIE <sup>(2)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65
IPR1	PMPIP <sup>(2)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65
PMCONH <sup>(2)</sup>	PMPEN	_	PSIDL	ADRMUX1	ADRMUX0	PTBEEN	PTWREN	PTRDEN	67
PMCONL <sup>(2)</sup>	CSF1	CSF0	ALP	_	CS1P	BEP	WRSP	RDSP	67
PMADDRH <sup>(1,2)</sup> /	_	CS1	Parallel M	laster Port A	ddress High	Byte			67
PMDOUT1H <sup>(1,2)</sup>	Parallel Po	rt Out Data I	-ligh Byte	(Buffer 1)					67
PMADDRL <sup>(1,2)</sup> /	Parallel Ma	ster Port Ad	dress Low	/ Byte					67
PMDOUT1L <sup>(1,2)</sup>	Parallel Po	rt Out Data I	_ow Byte (	Buffer 0)					67
PMDOUT2H <sup>(2)</sup>	Parallel Po	rt Out Data I	-ligh Byte	(Buffer 3)					68
PMDOUT2L <sup>(2)</sup>	Parallel Po	rt Out Data I	_ow Byte (	Buffer 2)					68
PMDIN1H <sup>(2)</sup>	Parallel Po	rt In Data Hi	gh Byte (E	Buffer 1)					67
PMDIN1L <sup>(2)</sup>	Parallel Po	rt In Data Lo	w Byte (B	uffer 0)					67
PMDIN2H <sup>(2)</sup>	Parallel Po	rt In Data Hi	gh Byte (E	Buffer 3)					68
PMDIN2L <sup>(2)</sup>	Parallel Po	rt In Data Lo	w Byte (B	uffer 2)					68
PMMODEH <sup>(2)</sup>	BUSY	IRQM1	IRQM0	INCM1	INCM0	MODE16	MODE1	MODE0	68
PMMODEL <sup>(2)</sup>	WAITB1	WAITB0	WAITM3	WAITM2	WAITM1	WAITM0	WAITE1	WAITE0	68
PMEH <sup>(2)</sup>	—	PTEN14	_	_	—	_	—		68
PMEL <sup>(2)</sup>	PTEN7	PTEN6	PTEN5	PTEN4	PTEN3	PTEN2	PTEN1	PTEN0	68
PMSTATH <sup>(2)</sup>	IBF	IBOV	—	—	IB3F	IB2F	IB1F	IB0F	68
PMSTATL <sup>(2)</sup>	OBE	OBUF	—		OB3E	OB2E	OB1E	OB0E	68
PADCFG1	—	—	_	_	_	RTSECSEL1	RTSECSEL0	PMPTTL	68

<b>TABLE 10-2</b> :	<b>REGISTERS ASSOCIATED WITH PMP MODULE</b>

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used during PMP operation.

**Note 1:** The PMADDRH/PMDOUT1H and PMADDRL/PMDOUT1L register pairs share the physical registers and addresses, but have different functions determined by the module's operating mode.

2: These bits and/or registers are only available in 44-pin devices.

NOTES:

### 11.0 TIMER0 MODULE

The Timer0 module incorporates the following features:

- Software selectable operation as a timer or counter in both 8-bit or 16-bit modes
- · Readable and writable registers
- Dedicated 8-bit, software programmable
   prescaler
- Selectable clock source (internal or external)
- · Edge select for external clock
- Interrupt-on-overflow

The T0CON register (Register 11-1) controls all aspects of the module's operation, including the prescale selection. It is both readable and writable.

Figure 11-1 provides a simplified block diagram of the Timer0 module in 8-bit mode. Figure 11-2 provides a simplified block diagram of the Timer0 module in 16-bit mode.

#### REGISTER 11-1: T0CON: TIMER0 CONTROL REGISTER (ACCESS FD5h)

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
TMR00N	T08BIT	TOCS	TOSE	PSA	T0PS2	T0PS1	T0PS0
bit 7							bit 0

Legend:							
R = Reada	ble bit	W = Writable bit	U = Unimplemented bit,	read as '0'			
-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			
bit 7	TMR0ON	: Timer0 On/Off Control bit					
	1 = Enab	les Timer0					
	0 = Stops	Timer0					
bit 6	<b>T08BIT</b> : 7	Timer0 8-Bit/16-Bit Control bi	t				
	1 = Timer	0 is configured as an 8-bit ti	mer/counter				
	0 = Timer	0 is configured as a 16-bit til	mer/counter				
bit 5	TOCS: Tir	mer0 Clock Source Select bit	t				
	1 = Trans	sition on TOCKI pin					
	0 = Internal instruction cycle clock (CLKO)						
bit 4	TOSE: Tir	mer0 Source Edge Select bit					
	1 = Increi	ment on high-to-low transition	n on T0CKI pin				
	0 = Increi	ment on low-to-high transition	n on T0CKI pin				
bit 3	PSA: Tim	er0 Prescaler Assignment bi	it				
			Timer0 clock input bypasses p				
	0 <b>= Time</b> i	0 prescaler is assigned. Tim	er0 clock input comes from pr	escaler output.			
bit 2-0	T0PS<2:	0>: Timer0 Prescaler Select	bits				
	111 <b>= 1:2</b>	256 Prescale value					
		28 Prescale value					
		64 Prescale value					
		<ul><li>B2 Prescale value</li><li>B16 Prescale value</li></ul>					
		B Prescale value					
		Prescale value					
	000 = 1:2						

#### 11.1 Timer0 Operation

Timer0 can operate as either a timer or a counter. The mode is selected with the TOCS bit (TOCON<5>). In Timer mode (TOCS = 0), the module increments on every clock by default unless a different prescaler value is selected (see **Section 11.3 "Prescaler"**). If the TMR0 register is written to, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0 register.

The Counter mode is selected by setting the T0CS bit (= 1). In this mode, Timer0 increments either on every rising edge or falling edge of pin, T0CKI. The incrementing edge is determined by the Timer0 Source Edge Select bit, T0SE (T0CON<4>); clearing this bit selects the rising edge. Restrictions on the external clock input are discussed below.


An external clock source can be used to drive Timer0; however, it must meet certain requirements to ensure that the external clock can be synchronized with the internal phase clock (Tosc). There is a delay between synchronization and the onset of incrementing the timer/counter.

### 11.2 Timer0 Reads and Writes in 16-Bit Mode


TMR0H is not the actual high byte of Timer0 in 16-bit mode. It is actually a buffered version of the real high byte of Timer0, which is not directly readable nor writable (refer to Figure 11-2). TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16 bits of Timer0 without having to verify that the read of the high and low byte were valid, due to a rollover between successive reads of the high and low byte.

Similarly, a write to the high byte of Timer0 must also take place through the TMR0H Buffer register. The high byte is updated with the contents of TMR0H when a write occurs to TMR0L. This allows all 16 bits of Timer0 to be updated at once.

#### FIGURE 11-1: TIMER0 BLOCK DIAGRAM (8-BIT MODE)



#### FIGURE 11-2: TIMER0 BLOCK DIAGRAM (16-BIT MODE)



#### 11.3 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module. The prescaler is not directly readable or writable. Its value is set by the PSA and T0PS<2:0> bits (T0CON<3:0>), which determine the prescaler assignment and prescale ratio.

Clearing the PSA bit assigns the prescaler to the Timer0 module. When it is assigned, prescale values from 1:2 through 1:256 in power-of-2 increments are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF TMR0, MOVWF TMR0, BSF TMR0, etc.) clear the prescaler count.

Note: Writing to TMR0 when the prescaler is assigned to Timer0 will clear the prescaler count but will not change the prescaler assignment.

#### 11.3.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control and can be changed "on-the-fly" during program execution.

#### 11.4 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h in 8-bit mode, or from FFFFh to 0000h in 16-bit mode. This overflow sets the TMR0IF flag bit. The interrupt can be masked by clearing the TMR0IE bit (INTCON<5>). Before re-enabling the interrupt, the TMR0IF bit must be cleared in software by the Interrupt Service Routine (ISR).

Since Timer0 is shutdown in Sleep mode, the TMR0 interrupt cannot awaken the processor from Sleep.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:	
TMR0L	Timer0 Reg	ister Low By	te						84	
TMR0H	Timer0 Register High Byte									
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	83	
T0CON	TMR0ON	T08BIT	TOCS	TOSE	PSA	T0PS2	T0PS1	T0PS0	84	

 TABLE 11-1:
 REGISTERS ASSOCIATED WITH TIMER0

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by Timer0.

NOTES:

### 12.0 TIMER1 MODULE

The Timer1 timer/counter module incorporates these features:

- Software selectable operation as a 16-bit timer or counter
- Readable and writable 8-bit registers (TMR1H and TMR1L)
- Selectable clock source (internal or external) with device clock or Timer1 oscillator internal options
- Interrupt-on-overflow
- Reset on ECCP Special Event Trigger
- Device clock status flag (T1RUN)
- Timer with gated control

Figure 12-1 displays a simplified block diagram of the Timer1 module.

The module incorporates its own low-power oscillator to provide an additional clocking option. The Timer1 oscillator can also be used as a low-power clock source for the microcontroller in power-managed operation.

Timer1 is controlled through the T1CON Control register (Register 12-1). It also contains the Timer1 oscillator Enable bit (T1OSCEN). Timer1 can be enabled or disabled by setting or clearing control bit, TMR10N (T1CON<0>).

The Fosc clock source (TMR1CS<1:0> = 01) should not be used with the ECCP capture/compare features. If the timer will be used with the capture or compare features, always select one of the other timer clocking options.

#### REGISTER 12-1: T1CON: TIMER1 CONTROL REGISTER (ACCESS FCDh)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
TMR1CS1	TMR1CS0	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	RD16	TMR10N
bit 7							bit 0

Legend:				
R = Reada	able bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown
bit 7-6	TMR1CS<	1:0>: Timer1 Clock Source	Select bits	
	01 = Timer	1 clock source is T1OSC or 1 clock source is system clo 1 clock source is instruction	ock (Fosc) <sup>(1)</sup>	
bit 5-4	T1CKPS<1	:0>: Timer1 Input Clock Pro	escale Select bits	
	11 = 1:8 Pi 10 = 1:4 Pi 01 = 1:2 Pi	escale value escale value escale value escale value		
bit 3	T1OSCEN	Timer1 Oscillator Source S	Select bit	
	1 = Power	<u>1CS&lt;1:0&gt; = 10:</u> up the Timer1 crystal driver crystal driver off <sup>(2)</sup> , Timer1	and supply the Timer1 clock fi clock is from the T1CKI input p	rom the crystal output pin
	1 = Power	<u>1CS&lt;1:0&gt; = 0x:</u> up the Timer1 crystal driver crystal driver off <sup>(2)</sup>		
bit 2		imer1 External Clock Input	Synchronization Select bit	
	1 = Do not	synchronize external clock onize external clock input	input	
			ernal clock when TMR1CS<1:	<b>0&gt; =</b> 0×.
bit 1		Bit Read/Write Mode Enable		
		es register read/write of Tim es register read/write of Tim		
bit 0	<b>TMR1ON:</b> 1 = Enable 0 = Stops			
Note 1: 2:	The Timer1 os	cillator crystal driver is powe	ered whenever T1OSCEN (T10	he ECCP capture/compare feature CON) or T3OSCEN (T3CON) = 1. the inverter and feedback resisto

2: The Timer1 oscillator crystal driver is powered whenever T1OSCEN (T1CON) or T3OSCEN (T3CON) = 1. The circuit is enabled by the logical OR of these two bits. When disabled, the inverter and feedback resistor are disabled to eliminate power drain. The TMR1ON and TMR3ON bits do not have to be enabled to power up the crystal driver.

#### 12.1 Timer1 Gate Control Register

The Timer1 Gate Control register (T1GCON), displayed in Register 12-2, is used to control the Timer1 gate.

#### REGISTER 12-2: T1GCON: TIMER1 GATE CONTROL REGISTER (ACCESS F9Ah)<sup>(1)</sup>

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-x	R/W-0	R/W-0
TMR1GE	T1GPOL	T1GTM	T1GSPM	T1GGO/T1DONE	T1GVAL	T1GSS1	T1GSS0
bit 7							bit 0
Legend:							
R = Readable	bit	W = Writable	hit	U = Unimplemented	hit read as	<b>'</b> Ω'	
-n = Value at		'1' = Bit is set		'0' = Bit is cleared	a bit, i cau as	x = Bit is unkn	0.4/0
		1 - Dit 13 301					OWIT
bit 7	TMR1GE: Ti	mer1 Gate Ena	able bit				
	If TMR10N =						
	This bit is ign						
	If TMR10N =						
				Timer1 gate function			
bit 6		ounts regardle ner1 Gate Pola		Jale function			
bit 0				ounts when gate is hi	ah)		
	•		•	unts when gate is low	• /		
bit 5	•	er1 Gate Toggl		Ū	,		
		Gate Toggle mo		d			
	0 = Timer1 0	Gate Toggle mo	ode is disable	d and toggle flip-flop	is cleared		
	-	flip-flop toggles	-				
bit 4		mer1 Gate Sin					
		ate Single Pul ate Single Pul		nabled and is controll sabled	ling Timer1 g	ate	
bit 3	T1GGO/T1D	ONE: Timer1 (	Gate Single P	ulse Acquisition State	us bit		
				is ready, waiting for			
				has completed or ha	is not been s	tarted	
		-		GSPM is cleared.			
bit 2	-	ner1 Gate Curr					
		current state Enable (TMR1		gate that could be p	provided to T	MR1H:TMR1L;	unaffected by
bit 1-0	T1GSS<1:0>	: Timer1 Gate	Source Sele	ct bits			
	00 = Timer1						
		overflow outpu					
	10 = IMR2 t	o match PR2 c	output				

**Note 1:** Programming the T1GCON prior to T1CON is recommended.

#### REGISTER 12-3: TCLKCON: TIMER CLOCK CONTROL REGISTER (BANKED F52h)

U-0	U-0	U-0	R-0	U-0	U-0	R/W-0	R/W-0
_	—	—	T1RUN	—	—	T3CCP2	T3CCP1
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-5	Unimplemented: Read as '0'
bit 4	T1RUN: Timer1 Run Status bit
	1 = Device is currently clocked by T1OSC/T1CKI
	0 = System clock comes from an oscillator other than T1OSC/T1CKI
bit 3-2	Unimplemented: Read as '0'
bit 1-0	T3CCP<2:1>: ECCP Timer Assignment bits
	10 = ECCP1 and ECCP2 both use Timer3 (capture/compare) and Timer4 (PWM)
	01 = ECCP1 uses Timer1 (compare/capture) and Timer2 (PWM); ECCP2 uses Timer3 (capture/compare) and Timer4 (PWM)
	00 = ECCP1 and ECCP2 both use Timer1 (capture/compare) and Timer2 (PWM)

#### 12.2 Timer1 Operation

The Timer1 module is an 8-bit or 16-bit incrementing counter, which is accessed through the TMR1H:TMR1L register pair.

When used with an internal clock source, the module is a timer and increments on every instruction cycle. When used with an external clock source, the module can be used as either a timer or counter and increments on every selected edge of the external source.

Timer1 is enabled by configuring the TMR1ON and TMR1GE bits in the T1CON and T1GCON registers, respectively.

When Timer1 is enabled, the RC1/T1OSI/UOE/RP12 and RC0/T1OSO/T1CKI/RP11 pins become inputs. This means the values of TRISC<1:0> are ignored and the pins are read as '0'.

#### 12.3 Clock Source Selection

The TMR1CS<1:0> and T1OSCEN bits of the T1CON register are used to select the clock source for Timer1. Register 12-1 displays the clock source selections.

#### 12.3.1 INTERNAL CLOCK SOURCE

When the internal clock source is selected, the TMR1H:TMR1L register pair will increment on multiples of Fosc as determined by the Timer1 prescaler.

#### 12.3.2 EXTERNAL CLOCK SOURCE

When the external clock source is selected, the Timer1 module may work as a timer or a counter.


When enabled to count, Timer1 is incremented on the rising edge of the external clock input, T1CKI, or the capacitive sensing oscillator signal. Either of these external clock sources can be synchronized to the microcontroller system clock or they can run asynchronously.

When used as a timer with a clock oscillator, an external 32.768 kHz crystal can be used in conjunction with the dedicated internal oscillator circuit.

Note:	In Counter mode, a falling edge must be
	registered by the counter prior to the first
	incrementing rising edge after any one or more of the following conditions:
	Timer1 enabled after POR Reset
	Write to TMR1H or TMR1L
	<ul> <li>Timer1 is disabled</li> </ul>
	<ul> <li>Timer1 is disabled (TMR1ON = 0)</li> </ul>
	when T1CKI is high, then Timer1 is
	enabled (TMR1ON = 1) when T1CKI is
	low.

TMR1CS1	TMR1CS0	T1OSCEN	Clock Source
0	1	х	Clock Source (Fosc)
0	0	Х	Instruction Clock (Fosc/4)
1	0	0	External Clock on T1CKI Pin
1	0	1	Oscillator Circuit on T1OSI/T1OSO Pin

#### TABLE 12-1: TIMER1 CLOCK SOURCE SELECTION



#### 12.4 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes. When the RD16 control bit (T1CON<1>) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L loads the contents of the high byte of Timer1 into the Timer1 High Byte Buffer register. This provides the user with the ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, has become invalid due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H Buffer register. The Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits to both the high and low bytes of Timer1 at once.


The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 High Byte Buffer register. Writes to TMR1H do not clear the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

#### 12.5 Timer1 Oscillator

An on-chip crystal oscillator circuit is incorporated between pins, T1OSI (input) and T1OSO (amplifier output). It is enabled by setting the Timer1 Oscillator Enable bit, T1OSCEN (T1CON<3>). The oscillator is a low-power circuit rated for 32 kHz crystals. It will continue to run during all power-managed modes. The circuit for a typical LP oscillator is depicted in Figure 12-2. Table 12-2 provides the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper start-up of the Timer1 oscillator.

#### FIGURE 12-2: EXTERNAL COMPONENTS FOR THE TIMER1 LP OSCILLATOR



# TABLE 12-2:CAPACITOR SELECTION FOR<br/>THE TIMER<br/>OSCILLATOR<sup>(2,3,4,5)</sup>

Oscillator Type	Freq.	C1	C2
LP	32 kHz	12 pF <sup>(1)</sup>	12 pF <sup>(1)</sup>

- Note 1: Microchip suggests these values as a starting point in validating the oscillator circuit.
  - 2: Higher capacitance increases the stability of the oscillator but also increases the start-up time.
  - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - Capacitor values are for design guidance only. Values listed would be typical of a CL = 10 pF rated crystal when LPT1OSC = 1.
  - Incorrect capacitance value may result in a frequency not meeting the crystal manufacturer's tolerance specification.

The Timer1 crystal oscillator drive level is determined based on the LPT1OSC (CONFIG2L<4>) Configuration bit. The Higher Drive Level mode, LPT1OSC = 1, is intended to drive a wide variety of 32.768 kHz crystals with a variety of load capacitance (CL) ratings.

The Lower Drive Level mode is highly optimized for extremely low-power consumption. It is not intended to drive all types of 32.768 kHz crystals. In the Low Drive Level mode, the crystal oscillator circuit may not work correctly if excessively large discrete capacitors are placed on the T1OSI and T1OSO pins. This mode is only designed to work with discrete capacitances of approximately 3 pF-10 pF on each pin.

Crystal manufacturers usually specify a CL (load capacitance) rating for their crystals. This value is related to, but not necessarily the same as, the values that should be used for C1 and C2 in Figure 12-2. See the crystal manufacturer's applications information for more details on how to select the optimum C1 and C2 for a given crystal. The optimum value depends in part on the amount of parasitic capacitance in the circuit, which is often unknown. Therefore, after values have been selected, it is highly recommended that thorough testing and validation of the oscillator be performed.

### 12.5.1 USING TIMER1 AS A CLOCK SOURCE

The Timer1 oscillator is also available as a clock source in power-managed modes. By setting the clock select bits, SCS<1:0> (OSCCON<1:0>), to '01', the device switches to SEC\_RUN mode; both the CPU and peripherals are clocked from the Timer1 oscillator. If the IDLEN bit (OSCCON<7>) is cleared and a SLEEP instruction is executed, the device enters SEC\_IDLE mode. Additional details are available in **Section 3.0** "Low-Power Modes".

Whenever the Timer1 oscillator is providing the clock source, the Timer1 system clock status flag, T1RUN (TCLKCON<4>), is set. This can be used to determine the controller's current clocking mode. It can also indicate the clock source currently being used by the Fail-Safe Clock Monitor. If the Clock Monitor is enabled and the Timer1 oscillator fails while providing the clock, polling the T1RUN bit will indicate whether the clock is being provided by the Timer1 oscillator or another source.

#### 12.5.2 TIMER1 OSCILLATOR LAYOUT CONSIDERATIONS


The Timer1 oscillator circuit draws very little power during operation. Due to the low-power nature of the oscillator, it may also be sensitive to rapidly changing signals in close proximity. This is especially true when the oscillator is configured for extremely Low-Power mode (LPT1OSC = 0).

The oscillator circuit, displayed in Figure 12-2, should be located as close as possible to the microcontroller. There should be no circuits passing within the oscillator circuit boundaries other than Vss or VDD.

If a high-speed circuit must be located near the oscillator (such as the ECCP1 pin in Output Compare or PWM mode, or the primary oscillator using the OSC2 pin), a grounded guard ring around the oscillator circuit, as displayed in Figure 12-3, may be helpful when used on a single-sided PCB or in addition to a ground plane.

#### FIGURE 12-3:

OSCILLATOR CIRCUIT WITH GROUNDED GUARD RING



In the Low Drive Level mode, LPT1OSC = 0, it is critical that the RC2 I/O pin signals be kept away from the oscillator circuit. Configuring RC2 as a digital output, and toggling it, can potentially disturb the oscillator circuit, even with relatively good PCB layout. If possible, it is recommended to either leave RC2 unused, or use it as an input pin with a slew rate limited signal source. If RC2 must be used as a digital output, it may be necessary to use the Higher Drive Level Oscillator mode (LPT1OSC = 1) with many PCB layouts. Even in the High Drive Level mode, careful layout procedures should still be followed when designing the oscillator circuit.

In addition to dV/dt induced noise considerations, it is also important to ensure that the circuit board is clean. Even a very small amount of conductive soldering flux residue can cause PCB leakage currents which can overwhelm the oscillator circuit.

#### 12.6 Timer1 Interrupt

The TMR1 register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The Timer1 interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit, TMR1IF (PIR1<0>). This interrupt can be enabled or disabled by setting or clearing the Timer1 Interrupt Enable bit, TMR1IE (PIE1<0>).

#### 12.7 Resetting Timer1 Using the ECCP Special Event Trigger

If ECCP1 or ECCP2 is configured to use Timer1 and to generate a Special Event Trigger in Compare mode (CCPxM<3:0> = 1011), this signal will reset Timer3. The trigger from ECCP2 will also start an A/D conversion if the A/D module is enabled (see Section 17.3.4 "Special Event Trigger" for more information).

The module must be configured as either a timer or a synchronous counter to take advantage of this feature. When used this way, the CCPRxH:CCPRxL register pair effectively becomes a Period register for Timer1.

If Timer1 is running in Asynchronous Counter mode, this Reset operation may not work.

In the event that a write to Timer1 coincides with a Special Event Trigger, the write operation will take precedence.

Note:	The Special Event Trigger fro	m the
	ECCPx module will not set the T	MR1IF
	interrupt flag bit (PIR1<0>).	

#### 12.8 Timer1 Gate

The Timer1 can be configured to count freely or the count can be enabled and disabled using the Timer1 gate circuitry. This is also referred to as Timer1 gate count enable.

Timer1 gate can also be driven by multiple selectable sources.

#### 12.8.1 TIMER1 GATE COUNT ENABLE

The Timer1 Gate Enable mode is enabled by setting the TMR1GE bit of the T1GCON register. The polarity of the Timer1 Gate Enable mode is configured using the T1GPOL bit of the T1GCON register.

When Timer1 Gate Enable mode is enabled, Timer1 will increment on the rising edge of the Timer1 clock source. When Timer1 Gate Enable mode is disabled, no incrementing will occur and Timer1 will hold the current count. See Figure 12-4 for timing details.

TABLE 12-3:	TIMER1 GATE ENABLE
	SELECTIONS

T1CLK	T1GPOL	T1G	Timer1 Operation
$\uparrow$	0	0	Counts
$\uparrow$	0	1	Holds Count
$\uparrow$	1	0	Holds Count
$\uparrow$	1	1	Counts

### 

#### FIGURE 12-4: TIMER1 GATE COUNT ENABLE MODE

#### 12.8.2 TIMER1 GATE SOURCE SELECTION

The Timer1 gate source can be selected from one of four different sources. Source selection is controlled by the T1GSSx bits of the T1GCON register. The polarity for each available source is also selectable. Polarity selection is controlled by the T1GPOL bit of the T1GCON register.

TABLE 12-4: TIMER1 GATE SOURCES

T1GSS<1:0>	Timer1 Gate Source
00	Timer1 Gate Pin
01	Overflow of Timer0 (TMR0 increments from FFh to 00h)
10	TMR2 to Match PR2 (TMR2 increments to match PR2)

#### 12.8.2.1 T1G Pin Gate Operation

The T1G pin is one source for Timer1 gate control. It can be used to supply an external source to the Timer1 gate circuitry.

#### 12.8.2.2 Timer0 Overflow Gate Operation

When Timer0 increments from FFh to 00h, a low-to-high pulse will automatically be generated and internally supplied to the Timer1 gate circuitry.

#### 12.8.2.3 Timer2 Match Gate Operation

The TMR2 register will increment until it matches the value in the PR2 register. On the very next increment cycle, TMR2 will be reset to 00h. When this Reset occurs, a low-to-high pulse will automatically be generated and internally supplied to the Timer1 gate circuitry.

#### 12.8.3 TIMER1 GATE TOGGLE MODE


When Timer1 Gate Toggle mode is enabled, it is possible to measure the full cycle length of a Timer1 gate signal, as opposed to the duration of a single level pulse.

The Timer1 gate source is routed through a flip-flop that changes state on every incrementing edge of the signal. See Figure 12-5 for timing details.

#### FIGURE 12-5: TIMER1 GATE TOGGLE MODE

The T1GVAL bit will indicate when the Toggled mode is active and the timer is counting.

The Timer1 Gate Toggle mode is enabled by setting the T1GTM bit of the T1GCON register. When the T1GTM bit is cleared, the flip-flop is cleared and held clear. This is necessary in order to control which edge is measured.



#### 12.8.4 TIMER1 GATE SINGLE PULSE MODE


When Timer1 Gate Single Pulse mode is enabled, it is possible to capture a single pulse gate event. Timer1 Gate Single Pulse mode is first enabled by setting the T1GSPM bit in the T1GCON register. Next, the T1GGO/T1DONE bit in the T1GCON register must be set. The Timer1 will be fully enabled on the next incrementing edge. On the next trailing edge of the pulse, the T1GGO/T1DONE bit will automatically be cleared. No other gate events will be allowed to increment Timer1 until the T1GGO/T1DONE bit is once again set in software.

Clearing the T1GSPM bit of the T1GCON register will also clear the T1GGO/T1DONE bit. See Figure 12-6 for timing details.

Enabling the Toggle mode and the Single Pulse mode, simultaneously, will permit both sections to work together. This allows the cycle times on the Timer1 gate source to be measured. See Figure 12-7 for timing details.

#### 12.8.5 TIMER1 GATE VALUE STATUS

When the Timer1 gate value status is utilized, it is possible to read the most current level of the gate control value. The value is stored in the T1GVAL bit in the T1GCON register. The T1GVAL bit is valid even when the Timer1 gate is not enabled (TMR1GE bit is cleared).



TIMER1 GATE SINGLE PULSE MODE

FIGURE 12-6:

### FIGURE 12-7: TIMER1 GATE SINGLE PULSE AND TOGGLE COMBINED MODE TMR1GE T1GPOL T1GSPM T1GTM Cleared by Hardware on T1GGO/ Set by Software Falling Edge of T1GVAL T1DONE Counting Enabled on Rising Edge of T1G T1G\_IN T1CKI T1GVAL Timer1 N + 1 Ν N + 2 N + 3 N + 4 Cleared by Software Set by Hardware on Cleared by Software Falling Edge of T1GVAL TMR1GIF

TABLE 12-5: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER
-----------------------------------------------------------------

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	83
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	85
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	85
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	85
TMR1L	1L Timer1 Register Low Byte								
TMR1H	Timer1 Reg	gister High B	yte						84
T1CON	TMR1CS1	TMR1CS0	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	RD16	TMR10N	84
T1GCON	TMR1GE	T1GPOL	T1GTM	T1GSPM	T1GGO/ T1DONE	T1GVAL	T1GSS1	T1GSS0	85
TCLKCON	—	—		T1RUN	—	_	T3CCP2	T3CCP1	87

Legend: Shaded cells are not used by the Timer1 module.

Note 1: These bits are only available in 44-pin devices.

### 13.0 TIMER2 MODULE

The Timer2 module incorporates the following features:

- 8-bit Timer and Period registers (TMR2 and PR2, respectively)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4 and 1:16)
- Software programmable postscaler (1:1 through 1:16)
- Interrupt on TMR2 to PR2 match
- Optional use as the shift clock for the MSSP modules

The module is controlled through the T2CON register (Register 13-1) which enables or disables the timer and configures the prescaler and postscaler. Timer2 can be shut off by clearing control bit, TMR2ON (T2CON<2>), to minimize power consumption.

A simplified block diagram of the module is shown in Figure 13-1.

#### 13.1 Timer2 Operation

In normal operation, TMR2 is incremented from 00h on each clock (Fosc/4). A 4-bit counter/prescaler on the clock input gives direct input, divide-by-4 and divide-by-16 prescale options. These are selected by the prescaler control bits, T2CKPS<1:0> (T2CON<1:0>). The value of TMR2 is compared to that of the Period register, PR2, on each clock cycle. When the two values match, the comparator generates a match signal as the timer output. This signal also resets the value of TMR2 to 00h on the next cycle and drives the output counter/postscaler (see Section 13.2 "Timer2 Interrupt").

The TMR2 and PR2 registers are both directly readable and writable. The TMR2 register is cleared on any device Reset, while the PR2 register initializes at FFh. Both the prescaler and postscaler counters are cleared on the following events:

- a write to the TMR2 register
- a write to the T2CON register
- any device Reset (Power-on Reset (POR), MCLR Reset, Watchdog Timer Reset (WDTR) or Brown-out Reset (BOR))

TMR2 is not cleared when T2CON is written.

#### REGISTER 13-1: T2CON: TIMER2 CONTROL REGISTER (ACCESS FCAh)

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	T2OUTPS3	T2OUTPS2	T2OUTPS1	T2OUTPS0	TMR2ON	T2CKPS1	T2CKPS0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	Unimplemented: Read as '0'
bit 6-3	T2OUTPS<3:0>: Timer2 Output Postscale Select bits
	0000 = 1:1 Postscale
	0001 = 1:2 Postscale
	•
	•
	•
	1111 = 1:16 Postscale
bit 2	TMR2ON: Timer2 On bit
	1 = Timer2 is on
	0 = Timer2 is off
bit 1-0	T2CKPS<1:0>: Timer2 Clock Prescale Select bits
	00 = Prescaler is 1
	01 = Prescaler is 4
	1x = Prescaler is 16

#### 13.2 Timer2 Interrupt


Timer2 can also generate an optional device interrupt. The Timer2 output signal (TMR2 to PR2 match) provides the input for the 4-bit output counter/postscaler. This counter generates the TMR2 Match Interrupt Flag, which is latched in TMR2IF (PIR1<1>). The interrupt is enabled by setting the TMR2 Match Interrupt Enable bit, TMR2IE (PIE1<1>).

A range of 16 postscaler options (from 1:1 through 1:16 inclusive) can be selected with the postscaler control bits, T2OUTPS<3:0> (T2CON<6:3>).

#### 13.3 Timer2 Output

The unscaled output of TMR2 is available primarily to the ECCP modules, where it is used as a time base for operations in PWM mode.

Timer2 can be optionally used as the shift clock source for the MSSP modules operating in SPI mode. Additional information is provided in Section 18.0 "Master Synchronous Serial Port (MSSP) Module".



#### FIGURE 13-1: TIMER2 BLOCK DIAGRAM

#### TABLE 13-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	<b>INTOIE</b>	RBIE	TMR0IF	INT0IF	RBIF	83
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	85
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	85
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	85
TMR2	Timer2 Register								84
T2CON	_	T2OUTPS3	T2OUTPS2	T2OUTPS1	T2OUTPS0	TMR2ON	T2CKPS1	T2CKPS0	84
PR2	Timer2 Per	riod Register							84

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Timer2 module.

Note 1: These bits are only available in 44-pin devices.

### 14.0 TIMER3 MODULE

The Timer3 timer/counter module incorporates these features:

- Software selectable operation as a 16-bit timer or counter
- Readable and writable 8-bit registers (TMR3H and TMR3L)
- Selectable clock source (internal or external) with device clock or Timer1 oscillator internal options
- Interrupt-on-overflow
- · Module Reset on ECCP Special Event Trigger

A simplified block diagram of the Timer3 module is shown in Figure 14-1.

The Timer3 module is controlled through the T3CON register (Register 14-1). It also selects the clock source options for the ECCP modules; see **Section 17.1.1** "**ECCP Module and Timer Resources**" for more information.

The Fosc clock source (TMR3CS<1:0> = 01) should not be used with the ECCP capture/compare features. If the timer will be used with the capture or compare features, always select one of the other timer clocking options.

#### REGISTER 14-1: T3CON: TIMER3 CONTROL REGISTER (ACCESS F79h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
TMR3CS1	TMR3CS0	T3CKPS1	T3CKPS0	T3OSCEN	<b>T3SYNC</b>	RD16	TMR3ON
bit 7							bit 0

Legend:									
R = Reada	ble bit	W = Writable bit	U = Unimplemented bit	read as '0'					
-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is un									
bit 7-6		TMR3CS<1:0>: Timer3 Clock Source Select bits							
	01 <b>= Tim</b>	er3 clock source is the Timer1 er3 clock source is the syster er3 clock source is the instruc	m clock (Fosc) <sup>(1)</sup>	nput pin (assigned in PPS module					
bit 5-4		<1:0>: Timer3 Input Clock Pr							
	11 <b>= 1:8</b>	Prescale value							
		Prescale value							
		Prescale value Prescale value							
bit 3		N: Timer3 Oscillator Source S	Soloot hit						
DIL 3		<b>R3CS&lt;1:0&gt; =</b> 10:	Select bit						
			(T1OSC) and supply the Time	er3 clock from the crystal output					
				input pin assigned in PPS modu					
		1R3CS<1:0> = 0x:							
		er up the Timer1 crystal driver	(T1OSC)						
		r1 crystal driver off <sup>(2)</sup>							
bit 2		: Timer3 External Clock Input	Synchronization Control bit						
		<u>1R3CS&lt;1:0&gt; = 10:</u>							
		ot synchronize external clock hronize external clock input	Input						
		$\frac{1R3CS<1:0}{0} = 0x:$							
		ignored; Timer3 uses the int	ernal clock.						
bit 1		B-Bit Read/Write Mode Enable							
	1 = Enab	les register read/write of Time	er3 in one 16-bit operation						
		les register read/write of Time							
bit 0	TMR3ON	I: Timer3 On bit							
	1 = Enab	les Timer3							
	0 <b>= Stops</b>	s Timer3							
Note 1:	The Fosc clo	ck source should not be selecte	ed if the timer will be used with t	ne ECCP capture/compare feature					
				CON) or T3OSCEN (T3CON) = $1$					

2: The Timer1 oscillator crystal driver is powered whenever T1OSCEN (T1CON) or T3OSCEN (T3CON) = 1. The circuit is enabled by the logical OR of these two bits. When disabled, the inverter and feedback resistor are disabled to eliminate power drain. The TMR1ON and TMR3ON bits do not have to be enabled to power up the crystal driver.

<sup>© 2009</sup> Microchip Technology Inc.

#### 14.1 Timer3 Gate Control Register

The Timer3 Gate Control register (T3GCON), provided in Register 14-2, is used to control the Timer3 gate.

### REGISTER 14-2: T3GCON: TIMER3 GATE CONTROL REGISTER (ACCESS F97h)<sup>(1)</sup>

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-x	R/W-0	R/W-0
TMR3GE	T3GPOL	T3GTM	T3GSPM	T3GGO/T3DONE	T3GVAL	T3GSS1	T3GSS0
bit 7			÷	· · ·			bit 0
Legend:							
R = Readable	e bit	W = Writable	bit	U = Unimplemented	bit, read as '	0'	
-n = Value at		'1' = Bit is se		'0' = Bit is cleared	,	x = Bit is unkn	own
bit 7	TMR3GE: Tir	mer3 Gate En	able bit				
	If TMR3ON =	<u>: 0:</u>					
	This bit is ign	ored.					
	If TMR3ON =						
				Timer3 gate function			
		-		gate function			
bit 6	T3GPOL: Tir		•				
	•		•	ounts when gate is hi	•		
bit 5	T3GTM: Time			ounts when gate is low	(v)		
bit 5	1 = Timer3 (			vd.			
				ed and toggle flip-flop	is cleared		
	Timer3 gate f						
bit 4	T3GSPM: Tir	ner3 Gate Sir	ngle Pulse Mo	de bit			
				nabled and is control	lling Timer3 g	ate	
	0 = Timer3 G	•			0 0		
bit 3	T3GGO/T3D	ONE: Timer3	Gate Single F	Pulse Acquisition Stat	us bit		
	1 = Timer3 g	ate single pu	se acquisitior	n is ready, waiting for	an edge		
				has completed or ha	as not been s	tarted	
		-		3GSPM is cleared.			
bit 2	T3GVAL: Tin						
	Indicates the Timer3 Gate			3 gate that could be	provided to T	MR3H:TMR3L.	Unaffected by
bit 1-0	T3GSS<1:0>	: Timer3 Gate	e Source Sele	ect bits			
	10 <b>= TMR2 t</b>						
	01 = Timer0						
	00 = Timer3	gate pin (T3G	)				

**Note 1:** Programming the T3GCON prior to T3CON is recommended.

#### REGISTER 14-3: TCLKCON: TIMER CLOCK CONTROL REGISTER (BANKED F52h)

U-0	U-0	U-0	R-0	U-0	U-0	R/W-0	R/W-0
—	—	_	T1RUN	—	_	T3CCP2	T3CCP1
bit 7							bit 0


Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-5	Unimplemented: Read as '0'
bit 4	T1RUN: Timer1 Run Status bit
	1 = Device is currently clocked by T1OSC/T1CKI
	0 = System clock comes from an oscillator other than T1OSC/T1CKI
bit 3-2	Unimplemented: Read as '0'
bit 1-0	T3CCP<2:1>: ECCP Timer Assignment bits
	10 = ECCP1 and ECCP2 both use Timer3 (capture/compare) and Timer4 (PWM)
	01 = ECCP1 uses Timer1 (compare/capture) and Timer2 (PWM); ECCP2 uses Timer3 (capture/compare) and Timer4 (PWM)
	00 = ECCP1 and ECCP2 both use Timer1 (capture/compare) and Timer2 (PWM)

#### 14.2 Timer3 Operation

Timer3 can operate in one of three modes:

- Timer
- Synchronous Counter
- Asynchronous Counter
- · Timer with Gated Control



#### FIGURE 14-1: TIMER3 BLOCK DIAGRAM

**Note 1:** ST Buffer is high-speed type when using T3CKI.

- **2:** Timer3 register increments on rising edge.
- 3: Synchronize does not operate while in Sleep.
- 4: If T3OSCEN = 1, clock is from Timer1 crystal output. If T3OSCEN = 0, clock is from T3CKI digital input pin assigned in the PPS module.

The operating mode is determined by the clock select bits, TMR3CSx (T3CON<7:6>). When the TMR3CSx bits are cleared (= 00), Timer3 increments on every internal instruction cycle (Fosc/4). When TMR3CSx = 01, the Timer3 clock source is the system clock (Fosc), and when it is '10', Timer3 works as a counter from the external clock from the T3CKI pin (on the rising edge after the first falling edge) or the Timer1 oscillator.

#### 14.3 Timer3 16-Bit Read/Write Mode

Timer3 can be configured for 16-bit reads and writes (see Section 14.3 "Timer3 16-Bit Read/Write Mode"). When the RD16 control bit (T3CON<1>) is set, the address for TMR3H is mapped to a buffer register for the high byte of Timer3. A read from TMR3L will load the contents of the high byte of Timer3 into the Timer3 High Byte Buffer register. This provides the user with the ability to accurately read all 16 bits of Timer3 without having to determine whether a read of the high byte, followed by a read of the low byte, has become invalid due to a rollover between reads.

A write to the high byte of Timer3 must also take place through the TMR3H Buffer register. The Timer3 high byte is updated with the contents of TMR3H when a write occurs to TMR3L. This allows a user to write all 16 bits to both the high and low bytes of Timer3 at once.

The high byte of Timer3 is not directly readable or writable in this mode. All reads and writes must take place through the Timer3 High Byte Buffer register.

Writes to TMR3H do not clear the Timer3 prescaler. The prescaler is only cleared on writes to TMR3L.

#### 14.4 Using the Timer1 Oscillator as the Timer3 Clock Source

The Timer1 internal oscillator may be used as the clock source for Timer3. The Timer1 oscillator is enabled by setting the T1OSCEN (T1CON<3>) bit. To use it as the Timer3 clock source, the TMR3CS bit must also be set. As previously noted, this also configures Timer3 to increment on every rising edge of the oscillator source. The Timer1 oscillator is described in Section 12.0 "Timer1 Module".

#### 14.5 Timer3 Gate

Timer3 can be configured to count freely, or the count can be enabled and disabled using Timer3 gate circuitry. This is also referred to as Timer3 gate count enable.

Timer3 gate can also be driven by multiple selectable sources.


#### 14.5.1 TIMER3 GATE COUNT ENABLE

The Timer3 Gate Enable mode is enabled by setting the TMR3GE bit of the T3GCON register. The polarity of the Timer3 Gate Enable mode is configured using the T3GPOL bit of the T3GCON register.

When Timer3 Gate Enable mode is enabled, Timer3 will increment on the rising edge of the Timer3 clock source. When Timer3 Gate Enable mode is disabled, no incrementing will occur and Timer3 will hold the current count. See Figure 14-2 for timing details.

### TABLE 14-1: TIMER3 GATE ENABLE SELECTIONS

T3CLK	T3GPOL	T3G	Timer3 Operation
$\uparrow$	0	0	Counts
$\uparrow$	0	1	Holds Count
$\uparrow$	1	0	Holds Count
$\uparrow$	1	1	Counts



© 2009 Microchip Technology Inc.

#### 14.5.2 TIMER3 GATE SOURCE SELECTION

The Timer3 gate source can be selected from one of four different sources. Source selection is controlled by the T3GSSx bits of the T3GCON register. The polarity for each available source is also selectable. Polarity selection is controlled by the T3GPOL bit of the T3GCON register.

TABLE 14-2: TIMER3 GATE SOURCES

T3GSS<1:0>	Timer3 Gate Source				
00	Timer3 Gate Pin				
01	Overflow of Timer0 (TMR0 increments from FFh to 00h)				
10	TMR2 to Match PR2 (TMR2 increments to match PR2)				
11	Reserved				

#### 14.5.2.1 T3G Pin Gate Operation

The T3G pin is one source for Timer3 gate control. It can be used to supply an external source to the Timer3 gate circuitry.

#### 14.5.2.2 Timer0 Overflow Gate Operation

When Timer0 increments from FFh to 00h, a low-to-high pulse will automatically be generated and internally supplied to the Timer3 gate circuitry.

# TMR2 to Match PR2signal. See Figure 14-3 for timing details.TMR2 increments to match PR2)The T3GVAL bit will indicate when the Toggled mode is<br/>active and the timer is counting.

14.5.2.3

circuitry.

14.5.3

pulse.

Timer3 Gate Toggle mode is enabled by setting the T3GTM bit of the T3GCON register. When the T3GTM bit is cleared, the flip-flop is cleared and held clear. This is necessary in order to control which edge is measured.

Timer2 Match Gate Operation

The TMR2 register will increment until it matches the value in the PR2 register. On the very next increment

cycle, TMR2 will be reset to 00h. When this Reset


occurs, a low-to-high pulse will automatically be

generated and internally supplied to the Timer3 gate

When Timer3 Gate Toggle mode is enabled, it is possible to measure the full cycle length of a Timer3 gate signal, as opposed to the duration of a single level

The Timer1 gate source is routed through a flip-flop that changes state on every incrementing edge of the

TIMER3 GATE TOGGLE MODE



#### FIGURE 14-3: TIMER3 GATE TOGGLE MODE


#### 14.5.4 TIMER3 GATE SINGLE PULSE MODE

When Timer3 Gate Single Pulse mode is enabled, it is possible to capture a single pulse gate event. Timer3 Gate Single Pulse mode is first enabled by setting the T3GSPM bit in the T3GCON register. Next, the T3GGO/T3DONE bit in the T3GCON register must be set.

The Timer3 will be fully enabled on the next incrementing edge. On the next trailing edge of the pulse, the T3GGO/T3DONE bit will automatically be cleared. No other gate events will be allowed to increment Timer3 until the T3GGO/T3DONE bit is once again set in software.

Clearing the T3GSPM bit of the T3GCON register will also clear the T3GGO/T3DONE bit. See Figure 14-4 for timing details.

Enabling the Toggle mode and the Single Pulse mode, simultaneously, will permit both sections to work together. This allows the cycle times on the Timer3 gate source to be measured. See Figure 14-5 for timing details.



#### FIGURE 14-4: TIMER3 GATE SINGLE PULSE MODE

TMR3GE										-
										_
T3GPOL										
Г3GSPM										-
T3GTM										-
T3GG <u>O/</u> T3DONE			Software						d by Hardware Edge of T3G\	
			Enabled on lge of T3G							
T3G_IN										-
Т1СКІ				ļ						-
T3GVAL				¦ 	1 1 1 1 1	1 1 1 1	· · · · · · · · · · · · · · · · · · ·			
						1 1 1				
Timer3	Ν			N + 1	N + 2	N + 3	X	N + 4		
MR3GIF	— Clea	red by Softw	/are			by Hardwa Edge of T30			Clea Soft	

#### 14.5.5 TIMER3 GATE VALUE STATUS

When Timer3 gate value status is utilized, it is possible to read the most current level of the gate control value. The value is stored in the T3GVAL bit in the T3GCON register. The T3GVAL bit is valid even when the Timer3 gate is not enabled (TMR3GE bit is cleared).

#### 14.5.6 TIMER3 GATE EVENT INTERRUPT

When the Timer3 gate event interrupt is enabled, it is possible to generate an interrupt upon the completion of a gate event. When the falling edge of T3GVAL occurs, the TMR3GIF flag bit in the PIR3 register will be set. If the TMR3GIE bit in the PIE3 register is set, then an interrupt will be recognized.

The TMR3GIF flag bit operates even when the Timer3 gate is not enabled (TMR3GE bit is cleared).

#### 14.6 Timer3 Interrupt

The TMR3 register pair (TMR3H:TMR3L) increments from 0000h to FFFFh and overflows to 0000h. The Timer3 interrupt, if enabled, is generated on overflow and is latched in interrupt flag bit, TMR3IF (PIR2<1>). This interrupt can be enabled or disabled by setting or clearing the Timer3 Interrupt Enable bit, TMR3IE (PIE2<1>).

#### 14.7 Resetting Timer3 Using the ECCP Special Event Trigger

If ECCP1 or ECCP2 is configured to use Timer3 and to generate a Special Event Trigger in Compare mode (CCPxM<3:0> = 1011), this signal will reset Timer3.

The trigger from ECCP2 will also start an A/D conversion if the A/D module is enabled (see **Section 17.3.4 "Special Event Trigger"** for more information).

The module must be configured as either a timer or synchronous counter to take advantage of this feature. When used this way, the CCPRxH:CCPRxL register pair effectively becomes a Period register for Timer3.

If Timer3 is running in Asynchronous Counter mode, the Reset operation may not work.

In the event that a write to Timer3 coincides with a Special Event Trigger from an ECCP module, the write will take precedence.

**Note:** The Special Event Triggers from the ECCPx module will not set the TMR3IF interrupt flag bit (PIR1<0>).

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	83
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	85
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	85
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	85
TMR3L	Timer3 Register Low Byte								
TMR3H	Timer3 Register High Byte								
T1CON	TMR1CS1	TMR1CS0	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	RD16	TMR10N	84
T3CON	TMR3CS1	TMR3CS0	T3CKPS1	T3CKPS0	T3OSCEN	T3SYNC	RD16	TMR3ON	86
T3GCON	TMR3GE	T3GPOL	T3GTM	T3GSPM	T3GGO/ T3DONE	T3GVAL	T3GSS1	T3GSS0	86
TCLKCON	_		_	T1RUN	_		T3CCP2	T3CCP1	87
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	85
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	85
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	85

#### TABLE 14-3: REGISTERS ASSOCIATED WITH TIMER3 AS A TIMER/COUNTER

Legend: — = unimplemented, read as '0'. Shaded cells are not used by the Timer3 module.

NOTES:

#### 15.0 TIMER4 MODULE

The Timer4 timer module has the following features:

- 8-Bit Timer register (TMR4)
- 8-Bit Period register (PR4)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- Interrupt on TMR4 match of PR4

Timer4 has a control register shown in Register 15-1. Timer4 can be shut off by clearing control bit, TMR4ON (T4CON<2>), to minimize power consumption. The prescaler and postscaler selection of Timer4 is also controlled by this register. Figure 15-1 is a simplified block diagram of the Timer4 module.

#### 15.1 Timer4 Operation

Timer4 can be used as the PWM time base for the PWM mode of the ECCP modules. The TMR4 register is readable and writable and is cleared on any device Reset. The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits, T4CKPS<1:0> (T4CON<1:0>). The match output of TMR4 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a TMR4 interrupt, latched in flag bit, TMR4IF (PIR3<3>).

The prescaler and postscaler counters are cleared when any of the following occurs:

- · a write to the TMR4 register
- a write to the T4CON register
- any device Reset (Power-on Reset (POR), MCLR Reset, Watchdog Timer Reset (WDTR) or Brown-out Reset (BOR))

TMR4 is not cleared when T4CON is written.

#### REGISTER 15-1: T4CON: TIMER4 CONTROL REGISTER (ACCESS F76h)

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	T4OUTPS3	T4OUTPS2	T4OUTPS1	T4OUTPS0	TMR4ON	T4CKPS1	T4CKPS0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### bit 7 Unimplemented: Read as '0'

bit 6-3	<b>T4OUTPS&lt;3:0&gt;:</b> Timer4 Output Postscale Select bits 0000 = 1:1 Postscale 0001 = 1:2 Postscale
	•
	• 1111 = 1:16 Postscale
bit 2	TMR4ON: Timer4 On bit
	1 = Timer4 is on 0 = Timer4 is off
bit 1-0	T4CKPS<1:0>: Timer4 Clock Prescale Select bits
	00 = Prescaler is 1
	01 = Prescaler is 4
	1x = Prescaler is 16

#### 15.2 **Timer4 Interrupt**

The Timer4 module has an 8-bit Period register, PR4, which is both readable and writable. Timer4 increments from 00h until it matches PR4 and then resets to 00h on the next increment cycle. The PR4 register is initialized to FFh upon Reset.

#### **FIGURE 15-1: TIMER4 BLOCK DIAGRAM**

#### 4 1:1 to 1:16 T4OUTPS<3:0> Set TMR4IF Postscaler 2 TMR4 Output T4CKPS<1:0> (to PWM) TMR4/PR4 Reset Match 1:1, 1:4, 1:16 Comparator Fosc/4 TMR4 PR4 Prescaler ₽¥ ¥8 8 Internal Data Bus

15.3

is the Timer2 output.

**Output of TMR4** 

The output of TMR4 (before the postscaler) is used

only as a PWM time base for the ECCP modules. It is

not used as a baud rate clock for the MSSP modules as

#### **REGISTERS ASSOCIATED WITH TIMER4 AS A TIMER/COUNTER** TABLE 15-1:

Name	Bit 7 Bit 6 Bit 5 Bit 4 Bit 3 Bit 2 Bit 1 Bit 0								
INTCON GIE/GIEH PEIE/GIEL TMR0IE INT0IE RBIE TMR0IF INT0IF RBIF									83
IPR3	SSP2IP BCL2IP RC2IP TX2IP TMR4IP CTMUIP TMR3GIP RTCCIP								85
PIR3	R3 SSP2IF BCL2IF RC2IF TX2IF TMR4IF CTMUIF TMR3GIF RTCCIF								85
PIE3	PIE3 SSP2IE BCL2IE RC2IE TX2IE TMR4IE CTMUIE TMR3GIE RTCCIE								
TMR4	R4 Timer4 Register							86	
T4CON	N T4OUTPS3 T4OUTPS2 T4OUTPS1 T4OUTPS0 TMR4ON T4CKPS1 T4CKPS0								86
PR4 Timer4 Period Register							86		

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Timer4 module.


### 16.0 REAL-TIME CLOCK AND CALENDAR (RTCC)

The key features of the Real-Time Clock and Calendar (RTCC) module are:

- Time: hours, minutes and seconds
- 24-hour format (military time)
- Calendar: weekday, date, month and year
- Alarm configurable
- Year range: 2000 to 2099
- · Leap year correction
- BCD format for compact firmware
- · Optimized for low-power operation
- · User calibration with auto-adjust
- Calibration range: ±2.64 seconds error per month
- Requirements: external 32.768 kHz clock crystal
- Alarm pulse or seconds clock output on RTCC pin

The RTCC module is intended for applications where accurate time must be maintained for an extended period with minimum to no intervention from the CPU. The module is optimized for low-power usage in order to provide extended battery life while keeping track of time.

The module is a 100-year clock and calendar with automatic leap year detection. The range of the clock is from 00:00:00 (midnight) on January 1, 2000 to 23:59:59 on December 31, 2099. Hours are measured in 24-hour (military time) format. The clock provides a granularity of one second with half-second visibility to the user.



#### FIGURE 16-1: RTCC BLOCK DIAGRAM

### 16.1 RTCC MODULE REGISTERS

The RTCC module registers are divided into following categories:

#### **RTCC Control Registers**

- RTCCFG
- RTCCAL
- PADCFG1
- ALRMCFG
- ALRMRPT

#### **RTCC Value Registers**

- RTCVALH and RTCVALL Can access the following registers
  - YEAR
  - MONTH
  - DAY
  - WEEKDAY
  - HOUR
  - MINUTE
  - SECOND

#### **Alarm Value Registers**

- ALRMVALH and ALRMVALL Can access the following registers:
  - ALRMMNTH
  - ALRMDAY
  - ALRMWD
  - ALRMHR
  - ALRMMIN
  - ALRMSEC
- Note: The RTCVALH and RTCVALL registers can be accessed through RTCRPT<1:0>. ALRMVALH and ALRMVALL can be accessed through ALRMPTR<1:0>.

#### 16.1.1 RTCC CONTROL REGISTERS

### REGISTER 16-1: RTCCFG: RTCC CONFIGURATION REGISTER (BANKED F3Fh)<sup>(1)</sup>

						,	
R/W-0		R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0
RTCEN	<sup>2)</sup> —	RTCWREN	RTCSYNC	HALFSEC <sup>(3)</sup>	RTCOE	RTCPTR1	RTCPTR0
bit 7							bit 0
Legend:							
R = Reada	able bit	W = Writable	bit	U = Unimplem	nented bit, read	d as '0'	
-n = Value	at POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unki	nown
h:+ <b>7</b>							
bit 7		TCC Enable bit <sup>(2)</sup> module is enable					
		module is disable					
bit 6		ented: Read as '					
bit 5	-	I: RTCC Value Re		Enable bit			
		ALH and RTCVAL	-		by the user		
	0 = RTCVA	ALH and RTCVAL	L registers a	re locked out fro	om being writte	n to by the use	r
bit 4	RTCSYNC	: RTCC Value Re	gisters Read	Synchronization	n bit		
		ALH, RTCVALL ar		T registers can	change while r	eading due to a	rollover ripple
		ng in an invalid da er is read twice a		he same data t	the data can h	e assumed to b	e valid
		ALH, RTCVALL of					
bit 3		Half-Second Sta		U			
		d half period of a					
		alf period of a sec					
bit 2		TCC Output Enat					
		clock output enal clock output disa					
bit 1-0	RTCPTR<1	I:0>: RTCC Value	e Register Wi	ndow Pointer bi	ts		
		e corresponding F					
		R<1:0> value dec	rements on e	very read or writ	e of RTCVALH	I until it reaches	·'00'.
	00 = Minute						
	01 = Week						
	10 <b>= Month</b>	•					
	11 <b>= Reser</b>						
	RTCVAL<7						
	00 = Secor 01 = Hours						
	10 <b>= Day</b>						
	11 <b>= Year</b>						
Note 1:	The RTCCFG re	egister is only affe	cted by a PO	R.			
2:		CEN bit is only a	-				
-							

3: This bit is read-only. It is cleared to '0' on a write to the lower half of the MINSEC register.

# PIC18F46J50 FAMILY

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
CAL7	CAL6	CAL5	CAL4	CAL3	CAL2	CAL1	CAL0
bit 7							bit 0
Legend:							
R = Readat	ole bit	W = Writable	bit	U = Unimpler	nented bit, read	l as '0'	
-n = Value a	at POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown
	•						
bit 7-0	01111111 =	TC Drift Calibra Maximum posi		nt; adds 508 R <sup>:</sup>	TC clock pulses	s every minute	
		•		nt; adds four R1	C clock pulses	every minute	
		No adjustment Minimum nega		ent; subtracts fo	ur RTC clock p	ulses every mir	nute
	10000000 <del>-</del>	Maximum peg	ativa adiustma	ent: subtracts 5	12 RTC clock n	ulses every mi	nute
10000000 = Maximum negative adjustment; subtracts 512 RTC clock pulses every minute							

#### REGISTER 16-2: RTCCAL: RTCC CALIBRATION REGISTER (BANKED F3Eh)


#### REGISTER 16-3: PADCFG1: PAD CONFIGURATION REGISTER (BANKED F3Ch)

		U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
bit 7 bi		—	—		—	—	RTSECSEL1 <sup>(1)</sup>	RTSECSEL0 <sup>(1)</sup>	PMPTTL
	bit	7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

implemented: Read as '0'
implemented: Read as '0'

- bit 2-1 RTSECSEL<1:0>: RTCC Seconds Clock Output Select bits<sup>(1)</sup>
  - 11 = Reserved. Do not use
    - 10 = RTCC source clock is selected for the RTCC pin (pin can be INTRC or T1OSC, depending on the RTCOSC (CONFIG3L<1>) setting)
    - 01 = RTCC seconds clock is selected for the RTCC pin
    - 00 = RTCC alarm pulse is selected for the RTCC pin
- bit 0 PMPTTL: PMP Module TTL Input Buffer Select bit
  - 1 = PMP module uses TTL input buffers
  - 0 = PMP module uses Schmitt input buffers



#### REGISTER 16-4: ALRMCFG: ALARM CONFIGURATION REGISTER (ACCESS F91h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
ALRMEN	CHIME	AMASK3	AMASK2	AMASK1	AMASK0	ALRMPTR1	ALRMPTR0
bit 7							bit 0
Legend:							
R = Readable		W = Writable		-	mented bit, read		
-n = Value at	POR	'1' = Bit is set		'0' = Bit is cle	eared	x = Bit is unki	nown
bit 7	AI RMFN: A	larm Enable bit					
		enabled (cleare	d automatical	ly after an aları	m event whenev	ver ARPT<7:0>	= 0000 0000
		ME = 0)		,			
	0 = Alarm is	disabled					
bit 6	CHIME: Chir	ne Enable bit					
		s enabled; ARP s disabled; ARP				h to FFh	
bit 5-2		>: Alarm Mask			each oon		
DIL 5-2		ry half second	Comguration	DIIS			
	0000 = Eve						
		ry 10 seconds					
	0011 = Eve						
		ry 10 minutes					
	0101 = Eve	•					
	0110 = Onc 0111 = Onc	•					
	1000 = Onc						
		e a year (excep	t when config	ured for Febru	ary 29 <sup>th</sup> , once e	every four years	6)
		erved – do not				5 5	,
	11xx = Res	erved – do not	use				
bit 1-0	ALRMPTR<	1:0>: Alarm Val	ue Register W	/indow Pointer	bits		
		e corresponding e ALRMPTR<1:					
	ALRMVAL<1	5.9~.					
	00 = ALRMN						
	01 = ALRMV						
	10 = ALRMN	INTH					
	11 = Unimple	emented					
	<u>ALRMVAL&lt;7</u>						
	00 = ALRMS						
	01 = ALRMH						
	10 = ALRME 11 = Unimple						

# PIC18F46J50 FAMILY

.

#### REGISTER 16-5: ALRMRPT: ALARM CALIBRATION REGISTER (ACCESS F90h)

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| ARPT7 | ARPT6 | ARPT5 | ARPT4 | ARPT3 | ARPT2 | ARPT1 | ARPT0 |
| bit 7 |       |       |       |       |       |       | bit 0 |
|       |       |       |       |       |       |       |       |

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-0 ARPT<7:0>: Alarm Repeat Counter Value bits 11111111 = Alarm will repeat 255 more times

.

00000000 = Alarm will not repeat

The counter decrements on any alarm event. The counter is prevented from rolling over from 00h to FFh unless CHIME = 1.

#### 16.1.2 RTCVALH AND RTCVALL REGISTER MAPPINGS

#### REGISTER 16-6: RESERVED REGISTER (ACCESS F99h, PTR 11b)

U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	
_	_	—	-	—	—	—	—	
bit 7							bit 0	
Legend:								
R = Readable bit W = Writable bit			bit	U = Unimplemented bit, read as '0'				
-n = Value at POR '1' = Bit is set			'0' = Bit is cleared x = Bit is unknown			nown		

bit 7-0 Unimplemented: Read as '0'

#### REGISTER 16-7: YEAR: YEAR VALUE REGISTER (ACCESS F98h, PTR 11b)<sup>(1)</sup>

| R/W-x  |
|--------|--------|--------|--------|--------|--------|--------|--------|
| YRTEN3 | YRTEN2 | YRTEN1 | YRTEN0 | YRONE3 | YRONE2 | YRONE1 | YRONE0 |
| bit 7  |        |        |        |        |        |        | bit 0  |

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-4YRTEN<3:0>: Binary Coded Decimal Value of Year's Tens Digit bits<br/>Contains a value from 0 to 9.bit 3-0YRONE<3:0>: Binary Coded Decimal Value of Year's Ones Digit bits

Contains a value from 0 to 9.

**Note 1:** A write to the YEAR register is only allowed when RTCWREN = 1.

#### REGISTER 16-8: MONTH: MONTH VALUE REGISTER (ACCESS F99h, PTR 10b)<sup>(1)</sup>

U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
—	—	—	MTHTEN0	MTHONE3	MTHONE2	MTHONE1	MTHONE0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-5 Unimplemented: Read as '0'

bit 4 **MTHTEN0:** Binary Coded Decimal Value of Month's Tens Digit bit Contains a value of 0 or 1.

bit 3-0 **MTHONE<3:0>:** Binary Coded Decimal Value of Month's Ones Digit bits Contains a value from 0 to 9.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	
	—	DAYTEN1	DAYTEN0	DAYONE3	DAYONE2	DAYONE1	DAYONE0	
bit 7		-					bit 0	
Legend:								
R = Readab	ole bit	W = Writable	bit	U = Unimplemented bit, read as '0'				
-n = Value a	= Value at POR '1' = Bit is set			'0' = Bit is cleared x = Bit is unknown			nown	
bit 7-6	Unimplemen	ted: Read as '	0'					
bit 5-4	DAYTEN<1:0>: Binary Coded Decimal value of Day's Tens Digit bits							

#### REGISTER 16-9: DAY: DAY VALUE REGISTER (ACCESS F98h, PTR 10b)<sup>(1)</sup>

bit 5-4 **DAYTEN<1:0>:** Binary Coded Decimal va Contains a value from 0 to 3.

bit 3-0	DAYONE<3:0>: Binary Coded Decimal Value of Day's Ones Digit bits
	Contains a value from 0 to 9.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

#### REGISTER 16-10: WKDY: WEEKDAY VALUE REGISTER (ACCESS F99h, PTR 01b)<sup>(1)</sup>

U-0	U-0	U-0	U-0	U-0	R/W-x	R/W-x	R/W-x
—	—	—	—	—	WDAY2	WDAY1	WDAY0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	l as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-3 Unimplemented: Read as '0'

bit 2-0 **WDAY<2:0>:** Binary Coded Decimal Value of Weekday Digit bits Contains a value from 0 to 6.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

#### REGISTER 16-11: HOURS: HOURS VALUE REGISTER (ACCESS F98h, PTR 01b)<sup>(1)</sup>

U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
—	—	HRTEN1	HRTEN0	HRONE3	HRONE2	HRONE1	HRONE0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, rea	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-6	Unimplemented: Read as '0'
bit 5-4	<b>HRTEN&lt;1:0&gt;:</b> Binary Coded Decimal Value of Hour's Tens Digit bits Contains a value from 0 to 2.
bit 3-0	<b>HRONE&lt;3:0&gt;:</b> Binary Coded Decimal Value of Hour's Ones Digit bits Contains a value from 0 to 9.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

#### REGISTER 16-12: MINUTES: MINUTES VALUE REGISTER (ACCESS F99h, PTR 00b)

U-0	R/W-x						
—	MINTEN2	MINTEN1	MINTEN0	MINONE3	MINONE2	MINONE1	MINONE0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	Unimplemented: Read as '0'
bit 6-4	<b>MINTEN&lt;2:0&gt;:</b> Binary Coded Decimal Value of Minute's Tens Digit bits Contains a value from 0 to 5.
bit 3-0	MINONE<3:0>: Binary Coded Decimal Value of Minute's Ones Digit bits Contains a value from 0 to 9.

#### REGISTER 16-13: SECONDS: SECONDS VALUE REGISTER (ACCESS F98h, PTR 00b)

U-0	R/W-x						
—	SECTEN2	SECTEN1	SECTEN0	SECONE3	SECONE2	SECONE1	SECONE0
bit 7							bit 0

Legend:				
R = Reada	ible bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown
bit 7	Unimple	mented: Read as '0'		
bit 6-4		<2:0>: Binary Coded Decim a value from 0 to 5.	nal Value of Second's Tens Dig	jit bits
	0500115			

bit 3-0 SECONE<3:0>: Binary Coded Decimal Value of Second's Ones Digit bits Contains a value from 0 to 9.

#### 16.1.3 ALRMVALH AND ALRMVALL REGISTER MAPPINGS

### REGISTER 16-14: ALRMMNTH: ALARM MONTH VALUE REGISTER (ACCESS F8Fh, PTR 10b)<sup>(1)</sup>

U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x				
	MTHTEN0 MTHONE3 MTHONE2 MTHONE1 MTHONE0										
bit 7							bit 0				
Legend:											
R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'											
-n = Value at POR '1' = Bit is set		t	'0' = Bit is cleared		x = Bit is unknown						
bit 7-5	Unimplemen	ted: Read as '	0'								
bit 4	<b>MTHTEN0:</b> Binary Coded Decimal Value of Month's Tens Digit bit Contains a value of 0 or 1.										
bit 3-0	MTHONE<3:0>: Binary Coded Decimal Value of Month's Ones Digit bits Contains a value from 0 to 9.										

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

#### REGISTER 16-15: ALRMDAY: ALARM DAY VALUE REGISTER (ACCESS F8Eh, PTR 10b)<sup>(1)</sup>

U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
—	—	DAYTEN1	DAYTEN0	DAYONE3	DAYONE2	DAYONE1	DAYONE0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	l as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-6 Unimplemented: Read as '0'

bit 5-4	DAYTEN<1:0>: Binary Coded Decimal Value of Day's Tens Digit bits
	Contains a value from 0 to 3.

bit 3-0 **DAYONE<3:0>:** Binary Coded Decimal Value of Day's Ones Digit bits Contains a value from 0 to 9.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

### REGISTER 16-16: ALRMWD: ALARM WEEKDAY VALUE REGISTER (ACCESS F8Fh, PTR 01b)<sup>(1)</sup>

—         —         —         WDAY2         WDAY1         WDAY0           bit 7         bit	U-0	U-0	U-0	U-0	U-0	R/W-x	R/W-x	R/W-x
bit 7 bit	—	—		—	—	WDAY2	WDAY1	WDAY0
	bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-3 Unimplemented: Read as '0'

bit 2-0 **WDAY<2:0>:** Binary Coded Decimal Value of Weekday Digit bits Contains a value from 0 to 6.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

### REGISTER 16-17: ALRMHR: ALARM HOURS VALUE REGISTER (ACCESS F8Eh, PTR 01b)<sup>(1)</sup>

U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
—	—	HRTEN1	HRTEN0	HRONE3	HRONE2	HRONE1	HRONE0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	l as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-6	Unimplemented: Read as '0'
bit 5-4	<b>HRTEN&lt;1:0&gt;:</b> Binary Coded Decimal Value of Hour's Tens Digit bits Contains a value from 0 to 2.
bit 3-0	<b>HRONE3:HRONE0:</b> Binary Coded Decimal Value of Hour's Ones Digit bits Contains a value from 0 to 9.

**Note 1:** A write to this register is only allowed when RTCWREN = 1.

U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
	MINTEN2	MINTEN1	MINTEN0	MINONE3	MINONE2	MINONE1	MINONE0
bit 7				•		•	bit 0
Legend:							
R = Readat	ole bit	W = Writable	bit	U = Unimpler	mented bit, read	l as '0'	
-n = Value a	at POR	'1' = Bit is set	:	'0' = Bit is cle	ared	x = Bit is unkr	nown
bit 7	Unimplemer	nted: Read as '	0'				
bit 6-4	6-4 MINTEN<2:0>: Binary Coded Decimal Valu Contains a value from 0 to 5.			lue of Minute's	Tens Digit bits		

#### REGISTER 16-18: ALRMMIN: ALARM MINUTES VALUE REGISTER (ACCESS F8Fh, PTR 00b)

Com	
	<b>ONE&lt;3:0&gt;:</b> Binary Coded Decimal Value of Minute's Ones Digit bits dains a value from 0 to 9.

#### REGISTER 16-19: ALRMSEC: ALARM SECONDS VALUE REGISTER (ACCESS F8Eh, PTR 00b)

U-0	R/W-x						
—	SECTEN2	SECTEN1	SECTEN0	SECONE3	SECONE2	SECONE1	SECONE0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7 Unimplemented: Read as '0'

bit 6-4 SECTEN<2:0>: Binary Coded Decimal Value of Second's Tens Digit bits Contains a value from 0 to 5.

bit 3-0 SECONE<3:0>: Binary Coded Decimal Value of Second's Ones Digit bits Contains a value from 0 to 9.

#### 16.1.4 RTCEN BIT WRITE

An attempt to write to the RTCEN bit while RTCWREN = 0 will be ignored. RTCWREN must be set before a write to RTCEN can take place.


Like the RTCEN bit, the RTCVALH and RTCVALL registers can only be written to when RTCWREN = 1. A write to these registers, while RTCWREN = 0, will be ignored.

FIGURE 16-2: TIMER DIGIT FORMAT


#### 16.2 Operation

#### 16.2.1 REGISTER INTERFACE

The register interface for the RTCC and alarm values is implemented using the Binary Coded Decimal (BCD) format. This simplifies the firmware, when using the module, as each of the digits is contained within its own 4-bit value (see Figure 16-2 and Figure 16-3).




#### FIGURE 16-3: ALARM DIGIT FORMAT



#### 16.2.2 CLOCK SOURCE

As mentioned earlier, the RTCC module is intended to be clocked by an external Real-Time Clock crystal oscillating at 32.768 kHz, but also can be clocked by the INTRC. The RTCC clock selection is decided by the RTCOSC bit (CONFIG3L<1>).

FIGURE 16-4: CLOCK SOURCE MULTIPLEXING



#### 16.2.2.1 Real-Time Clock Enable

The RTCC module can be clocked by an external, 32.768 kHz crystal (Timer1 oscillator or T1CKI input) or the INTRC oscillator, which can be selected in CONFIG3L<1>.

If the Timer1 oscillator will be used as the clock source for the RTCC, make sure to enable it by setting T1CON<3> (T1OSCEN). The selected RTC clock can be brought out to the RTCC pin by the RTSECSEL<1:0> bits in the PADCFG register.

#### 16.2.3 DIGIT CARRY RULES

This section explains which timer values are affected when there is a rollover.

- Time of Day: From 23:59:59 to 00:00:00 with a carry to the Day field
- Month: From 12/31 to 01/01 with a carry to the Year field
- Day of Week: From 6 to 0 with no carry (see Table 16-1)
- Year Carry: From 99 to 00; this also surpasses the use of the RTCC

For the day to month rollover schedule, see Table 16-2.

Calibration of the crystal can be done through this

module to yield an error of 3 seconds or less per month.

(For further details, see Section 16.2.9 "Calibration".)

Considering that the following values are in BCD format, the carry to the upper BCD digit will occur at a count of 10 and not at 16 (SECONDS, MINUTES, HOURS, WEEKDAY, DAYS and MONTHS).

TABLE 16-1:	DAY OF WEEK SCHEDULE
-------------	----------------------

Day of Week		
Sunday	0	
Monday	1	
Tuesday	2	
Wednesday	3	
Thursday	4	
Friday	5	
Saturday	6	

### TABLE 16-2:DAY TO MONTH ROLLOVER<br/>SCHEDULE

Month	Maximum Day Field
01 (January)	31
02 (February)	28 or 29 <sup>(1)</sup>
03 (March)	31
04 (April)	30
05 (May)	31
06 (June)	30
07 (July)	31
08 (August)	31
09 (September)	30
10 (October)	31
11 (November)	30
12 (December)	31

Note 1: See Section 16.2.4 "Leap Year".

#### 16.2.4 LEAP YEAR

Since the year range on the RTCC module is 2000 to 2099, the leap year calculation is determined by any year divisible by '4' in the above range. Only February is effected in a leap year.

February will have 29 days in a leap year and 28 days in any other year.

#### 16.2.5 GENERAL FUNCTIONALITY

All timer registers containing a time value of seconds or greater are writable. The user configures the time by writing the required year, month, day, hour, minutes and seconds to the timer registers, via Register Pointers (see **Section 16.2.8 "Register Mapping"**).

The timer uses the newly written values and proceeds with the count from the required starting point.

The RTCC is enabled by setting the RTCEN bit (RTCCFGL<7>). If enabled, while adjusting these registers, the timer still continues to increment. However, any time the MINSEC register is written to, both of the timer prescalers are reset to '0'. This allows fraction of a second synchronization.

The Timer registers are updated in the same cycle as the write instruction's execution by the CPU. The user must ensure that when RTCEN = 1, the updated registers will not be incremented at the same time. This can be accomplished in several ways:

- By checking the RTCSYNC bit (RTCCFG<4>)
- By checking the preceding digits from which a carry can occur
- By updating the registers immediately following the seconds pulse (or alarm interrupt)

The user has visibility to the half-second field of the counter. This value is read-only and can be reset only by writing to the lower half of the SECONDS register.

#### 16.2.6 SAFETY WINDOW FOR REGISTER READS AND WRITES

The RTCSYNC bit indicates a time window during which the RTCC Clock Domain registers can be safely read and written without concern about a rollover. When RTCSYNC = 0, the registers can be safely accessed by the CPU.

Whether RTCSYNC = 1 or 0, the user should employ a firmware solution to ensure that the data read did not fall on a rollover boundary, resulting in an invalid or partial read. This firmware solution would consist of reading each register twice and then comparing the two values. If the two values matched, then, a rollover did not occur.

#### 16.2.7 WRITE LOCK

In order to perform a write to any of the RTCC timer registers, the RTCWREN bit (RTCCFG<5>) must be set.

To avoid accidental writes to the RTCC Timer register, it is recommended that the RTCWREN bit (RTCCFG<5>) be kept clear at any time other than while writing to. For the RTCWREN bit to be set, there is only one instruction cycle time window allowed between the 55h/AA sequence and the setting of RTCWREN. For that reason, it is recommended that users follow the code example in Example 16-1.

#### EXAMPLE 16-1: SETTING THE RTCWREN BIT

movlb	0x0F	;RTCCFG is banked
bcf	INTCON, GIE	;Disable interrupts
movlw	0x55	
movwf	EECON2	
movlw	0 xAA	
movwf	EECON2	
bsf	RTCCFG, RTCWRE	IN

#### 16.2.8 REGISTER MAPPING

To limit the register interface, the RTCC Timer and Alarm Timer registers are accessed through corresponding register pointers. The RTCC Value register window (RTCVALH<15:8> and RTCVALL<7:0>) uses the RTCPTR bits (RTCCFG<1:0>) to select the required Timer register pair.

By reading or writing to the RTCVALH register, the RTCC Pointer value (RTCPTR<1:0>) decrements by 1 until it reaches '00'. Once it reaches '00', the MINUTES and SECONDS value will be accessible through RTCVALH and RTCVALL until the pointer value is manually changed.

### TABLE 16-3:RTCVALH AND RTCVALLREGISTER MAPPING

RTCPTR<1:0>	RTCC Value Register Window			
RICPIR-1.02	RTCVAL<15:8>	RTCVAL<7:0>		
00	MINUTES	SECONDS		
01	WEEKDAY	HOURS		
10	MONTH	DAY		
11		YEAR		

The Alarm Value register window (ALRMVALH and ALRMVALL) uses the ALRMPTR bits (ALRMCFG<1:0>) to select the desired Alarm register pair.

By reading or writing to the ALRMVALH register, the Alarm Pointer value, ALRMPTR<1:0>, decrements by 1 until it reaches '00'. Once it reaches '00', the ALRMMIN and ALRMSEC value will be accessible through ALRMVALH and ALRMVALL until the pointer value is manually changed.

TABLE 16-4:	ALRMVAL REGISTER
	MAPPING

ALRMPTR<1:0>	Alarm Value Register Window					
ALRIVIPTR-1.02	ALRMVAL<15:8>	ALRMVAL<7:0>				
0.0	ALRMMIN	ALRMSEC				
01	ALRMWD	ALRMHR				
10	ALRMMNTH	ALRMDAY				
11		—				

#### 16.2.9 CALIBRATION

The real-time crystal input can be calibrated using the periodic auto-adjust feature. When properly calibrated, the RTCC can provide an error of less than three seconds per month.

To perform this calibration, find the number of error clock pulses and store the value in the lower half of the RTCCAL register. The 8-bit, signed value – loaded into RTCCAL – is multiplied by '4' and will either be added or subtracted from the RTCC timer, once every minute.

To calibrate the RTCC module:

- 1. Use another timer resource on the device to find the error of the 32.768 kHz crystal.
- 2. Convert the number of error clock pulses per minute (see Equation 16-1).

#### EQUATION 16-1: CONVERTING ERROR CLOCK PULSES

(Ideal Frequency (32,758) – Measured Frequency) \* 60 = Error Clocks per Minute

- If the oscillator is *faster* than ideal (negative result from step 2), the RCFGCALL register value needs to be negative. This causes the specified number of clock pulses to be subtracted from the timer counter once every minute.
- If the oscillator is *slower* than ideal (positive result from step 2), the RCFGCALL register value needs to be positive. This causes the specified number of clock pulses to be added to the timer counter once every minute.
- 3. Load the RTCCAL register with the correct value.

Writes to the RTCCAL register should occur only when the timer is turned off, or immediately after the rising edge of the seconds pulse.

Note:	In determining the crystal's error value, it is the user's responsibility to include the
	crystal's initial error from drift due to temperature or crystal aging.

#### 16.3 Alarm

The alarm features and characteristics are:

- · Configurable from half a second to one year
- Enabled using the ALRMEN bit (ALRMCFG<7>, Register 16-4)
- · Offers one-time and repeat alarm options

#### 16.3.1 CONFIGURING THE ALARM

The alarm feature is enabled using the ALRMEN bit.

This bit is cleared when an alarm is issued. The bit will not be cleared if the CHIME bit = 1 or if ALRMRPT  $\neq 0$ .

The interval selection of the alarm is configured through the ALRMCFG bits (AMASK<3:0>). (See Figure 16-5.) These bits determine which and how many digits of the alarm must match the clock value for the alarm to occur.

The alarm can also be configured to repeat based on a preconfigured interval. The number of times this occurs after the alarm is enabled is stored in the ALRMRPT register.

Note: While the alarm is enabled (ALRMEN = 1), changing any of the registers – other than the RTCCAL, ALRMCFG and ALRMRPT registers and the CHIME bit – can result in a false alarm event leading to a false alarm interrupt. To avoid this, only change the timer and alarm values while the alarm is disabled (ALRMEN = 0). It is recommended that the ALRMCFG and ALRMRPT registers and CHIME bit be changed when RTCSYNC = 0.

Alarm Mask Setting AMASK3:AMASK0	Day of the Week	Month Day	Hours	Minutes Seconds		
0000 – Every half second 0001 – Every second				:		
0010 – Every 10 seconds				:		
0011 – Every minute				: : : : : :		
0100 – Every 10 minutes				: m : s s		
0101 – Every hour				: m m : s s		
0110 <b>– Every day</b>			hh	: m m : s s		
0111 – Every week	d		h h	: m m : s s		
1000 – Every month		/ d	h h	: m m : s s		
1001 – Every year <sup>(1)</sup>		m m / d d	hh	: m m : s s		
<b>Note 1:</b> Annually, except when configured for February 29.						

#### FIGURE 16-5: ALARM MASK SETTINGS

# PIC18F46J50 FAMILY

When ALRMCFG = 00 and the CHIME bit = 0 (ALRMCFG<6>), the repeat function is disabled and only a single alarm will occur. The alarm can be repeated up to 255 times by loading the ALRMRPT register with FFh.

After each alarm is issued, the ALRMRPT register is decremented by one. Once the register has reached '00', the alarm will be issued one last time.

After the alarm is issued a last time, the ALRMEN bit is cleared automatically and the alarm turned off. Indefinite repetition of the alarm can occur if the CHIME bit = 1.

When CHIME = 1, the alarm is not disabled when the ALRMRPT register reaches '00', but it rolls over to FF and continues counting indefinitely.

#### 16.3.2 ALARM INTERRUPT


At every alarm event, an interrupt is generated. Additionally, an alarm pulse output is provided that operates at half the frequency of the alarm.

The alarm pulse output is completely synchronous with the RTCC clock and can be used as a trigger clock to other peripherals. This output is available on the RTCC pin. The output pulse is a clock with a 50% duty cycle and a frequency half that of the alarm event (see Figure 16-6).

The RTCC pin also can output the seconds clock. The user can select between the alarm pulse, generated by the RTCC module, or the seconds clock output.

The RTSECSEL (PADCFG1<2:1>) bits select between these two outputs:

- Alarm pulse RTSECSEL<2:1> = 00
- Seconds clock RTSECSEL<2:1> = 0



#### 16.4 Low-Power Modes

The timer and alarm can optionally continue to operate while in Sleep, Idle and even Deep Sleep mode. An alarm event can be used to wake-up the microcontroller from any of these Low-Power modes.

#### 16.5 Reset

#### 16.5.1 DEVICE RESET

When a device Reset occurs, the ALCFGRPT register is forced to its Reset state causing the alarm to be disabled (if enabled prior to the Reset). If the RTCC was enabled, it will continue to operate when a basic device Reset occurs.

#### 16.5.2 POWER-ON RESET (POR)

The RTCCFG and ALRMRPT registers are reset only on a POR. Once the device exits the POR state, the clock registers should be reloaded with the desired values.

The timer prescaler values can be reset only by writing to the SECONDS register. No device Reset can affect the prescalers.

#### 16.6 Register Maps

Table 16-5, Table 16-6 and Table 16-7 summarize the registers associated with the RTCC module.

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	All Resets
RTCCFG	RTCEN	_	RTCWREN	RTCSYNC	HALFSEC	RTCOE	RTCPTR1	RTCPTR0	0000
RTCCAL	CAL7	CAL6	CAL5	CAL4	CAL3	CAL2	CAL1	CAL0	0000
PADCFG1	_	_	_	—	_	RTSECSEL1	RTSECSEL0	PMPTTL	0000
ALRMCFG	ALRMEN	CHIME	AMASK3	AMASK2	AMASK1	AMASK0	ALRMPTR1	ALRMPTR0	0000
ALRMRPT	ARPT7	ARPT6	ARPT5	ARPT4	ARPT3	ARPT2	ARPT1	ARPT0	0000
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCCIF	0000
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCCIE	0000
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCCIP	0000

#### TABLE 16-5: RTCC CONTROL REGISTERS

Legend: — = unimplemented, read as '0'. Reset values are shown in hexadecimal for 44-pin devices.

#### TABLE 16-6: RTCC VALUE REGISTERS

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	All Resets
RTCVALH	RTCC Value Register Window High Byte, Based on RTCPTR<1:0>							XXXX	
RTCVALL	RTCC Value	Register Wi	indow Low By	/te, Based or	n RTCPTR<1	:0>			XXXX
RTCCFG	RTCEN		RTCWREN	RTCSYNC	HALFSEC	RTCOE	RTCPTR1	RTCPTR0	0000
ALRMCFG	ALRMEN	CHIME	AMASK3	AMASK2	AMASK1	AMASK0	ALRMPTR1	ALRMPTR0	0000
ALRMVALH	Alarm Value Register Window High Byte, Based on ALRMPTR<1:0>						XXXX		
ALRMVALL	Alarm Value	Alarm Value Register Window Low Byte, Based on ALRMPTR<1:0>							XXXX

Legend: — = unimplemented, read as '0'. Reset values are shown in hexadecimal for 44-pin devices.

#### TABLE 16-7: ALARM VALUE REGISTERS

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	All Resets
ALRMRPT	ARPT7	ARPT6	ARPT5	ARPT4	ARPT3	ARPT2	ARPT1	ARPT0	0000
ALRMVALH	Alarm Value R	Alarm Value Register Window High Byte, Based on ALRMPTR<1:0>							
ALRMVALL	Alarm Value R	egister Windo	w Low Byte, E	Based on ALF	RMPTR<1:0>				XXXX
RTCCAL	CAL7	CAL6	CAL5	CAL4	CAL3	CAL2	CAL1	CAL0	0000
RTCVALH	RTCC Value R	RTCC Value Register Window High Byte, Based on RTCPTR<1:0>							XXXX
RTCVALL	RTCC Value R	RTCC Value Register Window Low Byte, Based on RTCPTR<1:0>							

**Legend:** — = unimplemented, read as '0'. Reset values are shown in hexadecimal for 44-pin devices.

### PIC18F46J50 FAMILY

NOTES:

### 17.0 ENHANCED CAPTURE/COMPARE/PWM (ECCP) MODULE

PIC18F46J50 Family devices have two Enhanced Capture/Compare/PWM (ECCP) modules: ECCP1 and ECCP2. These modules contain a 16-bit register, which can operate as a 16-bit Capture register, a 16-bit Compare register or a PWM Master/Slave Duty Cycle register. These ECCP modules are upward compatible with CCP

Note: Register and bit names referencing one of the two ECCP modules substitute an 'x' for the module number. For example, registers CCP1CON and CCP2CON, which have the same definitions, are called CCPxCON. Figures and diagrams use ECCP1-based names, but those names also apply to ECCP2, with a "2" replacing the illustration name's "1". When writing firmware, the "x" in register and bit names must be replaced with the appropriate module number. ECCP1 and ECCP2 are implemented as standard CCP modules with enhanced PWM capabilities. These include:

- Provision for two or four output channels
- · Output Steering modes
- · Programmable polarity
- Programmable dead-band control
- · Automatic shutdown and restart

The enhanced features are discussed in detail in Section 17.5 "PWM (Enhanced Mode)".

**Note:** PxA, PxB, PxC and PxD are associated with the remappable pins (RPn).

# PIC18F46J50 FAMILY

### REGISTER 17-1: CCPxCON: ENHANCED CAPTURE/COMPARE/PWM x CONTROL REGISTER (ACCESS FBAh, FB4h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
PxM1	PxM0	DCxB1	DCxB0	CCPxM3	CCPxM2	CCPxM1	CCPxM0
bit 7							bit 0

Legend:								
R = Reada	ole bit	W = Writable bit	U = Unimplemented bit	, read as '0'				
-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown				
bit 7-6	PxM<1:0>: ⊟	nhanced PWM Output 0	Configuration bits					
		<u>2&gt; = 00, 01, 10:</u>	·					
	xx = PxA as	signed as capture/comp	are input/output; PxB, PxC ar	nd PxD assigned as port pins				
	If CCPxM<3:							
	•		id PxD controlled by steering (s	see Section 17.5.7 "Pulse Steering				
		/	modulated: DvA active: DvD	ByC inactive				
			) modulated; PxA active; PxB, modulated with dead-band c	ontrol; PxC and PxD assigned as				
	port pi	•						
	11 = Full-bri	dge output reverse: PxB	modulated; PxC active; PxA	and PxD inactive				
bit 5-4	DCxB<1:0>:	PWM Duty Cycle bit 1 a	nd bit 0					
	Capture mod	<u>e:</u>						
	Unused.							
		Compare mode:						
	Unused.							
	<u>PWM mode:</u> These bits are the two LSbs of the 10-bit PWM duty cycle. The eight MSbs of the duty cycle are found							
	in CCPRxL.		-bit PVVIVI duty cycle. The eigh	it MSbs of the duty cycle are found				
bit 3-0		ECCPx Mode Select b	vite					
Dit 5-0		ture/Compare/PWM off						
	0000 - Cap	•						
		npare mode, toggle outp	ut on match					
	0011 = Cap							
		ture mode, every falling						
		ture mode, every rising e ture mode, every 4 <sup>th</sup> risi						
	0110 = Cap	ture mode, every 4 This ture mode, every 16 <sup>th</sup> ris	ng euge sina edae					
			CPx pin low, set output on co	ompare match (set CCPxIF)				
				compare match (set CCPxIF)				
			oftware interrupt only, ECCPx					
			cial event (ECCPx resets TMF	R1 or TMR3, starts A/D conversion				
		CCxIF bit)	ctive-high; PxB and PxD activ	ve-high				
			ictive-high; PxB and PxD active-high; PxB and PxD active					
			ctive-low; PxB and PxD active					
			ctive-low; PxB and PxD active					

In addition to the expanded range of modes available through the CCPxCON and ECCPxAS registers, the ECCP modules have two additional registers associated with Enhanced PWM operation and auto-shutdown features. They are:

- ECCPxDEL (Enhanced PWM Control)
- PSTRxCON (Pulse Steering Control)

#### 17.1 ECCP Outputs and Configuration

The Enhanced CCP module may have up to four PWM outputs, depending on the selected operating mode. These outputs, designated PxA through PxD, are routed through the Peripheral Pin Select (PPS) module. Therefore, individual functions may be mapped to any of the remappable I/O pins, RPn. The outputs that are active depend on the ECCP operating mode selected. The pin assignments are summarized in Table 17-4.

To configure the I/O pins as PWM outputs, the proper PWM mode must be selected by setting the PxM<1:0> and CCPxM<3:0> bits. The appropriate TRIS direction bits for the port pins must also be set as outputs and the output functions need to be assigned to I/O pins in the PPS module. (For details on configuring the module, see **Section 9.7 "Peripheral Pin Select (PPS)"**.)

#### 17.1.1 ECCP MODULE AND TIMER RESOURCES

The ECCP modules utilize Timers 1, 2, 3 or 4, depending on the mode selected. Timer1 and Timer3 are available to modules in Capture or Compare modes, while Timer2 and Timer4 are available for modules in PWM mode.

### TABLE 17-1:ECCP MODE – TIMER<br/>RESOURCE

ECCP Mode	Timer Resource
Capture	Timer1 or Timer3
Compare	Timer1 or Timer3
PWM	Timer2 or Timer4

The assignment of a particular timer to a module is determined by the Timer-to-ECCP enable bits in the TCLKCON register (Register 12-3). The interactions between the two modules are depicted in Figure 17-1. Capture operations are designed to be used when the timer is configured for Synchronous Counter mode. Capture operations may not work as expected if the associated timer is configured for Asynchronous Counter mode.

#### 17.2 Capture Mode

In Capture mode, the CCPRxH:CCPRxL register pair captures the 16-bit value of the TMR1 or TMR3 registers when an event occurs on the corresponding ECCPx pin. An event is defined as one of the following:

- · Every falling edge
- Every rising edge
- Every 4<sup>th</sup> rising edge
- Every 16<sup>th</sup> rising edge

The event is selected by the mode select bits, CCPxM<3:0>, of the CCPxCON register. When a capture is made, the interrupt request flag bit, CCPxIF, is set; it must be cleared by software. If another capture occurs before the value in register CCPRx is read, the old captured value is overwritten by the new captured value.

#### 17.2.1 ECCP PIN CONFIGURATION

In Capture mode, the appropriate ECCPx pin should be configured as an input by setting the corresponding TRIS direction bit.

Additionally, the ECCPx input function needs to be assigned to an I/O pin through the Peripheral Pin Select module. For details on setting up the remappable pins, see Section 9.7 "Peripheral Pin Select (PPS)".

Note:	If the ECCPx pin is configured as an out-
	put, a write to the port can cause a capture
	condition.

#### 17.2.2 TIMER1/TIMER3 MODE SELECTION

The timers that are to be used with the capture feature (Timer1 and/or Timer3) must be running in Timer mode or Synchronized Counter mode. In Asynchronous Counter mode, the capture operation may not work. The timer to be used with each ECCP module is selected in the TCLKCON register (Register 12-3).

#### 17.2.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep the CCPxIE interrupt enable bit clear to avoid false interrupts. The interrupt flag bit, CCPxIF, should also be cleared following any such change in operating mode.

#### 17.2.4 ECCP PRESCALER


There are four prescaler settings in Capture mode; they are specified as part of the operating mode selected by the mode select bits (CCPxM<3:0>). Whenever the ECCP module is turned off, or Capture mode is disabled, the prescaler counter is cleared. This means that any Reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared; therefore, the first capture may be from a non-zero prescaler. Example 17-1 provides the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

#### EXAMPLE 17-1: CHANGING BETWEEN CAPTURE PRESCALERS

CLRF	CCP1CON	;	Turn CCP module off
MOVLW	NEW_CAPT_PS	;	Load WREG with the
		;	new prescaler mode
		;	value and CCP ON
MOVWF	CCP1CON	;	Load CCP1CON with
		;	this value

#### FIGURE 17-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



#### 17.3 Compare Mode

In Compare mode, the 16-bit CCPRx register value is constantly compared against either the TMR1 or TMR3 register pair value. When a match occurs, the ECCPx pin can be:

- Driven high
- Driven low
- Toggled (high-to-low or low-to-high)
- Remain unchanged (that is, reflects the state of the I/O latch)

The action on the pin is based on the value of the mode select bits (CCPxM<3:0>). At the same time, the interrupt flag bit, CCPxIF, is set.

#### 17.3.1 ECCP PIN CONFIGURATION

Users must configure the ECCPx pin as an output by clearing the appropriate TRIS bit.

Note:	Clearing the CCPxCON register will force
	the ECCPx compare output latch (depend-
	ing on device configuration) to the default
	low level. This is not the PORTx I/O data
	latch.

#### 17.3.2 TIMER1/TIMER3 MODE SELECTION

Timer1 and/or Timer3 must be running in Timer mode or Synchronized Counter mode if the ECCP module is using the compare feature. In Asynchronous Counter mode, the compare operation will not work reliably.

#### 17.3.3 SOFTWARE INTERRUPT MODE

When the Generate Software Interrupt mode is chosen (CCPxM<3:0> = 1010), the ECCPx pin is not affected; only the CCPxIF interrupt flag is affected.


#### 17.3.4 SPECIAL EVENT TRIGGER

The ECCP module is equipped with a Special Event Trigger. This is an internal hardware signal generated in Compare mode to trigger actions by other modules. The Special Event Trigger is enabled by selecting the Compare Special Event Trigger mode (CCPxM<3:0> = 1011).

The Special Event Trigger resets the Timer register pair for whichever timer resource is currently assigned as the module's time base. This allows the CCPRx registers to serve as a programmable period register for either timer.

The Special Event Trigger can also start an A/D conversion. In order to do this, the A/D converter must already be enabled.

#### FIGURE 17-2: COMPARE MODE OPERATION BLOCK DIAGRAM




#### 17.4 PWM Mode

In Pulse-Width Modulation (PWM) mode, the CCPx pin produces up to a 10-bit resolution PWM output.

Figure 17-3 shows a simplified block diagram of the CCP module in PWM mode.


For a step-by-step procedure on how to set up a CCP module for PWM operation, see Section 17.4.3.

FIGURE 17-3: SIMPLIFIED PWM BLOCK DIAGRAM



A PWM output (Figure 17-4) has a time base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (1/period).

#### FIGURE 17-4: PWM OUTPUT



#### 17.4.1 PWM PERIOD

The PWM period is specified by writing to the PR2 (PR4) register. The PWM period can be calculated using Equation 17-1:

#### EQUATION 17-1:

 $PWM Period = [(PR2) + 1] \cdot 4 \cdot TOSC \cdot (TMR2 Prescale Value)$ 

PWM frequency is defined as 1/[PWM period].

When TMR2 (TMR4) is equal to PR2 (PR4), the following three events occur on the next increment cycle:


- TMR2 (TMR4) is cleared
- The CCPx pin is set (exception: if PWM duty cycle = 0%, the CCPx pin will not be set)
- The PWM duty cycle is latched from CCPRxL into CCPRxH

Note:	The Timer2 and Timer 4 postscalers (see
	Section 14.0 "Timer3 Module" and
	Section 15.0 "Timer4 Module") are not
	used in the determination of the PWM
	frequency. The postscaler could be used
	to have a servo update rate at a different
	frequency than the PWM output.

#### 17.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPRxL register and to the CCPxCON<5:4> bits. Up to 10-bit resolution is available. The CCPRxL contains the eight MSbs and the CCPxCON<5:4> contains the two LSbs. This 10-bit value is represented by CCPRxL:CCPxCON<5:4>. Equation 17-2 is used to calculate the PWM duty cycle in time.

#### EQUATION 17-2:



CCPRxL and CCPxCON<5:4> can be written to at any time, but the duty cycle value is not latched into CCPRxH until after a match between PR2 (PR4) and TMR2 (TMR4) occurs (i.e., the period is complete). In PWM mode, CCPRxH is a read-only register.

The CCPRxH register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation.

When the CCPRxH and 2-bit latch match TMR2 (TMR4), concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 (TMR4) prescaler, the CCPx pin is cleared.

The maximum PWM resolution (bits) for a given PWM frequency is given by Equation 17-3:

#### EQUATION 17-3:

PWM Resolution (max) = 
$$\frac{\log(\frac{FOSC}{FPWM})}{\log(2)}$$
 bits

**Note:** If the PWM duty cycle value is longer than the PWM period, the CCPx pin will not be cleared.

#### 17.4.3 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- 1. Set the PWM period by writing to the PR2 (PR4) register.
- 2. Set the PWM duty cycle by writing to the CCPRxL register and CCPxCON<5:4> bits.
- 3. Make the CCPx pin an output by clearing the appropriate TRIS bit.
- 4. Set the TMR2 (TMR4) prescale value, then enable Timer2 (Timer4) by writing to T2CON (T4CON).
- 5. Configure the CCPx module for PWM operation.

#### TABLE 17-2: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

PWM Frequency	2.44 kHz	9.77 kHz	39.06 kHz	156.25 kHz	312.50 kHz	416.67 kHz
Timer Prescaler (1, 4, 16)	16	4	1	1	1	1
PR2 Value	FFh	FFh	FFh	3Fh	1Fh	17h
Maximum Resolution (bits)	10	10	10	8	7	6.58

# PIC18F46J50 FAMILY

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
RCON	IPEN	_	CM	RI	TO	PD	POR	BOR	64
PIR1	PMPIF	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65
PIE1	PMPIE	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65
IPR1	PMPIP	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65
TRISG	—	_	_	TRISG4	TRISG3	TRISG2	TRISG1	TRISG0	65
TMR2 <sup>(1)</sup>	Timer2 Reg	ister							64
PR2 <sup>(1)</sup>	Timer2 Peri	od Register							64
T2CON	_	T2OUTPS3	T2OUTPS2	T2OUTPS1	T2OUTPS0	TMR2ON	T2CKPS1	T2CKPS0	64
TMR4	Timer4 Reg	ister							67
PR4 <sup>(1)</sup>	Timer4 Peri	od Register							67
T4CON	_	T4OUTPS3	T4OUTPS2	T4OUTPS1	T4OUTPS0	TMR4ON	T4CKPS1	T4CKPS0	67
CCPR4L	Capture/Co	mpare/PWM	1 Register 4	Low Byte					67
CCPR4H	Capture/Co	mpare/PWM	1 Register 4	High Byte					67
CCPR5L	Capture/Co	mpare/PWM	1 Register 5	Low Byte					67
CCPR5H	Capture/Co	mpare/PWM	1 Register 5	High Byte					67
CCP4CON	_		DC4B1	DC4B0	CCP4M3	CCP4M2	CCP4M1	CCP4M0	67
CCP5CON	_		DC5B1	DC5B0	CCP5M3	CCP5M2	CCP5M1	CCP5M0	67
ODCON1 <sup>(2)</sup>				CCP5OD	CCP4OD	ECCP3OD	ECCP2OD	ECCP10D	68

#### TABLE 17-3: REGISTERS ASSOCIATED WITH PWM, TIMER2 AND TIMER4

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by PWM, Timer2 or Timer4.

Note 1: Default (legacy) SFR at this address, available when WDTCON<4> = 0.

2: Configuration SFR, overlaps with default SFR at this address; available only when WDTCON<4> = 1.

#### 17.5 PWM (Enhanced Mode)

The Enhanced PWM mode can generate a PWM signal on up to four different output pins with up to 10 bits of resolution. It can do this through four different PWM Output modes:

- Single PWM
- Half-Bridge PWM
- Full-Bridge PWM, Forward mode
- Full-Bridge PWM, Reverse mode

To select an Enhanced PWM mode, the PxM bits of the CCPxCON register must be set appropriately.


The PWM outputs are multiplexed with I/O pins and are designated: PxA, PxB, PxC and PxD. The polarity of the PWM pins is configurable and is selected by setting the CCPxM bits in the CCPxCON register appropriately.

Table 17-1 provides the pin assignments for each Enhanced PWM mode.

Figure 17-5 provides an example of a simplified block diagram of the Enhanced PWM module.

**Note:** To prevent the generation of an incomplete waveform when the PWM is first enabled, the ECCP module waits until the start of a new PWM period before generating a PWM signal.

#### FIGURE 17-5: EXAMPLE SIMPLIFIED BLOCK DIAGRAM OF THE ENHANCED PWM MODE



Note 1: The TRIS register value for each PWM output must be configured appropriately.2: Any pin not used by an Enhanced PWM mode is available for alternate pin functions.

ECCP Mode	PxM<1:0>	PxA	PxB	PxC	PxD
Single	00	Yes <sup>(1)</sup>	Yes <sup>(1)</sup>	Yes <sup>(1)</sup>	Yes <sup>(1)</sup>
Half-Bridge	10	Yes	Yes	No	No
Full-Bridge, Forward	01	Yes	Yes	Yes	Yes
Full-Bridge, Reverse	11	Yes	Yes	Yes	Yes

#### TABLE 17-4: EXAMPLE PIN ASSIGNMENTS FOR VARIOUS PWM ENHANCED MODES

**Note 1:** Outputs are enabled by pulse steering in Single mode (see Register 17-4).

### FIGURE 17-6: EXAMPLE PWM (ENHANCED MODE) OUTPUT RELATIONSHIPS (ACTIVE-HIGH STATE)

				Period —	<b>→</b>
00	(Single Output)	PxA Modulated	Delay <sup>(1)</sup>	Delay <sup>(1)</sup>	
		PxA Modulated			
10	(Half-Bridge)	PxB Modulated	— <u> </u>		i
		PxA Active			
01	(Full-Bridge,	PxB Inactive			1 1 1
01	Forward)	PxC Inactive	_ :		
		PxD Modulated	!		
		PxA Inactive	;		1 1 1
11	(Full-Bridge, Reverse)	PxB Modulated	=	'	   
		PxC Active —	_ :		
		PxD Inactive			1 1 1

Delay = 4 \* Tosc \* (ECCPxDEL<6:0>)

Note 1: Dead-band delay is programmed using the ECCPxDEL register (Section 17.5.6 "Programmable Dead-Band Delay Mode").


		_	 ' 		
00	(Single Output)	PxA Modulated	 ļ	J	
		PxA Modulated	 Delay <sup>(1)</sup>	<b>→→</b> Delay <sup>(1)</sup>	
10	(Half-Bridge)	PxB Modulated			
		PxA Active			i
01	(Full-Bridge, Forward)	PxB Inactive	 	<u> </u>	<i>i</i> I I
	i orwardy	PxC Inactive	     		I I 
		PxD Modulated	  		
		PxA Inactive	 i 1 1	1	1 1 1
11	(Full-Bridge,	PxB Modulated	 ļ		1     
	Reverse)	PxC Active	 · · ·		
		PxD Inactive	 1 1 1		 I I
		:* (PR2 + 1) * (TMR2 Pre sc * (CCPRxL<7:0>:CCP		·	


#### FIGURE 17-7: EXAMPLE ENHANCED PWM OUTPUT RELATIONSHIPS (ACTIVE-LOW STATE)

#### 17.5.1 HALF-BRIDGE MODE

In Half-Bridge mode, two pins are used as outputs to drive push-pull loads. The PWM output signal is output on the PxA pin, while the complementary PWM output signal is output on the PxB pin (see Figure 17-8). This mode can be used for half-bridge applications, as shown in Figure 17-9, or for full-bridge applications, where four power switches are being modulated with two PWM signals.


In Half-Bridge mode, the programmable dead-band delay can be used to prevent shoot-through current in half-bridge power devices. The value of the PxDC<6:0> bits of the ECCPxDEL register sets the number of instruction cycles before the output is driven active. If the value is greater than the duty cycle, the corresponding output remains inactive during the entire cycle. See **Section 17.5.6 "Programmable Dead-Band Delay Mode"** for more details of the dead-band delay operations. Since the PxA and PxB outputs are multiplexed with the PORT data latches, the associated TRIS bits must be cleared to configure PxA and PxB as outputs.





**<sup>2:</sup>** Output signals are shown as active-high.

#### FIGURE 17-9: EXAMPLE OF HALF-BRIDGE APPLICATIONS




#### 17.5.2 FULL-BRIDGE MODE


In Full-Bridge mode, all four pins are used as outputs. An example of a full-bridge application is provided in Figure 17-10.

In the Forward mode, the PxA pin is driven to its active state, the PxD pin is modulated, while the PxB and PxC pins will be driven to their inactive state as provided in Figure 17-11.


FIGURE 17-10: EXAMPLE OF FULL-BRIDGE APPLICATION



The PxA, PxB, PxC and PxD outputs are multiplexed with the PORT data latches. The associated TRIS bits must be cleared to configure the PxA, PxB, PxC and PxD pins as outputs.



# PIC18F46J50 FAMILY



### DS39931C-page 252

# 17.5.2.1 Direction Change in Full-Bridge Mode

In the Full-Bridge mode, the PxM1 bit in the CCPxCON register allows users to control the forward/reverse direction. When the application firmware changes this direction control bit, the module will change to the new direction on the next PWM cycle.

A direction change is initiated in software by changing the PxM1 bit of the CCPxCON register. The following sequence occurs prior to the end of the current PWM period:

- The modulated outputs (PxB and PxD) are placed in their inactive state.
- The associated unmodulated outputs (PxA and PxC) are switched to drive in the opposite direction.
- PWM modulation resumes at the beginning of the next period.

See Figure 17-12 for an illustration of this sequence.

The Full-Bridge mode does not provide a dead-band delay. As one output is modulated at a time, a dead-band delay is generally not required. There is a situation where a dead-band delay is required. This situation occurs when both of the following conditions are true:

- 1. The direction of the PWM output changes when the duty cycle of the output is at or near 100%.
- 2. The turn-off time of the power switch, including the power device and driver circuit, is greater than the turn-on time.


Figure 17-13 shows an example of the PWM direction changing from forward to reverse, at a near 100% duty cycle. In this example, at time, t1, the PxA and PxD outputs become inactive, while the PxC output becomes active. Since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current will flow through power devices, QC and QD (see Figure 17-10), for the duration of 't'. The same phenomenon will occur to power devices, QA and QB, for PWM direction change from reverse to forward.


If changing PWM direction at high duty cycle is required for an application, two possible solutions for eliminating the shoot-through current are:

- 1. Reduce PWM duty cycle for one PWM period before changing directions.
- 2. Use switch drivers that can drive the switches off faster than they can drive them on.

Other options to prevent shoot-through current may exist.

#### FIGURE 17-12: EXAMPLE OF PWM DIRECTION CHANGE





#### **FIGURE 17-13:**

- 3: TOFF is the turn-off delay of power switch QD and its driver.

#### 17.5.3 START-UP CONSIDERATIONS

When any PWM mode is used, the application hardware must use the proper external pull-up and/or pull-down resistors on the PWM output pins.

Note:	When the microcontroller is released from
	Reset, all of the I/O pins are in the
	high-impedance state. The external
	circuits must keep the power switch
	devices in the OFF state until the micro-
	controller drives the I/O pins with the
	proper signal levels or activates the PWM
	output(s).

The CCPxM<1:0> bits of the CCPxCON register allow the user to choose whether the PWM output signals are active-high or active-low for each pair of PWM output pins (PxA/PxC and PxB/PxD). The PWM output polarities must be selected before the PWM pin output drivers are enabled. Changing the polarity configuration while the PWM pin output drivers are enable is not recommended since it may result in damage to the application circuits.

The PxA, PxB, PxC and PxD output latches may not be in the proper states when the PWM module is initialized. Enabling the PWM pin output drivers at the same time as the Enhanced PWM modes may cause damage to the application circuit. The Enhanced PWM modes must be enabled in the proper Output mode and complete a full PWM cycle before enabling the PWM pin output drivers. The completion of a full PWM cycle is indicated by the TMR2IF or TMR4IF bit of the PIR1 or PIR3 register being set as the second PWM period begins.

#### 17.5.4 ENHANCED PWM AUTO-SHUTDOWN MODE

The PWM mode supports an Auto-Shutdown mode that will disable the PWM outputs when an external shutdown event occurs. Auto-Shutdown mode places the PWM output pins into a predetermined state. This mode is used to help prevent the PWM from damaging the application.

The auto-shutdown sources are selected using the ECCPxAS<2:0> bits of the ECCPxAS register. A shutdown event may be generated by:

- A logic '0' on the pin that is assigned the FLT0 input function
- Comparator C1
- Comparator C2
- Setting the ECCPxASE bit in firmware

A shutdown condition is indicated by the ECCPxASE (Auto-Shutdown Event Status) bit of the ECCPxAS register. If the bit is a '0', the PWM pins are operating normally. If the bit is a '1', the PWM outputs are in the shutdown state.

When a shutdown event occurs, two things happen:

The ECCPxASE bit is set to '1'. The ECCPxASE will remain set until cleared in firmware or an auto-restart occurs (see Section 17.5.5 "Auto-Restart Mode").

The enabled PWM pins are asynchronously placed in their shutdown states. The PWM output pins are grouped into pairs [PxA/PxC] and [PxB/PxD]. The state of each pin pair is determined by the PSSxAC and PSSxBD bits of the ECCPxAS register. Each pin pair may be placed into one of three states:

- Drive logic '1'
- Drive logic '0'
- Tri-state (high-impedance)

# REGISTER 17-2: ECCPxAS: ECCPx AUTO-SHUTDOWN CONTROL REGISTER (ACCESS FBEh, FB8h)


R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
ECCPxASE	ECCPxAS2	ECCPxAS1	ECCPxAS0	PSSxAC1	PSSxAC0	PSSxBD1	PSSxBD0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	ECCPxASE: ECCP Auto-Shutdown Event Status bit 1 = A shutdown event has occurred; ECCP outputs are in a shutdown state 0 = ECCP outputs are operating
bit 6-4	<ul> <li>ECCPxAS&lt;2:0&gt;: ECCP Auto-Shutdown Source Select bits</li> <li>000 = Auto-shutdown is disabled</li> <li>001 = Comparator C1OUT output is high</li> <li>010 = Comparator C2OUT output is high</li> <li>011 = Either Comparator C1OUT or C2OUT is high</li> <li>100 = VIL on FLT0 pin</li> <li>101 = VIL on FLT0 pin or Comparator C1OUT output is high</li> <li>110 = VIL on FLT0 pin or Comparator C2OUT output is high</li> <li>111 = VIL on FLT0 pin or Comparator C1OUT or C2OUT output is high</li> <li>111 = VIL on FLT0 pin or Comparator C1OUT or C2OUT is high</li> </ul>
bit 3-2	PSSxAC<1:0>: Pins PxA and PxC Shutdown State Control bits 00 = Drive pins PxA and PxC to '0' 01 = Drive pins PxA and PxC to '1' 1x = Pins PxA and PxC tri-state
bit 1-0	PSSxBD<1:0>: Pins PxB and PxD Shutdown State Control bits 00 = Drive pins PxB and PxD to '0' 01 = Drive pins PxB and PxD to '1' 1x = Pins PxB and PxD tri-state
Note 1:	The auto-shutdown condition is a level-based signal, not an edge-based signal. As long as the level is present, the auto-shutdown will persist.
2:	Writing to the ECCPxASE bit is disabled while an auto-shutdown condition persists.

3: Once the auto-shutdown condition has been removed and the PWM restarted (either through firmware or auto-restart), the PWM signal will always restart at the beginning of the next PWM period.






#### 17.5.5 AUTO-RESTART MODE

The Enhanced PWM can be configured to automatically restart the PWM signal once the auto-shutdown condition has been removed. Auto-restart is enabled by setting the PxRSEN bit in the ECCPxDEL register.

If auto-restart is enabled, the ECCPxASE bit will remain set as long as the auto-shutdown condition is active. When the auto-shutdown condition is removed, the ECCPxASE bit will be cleared via hardware and normal operation will resume. The module will wait until the next PWM period begins, however, before re-enabling the output pin. This behavior allows the auto-shutdown with auto-restart features to be used in applications based on current mode PWM control.

#### FIGURE 17-15: PWM AUTO-SHUTDOWN WITH AUTO-RESTART ENABLED (PxRSEN = 1)




#### 17.5.6 PROGRAMMABLE DEAD-BAND DELAY MODE

In half-bridge applications, where all power switches are modulated at the PWM frequency, the power switches normally require more time to turn off than to turn on. If both the upper and lower power switches are switched at the same time (one turned on and the other turned off), both switches may be on for a short period until one switch completely turns off. During this brief interval, a very high current (shoot-through current) will flow through both power switches, shorting the bridge supply. To avoid this potentially destructive shoot-through current from flowing during switching, turning on either of the power switches is normally delayed to allow the other switch to completely turn off.

In Half-Bridge mode, a digitally programmable dead-band delay is available to avoid shoot-through current from destroying the bridge power switches. The delay occurs at the signal transition from the non-active state to the active state. See Figure 17-16 for illustration. The lower seven bits of the associated ECCPxDEL register (Register 17-3) sets the delay period in terms of microcontroller instruction cycles (TcY or 4 Tosc).

#### **EXAMPLE OF** FIGURE 17-16: HALF-BRIDGE PWM OUTPUT Period Period Pulse Width PxA<sup>(2)</sup> td I PxB<sup>(2)</sup> (1) ·(1) (1) td = Dead-Band Delay Note 1: At this time, the TMR2 register is equal to the PR2 register. 2: Output signals are shown as active-high.

#### FIGURE 17-17: EXAMPLE OF HALF-BRIDGE APPLICATIONS



R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'							
Legend:							
bit 7							bit 0
PxRSEN	PxDC6	PxDC5	PxDC4	PxDC3	PxDC2	PxDC1	PxDC0
R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0

#### REGISTER 17-3: ECCPxDEL: ENHANCED PWM CONTROL REGISTER (ACCESS FBDh, FB7h)

bit 7 **PxRSEN:** PWM Restart Enable bit

'1' = Bit is set

1 = Upon auto-shutdown, the ECCPxASE bit clears automatically once the shutdown event goes away; the PWM restarts automatically

'0' = Bit is cleared

0 = Upon auto-shutdown, ECCPxASE must be cleared by software to restart the PWM

bit 6-0 **PxDC<6:0>:** PWM Delay Count bits

PxDCn = Number of Fosc/4 (4 \* Tosc) cycles between the scheduled time when a PWM signal **should** transition active and the **actual** time it transitions active.

#### 17.5.7 PULSE STEERING MODE

-n = Value at POR

In Single Output mode, pulse steering allows any of the PWM pins to be the modulated signal. Additionally, the same PWM signal can simultaneously be available on multiple pins.

Once the Single Output mode is selected (CCPxM<3:2> = 11 and PxM<1:0> = 00 of the CCPxCON register), the user firmware can bring out the same PWM signal to one, two, three or four output pins by setting the appropriate STR<D:A> bits of the PSTRxCON register, as provided in Table 17-4.

Note: The associated TRIS bits must be set to output ('0') to enable the pin output driver in order to see the PWM signal on the pin.

While the PWM Steering mode is active, the CCPxM<1:0> bits of the CCPxCON register select the PWM output polarity for the Px<D:A> pins.

x = Bit is unknown


The PWM auto-shutdown operation also applies to PWM Steering mode as described in **Section 17.5.4 "Enhanced PWM Auto-shutdown mode"**. An auto-shutdown event will only affect pins that have PWM outputs enabled.

## REGISTER 17-4: PSTRxCON: PULSE STEERING CONTROL REGISTER (ACCESS FBFh, FB9h)<sup>(1)</sup>

R/W-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-1		
CMPL1	CMPL0	—	STRSYNC	STRD	STRC	STRB	STRA		
bit 7			•				bit C		
Legend:									
R = Readable	bit	W = Writable	bit	U = Unimpler	nented bit, rea	id as '0'			
-n = Value at F	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown		
bit 7-6	CMPL<1:0>:	Complementa	ry Mode Outpu	t Assignment S	Steering Sync	bits			
			ggles between						
			•	abled; STRD:	STRA bits use	d to determine S	Steering mode		
bit 5	-	ted: Read as '							
bit 4		teering Sync b							
	•	• •	occurs on next	•	. in a transformation and				
<b>h</b> it 0		•	occurs at the b			cie boundary			
bit 3		ng Enable bit [				-1-0-			
		s assigned to j	vaveform with   port pin	polarity control		<1:0>			
bit 2	•	ng Enable bit (	•						
Sit 2		-	vaveform with	polarity control	from CCPxM	<1:0>			
		s assigned to							
bit 1	STRB: Steerin	ng Enable bit B	3						
	1 = PxB pin h	1 = PxB pin has the PWM waveform with polarity control from CCPxM<1:0>							
	0 = PxB pin is assigned to port pin								
L:1 0	STRA: Steerin	ng Enable bit A	A						
DITU		as the DN/M	vovoform with	olarity control	from CCPxM-	<1.0>			
bit 0		s assigned to r				1.0			

PxM<1:0> = 00.





#### 17.5.7.1 Steering Synchronization

The STRSYNC bit of the PSTRxCON register gives the user two selections of when the steering event will happen. When the STRSYNC bit is '0', the steering event will happen at the end of the instruction that writes to the PSTRxCON register. In this case, the output signal at the Px<D:A> pins may be an incomplete PWM waveform. This operation is useful when the user firmware needs to immediately remove a PWM signal from the pin.

When the STRSYNC bit is '1', the effective steering update will happen at the beginning of the next PWM period. In this case, steering on/off the PWM output will always produce a complete PWM waveform.

Figures 17-19 and 17-20 illustrate the timing diagrams of the PWM steering depending on the STRSYNC setting.

#### FIGURE 17-19: EXAMPLE OF STEERING EVENT AT END OF INSTRUCTION (STRSYNC = 0)





FIGURE 17-20: EXAMPLE OF STEERING EVENT AT BEGINNING OF INSTRUCTION (STRSYNC = 1)



# 17.5.8 OPERATION IN POWER-MANAGED MODES

In Sleep mode, all clock sources are disabled. Timer2 will not increment and the state of the module will not change. If the ECCPx pin is driving a value, it will continue to drive that value. When the device wakes up, it will continue from this state. If Two-Speed Start-ups are enabled, the initial start-up frequency from HFINTOSC and the postscaler may not be stable immediately.

In PRI\_IDLE mode, the primary clock will continue to clock the ECCPx module without change.

#### 17.5.8.1 Operation with Fail-Safe Clock Monitor (FSCM)

If the Fail-Safe Clock Monitor (FSCM) is enabled, a clock failure will force the device into the power-managed RC RUN mode and the OSCFIF bit of

the PIR2 register will be set. The ECCPx will then be clocked from the internal oscillator clock source, which may have a different clock frequency than the primary clock.

#### 17.5.9 EFFECTS OF A RESET

Both Power-on Reset and subsequent Resets will force all ports to Input mode and the ECCP registers to their Reset states.

This forces the ECCP module to reset to a state compatible with previous, non-enhanced ECCP modules used on other PIC18 and PIC16 devices.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RABIE	TMR0IF	INT0IF	RABIF	81
RCON	IPEN	SBOREN	_	RI	TO	PD	POR	BOR	84
PIR1	PMPIF <sup>(1)</sup>	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	81
PIE1	PMPIE <sup>(1)</sup>	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	85
IPR1	PMPIP <sup>(1)</sup>	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	85
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	85
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	85
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	85
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	—	TRISC2	TRISC1	TRISC0	86
TMR1L	Timer1 Regi	ster Low Byte							81
TMR1H	Timer1 Regi	ster High Byte	e						81
T1CON	TMR1CS1	TMR1CS0	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	RD16	TMR10N	81
TMR2	Timer2 Regi	ster							81
T2CON	_	T2OUTPS3	T2OUTPS2	T2OUTPS1	T2OUTPS0	TMR2ON	T2CKPS1	T2CKPS0	81
PR2	Timer2 Peric	d Register							81
TMR3L	Timer3 Regi	ster Low Byte	1						81
TMR3H	Timer3 Regi	ster High Byte	e						81
T3CON	TMR3CS1	TMR3CS0	T3CKPS1	T3CKPS0	T3OSCEN	T3SYNC	RD16	TMR3ON	81
CCPR1L	Capture/Compare/PWM Register 1 Low Byte							81	
CCPR1H	Capture/Compare/PWM Register 1 High Byte							81	
CCP1CON	P1M1	P1M0	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	81
ECCP1AS	ECCP1ASE	ECCP1AS2	ECCP1AS1	ECCP1AS0	PSS1AC1	PSS1AC0	PSS1BD1	PSS1BD0	81
ECCP1DEL	P1RSEN	P1DC6	P1DC5	P1DC4	P1DC3	P1DC2	P1DC1	P1DC0	258

### TABLE 17-5: REGISTERS ASSOCIATED WITH ECCP1 MODULE AND TIMER1 TO TIMER3

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used during ECCP operation.

**Note 1:** These bits are only available on 44-pin devices.

NOTES:

### 18.0 MASTER SYNCHRONOUS SERIAL PORT (MSSP) MODULE

The Master Synchronous Serial Port (MSSP) module is a serial interface, useful for communicating with other peripheral or microcontroller devices. These peripheral devices include serial EEPROMs, shift registers, display drivers and A/D Converters.

### 18.1 Master SSP (MSSP) Module Overview

The MSSP module can operate in one of two modes:

- Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C<sup>™</sup>)
  - Full Master mode
  - Slave mode (with general address call)

The  $I^2C$  interface supports the following modes in hardware:

- Master mode
- Multi-Master mode
- Slave mode with 5-bit and 7-bit address masking (with address masking for both 10-bit and 7-bit addressing)

All members of the PIC18F46J50 Family have two MSSP modules, designated as MSSP1 and MSSP2. The modules operate independently:

- PIC18F4XJ50 devices Both modules can be configured for either I<sup>2</sup>C or SPI communication
- PIC18F2XJ50 devices:
  - MSSP1 can be used for either I<sup>2</sup>C or SPI communication
  - MSSP2 can be used only for SPI communication

All of the MSSP1 module-related SPI and  $I^2C$  I/O functions are hard-mapped to specific I/O pins.

For MSSP2 functions:

 SPI I/O functions (SDO2, SDI2, SCK2 and SS2) are all routed through the Peripheral Pin Select (PPS) module.

These functions may be configured to use any of the RPn remappable pins, as described in **Section 9.7 "Peripheral Pin Select (PPS)"**.

• I<sup>2</sup>C functions (SCL2 and SDA2) have fixed pin locations.

On all PIC18F46J50 Family devices, the SPI DMA capability can only be used in conjunction with MSSP2. The SPI DMA feature is described in **Section 18.4 "SPI DMA Module"**.

Note:	Throughout this section, generic references to an MSSP module in any of its operating modes may be interpreted as being equally applicable to MSSP1 or MSSP2. Register names and module I/O signals use the generic designator 'x' to indicate the use of a numeral to distinguish a particular module when required. Control bit names are not individuated.
-------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

### 18.2 Control Registers

Each MSSP module has three associated control registers. These include a status register (SSPxSTAT) and two control registers (SSPxCON1 and SSPxCON2). The use of these registers and their individual Configuration bits differ significantly depending on whether the MSSP module is operated in SPI or I<sup>2</sup>C mode.

Additional details are provided under the individual sections.

Note: In devices with more than one MSSP module, it is very important to pay close attention to the SSPxCON register names. SSP1CON1 and SSP1CON2 control different operational aspects of the same module, while SSP1CON1 and SSP2CON1 control the same features for two different modules.

#### 18.3 SPI Mode

The SPI mode allows 8 bits of data to be synchronously transmitted and received simultaneously. All four modes of SPI are supported.

When MSSP2 is used in SPI mode, it can optionally be configured to work with the SPI DMA submodule described in **Section 18.4 "SPI DMA Module"**.

To accomplish communication, typically three pins are used:


- Serial Data Out (SDOx) RC7/RX1/DT1/SDO1/RP18 or SDO2/Remappable
- Serial Data In (SDIx) –
   RB5/KBI1/SDI1/SDA1/RP8 or SDI2/Remappable
- Serial Clock (SCKx) RB4/KBI0/SCK1/SCL1/RP7 or SCK2/Remappable

Additionally, a fourth pin may be used when in a Slave mode of operation:

 Slave Select (SSx) – RA5/AN4/SS1/ HLVDIN/RCV/RP2 or SS2/Remappable

Figure 18-1 depicts the block diagram of the MSSP module when operating in SPI mode.

#### FIGURE 18-1: MSSPx BLOCK DIAGRAM (SPI MODE)



lote: Only port I/O names are used in this diagram for the sake of brevity. Refer to the text for a full list of multiplexed functions.

#### 18.3.1 REGISTERS

Each MSSP module has four registers for SPI mode operation. These are:

- MSSPx Control Register 1 (SSPxCON1)
- MSSPx Status Register (SSPxSTAT)
- Serial Receive/Transmit Buffer Register (SSPxBUF)
- MSSPx Shift Register (SSPxSR) Not directly accessible

SSPxCON1 and SSPxSTAT are the control and status registers in SPI mode operation. The SSPxCON1 register is readable and writable. The lower six bits of the SSPxSTAT are read-only. The upper two bits of the SSPxSTAT are read/write.

SSPxSR is the shift register used for shifting data in or out. SSPxBUF is the buffer register to which data bytes are written to or read from.

In receive operations, SSPxSR and SSPxBUF together create a double-buffered receiver. When SSPxSR receives a complete byte, it is transferred to SSPxBUF and the SSPxIF interrupt is set.

During transmission, the SSPxBUF is not double-buffered. A write to SSPxBUF will write to both SSPxBUF and SSPxSR.

#### REGISTER 18-1: SSPxSTAT: MSSPx STATUS REGISTER (SPI MODE) (ACCESS FC7h, F73h)

R/W-1	R/W-1	R-1	R-1	R-1	R-1	R-1	R-1	
SMP	CKE <sup>(1)</sup>	D/A	Р	S	R/W	UA	BF	
bit 7	•	·					bit 0	
Legend:								
R = Reada	able bit	W = Writable	bit	U = Unimplem		id as '0'		
-n = Value	at POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unki	nown	
bit 7	SMP: Sample	e bit						
	SPI Master m							
	•	a sampled at er	•					
	•	a sampled at m	iddle of data c	output time				
	<u>SPI Slave mode:</u> SMP must be cleared when SPI is used in Slave mode.							
bit 6		CKE: SPI Clock Select bit <sup>(1)</sup>						
DILO				ve to Idle clock	stato			
				to active clock				
bit 5	D/A: Data/Ad	dress bit						
	Used in I <sup>2</sup> C™	1 mode only.						
bit 4	P: Stop bit							
	Used in I <sup>2</sup> C n	node only; this	bit is cleared v	when the MSSP	module is dis	abled, SSPEN i	s cleared.	
bit 3	S: Start bit							
	Used in I <sup>2</sup> C n	node only.						
bit 2	R/W: Read/W	/rite Information	n bit					
	Used in I <sup>2</sup> C n	node only.						
bit 1	UA: Update A	Address bit						
	Used in I <sup>2</sup> C n	node only.						
bit 0	BF: Buffer Fu	ull Status bit						
	1 = Receive of	complete, SSP	BUF is full					
	0 = Receive r	not complete, S	SPxBUF is er	npty				
Note 1:	Polarity of clock s	state is set bv th	ne CKP bit (SS	SPxCON1<4>).				
		,	· ·	,				

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
WCOL	SSPOV <sup>(1)</sup>	SSPEN <sup>(2)</sup>	CKP	SSPM3 <sup>(3)</sup>	SSPM2 <sup>(3)</sup>	SSPM1 <sup>(3)</sup>	SSPM0 <sup>(3)</sup>			
bit 7							bit			
Legend:										
R = Readab	ole bit	W = Writable b	bit	U = Unimplen	nented bit, read	d as '0'				
-n = Value a	at POR	'1' = Bit is set		'0' = Bit is clea		x = Bit is unkr	nown			
bit 7	WCOL · Write	e Collision Detec	t bit							
				e it is still transm	nitting the previ	ous word (mus	t be cleared			
		<ol> <li>The SSPxBUF register is written while it is still transmitting the previous word (must be cleared in software)</li> </ol>								
	0 = No collis									
bit 6	SSPOV: Rec	eive Overflow In	dicator bit <sup>(1)</sup>							
	SPI Slave mode:									
	1 = A new byte is received while the SSPxBUF register is still holding the previous data. In case of over									
	flow, the data in SSPxSR is lost. Overflow can only occur in Slave mode. The user must read the SSPxBUF, even if only transmitting data, to avoid setting overflow (must be cleared in software).									
	0 = No overfl		anomitting da		ing overnow (n		in solwarc)			
bit 5		ter Synchronous	s Serial Port I	-nable bit <sup>(2)</sup>						
		serial port and c			and SSx as s	erial port pins				
		serial port and c								
bit 4	CKP: Clock F	Polarity Select bi	t							
	1 = Idle state	for clock is a high	gh level							
	0 = Idle state	for clock is a low	w level							
bit 3-0	SSPM<3:0>:	SSPM<3:0>: Master Synchronous Serial Port Mode Select bits <sup>(3)</sup>								
	0101 = SPI Slave mode, clock = SCKx pin, $\overline{SSx}$ pin control disabled, $\overline{SSx}$ can be used as I/O pin									
	0100 = SPI Slave mode, clock = SCKx pin, SSx pin control enabled									
	0011 = SPI Master mode, clock = TMR2 output/2 0010 = SPI Master mode, clock = Fosc/64									
		Master mode, clo								
		Master mode, clo								
Note 1:	n Master mode,	the overflow hit	is not set sind	e each new rec	ention (and tra	insmission) is i	nitiated by			
	writing to the SSI					10111001011/101	induce by			

### REGISTER 18-2: SSPxCON1: MSSPx CONTROL REGISTER 1 (SPI MODE) (ACCESS FC6h, F72h)

- writing to the SSPxBUF register.
  - **2:** When enabled, this pin must be properly configured as input or output.
  - **3:** Bit combinations not specifically listed here, are either reserved or implemented in  $I^2C^{TM}$  mode only.

#### 18.3.2 OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPxCON1<5:0> and SSPxSTAT<7:6>). These control bits allow the following to be specified:

- Master mode (SCKx is the clock output)
- Slave mode (SCKx is the clock input)
- Clock Polarity (Idle state of SCKx)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCKx)
- Clock Rate (Master mode only)
- Slave Select mode (Slave mode only)

Each MSSP module consists of a transmit/receive shift register (SSPxSR) and a buffer register (SSPxBUF). The SSPxSR shifts the data in and out of the device, MSb first. The SSPxBUF holds the data that was written to the SSPxSR until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPxBUF register. Then, the Buffer Full (BF) detect bit (SSPxSTAT<0>) and the interrupt flag bit, SSPxIF, are set. This double-buffering of the received data (SSPxBUF) allows the next byte to start reception before reading the data that was just received.

Any write to the SSPxBUF register during transmission/reception of data will be ignored and the Write Collision Detect bit, WCOL (SSPxCON1<7>), will be set. User software must clear the WCOL bit so that it can be determined if the following write(s) to the SSPxBUF register completed successfully.

Note:	When the application software is expecting to receive valid data, the SSPxBUF should
	be read before the next byte of transfer data is written to the SSPxBUF. Application
	software should follow this process even when the current contents of SSPxBUF are not important.

The Buffer Full bit, BF (SSPxSTAT<0>), indicates when SSPxBUF has been loaded with the received data (transmission is complete). When the SSPxBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur.

Example 18-1 provides the loading of the SSPxBUF (SSPxSR) for data transmission.

The SSPxSR is not directly readable or writable and can only be accessed by addressing the SSPxBUF register. Additionally, the SSPxSTAT register indicates the various status conditions.

#### 18.3.3 OPEN-DRAIN OUTPUT OPTION

The drivers for the SDOx output and SCKx clock pins can be optionally configured as open-drain outputs. This feature allows the voltage level on the pin to be pulled to a higher level through an external pull-up resistor, provided the SDOx or SCKx pin is not multiplexed with an ANx analog function. This allows the output to communicate with external circuits without the need for additional level shifters. For more information, see **Section 9.1.4 "Open-Drain Outputs"**.

The open-drain output option is controlled by the SPI2OD and SPI1OD bits (ODCON3<1:0>). Setting an SPIxOD bit configures both SDOx and SCKx pins for the corresponding open-drain operation.

#### EXAMPLE 18-1: LOADING THE SSP1BUF (SSP1SR) REGISTER

LOOP	BRA	LOOP	;Has data been received (transmit complete)? ;No ;WREG reg = contents of SSP1BUF
	MOVWF	RXDATA	;Save in user RAM, if data is meaningful
	MOVF MOVWF	TXDATA, W SSP1BUF	;W reg = contents of TXDATA ;New data to xmit

### 18.3.4 ENABLING SPI I/O

To enable the serial port, MSSP Enable bit, SSPEN (SSPxCON1<5>), must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, reinitialize the SSPxCON1 registers and then set the SSPEN bit. This configures the SDIx, SDOx, SCKx and SSx pins as serial port pins. For the pins to behave as the serial port function, the appropriate TRIS bits, ANCON/PCFG bits and Peripheral Pin Select registers (if using MSSP2) should be correctly initialized prior to setting the SSPEN bit.

A typical SPI serial port initialization process follows:

- Initialize ODCON3 register (optional open-drain output control)
- Initialize remappable pin functions (if using MSSP2, see Section 9.7 "Peripheral Pin Select (PPS)")
- Initialize SCKx LAT value to desired Idle SCK level (if master device)
- Initialize SCKx ANCON/PCFG bit (if Slave mode and multiplexed with ANx function)
- Initialize SCKx TRIS bit as output (Master mode) or input (Slave mode)
- Initialize SDIx ANCON/PCFG bit (if SDIx is multiplexed with ANx function)
- · Initialize SDIx TRIS bit
- Initialize SSx ANCON/PCFG bit (if Slave mode and multiplexed with ANx function)
- Initialize SSx TRIS bit (Slave modes)
- Initialize SDOx TRIS bit
- Initialize SSPxSTAT register
- Initialize SSPxCON1 register
- Set SSPEN bit to enable the module


Any MSSP1 serial port function that is not desired may be overridden by programming the corresponding Data Direction (TRIS) register to the opposite value. If individual MSSP2 serial port functions will not be used, they may be left unmapped.

Note: When MSSP2 is used in SPI Master mode, the SCK2 function must be configured as both an output and an input in the PPS module. SCK2 must be initialized as an output pin (by writing 0x0A to one of the RPORx registers). Additionally, SCK2IN must also be mapped to the same pin by initializing the RPINR22 register. Failure to initialize SCK2/SCK2IN as both output and input will prevent the module from receiving data on the SDI2 pin, as the module uses the SCK2IN signal to latch the received data.

### 18.3.5 TYPICAL CONNECTION

Figure 18-2 illustrates a typical connection between two microcontrollers. The master controller (Processor 1) initiates the data transfer by sending the SCKx signal. Data is shifted out of both shift registers on their programmed clock edge and latched on the opposite edge of the clock. Both processors should be programmed to the same Clock Polarity (CKP), then both controllers would send and receive data at the same time. Whether the data is meaningful (or dummy data) depends on the application software. This leads to three scenarios for data transmission:

- Master sends valid data Slave sends dummy data
- Master sends valid data Slave sends valid data
- Master sends dummy data Slave sends valid data



### FIGURE 18-2: SPI MASTER/SLAVE CONNECTION

#### 18.3.6 MASTER MODE

The master can initiate the data transfer at any time because it controls the SCKx. The master determines when the slave (Processor 2, Figure 18-2) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPxBUF register is written to. If the SPI is only going to receive, the SDOx output could be disabled (programmed as an input). The SSPxSR register will continue to shift in the signal present on the SDIx pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPxBUF register as if a normal received byte (interrupts and status bits appropriately set). This could be useful in receiver applications as a "Line Activity Monitor" mode.

The CKP is selected by appropriately programming the CKP bit (SSPxCON1<4>). This then, would give waveforms for SPI communication as illustrated in Figure 18-3, Figure 18-5 and Figure 18-6, where the

Most Significant Byte (MSB) is transmitted first. In Master mode, the SPI clock rate (bit rate) is user-programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 Tcy)
- Fosc/64 (or 16 Tcy)
- Timer2 output/2

When using the Timer2 output/2 option, the Period Register 2 (PR2) can be used to determine the SPI bit rate. However, only PR2 values of 0x01 to 0xFF are valid in this mode.

Figure 18-3 illustrates the waveforms for Master mode. When the CKE bit is set, the SDOx data is valid before there is a clock edge on SCKx. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPxBUF is loaded with the received data is shown.




FIGURE 18-3: SPI MODE WAVEFORM (MASTER MODE)

#### 18.3.7 SLAVE MODE

In Slave mode, the data is transmitted and received as the external clock pulses appear on SCKx. When the last bit is latched, the SSPxIF interrupt flag bit is set.

While in Slave mode, the external clock is supplied by the external clock source on the SCKx pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in Sleep mode, the slave can transmit/receive data. When a byte is received, the device can be configured to wake-up from Sleep.

#### 18.3.8 SLAVE SELECT SYNCHRONIZATION


The  $\overline{SSx}$  pin allows a Synchronous Slave mode. The SPI must be in Slave mode with the  $\overline{SSx}$  pin control enabled (SSPxCON1<3:0> = 04h). When the  $\overline{SSx}$  pin is low, transmission and reception are enabled and the SDOx pin is driven. When the  $\overline{SSx}$  pin goes high, the SDOx pin is no longer driven, even if in the middle of a

transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.


- Note 1: When the SPI is in Slave mode with the SSx pin control enabled (SSPxCON1<3:0> = 0100), the SPI module will reset if the SSx pin is set to VDD.
  - If the SPI is used in Slave mode with CKE set, then the SSx pin control must be enabled.

When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the SSx pin to a high level or clearing the SSPEN bit.


To emulate two-wire communication, the SDOx pin can be connected to the SDIx pin. When the SPI needs to operate as a receiver, the SDOx pin can be configured as an input. This disables transmissions from the SDOx. The SDIx can always be left as an input (SDIx function) since it cannot create a bus conflict.



### FIGURE 18-4: SLAVE SYNCHRONIZATION WAVEFORM







#### 18.3.9 OPERATION IN POWER-MANAGED MODES

In SPI Master mode, module clocks may be operating at a different speed than when in full-power mode. In the case of Sleep mode, all clocks are halted.

In Idle modes, a clock is provided to the peripherals. That clock can be from the primary clock source, the secondary clock (Timer1 oscillator) or the INTOSC source. See **Section 2.5** "**Clock Sources and Oscillator Switching**" for additional information.

In most cases, the speed that the master clocks SPI data is not important; however, this should be evaluated for each system.

If MSSP interrupts are enabled, they can wake the controller from Sleep mode, or one of the Idle modes, when the master completes sending data. If an exit from Sleep or Idle mode is not desired, MSSP interrupts should be disabled.

If the Sleep mode is selected, all module clocks are halted and the transmission/reception will remain in that state until the device wakes. After the device returns to Run mode, the module will resume transmitting and receiving data.

In SPI Slave mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in any power-managed mode and data to be shifted into the SPI Transmit/Receive Shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set, and if enabled, will wake the device.

#### 18.3.10 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

#### 18.3.11 BUS MODE COMPATIBILITY

Table 18-1 provides the compatibility between the standard SPI modes and the states of the CKP and CKE control bits.

TABLE 18-1:	SPI BUS MODES
-------------	---------------

Standard SPI Mode	Control Bits State				
Terminology	СКР	CKE			
0, 0	0	1			
0, 1	0	0			
1, 0	1	1			
1, 1	1	0			

There is also an SMP bit, which controls when the data is sampled.

# 18.3.12 SPI CLOCK SPEED AND MODULE INTERACTIONS

Because MSSP1 and MSSP2 are independent modules, they can operate simultaneously at different data rates. Setting the SSPM<3:0> bits of the SSPxCON1 register determines the rate for the corresponding module.

An exception is when both modules use Timer2 as a time base in Master mode. In this instance, any changes to the Timer2 module's operation will affect both MSSP modules equally. If different bit rates are required for each module, the user should select one of the other three time base options for one of the modules.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
PIR1	PMPIF <sup>(2)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65
PIE1	PMPIE <sup>(2)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65
IPR1	PMPIP <sup>(2)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65
TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	66
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	—	TRISC2	TRISC1	TRISC0	66
TRISD	TRISD7	TRISD6	TRISD5	TRISD4	TRISD3	TRISD2	TRISD1	TRISD0	66
SSP1BUF	MSSP1 Re	ceive Buffer	/Transmit R	egister					64
SSPxCON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	64
SSPxSTAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	64
SSP2BUF	MSSP2 Re	ceive Buffer	/Transmit R	egister	•	•	•		67
ODCON3 <sup>(1)</sup>							SPI2OD	SPI10D	68

TABLE 18-2: REGISTERS ASSOCIATED WITH SPI OPERATION

 $\label{eq:legend: Legend: Shaded cells are not used by the MSSP module in SPI mode.$ 

**Note 1:** Configuration SFR overlaps with default SFR at this address; available only when WDTCON<4> = 1.

2: These bits are only available on 44-pin devices.

### 18.4 SPI DMA MODULE

The SPI DMA module contains control logic to allow the MSSP2 module to perform SPI direct memory access transfers. This enables the module to quickly transmit or receive large amounts of data with relatively little CPU intervention. When the SPI DMA module is used, MSSP2 can directly read and write to general purpose SRAM. When the SPI DMA module is not enabled, MSSP2 functions normally, but without DMA capability.

The SPI DMA module is composed of control logic, a Destination Receive Address Pointer, a Transmit Source Address Pointer, an interrupt manager and a Byte Count register for setting the size of each DMA transfer. The DMA module may be used with all SPI Master and Slave modes, and supports both half-duplex and full-duplex transfers.

#### 18.4.1 I/O PIN CONSIDERATIONS

When enabled, the SPI DMA module uses the MSSP2 module. All SPI related input and output signals related to MSSP2 are routed through the Peripheral Pin Select module. The appropriate initialization procedure as described in **Section 18.4.6 "Using the SPI DMA Module"** will need to be followed prior to using the SPI DMA module. The output pins assigned to the SDO2 and SCK2 functions can optionally be configured as open-drain outputs, such as for level shifting operations mentioned in the same section.

#### 18.4.2 RAM TO RAM COPY OPERATIONS

Although the SPI DMA module is primarily intended to be used for SPI communication purposes, the module can also be used to perform RAM to RAM copy operations. To do this, configure the module for Full-Duplex Master mode operation, but assign the SDO2 output and SDI2 input functions onto the same RPn pin in the PPS module. Also assign SCK2 out and SCK2 in onto the same RPn pin (a different pin than used for SDO2 and SDI2). This will allow the module to operate in Loopback mode, providing RAM copy capability.

#### 18.4.3 IDLE AND SLEEP CONSIDERATIONS

The SPI DMA module remains fully functional when the microcontroller is in Idle mode.

During normal sleep, the SPI DMA module is not functional and should not be used. To avoid corrupting a transfer, user firmware should be careful to make certain that pending DMA operations are complete by polling the DMAEN bit in the DMACON1 register prior to putting the microcontroller into Sleep.

In SPI Slave modes, the MSSP2 module is capable of transmitting and/or receiving one byte of data while in Sleep mode. This allows the SSP2IF flag in the PIR3 register to be used as a wake-up source. When the DMAEN bit is cleared, the SPI DMA module is effectively disabled, and the MSSP2 module functions normally, but without DMA capabilities. If the DMAEN bit is clear prior to entering Sleep, it is still possible to use the SSP2IF as a wake-up source without any data loss.

Neither MSSP2 nor the SPI DMA module will provide any functionality in Deep Sleep. Upon exiting from Deep Sleep, all of the I/O pins, MSSP2 and SPI DMA related registers will need to be fully reinitialized before the SPI DMA module can be used again.

#### 18.4.4 REGISTERS

The SPI DMA engine is enabled and controlled by the following Special Function Registers:

- DMACON1
- DMACON2
   TXADDRL
- TXADDRHRXADDRH
- RXADDRL
- DMABCH
- DMABCL

#### 18.4.4.1 DMACON1

The DMACON1 register is used to select the main operating mode of the SPI DMA module. The SSCON1 and SSCON0 bits are used to control the slave select pin.

When MSSP2 is used in SPI Master mode with the SPI DMA module, SSDMA can be controlled by the DMA module as an output pin. If MSSP2 will be used to communicate with an SPI slave device that needs the SS pin to be toggled periodically, the SPI DMA hardware can automatically be used to deassert SS between each byte, every two bytes or every four bytes.

Alternatively, user firmware can manually generate slave select signals with normal general purpose I/O pins, if required by the slave device(s).

When the TXINC bit is set, the TXADDR register will automatically increment after each transmitted byte. Automatic transmit address increment can be disabled by clearing the TXINC bit. If the automatic transmit address increment is disabled, each byte which is output on SDO2, will be the same (the contents of the SRAM pointed to by the TXADDR register) for the entire DMA transaction.

When the RXINC bit is set, the RXADDR register will automatically increment after each received byte. Automatic receive address increment can be disabled by clearing the RXINC bit. If RXINC is disabled in Full-Duplex or Half-Duplex Receive modes, all incoming data bytes on SDI2 will overwrite the same memory location pointed to by the RXADDR register. After the SPI DMA transaction has completed, the last received byte will reside in the memory location pointed to by the RXADDR register.

The SPI DMA module can be used for either half-duplex receive only communication, half-duplex transmit only communication or full-duplex simultaneous transmit and receive operations. All modes are available for both SPI master and SPI slave configurations. The DUPLEX0 and DUPLEX1 bits can be used to select the desired operating mode.

The behavior of the DLYINTEN bit varies greatly depending on the SPI operating mode. For example behavior for each of the modes, see Figure 18-3 through Figure 18-6.

SPI Slave mode, DLYINTEN = 1: In this mode, an SSP2IF interrupt will be generated during a transfer if the time between successful byte transmission events is longer than the value set by the DLYCYC<3:0> bits in the DMACON2 register. This interrupt allows slave firmware to know that the master device is taking an unusually large amount of time between byte transmissions. For example, this information may be useful for implementing application-defined communication protocols involving time-outs if the bus remains Idle for too long. When DLYINTEN = 1, the DLYLVL<3:0> interrupts occur normally according to the selected setting.

SPI Slave mode, DLYINTEN = 0: In this mode, the time-out based interrupt is disabled. No additional SSP2IF interrupt events will be generated by the SPI DMA module, other than those indicated by the INTLVL<3:0> bits in the DMACON2 register. In this mode, always set DLYCYC<3:0> = 0000.

SPI Master mode, DLYINTEN = 0: The DLYCYC<3:0> bits in the DMACON2 register determine the amount of additional inter-byte delay, which is added by the <u>SPI</u> DMA module during a transfer. The Master mode <u>SS2</u> output feature may be used.

SPI Master mode, DLYINTEN = 1: The amount of hardware overhead is slightly reduced in this mode, and the minimum inter-byte delay is 8 TcY for Fosc/4, 9 TcY for Fosc/16 and 15 TcY for Fosc/64. This mode can potentially be used to obtain slightly higher effective SPI bandwidth. In this mode, the SS2 control feature cannot be used, and should always be disabled (DMACON1<7:6> = 00). Additionally, the interrupt generating hardware (used in Slave mode) remains active. To avoid extraneous SSP2IF interrupt events, set the DMACON2 delay bits, DLYCYC<3:0> = 1111, and ensure that the SPI serial clock rate is no slower than Fosc/64.

In SPI Master modes, the DMAEN bit is used to enable the SPI DMA module and to initiate an SPI DMA transaction. After user firmware sets the DMAEN bit, the DMA hardware will begin transmitting and/or receiving data bytes according to the configuration used. In SPI Slave modes, setting the DMAEN bit will finish the initialization steps needed to prepare the SPI DMA module for communication (which must still be initiated by the master device).

To avoid possible data corruption, once the DMAEN bit is set, user firmware should not attempt to modify any of the MSSP2 or SPI DMA related registers, with the exception of the INTLVL bits in the DMACON2 register.

If user firmware wants to halt an ongoing DMA transaction, the DMAEN bit can be manually cleared by the firmware. Clearing the DMAEN bit while a byte is currently being transmitted will not immediately halt the byte in progress. Instead, any byte currently in progress will be completed before the MSSP2 and SPI DMA modules go back to their Idle conditions. If user firmware clears the DMAEN bit, the TXADDR, RXADDR and DMABC registers will no longer update, and the DMA module will no longer make any additional read or writes to SRAM; therefore, state information can be lost.

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0						
SSCON1	SSCON0	TXINC	RXINC	DUPLEX1	DUPLEX0	DLYINTEN	DMAEN						
bit 7							bit (						
Legend:													
R = Readable	e bit	W = Writable	bit	U = Unimpler	nented bit, read	d as '0'							
-n = Value at	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkn	own						
bit 7-6	SSCON<1:0	>: SSDMA Out	out Control bit	ts (Master mode	es only)								
		<b>SSCON&lt;1:0&gt;:</b> SSDMA Output Control bits (Master modes only) 11 = SSDMA is asserted for the duration of 4 bytes; DLYINTEN is always reset low											
	01 = <u>SSDMA</u> is asserted for the duration of 2 bytes; DLYINTEN is always reset low												
		10 = <u>SSDMA</u> is asserted for the duration of 1 byte; DLYINTEN is always reset low 00 = <u>SSDMA</u> is not controlled by the DMA module; DLYINTEN bit is software programmable											
bit 5	TXINC: Transmit Address Increment Enable bit												
	Allows the transmit address to increment as the transfer progresses.												
	1 = The transmit address is to be incremented from the initial value of TXADDR<11:0>												
	0 = The trans	0 = The transmit address is always set to the initial value of TXADDR<11:0>											
bit 4		RXINC: Receive Address Increment Enable bit											
	Allows the receive address to increment as the transfer progresses.												
	<ul> <li>1 = The received address is to be incremented from the initial value of RXADDR&lt;11:0&gt;</li> <li>0 = The received address is always set to the initial value of RXADDR&lt;11:0&gt;</li> </ul>												
bit 3-2	<ul> <li>Ine received address is always set to the initial value of RXADDR&lt;11:0&gt;</li> <li>DUPLEX&lt;1:0&gt;: Transmit/Receive Operating Mode Select bits</li> </ul>												
	10 = SPI DMA operates in Full-Duplex mode, data is simultaneously transmitted and received												
	01 = DMA operates in Half-Duplex mode, data is transmitted only												
	00 = DMA operates in Half-Duplex mode, data is received only												
bit 1	DLYINTEN: Delay Interrupt Enable bit												
		Enables the interrupt to be invoked after the number of TCY cycles specified in DLYCYC<2:0> ha elapsed from the latest completed transfer.											
	•			> must be set t	<b>o</b> '00'								
	0 = The inter	rupt is disabled											
bit 0		A Operation St											
				art the DMA op eted or aborted		set back to zero	o by the DM						
	1 = DMA is ir												
	0 = DMA is n	ot in session											

#### REGISTER 18-3: DMACON1: DMA CONTROL REGISTER 1 (ACCESS F88h)

#### 18.4.4.2 DMACON2

The DMACON2 register contains control bits for controlling interrupt generation and inter-byte delay behavior. The INTLVL<3:0> bits are used to select when an SSP2IF interrupt should be generated. The function of the DLYCYC<3:0> bits depends on the SPI operating mode (Master/Slave), as well as the DLYINTEN setting. In SPI Master mode, the DLYCYC<3:0> bits can be used

to control how much time the module will Idle between bytes in a transfer. By default, the hardware requires a minimum delay of: 8 Tcy for Fosc/4, 9 Tcy for Fosc/16 and 15 Tcy for Fosc/64. Additional delay can be added with the DLYCYC bits. In SPI Slave modes, the DLYCYC<3:0> bits may optionally be used to trigger an additional time-out based interrupt.

#### REGISTER 18-4: DMACON2: DMA CONTROL REGISTER 2 (ACCESS F86h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
DLYCYC3	DLYCYC2	DLYCYC1	DLYCYC0	INTLVL3	INTLVL2	INTLVL1	INTLVL0	
bit 7		•				•	bit 0	
Legend:								
R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'								
-n = Value at P	OR	'1' = Bit is set		'0' = Bit is cleared x = Bit is unknown				

bit 7_4	DI VCVC<3:0>: Delay Cycle Selection hits
bit 7-4	DLYCYC<3:0>: Delay Cycle Selection bits When DLYINTEN = 0, these bits specify the additional delay (above the base overhead of the hard- ware) in number of Tcy cycles before the SSP2BUF register is written again for the next transfer. When DLYINTEN = 1, these bits specify the delay in number of Tcy cycles from the latest completed transfer before an interrupt to the CPU is invoked. In this case, the additional delay before the SSP2BUF register is written again is 1 Tcy + (base overhead of hardware). 1111 = Delay time in number of instruction cycles is 2,048 cycles 1110 = Delay time in number of instruction cycles is 1,024 cycles 1101 = Delay time in number of instruction cycles is 986 cycles 1101 = Delay time in number of instruction cycles is 640 cycles 1001 = Delay time in number of instruction cycles is 512 cycles 1011 = Delay time in number of instruction cycles is 512 cycles 1010 = Delay time in number of instruction cycles is 256 cycles 1011 = Delay time in number of instruction cycles is 246 cycles 1000 = Delay time in number of instruction cycles is 246 cycles 1011 = Delay time in number of instruction cycles is 256 cycles 1011 = Delay time in number of instruction cycles is 128 cycles 1010 = Delay time in number of instruction cycles is 128 cycles 1010 = Delay time in number of instruction cycles is 64 cycles 1010 = Delay time in number of instruction cycles is 64 cycles 0111 = Delay time in number of instruction cycles is 64 cycles 0102 = Delay time in number of instruction cycles is 64 cycles 0103 = Delay time in number of instruction cycles is 128 cycles 0104 = Delay time in number of instruction cycles is 64 cycles 0105 = Delay time in number of instruction cycles is 64 cycles 0106 = Delay time in number of instruction cycles is 16 cycles 0107 = Delay time in number of instruction cycles is 8 cycles 0108 = Delay time in number of instruction cycles is 8 cycles 0109 = Delay time in number of instruction cycles is 4 cycles 0101 = Delay time in number of instruction cycles
	0000 = Delay time in number of instruction cycles is 1 cycle
bit 3-0	INTLVL<3:0>: Watermark Interrupt Enable bits
	These bits specify the amount of remaining data yet to be transferred (transmitted and/or received) upon which an interrupt is generated.
	<ul> <li>1111 = Amount of remaining data to be transferred is 576 bytes</li> <li>1110 = Amount of remaining data to be transferred is 512 bytes</li> <li>1101 = Amount of remaining data to be transferred is 448 bytes</li> <li>1000 = Amount of remaining data to be transferred is 384 bytes</li> <li>1011 = Amount of remaining data to be transferred is 320 bytes</li> <li>1010 = Amount of remaining data to be transferred is 256 bytes</li> <li>1001 = Amount of remaining data to be transferred is 192 bytes</li> <li>1000 = Amount of remaining data to be transferred is 128 bytes</li> <li>1011 = Amount of remaining data to be transferred is 128 bytes</li> <li>1011 = Amount of remaining data to be transferred is 32 bytes</li> <li>1010 = Amount of remaining data to be transferred is 32 bytes</li> <li>1110 = Amount of remaining data to be transferred is 32 bytes</li> <li>1110 = Amount of remaining data to be transferred is 16 bytes</li> <li>1110 = Amount of remaining data to be transferred is 8 bytes</li> <li>1111 = Amount of remaining data to be transferred is 2 bytes</li> <li>1111 = Amount of remaining data to be transferred is 2 bytes</li> <li>1111 = Amount of remaining data to be transferred is 4 bytes</li> <li>1110 = Amount of remaining data to be transferred is 4 bytes</li> <li>1110 = Amount of remaining data to be transferred is 2 bytes</li> <li>111 = Amount of remaining data to be transferred is 2 bytes</li> <li>112 = Amount of remaining data to be transferred is 2 bytes</li> <li>113 = Amount of remaining data to be transferred is 2 bytes</li> <li>114 = Amount of remaining data to be transferred is 2 bytes</li> <li>115 = Amount of remaining data to be transferred is 2 bytes</li> <li>116 = Amount of remaining data to be transferred is 4 bytes</li> <li>111 = Amount of remaining data to be transferred is 1 byte</li> <li>112 = Amount of remaining data to be transferred is 1 byte</li> <li>114 = Amount of remaining data to be transferred is 1 byte</li> <li>115 = Amount of remaining data to be transferred is 1 byte</li> <li< th=""></li<></ul>

#### 18.4.4.3 DMABCH and DMABCL

The DMABCH and DMABCL register pair forms a 10-bit Byte Count register, which is used by the SPI DMA module to send/receive up to 1,024 bytes for each DMA transaction. When the DMA module is actively running (DMAEN = 1), the DMA Byte Count register decrements after each byte is transmitted/received. The DMA transaction will halt, and the DMAEN bit will be automatically cleared by hardware after the last byte has completed. After a DMA transaction is complete, the DMABC register will read 0x000.

Prior to initiating a DMA transaction by setting the DMAEN bit, user firmware should load the appropriate value into the DMABCH/DMABCL registers. The DMABC is a "base zero" counter, so the actual number of bytes, which will be transmitted, follows in Equation 18-1.

For example, if user firmware wants to transmit 7 bytes in one transaction, DMABC should be loaded with 006h. Similarly, if user firmware wishes to transmit 1,024 bytes, DMABC should be loaded with 3FFh.

#### EQUATION 18-1: BYTES TRANSMITTED FOR A GIVEN DMABC

Bytes<sub>XMIT</sub>  $\equiv$  (DMABC + 1)

### 18.4.4.4 TXADDRH and TXADDRL

The TXADDRH and TXADDRL registers pair together to form a 12-bit Transmit Source Address Pointer register. In modes that use TXADDR (Full-Duplex and Half-Duplex Transmit), the TXADDR will be incremented after each byte is transmitted. Transmitted data bytes will be taken from the memory location pointed to by the TXADDR register. The contents of the memory locations pointed to by TXADDR will not be modified by the DMA module during a transmission.

The SPI DMA module can read from and transmit data from all general purpose memory on the device, including memory used for USB endpoint buffers. The SPI DMA module cannot be used to read from the Special Function Registers (SFRs) contained in banks 14 and 15.

#### 18.4.4.5 RXADDRH and RXADDRL

The RXADDRH and RXADDRL register pair together to form a 12-bit Receive Destination Address Pointer. In modes that use RXADDR (Full-Duplex and Half-Duplex Receive), the RXADDR register will be incremented after each byte is received. Received data bytes will be stored at the memory location pointed to by the RXADDR register. The SPI DMA module can write received data to all general purpose memory on the device, including memory used for USB endpoint buffers. The SPI DMA module cannot be used to modify the Special Function Registers contained in banks 14 and 15.

#### 18.4.5 INTERRUPTS

The SPI DMA module alters the behavior of the SSP2IF interrupt flag. In normal/non-DMA modes, the SSP2IF is set once after every single byte is transmitted/received through the MSSP2 module. When MSSP2 is used with the SPI DMA module, the SSP2IF interrupt flag will be set according to the user-selected INTLVL<3:0> value specified in the DMACON2 register. The SSP2IF interrupt condition will also be generated once the SPI DMA transaction has fully completed, and the DMAEN bit has been cleared by hardware.

The SSP2IF flag becomes set once the DMA byte count value indicates that the specified INTLVL has been reached. For example, if DMACON2<3:0> = 0101 (16 bytes remaining), the SSP2IF interrupt flag will become set once DMABC reaches 00Fh. If user firmware then clears the SSP2IF interrupt flag, the flag will not be set again by the hardware until after all bytes have been fully transmitted, and the DMA transaction is complete.

**Note:** User firmware may modify the INTLVL bits while a DMA transaction is in progress (DMAEN = 1). If an INTLVL value is selected which is higher than the actual remaining number of bytes (indicated by DMABC + 1), the SSP2IF interrupt flag will immediately become set.

For example, if DMABC = 00Fh (implying 16 bytes are remaining) and user firmware writes '1111' to INTLVL<3:0> (interrupt when 576 bytes remaining), the SSP2IF interrupt flag will immediately become set. If user firmware clears this interrupt flag, a new interrupt condition will not be generated until either: user firmware again writes INTLVL with an interrupt level higher than the actual remaining level, or the DMA transaction completes and the DMAEN bit is cleared.

**Note:** If the INTLVL bits are modified while a DMA transaction is in progress, care should be taken to avoid inadvertently changing the DLYCYC<3:0> value.

#### 18.4.6 USING THE SPI DMA MODULE

The following steps would typically be taken to enable and use the SPI DMA module:

- 1. Configure the I/O pins, which will be used by MSSP2.
  - a) Assign SCK2, SDO2, SDI2 and SS2 to RPn pins as appropriate for the SPI mode which will be used. Only functions which will be used need to be assigned to a pin.
  - b) Initialize the associated LATx registers for the desired Idle SPI bus state.
  - c) If Open-Drain Output mode on SDO2 and SCK2 (Master mode) is desired, set ODCON3<1>.
  - d) Configure corresponding TRISx bits for each I/O pin used.
- 2. Configure and enable MSSP2 for the desired SPI operating mode.
  - a) Select the desired operating mode (Master or Slave, SPI Mode 0, 1, 2 and 3) and configure the module by writing to the SSP2STAT and SSP2CON1 registers.
  - b) Enable MSSP2 by setting SSP2CON1<5> = 1.
- 3. Configure the SPI DMA engine.
  - a) Select the desired operating mode by writing the appropriate values to DMACON2 and DMACON1.
  - b) Initialize the TXADDRH/TXADDRL Pointer (Full-Duplex or Half-Duplex Transmit Only mode).
  - c) Initialize the RXADDRH/RXADDRL Pointer (Full-Duplex or Half-Duplex Receive Only mode).
  - d) Initialize the DMABCH/DMABCL Byte Count register with the number of bytes to be transferred in the next SPI DMA operation.
  - e) Set the DMAEN bit (DMACON1<0>).

In SPI Master modes, this will initiate a DMA transaction. In SPI Slave modes, this will complete the initialization process, and the module will now be ready to begin receiving and/or transmitting data to the master device once the master starts the transaction.

- 4. Detect the SSP2IF interrupt condition (PIR3<7).
  - a) If the interrupt was configured to occur at the completion of the SPI DMA transaction, the DMAEN bit (DMACON1<0>) will be clear. User firmware may prepare the module for another transaction by repeating steps 3.b through 3.e.
  - b) If the interrupt was configured to occur prior to the completion of the SPI DMA transaction, the DMAEN bit may still be set, indicating the transaction is still in progress. User firmware would typically use this interrupt condition to begin preparing new data for the next DMA transaction. Firmware should not repeat steps 3.b. through 3.e. until the DMAEN bit is cleared by the hardware, indicating the transaction is complete.

Example 18-2 provides example code demonstrating the initialization process and the steps needed to use the SPI DMA module to perform a 512-byte Full-Duplex, Master mode transfer.

		;For this example, let's use RP5(RB2) for SCK2, ;RP4(RB1) for SDO2, and RP3(RB0) for SDI2
		;Let's use SPI master mode, CKE = 0, CKP = 0, ;without using slave select signalling.
InitSPIPins:	:	
movlb	0x0F	;Select bank 15, for access to ODCON3 register
bcf	ODCON3, SPI2OD	;Let's not use open drain outputs in this example
bcf	LATB, RB2	;Initialize our (to be) SCK2 pin low (idle).
bcf	LATB, RB1	;Initialize our (to be) SDO2 pin to an idle state
bcf	TRISB, RB1	;Make SDO2 output, and drive low
bcf	TRISB, RB2	;Make SCK2 output, and drive low (idle state)
bsf	TRISB, RBO	;SDI2 is an input, make sure it is tri-stated
		;Now we should unlock the PPS registers, so we can ;assign the MSSP2 functions to our desired I/O pins.
movlb bcf	0x0E INTCON, GIE	;Select bank 14 for access to PPS registers ;I/O Pin unlock sequence will not work if CPU
		;services an interrupt during the sequence
movlw	0x55	;Unlock sequence consists of writing 0x55
movwf	EECON2	;and 0xAA to the EECON2 register.
movlw	0xAA	
movwf	EECON2	
bcf bsf	PPSCON, IOLOCK INTCON, GIE	;We may now write to RPINRx and RPORx registers ;May now turn back on interrupts if desired
movlw	0x03	;RP3 will be SDI2
movwf	RPINR21	;Assign the SDI2 function to pin RP3
movlw	OxOA	;Let's assign SCK2 output to pin RP4
movwf	RPOR4	;RPOR4 maps output signals to RP4 pin
movlw	0×04	;SCK2 also needs to be configured as an input on the same pin
movwf	RPINR22	;SCK2 input function taken from RP4 pin
movlw	0x09	;0x09 is SD02 output
movwf	RPOR5	Assign SDO2 output signal to the RP5 (RB2) pin
movlb	0×0F	;Done with PPS registers, bank 15 has other SFRs
InitMSSP2:		
clrf	SSP2STAT	;CKE = 0, SMP = 0 (sampled at middle of bit)
movlw	b'00000000'	;CKP = 0, SPI Master mode, Fosc/4
movwf	SSP2CON1	;MSSP2 initialized
bsf	SSP2CON1, SSPEN	;Enable the MSSP2 module
InitSPIDMA:		
movlw	b'00111010'	;Full duplex, RX/TXINC enabled, no SSCON
movwf	DMACON1	;DLYINTEN is set, so DLYCYC3:DLYCYC0 = 1111
movlw	b'11110000'	;Minimum delay between bytes, interrupt
movwf	DMACON2	;only once when the transaction is complete

### EXAMPLE 18-2: 512-BYTE SPI MASTER MODE Init AND TRANSFER

٦

### EXAMPLE 18-2: 512-BYTE SPI MASTER MODE Init AND TRANSFER (CONTINUED)

			;Somewhere else in our project, lets assume we have ;allocated some RAM for use as SPI receive and ;transmit buffers.
; ;DestBuf ; ;SrcBuf	udata res res	0x500 0x200 0x200	;Let's reserve 0x500-0x6FF for use as our SPI ;receive data buffer in this example ;Lets reserve 0x700-0x8FF for use as our SPI
;	200	0112.0.0	;transmit data buffer in this example
PrepareTrans	sfer:		
movlw movwf movlw movwf	HIGH(Des RXADDRH LOW(Dest RXADDRL	,	;Get high byte of DestBuf address (0x05) ;Load upper four bits of the RXADDR register ;Get low byte of the DestBuf address (0x00) ;Load lower eight bits of the RXADDR register
movlw movwf movlw movwf	HIGH (Src TXADDRH LOW (SrcB TXADDRL		;Get high byte of SrcBuf address (0x07) ;Load upper four bits of the TXADDR register ;Get low byte of the SrcBuf address (0x00) ;Load lower eight bits of the TXADDR register
movlw movwf movlw movwf	0x01 DMABCH 0xFF DMABCL		;Lets move 0x200 (512) bytes in one DMA xfer ;Load the upper two bits of DMABC register ;Actual bytes transferred is (DMABC + 1), so ;we load 0x01FF into DMABC to xfer 0x200 bytes
BeginXfer:			
bsf	DMACON1,	DMAEN	;The SPI DMA module will now begin transferring ;the data taken from SrcBuf, and will store ;received bytes into DestBuf.
;Execute	whatever		;CPU is now free to do whatever it wants to ;and the DMA operation will continue without ;intervention, until it completes.
			;When the transfer is complete, the SSP2IF flag in ;the PIR3 register will become set, and the DMAEN bit ;is automatically cleared by the hardware. ;The DestBuf (0x500-0x7FF) will contain the received ;data. To start another transfer, firmware will need ;to reinitialize RXADDR, TXADDR, DMABC and then ;set the DMAEN bit.

Γ

### 18.5 I<sup>2</sup>C Mode


The MSSP module in I<sup>2</sup>C mode fully implements all master and slave functions (including general call support), and provides interrupts on Start and Stop bits in hardware to determine a free bus (multi-master function). The MSSP module implements the standard mode specifications and 7-bit and 10-bit addressing.

Two pins are used for data transfer:

- Serial Clock (SCLx) RB4/PMA1/KBI0/SCK1/SCL1/RP7 or RD0/PMD0/SCL2
- Serial Data (SDAx) RB5/PMA0/KBI1/SDI1/SDA1/RP8 or RD1/PMD1/SDA2

The user must configure these pins as inputs by setting the associated TRIS bits. These pins are up to 5.5V tolerant, allowing direct use in I<sup>2</sup>C busses operating at voltages higher than VDD.

#### FIGURE 18-7: MSSPx BLOCK DIAGRAM (I<sup>2</sup>C™ MODE)



#### 18.5.1 REGISTERS

The MSSP module has six registers for  $\mathsf{I}^2\mathsf{C}$  operation. These are:

- MSSPx Control Register 1 (SSPxCON1)
- MSSPx Control Register 2 (SSPxCON2)
- MSSPx Status Register (SSPxSTAT)
- Serial Receive/Transmit Buffer Register (SSPxBUF)
- MSSPx Shift Register (SSPxSR) Not directly accessible
- MSSPx Address Register (SSPxADD)
- MSSPx 7-Bit Address Mask Register (SSPxMSK)

SSPxCON1, SSPxCON2 and SSPxSTAT are the control and status registers in  $I^2C$  mode operation. The SSPxCON1 and SSPxCON2 registers are readable and writable. The lower six bits of the SSPxSTAT are read-only. The upper two bits of the SSPxSTAT are read/write.

SSPxSR is the shift register used for shifting data in or out. SSPxBUF is the buffer register to which data bytes are written to or read from.

SSPxADD contains the slave device address when the MSSP is configured in I<sup>2</sup>C Slave mode. When the MSSP is configured in Master mode, the lower seven bits of SSPxADD act as the Baud Rate Generator (BRG) reload value.

SSPxMSK holds the slave address mask value when the module is configured for 7-Bit Address Masking mode. While it is a separate register, it shares the same SFR address as SSPxADD; it is only accessible when the SSPM<3:0> bits are specifically set to permit access. Additional details are provided in Section 18.5.3.4 "7-Bit Address Masking Mode".

In receive operations, SSPxSR and SSPxBUF together, create a double-buffered receiver. When SSPxSR receives a complete byte, it is transferred to SSPxBUF and the SSPxIF interrupt is set.

During transmission, the SSPxBUF is not double-buffered. A write to SSPxBUF will write to both SSPxBUF and SSPxSR.

### REGISTER 18-5: SSPxSTAT: MSSPx STATUS REGISTER (I<sup>2</sup>C<sup>™</sup> MODE) (ACCESS FC7h, F73h)

R/W-1	R/W-1	R-1	R-1	R-1	R-1	R-1	R-1						
SMP	CKE	D/Ā	P <sup>(1)</sup>	S <sup>(1)</sup>	R/W <sup>(2,3)</sup>	UA	BF						
bit 7							bit C						
Lanandi													
Legend:	abla bit		L.14	II — I Inimania									
R = Reada		W = Writable '1' = Bit is set		-	mented bit, read								
-n = Value	alPOR	I = Bit is set		'0' = Bit is cl	eared	x = Bit is unkr	IOWI						
bit 7	SMP: Slew	Rate Control bit											
	In Master or	In Master or Slave mode:											
	1 = Slew ra	te control disabl			e (100 kHz and 1	MHz)							
		te control enable	ed for High-Sp	eed mode (40	0 kHz)								
bit 6	CKE: SMBu												
		<u>In Master or Slave mode:</u> 1 = Enable SMBus specific inputs											
		SMBus specific											
bit 5	D/A: Data/A	-											
	In Master m	ode:											
	Reserved.												
	In Slave mo												
		s that the last by s that the last by											
bit 4	P: Stop bit <sup>(1</sup>	-	te received of		as address								
	1 = Indicates	1 = Indicates that a Stop bit has been detected last											
	0 = Stop bit was not detected last												
bit 3	S: Start bit <sup>(1</sup>												
		s that a Start bit was not detecte		ected last									
bit 2	_	Write Information											
	In Slave mo												
	1 = Read												
	0 = Write												
	In Master m	<u>ode:</u> t is in progress											
		t is not in progre	SS										
bit 1		Address bit (10-		le only)									
					in the SSPxADD	register							
	0 = Address	does not need	to be updated										
bit 0	BF: Buffer F	ull Status bit											
	In Transmit												
	1 = SSPxBL 0 = SSPxBL												
	In Receive r												
		JF is full (does n	ot include the	ACK and Stop	bits)								
		JF is empty (doe											
Note 1:	This bit is cleare	ed on Reset and	when SSPEN	is cleared.									
2:	This bit holds th	e R/W bit inform	ation following	the last addre	ess match. This l	bit is only valid	from the						
	address match t					-							

3: ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSPx is in Active mode.

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0				
WCOL	SSPOV	SSPEN <sup>(1)</sup>	CKP	SSPM3 <sup>(2)</sup>	SSPM2 <sup>(2)</sup>	SSPM1 <sup>(2)</sup>	SSPM0 <sup>(2)</sup>				
bit 7						•	bit				
Legend:											
R = Reada	able bit	W = Writable	bit	U = Unimplen	nented bit, read	d as '0'					
-n = Value	at POR	'1' = Bit is set		'0' = Bit is clea		x = Bit is unkr	nown				
bit 7	WCOL · Write	e Collision Dete	ct bit								
	In Master Tra										
			IF register wa	is attempted wh	nile the I <sup>2</sup> C co	nditions were	not valid for				
				eared in softwa							
	0 = No collis	ion									
	In Slave Tran										
		-	is written while	e it is still transm	nitting the previ	ous word (mus	t be cleared i				
	software 0 = No collis	,									
		ode (Master or	Slave modes	۱.							
	This is a "dor			<u>.</u>							
bit 6	SSPOV: Receive Overflow Indicator bit										
	In Receive m	In Receive mode:									
	1 = A byte is	1 = A byte is received while the SSPxBUF register is still holding the previous byte (must be cleared									
		software)									
		0 = No overflow In Transmit mode:									
			ransmit mode								
bit 5		lon't care" bit in Transmit mode. laster Synchronous Serial Port Enable bit <sup>(1)</sup>									
bit o		the serial port and configures the SDAx and SCLx pins as the serial port pins									
				ese pins as I/O p							
bit 4	CKP: SCKx F	Release Contro	l bit								
		In Slave mode:									
		1 = Releases clock									
		<ul> <li>0 = Holds clock low (clock stretch); used to ensure data setup time In Master mode:</li> </ul>									
	Unused in thi										
bit 3-0	SSPM<3:0>:	Master Synchr	onous Serial I	Port Mode Selec	ct bits <sup>(2)</sup>						
				ith Start and Sto		enabled					
	1110 <b>= I<sup>2</sup>C S</b>	Blave mode, 7-b	it address wit	n Start and Stop	bit interrupts e						
				ode (slave Idle)							
				DD SFR addres * (SSPxADD +							
		Slave mode, 10-			'))						
		lave mode, 7-b									
Note 1:	When enabled, th	he SDAx and S	CLx pins mus	t be configured a	as inputs.						
2:	Bit combinations		-	-	-	ed in SPI mode	e only.				
3:	When SSPM<3:0 SSPxMSK registe	)> = 1001, any			-		-				
	•	ovoilable when	7 Dit Address	Mooking mode is	a alastad (MCC		nation bit is (1				

\_ \_ \_ \_ \_ \_ \_ \_ \_

4: This mode is only available when 7-Bit Address Masking mode is selected (MSSPMSK Configuration bit is '1').

# REGISTER 18-7: SSPxCON2: MSSPx CONTROL REGISTER 2 (I<sup>2</sup>C<sup>™</sup> MASTER MODE) (ACCESS FC5h, F71h)

		,					
R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
GCEN <sup>(3)</sup>	ACKSTAT	ACKDT <sup>(1)</sup>	ACKEN <sup>(2)</sup>	RCEN <sup>(2)</sup>	PEN <sup>(2)</sup>	RSEN <sup>(2)</sup>	SEN <sup>(2)</sup>
bit 7	÷						bit 0
Legend:							
R = Reada	ıble bit	W = Writable	bit	U = Unimplen	nented bit, rea	d as '0'	
-n = Value	at POR	'1' = Bit is set		'0' = Bit is clea		x = Bit is unkn	iown
bit 7	GCEN: Gene	ral Call Enable	bit (Slave mod	e only) <sup>(3)</sup>			
		terrupt when a	•	• ·	is received in	the SSPxSR	
	0 = General c	all address dis	abled				
bit 6	ACKSTAT: Ad	cknowledge Sta	atus bit (Master	Transmit mod	e only)		
		dge was not re		ave			
		dge was receiv					
bit 5		nowledge Data	bit (Master Red	ceive mode onl	y)(1)		
	1 = Not Ackno 0 = Acknowle	U U					
bit 4		nowledge Sequ	ience Enable b	;+(2)			
		• .			CLX nins and	transmits ACI	KDT data bit <sup>.</sup>
		cally cleared by	•				
	0 = Acknowle	edge sequence	Idle				
bit 3		ve Enable bit (I		e mode only) <sup>(2)</sup>			
		Receive mode f	or I <sup>2</sup> C				
	0 = Receive l						
bit 2		ondition Enable					
	1 = Initiates S 0 = Stop cond		n SDAx and So	Lx pins; autor	natically cleare	ed by hardware	
bit 1		ated Start Cond	lition Enable bi	<sub>t</sub> (2)			
bit i					pins: automat	tically cleared by	/ hardware
		d Start condition			pino, automa		, naranaro
bit 0	SEN: Start Co	ondition Enable	bit <sup>(2)</sup>				
	1 = Initiates S	start condition o	n SDAx and S	CLx pins; autor	matically clear	ed by hardware	
	0 = Start cond	lition Idle					
Note 1:	Value that will be	transmitted wh	en the user init	iates an Ackno	wledae seaue	ence at the end o	of a receive.
	If the I <sup>2</sup> C module				• ·		
	(or writes to the S	SPxBUF are d	isabled).			-	

**3:** This bit is not implemented in I<sup>2</sup>C Master mode.

#### REGISTER 18-8: SSPxCON2: MSSPx CONTROL REGISTER 2 (I<sup>2</sup>C<sup>™</sup> SLAVE MODE) (ACCESS FC5h, F71h)

	•		,									
R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0					
GCEN	ACKSTAT <sup>(2)</sup>	ADMSK5	ADMSK4	ADMSK3	ADMSK2	ADMSK1	SEN <sup>(1)</sup>					
bit 7							bit 0					
Legend:												
R = Readab	le bit	W = Writable	bit	U = Unimplem	nented bit, read	l as '0'						
-n = Value a	t POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkn	own					
bit 7	GCEN: Gener	al Call Enable	bit (Slave mod	le only)								
	1 = Enables ir 0 = General ca		0	ddress (0000h)	) is received in	the SSPxSR						
bit 6	ACKSTAT: Ac	ACKSTAT: Acknowledge Status bit <sup>(2)</sup>										
	Unused in Slave mode.											
bit 5-2	ADMSK<5:2>	ADMSK<5:2>: Slave Address Mask Select bits (5-Bit Address Masking)										
	1 = Masking of corresponding bits of SSPxADD enabled											
	0 = Masking o	f correspondin	g bits of SSPx	ADD disabled								
bit 1		ADMSK1: Slave Address Least Significant bit(s) Mask Select bit										
		In 7-Bit Addressing mode:										
	0	1 = Masking of SSPxADD<1> only enabled 0 = Masking of SSPxADD<1> only disabled										
	0	In 10-Bit Addressing mode:										
	1 = Masking o		:0> enabled									
	0 = Masking o	f SSPxADD<1	:0> disabled									
bit 0	SEN: Start Co	ndition Enable	/Stretch Enabl	e bit <sup>(1)</sup>								
	1 = Clock stre 0 = Clock stre	-		ve transmit and	I slave receive	(stretch enable	d)					
Note 1: If	the I <sup>2</sup> C module i	s active, these	bits may not t	be set (no spool	ling) and the S	SPxBUF may n	ot be writter					

**lote 1:** If the I<sup>2</sup>C module is active, these bits may not be set (no spooling) and the SSPxBUF may not be written (or writes to the SSPxBUF are disabled).

2: This bit is unimplemented in I<sup>2</sup>C Slave mode.

#### REGISTER 18-9: SSPxMSK: I<sup>2</sup>C<sup>™</sup> SLAVE ADDRESS MASK REGISTER (7-BIT MASKING MODE) (ACCESS FC8h, F74h)<sup>(1)</sup>

| R/W-1               |
|-------|-------|-------|-------|-------|-------|-------|---------------------|
| MSK7  | MSK6  | MSK5  | MSK4  | MSK3  | MSK2  | MSK1  | MSK0 <sup>(2)</sup> |
| bit 7 |       |       |       |       |       |       | bit 0               |

Legend:				
R = Readable bit	Readable bit W = Writable bit U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

bit 7-0 MSK<7:0>: Slave Address Mask Select bits

- 1 = Masking of corresponding bit of SSPxADD enabled
- 0 = Masking of corresponding bit of SSPxADD disabled
- Note 1: This register shares the same SFR address as SSPxADD and is only addressable in select MSSP operating modes. See Section 18.5.3.4 "7-Bit Address Masking Mode" for more details.
  - 2: MSK0 is not used as a mask bit in 7-bit addressing.

#### 18.5.2 OPERATION

The MSSP module functions are enabled by setting the MSSP Enable bit, SSPEN (SSPxCON1<5>).

The SSPxCON1 register allows control of the  $I^2C$  operation. Four mode selection bits (SSPxCON1<3:0>) allow one of the following  $I^2C$  modes to be selected:

- I<sup>2</sup>C Master mode, clock
- I<sup>2</sup>C Slave mode (7-bit address)
- I<sup>2</sup>C Slave mode (10-bit address)
- I<sup>2</sup>C Slave mode (7-bit address) with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Slave mode (10-bit address) with Start and Stop bit interrupts enabled
- I<sup>2</sup>C Firmware Controlled Master mode, slave is Idle

Selection of any I<sup>2</sup>C mode with the SSPEN bit set forces the SCLx and SDAx pins to be open-drain, provided these pins are programmed as inputs by setting the appropriate TRISB or TRISD bits. To ensure proper operation of the module, pull-up resistors must be provided externally to the SCLx and SDAx pins.

#### 18.5.3 SLAVE MODE

In Slave mode, the SCLx and SDAx pins must be configured as inputs (TRISB<5:4> set). The MSSP module will override the input state with the output data when required (slave-transmitter).

The  $I^2C$  Slave mode hardware will always generate an interrupt on an address match. Address masking will allow the hardware to generate an interrupt for more than one address (up to 31 in 7-bit addressing and up to 63 in 10-bit addressing). Through the mode select bits, the user can also choose to interrupt on Start and Stop bits.

When an address is matched, or the data transfer after an address match is received, the hardware automatically will generate the Acknowledge (ACK) pulse and load the SSPxBUF register with the received value currently in the SSPxSR register.

Any combination of the following conditions will cause the MSSP module not to give this ACK pulse:

- The Buffer Full bit, BF (SSPxSTAT<0>), was set before the transfer was received.
- The overflow bit, SSPOV (SSPxCON1<6>), was set before the transfer was received.

In this case, the SSPxSR register value is not loaded into the SSPxBUF, but bit SSPxIF is set. The BF bit is cleared by reading the SSPxBUF register, while bit SSPOV is cleared through software. The SCLx clock input must have a minimum high and low for proper operation. The high and low times of the  $I^2C$  specification, as well as the requirement of the MSSP module, are shown in timing parameter 100 and parameter 101.

#### 18.5.3.1 Addressing

Once the MSSP module has been enabled, it waits for a Start condition to occur. Following the Start condition, the 8 bits are shifted into the SSPxSR register. All incoming bits are sampled with the rising edge of the clock (SCLx) line. The value of register, SSPxSR<7:1>, is compared to the value of the SSPxADD register. The address is compared on the falling edge of the eighth clock (SCLx) pulse. If the addresses match and the BF and SSPOV bits are clear, the following events occur:

- 1. The SSPxSR register value is loaded into the SSPxBUF register.
- 2. The Buffer Full bit, BF, is set.
- 3. An ACK pulse is generated.
- 4. The MSSPx Interrupt Flag bit, SSPxIF, is set (and interrupt is generated, if enabled) on the falling edge of the ninth SCLx pulse.

In 10-Bit Addressing mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit  $R/\overline{W}$  (SSPxSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal '11110 A9 A8 0', where 'A9' and 'A8' are the two MSbs of the address. The sequence of events for 10-bit addressing is as follows, with steps 7 through 9 for the slave-transmitter:

- 1. Receive first (high) byte of address (bits, SSPxIF, BF and UA, are set on address match).
- 2. Update the SSPxADD register with second (low) byte of address (clears bit, UA, and releases the SCLx line).
- 3. Read the SSPxBUF register (clears bit, BF) and clear flag bit, SSPxIF.
- 4. Receive second (low) byte of address (bits, SSPxIF, BF and UA, are set).
- 5. Update the SSPxADD register with the first (high) byte of address. If match releases SCLx line, this will clear bit, UA.
- 6. Read the SSPxBUF register (clears bit, BF) and clear flag bit, SSPxIF.
- 7. Receive Repeated Start condition.
- 8. Receive first (high) byte of address (bits, SSPxIF and BF, are set).
- 9. Read the SSPxBUF register (clears bit, BF) and clear flag bit, SSPxIF.

#### 18.5.3.2 Address Masking Modes

Masking an address bit causes that bit to become a "don't care". When one address bit is masked, two addresses will be Acknowledged and cause an interrupt. It is possible to mask more than one address bit at a time, which greatly expands the number of addresses Acknowledged.

The  $l^2C$  slave behaves the same way, whether address masking is used or not. However, when address masking is used, the  $l^2C$  slave can Acknowledge multiple addresses and cause interrupts. When this occurs, it is necessary to determine which address caused the interrupt by checking SSPxBUF.

The PIC18F46J50 Family of devices is capable of using two different Address Masking modes in I<sup>2</sup>C slave operation: 5-Bit Address Masking and 7-Bit Address Masking. The Masking mode is selected at device configuration using the MSSPMSK Configuration bit. The default device configuration is 7-Bit Address Masking.

Both Masking modes, in turn, support address masking of 7-bit and 10-bit addresses. The combination of Masking modes and addresses provide different ranges of Acknowledgable addresses for each combination.

While both Masking modes function in roughly the same manner, the way they use address masks is different.

#### 18.5.3.3 5-Bit Address Masking Mode

As the name implies, 5-Bit Address Masking mode uses an address mask of up to five bits to create a range of addresses to be Acknowledged, using bits 5 through 1 of the incoming address. This allows the module to Acknowledge up to 31 addresses when using 7-bit addressing, or 63 addresses with 10-bit addressing (see Example 18-3). This Masking mode is selected when the MSSPMSK Configuration bit is programmed ('0').

The address mask in this mode is stored in the SSPxCON2 register, which stops functioning as a control register in I<sup>2</sup>C Slave mode (Register 18-8). In 7-Bit Address Masking mode, address mask bits, ADMSK<5:1> (SSPxCON2<5:1>), mask the corresponding address bits in the SSPxADD register. For any ADMSK bits that are set (ADMSK<n> = 1), the corresponding address bit is ignored (SSPxADD<n> = x). For the module to issue an address Acknowledge, it is sufficient to match only on addresses that do not have an active address mask.

In 10-Bit Address Masking mode, bits, ADMSK<5:2>, mask the corresponding address bits in the SSPxADD register. In addition, ADMSK1 simultaneously masks the two LSbs of the address (SSPxADD<1:0>). For any ADMSK bits that are active (ADMSK<n> = 1), the corresponding address bit is ignored (SPxADD<n> = x). Also note, that although in 10-Bit Address Masking mode, the upper address bits reuse part of the SSPxADD register bits. The address mask bits do not interact with those bits; they only affect the lower address bits.

**Note 1:** ADMSK1 masks the two Least Significant bits of the address.

2: The two MSbs of the address are not affected by address masking.

#### EXAMPLE 18-3: ADDRESS MASKING EXAMPLES IN 5-BIT MASKING MODE

#### 7-Bit Addressing:

SSPxADD<7:1>= A0h (1010000) (SSPxADD<0> is assumed to be '0')

#### ADMSK<5:1> = 00111

Addresses Acknowledged: A0h, A2h, A4h, A6h, A8h, AAh, ACh, AEh

#### 10-Bit Addressing:

SSPxADD<7:0> = A0h (10100000) (The two MSbs of the address are ignored in this example, since they are not affected by masking)

ADMSK<5:1> = 00111

Addresses Acknowledged: A0h, A1h, A2h, A3h, A4h, A5h, A6h, A7h, A8h, A9h, AAh, ABh, ACh, ADh, AEh, AFh

#### 18.5.3.4 7-Bit Address Masking Mode

Unlike 5-Bit Address Masking mode, 7-Bit Address Masking mode uses a mask of up to eight bits (in 10-bit addressing) to define a range of addresses than can be Acknowledged, using the lowest bits of the incoming address. This allows the module to Acknowledge up to 127 different addresses with 7-bit addressing, or 255 with 10-bit addressing (see Example 18-4). This mode is the default configuration of the module, and is selected when MSSPMSK is unprogrammed ('1').

The address mask for 7-Bit Address Masking mode is stored in the SSPxMSK register, instead of the SSPxCON2 register. SSPxMSK is a separate hardware register within the module, but it is not directly addressable. Instead, it shares an address in the SFR space with the SSPxADD register. To access the SSPxMSK register, it is necessary to select MSSP mode, '1001' (SSPCON1<3:0> = 1001), and then read or write to the location of SSPxADD.

To use 7-Bit Address Masking mode, it is necessary to initialize SSPxMSK with a value before selecting the  $I^2C$  Slave Addressing mode. Thus, the required sequence of events is:

- 1. Select SSPxMSK Access mode (SSPxCON2<3:0> = 1001).
- 2. Write the mask value to the appropriate SSPxADD register address (FC8h for MSSP1, F6Eh for MSSP2).
- 3. Set the appropriate I<sup>2</sup>C Slave mode (SSPxCON2<3:0> = 0111 for 10-bit addressing, 0110 for 7-bit addressing).

Setting or clearing mask bits in SSPxMSK behaves in the opposite manner of the ADMSK bits in 5-Bit Address Masking mode. That is, clearing a bit in SSPxMSK causes the corresponding address bit to be masked; setting the bit requires a match in that position. SSPxMSK resets to all '1's upon any Reset condition and, therefore, has no effect on the standard MSSP operation until written with a mask value.

With 7-Bit Address Masking mode, SSPxMSK<7:1> bits mask the corresponding address bits in the SSPxADD register. For any SSPxMSK bits that are active (SSPxMSK<n> = 0), the corresponding SSPxADD address bit is ignored (SSPxADD<n> = x). For the module to issue an address Acknowledge, it is sufficient to match only on addresses that do not have an active address mask.

With 10-Bit Address Masking mode, SSPxMSK<7:0> bits mask the corresponding address bits in the SSPxADD register. For any SSPxMSK bits that are active (= 0), the corresponding SSPxADD address bit is ignored (SSPxADD<n> = x).

Note: The two MSbs of the address are not affected by address masking.

#### EXAMPLE 18-4: ADDRESS MASKING EXAMPLES IN 7-BIT MASKING MODE

#### 7-Bit Addressing:

SSPxADD<7:1>= 1010 000

SSPxMSK<7:1>= 1111 001

Addresses Acknowledged = A8h, A6h, A4h, A0h

#### 10-Bit Addressing:

SSPxADD<7:0> = 1010 0000 (The two MSbs are ignored in this example since they are not affected)

**SSPxMSK<5:1> =** 1111 0

Addresses Acknowledged = A8h, A6h, A4h, A0h

#### 18.5.3.5 Reception

When the R/W bit of the address byte is clear and an address match occurs, the R/W bit of the SSPxSTAT register is cleared. The received address is loaded into the SSPxBUF register and the SDAx line is held low (ACK).

When the address byte overflow condition exists, then the no Acknowledge (ACK) pulse is given. An overflow condition is defined as either bit, BF (SSPxSTAT<0>), is set or bit, SSPOV (SSPxCON1<6>), is set.

An MSSP interrupt is generated for each data transfer byte. The interrupt flag bit, SSPxIF, must be cleared in software. The SSPxSTAT register is used to determine the status of the byte.


If SEN is enabled (SSPxCON2<0> = 1), SCLx will be held low (clock stretch) following each data transfer. The clock must be released by setting bit, CKP (SSPxCON1<4>). See **Section 18.5.4** "Clock **Stretching**" for more details.

#### 18.5.3.6 Transmission


When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPxSTAT register is set. The received address is loaded into the SSPxBUF register. The ACK pulse will be sent on the ninth bit and pin SCLx is held low regardless of SEN (see Section 18.5.4 "Clock Stretching" for more details). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data. The transmit data must be loaded into the SSPxBUF register, which also loads the SSPxSR register. Then, the SCLx pin be enabled by setting bit, should CKP (SSPxCON1<4>). The eight data bits are shifted out on the falling edge of the SCLx input. This ensures that the SDAx signal is valid during the SCLx high time (Figure 18-10).


The  $\overline{ACK}$  pulse from the master-receiver is latched on the rising edge of the ninth SCLx input pulse. If the SDAx line is high (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the  $\overline{ACK}$  is latched by the slave, the slave logic is reset (resets the SSPxSTAT register) and the slave monitors for another occurrence of the Start bit. If the SDAx line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPxBUF register. Again, the SCLx pin must be enabled by setting bit, CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPxIF bit must be cleared in software and the SSPxSTAT register is used to determine the status of the byte. The SSPxIF bit is set on the falling edge of the ninth clock pulse.




















#### 18.5.4 CLOCK STRETCHING

Both 7-Bit and 10-Bit Slave modes implement automatic clock stretching during a transmit sequence.

The SEN bit (SSPxCON2<0>) allows clock stretching to be enabled during receives. Setting SEN will cause the SCLx pin to be held low at the end of each data receive sequence.

#### 18.5.4.1 Clock Stretching for 7-Bit Slave Receive Mode (SEN = 1)

In 7-Bit Slave Receive mode, on the falling edge of the ninth clock at the end of the ACK sequence, if the BF bit is set, the CKP bit in the SSPxCON1 register is automatically cleared, forcing the SCLx output to be held low. The CKP bit being cleared to '0' will assert the SCLx line low. The CKP bit must be set in the user's ISR before reception is allowed to continue. By holding the SCLx line low, the user has time to service the ISR and read the contents of the SSPxBUF before the master device can initiate another receive sequence. This will prevent buffer overruns from occurring (see Figure 18-15).

- Note 1: If the user reads the contents of the SSPxBUF before the falling edge of the ninth clock, thus clearing the BF bit, the CKP bit will not be cleared and clock stretching will not occur.
  - 2: The CKP bit can be set in software regardless of the state of the BF bit. The user should be careful to clear the BF bit in the ISR before the next receive sequence in order to prevent an overflow condition.

#### 18.5.4.2 Clock Stretching for 10-Bit Slave Receive Mode (SEN = 1)

In 10-Bit Slave Receive mode, during the address sequence, clock stretching automatically takes place but CKP is not cleared. During this time, if the UA bit is set after the ninth clock, clock stretching is initiated. The UA bit is set after receiving the upper byte of the 10-bit address and following the receive of the second byte of the 10-bit address with the R/W bit cleared to '0'. The release of the clock line occurs upon updating SSPxADD. Clock stretching will occur on each data receive sequence as described in 7-bit mode.

**Note:** If the user polls the UA bit and clears it by updating the SSPxADD register before the falling edge of the ninth clock occurs, and if the user has not cleared the BF bit by reading the SSPxBUF register before that time, then the CKP bit will still NOT be asserted low. Clock stretching on the basis of the state of the BF bit only occurs during a data sequence, not an address sequence.

#### 18.5.4.3 Clock Stretching for 7-Bit Slave Transmit Mode

The 7-Bit Slave Transmit mode implements clock stretching by clearing the CKP bit after the falling edge of the ninth clock if the BF bit is clear. This occurs regardless of the state of the SEN bit.

The user's Interrupt Service Routine (ISR) must set the CKP bit before transmission is allowed to continue. By holding the SCLx line low, the user has time to service the ISR and load the contents of the SSPxBUF before the master device can initiate another transmit sequence (see Figure 18-10).

- Note 1: If the user loads the contents of SSPxBUF, setting the BF bit before the falling edge of the ninth clock, the CKP bit will not be cleared and clock stretching will not occur.
  - **2:** The CKP bit can be set in software regardless of the state of the BF bit.


#### 18.5.4.4 Clock Stretching for 10-Bit Slave Transmit Mode

In 10-Bit Slave Transmit mode, clock stretching is controlled during the first two address sequences by the state of the UA bit, just as it is in 10-Bit Slave Receive mode. The first two addresses are followed by a third address sequence, which contains the high-order bits of the 10-bit address and the R/W bit set to '1'. After the third address sequence is performed, the UA bit is not set, the module is now configured in Transmit mode and clock stretching is controlled by the BF flag as in 7-Bit Slave Transmit mode (see Figure 18-13).


#### 18.5.4.5 Clock Synchronization and CKP bit


When the CKP bit is cleared, the SCLx output is forced to '0'. However, clearing the CKP bit will not assert the SCLx output low until the SCLx output is already sampled low. Therefore, the CKP bit will not assert the SCLx line until an external  $I^2C$  master device has

already asserted the SCLx line. The SCLx output will remain low until the CKP bit is set and all other devices on the  $l^2$ C bus have deasserted SCLx. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCLx (see Figure 18-14).



#### FIGURE 18-14: CLOCK SYNCHRONIZATION TIMING





#### 18.5.5 GENERAL CALL ADDRESS SUPPORT

The addressing procedure for the  $I^2C$  bus is such that the first byte after the Start condition usually determines which device will be the slave addressed by the master. The exception is the general call address which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is one of eight addresses reserved for specific purposes by the I<sup>2</sup>C protocol. It consists of all '0's with R/W = 0.


The general call address is recognized when the General Call Enable bit, GCEN, is enabled (SSPxCON2<7> set). Following a Start bit detect, 8 bits are shifted into the SSPxSR and the address is compared against the SSPxADD. It is also compared to the general call address and fixed in hardware.

If the general call address matches, the SSPxSR is transferred to the SSPxBUF, the BF flag bit is set (eighth bit), and on the falling edge of the ninth bit (ACK bit), the SSPxIF interrupt flag bit is set.

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the SSPxBUF. The value can be used to determine if the address was device-specific or a general call address.

In 10-bit mode, the SSPxADD is required to be updated for the second half of the address to match and the UA bit is set (SSPxSTAT<1>). If the general call address is sampled when the GCEN bit is set, while the slave is configured in 10-Bit Addressing mode, then the second half of the address is not necessary, the UA bit will not be set and the slave will begin receiving data after the Acknowledge (Figure 18-17).





#### 18.5.6 MASTER MODE

Master mode is enabled by setting and clearing the appropriate SSPM bits in SSPxCON1 and by setting the SSPEN bit. In Master mode, the SCLx and SDAx lines are manipulated by the MSSP hardware if the TRIS bits are set.

Master mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Start (S) and Stop (P) bits are cleared from a Reset or when the MSSP module is disabled. Control of the  $I^{2}C$  bus may be taken when the Stop bit is set, or the bus is Idle, with both the Start and Stop bits clear.

In Firmware Controlled Master mode, user code conducts all  $I^2C$  bus operations based on Start and Stop bit conditions.

Once Master mode is enabled, the user has six options.


- 1. Assert a Start condition on SDAx and SCLx.
- 2. Assert a Repeated Start condition on SDAx and SCLx.
- 3. Write to the SSPxBUF register initiating transmission of data/address.
- 4. Configure the  $I^2C$  port to receive data.
- 5. Generate an Acknowledge condition at the end of a received byte of data.
- 6. Generate a Stop condition on SDAx and SCLx.

Note: The MSSP module, when configured in I<sup>2</sup>C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a Start condition and immediately write the SSPxBUF register to initiate transmission before the Start condition is complete. In this case, the SSPxBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPxBUF did not occur.

The following events will cause the MSSP Interrupt Flag bit, SSPxIF, to be set (and MSSP interrupt, if enabled):

- · Start condition
- Stop condition
- · Data transfer byte transmitted/received
- · Acknowledge transmitted
- Repeated Start

#### FIGURE 18-18: MSSPx BLOCK DIAGRAM (I<sup>2</sup>C<sup>™</sup> MASTER MODE)



#### 18.5.6.1 I<sup>2</sup>C Master Mode Operation

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus will not be released.

In Master Transmitter mode, serial data is output through SDAx while SCLx outputs the serial clock. The first byte transmitted contains the slave address of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. S and P conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the  $R/\overline{W}$  bit. In this case, the  $R/\overline{W}$  bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address, followed by a '1' to indicate the receive bit. Serial data is received via SDAx, while SCLx outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. S and P conditions indicate the beginning and end of transmission.

The BRG, used for the SPI mode operation, is used to set the SCLx clock frequency for either 100 kHz, 400 kHz or 1 MHz  $I^2$ C operation. See **Section 18.5.7 "Baud Rate"** for more details.

A typical transmit sequence would go as follows:

- 1. The user generates a Start condition by setting the Start Enable bit, SEN (SSPxCON2<0>).
- SSPxIF is set. The MSSP module will wait for the required start time before any other operation takes place.
- 3. The user loads the SSPxBUF with the slave address to transmit.
- 4. Address is shifted out of the SDAx pin until all 8 bits are transmitted.
- The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPxCON2 register (SSPxCON2<6>).
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPxIF bit.
- 7. The user loads the SSPxBUF with 8 bits of data.
- 8. Data is shifted out the SDAx pin until all 8 bits are transmitted.
- The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPxCON2 register (SSPxCON2<6>).
- 10. The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPxIF bit.
- 11. The user generates a Stop condition by setting the Stop Enable bit, PEN (SSPxCON2<2>).
- 12. Interrupt is generated once the Stop condition is complete.

#### 18.5.7 BAUD RATE

In I<sup>2</sup>C Master mode, the BRG reload value is placed in the lower seven bits of the SSPxADD register (Figure 18-19). When a write occurs to SSPxBUF, the Baud Rate Generator will automatically begin counting. The BRG counts down to 0 and stops until another reload has taken place. The BRG count is decremented twice per instruction cycle (TcY) on the Q2 and Q4 clocks. In I<sup>2</sup>C Master mode, the BRG is reloaded automatically.

Once the given operation is complete (i.e., transmission of the last data bit is followed by ACK), the internal clock will automatically stop counting and the SCLx pin will remain in its last state.


Table 18-3 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPxADD.

#### 18.5.7.1 Baud Rate and Module Interdependence

Because MSSP1 and MSSP2 are independent, they can operate simultaneously in  $I^2C$  Master mode at different baud rates. This is done by using different BRG reload values for each module.

Because this mode derives its basic clock source from the system clock, any changes to the clock will affect both modules in the same proportion. It may be possible to change one or both baud rates back to a previous value by changing the BRG reload value.

#### FIGURE 18-19: BAUD RATE GENERATOR BLOCK DIAGRAM



#### TABLE 18-3: I<sup>2</sup>C<sup>™</sup> CLOCK RATE w/BRG

Fosc	Fcy	Fcy * 2	BRG Value	FSCL (2 Rollovers of BRG)
40 MHz	10 MHz	20 MHz	18h	400 kHz <sup>(1)</sup>
40 MHz	10 MHz	20 MHz	1Fh	312.5 kHz
40 MHz	10 MHz	20 MHz	63h	100 kHz
16 MHz	4 MHz	8 MHz	09h	400 kHz <sup>(1)</sup>
16 MHz	4 MHz	8 MHz	0Ch	308 kHz
16 MHz	4 MHz	8 MHz	27h	100 kHz
4 MHz	1 MHz	2 MHz	02h	333 kHz <sup>(1)</sup>
4 MHz	1 MHz	2 MHz	09h	100 kHz
4 MHz	1 MHz	2 MHz	00h	1 MHz <sup>(1)</sup>


**Note 1:** The I<sup>2</sup>C interface does not conform to the 400 kHz I<sup>2</sup>C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.

#### 18.5.7.2 Clock Arbitration

Clock arbitration occurs when the master, during any receive, transmit or Repeated Start/Stop condition, deasserts the SCLx pin (SCLx allowed to float high). When the SCLx pin is allowed to float high, the BRG is suspended from counting until the SCLx pin is actually

sampled high. When the SCLx pin is sampled high, the BRG is reloaded with the contents of SSPxADD<6:0> and begins counting. This ensures that the SCLx high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 18-20).





#### 18.5.8 I<sup>2</sup>C MASTER MODE START CONDITION TIMING


To initiate a Start condition, the user sets the Start Enable bit, SEN (SSPxCON2<0>). If the SDAx and SCLx pins are sampled high, the BRG is reloaded with the contents of SSPxADD<6:0> and starts its count. If SCLx and SDAx are both sampled high when the Baud Rate Generator times out (TBRG), the SDAx pin is driven low. The action of the SDAx being driven low while SCLx is high is the Start condition and causes the Start bit (SSPxSTAT<3>) to be set. Following this, the BRG is reloaded with the contents of SSPxADD<6:0> and resumes its count. When the BRG times out (TBRG), the SEN bit (SSPxCON2<0>) will be automatically cleared by hardware. The BRG is suspended, leaving the SDAx line held low and the Start condition is complete.

# Note: If, at the beginning of the Start condition, the SDAx and SCLx pins are already sampled low, or if during the Start condition, the SCLx line is sampled low, before the SDAx line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag, BCLxIF, is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.

#### 18.5.8.1 WCOL Status Flag

If the user writes the SSPxBUF when a Start sequence is in progress, the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

Note: Because queueing of events is not allowed, writing to the lower five bits of SSPxCON2 is disabled until the Start condition is complete.



#### FIGURE 18-21: FIRST START BIT TIMING

#### 18.5.9 I<sup>2</sup>C MASTER MODE REPEATED START CONDITION TIMING

A Repeated Start condition occurs when the RSEN bit (SSPxCON2<1>) is programmed high and the I<sup>2</sup>C logic module is in the Idle state. When the RSEN bit is set, the SCLx pin is asserted low. When the SCLx pin is sampled low, the BRG is loaded with the contents of SSPxADD<5:0> and begins counting. The SDAx pin is released (brought high) for one BRG count (TBRG). When the BRG times out, and if SDAx is sampled high, the SCLx pin will be deasserted (brought high). When SCLx is sampled high, the BRG is reloaded with the contents of SSPxADD<6:0> and begins counting. SDAx and SCLx must be sampled high for one TBRG. This action is then followed by assertion of the SDAx pin (SDAx = 0) for one TBRG while SCLx is high. Following this, the RSEN bit (SSPxCON2<1>) will be automatically cleared and the BRG will not be reloaded, leaving the SDAx pin held low. As soon as a Start condition is detected on the SDAx and SCLx pins, the Start bit (SSPxSTAT<3>) will be set. The SSPxIF bit will not be set until the BRG has timed out.

- Note 1: If RSEN is programmed while any other event is in progress, it will not take effect.
  - **2:** A bus collision during the Repeated Start condition occurs if:
    - SDAx is sampled low when SCLx goes from low-to-high.
    - SCLx goes low before SDAx is asserted low. This may indicate that another master is attempting to transmit a data '1'.


Immediately following the SSPxIF bit getting set, the user may write the SSPxBUF with the 7-bit address in 7-bit mode, or the default first address in 10-bit mode. After the first eight bits are transmitted and an ACK is received, the user may then transmit an additional 8 bits of address (10-bit mode) or 8 bits of data (7-bit mode).

#### 18.5.9.1 WCOL Status Flag

If the user writes the SSPxBUF when a Repeated Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write does not occur).

Note: Because queueing of events is not allowed, writing of the lower five bits of SSPxCON2 is disabled until the Repeated Start condition is complete.

#### FIGURE 18-22: REPEATED START CONDITION WAVEFORM



#### 18.5.10 I<sup>2</sup>C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address, is accomplished by simply writing a value to the SSPxBUF register. This action will set the Buffer Full flag bit, BF, and allow the BRG to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDAx pin after the falling edge of SCLx is asserted (see data hold time specification parameter 106). SCLx is held low for one BRG rollover count (TBRG). Data should be valid before SCLx is released high (see data setup time specification parameter 107). When the SCLx pin is released high, it is held that way for TBRG.

The data on the SDAx pin must remain stable for that duration and some hold time after the next falling edge of SCLx. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDAx. This allows the slave device being addressed to respond with an ACK bit during the ninth bit time if an address match occurred, or if data was received properly. The status of ACK is written into the ACKDT bit on the falling edge of the ninth clock.

If the master receives an Acknowledge, the Acknowledge Status bit, ACKSTAT, is cleared; if not, the bit is set. After the ninth clock, the SSPxIF bit is set and the master clock (BRG) is suspended until the next data byte is loaded into the SSPxBUF, leaving SCLx low and SDAx unchanged (Figure 18-23).

After the write to the SSPxBUF, each bit of the address will be shifted out on the falling edge of SCLx until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will deassert the SDAx pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDAx pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT status bit (SSPxCON2<6>). Following the falling edge of the ninth clock transmission of the address, the SSPxIF flag is set, the BF flag is cleared and the BRG is turned off until another write to the SSPxBUF takes place, holding SCLx low and allowing SDAx to float.

#### 18.5.10.1 BF Status Flag

In Transmit mode, the BF bit (SSPxSTAT<0>) is set when the CPU writes to SSPxBUF and is cleared when all eight bits are shifted out.

#### 18.5.10.2 WCOL Status Flag

If the user writes the SSPxBUF when a transmit is already in progress (i.e., SSPxSR is still shifting out a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur) after 2 TcY after the SSPxBUF write. If SSPxBUF is rewritten within 2 TcY, the WCOL bit is set and SSPxBUF is updated. This may result in a corrupted transfer. The user should verify that the WCOL bit is clear after each write to SSPxBUF to ensure the transfer is correct. In all cases, WCOL must be cleared in software.

#### 18.5.10.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit (SSPxCON2<6>) is cleared when the slave has sent an Acknowledge  $(\overline{ACK} = 0)$  and is set when the slave does not Acknowledge  $(\overline{ACK} = 1)$ . A slave sends an Acknowledge when it has recognized its address (including a general call), or when the slave has properly received its data.

#### 18.5.11 I<sup>2</sup>C MASTER MODE RECEPTION

Master mode reception is enabled by programming the Receive Enable bit, RCEN (SSPxCON2<3>).

Note: The MSSP module must be in an inactive state before the RCEN bit is set or the RCEN bit will be disregarded.

The BRG begins counting and on each rollover, the state of the SCLx pin changes (high-to-low/low-to-high) and data is shifted into the SSPxSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPxSR are loaded into the SSPxBUF, the BF flag bit is set, the SSPxIF flag bit is set and the BRG is suspended from counting, holding SCLx low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Acknowledge Sequence Enable bit, ACKEN (SSPxCON2<4>).

#### 18.5.11.1 BF Status Flag


In receive operation, the BF bit is set when an address or data byte is loaded into SSPxBUF from SSPxSR. It is cleared when the SSPxBUF register is read.


#### 18.5.11.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when 8 bits are received into the SSPxSR and the BF flag bit is already set from a previous reception.

#### 18.5.11.3 WCOL Status Flag

If users write the SSPxBUF when a receive is already in progress (i.e., SSPxSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).





#### 18.5.12 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge Sequence Enable bit. ACKEN (SSPxCON2<4>). When this bit is set, the SCLx pin is pulled low and the contents of the Acknowledge data bit are presented on the SDAx pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The BRG then counts for one rollover period (TBRG) and the SCLx pin is deasserted (pulled high). When the SCLx pin is sampled high (clock arbitration), the BRG counts for TBRG; the SCLx pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the BRG is turned off and the MSSP module then goes into an inactive state (Figure 18-25).

#### 18.5.12.1 WCOL Status Flag

If the user writes the SSPxBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write does not occur).


#### 18.5.13 STOP CONDITION TIMING

A Stop bit is asserted on the SDAx pin at the end of a receive/transmit by setting the Stop Sequence Enable bit, PEN (SSPxCON2<2>). At the end of a receive/transmit, the SCLx line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDAx line low. When the SDAx line is sampled low, the BRG is reloaded and counts down to 0. When the BRG times out, the SCLx pin will be brought high and one Baud Rate Generator rollover count (TBRG) later, the SDAx pin will be deasserted. When the SDAx pin is sampled high while SCLx is high, the Stop bit (SSPxSTAT<4>) is set. A TBRG later, the PEN bit is cleared and the SSPxIF bit is set (Figure 18-26).


#### 18.5.13.1 WCOL Status Flag

If the user writes the SSPxBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

#### FIGURE 18-25: ACKNOWLEDGE SEQUENCE WAVEFORM



#### FIGURE 18-26: STOP CONDITION RECEIVE OR TRANSMIT MODE



#### 18.5.14 SLEEP OPERATION

While in Sleep mode, the  $I^2C$  module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

#### 18.5.15 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

#### 18.5.16 MULTI-MASTER MODE

In Multi-Master mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Start and Stop bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit (SSPxSTAT<4>) is set, or the bus is Idle, with both the Start and Stop bits clear. When the bus is busy, enabling the MSSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-master operation, the SDAx line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed in hardware with the result placed in the BCLxIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- · Data Transfer
- A Start Condition
- A Repeated Start Condition
- An Acknowledge Condition

#### 18.5.17 MULTI -MASTER COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDAx pin, arbitration takes place when the master outputs a '1' on SDAx, by letting SDAx float high and another master asserts a '0'. When the SCLx pin floats high, data should be stable. If the expected data on SDAx is a '1' and the data sampled on the SDAx pin = 0, then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag, BCLxIF, and reset the I<sup>2</sup>C port to its Idle state (Figure 18-27).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDAx and SCLx lines are deasserted and the SSPxBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the  $I^2C$  bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDAx and SCLx lines are deasserted and the respective control bits in the SSPxCON2 register are cleared. When the user services the bus collision Interrupt Service Routine (ISR), and if the  $I^2C$  bus is free, the user can resume communication by asserting a Start condition.

The master will continue to monitor the SDAx and SCLx pins. If a Stop condition occurs, the SSPxIF bit will be set.

A write to the SSPxBUF will start the transmission of data at the first data bit regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the I<sup>2</sup>C bus can be taken when the Stop bit is set in the SSPxSTAT register, or the bus is Idle and the Start and Stop bits are cleared.

#### FIGURE 18-27: BUS COLLISION TIMING FOR TRANSMIT AND ACKNOWLEDGE



#### 18.5.17.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- a) SDAx or SCLx is sampled low at the beginning of the Start condition (Figure 18-28).
- b) SCLx is sampled low before SDAx is asserted low (Figure 18-29).

During a Start condition, both the SDAx and the SCLx pins are monitored.


If the SDAx pin is already low, or the SCLx pin is already low, then all of the following occur:

- · The Start condition is aborted
- · The BCLxIF flag is set
- The MSSP module is reset to its inactive state (Figure 18-28)

The Start condition begins with the SDAx and SCLx pins deasserted. When the SDAx pin is sampled high, the BRG is loaded from SSPxADD<6:0> and counts down to 0. If the SCLx pin is sampled low while SDAx is high, a bus collision occurs because it is assumed that another master is attempting to drive a data '1' during the Start condition.


If the SDAx pin is sampled low during this count, the BRG is reset and the SDAx line is asserted early (Figure 18-30). If, however, a '1' is sampled on the SDAx pin, the SDAx pin is asserted low at the end of the BRG count. The BRG is then reloaded and counts down to 0. If the SCLx pin is sampled as '0' during this time, a bus collision does not occur. At the end of the BRG count, the SCLx pin is asserted low.


Note: The reason that bus collision is not a factor during a Start condition is that no two bus masters can assert a Start condition at the exact same time. Therefore, one master will always assert SDAx before the other. This condition does not cause a bus collision because the two masters must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.




#### FIGURE 18-28: BUS COLLISION DURING START CONDITION (SDAx ONLY)









### 18.5.17.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:


- a) A low level is sampled on SDAx when SCLx goes from a low level to a high level.
- b) SCLx goes low before SDAx is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user deasserts SDAx and the pin is allowed to float high, the BRG is loaded with SSPxADD<6:0> and counts down to 0. The SCLx pin is then deasserted and when sampled high, the SDAx pin is sampled.

If SDAx is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', see Figure 18-31). If SDAx is sampled high, the BRG is reloaded and begins counting. If SDAx goes from high-to-low before the BRG times out, no bus collision occurs because no two masters can assert SDAx at exactly the same time.


If SCLx goes from high-to-low before the BRG times out and SDAx has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated Start condition (see Figure 18-32).

If, at the end of the BRG time-out, both SCLx and SDAx are still high, the SDAx pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCLx pin, the SCLx pin is driven low and the Repeated Start condition is complete.



#### FIGURE 18-31: BUS COLLISION DURING A REPEATED START CONDITION (CASE 1)

#### FIGURE 18-32: BUS COLLISION DURING REPEATED START CONDITION (CASE 2)




#### 18.5.17.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:


- a) After the SDAx pin has been deasserted and allowed to float high, SDAx is sampled low after the BRG has timed out.
- b) After the SCLx pin is deasserted, SCLx is sampled low before SDAx goes high.

The Stop condition begins with SDAx asserted low. When SDAx is sampled low, the SCLx pin is allowed to float. When the pin is sampled high (clock arbitration), the BRG is loaded with SSPxADD<6:0> and counts down to 0. After the BRG times out, SDAx is sampled. If SDAx is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 18-33). If the SCLx pin is sampled low before SDAx is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 18-34).

#### FIGURE 18-33: BUS COLLISION DURING A STOP CONDITION (CASE 1)



#### FIGURE 18-34: BUS COLLISION DURING A STOP CONDITION (CASE 2)



Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
PIR1	PMPIF <sup>(3)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65
PIE1	PMPIE <sup>(3)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65
IPR1	PMPIP <sup>(3)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	65
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	65
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	65
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65
TRISC	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0	66
TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	66
SSP1BUF	MSSP1 Red	ceive Buffer/T	ransmit Reg	ister					65
SSPxADD	MSSP1 Add	lress Register	<sup>-</sup> (I <sup>2</sup> C™ Slave	e mode), MSS	SP1 Baud Ra	ite Reload Re	egister (I <sup>2</sup> C M	laster mode)	64, 67
SSPxMSK <sup>(1)</sup>	MSK7	MSK6	MSK5	MSK4	MSK3	MSK2	MSK1	MSK0	64, 67
SSPxCON1	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	64, 67
SSPxCON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	64, 67
	GCEN	ACKSTAT	ADMSK5(2)	ADMSK4(2)	ADMSK3(2)	ADMSK2(2)	ADMSK1(2)	SEN	
SSPxSTAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	64, 67
SSP2BUF	MSSP2 Red	ceive Buffer/T	ransmit Reg	ister	1		1		67
SSP2ADD	MSSP2 Add	lress Registe	r (I <sup>2</sup> C Slave	mode), MSS	P2 Baud Rat	e Reload Re	gister (I <sup>2</sup> C M	aster mode)	67

#### TABLE 18-4: REGISTERS ASSOCIATED WITH I<sup>2</sup>C<sup>™</sup> OPERATION

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the MSSPx module in  $I^2C^{TM}$  mode.

**Note 1:** SSPxMSK shares the same address in SFR space as SSPxADD, but is only accessible in certain I<sup>2</sup>C Slave mode operations in 7-Bit Masking mode. See **Section 18.5.3.4 "7-Bit Address Masking Mode**" for more details.

2: Alternate bit definitions for use in I<sup>2</sup>C Slave mode operations only.

3: These bits are only available on 44-pin devices.

#### 19.0 ENHANCED UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (EUSART)

The Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) module is one of two serial I/O modules. (Generically, the EUSART is also known as a Serial Communications Interface or SCI.) The EUSART can be configured as a full-duplex asynchronous system that can communicate with peripheral devices, such as CRT terminals and personal computers. It can also be configured as a half-duplex synchronous system that can communicate with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs and so on.

The Enhanced USART module implements additional features, including automatic baud rate detection and calibration, automatic wake-up on Sync Break reception and 12-bit Break character transmit. These make it ideally suited for use in Local Interconnect Network bus (LIN bus) systems.

All members of the PIC18F46J50 Family are equipped with two independent EUSART modules, referred to as EUSART1 and EUSART2. They can be configured in the following modes:

- Asynchronous (full-duplex) with:
  - Auto-wake-up on character reception
  - Auto-baud calibration
  - 12-bit Break character transmission
- Synchronous Master (half-duplex) with selectable clock polarity
- Synchronous Slave (half-duplex) with selectable clock polarity

The pins of EUSART1 and EUSART2 are multiplexed with the functions of PORTC (RC6/TX1/CK1/RP17 and RC7/RX1/DT1/SD01/RP18) and remapped (RPn1/TX2/CK2 and RPn2/RX2/DT2), respectively. In order to configure these pins as an EUSART:

- For EUSART1:
  - SPEN bit (RCSTA1<7>) must be set (= 1)
  - TRISC<7> bit must be set (= 1)
  - TRISC<6> bit must be cleared (= 0) for Asynchronous and Synchronous Master modes
  - TRISC<6> bit must be set (= 1) for Synchronous Slave mode
- For EUSART2:
  - SPEN bit (RCSTA2<7>) must be set (= 1)
  - TRIS bit for RPn2/RX2/DT2 = 1
  - TRIS bit for RPn1/TX2/CK2 = 0 for Asynchronous and Synchronous Master modes
  - TRISC<6> bit must be set (= 1) for Synchronous Slave mode

Note: The EUSART control will automatically reconfigure the pin from input to output as needed.

The TXx/CKx I/O pins have an optional open-drain output capability. By default, when this pin is used by the EUSART as an output, it will function as a standard push-pull CMOS output. The TXx/CKx I/O pins' open-drain, output feature can be enabled by setting the corresponding UxOD bit in the ODCON2 register. For more details, see **Section 18.3.3 "Open-Drain Output Option"**.

The operation of each Enhanced USART module is controlled through three registers:

- Transmit Status and Control (TXSTAx)
- Receive Status and Control (RCSTAx)
- Baud Rate Control (BAUDCONx)

These are covered in detail in Register 19-1, Register 19-2 and Register 19-3, respectively.

Note: Throughout this section, references to register and bit names that may be associated with a specific EUSART module are referred to generically by the use of 'x' in place of the specific module number. Thus, "RCSTAx" might refer to the Receive Status register for either EUSART1 or EUSART2.

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-1	R/W-0
CSRC	TX9	TXEN <sup>(1)</sup>	SYNC	SENDB	BRGH	TRMT	TX9D
oit 7			•			•	bit
lagandi							
L <b>egend:</b> R = Reada	ble bit	W = Writable	bit	U = Unimplerr	nented bit, read	l as '0'	
-n = Value	at POR	'1' = Bit is set		'0' = Bit is clea		x = Bit is unkr	nown
bit 7		Source Select	bit				
	Asynchronous Don't care.	<u>s mode:</u>					
	Synchronous						
		ode (clock gen de (clock from					
bit 6		ansmit Enable I		,			
		-bit transmissic					
		-bit transmissio					
bit 5		mit Enable bit <sup>(1</sup>	)				
	1 = Transmit 0 = Transmit						
bit 4	SYNC: EUSA	RT Mode Sele	ct bit				
	1 = Synchron 0 = Asynchro						
bit 3	•	d Break Chara	ter hit				
	Asynchronous						
	1 = Send Syn			n (cleared by ha	rdware upon co	ompletion)	
	Synchronous		· · · · · · · · · · · · · · · · · · · ·				
	Don't care.						
bit 2	-	Baud Rate Sel	ect bit				
	Asynchronous						
	0 = Low spee						
	Synchronous Unused in this	mode:					
bit 1		mit Shift Regist	er Status hit				
	1 = TSR emp	-					
	0 = TSR full						
bit 0	TX9D: 9 <sup>th</sup> bit	of Transmit Da	ta				
	Can be addre						

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	R-x
SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
bit 7							bit (
_egend:							
R = Readab		W = Writable b	bit	U = Unimplem			
-n = Value a	t POR	'1' = Bit is set		'0' = Bit is clea	ired	x = Bit is unkr	IOWN
bit 7	SPEN: Seria	al Port Enable bit					
		ort enabled (cont		Tx and TXx/CK	c pins as seria	Il port pins)	
		ort disabled (held	•			,	
bit 6	<b>RX9:</b> 9-Bit F	Receive Enable b	it				
		9-bit reception 8-bit reception					
bit 5	SREN: Sing	le Receive Enab	e bit				
	<u>Asynchrono</u> Don't care.	<u>us mode</u> :					
		s mode – Master	<u>:</u>				
		s single receive					
		s single receive eared after recep	tion is comple	ete.			
		s mode – Slave:	p				
bit 4	CREN: Con	tinuous Receive	Enable bit				
	Asynchrono						
	0 = Disable	s receiver					
	<u>Synchronou</u>						
		s continuous rece s continuous rece		ble bit, CREN, is	cleared (CRE	N overrides SR	EN)
bit 3	ADDEN: Ad	dress Detect Ena	able bit				
	Asynchrono	<u>us mode 9-Bit (</u> R	X9 = <u>1)</u> :				
		s address detecti					
		s address detect us mode 9-Bit (R	•	are received and	i ninth dit can	be used as part	ty bit
	Don't care.		<u> </u>				
bit 2	FERR: Fram	ning Error bit					
	1 = Framing 0 = No fram	g error (can be up ning error	odated by rea	ding RCREGx re	egister and re	ceiving next vali	d byte)
bit 1	OERR: Ove	rrun Error bit					
	1 = Overrur	n error (can be cl	eared by clea	ring bit CREN)			
	0 = No over	rrun error it of Received Da					

R/W-0	R-1	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0
ABDOVF	RCIDL	RXDTP	TXCKP	BRG16	_	WUE	ABDEN
bit 7							bit (
Legend:							
R = Readabl	e bit	W = Writable b	oit	U = Unimplem	ented bit, read	d as '0'	
-n = Value at	POR	'1' = Bit is set		'0' = Bit is clea		x = Bit is unkr	nown
hit 7		uto Doud Acquia	ition Dollovor	Statua bit			
bit 7	1 = A BRG	uto-Baud Acquis rollover has occu G rollover has occ	rred during A		etect mode (r	must be cleared	d in software)
bit 6	RCIDL: Rec	eive Operation Ic	lle Status bit				
	1 = Receive	operation is Idle operation is activ					
bit 5		ta/Receive Polari					
	Asynchronou 1 = Receive		erted (active-				
		<u>s mode:</u> Tx) is inverted (ad Tx) is not inverted					
bit 4	TXCKP: Syr	nchronous Clock	Polarity Selec	t bit			
		<u>us mode:</u> e for transmit (TX e for transmit (TX	,				
	Synchronous	-	is a high level				
bit 3	1 = 16-bit Ba	Bit Baud Rate Re aud Rate Genera ud Rate Generate	tor – SPBRGI	Hx and SPBRGx		RGHx value iq	nored
bit 2		nted: Read as '0				0	
bit 1	WUE: Wake	-up Enable bit					
	hardwai	<u>us mode:</u> T will continue to re on following ris not monitored o	sing edge	·	pt generated	on falling edge	; bit cleared i
	<u>Synchronou</u> Unused in th						
bit 0	ABDEN: Au	to-Baud Detect E	nable bit				
	cleared	us mode: baud rate measu in hardware upo te measurement	n completion		r; requires rec	ception of a Sy	nc field (55h)
	<u>Synchronous</u> Unused in th						

#### 19.1 Baud Rate Generator (BRG)

The BRG is a dedicated, 8-bit or 16-bit generator that supports both the Asynchronous and Synchronous modes of the EUSART. By default, the BRG operates in 8-bit mode; setting the BRG16 bit (BAUDCONx<3>) selects 16-bit mode.

The SPBRGHx:SPBRGx register pair controls the period of a free-running timer. In Asynchronous mode, bits BRGH (TXSTAx<2>) and BRG16 (BAUDCONx<3>) also control the baud rate. In Synchronous mode, BRGH is ignored.

Table 19-1 provides the formula for computation of the baud rate for different EUSART modes, which only apply in Master mode (internally generated clock).

Given the desired baud rate and Fosc, the nearest integer value for the SPBRGHx:SPBRGx registers can be calculated using the formulas in Table 19-1. From this, the error in baud rate can be determined. An example calculation is provided in Example 19-1. Typical baud rates and error values for the various Asynchronous modes are provided in Table 19-2. It may be advantageous to use the high baud rate (BRGH = 1) or the 16-bit BRG to reduce the baud rate error, or achieve a slow baud rate for a fast oscillator frequency.

Writing a new value to the SPBRGHx:SPBRGx registers causes the BRG timer to be reset (or cleared). This ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

#### 19.1.1 OPERATION IN POWER-MANAGED MODES

The device clock is used to generate the desired baud rate. When one of the power-managed modes is entered, the new clock source may be operating at a different frequency. This may require an adjustment to the value in the SPBRGx register pair.

#### 19.1.2 SAMPLING

The data on the RXx pin (either RC7/PMA4/RX1/DT1/SDO1/RP18 or RPn2/RX2/DT2) is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RXx pin.

C	onfiguration B	its		Poud Poto Formula			
SYNC	SYNC BRG16 BRGH		BRG/EUSART Mode	Baud Rate Formula			
0	0	0	8-bit/Asynchronous	Fosc/[64 (n + 1)]			
0	0	1	8-bit/Asynchronous	$\Gamma_{000}/[16(n+1)]$			
0	1	0	16-bit/Asynchronous	Fosc/[16 (n + 1)]			
0	1	1	16-bit/Asynchronous				
1	0	х	8-bit/Synchronous	Fosc/[4 (n + 1)]			
1	1 1 x		16-bit/Synchronous	1			

TABLE 19-1: BAUD RATE FORMULAS

**Legend:** x = Don't care, n = value of SPBRGHx:SPBRGx register pair

#### EXAMPLE 19-1: CALCULATING BAUD RATE ERROR

```
For a device with Fosc of 16 MHz, desired baud rate of 9600, Asynchronous mode, and
8-bit BRG:
Desired Baud Rate = Fosc/(64 ([SPBRGHx:SPBRGx] + 1))
Solving for SPBRGHx:SPBRGx:
X = ((Fosc/Desired Baud Rate)/64) - 1
= ((16000000/9600)/64) - 1
= [25.042] = 25
Calculated Baud Rate=16000000/(64 (25 + 1))
= 9615
Error = (Calculated Baud Rate - Desired Baud Rate)/Desired Baud Rate
= (9615 - 9600)/9600 = 0.16%
```

#### TABLE 19-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:	
TXSTAx	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65	
RCSTAx	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65	
BAUDCONx	ABDOVF	ABDOVF RCIDL RXDTP TXCKP BRG16 — WUE ABDEN								
SPBRGHx	EUSARTx		66							
SPBRGx	SPBRGx EUSARTx Baud Rate Generator Register Low Byte									

Legend: — = unimplemented, read as '0'. Shaded cells are not used by the BRG.

					SYNC	= 0, BRGH	I = 0, BRG	6 <b>16 =</b> 0				
BAUD	Fosc	= 40.000	) MHz	Fosc	= 20.000	) MHz	Foso	; = 10.000	) MHz	Fos	c = 8.000	MHz
RATE (K)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)
0.3	_									_		_
1.2	—	—	—	1.221	1.73	255	1.202	0.16	129	1.201	-0.16	103
2.4	2.441	1.73	255	2.404	0.16	129	2.404	0.16	64	2.403	-0.16	51
9.6	9.615	0.16	64	9.766	1.73	31	9.766	1.73	15	9.615	-0.16	12
19.2	19.531	1.73	31	19.531	1.73	15	19.531	1.73	7	—	_	_
57.6	56.818	-1.36	10	62.500	8.51	4	52.083	-9.58	2	_	_	_
115.2	125.000	8.51	4	104.167	-9.58	2	78.125	-32.18	1	_	_	_

#### TABLE 19-3: BAUD RATES FOR ASYNCHRONOUS MODES

			S	YNC = 0, E	BRGH = (	), <b>BRG16 =</b>	0		
BAUD RATE	Fos	c = 4.000	MHz	Fos	c = 2.000	MHz	Fos	c = 1.000	MHz
(K)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)
0.3	0.300	0.16	207	0.300	-0.16	103	0.300	-0.16	51
1.2	1.202	0.16	51	1.201	-0.16	25	1.201	-0.16	12
2.4	2.404	0.16	25	2.403	-0.16	12	—	_	_
9.6	8.929	-6.99	6	—	_	_	—	_	_
19.2	20.833	8.51	2	—	_	_	—	_	_
57.6	62.500	8.51	0	—	_	_	—	_	_
115.2	62.500	-45.75	0	_	—	_	_		

					SYNC	= 0, BRGH	I = 1, BRG	<b>16 =</b> 0				
BAUD RATE	Fosc	= 40.000	) MHz	Fosc = 20.000 MHz			Fosc	= 10.000	) MHz	Fosc = 8.000 MHz		
(K)	Actual Rate (K)	% Error	SPBRG value (decimal)	value Rate % va		SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)
0.3	—	_	_	_	_	_	_	_	_	_	_	_
1.2	—	—	—	—	—	—	—	—	—	—	—	—
2.4	—	_	_	—	_	_	2.441	1.73	255	2.403	-0.16	207
9.6	9.766	1.73	255	9.615	0.16	129	9.615	0.16	64	9615.	-0.16	51
19.2	19.231	0.16	129	19.231	0.16	64	19.531	1.73	31	19.230	-0.16	25
57.6	58.140	0.94	42	56.818	-1.36	21	56.818	-1.36	10	55.555	3.55	8
115.2	113.636	-1.36	21	113.636	-1.36	10	125.000	8.51	4	—	_	_

		SYNC = 0, BRGH = 1, BRG16 = 0												
BAUD RATE	Foso	c = 4.000	MHz	Fos	c = 2.000	MHz	Fos	c = 1.000	MHz					
(K)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)					
0.3			_			_	0.300	-0.16	207					
1.2	1.202	0.16	207	1.201	-0.16	103	1.201	-0.16	51					
2.4	2.404	0.16	103	2.403	-0.16	51	2.403	-0.16	25					
9.6	9.615	0.16	25	9.615	-0.16	12	_	_	_					
19.2	19.231	0.16	12	—	_	_	_	_	_					
57.6	62.500	8.51	3	—	_	_	_	_	_					
115.2	125.000	8.51	1	_	_	—	_	_	—					

© 2009 Microchip Technology Inc.

					SYNC	= 0, BRGH	I = 0, BRG	16 = 1				
BAUD RATE	Fosc	= 40.000	) MHz	Fosc = 20.000 MHz			Fosc = 10.000 MHz			Fosc = 8.000 MHz		
(K)	Actual Rate (K)	% Error	SPBRG value (decimal)	Rate % val		SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)
0.3	0.300	0.00	8332	0.300	0.02	4165	0.300	0.02	2082	0.300	-0.04	1665
1.2	1.200	0.02	2082	1.200	-0.03	1041	1.200	-0.03	520	1.201	-0.16	415
2.4	2.402	0.06	1040	2.399	-0.03	520	2.404	0.16	259	2.403	-0.16	207
9.6	9.615	0.16	259	9.615	0.16	129	9.615	0.16	64	9.615	-0.16	51
19.2	19.231	0.16	129	19.231	0.16	64	19.531	1.73	31	19.230	-0.16	25
57.6	58.140	0.94	42	56.818	-1.36	21	56.818	-1.36	10	55.555	3.55	8
115.2	113.636	-1.36	21	113.636	-1.36	10	125.000	8.51	4	_	_	—

#### TABLE 19-3: BAUD RATES FOR ASYNCHRONOUS MODES (CONTINUED)

BAUD RATE (K)	SYNC = 0, BRGH = 0, BRG16 = 1										
	Fose	c = 4.000	MHz	Fos	c = 2.000	MHz	Fosc = 1.000 MHz				
	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)		
0.3	0.300	0.04	832	0.300	-0.16	415	0.300	-0.16	207		
1.2	1.202	0.16	207	1.201	-0.16	103	1.201	-0.16	51		
2.4	2.404	0.16	103	2.403	-0.16	51	2.403	-0.16	25		
9.6	9.615	0.16	25	9.615	-0.16	12	—	_	_		
19.2	19.231	0.16	12	—	_	_	—	_	_		
57.6	62.500	8.51	3	—	_	_	—	_	_		
115.2	125.000	8.51	1		—	_	_	—	—		

BAUD RATE (K)	SYNC = 0, BRGH = 1, BRG16 = 1 or SYNC = 1, BRG16 = 1												
	Fosc = 40.000 MHz			Fosc = 20.000 MHz			Fosc = 10.000 MHz			Fosc = 8.000 MHz			
	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	
0.3	0.300	0.00	33332	0.300	0.00	16665	0.300	0.00	8332	0.300	-0.01	6665	
1.2	1.200	0.00	8332	1.200	0.02	4165	1.200	0.02	2082	1.200	-0.04	1665	
2.4	2.400	0.02	4165	2.400	0.02	2082	2.402	0.06	1040	2.400	-0.04	832	
9.6	9.606	0.06	1040	9.596	-0.03	520	9.615	0.16	259	9.615	-0.16	207	
19.2	19.193	-0.03	520	19.231	0.16	259	19.231	0.16	129	19.230	-0.16	103	
57.6	57.803	0.35	172	57.471	-0.22	86	58.140	0.94	42	57.142	0.79	34	
115.2	114.943	-0.22	86	116.279	0.94	42	113.636	-1.36	21	117.647	-2.12	16	

BAUD RATE (K)	SYNC = 0, BRGH = 1, BRG16 = 1 or SYNC = 1, BRG16 = 1											
	Foso	c = 4.000	MHz	Fos	c = 2.000	MHz	Fosc = 1.000 MHz					
	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)	Actual Rate (K)	% Error	SPBRG value (decimal)			
0.3	0.300	0.01	3332	0.300	-0.04	1665	0.300	-0.04	832			
1.2	1.200	0.04	832	1.201	-0.16	415	1.201	-0.16	207			
2.4	2.404	0.16	415	2.403	-0.16	207	2.403	-0.16	103			
9.6	9.615	0.16	103	9.615	-0.16	51	9.615	-0.16	25			
19.2	19.231	0.16	51	19.230	-0.16	25	19.230	-0.16	12			
57.6	58.824	2.12	16	55.555	3.55	8	—	_	—			
115.2	111.111	-3.55	8	—	_	—	—	_	_			

# 19.1.3 AUTO-BAUD RATE DETECT

The Enhanced USART module supports the automatic detection and calibration of baud rate. This feature is active only in Asynchronous mode and while the WUE bit is clear.

The automatic baud rate measurement sequence (Figure 19-1) begins whenever a Start bit is received and the ABDEN bit is set. The calculation is self-averaging.

In the Auto-Baud Rate Detect (ABD) mode, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RXx signal, the RXx signal is timing the BRG. In ABD mode, the internal BRG is used as a counter to time the bit period of the incoming serial byte stream.

Once the ABDEN bit is set, the state machine will clear the BRG and look for a Start bit. The ABD must receive a byte with the value, 55h (ASCII "U", which is also the LIN bus Sync character), in order to calculate the proper bit rate. The measurement is taken over both a low and high bit time in order to minimize any effects caused by asymmetry of the incoming signal. After a Start bit, the SPBRGx begins counting up, using the preselected clock source on the first rising edge of RXx. After eight bits on the RXx pin or the fifth rising edge, an accumulated value totalling the proper BRG period is left in the SPBRGHX:SPBRGx register pair. Once the 5<sup>th</sup> edge is seen (this should correspond to the Stop bit), the ABDEN bit is automatically cleared.

If a rollover of the BRG occurs (an overflow from FFFFh to 0000h), the event is trapped by the ABDOVF status bit (BAUDCONx<7>). It is set in hardware by BRG rollovers and can be set or cleared by the user in software. ABD mode remains active after rollover events and the ABDEN bit remains set (Figure 19-2).

While calibrating the baud rate period, the BRG registers are clocked at 1/8<sup>th</sup> the preconfigured clock rate. Note that the BRG clock will be configured by the BRG16 and BRGH bits. Independent of the BRG16 bit setting, both the SPBRGx and SPBRGHx will be used as a 16-bit counter. This allows the user to verify that no carry occurred for 8-bit modes by checking for 00h in the SPBRGHx register.

Refer to Table 19-4 for counter clock rates to the BRG.

While the ABD sequence takes place, the EUSART state machine is held in Idle. The RCxIF interrupt is set once the fifth rising edge on RXx is detected. The value in the RCREGx needs to be read to clear the RCxIF interrupt. The contents of RCREGx should be discarded.

- Note 1: If the WUE bit is set with the ABDEN bit, Auto-Baud Rate Detection will occur on the byte *following* the Break character.
  - 2: It is up to the user to determine that the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and EUSART baud rates are not possible due to bit error rates. Overall system timing and communication baud rates must be taken into consideration when using the Auto-Baud Rate Detection feature.

## TABLE 19-4: BRG COUNTER CLOCK RATES


BRG16	BRGH	BRG Counter Clock
0	0	Fosc/512
0	1	Fosc/128
1	0	Fosc/128
1	1	Fosc/32
Mater	Duration	

**Note:** During the ABD sequence, SPBRGx and SPBRGHx are both used as a 16-bit counter, independent of BRG16 setting.


# 19.1.3.1 ABD and EUSART Transmission

Since the BRG clock is reversed during ABD acquisition, the EUSART transmitter cannot be used during ABD. This means that whenever the ABDEN bit is set, TXREGx cannot be written to. Users should also ensure that ABDEN does not become set during a transmit sequence. Failing to do this may result in unpredictable EUSART operation.

# PIC18F46J50 FAMILY



# FIGURE 19-2: BRG OVERFLOW SEQUENCE



# 19.2 EUSART Asynchronous Mode

The Asynchronous mode of operation is selected by clearing the SYNC bit (TXSTAx<4>). In this mode, the EUSART uses standard Non-Return-to-Zero (NRZ) format (one Start bit, eight or nine data bits and one Stop bit). The most common data format is 8 bits. An on-chip dedicated 8-bit/16-bit BRG can be used to derive standard baud rate frequencies from the oscillator.

The EUSART transmits and receives the LSb first. The EUSART's transmitter and receiver are functionally independent but use the same data format and baud rate. The BRG produces a clock, either x16 or x64 of the bit shift rate, depending on the BRGH and BRG16 bits (TXSTAx<2> and BAUDCONx<3>). Parity is not supported by the hardware but can be implemented in software and stored as the ninth data bit.

When operating in Asynchronous mode, the EUSART module consists of the following important elements:

- Baud Rate Generator
- Sampling Circuit
- Asynchronous Transmitter
- · Asynchronous Receiver
- Auto-Wake-up on Sync Break Character
- 12-Bit Break Character Transmit
- Auto-Baud Rate Detection

### 19.2.1 EUSART ASYNCHRONOUS TRANSMITTER

Figure 19-3 displays the EUSART transmitter block diagram.

The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The Shift register obtains its data from the Read/Write Transmit Buffer register, TXREGx. The TXREGx register is loaded with data in software. The TSR register is not loaded until the Stop bit has been transmitted from the previous load. As soon as the Stop bit is transmitted, the TSR is loaded with new data from the TXREGx register (if available). Once the TXREGx register transfers the data to the TSR register (occurs in one TcY), the TXREGx register is empty and the TXxIF flag bit is set. This interrupt can be enabled or disabled by setting or clearing the interrupt enable bit, TXxIE. TXxIF will be set regardless of the state of TXxIE; it cannot be cleared in software. TXxIF is also not cleared immediately upon loading TXREGx, but becomes valid in the second instruction cycle following the load instruction. Polling TXxIF immediately following a load of TXREGx will return invalid results.

While TXxIF indicates the status of the TXREGx register; another bit, TRMT (TXSTAx<1>), shows the status of the TSR register. TRMT is a read-only bit, which is set when the TSR register is empty. No interrupt logic is tied to this bit so the user has to poll this bit in order to determine if the TSR register is empty.


Note 1: The TSR register is not mapped in data memory, so it is not available to the user.2: Flag bit, TXxIF, is set when enable bit,

To set up an Asynchronous Transmission:


TXEN, is set.

- 1. Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2. Enable the asynchronous serial port by clearing bit, SYNC, and setting bit, SPEN.
- 3. If interrupts are desired, set enable bit, TXxIE.
- 4. If 9-bit transmission is desired, set transmit bit, TX9. Can be used as address/data bit.
- 5. Enable the transmission by setting bit, TXEN, which will also set bit, TXxIF.
- 6. If 9-bit transmission is selected, the ninth bit should be loaded in bit, TX9D.
- 7. Load data to the TXREGx register (starts transmission).
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.


# FIGURE 19-3: EUSART TRANSMIT BLOCK DIAGRAM



# PIC18F46J50 FAMILY



# FIGURE 19-5: ASYNCHRONOUS TRANSMISSION (BACK-TO-BACK)



# TABLE 19-5: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:		
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63		
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65		
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65		
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65		
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65		
PIE3	SSP2IE BCL2IE RC2IE TX2IE TMR4IE CTMUIE TMR3GIE RTCCIE							65			
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65		
RCSTAx	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65		
TXREGx	EUSARTx	Transmit Re	gister						65		
TXSTAx	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65		
BAUDCONx	ABDOVF	RCIDL	RXDTP	TXDTP	BRG16	—	WUE	ABDEN	66		
SPBRGHx	EUSARTx	EUSARTx Baud Rate Generator Register High Byte									
SPBRGx	EUSARTx Baud Rate Generator Register Low Byte										
ODCON2							U2OD	U10D	68		

Legend: -= unimplemented locations read as '0'. Shaded cells are not used for asynchronous transmission.

**Note 1:** These bits are only available on 44-pin devices.

#### **EUSART ASYNCHRONOUS** 19.2.2 RECEIVER

The receiver block diagram is displayed in Figure 19-6. The data is received on the RXx pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc. This mode would typically be used in RS-232 systems.

To set up an Asynchronous Reception:


- Initialize the SPBRGHx:SPBRGx registers for 1. the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2 Enable the asynchronous serial port by clearing bit, SYNC, and setting bit, SPEN.
- 3. If interrupts are desired, set enable bit, RCxIE.
- If 9-bit reception is desired, set bit, RX9. 4
- 5. Enable the reception by setting bit, CREN.
- Flag bit, RCxIF, will be set when reception is 6. complete and an interrupt will be generated if enable bit, RCxIE, was set.
- 7. Read the RCSTAx register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 8. Read the 8-bit received data by reading the RCREGx register.
- 9. If any error occurred, clear the error by clearing enable bit, CREN.
- 10. If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.


### **FIGURE 19-6:**

#### SETTING UP 9-BIT MODE WITH 19.2.3 ADDRESS DETECT

This mode would typically be used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRGHx:SPBRGx registers for 1. the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2. Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If interrupts are required, set the RCEN bit and 3. select the desired priority level with the RCxIP bit.
- 4. Set the RX9 bit to enable 9-bit reception.
- 5. Set the ADDEN bit to enable address detect.
- 6. Enable reception by setting the CREN bit.
- 7 The RCxIF bit will be set when reception is complete. The interrupt will be Acknowledged if the RCxIE and GIE bits are set.
- 8. Read the RCSTAx register to determine if any error occurred during reception, as well as read bit 9 of data (if applicable).
- 9. Read RCREGx to determine if the device is being addressed.
- 10. If any error occurred, clear the CREN bit.
- 11. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and interrupt the CPU.





### FIGURE 19-7: ASYNCHRONOUS RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:	
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63	
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65	
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65	
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65	
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65	
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65	
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65	
RCSTAx	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65	
RCREGx	EUSARTx	Receive Reg	ister						65	
TXSTAx	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65	
BAUDCONx	ABDOVF	ABDOVF RCIDL RXDTP TXCKP BRG16 — WUE ABDEN								
SPBRGHx	EUSARTx Baud Rate Generator Register High Byte									
SPBRGx	EUSARTx	Baud Rate G	enerator R	egister Low	Byte				65	

### TABLE 19-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

**Legend:** — = unimplemented locations read as '0'. Shaded cells are not used for asynchronous reception.

**Note 1:** These bits are only available on 44-pin devices.

### 19.2.4 AUTO-WAKE-UP ON SYNC BREAK CHARACTER

During Sleep mode, all clocks to the EUSART are suspended. Because of this, the BRG is inactive and a proper byte reception cannot be performed. The auto-wake-up feature allows the controller to wake-up due to activity on the RXx/DTx line while the EUSART is operating in Asynchronous mode.

The auto-wake-up feature is enabled by setting the WUE bit (BAUDCONx<1>). Once set, the typical receive sequence on RXx/DTx is disabled and the

EUSART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a high-to-low transition on the RXx/DTx line. (This coincides with the start of a Sync Break or a Wake-up Signal character for the LIN protocol.)

Following a wake-up event, the module generates an RCxIF interrupt. The interrupt is generated synchronously to the Q clocks in normal operating modes (Figure 19-8) and asynchronously if the device is in Sleep mode (Figure 19-9). The interrupt condition is cleared by reading the RCREGx register. The WUE bit is automatically cleared once a low-to-high transition is observed on the RXx line following the wake-up event. At this point, the EUSART module is in Idle mode and returns to normal operation. This signals to the user that the Sync Break event is over.

## 19.2.4.1 Special Considerations Using Auto-Wake-up

Since auto-wake-up functions by sensing rising edge transitions on RXx/DTx, information with any state changes before the Stop bit may signal a false End-Of-Character (EOC) and cause data or framing errors. To work properly, therefore, the initial character in the transmission must be all '0's. This can be 00h (8 bytes) for standard RS-232 devices or 000h (12 bits) for LIN bus.

Oscillator start-up time must also be considered, especially in applications using oscillators with longer start-up intervals (i.e., HS or HSPLL mode). The Sync Break (or Wake-up Signal) character must be of sufficient length and be followed by a sufficient interval to allow enough time for the selected oscillator to start and provide proper initialization of the EUSART.


# 19.2.4.2 Special Considerations Using the WUE Bit

The timing of WUE and RCxIF events may cause some confusion when it comes to determining the validity of received data. As noted, setting the WUE bit places the EUSART in an Idle mode. The wake-up event causes a receive interrupt by setting the RCxIF bit. The WUE bit is cleared after this when a rising edge is seen on RXx/DTx. The interrupt condition is then cleared by reading the RCREGx register. Ordinarily, the data in RCREGx will be dummy data and should be discarded.


The fact that the WUE bit has been cleared (or is still set) and the RCxIF flag is set should not be used as an indicator of the integrity of the data in RCREGx. Users should consider implementing a parallel method in firmware to verify received data integrity.

To assure that no actual data is lost, check the RCIDL bit to verify that a receive operation is not in process. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.





# FIGURE 19-9: AUTO-WAKE-UP BIT (WUE) TIMINGS DURING SLEEP



# 19.2.5 BREAK CHARACTER SEQUENCE

The EUSART module has the capability of sending the special Break character sequences that are required by the LIN bus standard. The Break character transmit consists of a Start bit, followed by twelve '0' bits and a Stop bit. The Frame Break character is sent whenever the SENDB and TXEN bits (TXSTAx<3> and TXSTAx<5>) are set while the Transmit Shift Register is loaded with data.

Note that the value of data written to TXREGx will be ignored and all '0's will be transmitted.

The SENDB bit is automatically reset by hardware after the corresponding Stop bit is sent. This allows the user to preload the transmit FIFO with the next transmit byte following the Break character (typically, the Sync character in the LIN specification).

Note that the data value written to the TXREGx for the Break character is ignored. The write simply serves the purpose of initiating the proper sequence.

The TRMT bit indicates when the transmit operation is active or Idle, just as it does during normal transmission. See Figure 19-10 for the timing of the Break character sequence.

# 19.2.5.1 Break and Sync Transmit Sequence

The following sequence will send a message frame header made up of a Break, followed by an Auto-Baud Sync byte. This sequence is typical of a LIN bus master.

- 1. Configure the EUSART for the desired mode.
- 2. Set the TXEN and SENDB bits to set up the Break character.
- 3. Load the TXREGx with a dummy character to initiate transmission (the value is ignored).
- 4. Write '55h' to TXREGx to load the Sync character into the transmit FIFO buffer.
- 5. After the Break has been sent, the SENDB bit is reset by hardware. The Sync character now transmits in the preconfigured mode.

When the TXREGx becomes empty, as indicated by the TXxIF, the next data byte can be written to TXREGx.


# 19.2.6 RECEIVING A BREAK CHARACTER

The Enhanced USART module can receive a Break character in two ways.

The first method forces configuration of the baud rate at a frequency of 9/13 the typical speed. This allows for the Stop bit transition to be at the correct sampling location (13 bits for Break versus Start bit and 8 data bits for typical data).

The second method uses the auto-wake-up feature described in **Section 19.2.4 "Auto-Wake-up on Sync Break Character"**. By enabling this feature, the EUSART will sample the next two transitions on RXx/DTx, cause an RCxIF interrupt and receive the next data byte followed by another interrupt.

Note that following a Break character, the user will typically want to enable the Auto-Baud Rate Detect feature. For both methods, the user can set the ABDEN bit once the TXxIF interrupt is observed.



# FIGURE 19-10: SEND BREAK CHARACTER SEQUENCE

# 19.3 EUSART Synchronous Master Mode

The Synchronous Master mode is entered by setting the CSRC bit (TXSTAx<7>). In this mode, the data is transmitted in a half-duplex manner (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit, SYNC (TXSTAx<4>). In addition, enable bit, SPEN (RCSTAx<7>), is set in order to configure the TXx and RXx pins to CKx (clock) and DTx (data) lines, respectively.

The Master mode indicates that the processor transmits the master clock on the CKx line. Clock polarity is selected with the TXCKP bit (BAUDCONx<4>). Setting TXCKP sets the Idle state on CKx as high, while clearing the bit sets the Idle state as low. This option is provided to support Microwire devices with this module.

### 19.3.1 EUSART SYNCHRONOUS MASTER TRANSMISSION


The EUSART transmitter block diagram is shown in Figure 19-3. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The Shift register obtains its data from the Read/Write Transmit Buffer register, TXREGx. The TXREGx register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREGx (if available).

Once the TXREGx register transfers the data to the TSR register (occurs in one TcY), the TXREGx is empty and the TXxIF flag bit is set. The interrupt can be enabled or disabled by setting or clearing the interrupt enable bit, TXxIE. TXxIF is set regardless of the state of enable bit, TXxIE; it cannot be cleared in software. It will reset only when new data is loaded into the TXREGx register.

While flag bit, TXxIF, indicates the status of the TXREGx register, another bit, TRMT (TXSTAx<1>), shows the status of the TSR register. TRMT is a read-only bit which is set when the TSR is empty. No interrupt logic is tied to this bit, so the user must poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory so it is not available to the user.


To set up a Synchronous Master Transmission:

- 1. Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRG16 bit, as required, to achieve the required baud rate.
- 2. Enable the synchronous master serial port by setting bits, SYNC, SPEN and CSRC.
- 3. If interrupts are desired, set enable bit, TXxIE.
- 4. If 9-bit transmission is required, set bit, TX9.
- 5. Enable the transmission by setting bit, TXEN.
- 6. If 9-bit transmission is selected, the ninth bit should be loaded in bit, TX9D.
- 7. Start transmission by loading data to the TXREGx register.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.



# FIGURE 19-11: SYNCHRONOUS TRANSMISSION

# PIC18F46J50 FAMILY



# FIGURE 19-12: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)

# TABLE 19-7: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:	
INTCON	<b>GIE/GIEH</b>	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63	
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65	
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65	
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65	
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65	
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65	
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65	
RCSTAx	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65	
TXREGx	EUSARTx	Transmit Re	gister						65	
TXSTAx	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65	
BAUDCONx	ABDOVF	RCIDL	RXDTP	TXCKP	BRG16	_	WUE	ABDEN	66	
SPBRGHx	EUSARTx Baud Rate Generator Register High Byte									
SPBRGx	EUSARTx Baud Rate Generator Register Low Byte									
ODCON2	_	_		_			U2OD	U10D	68	

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for synchronous master transmission.

Note 1: These pins are only available on 44-pin devices.

### 19.3.2 EUSART SYNCHRONOUS MASTER RECEPTION

Once Synchronous mode is selected, reception is enabled by setting either the Single Receive Enable bit, SREN (RCSTAx<5>) or the Continuous Receive Enable bit, CREN (RCSTAx<4>). Data is sampled on the RXx pin on the falling edge of the clock.

If enable bit, SREN, is set, only a single word is received. If enable bit, CREN, is set, the reception is continuous until CREN is cleared. If both bits are set, then CREN takes precedence.

To set up a Synchronous Master Reception:

- 1. Initialize the SPBRGHx:SPBRGx registers for the appropriate baud rate. Set or clear the BRG16 bit, as required, to achieve the desired baud rate.
- 2. Enable the synchronous master serial port by setting bits, SYNC, SPEN and CSRC.

- 3. Ensure bits, CREN and SREN, are clear.
- 4. If interrupts are desired, set enable bit, RCxIE.
- 5. If 9-bit reception is desired, set bit, RX9.
- 6. If a single reception is required, set bit, SREN. For continuous reception, set bit, CREN.
- 7. Interrupt flag bit, RCxIF, will be set when reception is complete and an interrupt will be generated if the enable bit, RCxIE, was set.
- 8. Read the RCSTAx register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 9. Read the 8-bit received data by reading the RCREGx register.
- 10. If any error occurred, clear the error by clearing bit, CREN.
- 11. If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

<u> </u>	bit 7	~ <u>+</u>	bit 6	$\sim$	bit 5		bit 4	$\overline{}$	' bit 3	$\overline{}$	bit 2	$\sim$	bit 1	$\sim$	' bit 0	$\sim$		RC7/RX1/DT1/ SDO1/RP18 pin
;		$\sim$				_^_					DILZ	<u> </u>				_^_		SDO1/RP18 pin
1 1			<u>-</u>		<u>;</u>		÷∟		 :				<u>-</u>		; ;			RC6/TX1/CK1/RP17 pin (TXCKP = 0)
;					; :		; ;		; ;						; ;			RC6/TX1/CK1/RP17 pin (TXCKP = 1)
1 1 1			1 1 1		1 1 1 1		1 1 1		1 1 1 1			י י י	1 1 1		1 1 1 1		ų.	Write to bit SREN
					, , ,												<u>_</u>	SREN bit
ء ١					, ,		۱ ۱											CREN bit '0'
: :			1 1 1		1 1 1		<u>.</u>		• • •				, , ,		• • •			RC1IF bit (Interrupt)——
					1 1						1						, , ,	Read RCREG1 ——

# FIGURE 19-13: SYNCHRONOUS RECEPTION (MASTER MODE, SREN)

# PIC18F46J50 FAMILY

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:		
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	<b>INTOIE</b>	RBIE	TMR0IF	INT0IF	RBIF	63		
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65		
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65		
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65		
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65		
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65		
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65		
RCSTAx	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65		
RCREGx	EUSARTx I	Receive Reg	gister						65		
TXSTAx	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65		
BAUDCONx	ABDOVF	RCIDL	RXDTP	TXCKP	BRG16	_	WUE	ABDEN	66		
SPBRGHx	EUSARTx I	EUSARTx Baud Rate Generator Register High Byte									
SPBRGx	EUSARTx I	EUSARTx Baud Rate Generator Register Low Byte									
ODCON2	_	_					U2OD	U10D	68		

# TABLE 19-8: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for synchronous master reception.

Note 1: These pins are only available on 44-pin devices.

# 19.4 EUSART Synchronous Slave Mode

Synchronous Slave mode is entered by clearing bit, CSRC (TXSTAx<7>). This mode differs from the Synchronous Master mode in that the shift clock is supplied externally at the CKx pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in any low-power mode.

### 19.4.1 EUSART SYNCHRONOUS SLAVE TRANSMISSION

The operation of the Synchronous Master and Slave modes is identical, except in the case of Sleep mode.

If two words are written to the TXREGx and then the SLEEP instruction is executed, the following will occur:

- a) The first word will immediately transfer to the TSR register and transmit.
- b) The second word will remain in the TXREGx register.
- c) Flag bit, TXxIF, will not be set.
- d) When the first word has been shifted out of TSR, the TXREGx register will transfer the second word to the TSR and flag bit, TXxIF, will now be set.
- e) If enable bit, TXxIE, is set, the interrupt will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

To set up a Synchronous Slave Transmission:

- 1. Enable the synchronous slave serial port by setting bits, SYNC and SPEN, and clearing bit, CSRC.
- 2. Clear bits, CREN and SREN.
- 3. If interrupts are desired, set enable bit, TXxIE.
- 4. If 9-bit transmission is desired, set bit, TX9.
- 5. Enable the transmission by setting enable bit, TXEN.
- 6. If 9-bit transmission is selected, the ninth bit should be loaded in bit, TX9D.
- 7. Start transmission by loading data to the TXREGx register.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:		
GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63		
PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65		
PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65		
PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65		
SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65		
SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65		
SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65		
SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65		
EUSARTx	Transmit Reo	gister						65		
CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65		
ABDOVF	ABDOVF RCIDL RXDTP TXCKP BRG16 - WUE ABDEN									
Hx EUSARTx Baud Rate Generator Register High Byte										
SPBRGx EUSARTx Baud Rate Generator Register Low Byte										
	GIE/GIEH PMPIF <sup>(1)</sup> PMPIP <sup>(1)</sup> SSP2IF SSP2IF SSP2IP SPEN EUSARTx CSRC ABDOVF EUSARTx	GIE/GIEHPEIE/GIELPMPIF(1)ADIFPMPIE(1)ADIEPMPIP(1)ADIPSSP2IFBCL2IFSSP2IEBCL2IESSP2IPBCL2IPSPENRX9EUSARTx Transmit RegCSRCTX9ABDOVFRCIDLEUSARTx Baud Rate G	GIE/GIEHPEIE/GIELTMR0IEPMPIF(1)ADIFRC1IFPMPIE(1)ADIERC1IEPMPIP(1)ADIPRC1IPSSP2IFBCL2IFRC2IFSSP2IEBCL2IERC2IESSP2IPBCL2IPRC2IPSPENRX9SRENEUSARTx Transmit RejsterCSRCTX9ABDOVFRCIDLRXDTPEUSARTx Baud Rate Generator R	GIE/GIEHPEIE/GIELTMROIEINTOIEPMPIF(1)ADIFRC1IFTX1IFPMPIE(1)ADIERC1IETX1IEPMPIP(1)ADIPRC1IPTX1IPSSP2IFBCL2IFRC2IFTX2IFSSP2IEBCL2IERC2IETX2IESSP2IPBCL2IPRC2IPTX2IPSPENRX9SRENCRENEUSARTx Transmit RegisterCSRCTX9TXENABDOVFRCIDLRXDTPTXCKP	GIE/GIEHPEIE/GIELTMR0IEINT0IERBIEPMPIF(1)ADIFRC1IFTX1IFSSP1IFPMPIE(1)ADIERC1IETX1IESSP1IEPMPIP(1)ADIPRC1IPTX1IPSSP1IPSSP2IFBCL2IFRC2IFTX2IFTMR4IFSSP2IEBCL2IFRC2IETX2IETMR4IESSP2IPBCL2IPRC2IPTX2IPTMR4IPSPENRX9SRENCRENADDENEUSARTx Transmit RegisterTX2NSYNCSENDBABDOVFRCIDLRXDTPTXCKPBRG16EUSARTx Bud Rate Generator Register HightByte	GIE/GIEHPEIE/GIELTMROIEINTOIERBIETMROIFPMPIF(1)ADIFRC1IFTX1IFSSP1IFCCP1IFPMPIE(1)ADIERC1IETX1IESSP1IECCP1IEPMPIP(1)ADIPRC1IPTX1IPSSP1IPCCP1IPSSP2IFBCL2IFRC2IFTX2IFTMR4IFCTMUIFSSP2IEBCL2IERC2IETX2IETMR4IECTMUIFSSP2IPBCL2IPRC2IPTX2IPTMR4IPCTMUIPSSP2IPBCL2IPRC2IPTX2IPTMR4IPCTMUIPSPENRX9SRENCRENADDENFERREUSARTx Transmit RegisterSYNCSENDBBRGHABDOVFRCIDLRXDTPTXCKPBRG16—EUSARTx Bud Rate Generator Register HightFERRFERRFERRFERRFERRFERRFERR	GIE/GIEHPEIE/GIELTMROIEINTOIERBIETMROIFINTOIFPMPIF(1)ADIFRC1IFTX1IFSSP1IFCCP1IFTMR2IFPMPIE(1)ADIERC1IETX1IESSP1IFCCP1IETMR2IEPMPIP(1)ADIPRC1IPTX1IPSSP1IPCCP1IPTMR2IPSSP2IFBCL2IFRC2IFTX2IFTMR4IFCTMUIFTMR3GIFSSP2IPBCL2IPRC2IPTX2IPTMR4IECTMUIPTMR3GIPSSP2IPBCL2IPRC2IPTX2IPTMR4IPCTMUIPTMR3GIPSPENRX9SRENCRENADDENFERROERREUSARTx Transmit ResterSYNCSENDBBRGHTRMTABDOVFRCIDLRXDTPTXCKPBRG16—WUEEUSARTx Bud Rate Generator ResterByterByterByterByter	GIE/GIEHPEIE/GIELTMR0IEINT0IERBIETMR0IFINT0IFRBIFPMPIF(1)ADIFRC1IFTX1IFSSP1IFCCP1IFTMR2IFTMR1IFPMPIE(1)ADIERC1IETX1IESSP1IECCP1IETMR2IFTMR1IEPMPIP(1)ADIPRC1IPTX1IPSSP1IPCCP1IPTMR2IFTMR1IPSSP2IFBCL2IFRC2IFTX2IFTMR4IFCTMUIFTMR3GIFRTCCIFSSP2IPBCL2IPRC2IPTX2IPTMR4IECTMUIETMR3GIPRTCCIPSSP2IPBCL2IPRC2IPTX2IPTMR4IPCTMUIPTMR3GIPRTCCIPSPENRX9SRENCRENADDENFERROERRRX9DEUSARTxTransmit ResisterSYNCSENDBBRGHTRMTTX9DABDOVFRCIDLRXDTPTXCKPBRG16—WUEABDENEUSARTx Bud Rate Generator Resister HightStreStreStreStreStre		

# TABLE 19-9: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

Legend: — = unimplemented, read as '0'. Shaded cells are not used for synchronous slave transmission.

Note 1: These pins are only available on 44-pin devices.

## 19.4.2 EUSART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Slave modes is identical, except in the case of Sleep, or any Idle mode and bit, SREN, which is a "don't care" in Slave mode.

If receive is enabled by setting the CREN bit prior to entering Sleep or any Idle mode, then a word may be received while in this low-power mode. Once the word is received, the RSR register will transfer the data to the RCREGx register. If the RCxIE enable bit is set, the interrupt generated will wake the chip from the low-power mode. If the global interrupt is enabled, the program will branch to the interrupt vector. To set up a Synchronous Slave Reception:

- Enable the synchronous master serial port by setting bits, SYNC and SPEN, and clearing bit, CSRC.
- 2. If interrupts are desired, set enable bit, RCxIE.
- 3. If 9-bit reception is desired, set bit, RX9.
- 4. To enable reception, set enable bit, CREN.
- 5. Flag bit, RCxIF, will be set when reception is complete. An interrupt will be generated if enable bit, RCxIE, was set.
- Read the RCSTAx register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 7. Read the 8-bit received data by reading the RCREGx register.
- 8. If any error occurred, clear the error by clearing bit, CREN.
- If using interrupts, ensure that the GIE and PEIE bits in the INTCON register (INTCON<7:6>) are set.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:	
INTCON	<b>GIE/GIEH</b>	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63	
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65	
PIE1	PMPIE <sup>(1)</sup> ADIE RC1IE TX1IE SSP1IE CCP1IE TMR2IE TMR1IE								65	
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65	
PIR3	SSP2IF	BCL2IF	RC2IF	TX2IF	TMR4IF	CTMUIF	TMR3GIF	RTCCIF	65	
PIE3	SSP2IE	BCL2IE	RC2IE	TX2IE	TMR4IE	CTMUIE	TMR3GIE	RTCCIE	65	
IPR3	SSP2IP	BCL2IP	RC2IP	TX2IP	TMR4IP	CTMUIP	TMR3GIP	RTCCIP	65	
RCSTAx	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	65	
RCREGx	EUSARTx	Receive Reg	gister						65	
TXSTAx	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D	65	
BAUDCONx	ABDOVF	RCIDL	RXDTP	TXCKP	BRG16	_	WUE	ABDEN	66	
SPBRGHx	Hx         EUSARTx Baud Rate Generator Register High Byte									
SPBRGx										

## TABLE 19-10: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

Legend: — = unimplemented, read as '0'. Shaded cells are not used for synchronous slave reception.

**Note 1:** These pins are only available on 44-pin devices.

# PIC18F46J50 FAMILY

NOTES:

# 20.0 10-BIT ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

The Analog-to-Digital (A/D) Converter module has 10 inputs for the 28-pin devices and 13 for the 44-pin devices. Additionally, two internal channels are available for sampling the VDDCORE and VBG absolute reference voltage. This module allows conversion of an analog input signal to a corresponding 10-bit digital number.

The module has six registers:

- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)

- A/D Port Configuration Register 2 (ANCON0)
- A/D Port Configuration Register 1 (ANCON1)
- A/D Result Registers (ADRESH and ADRESL)

The ADCON0 register, in Register 20-1, controls the operation of the A/D module. The ADCON1 register, in Register 20-2, configures the A/D clock source, programmed acquisition time and justification.

The ANCON0 and ANCON1 registers, in Register 20-3 and Register 20-4, configure the functions of the port pins.

# REGISTER 20-1: ADCON0: A/D CONTROL REGISTER 0 (ACCESS FC2h)

:	OR	CHS3 W = Writable '1' = Bit is set		CHS1	CHS0	GO/DONE	ADON bit 0		
Legend: R = Readable t -n = Value at Po bit 7	OR						bit 0		
R = Readable t -n = Value at P bit 7	OR								
R = Readable t -n = Value at P bit 7	OR			II – Unimplon					
-n = Value at P	OR				onted hit rea	0' as '0'			
bit 7	-			U = Unimplemented bit, read as '0' '0' = Bit is cleared x = Bit is unknown					
:	VCFG1: Volta				aieu				
	1 = VREF- (AN 0 = AVSS	•	Configuration	bit (VREF- sourc	e)				
:	VCFG0: Volta 1 = VREF+ (A 0 = AVDD	•	Configuration	bit (VREF+ sour	ce)				
	0000 = Chan 0001 = Chan 0010 = Chan 0011 = Chan 0100 = Chan 0101 = Chan 0111 = Chan 0101 = Chan 1000 = Chan 1001 = Chan 1001 = Chan 1100 = Chan 1101 = Chan	nel 01 (AN1) nel 02 (AN2) nel 03 (AN3) nel 04 (AN4) nel 05 (AN5) <sup>(1)</sup> nel 06 (AN6) <sup>(1)</sup> nel 06 (AN6) nel 07 (AN7) <sup>(1)</sup> nel 08 (AN8) nel 09 (AN9) nel 10 (AN10) nel 11 (AN11) nel 12 (AN12) erved)		8)					
<u>N</u>	When ADON	/D Conversion <u>= 1:</u> version in progr							
-		Dn bit verter module is verter module is							

**3:** For best accuracy, the band gap reference circuit should be enabled (ANCON1<7> = 1) at least 10 ms before performing a conversion on this channel.

# PIC18F46J50 FAMILY

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
ADFM	ADCAL	ACQT2	ACQT1	ACQT0	ADCS2	ADCS1	ADCS0			
bit 7							bit (			
Legend:										
R = Readab	le bit	W = Writable	bit	U = Unimplen	nented bit, read	d as '0'				
-n = Value a		'1' = Bit is set		'0' = Bit is cle		x = Bit is unkr	nown			
bit 7	<b>ADFM:</b> A/D I 1 = Right jus 0 = Left justil		elect bit							
bit 6	ADCAL: A/D	Calibration bit								
		on is performed \/D Converter o		onversion						
bit 5-3	ACQT<2:0>: A/D Acquisition Time Select bits									
	111 = 20 TAU 110 = 16 TAU 101 = 12 TAU 100 = 8 TAD 011 = 6 TAD 010 = 4 TAD 001 = 2 TAD 000 = 0 TAD	2								
bit 2-0	110 = Fosc/ 101 = Fosc/ 100 = Fosc/	16 4 clock derived fro 32 8								

# REGISTER 20-2: ADCON1: A/D CONTROL REGISTER 1 (ACCESS FC1h)

**Note 1:** If the A/D FRC clock source is selected, a delay of one TcY (instruction cycle) is added before the A/D clock starts. This allows the SLEEP instruction to be executed before starting a conversion.

The ANCON0 and ANCON1 registers are used to configure the operation of the I/O pin associated with each analog channel. Setting any one of the PCFG bits configures the corresponding pin to operate as a digital only I/O. Clearing a bit configures the pin to operate as an analog input for either the A/D Converter or the comparator module; all digital peripherals are disabled and digital inputs read as '0'. As a rule, I/O pins that are multiplexed with analog inputs default to analog operation on device Resets.

In order to correctly perform A/D conversions on the VBG band gap reference (ADCON0<5:2> = 1111), the reference circuit must be powered on first. The VBGEN bit in the ANCON1 register allows the firmware to manually

request that the band gap reference circuit should be enabled. For best accuracy, firmware should allow a settling time of at least 10 ms prior to performing the first acquisition on this channel after enabling the band gap reference.

The reference circuit may already have been turned on if some other hardware module (such as the on-chip voltage regulator, comparators or HLVD) has already requested it. In this case, the initial turn-on settling time may have already elapsed and firmware does not need to wait as long before measuring VBG. Once the acquisition is complete, firmware may clear the VBGEN bit, which will save a small amount of power if no other modules are still requesting the VBG reference.

REGISTER 20-3:	ANCON0: A/D PORT CONFIGURATION REGISTER 2 (BANKED F48h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
PCFG7 <sup>(1)</sup>	PCFG6 <sup>(1)</sup>	PCFG5 <sup>(1)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0		
bit 7							bit 0		
Legend:									
R = Readable bit W = Writable bit				U = Unimplemented bit, read as '0'					
-n = Value at POR '1' = Bit is set			'0' = Bit is clea	nown					

bit 7-0 **PCFG<7:0>:** Analog Port Configuration bits (AN7-AN0)

1 = Pin configured as a digital port

0 = Pin configured as an analog channel – digital input disabled and reads '0'

**Note 1:** These bits are only available only on 44-pin devices.

# REGISTER 20-4: ANCON1: A/D PORT CONFIGURATION REGISTER 1 (BANKED F49h)

R/W-0	r	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
VBGEN	—	—	PCFG12	PCFG11	PCFG10	PCFG9	PCFG8
bit 7							bit 0

Legend:	r = Reserved			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

bit 7	<b>VBGEN:</b> 1.2V Band Gap Reference Enable bit 1 = 1.2V band gap reference is powered on 0 = 1.2V band gap reference is turned off to save power (if no other modules are requesting it)
bit 6	Reserved: Always maintain as '0' for lowest power consumption
bit 5	Unimplemented: Read as '0'
bit 4-0	<b>PCFG&lt;12:8&gt;:</b> Analog Port Configuration bits (AN12-AN8) 1 = Pin configured as a digital port 0 = Pin configured as an analog channel – digital input disabled and reads '0'

The analog reference voltage is software selectable to either the device's positive and negative supply voltage (AVDD and AVSS), or the voltage level on the RA3/AN3/VREF+/C1INB and RA2/AN2/VREF-/CVREF/C2INB pins.


The A/D Converter has a unique feature of being able to operate while the device is in Sleep mode. To operate in Sleep, the A/D conversion clock must be derived from the A/D's internal RC oscillator.

The output of the sample and hold is the input into the Converter, which generates the result via successive approximation.

Each port pin associated with the A/D Converter can be configured as an analog input or as a digital I/O. The ADRESH and ADRESL registers contain the result of the A/D conversion. When the A/D conversion is complete, the result is loaded into the ADRESH:ADRESL register pair, the GO/DONE bit (ADCON0<1>) is cleared and the A/D Interrupt Flag bit, ADIF, is set.

A device Reset forces all registers to their Reset state. This forces the A/D module to be turned off and any conversion in progress is aborted. The value in the ADRESH:ADRESL register pair is not modified for a Power-on Reset (POR). These registers will contain unknown data after a POR.

Figure 20-1 provides the block diagram of the A/D module.



## FIGURE 20-1: A/D BLOCK DIAGRAM


After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see **Section 20.1 "A/D Acquisition Requirements"**. After this acquisition time has elapsed, the A/D conversion can be started. An acquisition time <u>can be</u> programmed to occur between setting the GO/DONE bit and the actual start of the conversion.

The following steps should be followed to do an A/D conversion:

- 1. Configure the A/D module:
  - Configure the required ADC pins as analog pins using ANCON0, ANCON1
  - Set voltage reference using ADCON0
  - Select A/D input channel (ADCON0)
  - Select A/D acquisition time (ADCON1)
  - Select A/D conversion clock (ADCON1)
  - Turn on A/D module (ADCON0)



- 2. Configure A/D interrupt (if desired):
  - Clear ADIF bit
  - Set ADIE bit
  - Set GIE bit
- 3. Wait the required acquisition time (if required).
- 4. Start conversion:
  - Set GO/DONE bit (ADCON0<1>)
- 5. Wait for A/D conversion to complete, by either:
  Polling for the GO/DONE bit to be cleared OR
  - Waiting for the A/D interrupt
- 6. Read A/D Result registers (ADRESH:ADRESL); clear bit, ADIF, if required.
- 7. For next conversion, go to step 1 or step 2, as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2 TAD is required before next acquisition starts.



#### 20.1 **A/D Acquisition Requirements**

For the A/D Converter to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The analog input model is illustrated in Figure 20-2. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is 10 k $\Omega$ . After the analog input channel is selected (changed), the channel must be sampled for at least the minimum acquisition time before starting a conversion.

Note: When the conversion is started, the holding capacitor is disconnected from the input pin.

EQUATION 20-1: ACQUISITION TIME

TACO Amplifier Settling Time + Holding Capacitor Charging Time + Temperature Coefficient = TAMP + TC + TCOFF =

## EQUATION 20-2: A/D MINIMUM CHARGING TIME

VHOLD	=	$(\text{VREF} - (\text{VREF}/2048)) \bullet (1 - e^{(-\text{TC/CHOLD}(\text{RIC} + \text{RSS} + \text{RS}))})$
or TC	=	-(CHOLD)(RIC + RSS + RS) ln(1/2048)

#### EQUATION 20-3: CALCULATING THE MINIMUM REQUIRED ACQUISITION TIME

TACQ	=	TAMP + TC + TCOFF
TAMP	=	0.2 μs
TCOFF	=	(Temp – 25°C)(0.02 μs/°C) (85°C – 25°C)(0.02 μs/°C) 1.2 μs
Tempera	ature c	oefficient is only required for temperatures > 25°C. Below 25°C, TCOFF = 0 $\mu$ s.
Тс	=	-(CHOLD)(RIC + RSS + RS) $\ln(1/2048) \mu s$ -(25 pF) (1 k $\Omega$ + 2 k $\Omega$ + 2.5 k $\Omega$ ) ln(0.0004883) $\mu s$ 1.05 $\mu s$
TACQ	=	0.2 μs + 1.05 μs + 1.2 μs 2.45 μs

calculate the minimum acquisition To time. Equation 20-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

Equation 20-3 provides the calculation of the minimum required acquisition time, TACQ. This calculation is based on the following application svstem assumptions:

Chold	=	25 pF
Rs	=	2.5 kΩ
Conversion Error	$\leq$	1/2 LSb
Vdd	=	$3V \rightarrow Rss = 2 k\Omega$
Temperature	=	85°C (system max.)

# 20.2 Selecting and Configuring Automatic Acquisition Time

The ADCON1 register allows the user to select an acquisition time that occurs each time the GO/DONE bit is set.

When the GO/DONE bit is set, sampling is stopped and a conversion begins. The user is responsible for ensuring the required acquisition time has passed between selecting the desired input channel and setting the GO/DONE bit. This occurs when the ACQT<2:0> bits (ADCON1<5:3>) remain in their Reset state ('000') and is compatible with devices that do not offer programmable acquisition times.

If desired, the ACQT bits can be set to select a programmable acquisition time for the A/D module. When the GO/DONE bit is set, the A/D module continues to sample the input for the selected acquisition time, then automatically begins a conversion. Since the acquisition time is programmed, there may be no need to wait for an acquisition time between selecting a channel and setting the GO/DONE bit.

In either case, when the conversion is completed, the GO/DONE bit is cleared, the ADIF flag is set and the A/D begins sampling the currently selected channel again. If an acquisition time is programmed, there is nothing to indicate if the acquisition time has ended or if the conversion has begun.

# 20.3 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 11 TAD per 10-bit conversion. The source of the A/D conversion clock is software selectable.

There are seven possible options for TAD:

- 2 Tosc
- 4 Tosc
- 8 Tosc
- 16 Tosc
- 32 Tosc
- 64 Tosc
- Internal RC Oscillator

For correct A/D conversions, the A/D conversion clock (TAD) must be as short as possible but greater than the minimum TAD (see parameter 130 in Table 29-30 for more information).

Table 20-1 provides the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

# TABLE 20-1: TAD vs. DEVICE OPERATING FREQUENCIES

AD Clock S	Maximum	
Operation	ADCS<2:0>	Device Frequency
2 Tosc	000	2.86 MHz
4 Tosc	100	5.71 MHz
8 Tosc	001	11.43 MHz
16 Tosc	101	22.86 MHz
32 Tosc	010	45.71 MHz
64 Tosc	110	48.0 MHz
RC <sup>(2)</sup>	011	1.00 MHz <sup>(1)</sup>

Note 1: The RC source has a typical TAD time of  $4 \ \mu$ s.

2: For device frequencies above 1 MHz, the device must be in Sleep mode for the entire conversion or the A/D accuracy may be out of specification.

# 20.4 Configuring Analog Port Pins

The ANCON0, ANCON1 and TRISA registers control the operation of the A/D port pins. The port pins needed as analog inputs must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS<3:0> bits and the TRIS bits.

- Note 1: When reading the PORT register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as digital inputs will convert an analog input. Analog levels on a digitally configured input will be accurately converted.
  - Analog levels on any pin defined as a digital input may cause the digital input buffer to consume current out of the device's specification limits.

# 20.5 A/D Conversions

Figure 20-3 displays the operation of the A/D Converter after the GO/DONE bit has been set and the ACQT<2:0> bits are cleared. A conversion is started after the following instruction to allow entry into Sleep mode before the conversion begins.

Figure 20-4 displays the operation of the A/D Converter after the GO/DONE bit has been set, the ACQT<2:0> bits are set to '010' and selecting a 4 TAD acquisition time before the conversion starts.

Clearing the GO/DONE bit during a conversion will abort the current conversion. The A/D Result register pair will NOT be updated with the partially completed A/D conversion sample. This means the ADRESH:ADRESL registers will continue to contain the value of the last completed conversion (or the last value written to the ADRESH:ADRESL registers).

After the A/D conversion is completed or aborted, a 2 TAD wait is required before the next acquisition can be started. After this wait, acquisition on the selected channel is automatically started.


Note:	The GO/DONE bit should NOT be set in
	the same instruction that turns on the A/D.

# 20.6 Use of the ECCP2 Trigger


An A/D conversion can be started by the Special Event Trigger of the ECCP2 module. This requires that the CCP2M<3:0> bits (CCP2CON<3:0>) be programmed as '1011' and that the A/D module is enabled (ADON bit is set). When the trigger occurs, the GO/DONE bit will be set, starting the A/D acquisition and conversion, and the Timer1 (or Timer3) counter will be reset to zero. Timer1 (or Timer3) is reset to automatically repeat the A/D acquisition period with minimal software overhead (moving ADRESH/ADRESL to the desired location). The appropriate analog input channel must be selected and the minimum acquisition period is either timed by the user, or an appropriate TACQ time is selected before the Special Event Trigger sets the GO/DONE bit (starts a conversion).

If the A/D module is not enabled (ADON is cleared), the Special Event Trigger will be ignored by the A/D module but will still reset the Timer1 (or Timer3) counter.

# FIGURE 20-3: A/D CONVERSION TAD CYCLES (ACQT<2:0> = 000, TACQ = 0)



### FIGURE 20-4: A/D CONVERSION TAD CYCLES (ACQT<2:0> = 010, TACQ = 4 TAD)



# 20.7 A/D Converter Calibration

The A/D Converter in the PIC18F46J50 Family of devices includes a self-calibration feature, which compensates for any offset generated within the module. The calibration process is automated and is initiated by setting the ADCAL bit (ADCON1<6>). The next time the GO/DONE bit is set, the module will perform a "dummy" conversion (that is, with reading none of the input channels) and store the resulting value internally to compensate for the offset. Thus, subsequent offsets will be compensated.

Example 20-1 provides an example of a calibration routine.

The calibration process assumes that the device is in a relatively steady-state operating condition. If A/D calibration is used, it should be performed after each device Reset or if there are other major changes in operating conditions.

# 20.8 Operation in Power-Managed Modes

The selection of the automatic acquisition time and A/D conversion clock is determined in part by the clock source and frequency while in a power-managed mode.

If the A/D is expected to operate while the device is in a power-managed mode, the ACQT<2:0> and ADCS<2:0> bits in ADCON1 should be updated in accordance with the power-managed mode clock that will be used. After the power-managed mode is entered (either of the power-managed Run modes), an A/D acquisition or conversion may be started. Once an acquisition or conversion is started, the device should continue to be clocked by the same power-managed mode clock source until the conversion has been completed. If desired, the device may be placed into the corresponding power-managed Idle mode during the conversion.

If the power-managed mode clock frequency is less than 1 MHz, the A/D RC clock source should be selected.

Operation in the Sleep mode requires the A/D RC clock to be selected. If bits, ACQT<2:0>, are set to '000' and a conversion is started, the conversion will be delayed one instruction cycle to allow execution of the SLEEP instruction and entry to Sleep mode. The IDLEN and SCS bits in the OSCCON register must have already been cleared prior to starting the conversion.

# EXAMPLE 20-1: SAMPLE A/D CALIBRATION ROUTINE

CALIB	BCF BSF BSF RATION BTFSC BRA BCF	ANCON0, PCFG0 ADCON0, ADON ADCON1, ADCAL ADCON0, GO ADCON0, GO CALIBRATION ADCON1, ADCAL	<pre>;Make Channel 0 analog ;Enable A/D module ;Enable Calibration ;Start a dummy A/D conversion ; ;Wait for the dummy conversion to finish ; :Calibration done turn off calibration enable</pre>
CALTD		11200110,000	
CALIB	RATION		;
	BTFSC	ADCON0,GO	;Wait for the dummy conversion to finish
	BRA	CALIBRATION	;
	BCF	ADCON1, ADCAL	;Calibration done, turn off calibration enable
			;Proceed with the actual A/D conversion
			,

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
PIR1	PMPIF <sup>(1)</sup>	ADIF	RC1IF	TX1IF	SSP1IF	CCP1IF	TMR2IF	TMR1IF	65
PIE1	PMPIE <sup>(1)</sup>	ADIE	RC1IE	TX1IE	SSP1IE	CCP1IE	TMR2IE	TMR1IE	65
IPR1	PMPIP <sup>(1)</sup>	ADIP	RC1IP	TX1IP	SSP1IP	CCP1IP	TMR2IP	TMR1IP	65
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	65
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	65
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	65
ADRESH	A/D Result Register High Byte								64
ADRESL	A/D Result	t Register Lo	w Byte						64
ADCON0	VCFG1	VCFG0	CHS3	CHS3	CHS1	CHS0	GO/DONE	ADON	64
ANCON0	PCFG7 <sup>(1)</sup>	PCFG6 <sup>(1)</sup>	PCFG5 <sup>(1)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	68
ADCON1	ADFM	ADCAL	ACQT2	ACQT1	ACQT0	ADCS2	ADCS1	ADCS0	64
ANCON1	VBGEN	r	_	PCFG12	PCFG11	PCFG10	PCFG9	PCFG8	68
CCP2CON	P2M1	P2M0	DC2B1	DC2B0	CCP2M3	CCP2M2	CCP2M1	CCP2M0	65
PORTA	RA7	RA6	RA5		RA3	RA2	RA1	RA0	66
TRISA	TRISA7	TRISA6	TRISA5	_	TRISA3	TRISA2	TRISA1	TRISA0	66

# TABLE 20-2: SUMMARY OF A/D REGISTERS

Legend: — = unimplemented, read as '0', r = reserved. Shaded cells are not used for A/D conversion.

Note 1: These bits are only available on 44-pin devices.


#### 21.0 UNIVERSAL SERIAL BUS (USB)

This section describes the details of the USB peripheral. Because of the very specific nature of the module, knowledge of USB is expected. Some high-level USB information is provided in Section 21.9 "Overview of **USB**" only for application design reference. Designers are encouraged to refer to the official specification published by the USB Implementers Forum (USB-IF) for the latest information. USB Specification Revision 2.0 is the most current specification at the time of publication of this document.

#### 21.1 **Overview of the USB Peripheral**

PIC18F46J50 Family devices contain a full-speed and low-speed, compatible USB Serial Interface Engine (SIE) that allows fast communication between any USB host and the PIC® MCU. The SIE can be interfaced directly to the USB, utilizing the internal transceiver.

Some special hardware features have been included to improve performance. Dual access port memory in the device's data memory space (USB RAM) has been supplied to share direct memory access between the microcontroller core and the SIE. Buffer descriptors are also provided, allowing users to freely program endpoint memory usage within the USB RAM space. Figure 21-1 provides a general overview of the USB peripheral and its features.



#### FIGURE 21-1: **USB PERIPHERAL AND OPTIONS**

# 21.2 USB Status and Control

The operation of the USB module is configured and managed through three control registers. In addition, a total of 22 registers are used to manage the actual USB transactions. The registers are:

- USB Control register (UCON)
- USB Configuration register (UCFG)
- USB Transfer Status register (USTAT)
- USB Device Address register (UADDR)
- Frame Number registers (UFRMH:UFRML)
- Endpoint Enable registers 0 through 15 (UEPn)

## 21.2.1 USB CONTROL REGISTER (UCON)

The USB Control register (Register 21-1) contains bits needed to control the module behavior during transfers. The register contains bits that control the following:

- Main USB Peripheral Enable
- Ping-Pong Buffer Pointer Reset
- Control of the Suspend mode
- Packet Transfer Disable

In addition, the USB Control register contains a status bit, SE0 (UCON<5>), which is used to indicate the occurrence of a single-ended zero on the bus. When the USB module is enabled, this bit should be monitored to determine whether the differential data lines have come out of a single-ended zero condition. This helps to differentiate the initial power-up state from the USB Reset signal.

The overall operation of the USB module is controlled by the USBEN bit (UCON<3>). Setting this bit activates the module and resets all of the PPBI bits in the Buffer Descriptor Table (BDT) to '0'. This bit also activates the internal pull-up resistors, if they are enabled. Thus, this bit can be used as a soft attach/detach to the USB. Although all status and control bits are ignored when this bit is clear, the module needs to be fully preconfigured prior to setting this bit. The USB clock source should have been already configured for the correct frequency and running. If the PLL is being used, it should be enabled at least 2 ms (enough time for the PLL to lock) before attempting to set the USBEN bit.

Note: When disabling the USB module, make sure the SUSPND bit (UCON<1>) is clear prior to clearing the USBEN bit. Clearing the USBEN bit when the module is in the suspended state may prevent the module from fully powering down

# PIC18F46J50 FAMILY

# REGISTER 21-1: UCON: USB CONTROL REGISTER (ACCESS F65h)

U-0	R/W-0	R-x	R/C-0	R/W-0	R/W-0	R/W-0	U-0
—	PPBRST	SE0	PKTDIS	USBEN <sup>(1)</sup>	RESUME	SUSPND	—
bit 7							bit 0

Legend:	C = Clearable bit		
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	Unimplemented: Read as '0'
bit 6	PPBRST: Ping-Pong Buffers Reset bit
	<ul> <li>1 = Reset all Ping-Pong Buffer Pointers to the Even Buffer Descriptor (BD) banks</li> <li>0 = Ping-Pong Buffer Pointers not being reset</li> </ul>
bit 5	SE0: Live Single-Ended Zero Flag bit
	<ul><li>1 = Single-ended zero active on the USB bus</li><li>0 = No single-ended zero detected</li></ul>
bit 4	PKTDIS: Packet Transfer Disable bit
	<ul> <li>1 = SIE token and packet processing disabled, automatically set when a SETUP token is received</li> <li>0 = SIE token and packet processing enabled</li> </ul>
bit 3	USBEN: USB Module Enable bit <sup>(1)</sup>
	<ul><li>1 = USB module and supporting circuitry enabled (device attached)</li><li>0 = USB module and supporting circuitry disabled (device detached)</li></ul>
bit 2	RESUME: Resume Signaling Enable bit
	<ul><li>1 = Resume signaling activated</li><li>0 = Resume signaling disabled</li></ul>
bit 1	SUSPND: Suspend USB bit
	<ul> <li>1 = USB module and supporting circuitry in Power Conserve mode, SIE clock inactive</li> <li>0 = USB module and supporting circuitry in normal operation, SIE clocked at the configured rate</li> </ul>
bit 0	Unimplemented: Read as '0'

Note 1: Make sure the USB clock source is correctly configured before setting this bit.

The PPBRST bit (UCON<6>) controls the Reset status when Double-Buffering mode (ping-pong buffering) is used. When the PPBRST bit is set, all Ping-Pong Buffer Pointers are set to the Even buffers. PPBRST has to be cleared by firmware. This bit is ignored in buffering modes not using ping-pong buffering.

The PKTDIS bit (UCON<4>) is a flag indicating that the SIE has disabled packet transmission and reception. This bit is set by the SIE when a SETUP token is received to allow setup processing. This bit cannot be set by the microcontroller, only cleared; clearing it allows the SIE to continue transmission and/or reception. Any pending events within the Buffer Descriptor Table will still be available, indicated within the USTAT register's FIFO buffer.

The RESUME bit (UCON<2>) allows the peripheral to perform a remote wake-up by executing resume signaling. To generate a valid remote wake-up, firmware must set RESUME for 10 ms and then clear the bit. For more information on resume signaling, see Sections 7.1.7.5, 11.4.4 and 11.9 in the USB 2.0 Specification.

The SUSPND bit (UCON<1>) places the module and supporting circuitry in a low-power mode. The input clock to the SIE is also disabled. This bit should be set by the software in response to an IDLEIF interrupt. It should be reset by the microcontroller firmware after an ACTVIF interrupt is observed. When this bit is active, the device remains attached to the bus but the transceiver outputs remain Idle. The voltage on the VUSB pin may vary depending on the value of this bit. Setting this bit before a IDLEIF request will result in unpredictable bus behavior.

Note: While in Suspend mode, a typical bus-powered USB device is limited to 2.5 mA of current. This is the complete current which may be drawn by the PIC device and its supporting circuitry. Care should be taken to assure minimum current draw when the device enters Suspend mode.

# 21.2.2 USB CONFIGURATION REGISTER (UCFG)

Prior to communicating over USB, the module's associated internal and/or external hardware must be configured. Most of the configuration is performed with the UCFG register (Register 21-2).The UFCG register contains most of the bits that control the system level behavior of the USB module. These include:

- Bus Speed (full speed versus low speed)
- On-Chip Pull-up Resistor Enable
- On-Chip Transceiver Enable
- Ping-Pong Buffer Usage

The UCFG register also contains two bits, which aid in module testing, debugging and USB certifications. These bits control output enable state monitoring and eye pattern generation.

Note:	The USB speed, transceiver and pull-up should only be configured during the module setup phase. It is not recom-
	mended to switch these settings while the module is enabled.

# 21.2.2.1 Internal Transceiver

The USB peripheral has a built-in, USB 2.0, full-speed and low-speed capable transceiver, internally connected to the SIE. This feature is useful for low-cost, single chip applications. The UTRDIS bit (UCFG<3>) controls the transceiver; it is enabled by default (UTRDIS = 0). The FSEN bit (UCFG<2>) controls the transceiver speed; setting the bit enables full-speed operation.

The on-chip USB pull-up resistors are controlled by the UPUEN bit (UCFG<4>). They can only be selected when the on-chip transceiver is enabled.

The internal USB transceiver obtains power from the VUSB pin. In order to meet USB signalling level specifications, VUSB must be supplied with a voltage source between 3.0V and 3.6V. The best electrical signal quality is obtained when a 3.3V supply is used and locally bypassed with a high quality ceramic capacitor (ex: 0.1  $\mu$ F). The capacitor should be placed as close as possible to the VUSB and VSS pins.

VUSB should always be maintained  $\geq$  VDD. If the USB module is not used, but RC4 or RC5 are used as general purpose inputs, VUSB should still be connected to a power source (such as VDD). The input thresholds for the RC4 and RC5 pins are dependent upon the VUSB supply level.

The D+ and D- signal lines can be routed directly to their respective pins on the USB connector or cable (for hard-wired applications). No additional resistors, capacitors, or magnetic components are required as the D+ and D- drivers have controlled slew rate and output impedance intended to match with the characteristic impedance of the USB cable.

In order to achieve optimum USB signal quality, the D+ and D- traces between the microcontroller and USB connector (or cable) should be less than 19 cm long. Both traces should be equal in length and they should be routed parallel to each other. Ideally, these traces should be designed to have a characteristic impedance matching that of the USB cable.

# REGISTER 21-2: UCFG: USB CONFIGURATION REGISTER (BANKED F39h)

R/W-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
UTEYE	UOEMON	_	UPUEN <sup>(1,2)</sup>	UTRDIS <sup>(1,3)</sup>	FSEN <sup>(1)</sup>	PPB1	PPB0
bit 7							bit 0
Legend:							
R = Reada	ble bit	W = Writable bit		U = Unimplem	ented bit, rea	d as '0'	
-n = Value	at POR	'1' = Bit is se	et	'0' = Bit is clea	ared	x = Bit is unkr	nown
bit 7		-	Test Enable bit				
	• •	ern test enable					
hit C		ern test disabl ISB OE Monito					
bit 6			icating intervals	during which t	ho D±/D linor	aro driving	
	0 = UOE sig					s are unving	
bit 5	•	nted: Read as	<b>'</b> 0 <b>'</b>				
bit 4	UPUEN: USE	3 On-Chip Pul	I-up Enable bit <sup>(</sup>	1,2)			
			d (pull-up on D+		1 or D- with F	SEN = 0)	
		oull-up disable					
bit 3			iver Disable bit <sup>(</sup>	1,3)			
		ransceiver dis					
bit 2		ransceiver act					
DILZ		•	rols transceiver	edae rates: re	quires input c	lock at 48 MHz	
			trols transceive				
bit 1-0	•		ers Configuration	•			
		• •	buffers enabled		1 to 15		
			buffers enabled				
			buffer enabled f	•	int 0		
		uu ping-pong i	buffers disabled	I			
	The UPUEN, UTR				d while the US	SB module is en	abled. These
	values must be pr	•	•				
2:	This bit is only vali		-chip transceive	•			ea.

**3:** If UTRDIS is set, the  $\overline{\text{UOE}}$  signal will be active – independent of the UOEMON bit setting.

# 21.2.2.2 Internal Pull-up Resistors

The PIC18F46J50 Family devices have built-in pull-up resistors designed to meet the requirements for low-speed and full-speed USB. The UPUEN bit (UCFG<4>) enables the internal pull-ups. Figure 21-1 shows the pull-ups and their control.


Note: A compliant USB device should never source any current onto the +5V VBUS line of the USB cable. Additionally, USB devices should not source any current on the D+ and D- data lines whenever the +5V VBUS line is less than 1.17V. In order to be USB compliant, applications which are not purely bus-powered should monitor the VBUS line and avoid turning on the USB module and the D+ or D- pull-up resistor until VBUS is greater than 1.17V. VBUS can be connected to and monitored by a 5V tolerant I/O pin, or if a resistive divider is used, by an analog capable pin.

# 21.2.2.3 External Pull-up Resistors

External pull-ups may also be used. The VUSB pin may be used to pull up D+ or D-. The pull-up resistor must be  $1.5 \text{ k}\Omega \text{ (}\pm5\%\text{)}$  as required by the USB specifications.

Figure 21-2 provides an example of external circuitry.





# 21.2.2.4 Ping-Pong Buffer Configuration

The usage of ping-pong buffers is configured using the PPB<1:0> bits. Refer to **Section 21.4.4** "**Ping-Pong Buffering**" for a complete explanation of the ping-pong buffers.

# 21.2.2.5 Eye Pattern Test Enable

An automatic eye pattern test can be generated by the module when the UCFG<7> bit is set. The eye pattern output will be observable based on module settings, meaning that the user is first responsible for configuring the SIE clock settings, pull-up resistor and Transceiver mode. In addition, the module has to be enabled.

Once UTEYE is set, the module emulates a switch from a receive to transmit state and will start transmitting a J-K-J-K bit sequence (K-J-K-J for full speed). The sequence will be repeated indefinitely while the Eye Pattern Test mode is enabled.

Note that this bit should never be set while the module is connected to an actual USB system. This Test mode is intended for board verification to aid with USB certification tests. It is intended to show a system developer the noise integrity of the USB signals which can be affected by board traces, impedance mismatches and proximity to other system components. It does not properly test the transition from a receive to a transmit state. Although the eye pattern is not meant to replace the more complex USB certification test, it should aid during first order system debugging.

# 21.2.3 USB STATUS REGISTER (USTAT)

The USB Status register reports the transaction status within the SIE. When the SIE issues a USB transfer complete interrupt, USTAT should be read to determine the status of the transfer. USTAT contains the transfer endpoint number, direction and Ping-Pong Buffer Pointer value (if used).


Note:	The data in the USB Status register is valid					
	only when the TRNIF interrupt flag is					
	asserted.					

The USTAT register is actually a read window into a four-byte status FIFO, maintained by the SIE. It allows the microcontroller to process one transfer while the SIE processes additional endpoints (Figure 21-3). When the SIE completes using a buffer for reading or writing data, it updates the USTAT register. If another USB transfer is performed before a transaction complete interrupt is serviced, the SIE will store the status of the next transfer into the status FIFO.

Clearing the transfer complete flag bit, TRNIF, causes the SIE to advance the FIFO. If the next data in the FIFO holding register is valid, the SIE will reassert the interrupt within 5 TCY of clearing TRNIF. If no additional data is present, TRNIF will remain clear; USTAT data will no longer be reliable.

Note:	If an end	lpoint re	que	st is re	ceive	d while	e the
	USTAT	FIFO	is	full,	the	SIE	will
	automat	ically iss	sue a	a NAK	back	to the I	nost.

### FIGURE 21-3: USTAT FIFO



# REGISTER 21-3: USTAT: USB STATUS REGISTER (ACCESS F64h)

				•	-					
U-0	R-x	R-x	R-x	R-x	R-x	R-x	U-0			
—	ENDP3	ENDP2	ENDP1	ENDP0	DIR	PPBI <sup>(1)</sup>				
oit 7			•				bit			
_egend:										
R = Readab	le bit	W = Writable	bit	U = Unimpler	nented bit, read	d as '0'				
-n = Value a	t POR	'1' = Bit is set	t	'0' = Bit is cle	ared	x = Bit is unkno	own			
bit 7	Unimplemer	nted: Read as '	0'							
oit 6-3		Encoded Num								
	(represents tl	(represents the number of the BDT updated by the last USB transfer)								
	1111 = End	1111 = Endpoint 15								
	1110 <b>= End</b>	point 14								
	•									
	•									
	0001 = End	noint 1								
	0000 = End									
oit 2	-	-	sator bit							
511 2		DIR: Last BD Direction Indicator bit								
		<ol> <li>The last transaction was an IN token</li> <li>The last transaction was an OUT or SETUP token</li> </ol>								
oit 1		ong BD Pointe								
	0	0								
		<ul> <li>1 = The last transaction was to the Odd BD bank</li> <li>0 = The last transaction was to the Even BD bank</li> </ul>								
bit 0										
JILU	ommpiemer	nted: Read as '	U							
Note 1: ⊤	his bit is only val	id for endpoints	s with available	e Even and Od	d BD registers.					

© 2009 Microchip Technology Inc.

# 21.2.4 USB ENDPOINT CONTROL

Each of the 16 possible bidirectional endpoints has its own independent control register, UEPn (where 'n' represents the endpoint number). Each register has an identical complement of control bits.

Register 21-4 provides the prototype.

The EPHSHK bit (UEPn<4>) controls handshaking for the endpoint; setting this bit enables USB handshaking. Typically, this bit is always set except when using isochronous endpoints.

The EPCONDIS bit (UEPn<3>) is used to enable or disable USB control operations (SETUP) through the endpoint. Clearing this bit enables SETUP transactions. Note that the corresponding EPINEN and EPOUTEN bits must be set to enable IN and OUT transactions. For Endpoint 0, this bit should always be cleared since the USB specifications identify Endpoint 0 as the default control endpoint.

The EPOUTEN bit (UEPn<2>) is used to enable or disable USB OUT transactions from the host. Setting this bit enables OUT transactions. Similarly, the EPINEN bit (UEPn<1>) enables or disables USB IN transactions from the host.

The EPSTALL bit (UEPn<0>) is used to indicate a STALL condition for the endpoint. If a STALL is issued on a particular endpoint, the EPSTALL bit for that endpoint pair will be set by the SIE. This bit remains set until it is cleared through firmware, or until the SIE is reset.

# REGISTER 21-4: UEPn: USB ENDPOINT n CONTROL REGISTER (UEP0 THROUGH UEP15) (BANKED F26h-F35h)

U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
		_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	l as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-5	Unimplemented: Read as '0'
bit 4	EPHSHK: Endpoint Handshake Enable bit
	1 = Endpoint handshake enabled
	0 = Endpoint handshake disabled (typically used for isochronous endpoints)
bit 3	EPCONDIS: Bidirectional Endpoint Control bit
	If EPOUTEN = 1 and EPINEN = 1:
	1 = Disable Endpoint n from control transfers; only IN and OUT transfers allowed
	0 = Enable Endpoint n for control (SETUP) transfers; IN and OUT transfers also allowed
bit 2	EPOUTEN: Endpoint Output Enable bit
	1 = Endpoint n output enabled
	0 = Endpoint n output disabled
bit 1	EPINEN: Endpoint Input Enable bit
	1 = Endpoint n input enabled
	0 = Endpoint n input disabled
bit 0	EPSTALL: Endpoint Stall Indicator bit
	1 = Endpoint n has issued one or more STALL packets
	0 = Endpoint n has not issued any STALL packets

# 21.2.5 USB ADDRESS REGISTER (UADDR)

The USB Address register contains the unique USB address that the peripheral will decode when active. UADDR is reset to 00h when a USB Reset is received, indicated by URSTIF, or when a Reset is received from the microcontroller. The USB address must be written by the microcontroller during the USB setup phase (enumeration) as part of the Microchip USB firmware support.

# 21.2.6 USB FRAME NUMBER REGISTERS (UFRMH:UFRML)

The Frame Number registers contain the 11-bit frame number. The low-order byte is contained in UFRML, while the three high-order bits are contained in UFRMH. The register pair is updated with the current frame number whenever a SOF token is received. For the microcontroller, these registers are read-only. The Frame Number registers are primarily used for isochronous transfers. The contents of the UFRMH and UFRML registers are only valid when the 48 MHz SIE clock is active (i.e., contents are inaccurate when SUSPND (UCON<1>) bit = 1).

# 21.3 USB RAM


USB data moves between the microcontroller core and the SIE through a memory space known as the USB RAM. This is a special dual access memory that is mapped into the normal data memory space in Banks 0 through 14 (00h to EBFh) for a total of 3.8 Kbytes (Figure 21-4).

Bank 4 (400h through 4FFh) is used specifically for endpoint buffer control, while Banks 0 through 3 and Banks 5 through 14 are available for USB data. Depending on the type of buffering being used, all but 8 bytes of Bank 4 may also be available for use as USB buffer space.

Although USB RAM is available to the microcontroller as data memory, the sections that are being accessed by the SIE should not be accessed by the microcontroller. A semaphore mechanism is used to determine the access to a particular buffer at any given time. This is discussed in **Section 21.4.1.1 "Buffer Ownership**".

# FIGURE 21-4:

### IMPLEMENTATION OF USB RAM IN DATA MEMORY SPACE



# 21.4 Buffer Descriptors and the Buffer Descriptor Table

The registers in Bank 4 are used specifically for endpoint buffer control in a structure known as the Buffer Descriptor Table (BDT). This provides a flexible method for users to construct and control endpoint buffers of various lengths and configuration.

The BDT is composed of Buffer Descriptors (BD) which are used to define and control the actual buffers in the USB RAM space. Each BD, in turn, consists of four registers, where n represents one of the 64 possible BDs (range of 0 to 63):

- BDnSTAT: BD Status register
- BDnCNT: BD Byte Count register
- · BDnADRL: BD Address Low register
- BDnADRH: BD Address High register

BDs always occur as a four-byte block in the sequence, BDnSTAT:BDnCNT:BDnADRL:BDnADRH. The address of BDnSTAT is always an offset of (4n - 1) (in hexadecimal) from 400h, with n being the buffer descriptor number.

Depending on the buffering configuration used (Section 21.4.4 "Ping-Pong Buffering"), there are up to 32, 33 or 64 sets of buffer descriptors. At a minimum, the BDT must be at least 8 bytes long. This is because the USB specification mandates that every device must have Endpoint '0' with both input and output for initial setup. Depending on the endpoint and buffering configuration, the BDT can be as long as 256 bytes.


Although they can be thought of as Special Function Registers, the Buffer Descriptor Status and Address registers are not hardware mapped, as conventional microcontroller SFRs in Bank 15 are. If the endpoint corresponding to a particular BD is not enabled, its registers are not used. Instead of appearing as unimplemented addresses, however, they appear as available RAM. Only when an endpoint is enabled by setting the UEPn<1> bit does the memory at those addresses become functional as BD registers. As with any address in the data memory space, the BD registers have an indeterminate value on any device Reset.

Figure 21-5 provides an example of a BD for a 64-byte buffer, starting at 500h. A particular set of BD registers is only valid if the corresponding endpoint has been enabled using the UEPn register. All BD registers are available in USB RAM. The BD for each endpoint should be set up prior to enabling the endpoint.

# 21.4.1 BD STATUS AND CONFIGURATION

Buffer descriptors not only define the size of an endpoint buffer, but also determine its configuration and control. Most of the configuration is done with the BD Status register, BDnSTAT. Each BD has its own unique and correspondingly numbered BDnSTAT register.

### FIGURE 21-5: EXAMPLE OF A BUFFER DESCRIPTOR



Unlike other control registers, the bit configuration for the BDnSTAT register is context sensitive. There are two distinct configurations, depending on whether the microcontroller or the USB module is modifying the BD and buffer at a particular time. Only three bit definitions are shared between the two.

## 21.4.1.1 Buffer Ownership

Because the buffers and their BDs are shared between the CPU and the USB module, a simple semaphore mechanism is used to distinguish which is allowed to update the BD and associated buffers in memory.

This is done by using the UOWN bit (BDnSTAT<7>) as a semaphore to distinguish which is allowed to update the BD and associated buffers in memory. UOWN is the only bit that is shared between the two configurations of BDnSTAT.

When UOWN is clear, the BD entry is "owned" by the microcontroller core. When the UOWN bit is set, the BD entry and the buffer memory are "owned" by the USB peripheral. The core should not modify the BD or its corresponding data buffer during this time. Note that the microcontroller core can still read BDnSTAT while the SIE owns the buffer and vice versa.

The buffer descriptors have a different meaning based on the source of the register update. Prior to placing ownership with the USB peripheral, the user can configure the basic operation of the peripheral through the BDnSTAT bits. During this time, the byte count and buffer location registers can also be set.

When UOWN is set, the user can no longer depend on the values that were written to the BDs. From this point, the SIE updates the BDs as necessary, overwriting the original BD values. The BDnSTAT register is updated by the SIE with the token PID and the transfer count, BDnCNT, is updated. The BDnSTAT byte of the BDT should always be the last byte updated when preparing to arm an endpoint. The SIE will clear the UOWN bit when a transaction has completed.

No hardware mechanism exists to block access when the UOWN bit is set. Thus, unexpected behavior can occur if the microcontroller attempts to modify memory when the SIE owns it. Similarly, reading such memory may produce inaccurate data until the USB peripheral returns ownership to the microcontroller.

## 21.4.1.2 BDnSTAT Register (CPU Mode)

When UOWN = 0, the microcontroller core owns the BD. At this point, the other seven bits of the register take on control functions.

The Data Toggle Sync Enable bit, DTSEN (BDnSTAT<3>), controls data toggle parity checking. Setting DTSEN enables data toggle synchronization by the SIE. When enabled, it checks the data packet's parity against the value of DTS (BDnSTAT<6>). If a packet arrives with an incorrect synchronization, the data will essentially be ignored. It will not be written to the USB RAM and the USB transfer complete interrupt flag will not be set. The SIE will send an ACK token back to the host to Acknowledge receipt, however. The effects of the DTSEN bit on the SIE are summarized in Table 21-1.

The Buffer Stall bit, BSTALL (BDnSTAT<2>), provides support for control transfers, usually one-time stalls on Endpoint 0. It also provides support for the SET\_FEATURE/CLEAR\_FEATURE commands specified in Chapter 9 of the USB specification; typically, continuous STALLs to any endpoint other than the default control endpoint.

The BSTALL bit enables buffer stalls. Setting BSTALL causes the SIE to return a STALL token to the host if a received token would use the BD in that location. The EPSTALL bit in the corresponding UEPn control register is set and a STALL interrupt is generated when a STALL is issued to the host. The UOWN bit remains set and the BDs are not changed unless a SETUP token is received. In this case, the STALL condition is cleared and the ownership of the BD is returned to the microcontroller core.

The BD<9:8> bits (BDnSTAT<1:0>) store the two most significant digits of the SIE byte count; the lower 8 digits are stored in the corresponding BDnCNT register. See **Section 21.4.2 "BD Byte Count"** for more information.

OUT Packet	BDnSTAT	Settings	I	Device Response after Receiving Packet				
from Host	DTSEN	DTS	Handshake	UOWN	TRNIF	BDnSTAT and USTAT Status		
DATA0	1	0	ACK	0	1	Updated		
DATA1	1	0	ACK	1	0	Not Updated		
DATA0	1	1	ACK	1	0	Not Updated		
DATA1	1	1	ACK	0	1	Updated		
Either	0	Х	ACK	0	1	Updated		
Either, with error	х	Х	NAK	1	0	Not Updated		

# TABLE 21-1: EFFECT OF DTSEN BIT ON ODD/EVEN (DATA0/DATA1) PACKET RECEPTION

**Legend:** x = don't care

# PIC18F46J50 FAMILY

# REGISTER 21-5: BDnSTAT: BUFFER DESCRIPTOR n STATUS REGISTER (BD0STAT THROUGH BD63STAT), CPU MODE (BANKED 4xxh)

R/W-x	R/W-x	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x
UOWN <sup>(1)</sup>	DTS <sup>(2)</sup>	(3)	(3)	DTSEN	BSTALL	BC9	BC8
bit 7						•	bit C
Legend:							
R = Readable	bit	W = Writable b	it	•	mented bit, read	as '0'	
-n = Value at F	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown
		(4)					
bit 7	UOWN: USB	Own bit <sup>(1)</sup>					
		ocontroller core		D and its corres	ponding buffer		
bit 6	DTS: Data To	ggle Synchroniz	ation bit <sup>(2)</sup>				
	1 = Data 1 pa	acket					
	0 = Data 0 pa	acket					
bit 5-4	Unimplemen	ted: These bits	should alwa	ys be programr	ned to '0' <sup>(3)</sup>		
bit 3	DTSEN: Data	a Toggle Synchro	onization En	able bit			
	1 = Data tog	gle synchroniza	tion is enab	led; data packe	ets with incorrect	t Sync value v	will be ignore
	•	or a SETUP tran		•	even if the data	toggle bits do	not match
	0 = No data f	toggle synchron	zation is pe	rformed			
bit 2	BSTALL: Buf	fer Stall Enable	bit				
		all enabled; STA				that would use	e the BD in th
	•	ation (UOWN bi	t remains se	et, BD value is ι	inchanged)		
	0 = Buffer sta						
bit 1-0	,	te Count 9 and 8					
	•	nt bits represent T token. Togeth		•			en or receive
Note 1: This	s bit must be in	itialized by the u	ser to the d	esired value pri	or to enabling th	ne USB module	Э.

- **2:** This bit is ignored unless DTSEN = 1.
- **3:** If these bits are set, USB communication may not work. Hence, these bits should always be maintained as '0'.

## 21.4.1.3 BDnSTAT Register (SIE Mode)

When the BD and its buffer are owned by the SIE, most of the bits in BDnSTAT take on a different meaning. The configuration is shown in Register 21-6. Once UOWN is set, any data or control settings previously written there by the user will be overwritten with data from the SIE.

The BDnSTAT register is updated by the SIE with the token Packet Identifier (PID) which is stored in BDnSTAT<5:2>. The transfer count in the corresponding BDnCNT register is updated. Values that overflow the 8-bit register carry over to the two most significant digits of the count, stored in BDnSTAT<1:0>.

### 21.4.2 BD BYTE COUNT

The byte count represents the total number of bytes that will be transmitted during an IN transfer. After an IN transfer, the SIE will return the number of bytes sent to the host.

For an OUT transfer, the byte count represents the maximum number of bytes that can be received and stored in USB RAM. After an OUT transfer, the SIE will return the actual number of bytes received. If the number of bytes received exceeds the corresponding byte count, the data packet will be rejected and a NAK handshake will be generated. When this happens, the byte count will not be updated.

The 10-bit byte count is distributed over two registers. The lower 8 bits of the count reside in the BDnCNT register. The upper two bits reside in BDnSTAT<1:0>. This represents a valid byte range of 0 to 1023.

#### 21.4.3 BD ADDRESS VALIDATION

The BD Address register pair contains the starting RAM address location for the corresponding endpoint buffer. No mechanism is available in hardware to validate the BD address.

If the value of the BD address does not point to an address in the USB RAM, or if it points to an address within another endpoint's buffer, data is likely to be lost or overwritten. Similarly, overlapping a receive buffer (OUT endpoint) with a BD location in use can yield unexpected results. When developing USB applications, the user may want to consider the inclusion of software-based address validation in their code.

#### REGISTER 21-6: BDnSTAT: BUFFER DESCRIPTOR n STATUS REGISTER (BD0STAT THROUGH BD63STAT), SIE MODE (DATA RETURNED BY THE SIE TO THE MCU) (BANKED 4xxh)

R/W-x	r-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
UOWN	—	PID3	PID2	PID1	PID0	BC9	BC8
bit 7							bit 0

Legend:	r = Reserved		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	1 as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	UOWN: USB Own bit
	1 = The SIE owns the BD and its corresponding buffer

bit 6 **Reserved:** Not written by the SIE

bit 5-2 **PID<3:0>:** Packet Identifier bits

The received token PID value of the last transfer (IN, OUT or SETUP transactions only).

bit 1-0 BC<9:8>: Byte Count 9 and 8 bits These bits are updated by the SIE to reflect the actual number of bytes received on an OUT transfer and the actual number of bytes transmitted on an IN transfer.

## 21.4.4 PING-PONG BUFFERING

An endpoint is defined to have a ping-pong buffer when it has two sets of BD entries: one set for an Even transfer and one set for an Odd transfer. This allows the CPU to process one BD while the SIE is processing the other BD. Double-buffering BDs in this way allows for maximum throughput to/from the USB.

The USB module supports four modes of operation:

- · No ping-pong support
- Ping-pong buffer support for OUT Endpoint 0 only
- · Ping-pong buffer support for all endpoints
- Ping-pong buffer support for all other Endpoints except Endpoint 0


The ping-pong buffer settings are configured using the PPB<1:0> bits in the UCFG register.

The USB module keeps track of the Ping-Pong Pointer individually for each endpoint. All pointers are initially reset to the Even BD when the module is enabled. After the completion of a transaction (UOWN cleared by the SIE), the pointer is toggled to the Odd BD. After the completion of the next transaction, the pointer is toggled back to the Even BD and so on.

The Even/Odd status of the last transaction is stored in the PPBI bit of the USTAT register. The user can reset all Ping-Pong Pointers to Even using the PPBRST bit.

Figure 21-6 shows the four different modes of operation and how USB RAM is filled with the BDs.

BDs have a fixed relationship to a particular endpoint, depending on the buffering configuration. Table 21-2 provides the mapping of BDs to endpoints. This relationship also means that gaps may occur in the BDT if endpoints are not enabled contiguously. This theoretically means that the BDs for disabled endpoints could be used as buffer space. In practice, users should avoid using such spaces in the BDT unless a method of validating BD addresses is implemented.



### FIGURE 21-6: BUFFER DESCRIPTOR TABLE MAPPING FOR BUFFERING MODES

# TABLE 21-2:ASSIGNMENT OF BUFFER DESCRIPTORS FOR THE DIFFERENT<br/>BUFFERING MODES

1										
	BDs Assigned to Endpoint									
Endpoint	Moo (No Ping	de 0 g-Pong)	Mode 1 (Ping-Pong on EP0 OUT)		Moc (Ping-Pong		Mode 3 (Ping-Pong on all other EPs, except EP0)			
	Out	In	Out	In	Out	In	Out	In		
0	0	1	0 (E), 1 (O)	2	0 (E), 1 (O)	2 (E), 3 (O)	0	1		
1	2	3	3	4	4 (E), 5 (O)	6 (E), 7 (O)	2 (E), 3 (O)	4 (E), 5 (O)		
2	4	5	5	6	8 (E), 9 (O)	10 (E), 11 (O)	6 (E), 7 (O)	8 (E), 9 (O)		
3	6	7	7	8	12 (E), 13 (O)	14 (E), 15 (O)	10 (E), 11 (O)	12 (E), 13 (O)		
4	8	9	9	10	16 (E), 17 (O)	18 (E), 19 (O)	14 (E), 15 (O)	16 (E), 17 (O)		
5	10	11	11	12	20 (E), 21 (O)	22 (E), 23 (O)	18 (E), 19 (O)	20 (E), 21 (O)		
6	12	13	13	14	24 (E), 25 (O)	26 (E), 27 (O)	22 (E), 23 (O)	24 (E), 25 (O)		
7	14	15	15	16	28 (E), 29 (O)	30 (E), 31 (O)	26 (E), 27 (O)	28 (E), 29 (O)		
8	16	17	17	18	32 (E), 33 (O)	34 (E), 35 (O)	30 (E), 31 (O)	32 (E), 33 (O)		
9	18	19	19	20	36 (E), 37 (O)	38 (E), 39 (O)	34 (E), 35 (O)	36 (E), 37 (O)		
10	20	21	21	22	40 (E), 41 (O)	42 (E), 43 (O)	38 (E), 39 (O)	40 (E), 41 (O)		
11	22	23	23	24	44 (E), 45 (O)	46 (E), 47 (O)	42 (E), 43 (O)	44 (E), 45 (O)		
12	24	25	25	26	48 (E), 49 (O)	50 (E), 51 (O)	46 (E), 47 (O)	48 (E), 49 (O)		
13	26	27	27	28	52 (E), 53 (O)	54 (E), 55 (O)	50 (E), 51 (O)	52 (E), 53 (O)		
14	28	29	29	30	56 (E), 57 (O)	58 (E), 59 (O)	54 (E), 55 (O)	56 (E), 57 (O)		
15	30	31	31	32	60 (E), 61 (O)	62 (E), 63 (O)	58 (E), 59 (O)	60 (E), 61 (O)		

Legend: (E) = Even transaction buffer, (O) = Odd transaction buffer

TABLE 21-3: SUMMARY OF USB BUFFER DESCRIPTOR TABLE REGISTER
-------------------------------------------------------------

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0			
BDnSTAT <sup>(1)</sup>	UOWN	DTS <sup>(4)</sup>	PID3 <sup>(2)</sup>	PID2 <sup>(2)</sup>	PID1 <sup>(2)</sup> DTSEN <sup>(3)</sup>	PID0 <sup>(2)</sup> BSTALL <sup>(3)</sup>	BC9	BC8			
BDnCNT <sup>(1)</sup>		Byte Count									
BDnADRL <sup>(1)</sup>		Buffer Address Low									
BDnADRH <sup>(1)</sup>				Buffer Ad	dress High						

**Note 1:** For buffer descriptor registers, n may have a value of 0 to 63. For the sake of brevity, all 64 registers are shown as one generic prototype. All registers have indeterminate Reset values (xxxx xxxx).

2: Bits 5 through 2 of the BDnSTAT register are used by the SIE to return PID<3:0> values once the register is turned over to the SIE (UOWN bit is set). Once the registers have been under SIE control, the values written for DTSEN and BSTALL are no longer valid.


**3:** Prior to turning the buffer descriptor over to the SIE (UOWN bit is cleared), bits 5 through 2 of the BDnSTAT register are used to configure the DTSEN and BSTALL settings.

4: This bit is ignored unless DTSEN = 1.


# 21.5 USB Interrupts

The USB module can generate multiple interrupt conditions. To accommodate all of these interrupt sources, the module is provided with its own interrupt logic structure, similar to that of the microcontroller. USB interrupts are enabled with one set of control registers and trapped with a separate set of flag registers. All sources are funneled into a single USB interrupt request, USBIF (PIR2<4>), in the microcontroller's interrupt logic. Figure 21-7 provides the interrupt logic for the USB module. There are two layers of interrupt registers in the USB module. The top level consists of overall USB status interrupts; these are enabled and flagged in the UIE and UIR registers, respectively. The second level consists of USB error conditions, which are enabled and flagged in the UEIR and UEIE registers. An interrupt condition in any of these triggers a USB Error Interrupt Flag (UERRIF) in the top level.

Interrupts may be used to trap routine events in a USB transaction. Figure 21-8 provides some common events within a USB frame and their corresponding interrupts.



### FIGURE 21-8: EXAMPLE OF A USB TRANSACTION AND INTERRUPT EVENTS



## FIGURE 21-7: USB INTERRUPT LOGIC FUNNEL

## 21.5.1 USB INTERRUPT STATUS REGISTER (UIR)

The USB Interrupt Status register (Register 21-7) contains the flag bits for each of the USB status interrupt sources. Each of these sources has a corresponding interrupt enable bit in the UIE register. All of the USB status flags are ORed together to generate the USBIF interrupt flag for the microcontroller's interrupt funnel.

Once an interrupt bit has been set by the SIE, it must be cleared by software by writing a '0'. The flag bits can also be set in software, which can aid in firmware debugging. When the USB module is in the Low-Power Suspend mode (UCON<1> = 1), the SIE does not get clocked. When in this state, the SIE cannot process packets and, therefore, cannot detect new interrupt conditions other than the Activity Detect Interrupt, ACTVIF. The ACTVIF bit is typically used by USB firmware to detect when the microcontroller should bring the USB module out of the Low-Power Suspend mode (UCON<1> = 0).

## REGISTER 21-7: UIR: USB INTERRUPT STATUS REGISTER (ACCESS F62h)

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R/W-0
—	SOFIF	STALLIF	IDLEIF <sup>(1)</sup>	TRNIF <sup>(2)</sup>	ACTVIF <sup>(3)</sup>	UERRIF <sup>(4)</sup>	URSTIF
bit 7							bit 0

Legend:				
R = Read	able bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown
bit 7	Unimple	mented: Read as '0'		
bit 6	•	Start-Of-Frame Token Interru	ot bit	
	1 = A St	art-Of-Frame token received Start-Of-Frame token receive	by the SIE	
bit 5	STALLIF	: A STALL Handshake Inter	rupt bit	
		TALL handshake was sent by TALL handshake has not be		
bit 4	1 = Idle	Idle Detect Interrupt bit <sup>(1)</sup> condition detected (constant dle condition detected	Idle state of 3 ms or more)	
bit 3	TRNIF:	Fransaction Complete Interru	ıpt bit <sup>(2)</sup>	
			on is complete; read USTAT re on is not complete or no transa	gister for endpoint information action is pending
bit 2	ACTVIF:	Bus Activity Detect Interrup	t bit <sup>(3)</sup>	
		vity on the D+/D- lines was d activity detected on the D+/D		
bit 1	UERRIF	: USB Error Condition Interru	ıpt bit <sup>(4)</sup>	
		Inmasked error condition has Inmasked error condition ha		
bit 0	URSTIF	USB Reset Interrupt bit		
		d USB Reset occurred; 00h i JSB Reset has occurred	s loaded into UADDR register	
Note 1:			ay want to place the USB mod	•
2:	•		O to advance (valid only for IN	· · · ·
3: 4:	••	• •	g the detection of a UIDLE int	•
4:	Unity error cor	iuliuons enabled through the	UEIE register will set this bit.	This bit is a status bit only and

4: Only error conditions enabled through the UEIE register will set this bit. This bit is a status bit only and cannot be set or cleared by the user.

# 21.5.1.1 Bus Activity Detect Interrupt Bit (ACTVIF)

The ACTVIF bit cannot be cleared immediately after the USB module wakes up from Suspend or while the USB module is suspended. A few clock cycles are required to synchronize the internal hardware state machine before the ACTVIF bit can be cleared by firmware. Clearing the ACTVIF bit before the internal hardware is synchronized may not have an effect on the value of ACTVIF. Additionally, if the USB module uses the clock from the 96 MHz PLL source, then after clearing the SUSPND bit, the USB module may not be

## EXAMPLE 21-1: CLEARING ACTVIF BIT (UIR<2>)

#### Assembly:

```
BCF UCON, SUSPND
LOOP:
BTFSS UIR, ACTVIF
BRA DONE
BCF UIR, ACTVIF
BRA LOOP
DONE:
```

### C:

```
UCONbits.SUSPND = 0;
while (UIRbits.ACTVIF) { UIRbits.ACTVIF = 0; }
```

immediately operational while waiting for the 96 MHz PLL to lock. The application code should clear the ACTVIF flag as provided in Example 21-1.

Note: Only one ACTVIF interrupt is generated when resuming from the USB bus Idle condition. If user firmware clears the ACTVIF bit, the bit will not immediately become set again, even when there is continuous bus traffic. Bus traffic must cease long enough to generate another IDLEIF condition before another ACTVIF interrupt can be generated.

### 21.5.2 USB INTERRUPT ENABLE REGISTER (UIE)

The USB Interrupt Enable (UIE) register (Register 21-8) contains the enable bits for the USB status interrupt sources. Setting any of these bits will enable the respective interrupt source in the UIR register.

The values in this register only affect the propagation of an interrupt condition to the microcontroller's interrupt logic. The flag bits are still set by their interrupt conditions, allowing them to be polled and serviced without actually generating an interrupt.

### REGISTER 21-8: UIE: USB INTERRUPT ENABLE REGISTER (BANKED F36h)

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	SOFIE	STALLIE	IDLEIE	TRNIE	ACTVIE	UERRIE	URSTIE
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	Unimplemented: Read as '0'
bit 6	SOFIE: Start-Of-Frame Token Interrupt Enable bit
	<ul><li>1 = Start-Of-Frame token interrupt enabled</li><li>0 = Start-Of-Frame token interrupt disabled</li></ul>
bit 5	STALLIE: STALL Handshake Interrupt Enable bit
	<ul><li>1 = STALL interrupt enabled</li><li>0 = STALL interrupt disabled</li></ul>
bit 4	IDLEIE: Idle Detect Interrupt Enable bit
	<ul><li>1 = Idle detect interrupt enabled</li><li>0 = Idle detect interrupt disabled</li></ul>
bit 3	TRNIE: Transaction Complete Interrupt Enable bit
	<ul><li>1 = Transaction interrupt enabled</li><li>0 = Transaction interrupt disabled</li></ul>
bit 2	ACTVIE: Bus Activity Detect Interrupt Enable bit
	<ul><li>1 = Bus activity detect interrupt enabled</li><li>0 = Bus activity detect interrupt disabled</li></ul>
bit 1	UERRIE: USB Error Interrupt Enable bit
	<ul><li>1 = USB error interrupt enabled</li><li>0 = USB error interrupt disabled</li></ul>
bit 0	URSTIE: USB Reset Interrupt Enable bit
	<ul><li>1 = USB Reset interrupt enabled</li><li>0 = USB Reset interrupt disabled</li></ul>

### 21.5.3 USB ERROR INTERRUPT STATUS REGISTER (UEIR)

The USB Error Interrupt Status register (Register 21-9) contains the flag bits for each of the error sources within the USB peripheral. Each of these sources is controlled by a corresponding interrupt enable bit in the UEIE register. All of the USB error flags are ORed together to generate the USB Error Interrupt Flag (UERRIF) at the top level of the interrupt logic.

Each error bit is set as soon as the error condition is detected. Thus, the interrupt will typically not correspond with the end of a token being processed.

Once an interrupt bit has been set by the SIE, it must be cleared by software by writing a '0'.

## REGISTER 21-9: UEIR: USB ERROR INTERRUPT STATUS REGISTER (ACCESS F63h)

R/C-0	U-0	U-0	R/C-0	R/C-0	R/C-0	R/C-0	R/C-0	
BTSEF	—	—	BTOEF	DFN8EF	CRC16EF	CRC5EF	PIDEF	
bit 7							bit 0	
Legend:								
R = Readable	bit	C = Clearable	e bit	U = Unimpler	mented bit, read	l as '0'		
-n = Value at F	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	iown	
bit 7	BTSEF: Bit St	tuff Error Flag	bit					
		f error has bee	n detected					
	0 = No bit stu							
bit 6-5	Unimplemen	ted: Read as '	0'					
bit 4	BTOEF: Bus	Turnaround Tir	me-out Error F	-lag bit				
				d (more than 16	bit times of Idle	e from previous	EOP elapsed)	
		urnaround time						
bit 3		a Field Size Er	-					
		field was not a	•	•				
bit 2		field was an in	•	I OI Dytes				
DIL 2	1 = The CRC	RC16 Failure F	-lag bit					
	1 = The CRC 0 = The CRC							
bit 1		•	Flag bit					
	<ul> <li>CRC5EF: CRC5 Host Error Flag bit</li> <li>1 = The token packet was rejected due to a CRC5 error</li> </ul>							
	0 = The token packet was accepted							
bit 0	PIDEF: PID Check Failure Flag bit							
	1 = PID chec		-					
	0 = PID chec	k passed						

## 21.5.4 USB ERROR INTERRUPT ENABLE REGISTER (UEIE)

The USB Error Interrupt Enable register (Register 21-10) contains the enable bits for each of the USB error interrupt sources. Setting any of these bits will enable the respective error interrupt source in the UEIR register to propagate into the UERR bit at the top level of the interrupt logic.

As with the UIE register, the enable bits only affect the propagation of an interrupt condition to the microcontroller's interrupt logic. The flag bits are still set by their interrupt conditions, allowing them to be polled and serviced without actually generating an interrupt.

## REGISTER 21-10: UEIE: USB ERROR INTERRUPT ENABLE REGISTER (BANKED F37h)

R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
BTSEE	—	—	BTOEE	DFN8EE	CRC16EE	CRC5EE	PIDEE
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	<b>BTSEE:</b> Bit Stuff Error Interrupt Enable bit 1 = Bit stuff error interrupt enabled 0 = Bit stuff error interrupt disabled
bit 6-5	Unimplemented: Read as '0'
bit 4	BTOEE: Bus Turnaround Time-out Error Interrupt Enable bit
	<ul> <li>1 = Bus turnaround time-out error interrupt enabled</li> <li>0 = Bus turnaround time-out error interrupt disabled</li> </ul>
bit 3	DFN8EE: Data Field Size Error Interrupt Enable bit
	<ul><li>1 = Data field size error interrupt enabled</li><li>0 = Data field size error interrupt disabled</li></ul>
bit 2	CRC16EE: CRC16 Failure Interrupt Enable bit
	<ul><li>1 = CRC16 failure interrupt enabled</li><li>0 = CRC16 failure interrupt disabled</li></ul>
bit 1	CRC5EE: CRC5 Host Error Interrupt Enable bit
	<ul><li>1 = CRC5 host error interrupt enabled</li><li>0 = CRC5 host error interrupt disabled</li></ul>
bit 0	<b>PIDEE:</b> PID Check Failure Interrupt Enable bit 1 = PID check failure interrupt enabled 0 = PID check failure interrupt disabled

# 21.6 USB Power Modes

Many USB applications will likely have several different sets of power requirements and configuration. The most common power modes encountered are Bus Power Only, Self-Power Only and Dual Power with Self-Power Dominance. The most common cases are presented here. Also provided is a means of estimating the current consumption of the USB transceiver.

## 21.6.1 BUS POWER ONLY

In Bus Power Only mode, all power for the application is drawn from the USB (Figure 21-9). This is effectively the simplest power method for the device.


In order to meet the inrush current requirements of the USB 2.0 Specification, the total effective capacitance appearing across VBUs and ground must be no more than 10  $\mu$ F. If not, some kind of inrush timing is required. For more details, see Section 7.2.4 of the USB 2.0 Specification.

According to the USB 2.0 Specification, all USB devices must also support a Low-Power Suspend mode. In the USB Suspend mode, devices must consume no more than 2.5 mA from the 5V VBUS line of the USB cable.

The host signals the USB device to enter the Suspend mode by stopping all USB traffic to that device for more than 3 ms. This condition will cause the IDLEIF bit in the UIR register to become set.

During the USB Suspend mode, the D+ or D- pull-up resistor must remain active, which will consume some of the allowed suspend current: 2.5 mA budget.






## 21.6.2 SELF-POWER ONLY

In Self-Power Only mode, the USB application provides its own power, with very little power being pulled from the USB. See Figure 21-10 for an example.

Note that an attach indication is added to indicate when the USB has been connected and the host is actively powering VBUS. In order to meet compliance specifications, the USB module (and the D+ or D- pull-up resistor) should not be enabled until the host actively drives VBUS high. One of the 5.5V tolerant I/O pins may be used for this purpose.

The application should never source any current onto the 5V V  $_{\rm BUS}$  pin of the USB cable.






## 21.6.3 DUAL POWER WITH SELF-POWER DOMINANCE

Some applications may require a dual power option. This allows the application to use internal power primarily, but switch to power from the USB when no internal power is available. See Figure 21-11 for a simple Dual Power with Self-Power Dominance mode example, which automatically switches between Self-Power Only and USB Bus Power Only modes.

Dual power devices must also meet all of the special requirements for inrush current and Suspend mode current and must not enable the USB module until VBUS is driven high. See Section 21.6.1 "Bus Power Only" and Section 21.6.2 "Self-Power Only" for descriptions of those requirements. Additionally, dual power devices must never source current onto the 5V VBUS pin of the USB cable.

## FIGURE 21-11: DUAL POWER EXAMPLE



Note: Users should keep in mind the limits for devices drawing power from the USB. According to USB Specification 2.0, this cannot exceed 100 mA per low-power device or 500 mA per high-power device.

### 21.6.4 USB TRANSCEIVER CURRENT CONSUMPTION

The USB transceiver consumes a variable amount of current depending on the characteristic impedance of the USB cable, the length of the cable, the VUSB supply voltage and the actual data patterns moving across the USB cable. Longer cables have larger capacitances and consume more total energy when switching output states.

Data patterns that consist of "IN" traffic consume far more current than "OUT" traffic. IN traffic requires the  $PIC^{\textcircled{B}}$  MCU to drive the USB cable, whereas OUT traffic requires that the host drive the USB cable.

The data that is sent across the USB cable is NRZI encoded. In the NRZI encoding scheme, '0' bits cause a toggling of the output state of the transceiver (either from a "J" state to a "K" state, or vise versa). With the exception of the effects of bit stuffing, NRZI encoded '1'

bits do not cause the output state of the transceiver to change. Therefore, IN traffic consisting of data bits of value, '0', cause the most current consumption, as the transceiver must charge/discharge the USB cable in order to change states.

More details about NRZI encoding and bit stuffing can be found in the USB 2.0 Specification's Section 7.1, although knowledge of such details is not required to make USB applications using the PIC18F46J50 Family of microcontrollers. Among other things, the SIE handles bit stuffing/unstuffing, NRZI encoding/decoding and CRC generation/checking in hardware.

The total transceiver current consumption will be application-specific. However, to help estimate how much current actually may be required in full-speed applications, Equation 21-1 can be used.

See Equation 21-2 to know how this equation can be used for a theoretical application.

## EQUATION 21-1: ESTIMATING USB TRANSCEIVER CURRENT CONSUMPTION

IXCVR =	$(40 \text{ mA} \bullet \text{VUSB} \bullet \text{PZERO} \bullet \text{PIN} \bullet \text{LCABLE})$	⊥Ілптты
IACVR -	(3.3V • 5m)	+ IPULLUP

Legend: VUSB – Voltage applied to the VUSB pin in volts (should be 3.0V to 3.6V).

PZERO – Percentage (in decimal) of the IN traffic bits sent by the PIC® MCU that are a value of '0'.

PIN – Percentage (in decimal) of total bus bandwidth that is used for IN traffic.

LCABLE – Length (in meters) of the USB cable. The USB 2.0 Specification requires that full-speed applications use cables no longer than 5m.

IPULLUP – Current which the nominal, 1.5 k $\Omega$  pull-up resistor (when enabled) must supply to the USB cable. On the host or hub end of the USB cable, 15 k $\Omega$  nominal resistors (14.25 k $\Omega$  to 24.8 k $\Omega$ ) are present which pull both the D+ and D- lines to ground. During bus Idle conditions (such as between packets or during USB Suspend mode), this results in up to 218  $\mu$ A of quiescent current drawn at 3.3V.

IPULLUP is also dependant on bus traffic conditions and can be as high as 2.2 mA when the USB bandwidth is fully utilized (either IN or OUT traffic) for data that drives the lines to the "K" state most of the time.

## EQUATION 21-2: CALCULATING USB TRANSCEIVER CURRENT<sup>†</sup>

For this example, the following assumptions are made about the application:

- 3.3V will be applied to VUSB and VDD, with the core voltage regulator enabled.
- This is a full-speed application that uses one interrupt IN endpoint that can send one packet of 64 bytes every 1 ms, with no restrictions on the values of the bytes being sent. The application may or may not have additional traffic on OUT endpoints.
- A regular USB "B" or "mini-B" connector will be used on the application circuit board.

In this case, PZERO = 100% = 1, because there should be no restriction on the value of the data moving through the IN endpoint. All 64 kbps of data could potentially be bytes of value, 00h. Since '0' bits cause toggling of the output state of the transceiver, they cause the USB transceiver to consume extra current charging/discharging the cable. In this case, 100% of the data bits sent can be of value '0'. This should be considered the "max" value, as normal data will consist of a fair mix of ones and zeros.

This application uses 64 kbps for IN traffic out of the total bus bandwidth of 1.5 Mbps (12 Mbps), therefore:

Pin = 
$$\frac{64 \text{ kbps}}{1.5 \text{ Mbps}} = 4.3\% = 0.043$$

Since a regular "B" or "mini-B" connector is used in this application, the end user may plug in any type of cable up to the maximum allowed 5m length. Therefore, we use the worst-case length:

LCABLE = 5 meters

Assume IPULLUP = 2.2 mA. The actual value of IPULLUP will likely be closer to 218  $\mu$ A, but allow for the worst-case. USB bandwidth is shared between all the devices which are plugged into the root port (via hubs). If the application is plugged into a USB 1.1 hub that has other devices plugged into it, your device may see host to device traffic on the bus, even if it is not addressed to your device. Since any traffic, regardless of source, can increase the IPULLUP current above the base 218  $\mu$ A, it is safest to allow for the worst-case of 2.2 mA.

Therefore:

IXCVR = 
$$\frac{(40 \text{ mA} \cdot 3.3\text{V} \cdot 1 \cdot 0.043 \cdot 5\text{m})}{(3.3\text{V} \cdot 5\text{m})} + 2.2 \text{ mA} = 3.9 \text{ mA}$$

† The calculated value should be considered an approximation and additional guardband or application-specific product testing is recommended. The transceiver current is "in addition to" the rest of the current consumed by the PIC18F46J50 Family device that is needed to run the core, drive the other I/O lines, power the various modules, etc.

## 21.7 Oscillator

The USB module has specific clock requirements. For full-speed operation, the clock source must be 48 MHz. Even so, the microcontroller core and other peripherals are not required to run at that clock speed. Available clocking options are described in detail in **Section 2.3 "Oscillator Settings for USB"**.

## 21.8 USB Firmware and Drivers

Microchip provides a number of application-specific resources, such as USB firmware and driver support. Refer to www.microchip.com for the latest firmware and driver support.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Details on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	65
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	65
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	65
UCON	—	PPBRST	SE0	PKTDIS	USBEN	RESUME	SUSPND	_	67
UCFG	UTEYE	UOEMON	_	UPUEN	UTRDIS	FSEN	PPB1	PPB0	68
USTAT	—	ENDP3	ENDP2	ENDP1	ENDP0	DIR	PPBI	—	67
UADDR	—	ADDR6	ADDR5	ADDR4	ADDR3	ADDR2	ADDR1	ADDR0	68
UFRML	FRM7	FRM6	FRM5	FRM4	FRM3	FRM2	FRM1	FRM0	67
UFRMH	—	—	_	_	—	FRM10	FRM9	FRM8	67
UIR	—	SOFIF	STALLIF	IDLEIF	TRNIF	ACTVIF	UERRIF	URSTIF	67
UIE	—	SOFIE	STALLIE	IDLEIE	TRNIE	ACTVIE	UERRIE	URSTIE	68
UEIR	BTSEF	—	_	BTOEF	DFN8EF	CRC16EF	CRC5EF	PIDEF	67
UEIE	BTSEE	—	_	BTOEE	DFN8EE	CRC16EE	CRC5EE	PIDEE	68
UEP0	_	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP1	_	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP2	—	_		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP3	—	_		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP4	_	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP5	—	_		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP6	_	_	-	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	69
UEP7	_	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP8	—	_		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP9	_	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP10	_	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP11	—	_		EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP12	—	—	—	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP13	—	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP14	—			EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68
UEP15	—	_	_	EPHSHK	EPCONDIS	EPOUTEN	EPINEN	EPSTALL	68

 $\label{eq:legend: Legend: Le$ 

**Note 1:** This table includes only those hardware mapped SFRs located in Bank 15 of the data memory space. The Buffer Descriptor registers, which are mapped into Bank 4 and are not true SFRs, are listed separately in Table 21-3.

# 21.9 Overview of USB

This section presents some of the basic USB concepts and useful information necessary to design a USB device. Although much information is provided in this section, there is a plethora of information provided within the USB specifications and class specifications. Thus, the reader is encouraged to refer to the USB specifications for more information (www.usb.org). If you are very familiar with the details of USB, then this section serves as a basic, high-level refresher of USB.

### 21.9.1 LAYERED FRAMEWORK

USB device functionality is structured into a layered framework graphically illustrated in Figure 21-12. Each level is associated with a functional level within the device. The highest layer, other than the device, is the configuration. A device may have multiple configurations. For example, a particular device may have multiple power requirements based on Self-Power Only or Bus Power Only modes.

For each configuration, there may be multiple interfaces. Each interface could support a particular mode of that configuration.

Below the interface is the endpoint(s). Data is directly moved at this level. There can be as many as 16 bidirectional endpoints. Endpoint 0 is always a control endpoint, and by default, when the device is on the bus, Endpoint 0 must be available to configure the device.

## 21.9.2 FRAMES

Information communicated on the bus is grouped into 1 ms time slots, referred to as frames. Each frame can contain many transactions to various devices and endpoints. See Figure 21-8 for an example of a transaction within a frame.

### 21.9.3 TRANSFERS


There are four transfer types defined in the USB specification.

- **Isochronous:** This type provides a transfer method for large amounts of data (up to 1023 bytes) with timely delivery ensured; however, the data integrity is not ensured. This is good for streaming applications where small data loss is not critical, such as audio.
- **Bulk:** This type of transfer method allows for large amounts of data to be transferred with ensured data integrity; however, the delivery timeliness is not ensured.
- Interrupt: This type of transfer provides for ensured timely delivery for small blocks of data, plus data integrity is ensured.
- **Control:** This type provides for device setup control.

While full-speed devices support all transfer types, low-speed devices are limited to interrupt and control transfers only.

#### 21.9.4 POWER

Power is available from the USB. The USB specification defines the bus power requirements. Devices may either be self-powered or bus-powered. Self-powered devices draw power from an external source, while bus-powered devices use power supplied from the bus.



## FIGURE 21-12: USB LAYERS

The USB specification limits the power taken from the bus. Each device is ensured 100 mA at approximately 5V (one unit load). Additional power may be requested, up to a maximum of 500 mA.

Note that power above one unit load is a request and the host or hub is not obligated to provide the extra current. Thus, a device capable of consuming more than one unit load must be able to maintain a low-power configuration of a one unit load or less, if necessary.

The USB specification also defines a Suspend mode. In this situation, current must be limited to 500  $\mu$ A, averaged over one second. A device must enter a suspend state after 3 ms of inactivity (i.e., no SOF tokens for 3 ms). A device entering Suspend mode must drop current consumption within 10 ms after suspend. Likewise, when signaling a wake-up, the device must signal a wake-up within 10 ms of drawing current above the suspend limit.

## 21.9.5 ENUMERATION

When the device is initially attached to the bus, the host enters an enumeration process in an attempt to identify the device. Essentially, the host interrogates the device, gathering information such as power consumption, data rates and sizes, protocol and other descriptive information; descriptors contain this information. A typical enumeration process would be as follows:

- 1. USB Reset Reset the device. Thus, the device is not configured and does not have an address (address 0).
- 2. Get Device Descriptor The host requests a small portion of the device descriptor.
- 3. USB Reset Reset the device again.
- 4. Set Address The host assigns an address to the device.
- 5. Get Device Descriptor The host retrieves the device descriptor, gathering info such as manufacturer, type of device, maximum control packet size.
- 6. Get configuration descriptors.
- 7. Get any other descriptors.
- 8. Set a configuration.

The exact enumeration process depends on the host.

## 21.9.6 DESCRIPTORS

There are eight different standard descriptor types, of which, five are most important for this device.

## 21.9.6.1 Device Descriptor

The device descriptor provides general information, such as manufacturer, product number, serial number, the class of the device and the number of configurations. There is only one device descriptor.

## 21.9.6.2 Configuration Descriptor

The configuration descriptor provides information on the power requirements of the device and how many different interfaces are supported when in this configuration. There may be more than one configuration for a device (i.e., low-power and high-power configurations).

### 21.9.6.3 Interface Descriptor

The interface descriptor details the number of endpoints used in this interface, as well as the class of the interface. There may be more than one interface for a configuration.

### 21.9.6.4 Endpoint Descriptor

The endpoint descriptor identifies the transfer type (**Section 21.9.3 "Transfers**") and direction, and some other specifics for the endpoint. There may be many endpoints in a device and endpoints may be shared in different configurations.

### 21.9.6.5 String Descriptor

Many of the previous descriptors reference one or more string descriptors. String descriptors provide human readable information about the layer (Section 21.9.1 "Layered Framework") they describe. Often these strings show up in the host to help the user identify the device. String descriptors are generally optional to save memory and are encoded in a unicode format.

## 21.9.7 BUS SPEED

Each USB device must indicate its bus presence and speed to the host. This is accomplished through a  $1.5 \text{ k}\Omega$  resistor, which is connected to the bus at the time of the attachment event.

Depending on the speed of the device, the resistor either pulls up the D+ or D- line to 3.3V. For a low-speed device, the pull-up resistor is connected to the D- line. For a full-speed device, the pull-up resistor is connected to the D+ line.

# 21.9.8 CLASS SPECIFICATIONS AND DRIVERS

USB specifications include class specifications, which operating system vendors optionally support. Examples of classes include Audio, Mass Storage, Communications and Human Interface (HID). In most cases, a driver is required at the host side to 'talk' to the USB device. In custom applications, a driver may need to be developed. Fortunately, drivers are available for most common host systems for the most common classes of devices. Thus, these drivers can be reused.

# PIC18F46J50 FAMILY

NOTES:

# 22.0 COMPARATOR MODULE

The analog comparator module contains two comparators that can be independently configured in a variety of ways. The inputs can be selected from the analog inputs and two internal voltage references. The digital outputs are available at the pin level and can also be read through the control register. Multiple output and interrupt event generation is also available. Figure 22-1 provides a generic single comparator from the module.

Key features of the module are:


- Independent comparator control
- Programmable input configuration
- Output to both pin and register levels
- · Programmable output polarity
- Independent interrupt generation for each comparator with configurable interrupt-on-change

# 22.1 Registers

The CMxCON registers (Register 22-1) select the input and output configuration for each comparator, as well as the settings for interrupt generation.

The CMSTAT register (Register 22-2) provides the output results of the comparators. The bits in this register are read-only.

## FIGURE 22-1: COMPARATOR SIMPLIFIED BLOCK DIAGRAM



# PIC18F46J50 FAMILY

R/W-0	R/W-0	R/W-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	
CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	
bit 7	•		•	•		·	bit	
Legend:	1		1.11			1		
	R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'							
-n = Value a	t POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkr	nown	
bit 7	CON: Compa	arator Enable b	it					
		tor is enabled tor is disabled						
bit 6	COE: Compa	arator Output E	nable bit					
		tor output is protor output is int		xOUT pin (assig	ned in the PF	'S module)		
bit 5	CPOL: Comp	parator Output	Polarity Select	bit				
		tor output is inv						
	•	tor output is no						
bit 4-3		: Interrupt Pola	,					
		t generation on	, ,	f the output(") w transition of t	ho output			
	•	•		gh transition of t	•			
		t generation is		<u></u>				
bit 2	CREF: Comp	arator Referen	ce Select bit (r	non-inverting inp	out)			
	1 = Non-inver	rting input conr	ects to interna	I CVREF voltage	•			
	0 = Non-inverting input connects to CxINA pin							
bit 1-0	CCH<1:0>: C	Comparator Cha	annel Select bi	ts				
		• .	•	cts to VIRV (0.6V	,			
	00 = Invertir	ng input of com	parator connec	ts to CxINB pin				
Note 1: ⊺	he CMxIF is aut	omatically set a	any time this m	ode is selected a	and must be c	leared by the ap	plication afte	

# REGISTER 22-1: CMxCON: COMPARATOR CONTROL x REGISTER (ACCESS FD2h, FD1h)

Note 1: The CMxIF is automatically set any time this mode is selected and must be cleared by the application after the initial configuration.

# PIC18F46J50 FAMILY

### REGISTER 22-2: CMSTAT: COMPARATOR STATUS REGISTER (ACCESS F70h)

U-0	U-0	U-0	U-0	U-0	U-0	R-1	R-1
—	—	—	—	—	—	COUT2	COUT1
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### bit 7-2 Unimplemented: Read as '0'

## bit 1-0 COUT<2:1>: Comparator x Status bits

#### If CPOL = 0 (non-inverted polarity):

1 = Comparator VIN+ > VIN-

0 = Comparator VIN+ < VIN-

If CPOL = 1 (inverted polarity):


1 = Comparator VIN+ < VIN-

0 = Comparator VIN+ > VIN-

# 22.2 Comparator Operation

A single comparator is shown in Figure 22-2, along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input, VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input, VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 22-2 represent the uncertainty due to input offsets and response time.

FIGURE 22-2: SINGLE COMPARATOR




## 22.3 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output has a valid level. The response time of the comparator differs from the settling time of the voltage reference. Therefore, both of these times must be considered when determining the total response to a comparator input change. Otherwise, the maximum delay of the comparators should be used (see **Section 29.0 "Electrical Characteristics"**).

# 22.4 Analog Input Connection Considerations

Figure 22-3 provides a simplified circuit for an analog input. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up condition may occur. A maximum source impedance of 10 k $\Omega$  is recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.





# 22.5 Comparator Control and Configuration

Each comparator has up to eight possible combinations of inputs: up to four external analog inputs, and one of two internal voltage references.

Both comparators allow a selection of the signal from pin, CxINA, or the voltage from the comparator reference (CVREF) on the non-inverting channel. This is compared to either CxINB, CTMU or the microcontroller's fixed internal reference voltage (VIRV, 0.6V nominal) on the inverting channel.

Table 22-1 provides the comparator inputs and outputs tied to fixed I/O pins.

Comparator	Input or Output	I/O Pin
	C1INA (VIN+)	RA0
1	C1INB (VIN-)	RA3
I I	C1OUT	Remapped RPn
	C2INA(VIN+)	RA1
2	C2INB(VIN-)	RA2
2	C2OUT	Remapped RPn

# TABLE 22-1: COMPARATOR INPUTS AND OUTPUTS

# 22.5.1 COMPARATOR ENABLE AND INPUT SELECTION

Setting the CON bit of the CMxCON register (CMxCON<7>) enables the comparator for operation. Clearing the CON bit disables the comparator, resulting in minimum current consumption.

The CCH<1:0> bits in the CMxCON register (CMxCON<1:0>) direct either one of three analog input pins, or the Internal Reference Voltage (VIRV), to the comparator VIN-. Depending on the comparator operating mode, either an external or internal voltage reference may be used. The analog signal present at VIN- is compared to the signal at VIN+ and the digital output of the comparator is adjusted accordingly.

The external reference is used when CREF = 0 (CMxCON<2>) and VIN+ is connected to the CxINA pin. When external voltage references are used, the comparator module can be configured to have the reference sources externally. The reference signal must be between VSS and VDD, and can be applied to either pin of the comparator.

The comparator module also allows the selection of an internally generated voltage reference (CVREF) from the comparator voltage reference module. This module is described in more detail in **Section 22.0 "Comparator Module"**. The reference from the comparator voltage reference module is only available when CREF = 1. In this mode, the internal voltage reference is applied to the comparator's VIN+ pin.

Note:	The comparator input pin selected by
	CCH<1:0> must be configured as an input
	by setting both the corresponding TRIS and
	PCFG bits in the ANCON1 register.

# 22.5.2 COMPARATOR ENABLE AND OUTPUT SELECTION

The comparator outputs are read through the CMSTAT register. The CMSTAT<0> reads the Comparator 1 output and CMSTAT<1> reads the Comparator 2 output. These bits are read-only.

The comparator outputs may also be directly output to the RPn I/O pins by setting the COE bit (CMxCON<6>). When enabled, multiplexers in the output path of the pins switch to the output of the comparator.

By default, the comparator's output is at logic high whenever the voltage on VIN+ is greater than on VIN-. The polarity of the comparator outputs can be inverted using the CPOL bit (CMxCON<5>).

The uncertainty of each of the comparators is related to the input offset voltage and the response time given in the specifications, as discussed in **Section 22.2 "Comparator Operation"**.

# 22.6 Comparator Interrupts

The comparator interrupt flag is set whenever any of the following occurs:

- Low-to-high transition of the comparator output
- High-to-low transition of the comparator output
- Any change in the comparator output

The comparator interrupt selection is done by the EVPOL<1:0> bits in the CMxCON register (CMxCON<4:3>).

In order to provide maximum flexibility, the output of the comparator may be inverted using the CPOL bit in the CMxCON register (CMxCON<5>). This is functionally identical to reversing the inverting and non-inverting inputs of the comparator for a particular mode.

An interrupt is generated on the low-to-high or high-tolow transition of the comparator output. This mode of interrupt generation is dependent on EVPOL<1:0> in the CMxCON register. When EVPOL<1:0> = 01 or 10, the interrupt is generated on a low-to-high or high-tolow transition of the comparator output. Once the interrupt is generated, it is required to clear the interrupt flag by software. When EVPOL<1:0> = 11, the comparator interrupt flag is set whenever there is a change in the output value of either comparator. Software will need to maintain information about the status of the output bits, as read from CMSTAT<1:0>, to determine the actual change that occurred. The CMxIF bits (PIR2<6:5>) are the Comparator Interrupt Flags. The CMxIF bits must be reset by clearing them. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

Table 22-2 provides the interrupt generation corresponding to comparator input voltages and EVPOL bit settings.

Both the CMxIE bits (PIE2<6:5>) and the PEIE bit (INTCON<6>) must be set to enable the interrupt. In addition, the GIE bit (INTCON<7>) must also be set. If any of these bits are clear, the interrupt is not enabled, though the CMxIF bits will still be set if an interrupt condition occurs.

Figure 22-3 provides a simplified diagram of the interrupt section.

CPOL	EVPOL<1:0>	Comparator Input Change	COUTx Transition	Interrupt Generated	
	00	VIN+ > VIN-	Low-to-High	No	
	00	VIN+ < VIN-	High-to-Low	No	
	0.1	VIN+ > VIN-	IngeCOULX transitionGeneIN-Low-to-HighMIN-High-to-LowMIN-Low-to-HighMIN-High-to-LowMIN-Low-to-HighMIN-Low-to-HighMIN-High-to-LowMIN-High-to-LowMIN-High-to-LowMIN-High-to-LowMIN-High-to-LowMIN-High-to-LowMIN-Low-to-HighMIN-Low-to-HighMIN-Low-to-HighMIN-Low-to-HighM	Yes	
0	01	VIN+ < VIN-	High-to-Low	No	
0	1.0	VIN+ > VIN-	/IN- High-to-Low	No	
	10	VIN+ < VIN-		Yes	
	11	VIN+ > VIN-	Low-to-High	Yes	
	11	VIN+ < VIN-	High-to-Low	Yes	
	0.0	VIN+ > VIN-	High-to-Low	No	
	00	VIN+ < VIN-	Low-to-High	No	
	0.1	VIN+ > VIN-	High-to-Low	No	
1	01	VIN+ < VIN-	Low-to-High	Yes	
1	1.0	VIN+ > VIN-	High-to-Low	Yes	
	10	VIN+ < VIN-	Low-to-High	No	
	1 1	VIN+ > VIN-	High-to-Low	Yes	
	11	VIN+ < VIN-	Low-to-High	Yes	

# TABLE 22-2: COMPARATOR INTERRUPT GENERATION

# 22.7 Comparator Operation During Sleep

When a comparator is active and the device is placed in Sleep mode, the comparator remains active and the interrupt is functional if enabled. This interrupt will wake-up the device from Sleep mode when enabled. Each operational comparator will consume additional current. To minimize power consumption while in Sleep mode, turn off the comparators (CON = 0) before entering Sleep. If the device wakes up from Sleep, the contents of the CMxCON register are not affected.

# 22.8 Effects of a Reset

A device Reset forces the CMxCON registers to their Reset state. This forces both comparators and the voltage reference to the OFF state.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	63
PIR2	OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	65
PIE2	OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	65
IPR2	OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	65
CMxCON	CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	64
CVRCON <sup>(1)</sup>	CVREN	CVROE	CVRR	r	CVR3	CVR2	CVR1	CVR0	68
CMSTAT		_	_	_	_	_	COUT2	COUT1	67
ANCON0	PCFG7 <sup>(1)</sup>	PCFG6 <sup>(1)</sup>	PCFG5 <sup>(1)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	68
TRISA	TRISA7	TRISA6	TRISA5	_	TRISA3	TRISA2	TRISA1	TRISA0	66

 TABLE 22-3:
 REGISTERS ASSOCIATED WITH COMPARATOR MODULE

**Legend:** — = unimplemented, read as '0'. Shaded cells are not related to comparator operation.

**Note 1:** These bits and/or registers are not implemented on 28-pin devices.


# PIC18F46J50 FAMILY

NOTES:

# 23.0 COMPARATOR VOLTAGE REFERENCE MODULE

The comparator voltage reference is a 16-tap resistor ladder network that provides a selectable reference voltage. Although its primary purpose is to provide a reference for the analog comparators, it may also be used independently of them. Figure 23-1 provides a block diagram of the module. The resistor ladder is segmented to provide two ranges of CVREF values and has a power-down function to conserve power when the reference is not being used. The module's supply reference is provided by VDD/VSS.





## 23.1 Configuring the Comparator Voltage Reference

The comparator voltage reference module is controlled through the CVRCON register (Register 23-1). The comparator voltage reference provides two ranges of output voltage, each with 16 distinct levels. The range to be used is selected by the CVRR bit (CVRCON<5>). The primary difference between the ranges is the size of the steps selected by the CVREF Selection bits (CVR<3:0>), with one range offering finer resolution. The equations used to calculate the output of the comparator voltage reference are as follows:

#### EQUATION 23-1: CALCULATING OUTPUT OF THE COMPARATOR VOLTAGE REFERENCE

 $\frac{When CVRR = 1:}{CVREF = ((CVR<3:0>)/24) x (VDD)}$  $\frac{When CVRR = 0:}{CVREF = (VDD/4) + ((CVR<3:0>)/32) x (VDD)}$ 

The settling time of the comparator voltage reference must be considered when changing the CVREF output (see Table 29-3 in **Section 29.0 "Electrical Characteristics"**).

# REGISTER 23-1: CVRCON: COMPARATOR VOLTAGE REFERENCE CONTROL REGISTER (BANKED F53h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
CVREN	CVROE <sup>(1)</sup>	CVRR	r	CVR3	CVR2	CVR1	CVR0
bit 7						•	bit 0
Legend:		r = Reserved					
R = Readable	e bit	W = Writable I	oit	U = Unimplem	nented bit, read	d as '0'	
-n = Value at	POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkr	nown
bit 7 bit 6 bit 5	1 = CVREF ci 0 = CVREF ci CVROE: Com 1 = CVREF vc 0 = CVREF vc	•	n lown Dutput Enable lso output on t nected from th	bit <sup>(1)</sup> he RA2/AN2/Vr le RA2/AN2/Vri			
bit 5	1 = 0  to  0.66	7 Vdd, with Vda	0/24 step size		ige)		
bit 4	Reserved: Al	ways maintain	<b>as</b> '0'				
bit 3-0	When CVRR CVREF = ((CV When CVRR	<u>= 1:</u> /R<3:0>)/24) • (	(VDD)	ion bits ( $0 \le (C^{V})$	VR<3:0>) ≤ 15	)	

Note 1: CVROE overrides the TRIS bit setting.

## 23.2 Voltage Reference Accuracy/Error

The full range of voltage reference cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (see Figure 23-1) keep CVREF from approaching the reference source rails. The voltage reference is derived from the reference source; therefore, the CVREF output changes with fluctuations in that source. The accuracy of the voltage reference can be found in **Section 29.0 "Electrical Characteristics"**.

## 23.3 Connection Considerations

The voltage reference module operates independently of the comparator module. The output of the reference generator may be connected to the RA2 pin if the CVROE bit is set. Enabling the voltage reference output onto RA2 when it is configured as a digital input will increase current consumption. The RA2 pin can be used as a simple D/A output with limited drive capability. Due to the limited current drive capability, a buffer must be used on the voltage reference output for external connections to VREF. See Figure 23-2 for an example buffering technique.


# 23.4 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the CVRCON register are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

## 23.5 Effects of a Reset

A device Reset disables the voltage reference by clearing bit, CVREN (CVRCON<7>). This Reset also disconnects the reference from the RA2 pin by clearing bit, CVROE (CVRCON<6>) and selects the high-voltage range by clearing bit, CVRR (CVRCON<5>). The CVR value select bits are also cleared.





Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:
CVRCON	CVREN	CVROE	CVRR	r	CVR3	CVR2	CVR1	CVR0	68
CM1CON	CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	64
CM2CON	CON	COE	CPOL	EVPOL1	EVPOL0	CREF	CCH1	CCH0	64
TRISA	TRISA7	TRISA6	TRISA5	_	TRISA3	TRISA2	TRISA1	TRISA0	66
ANCON0	PCFG7 <sup>(1)</sup>	PCFG6 <sup>(1)</sup>	PCFG5 <sup>(1)</sup>	PCFG4	PCFG3	PCFG2	PCFG1	PCFG0	68
ANCON1	VBGEN	r		PCFG12	PCFG11	PCFG10	PCFG9	PCFG8	68

**Legend:** — = unimplemented, read as '0', r = reserved. Shaded cells are not used with the comparator voltage reference.

Note 1: These bits are only available on 44-pin devices.

# PIC18F46J50 FAMILY

NOTES:

# 24.0 HIGH/LOW VOLTAGE DETECT (HLVD)

The High/Low-Voltage Detect (HLVD) module can be used to monitor the absolute voltage on VDD or the HLVDIN pin. This is a programmable circuit that allows the user to specify both a device voltage trip point and the direction of change from that point.

If the module detects an excursion past the trip point in that direction, an interrupt flag is set. If the interrupt is enabled, the program execution will branch to the interrupt vector address and the software can then respond to the interrupt. The High/Low-Voltage Detect Control register (Register 24-1) completely controls the operation of the HLVD module. This allows the circuitry to be "turned off" by the user under software control, which minimizes the current consumption for the device.

Figure 24-1 provides a block diagram for the HLVD module.

## REGISTER 24-1: HLVDCON: HIGH/LOW-VOLTAGE DETECT CONTROL REGISTER (ACCESS F85h)

R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
VDIRMAG	BGVST	IRVST	HLVDEN	HLVDL3 <sup>(1)</sup>	HLVDL2 <sup>(1)</sup>	HLVDL1 <sup>(1)</sup>	HLVDL0 <sup>(1)</sup>
bit 7							bit 0
Legend:							
R = Readable	bit	W = Writable	bit	U = Unimpler	nented bit, read	l as '0'	
-n = Value at F	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unkr	nown
bit 7		oltage Directio	-				
					int (HLVDL<3:0 point (HLVDL<3		
bit 6			•	table Status Fla		,	
				ferences is stal			
	0 = Indicates	internal band g	gap voltage re	ference is not s	stable		
bit 5	IRVST: Intern	al Reference V	oltage Stable	Flag bit			
		Ų	0	U U	e interrupt flag		0 0
				not be enabled	ate the interrup	t hag at the spe	ecilieu voltage
bit 4	•	gh/Low-Voltage	•				
	1 = HLVD en	abled					
	0 = HLVD dis						
bit 3-0		: Voltage Deteo					
		÷ .	ut is used (inp	ut comes from	the HLVDIN pin	1)	
	1110 <b>= Maxir</b>	num setting					
	•						
	0000 <b>= Minim</b>	num setting					

Note 1: See Table 29-8 in Section 29.0 "Electrical Characteristics" for specifications.

The module is enabled by setting the HLVDEN bit. Each time the module is enabled, the circuitry requires some time to stabilize. The IRVST bit is a read-only bit that indicates when the circuit is stable. The module can generate an interrupt only after the circuit is stable and IRVST is set. The VDIRMAG bit determines the overall operation of the module. When VDIRMAG is cleared, the module monitors for drops in VDD below a predetermined set point. When the bit is set, the module monitors for rises in VDD above the set point.

# 24.1 Operation


When the HLVD module is enabled, a comparator uses an internally generated reference voltage as the set point. The set point is compared with the trip point, where each node in the resistor divider represents a trip point voltage. The "trip point" voltage is the voltage level at which the device detects a high or low-voltage event, depending on the configuration of the module.

When the supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal by setting the HLVDIF bit.

The trip point voltage is software programmable to any one of 16 values. The trip point is selected by programming the HLVDL<3:0> bits (HLVDCON<3:0>).

Additionally, the HLVD module allows the user to supply the trip voltage to the module from an external source. This mode is enabled when bits, HLVDL<3:0>, are set to '1111'. In this state, the comparator input is multiplexed from the external input pin, HLVDIN. This gives users flexibility because it allows them to configure the HLVD interrupt to occur at any voltage in the valid operating range.

## FIGURE 24-1: HLVD MODULE BLOCK DIAGRAM (WITH EXTERNAL INPUT)



# 24.2 HLVD Setup

To set up the HLVD module:

- 1. Disable the module by clearing the HLVDEN bit (HLVDCON<4>).
- 2. Write the value to the HLVDL<3:0> bits that selects the desired HLVD trip point.
- 3. Set the VDIRMAG bit to detect one of the following:
  - High voltage (VDIRMAG = 1)
  - Low voltage (VDIRMAG = 0)
- 4. Enable the HLVD module by setting the HLVDEN bit.
- Clear the HLVD Interrupt Flag, HLVDIF (PIR2<2>), which may have been set from a previous interrupt.
- If interrupts are desired, enable the HLVD interrupt by setting the HLVDIE and GIE/GIEH bits (PIE2<2> and INTCON<7>).

An interrupt will not be generated until the IRVST bit is set.

# 24.3 Current Consumption

When the module is enabled, the HLVD comparator and voltage divider are enabled and will consume static current. The total current consumption, when enabled, is specified in electrical specification parameter D022B ( $\Delta$ IHLVD) (Section 29.2 "DC Characteristics: Power-Down and Supply Current PIC18F46J50 Family (Industrial)").

Depending on the application, the HLVD module does not need to operate constantly. To decrease the current requirements, the HLVD circuitry may only need to be enabled for short periods where the voltage is checked. After doing the check, the HLVD module may be disabled.


## 24.4 HLVD Start-up Time


The internal reference voltage of the HLVD module, specified in electrical specification parameter D420(see Table 29-8 in **Section 29.0 "Electrical Characteristics"**), may be used by other internal circuitry, such as the Programmable Brown-out Reset (BOR).

If the HLVD or other circuits using the voltage reference are disabled to lower the device's current consumption, the reference voltage circuit will require time to become stable before a low or high-voltage condition can be reliably detected. This start-up time, TIRVST, is an interval that is independent of device clock speed. It is specified in electrical specification parameter 36 (Table 29-13).

The HLVD interrupt flag is not enabled until TIRVST has expired and a stable reference voltage is reached. For this reason, brief excursions beyond the set point may not be detected during this interval. Refer to Figure 24-2 or Figure 24-3.

# PIC18F46J50 FAMILY





## 24.5 Applications

In many applications, it is desirable to have the ability to detect a drop below, or rise above, a particular threshold. For example, the HLVD module could be enabled periodically to detect Universal Serial Bus (USB) attach or detach.


For general battery applications, Figure 24-4 provides a possible voltage curve.

Over time, the device voltage decreases. When the device voltage reaches voltage, VA, the HLVD logic generates an interrupt at time, TA. The interrupt could cause the execution of an ISR, which would allow the application to perform "housekeeping tasks" and perform a controlled shutdown before the device voltage exits the valid operating range at TB.

The HLVD, thus, would give the application a time window, represented by the difference between TA and TB, to safely exit.



TYPICAL HIGH/ LOW-VOLTAGE DETECT APPLICATION



## 24.6 Operation During Sleep

When enabled, the HLVD circuitry continues to operate during Sleep. If the device voltage crosses the trip point, the HLVDIF bit will be set and the device will wake-up from Sleep. Device execution will continue from the interrupt vector address if interrupts have been globally enabled.

## 24.7 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the HLVD module to be turned off.

Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
VDIRMAG	BGVST	IRVST	HLVDEN	HLVDL3	HLVDL2	HLVDL1	HLVDL0	66
GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	<b>INT0IF</b>	RBIF	63
OSCFIF	CM2IF	CM1IF	USBIF	BCL1IF	HLVDIF	TMR3IF	CCP2IF	65
OSCFIE	CM2IE	CM1IE	USBIE	BCL1IE	HLVDIE	TMR3IE	CCP2IE	65
OSCFIP	CM2IP	CM1IP	USBIP	BCL1IP	HLVDIP	TMR3IP	CCP2IP	65
	VDIRMAG GIE/GIEH OSCFIF OSCFIF OSCFIP	VDIRMAGBGVSTGIE/GIEHPEIE/GIELOSCFIFCM2IFOSCFIECM2IEOSCFIPCM2IP	VDIRMAGBGVSTIRVSTGIE/GIEHPEIE/GIELTMR0IEOSCFIFCM2IFCM1IFOSCFIECM2IECM1IEOSCFIPCM2IPCM1IP	VDIRMAGBGVSTIRVSTHLVDENGIE/GIEHPEIE/GIELTMR0IEINT0IEOSCFIFCM2IFCM1IFUSBIFOSCFIECM2IECM1IEUSBIEOSCFIPCM2IPCM1IPUSBIP	VDIRMAGBGVSTIRVSTHLVDENHLVDL3GIE/GIEHPEIE/GIELTMR0IEINT0IERBIEOSCFIFCM2IFCM1IFUSBIFBCL1IFOSCFIECM2IECM1IEUSBIEBCL1IEOSCFIPCM2IPCM1IPUSBIPBCL1IP	VDIRMAGBGVSTIRVSTHLVDENHLVDL3HLVDL2GIE/GIEHPEIE/GIELTMR0IEINT0IERBIETMR0IFOSCFIFCM2IFCM1IFUSBIFBCL1IFHLVDIFOSCFIECM2IECM1IEUSBIEBCL1IEHLVDIE	VDIRMAGBGVSTIRVSTHLVDENHLVDL3HLVDL2HLVDL1GIE/GIEHPEIE/GIELTMR0IEINT0IERBIETMR0IFINT0IFOSCFIFCM2IFCM1IFUSBIFBCL1IFHLVDIFTMR3IFOSCFIECM2IECM1IEUSBIEBCL1IEHLVDIETMR3IE	VDIRMAGBGVSTIRVSTHLVDENHLVDL3HLVDL2HLVDL1HLVDL0GIE/GIEHPEIE/GIELTMR0IEINT0IERBIETMR0IFINT0IFRBIFOSCFIFCM2IFCM1IFUSBIFBCL1IFHLVDIFTMR3IFCCP2IFOSCFIPCM2IPCM1IPUSBIFBCL1IEHLVDIETMR3IECCP2IFOSCFIPCM2IPCM1IPUSBIFBCL1IPHLVDIFTMR3IFCCP2IF

## TABLE 24-1: REGISTERS ASSOCIATED WITH HIGH/LOW-VOLTAGE DETECT MODULE

Legend: — = unimplemented, read as '0'. Shaded cells are unused by the HLVD module.

# 25.0 CHARGE TIME MEASUREMENT UNIT (CTMU)

The Charge Time Measurement Unit (CTMU) is a flexible analog module that provides accurate differential time measurement between pulse sources, as well as asynchronous pulse generation. By working with other on-chip analog modules, the CTMU can be used to precisely measure time, measure capacitance, measure relative changes in capacitance or generate output pulses with a specific time delay. The CTMU is ideal for interfacing with capacitive-based sensors.


The module includes the following key features:

- Up to 13 channels available for capacitive or time measurement input
- · On-chip precision current source
- Four-edge input trigger sources
- · Polarity control for each edge source

- Control of edge sequence
- · Control of response to edges
- · Time measurement resolution of 1 nanosecond
- High precision time measurement
- Time delay of external or internal signal asynchronous to system clock
- Accurate current source suitable for capacitive measurement

The CTMU works in conjunction with the A/D Converter to provide up to 13 channels for time or charge measurement, depending on the specific device and the number of A/D channels available. When configured for time delay, the CTMU is connected to one of the analog comparators. The level-sensitive input edge sources can be selected from four sources: two external inputs, Timer1 or Output Compare Module 1.

Figure 25-1 provides a block diagram of the CTMU.



### FIGURE 25-1: CTMU BLOCK DIAGRAM

# 25.1 CTMU Operation

The CTMU works by using a fixed current source to charge a circuit. The type of circuit depends on the type of measurement being made. In the case of charge measurement, the current is fixed, and the amount of time the current is applied to the circuit is fixed. The amount of voltage read by the A/D is then a measurement of the capacitance of the circuit. In the case of time measurement, the current, as well as the capacitance of the circuit, is fixed. In this case, the voltage read by the A/D is then representative of the amount of time elapsed from the time the current source starts and stops charging the circuit.

If the CTMU is being used as a time delay, both capacitance and current source are fixed, as well as the voltage supplied to the comparator circuit. The delay of a signal is determined by the amount of time it takes the voltage to charge to the comparator threshold voltage.

### 25.1.1 THEORY OF OPERATION

The operation of the CTMU is based on the equation for charge:

$$C = I \cdot \frac{dV}{dT}$$

More simply, the amount of charge measured in coulombs in a circuit is defined as current in amperes (*I*) multiplied by the amount of time in seconds that the current flows (*t*). Charge is also defined as the capacitance in farads (*C*) multiplied by the voltage of the circuit (V). It follows that:

$$I \cdot t = C \cdot V.$$

The CTMU module provides a constant, known current source. The A/D Converter is used to measure (V) in the equation, leaving two unknowns: capacitance (C) and time (t). The above equation can be used to calculate capacitance or time, by either the relationship using the known fixed capacitance of the circuit:

$$t = (C \cdot V)/I$$

or by:

$$C = (I \cdot t) / V$$

using a fixed time that the current source is applied to the circuit.

### 25.1.2 CURRENT SOURCE

At the heart of the CTMU is a precision current source, designed to provide a constant reference for measurements. The level of current is user-selectable across three ranges or a total of two orders of magnitude, with the ability to trim the output in  $\pm 2\%$  increments (nominal). The current range is selected by the IRNG<1:0> bits (CTMUICON<9:8>), with a value of '00' representing the lowest range.

Current trim is provided by the ITRIM<5:0> bits (CTMUICON<7:2>). These six bits allow trimming of the current source in steps of approximately 2% per step. Note that half of the range adjusts the current source positively and the other half reduces the current source. A value of '000000' is the neutral position (no change). A value of '100000' is the maximum negative adjustment (approximately -62%) and '011111' is the maximum positive adjustment (approximately +62%).

### 25.1.3 EDGE SELECTION AND CONTROL

CTMU measurements are controlled by edge events occurring on the module's two input channels. Each channel, referred to as Edge 1 and Edge 2, can be configured to receive input pulses from one of the edge input pins (CTEDG1 and CTEDG2), Timer1 or Output Compare Module 1. The input channels are levelsensitive, responding to the instantaneous level on the channel rather than a transition between levels. The inputs are selected using the EDG1SEL and EDG2SEL bit pairs (CTMUCONL<3:2 and 6:5>).

In addition to source, each channel can be configured for event polarity using the EDGE2POL and EDGE1POL bits (CTMUCONL<7,4>). The input channels can also be filtered for an edge event sequence (Edge 1 occurring before Edge 2) by setting the EDGSEQEN bit (CTMUCONH<2>).

## 25.1.4 EDGE STATUS

The CTMUCON register also contains two status bits: EDG2STAT and EDG1STAT (CTMUCONL<1:0>). Their primary function is to show if an edge response has occurred on the corresponding channel. The CTMU automatically sets a particular bit when an edge response is detected on its channel. The level-sensitive nature of the input channels also means that the status bits become set immediately if the channel's configuration is changed and is the same as the channel's current state.

The module uses the edge status bits to control the current source output to external analog modules (such as the A/D Converter). Current is only supplied to external modules when only one (but not both) of the status bits is set, and shuts current off when both bits are either set or cleared. This allows the CTMU to measure current only during the interval between edges. After both status bits are set, it is necessary to clear them before another measurement is taken. Both bits should be cleared simultaneously, if possible, to avoid re-enabling the CTMU current source.

In addition to being set by the CTMU hardware, the edge status bits can also be set by software. This is also the user's application to manually enable or disable the current source. Setting either one (but not both) of the bits enables the current source. Setting or clearing both bits at once disables the source.

### 25.1.5 INTERRUPTS

The CTMU sets its interrupt flag (PIR3<2>) whenever the current source is enabled, then disabled. An interrupt is generated only if the corresponding interrupt enable bit (PIE3<2>) is also set. If edge sequencing is not enabled (i.e., Edge 1 must occur before Edge 2), it is necessary to monitor the edge status bits and determine which edge occurred last and caused the interrupt.

## 25.2 CTMU Module Initialization

The following sequence is a general guideline used to initialize the CTMU module:

- 1. Select the current source range using the IRNG bits (CTMUICON<1:0>).
- 2. Adjust the current source trim using the ITRIM bits (CTMUICON<7:2>).
- 3. Configure the edge input sources for Edge 1 and Edge 2 by setting the EDG1SEL and EDG2SEL bits (CTMUCONL<3:2 and 6:5>).
- Configure the input polarities for the edge inputs using the EDG1POL and EDG2POL bits (CTMUCONL<4,7>). The default configuration is for negative edge polarity (high-to-low transitions).
- Enable edge sequencing using the EDGSEQEN bit (CTMUCONH<2>). By default, edge sequencing is disabled.
- 6. Select the operating mode (Measurement or Time Delay) with the TGEN bit. The default mode is Time/Capacitance Measurement.
- Discharge the connected circuit by setting the IDISSEN bit (CTMUCONH<1>); after waiting a sufficient time for the circuit to discharge, clear IDISSEN.
- 8. Disable the module by clearing the CTMUEN bit (CTMUCONH<7>).
- 9. Enable the module by setting the CTMUEN bit.
- 10. Clear the Edge Status bits: EDG2STAT and EDG1STAT (CTMUCONL<1:0>).
- 11. Enable both edge inputs by setting the EDGEN bit (CTMUCONH<3>).

Depending on the type of measurement or pulse generation being performed, one or more additional modules may also need to be initialized and configured with the CTMU module:

- Edge Source Generation: In addition to the external edge input pins, both Timer1 and the Output Compare/PWM1 module can be used as edge sources for the CTMU.
- Capacitance or Time Measurement: The CTMU module uses the A/D Converter to measure the voltage across a capacitor that is connected to one of the analog input channels.
- Pulse Generation: When generating system clock independent output pulses, the CTMU module uses Comparator 2 and the associated comparator voltage reference.

# 25.3 Calibrating the CTMU Module

The CTMU requires calibration for precise measurements of capacitance and time, as well as for accurate time delay. If the application only requires measurement of a relative change in capacitance or time, calibration is usually not necessary. An example of this type of application would include a capacitive touch switch, in which the touch circuit has a baseline capacitance, and the added capacitance of the human body changes the overall capacitance of a circuit.

If actual capacitance or time measurement is required, two hardware calibrations must take place: the current source needs calibration to set it to a precise current, and the circuit being measured needs calibration to measure and/or nullify all other capacitance other than that to be measured.

## 25.3.1 CURRENT SOURCE CALIBRATION


The current source on board the CTMU module has a range of  $\pm 60\%$  nominal for each of three current ranges. Therefore, for precise measurements, it is possible to measure and adjust this current source by placing a high precision resistor, RCAL, onto an unused analog channel. An example circuit is shown in Figure 25-2. The current source measurement is performed using the following steps:

- 1. Initialize the A/D Converter.
- 2. Initialize the CTMU.
- 3. Enable the current source by setting EDG1STAT (CTMUCONL<0>).
- 4. Issue settling time delay.
- 5. Perform A/D conversion.
- 6. Calculate the current source current using I = V/RCAL, where RCAL is a high precision resistance and *V* is measured by performing an A/D conversion.

The CTMU current source may be trimmed with the trim bits in CTMUICON using an iterative process to get an exact desired current. Alternatively, the nominal value without adjustment may be used; it may be stored by the software for use in all subsequent capacitive or time measurements.

To calculate the value for *RCAL*, the nominal current must be chosen, and then the resistance can be calculated. For example, if the A/D Converter reference voltage is 3.3V, use 70% of full scale, or 2.31V as the desired approximate voltage to be read by the A/D Converter. If the range of the CTMU current source is selected to be 0.55  $\mu$ A, the resistor value needed is calculated as *RCAL* = 2.31V/0.55  $\mu$ A, for a value of 4.2 M $\Omega$ . Similarly, if the current source is chosen to be 5.5  $\mu$ A, *RCAL* would be 420,000 $\Omega$ , and 42,000 $\Omega$  if the current source is set to 55  $\mu$ A.

### FIGURE 25-2: CTMU CURRENT SOURCE CALIBRATION CIRCUIT



A value of 70% of full-scale voltage is chosen to make sure that the A/D Converter was in a range that is well above the noise floor. Keep in mind that if an exact current is chosen that is to incorporate the trimming bits from CTMUICON, the resistor value of RCAL may need to be adjusted accordingly. RCAL may also be adjusted to allow for available resistor values. RCAL should be of the highest precision available, keeping in mind the amount of precision needed for the circuit that the CTMU will be used to measure. A recommended minimum would be 0.1% tolerance.

The following examples show one typical method for performing a CTMU current calibration. Example 25-1 demonstrates how to initialize the A/D Converter and the CTMU; this routine is typical for applications using both modules. Example 25-2 demonstrates one method for the actual calibration routine.

#### EXAMPLE 25-1: SETUP FOR CTMU CALIBRATION ROUTINES

```
#include "p18cxxx.h"
             /***********
void setup(void)
{ //CTMUCON - CTMU Control register
  CTMUCONH = 0 \times 00;
                          //make sure CTMU is disabled
  CTMUCONL = 0 \times 90;
  //CTMU continues to run when emulator is stopped,CTMU continues
  //to run in idle mode, Time Generation mode disabled, Edges are blocked
  //{\rm No} edge sequence order, Analog current source not grounded, trigger
  //output disabled, Edge2 polarity = positive level, Edge2 source =
  //source 0, Edge1 polarity = positive level, Edge1 source = source 0,
  //CTMUICON - CTMU Current Control Register
  CTMUICON = 0 \times 01;
                            //0.55uA, Nominal - No Adjustment
//Setup AD converter;
TRISA=0x04;
                             //set channel 2 as an input
  // Configured AN2 as an analog channel
  // ANCONO
  ANCONO = OXFB;
  // ANCON1
  ANCON1 = 0X1F;
  // ADCON1
  ADCON1bits.ADFM=1;
                         // Resulst format 1= Right justified
                          // Normal A/D conversion operation
  ADCON1bits.ADCAL=0;
                          // Acquition time 7 = 20TAD 2 = 4TAD 1=2TAD
  ADCON1bits.ACQT=1;
  ADCON1bits.ADCS=2;
                         // Clock conversion bits 6= FOSC/64 2=FOSC/32
  ANCON1bits.VBGEN=1;
                         // Turn on the Bandgap needed for Rev A0 parts
  // ADCON0
  ADCONObits.VCFG0 =0;
                         // Vref+ = AVdd
                          // Vref- = AVss
  ADCON0bits.VCFG1 =0;
                          // Select ADC channel
  ADCONObits.CHS=2;
  ADCON0bits.ADON=1;
                         // Turn on ADC
}
```

### EXAMPLE 25-2: CURRENT CALIBRATION ROUTINE

```
#include "p18cxxx.h"
#define COUNT 500
                                           //@ 8MHz = 125uS.
#define DELAY for(i=0;i<COUNT;i++)</pre>
#define RCAL .027
                                           //R value is 4200000 (4.2M)
                                           //scaled so that result is in
                                           //1/100th of uA
#define ADSCALE 1023
                                           //for unsigned conversion 10 sig bits
#define ADREF 3.3
                                           //Vdd connected to A/D Vr+
int main (void)
{
   int i;
   int j = 0; //index for loop
   unsigned int Vread = 0;
   double VTot = 0;
   float Vavg=0, Vcal=0, CTMUISrc = 0; //float values stored for calcs
//assume CTMU and A/D have been setup correctly
//see Example 25-1 for CTMU & A/D setup
setup();
CTMUCONHbits.CTMUEN = 1;
                                           //Enable the CTMU
CTMUCONLbits.EDG1STAT = 0;
                                           // Set Edge status bits to zero
CTMUCONLbits.EDG2STAT = 0;
   for(j=0;j<10;j++)</pre>
   {
       CTMUCONHbits.IDISSEN = 1;
                                         //drain charge on the circuit
       DELAY;
                                           //wait 125us
       CTMUCONHbits.IDISSEN = 0;
                                           //end drain of circuit
       CTMUCONLbits.EDG1STAT = 1;
                                           //Begin charging the circuit
                                           //using CTMU current source
       DELAY;
                                           //wait for 125us
       CTMUCONLbits.EDG1STAT = 0;
                                           //Stop charging circuit
       PIR1bits.ADIF = 0;
                                          //make sure A/D Int not set
       ADCON0bits.GO=1;
                                           //and begin A/D conv.
       while(!PIR1bits.ADIF);
                                          //Wait for A/D convert complete
                                           //Get the value from the A/D
       Vread = ADRES;
       PIR1bits.ADIF = 0;
                                           //Clear A/D Interrupt Flag
       VTot += Vread;
                                           //Add the reading to the total
   }
   Vavg = (float) (VTot/10.000);
                                          //Average of 10 readings
   Vcal = (float) (Vavg/ADSCALE*ADREF);
   CTMUISrc = Vcal/RCAL;
                                           //CTMUISrc is in 1/100ths of uA
```

### 25.3.2 CAPACITANCE CALIBRATION

There is a small amount of capacitance from the internal A/D Converter sample capacitor as well as stray capacitance from the circuit board traces and pads that affect the precision of capacitance measurements. A measurement of the stray capacitance can be taken by making sure the desired capacitance to be measured has been removed. The measurement is then performed using the following steps:

- 1. Initialize the A/D Converter and the CTMU.
- 2. Set EDG1STAT (= 1).
- 3. Wait for a fixed delay of time *t*.
- 4. Clear EDG1STAT.
- 5. Perform an A/D conversion.
- 6. Calculate the stray and A/D sample capacitances:

$$C_{\text{OFFSET}} = C_{\text{STRAY}} + C_{\text{AD}} = (I \cdot t) / V$$

where *I* is known from the current source measurement step, *t* is a fixed delay and *V* is measured by performing an A/D conversion.

This measured value is then stored and used for calculations of time measurement or subtracted for capacitance measurement. For calibration, it is expected that the capacitance of CSTRAY + CAD is approximately known. CAD is approximately 4 pF.

An iterative process may need to be used to adjust the time, t, that the circuit is charged to obtain a reasonable voltage reading from the A/D Converter. The value of t may be determined by setting COFFSET to a theoretical value, then solving for t. For example, if CSTRAY is theoretically calculated to be 11 pF, and V is expected to be 70% of VDD, or 2.31V, then t would be:

$$(4 \text{ pF} + 11 \text{ pF}) \cdot 2.31 \text{V}/0.55 \text{ }\mu\text{A}$$

or 63 µs.

See Example 25-3 for a typical routine for CTMU capacitance calibration.

#### EXAMPLE 25-3: CAPACITANCE CALIBRATION ROUTINE

```
#include "p18cxxx.h"
#define COUNT 25
                                            //@ 8MHz INTFRC = 62.5 us.
#define ETIME COUNT*2.5
                                            //time in uS
#define DELAY for(i=0;i<COUNT;i++)</pre>
#define ADSCALE 1023
                                            //for unsigned conversion 10 sig
bits
#define ADREF 3.3
                                            //Vdd connected to A/D Vr+
#define RCAL .027
                                            //R value is 4200000 (4.2M)
                                            //scaled so that result is in
                                            //1/100th of uA
int main (void)
{
   int i;
   int j = 0;
                                             //index for loop
   unsigned int Vread = 0;
   float CTMUISrc, CTMUCap, Vavg, VTot, Vcal;
//assume CTMU and A/D have been setup correctly
//see Example 25-1 for CTMU & A/D setup
setup();
CTMUCONHbits.CTMUEN = 1;
                                           // Enable the CTMU
CTMUCONLbits.EDG1STAT = 0;
                                           // Set Edge status bits to zero
CTMUCONLbits.EDG2STAT = 0;
   for(j=0;j<10;j++)</pre>
   {
       CTMUCONHbits.IDISSEN = 1;
                                           //drain charge on the circuit
       DELAY;
                                            //wait 125us
       CTMUCONHbits.IDISSEN = 0;
                                            //end drain of circuit
       CTMUCONLbits.EDG1STAT = 1;
                                            //Begin charging the circuit
                                            //using CTMU current source
       DELAY;
                                           //wait for 125us
       CTMUCONLbits.EDG1STAT = 0;
                                           //Stop charging circuit
       PIR1bits.ADIF = 0;
                                           //make sure A/D Int not set
                                           //and begin A/D conv.
       ADCON0bits.GO=1;
       while(!PIR1bits.ADIF);
                                           //Wait for A/D convert complete
       Vread = ADRES;
                                           //Get the value from the A/D
       PIR1bits.ADIF = 0;
                                           //Clear A/D Interrupt Flag
       VTot += Vread;
                                           //Add the reading to the total
    }
   Vavg = (float) (VTot/10.000);
                                           //Average of 10 readings
   Vcal = (float) (Vavg/ADSCALE*ADREF);
   CTMUISrc = Vcal/RCAL;
                                            //CTMUISrc is in 1/100ths of uA
   CTMUCap = (CTMUISrc*ETIME/Vcal)/100;
```

# 25.4 Measuring Capacitance with the CTMU

There are two separate methods of measuring capacitance with the CTMU. The first is the absolute method, in which the actual capacitance value is desired. The second is the relative method, in which the actual capacitance is not needed, rather an indication of a change in capacitance is required.

### 25.4.1 ABSOLUTE CAPACITANCE MEASUREMENT

For absolute capacitance measurements, both the current and capacitance calibration steps found in **Section 25.3 "Calibrating the CTMU Module"** should be followed. Capacitance measurements are then performed using the following steps:

- 1. Initialize the A/D Converter.
- 2. Initialize the CTMU.
- 3. Set EDG1STAT.
- 4. Wait for a fixed delay, *T*.
- 5. Clear EDG1STAT.
- 6. Perform an A/D conversion.
- 7. Calculate the total capacitance, CTOTAL = (I \* T)/V, where *I* is known from the current source measurement step (see **Section 25.3.1 "Current Source Calibration"**), *T* is a fixed delay and *V* is measured by performing an A/D conversion.
- 8. Subtract the stray and A/D capacitance (*C*OFFSET from **Section 25.3.2** "**Capacitance Calibration**") from *CTOTAL* to determine the measured capacitance.

### 25.4.2 RELATIVE CHARGE MEASUREMENT

An application may not require precise capacitance measurements. For example, when detecting a valid press of a capacitance-based switch, detecting a relative change of capacitance is of interest. In this type of application, when the switch is open (or not touched), the total capacitance is the capacitance of the combination of the board traces, the A/D Converter, etc. A larger voltage will be measured by the A/D Converter. When the switch is closed (or is touched), the total capacitance is larger due to the addition of the capacitance of the human body to the above listed capacitances, and a smaller voltage will be measured by the A/D Converter.

Detecting capacitance changes is easily accomplished with the CTMU using these steps:

- 1. Initialize the A/D Converter and the CTMU.
- 2. Set EDG1STAT.
- 3. Wait for a fixed delay.
- 4. Clear EDG1STAT.
- 5. Perform an A/D conversion.

The voltage measured by performing the A/D conversion is an indication of the relative capacitance. Note that in this case, no calibration of the current source or circuit capacitance measurement is needed. See Example 25-4 for a sample software routine for a capacitive touch switch.

### EXAMPLE 25-4: ROUTINE FOR CAPACITIVE TOUCH SWITCH

```
#include "p18cxxx.h"
#define COUNT 500
                                       //@ 8MHz = 125uS.
#define DELAY for(i=0;i<COUNT;i++)</pre>
#define OPENSW 1000
                                       //Un-pressed switch value
#define TRIP 300
                                       //Difference between pressed
                                       //and un-pressed switch
#define HYST 65
                                       //amount to change
                                       //from pressed to un-pressed
#define PRESSED 1
#define UNPRESSED 0
int main(void)
{
   unsigned int Vread;
                                       //storage for reading
   unsigned int switchState;
   int i;
   //assume CTMU and A/D have been setup correctly
   //see Example 25-1 for CTMU & A/D setup
   setup();
   CTMUCONLDITS.EDGISTAT = 0; // Enable the CTMU
                                       // Set Edge status bits to zero
   CTMUCONLbits.EDG2STAT = 0;
   CTMUCONHbits.IDISSEN = 1;
                                       //drain charge on the circuit
                                       //wait 125us
   DELAY:
   CTMUCONHbits.IDISSEN = 0;
                                       //end drain of circuit
   CTMUCONLbits.EDG1STAT = 1;
                                       //Begin charging the circuit
                                       //using CTMU current source
   DELAY;
                                       //wait for 125us
   CTMUCONLbits.EDG1STAT = 0;
                                       //Stop charging circuit
   PIR1bits.ADIF = 0;
                                       //make sure A/D Int not set
   ADCON0bits.GO=1;
                                       //and begin A/D conv.
   while(!PIR1bits.ADIF);
                                       //Wait for A/D convert complete
   Vread = ADRES;
                                       //Get the value from the A/D
   if(Vread < OPENSW - TRIP)
   {
       switchState = PRESSED;
   }
   else if (Vread > OPENSW - TRIP + HYST)
   {
       switchState = UNPRESSED;
   }
```


# 25.5 Measuring Time with the CTMU Module

Time can be precisely measured after the ratio (C/I) is measured from the current and capacitance calibration step by following these steps:

- 1. Initialize the A/D Converter and the CTMU.
- 2. Set EDG1STAT.
- 3. Set EDG2STAT.
- 4. Perform an A/D conversion.
- 5. Calculate the time between edges as T = (C/I) \* V, where *I* is calculated in the current calibration step (Section 25.3.1 "Current Source Calibration"), *C* is calculated in the capacitance calibration step (Section 25.3.2 "Capacitance Calibration") and *V* is measured by performing the A/D conversion.

It is assumed that the time measured is small enough that the capacitance, *C*OFFSET, provides a valid voltage to the A/D Converter. For the smallest time measurement, always set the A/D Channel Select register (AD1CHS) to an unused A/D channel; the corresponding pin for which is not connected to any circuit board trace. This minimizes added stray capacitance, keeping the total circuit capacitance close to that of the A/D Converter itself (4-5 pF). To measure longer time intervals, an external capacitor may be connected to an A/D channel and this channel selected when making a time measurement.

# FIGURE 25-3: TYPICAL CONNECTIONS AND INTERNAL CONFIGURATION FOR TIME MEASUREMENT



# 25.6 Creating a Delay with the CTMU Module

A unique feature on board the CTMU module is its ability to generate system clock independent output pulses based on an external capacitor value. This is accomplished using the internal comparator voltage reference module, Comparator 2 input pin and an external capacitor. The pulse is output onto the CTPLS pin. To enable this mode, set the TGEN bit.


See Figure 25-4 for an example circuit. *C*PULSE is chosen by the user to determine the output pulse width on CTPLS. The pulse width is calculated by T = (CPULSE/I) \* V, where *I* is known from the current source measurement step (Section 25.3.1 "Current Source Calibration") and *V* is the internal reference voltage (CVREF).

An example use of this feature is for interfacing with variable capacitive-based sensors, such as a humidity sensor. As the humidity varies, the pulse width output on CTPLS will vary. The CTPLS output pin can be connected to an input capture pin and the varying pulse width is measured to determine the humidity in the application.

Follow these steps to use this feature:

- 1. Initialize Comparator 2.
- 2. Initialize the comparator voltage reference.
- 3. Initialize the CTMU and enable time delay generation by setting the TGEN bit.
- 4. Set EDG1STAT.
- 5. When CPULSE charges to the value of the voltage reference trip point, an output pulse is generated on CTPLS.

# FIGURE 25-4: TYPICAL CONNECTIONS AND INTERNAL CONFIGURATION FOR PULSE DELAY GENERATION



### 25.7 Operation During Sleep/Idle Modes

#### 25.7.1 SLEEP MODE AND DEEP SLEEP MODES

When the device enters any Sleep mode, the CTMU module current source is always disabled. If the CTMU is performing an operation that depends on the current source when Sleep mode is invoked, the operation may not terminate correctly. Capacitance and time measurements may return erroneous values.

### 25.7.2 IDLE MODE

The behavior of the CTMU in Idle mode is determined by the CTMUSIDL bit (CTMUCONH<5>). If CTMUSIDL is cleared, the module will continue to operate in Idle mode. If CTMUSIDL is set, the module's current source is disabled when the device enters Idle mode. If the module is performing an operation when Idle mode is invoked, in this case, the results will be similar to those with Sleep mode.

# 25.8 Effects of a Reset on CTMU

Upon Reset, all registers of the CTMU are cleared. This leaves the CTMU module disabled, its current source is turned off and all configuration options return to their default settings. The module needs to be re-initialized following any Reset.

If the CTMU is in the process of taking a measurement at the time of Reset, the measurement will be lost. A partial charge may exist on the circuit that was being measured, and should be properly discharged before the CTMU makes subsequent attempts to make a measurement. The circuit is discharged by setting and then clearing the IDISSEN bit (CTMUCONH<1>) while the A/D Converter is connected to the appropriate channel.

### 25.9 Registers

There are three control registers for the CTMU:

- CTMUCONH
- CTMUCONL
- CTMUICON

The CTMUCONH and CTMUCONL registers (Register 25-1 and Register 25-2) contain control bits for configuring the CTMU module edge source selection, edge source polarity selection, edge sequencing, A/D trigger, analog circuit capacitor discharge and enables. The CTMUICON register (Register 25-3) has bits for selecting the current source range and current source trim.

### REGISTER 25-1: CTMUCONH: CTMU CONTROL REGISTER HIGH (ACCESS FB3h)

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0
CTMUEN	—	CTMUSIDL	TGEN	EDGEN	EDGSEQEN	IDISSEN	—
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	CTMUEN: CTMU Enable bit
	1 = Module is enabled
	0 = Module is disabled
bit 6	Unimplemented: Read as '0'
bit 5	CTMUSIDL: Stop in Idle Mode bit
	<ul><li>1 = Discontinue module operation when device enters Idle mode</li><li>0 = Continue module operation in Idle mode</li></ul>
bit 4	TGEN: Time Generation Enable bit
	1 = Enables edge delay generation
	0 = Disables edge delay generation
bit 3	EDGEN: Edge Enable bit
	1 = Edges are not blocked
	0 = Edges are blocked
bit 2	EDGSEQEN: Edge Sequence Enable bit
	1 = Edge 1 event must occur before Edge 2 event can occur
	0 = No edge sequence is needed
bit 1	IDISSEN: Analog Current Source Control bit
	1 = Analog current source output is grounded
	0 = Analog current source output is not grounded
bit 0	Reserved: Write as '0'

# REGISTER 25-2: CTMUCONL: CTMU CONTROL REGISTER LOW (ACCESS FB2h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x	R/W-x
EDG2POL	EDG2SEL1	EDG2SEL0	EDG1POL	EDG1SEL1	EDG1SEL0	EDG2STAT	EDG1STA
bit 7		•				•	bit
Legend:							
R = Readable		W = Writable	bit	•	nented bit, read		
-n = Value at	POR	'1' = Bit is set		'0' = Bit is clea	ared	x = Bit is unkr	nown
bit 7	EDG2POL: E	dge 2 Polarity	Select bit				
		rogrammed for rogrammed for					
bit 6-5	EDG2SEL<1:	0>: Edge 2 So	urce Select bit	s			
	11 = CTEDG <sup>2</sup> 10 = CTEDG <sup>2</sup>	•					
		Output Compar	e module				
	00 <b>= Timer1 r</b>	nodule					
bit 4	EDG1POL: E	dge 1 Polarity	Select bit				
	• •	rogrammed for rogrammed for		•			
bit 3-2	EDG1SEL<1:	0>: Edge 1 So	urce Select bit	S			
	11 = CTEDG	1 pin					
	10 = CTEDG2						
	01 = ECCP1 00 = Timer1 r	Output Compar nodule	e module				
bit 1		Edge 2 Status b	it				
		vent has occur					
	0 = Edge 2 e	vent has not oc	curred				
bit 0	EDG1STAT: E	Edge 1 Status b	it				
	U U	vent has occuri					
	0 = Edge 1 e	vent has not oc	curred				

### REGISTER 25-3: CTMUICON: CTMU CURRENT CONTROL REGISTER (ACCESS FB1h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
ITRIM5	ITRIM4	ITRIM3	ITRIM2	ITRIM1	ITRIM0	IRNG1	IRNG0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, rea	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-2	ITRIM<5:0>: Current Source Trim bits 011111 = Maximum positive change from nominal current 011110
	•
	000001 = Minimum positive change from nominal current 000000 = Nominal current output specified by IRNG<1:0> 111111 = Minimum negative change from nominal current
	•
	100010
	100001 = Maximum negative change from nominal current
bit 1-0	IRNG<1:0>: Current Source Range Select bits
	<ul> <li>11 = 100 × Base current</li> <li>10 = 10 × Base current</li> <li>01 = Base current level (0.55 μA nominal)</li> </ul>

00 = Current source disabled

TABLE 25-1: REGISTERS ASSOCIATED WITH CTMU MODULE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page:
CTMUCONH	CTMUEN	_	CTMUSIDL	TGEN	EDGEN	EDGSEQEN	IDISSEN	_	65
CTMUCONL	EDG2POL	EDG2SEL1	EDG2SEL0	EDG1POL	EDG1SEL1	EDG1SEL0	EDG2STAT	EDG1STAT	65
CTMUICON	ITRIM5	ITRIM4	ITRIM3	ITRIM2	ITRIM1	ITRIM0	IRNG1	IRNG0	65

Legend: — = unimplemented, read as '0'. Shaded cells are not used during ECCP operation.

# PIC18F46J50 FAMILY

NOTES:

# 26.0 SPECIAL FEATURES OF THE CPU

PIC18F46J50 Family devices include several features intended to maximize reliability and minimize cost through elimination of external components. These are:

- · Oscillator Selection
- Resets:
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
- Brown-out Reset (BOR)
- Interrupts
- Watchdog Timer (WDT)
- Fail-Safe Clock Monitor (FSCM)
- Two-Speed Start-up
- Code Protection
- In-Circuit Serial Programming (ICSP)

The oscillator can be configured for the application depending on frequency, power, accuracy and cost. All of the options are discussed in detail in **Section 2.0 "Oscillator Configurations"**.

A complete discussion of device Resets and interrupts is available in previous sections of this data sheet. In addition to their Power-up and Oscillator Start-up Timers provided for Resets, the PIC18F46J50 Family of devices has a configurable Watchdog Timer (WDT), which is controlled in software.

The inclusion of an internal RC oscillator also provides the additional benefits of a Fail-Safe Clock Monitor (FSCM) and Two-Speed Start-up. FSCM provides for background monitoring of the peripheral clock and automatic switchover in the event of its failure. Two-Speed Start-up enables code to be executed almost immediately on start-up, while the primary clock source completes its start-up delays.

All of these features are enabled and configured by setting the appropriate Configuration register bits.

## 26.1 Configuration Bits

The Configuration bits can be programmed to select various device configurations. The configuration data is stored in the last four words of Flash program memory; Figure 5-1 depicts this. The configuration data gets loaded into the volatile Configuration registers, CONFIG1L through CONFIG4H, which are readable and mapped to program memory starting at location 300000h.

Table 26-2 provides a complete list. A detailed explanation of the various bit functions is provided in Register 26-1 through Register 26-6.

### 26.1.1 CONSIDERATIONS FOR CONFIGURING THE PIC18F46J50 FAMILY DEVICES

Unlike some previous PIC18 microcontrollers, devices of the PIC18F46J50 Family do not use persistent memory registers to store configuration information. The Configuration registers, CONFIG1L through CONFIG4H, are implemented as volatile memory.

Immediately after power-up, or after a device Reset, the microcontroller hardware automatically loads the CONFIG1L through CONFIG4L registers with configuration data stored in nonvolatile Flash program memory. The last four words of Flash program memory, known as the Flash Configuration Words (FCW), are used to store the configuration data.

Table 26-1 provides the Flash program memory, which will be loaded into the corresponding Configuration register.

When creating applications for these devices, users should always specifically allocate the location of the FCW for configuration data. This is to make certain that program code is not stored in this address when the code is compiled.

The four Most Significant bits (MSb) of the FCW corresponding to CONFIG1H, CONFIG2H, CONFIG3H and CONFIG4H should always be programmed to '1111'. This makes these FCWs appear to be NOP instructions in the remote event that their locations are ever executed by accident.

The four MSbs of the CONFIG1H, CONFIG2H, CONFIG3H and CONFIG4H registers are not implemented, so writing '1's to their corresponding FCW has no effect on device operation.

To prevent inadvertent configuration changes during code execution, the Configuration registers, CONFIG1L through CONFIG4L, are loaded only once per power-up or Reset cycle. User's firmware can still change the configuration by using self-reprogramming to modify the contents of the FCW.

Modifying the FCW will not change the active contents being used in the CONFIG1L through CONFIG4H registers until after the device is reset.

# TABLE 26-1:MAPPING OF THE FLASH CONFIGURATION WORDS TO THE CONFIGURATION<br/>REGISTERS

Configuration Register (Volatile)	Configuration Register Address	Flash Configuration Byte Address
CONFIG1L	300000h	XXXF8h
CONFIG1H	300001h	XXXF9h
CONFIG2L	300002h	XXXFAh
CONFIG2H	300003h	XXXFBh
CONFIG3L	300004h	XXXFCh
CONFIG3H	300005h	XXXFDh
CONFIG4L	300006h	XXXFEh
CONFIG4H	300007h	XXXFFh

## TABLE 26-2: CONFIGURATION BITS AND DEVICE IDs

File	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Default/ Unprog. Value <sup>(1)</sup>
300000h	CONFIG1L	DEBUG	XINST	STVREN	_	PLLDIV2	PLLDIV1	PLLDIV0	WDTEN	111- 1111
300001h	CONFIG1H	(2)	(2)	(2)	(2)	_	CP0	CPDIV1	CPDIV0	1111 -111
300002h	CONFIG2L	IESO	FCMEN	-	LPT1OSC	T1DIG	FOSC2	FOSC1	FOSC0	11-1 1111
300003h	CONFIG2H	(2)	(2)	(2)	(2)	WDTPS3	WDTPS2	WDTPS1	WDTPS0	1111 1111
300004h	CONFIG3L	DSWDTPS3	DSWDTPS2	DSWDTPS1	DSWDTPS0	DSWDTEN	DSBOREN	RTCOSC	DSWDTOSC	1111 1111
300005h	CONFIG3H	(2)	(2)	(2)	(2)	MSSPMSK	_	_	IOL1WAY	1111 11
300006h	CONFIG4L	WPCFG	WPEND	WPFP5	WPFP4	WPFP3	WPFP2	WPFP1	WPFP0	1111 1111
300007h	CONFIG4H	(2)	(2)	(2)	(2)	_	_	_	WPDIS	11111
3FFFFEh	DEVID1	DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0	xxx0 0000 <b>(3)</b>
3FFFFFh	DEVID2	DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3	0100 00xx <b>(3)</b>

Legend: x = unknown, u = unchanged, - = unimplemented. Shaded cells are unimplemented, read as '0'.

**Note** 1: Values reflect the unprogrammed state as received from the factory and following Power-on Resets. In all other Reset states, the configuration bytes maintain their previously programmed states.

2: The value of these bits in program memory should always be programmed to '1'. This ensures that the location is executed as a NOP if it is accidentally executed.

3: See Register 26-9 and Register 26-10 for DEVID values. These registers are read-only and cannot be programmed by the user.

### REGISTER 26-1: CONFIG1L: CONFIGURATION REGISTER 1 LOW (BYTE ADDRESS 300000h)

R/WO-1	R/WO-1	R/WO-1	U-0	R/WO-1	R/WO-1	R/WO-1	R/WO-1
DEBUG	XINST	STVREN	—	PLLDIV2	PLLDIV1	PLLDIV0	WDTEN
bit 7							bit 0

Legend:				
R = Reada	able bit	WO = Write-Once bit	U = Unimplemented bit,	, read as '0'
-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown
bit 7	1 = Bacl	Background Debugger Enable (ground debugger disabled; RI (ground debugger enabled; RE	36 and RB7 configured as g	
bit 6	<b>XINST:</b> E 1 = Instr	extended Instruction Set Enable uction set extension and Index uction set extension and Index	e bit ed Addressing mode enable	ed
bit 5	•••••	: Stack Overflow/Underflow Re et on stack overflow/underflow		

0 = Reset on stack overflow/underflow disabled

bit 4 Unimplemented: Read as '0	4	Unimplemented: Read as '
---------------------------------	---	--------------------------

bit 3-1 PLLDIV<2:0>: Oscillator Selection bits

Divider must be selected to provide a 4 MHz input into the 96 MHz PLL.

- 111 = No divide oscillator used directly (4 MHz input)
- 110 = Oscillator divided by 2 (8 MHz input)
- 101 = Oscillator divided by 3 (12 MHz input)
- 100 = Oscillator divided by 4 (16 MHz input)
- 011 = Oscillator divided by 5 (20 MHz input)
- 010 = Oscillator divided by 6 (24 MHz input)
- 001 = Oscillator divided by 10 (40 MHz input)
- 000 = Oscillator divided by 12 (48 MHz input)
- bit 0 WDTEN: Watchdog Timer Enable bit
  - 1 = WDT enabled
  - 0 = WDT disabled (control is placed on SWDTEN bit)

# PIC18F46J50 FAMILY

# REGISTER 26-2: CONFIG1H: CONFIGURATION REGISTER 1 HIGH (BYTE ADDRESS 300001h)

U-1	U-1	U-1	U-1	U-0	R/WO-1	R/WO-1	R/WO-1
—	_	—	—	—	CP0	CPDIV1	CPDIV0
bit 7							bit 0

Legend:			
R = Readable bit	WO = Write-Once bit	U = Unimplemented bit,	read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-4	Unimplemented: Program the corresponding Flash Configuration bit to '1'
bit 3	Unimplemented: Maintain as '0'
bit 2	CP0: Code Protection bit
	<ul><li>1 = Program memory is not code-protected</li><li>0 = Program memory is code-protected</li></ul>
bit 1-0	CPDIV<1:0>: CPU System Clock Selection bits
	<ul> <li>11 = No CPU system clock divide</li> <li>10 = CPU system clock divided by 2</li> <li>01 = CPU system clock divided by 3</li> <li>00 = CPU system clock divided by 6</li> </ul>

# REGISTER 26-3: CONFIG2L: CONFIGURATION REGISTER 2 LOW (BYTE ADDRESS 300002h)

R/WO-1	R/WO-1	U-0	R/WO-1	R/WO-1	R/WO-1	R/WO-1	R/WO-1		
IESO	FCMEN	—	LPT1OSC	T1DIG	FOSC2	FOSC1	FOSC0		
bit 7							bit (		
Legend:									
R = Readable	e bit	WO = Write-	Once bit	U = Unimpler	nented bit, read	1 as '0'			
-n = Value at l	POR	'1' = Bit is se		'0' = Bit is cle		x = Bit is unkr	nown		
			•						
bit 7	IESO: Two-S	peed Start-up	(Internal/Extern	nal Oscillator S	witchover) Con	trol bit			
		ed Start-up ena	-		····, ···				
	0 = Two-Spee	ed Start-up dis	abled						
bit 6	FCMEN: Fail	-Safe Clock M	onitor Enable b	oit					
		Clock Monitor							
	0 = Fail-Safe	Clock Monitor	disabled						
bit 5	Unimplemented: Read as '0'								
bit 4	LPT1OSC: Low-Power Timer1 Oscillator Enable bit								
		0	ured for high-po ured for low-po		l				
bit 3	T1DIG: Seco	ndary Clock S	ource T1OSCE	N Enforcemer	nt bit				
	T1CON<	3> T1OSCEN	state	-	ted (OSCCON		regardless o		
	0 = Seconda	ry oscillator clo	ock source may	y not be select	ed unless T1C0	<b>DN&lt;3&gt; =</b> 1			
bit 2-0		Oscillator Sele							
			h PLL software	controlled, CL	KO on RA6				
		10 = EC oscillator with CLKO on RA6							
	101 = HSPLL oscillator with PLL software controlled 100 = HS oscillator								
			nal oscillator wi	th PLL softwar	e controlled, Cl	LKO on RA6, p	ort function o		
	010 = INTOS	SCPLL, interna	I oscillator with	PLL software	controlled, por	t function on R	A6 and RA7		
	001 = INTOS 000 = INTOS		· · · · ·	•	C) with CLKO				

# PIC18F46J50 FAMILY

# REGISTER 26-4: CONFIG2H: CONFIGURATION REGISTER 2 HIGH (BYTE ADDRESS 300003h)

U-1	U-1	U-1	U-1	R/WO-1	R/WO-1	R/WO-1	R/WO-1
—	—	—	—	WDTPS3	WDTPS2	WDTPS1	WDTPS0
bit 7							bit 0

Legend:			
R = Readable bit	WO = Write-Once bit	U = Unimplemented bit, re	ead as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-4 **Unimplemented:** Program the corresponding Flash Configuration bit to '1'

Unimplemented: Program the corresponding Flash Configu
WDTPS<3:0>: Watchdog Timer Postscale Select bits
1111 <b>= 1:32,768</b>
1110 <b>= 1:16,384</b>
1101 <b>= 1:8,192</b>
1100 <b>= 1:4,096</b>
1011 <b>= 1:2,048</b>
1010 <b>= 1:1,024</b>
1001 <b>= 1:512</b>
1000 <b>= 1:256</b>
0111 <b>= 1:128</b>
0110 <b>= 1:64</b>
0101 <b>= 1:32</b>
0100 <b>= 1:16</b>
0011 <b>= 1:8</b>
0010 <b>= 1:4</b>
0001 <b>= 1:2</b>
0000 <b>= 1:1</b>

# REGISTER 26-5: CONFIG3L: CONFIGURATION REGISTER 3 LOW (BYTE ADDRESS 300004h)

R/WO-1	R/WO-1	R/WO-1	R/WO-1	R/WO-1	R/WO-1	R/WO-1	R/WO-1
DSWDTPS3	<sup>(1)</sup> DSWDTPS2 <sup>(1</sup>	DSWDTPS1 <sup>(1)</sup>	DSWDTPS0 <sup>(1</sup>	DSWDTEN <sup>(1)</sup>	DSBOREN	RTCOSC	DSWDTOSC <sup>(1)</sup>
bit 7					•		bit (
Legend:							
R = Readable	e bit	WO = Write-Or	ce bit	U = Unimplem	ented bit, rea	ad as '0'	
-n = Value at	POR	'1' = Bit is set		'0' = Bit is clea	ired	x = Bit is ur	nknown
bit 7-4		0>: Deep Sleep					
		rescaler is 32. T		approximate ba	ase time unit	of 1 ms.	
		7,483,648 (25.7	• /				
		870,912 (6.4 day 217,728 (38.5 ho					
		54,432 (9.6 hour	,				
		8,608 (2.4 hours					
		7,152 (36 minute					
		288 (9 minutes)	,				
	1000 <b>= 1:131</b> ,	072 (135 second	s)				
		68 (34 seconds)					
		2 (8.5 seconds)					
		8 (2.1 seconds)					
	0100 = 1:512 0011 = 1:128						
	0010 = 1:32 (						
	0001 = 1:8 (8.	,					
	0000 = 1:2 (2.						
oit 3	<b>DSWDTEN:</b> D	eep Sleep Watcl	ndog Timer En	able bit <sup>(1)</sup>			
	1 = DSWDT e	nabled					
	0 = DSWDT d	sabled					
bit 2	DSBOREN: "F	" Device Deep S	leep BOR Ena	ble bit, "LF" De	vice VDD BO	R Enable bi	t
	For "F" Device	<u>s:</u>					
		ng BOR enabled					
		ng BOR circuit is	always disable	ed			
	For "LF" Devic						
		ng BOR circuit is	•				
		ng BOR circuit is	•	ed			
bit 1		CC Reference C					
		s T1OSC/T1CKI		lock			
		s INTRC as refe		(1)			
bit 0		DSWDT Referen		ct bit <sup>(1)</sup>			
		ses INTRC as re					
	0 = DSWDT u	ses T1OSC/T1C	KI as reference	e clock			

Note 1: Functions are not available on "LF" devices.

# PIC18F46J50 FAMILY

### REGISTER 26-6: CONFIG3H: CONFIGURATION REGISTER 3 HIGH (BYTE ADDRESS 300005h)

	 MSSPMSK		 IOL1WAY
	moor more		
bit 7			bit 0

Legend:			
R = Readable bit	WO = Write-Once bit	U = Unimplemented bit,	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-4	Unimplemented: Program the corresponding Flash Configuration bit to '1'
bit 3	MSSPMSK: MSSP 7-Bit Address Masking Mode Enable bit
	<ul> <li>1 = 7-Bit Address Masking mode enabled</li> <li>0 = 5-Bit Address Masking mode enabled</li> </ul>
bit 2-1	Unimplemented: Read as '0'
bit 0	IOL1WAY: IOLOCK One-Way Set Enable bit
	<ul> <li>1 = IOLOCK bit (PPSCON&lt;0&gt;) can be set once, provided the unlock sequence has been completed. Once set, the Peripheral Pin Select registers cannot be written to a second time.</li> <li>0 = IOLOCK bit (PPSCON&lt;0&gt;) can be set and cleared as needed, provided the unlock sequence has been completed</li> </ul>

### REGISTER 26-7: CONFIG4L: CONFIGURATION REGISTER 4 LOW (BYTE ADDRESS 300006h)

| R/WO-1 |
|--------|--------|--------|--------|--------|--------|--------|--------|
| WPCFG  | WPEND  | WPFP5  | WPFP4  | WPFP3  | WPFP2  | WPFP1  | WPFP0  |
| bit 7  |        |        |        |        |        |        | bit 0  |

Legend:					
R = Readable bit WO = Write-Once bit U = Unimplemented bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

bit 7	<ul> <li>WPCFG: Write/Erase Protect Configuration Region Select bit (valid when WPDIS = 0)</li> <li>1 = Configuration Words page is not erase/write-protected unless WPEND and WPFP&lt;5:0&gt; settings include the Configuration Words page<sup>(1)</sup></li> <li>0 = Configuration Words page is erase/write-protected, regardless of WPEND and WPFP&lt;5:0&gt;<sup>(1)</sup></li> </ul>
bit 6	WPEND: Write/Erase Protect Region Select bit (valid when WPDIS = 0)
	<ul> <li>1 = Flash pages WPFP&lt;5:0&gt; to (Configuration Words page) are write/erase protected</li> <li>0 = Flash pages 0 to WPFP&lt;5:0&gt; are erase/write-protected</li> </ul>
bit 5-0	WPFP<5:0>: Write/Erase Protect Page Start/End Location bits
	Used with WPEND bit to define which pages in Flash will be write/erase protected.
Note 1:	The "Configuration Words page" contains the FCWs and is the last page of implemented Flash memory on

**Note 1:** The "Configuration Words page" contains the FCWs and is the last page of implemented Flash memory on a given device. Each page consists of 1,024 bytes. For example, on a device with 64 Kbytes of Flash, the first page is 0 and the last page (Configuration Words page) is 63 (3Fh).

### REGISTER 26-8: CONFIG4H: CONFIGURATION REGISTER 4 HIGH (BYTE ADDRESS 300007h)

U-1	U-1	U-1	U-1	U-0	U-0	U-0	R/WO-1
—	—	—	_	_	—	—	WPDIS
bit 7							bit 0

Legend:			
R = Readable bit	WO = Write-Once bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7-4 Unimplemented: Program the corresponding Flash Configuration bit to '1'

bit 3-1 Unimplemented: Read as '0'

bit 0 WPDIS: Write-Protect Disable bit

- 1 = WPFP<5:0>, WPEND and WPCFG bits ignored; all Flash memory may be erased or written
- 0 = WPFP<5:0>, WPEND and WPCFG bits enabled; erase/write-protect active for the selected region(s)

# REGISTER 26-9: DEVID1: DEVICE ID REGISTER 1 FOR PIC18F46J50 FAMILY DEVICES (BYTE ADDRESS 3FFFFEh)

R	R	R	R	R	R	R	R
DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0
bit 7				•			bit 0

Legend:						
R = Readable bit	W = Writable bit	U = Unimplemented bit,	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

bit 7-5 **DEV<2:0>:** Device ID bits These bits are used with DEV<10:3> bits in Device ID Register 2 to identify the part number. See Register 26-10.

bit 4-0 **REV<4:0>:** Revision ID bits These bits are used to indicate the device revision.

# PIC18F46J50 FAMILY

# REGISTER 26-10: DEVID2: DEVICE ID REGISTER 2 FOR PIC18F46J50 FAMILY DEVICES (BYTE ADDRESS 3FFFFFh)

R	R	R	R	R	R	R	R
DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### bit 7-0 DEV<10:3>: Device ID bits

These bits are used with the DEV<2:0> bits in the Device ID Register 1 to identify the part number.

DEV<10:3> (DEVID2<7:0>)	DEV<2:0> (DEVID2<7:5>)	Device
0100 1100	101	PIC18F46J50
0100 1100	100	PIC18F45J50
0100 1100	011	PIC18F44J50
0100 1100	010	PIC18F26J50
0100 1100	001	PIC18F25J50
0100 1100	000	PIC18F24J50
0100 1101	011	PIC18LF46J50
0100 1101	010	PIC18LF45J50
0100 1101	001	PIC18LF44J50
0100 1101	000	PIC18LF26J50
0100 1100	111	PIC18LF25J50
0100 1100	110	PIC18LF24J50

### 26.2 Watchdog Timer (WDT)

PIC18F46J50 Family devices have both a conventional WDT circuit and a dedicated, Deep Sleep capable Watchdog Timer. When enabled, the conventional WDT operates in normal Run, Idle and Sleep modes. This data sheet section describes the conventional WDT circuit.

The dedicated, Deep Sleep capable WDT can only be enabled in Deep Sleep mode. This timer is described in Section 3.6.4 "Deep Sleep Watchdog Timer (DSWDT)".

The conventional WDT is driven by the INTRC oscillator. When the WDT is enabled, the clock source is also enabled. The nominal WDT period is 4 ms and has the same stability as the INTRC oscillator.

The 4 ms period of the WDT is multiplied by a 16-bit postscaler. Any output of the WDT postscaler is selected by a multiplexer, controlled by the WDTPS bits in Configuration Register 2H. Available periods range from about 4 ms to 135 seconds (2.25 minutes depending on voltage, temperature and WDT postscaler). The WDT and postscaler are cleared

#### FIGURE 26-1: WDT BLOCK DIAGRAM


whenever a SLEEP or CLRWDT instruction is executed, or a clock failure (primary or Timer1 oscillator) has occurred.

- Note 1: The CLRWDT and SLEEP instructions clear the WDT and postscaler counts when executed.
  - **2:** When a CLRWDT instruction is executed, the postscaler count will be cleared.

### 26.2.1 CONTROL REGISTER

The WDTCON register (Register 26-11) is a readable and writable register. The SWDTEN bit enables or disables WDT operation. This allows software to override the WDTEN Configuration bit and enable the WDT only if it has been disabled by the Configuration bit.

LVDSTAT is a read-only status bit that is continuously updated and provides information about the current level of VDDCORE. This bit is only valid when the on-chip voltage regulator is enabled.



# PIC18F46J50 FAMILY

R/W-1	R-x	R-x	U-0	R/W-0	R/W-0	R/W-0	R/W-0			
REGSLP	LVDSTAT <sup>(2)</sup>	ULPLVL		DS	ULPEN	ULPSINK	SWDTEN <sup>(1)</sup>			
bit 7							bit (			
<del></del>										
Legend:										
R = Readable		W = Writable b	It	•	nented bit, rea					
-n = Value at	POR	'1' = Bit is set		'0' = Bit is cle	ared	x = Bit is unk	nown			
bit 7	REGSL P. Vol	tage Regulator I	ow-Power (	Operation Enabl	e hit					
		egulator enters l		•		eep mode				
	•	egulator is active								
bit 6	LVDSTAT: Lo	w-Voltage Detec	t Status bit <sup>(2</sup>	2)						
		> 2.45V nomina	-							
	0 = VDDCORE	< 2.45V nomina	I							
bit 5		a Low-Power W	ake-up Outp	ut bit (not valid	unless ULPEN	= 1)				
	1 = Voltage on RA0 > ~0.5V 0 = Voltage on RA0 < ~0.5V									
bit 4	•	ted: Read as '0'								
bit 3	•			in conjunction w			a to dotorming			
DIL 3	Reset source)	ep Wake-up Sta j <sup>(2)</sup>	tus bit (used	In conjunction v	VIIN ROON, PC	IR and BOR bil	s to determine			
		exit from Reset exit from Reset								
bit 2	ULPEN: Ultra	Low-Power Wa	ke-up Modu	le Enable bit						
		-Power Wake-up			L bit indicates	comparator ou	tput			
L:1.4		-Power Wake-up			- 1-:4					
bit 1		tra Low-Power V	•							
		power wake-up		•	PEN = 1)					
bit 0	-	ftware Controlle			<sub>it</sub> (1)					
	1 = Watchdog		a materialog							
	0 = Watchdog									
Note 1: Th	nis bit has no eff	fect if the Config	uration bit. V	VDTEN, is enab	led.					
			· · · · · · · · · · · · · · · · · · ·	,	-					

### REGISTER 26-11: WDTCON: WATCHDOG TIMER CONTROL REGISTER (ACCESS FC0h)

2: Not available on devices where the on-chip voltage regulator is disabled ("LF" devices).

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on Page:		
RCON	IPEN	—	CM	RI	TO	PD	POR	BOR	64		
WDTCON	REGSLP	LVDSTAT	ULPLVL	_	DS	ULPEN	ULPSINK	SWDTEN	64		

### TABLE 26-3: SUMMARY OF WATCHDOG TIMER REGISTERS

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used by the Watchdog Timer.

## 26.3 On-Chip Voltage Regulator

- Note 1: The on-chip voltage regulator is only available in parts designated with an "F", such as PIC18F25J50. The on-chip regulator is disabled on devices with "LF" in their part number.
  - 2: The VDDCORE/VCAP pin must never be left floating. On "F" devices, it must be connected to a capacitor, of size CEFC, to ground. On "LF" devices, VDDCORE/VCAP must be connected to a power supply source between 2.0V and 2.7V.

The digital core logic of the PIC18F46J50 Family devices is designed on an advanced manufacturing process, which requires 2.0V to 2.7V. The digital core logic obtains power from the VDDCORE/VCAP power supply pin.

However, in many applications it may be inconvenient to run the I/O pins at the same core logic voltage, as it would restrict the ability of the device to interface with other, higher voltage devices, such as those run at a nominal 3.3V. Therefore, all PIC18F46J50 Family devices implement a dual power supply rail topology. The core logic obtains power from the VDDCORE/VCAP pin, while the general purpose I/O pins obtain power from the VDD pin of the microcontroller, which may be supplied with a voltage between 2.15V to 3.6V ("F" device) or 2.0V to 3.6V ("LF" device).

This dual supply topology allows the microcontroller to interface with standard 3.3V logic devices, while running the core logic at a lower voltage of nominally 2.5V.

In order to make the microcontroller more convenient to use, an integrated 2.5V low dropout, low quiescent current linear regulator has been integrated on the die inside PIC18F46J50 Family devices. This regulator is designed specifically to supply the core logic of the device. It allows PIC18F46J50 Family devices to effectively run from a single power supply rail, without the need for external regulators.

The on-chip voltage regulator is always enabled on "F" devices. The VDDCORE/VCAP pin serves simultaneously as the regulator output pin and the core logic supply power input pin. A capacitor should be connected to the VDDCORE/VCAP pin to ground and is necessary for regulator stability. For example connections for PIC18F and PIC18LF devices, see Figure 26-2.

On "LF" devices, the on-chip regulator is always disabled. This allows the device to save a small amount of quiescent current consumption, which may be

advantageous in some types of applications, such as those which will entirely be running at a nominal 2.5V. On "LF" devices, the VDDCORE/VCAP pin still serves as the core logic power supply input pin, and therefore, must be connected to a 2.0V to 2.7V supply rail at the application circuit board level. On these devices, the I/O pins may still optionally be supplied with a voltage between 2.0V to 3.6V, provided that VDD is always greater than, or equal to, VDDCORE/VCAP. For example connections for PIC18F and PIC18LF devices, see Figure 26-2.

Note: In parts designated with an "LF", such as PIC18LF46J50, VDDCORE must never exceed VDD.

The specifications for core voltage and capacitance are listed in Section 29.3 "DC Characteristics: PIC18F46J50 Family (Industrial)".

### 26.3.1 VOLTAGE REGULATOR TRACKING MODE AND LOW-VOLTAGE DETECTION

When it is enabled, the on-chip regulator provides a constant voltage of 2.5V nominal to the digital core logic. The regulator can provide this level from a VDD of about 2.5V, all the way up to the device's VDDMAX. It does not have the capability to boost VDD levels below 2.5V. When the VDD supply input voltage drops too low to regulate 2.5V, the regulator enters Tracking mode. In Tracking mode, the regulator output follows VDD, with a typical voltage drop of 100 mV or less.


The on-chip regulator includes a simple Low-Voltage Detect (LVD) circuit. This circuit is separate and independent of the High/Low-Voltage Detect (HLVD) module described in **Section 24.0** "**High/Low Voltage Detect (HLVD)**". The on-chip regulator LVD circuit continuously monitors the VDDCORE voltage level and updates the LVDSTAT bit in the WDTCON register. The LVD detect threshold is set slightly below the normal regulation set point of the on-chip regulator.

Application firmware may optionally poll the LVDSTAT bit to determine when it is safe to run at maximum rated frequency, so as not to inadvertently violate the voltage versus frequency requirements provided by Figure 29-1.

The VDDCORE monitoring LVD circuit is only active when the on-chip regulator is enabled. On "LF" devices, the analog-to-digital converter and the HLVD module can still be used to provide firmware with VDD and VDDCORE voltage level information.

# PIC18F46J50 FAMILY

# FIGURE 26-2: CONNECTIONS FOR THE ON-CHIP REGULATOR



## 26.3.2 ON-CHIP REGULATOR AND BOR

When the on-chip regulator is enabled, PIC18F46J50 Family devices also have a simple brown-out capability. If the voltage supplied to the regulator is inadequate to maintain a minimum output level; the regulator Reset circuitry will generate a <u>Brown</u>-out Reset (BOR). This event is captured by the BOR flag bit (RCON<0>).

The operation of the BOR is described in more detail in Section 4.4 "Brown-out Reset (BOR)" and Section 4.4.1 "Detecting BOR". The brown-out voltage levels are specific in Section 29.1 "DC Characteristics: Supply Voltage PIC18F46J50 Family (Industrial)".

# 26.3.3 POWER-UP REQUIREMENTS

The on-chip regulator is designed to meet the power-up requirements for the device. If the application does not use the regulator, then strict power-up conditions must be adhered to. While powering up, VDDCORE should not exceed VDD by 0.3 volts.

## 26.3.4 OPERATION IN SLEEP MODE

When enabled, the on-chip regulator always consumes a small incremental amount of current over IDD. This includes when the device is in Sleep mode, even though the core digital logic does not require much power. To provide additional savings in applications where power resources are critical, the regulator can be configured to automatically enter a lower quiescent draw Standby mode whenever the device goes into Sleep mode. This feature is controlled by the REGSLP bit (WDTCON<7>, Register 26-11). If this bit is set upon entry into Sleep mode, the regulator will transition into a lower power state. In this state, the regulator still provides a regulated output voltage necessary to maintain SRAM state information, but consumes less quiescent current.

Substantial Sleep mode power savings can be obtained by setting the REGSLP bit, but device wake-up time will increase in order to insure the regulator has enough time to stabilize.

## 26.4 Two-Speed Start-up

The Two-Speed Start-up feature helps to minimize the latency period, from oscillator start-up to code execution, by allowing the microcontroller to use the INTRC oscillator as a clock source until the primary clock source is available. It is enabled by setting the IESO Configuration bit.

Two-Speed Start-up should be enabled only if the primary oscillator mode is HS or HSPLL (Crystal-Based) modes. Since the EC and ECPLL modes do not require an Oscillator Start-up Timer (OST) delay, Two-Speed Start-up should be disabled. When enabled, Resets and wake-ups from Sleep mode cause the device to configure itself to run from the internal oscillator block as the clock source, following the time-out of the Power-up Timer after a Power-on Reset is enabled. This allows almost immediate code execution while the primary oscillator starts and the OST is running. Once the OST times out, the device automatically switches to PRI\_RUN mode.

In all other power-managed modes, Two-Speed Start-up is not used. The device will be clocked by the currently selected clock source until the primary clock source becomes available. The setting of the IESO bit is ignored.




FIGURE 26-3: TIMING TRANSITION FOR TWO-SPEED START-UP (INTRC TO HSPLL)

# 26.4.1 SPECIAL CONSIDERATIONS FOR USING TWO-SPEED START-UP

While using the INTRC oscillator in Two-Speed Start-up, the device still obeys the normal command sequences for entering power-managed modes, including serial SLEEP instructions (refer to **Section 3.1.4 "Multiple Sleep Commands"**). In practice, this means that user code can change the SCS<1:0> bit settings or issue SLEEP instructions before the OST times out. This would allow an application to briefly wake-up, perform routine "housekeeping" tasks and return to Sleep before the device starts to operate from the primary oscillator.


User code can also check if the primary clock source is currently providing the device clocking by checking the status of the OSTS bit (OSCCON<3>). If the bit is set, the primary oscillator is providing the clock. Otherwise, the internal oscillator block is providing the clock during wake-up from Reset or Sleep mode.

# 26.5 Fail-Safe Clock Monitor

The Fail-Safe Clock Monitor (FSCM) allows the microcontroller to continue operation in the event of an external oscillator failure by automatically switching the device clock to the internal oscillator block. The FSCM function is enabled by setting the FCMEN Configuration bit.

When FSCM is enabled, the INTRC oscillator runs at all times to monitor clocks to peripherals and provide a backup clock in the event of a clock failure. Clock monitoring (shown in Figure 26-4) is accomplished by creating a sample clock signal, which is the INTRC output divided by 64. This allows ample time between FSCM sample clocks for a peripheral clock edge to occur. The peripheral device clock and the sample clock are presented as inputs to the clock monitor latch. The clock monitor is set on the falling edge of the device clock source but cleared on the rising edge of the sample clock.

#### FIGURE 26-4: FSCM BLOCK DIAGRAM



Clock failure is tested for on the falling edge of the sample clock. If a sample clock falling edge occurs while the clock monitor is still set, and a clock failure has been detected (Figure 26-5), the following results:

- The FSCM generates an oscillator fail interrupt by setting bit, OSCFIF (PIR2<7>);
- The device clock source is switched to the internal oscillator block (OSCCON is not updated to show the current clock source this is the Fail-safe condition); and
- The WDT is reset.


During switchover, the postscaler frequency from the internal oscillator block may not be sufficiently stable for timing sensitive applications. In these cases, it may be desirable to select another clock configuration and enter an alternate power-managed mode. This can be done to attempt a partial recovery or execute a controlled shutdown. See Section 3.1.4 "Multiple Sleep Commands" and Section 26.4.1 "Special Considerations for Using Two-Speed Start-up" for more details.

The FSCM will detect failures of the primary or secondary clock sources only. If the internal oscillator block fails, no failure would be detected, nor would any action be possible.

### 26.5.1 FSCM AND THE WATCHDOG TIMER

Both the FSCM and the WDT are clocked by the INTRC oscillator. Since the WDT operates with a separate divider and counter, disabling the WDT has no effect on the operation of the INTRC oscillator when the FSCM is enabled.

As already noted, the clock source is switched to the INTRC clock when a clock failure is detected; this may mean a substantial change in the speed of code execution. If the WDT is enabled with a small prescale value, a decrease in clock speed allows a WDT time-out to occur and a subsequent device Reset. For this reason, Fail-Safe Clock Monitor events also reset the WDT and postscaler, allowing it to start timing from when execution speed was changed and decreasing the likelihood of an erroneous time-out.



### FIGURE 26-5: FSCM TIMING DIAGRAM

### 26.5.2 EXITING FAIL-SAFE OPERATION

The Fail-Safe Clock Monitor condition is terminated by either a device Reset or by entering a power-managed mode. On Reset, the controller starts the primary clock source specified in Configuration Register 2H (with any required start-up delays that are required for the oscillator mode, such as OST or PLL timer). The INTRC oscillator provides the device clock until the primary clock source becomes ready (similar to a Two-Speed Start-up). The clock source is then switched to the primary clock (indicated by the OSTS bit in the OSCCON register becoming set). The FSCM then resumes monitoring the peripheral clock.

The primary clock source may never become ready during start-up. In this case, operation is clocked by the INTRC oscillator. The OSCCON register will remain in its Reset state until a power-managed mode is entered.

### 26.5.3 FSCM INTERRUPTS IN POWER-MANAGED MODES

By entering a power-managed mode, the clock multiplexer selects the clock source selected by the OSCCON register. FSCM of the power-managed clock source resumes in the power-managed mode.

If an oscillator failure occurs during power-managed operation, the subsequent events depend on whether or not the oscillator failure interrupt is enabled. If enabled (OSCFIF = 1), code execution will be clocked by the INTRC multiplexer. An automatic transition back to the failed clock source will not occur.

If the interrupt is disabled, subsequent interrupts while in Idle mode will cause the CPU to begin executing instructions while being clocked by the INTRC source.

### 26.5.4 POR OR WAKE-UP FROM SLEEP

The FSCM is designed to detect oscillator failure at any point after the device has exited Power-on Reset (POR) or low-power Sleep mode. When the primary device clock is either the EC or INTRC modes, monitoring can begin immediately following these events.

For HS or HSPLL modes, the situation is somewhat different. Since the oscillator may require a start-up time considerably longer than the FSCM sample clock time, a false clock failure may be detected. To prevent this, the internal oscillator block is automatically configured as the device clock and functions until the primary clock is stable (the OST and PLL timers have timed out). This is identical to Two-Speed Start-up mode. Once the primary clock is stable, the INTRC returns to its role as the FSCM source.

Note: The same logic that prevents false oscillator failure interrupts on POR, or wake-up from Sleep, will also prevent the detection of the oscillator's failure to start at all following these events. This can be avoided by monitoring the OSTS bit and using a timing routine to determine if the oscillator is taking too long to start. Even so, no oscillator failure interrupt will be flagged.

As noted in Section 26.4.1 "Special Considerations for Using Two-Speed Start-up", it is also possible to select another clock configuration and enter an alternate power-managed mode while waiting for the primary clock to become stable. When the new power-managed mode is selected, the primary clock is disabled.

## 26.6 Program Verification and Code Protection

For all devices in the PIC18F46J50 Family of devices, the on-chip program memory space is treated as a single block. Code protection for this block is controlled by one Configuration bit, CP0. This bit inhibits external reads and writes to the program memory space. It has no direct effect in normal execution mode.

#### 26.6.1 CONFIGURATION REGISTER PROTECTION

The Configuration registers are protected against untoward changes or reads in two ways. The primary protection is the write-once feature of the Configuration bits, which prevents reconfiguration once the bit has been programmed during a power cycle. To safeguard against unpredictable events, Configuration bit changes resulting from individual cell level disruptions (such as ESD events) will cause a parity error and trigger a device Reset. This is seen by the user as a Configuration Mismatch (CM) Reset.

The data for the Configuration registers is derived from the FCW in program memory. When the CP0 bit is set, the source data for device configuration is also protected as a consequence.

# 26.7 In-Circuit Serial Programming (ICSP)

PIC18F46J50 Family microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data and three other lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

## 26.8 In-Circuit Debugger

When the  $\overline{\text{DEBUG}}$  Configuration bit is programmed to a '0', the In-Circuit Debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB<sup>®</sup> IDE. When the microcontroller has this feature enabled, some resources are not available for general use.

Table 26-4 lists the resources required by the background debugger.

	TABLE 26-4:	DEBUGGER RESOURCES
--	-------------	--------------------

I/O pins:	RB6, RB7
Stack:	2 levels
Program Memory:	512 bytes
Data Memory:	10 bytes

# 27.0 INSTRUCTION SET SUMMARY

The PIC18F46J50 Family of devices incorporates the standard set of 75 PIC18 core instructions, and an extended set of eight new instructions for the optimization of code that is recursive or that utilizes a software stack. The extended set is discussed later in this section.

## 27.1 Standard Instruction Set

The standard PIC18 instruction set adds many enhancements to the previous PIC<sup>®</sup> MCU instruction sets, while maintaining an easy migration from these PIC MCU instruction sets. Most instructions are a single program memory word (16 bits), but there are four instructions that require two program memory locations.

Each single-word instruction is a 16-bit word divided into an opcode, which specifies the instruction type and one or more operands, which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- Byte-oriented operations
- Bit-oriented operations
- · Literal operations
- Control operations

The PIC18 instruction set summary in Table 27-2 lists the **byte-oriented**, **bit-oriented**, **literal** and **control** operations.

Table 27-1 provides the opcode field descriptions.

Most Byte-oriented instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator, 'f', specifies which file register is to be used by the instruction. The destination designator, 'd', specifies where the result of the operation is to be placed. If 'd' is '0', the result is placed in the WREG register. If 'd' is '1', the result is placed in the file register specified in the instruction.

All **Bit-oriented** instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator, 'f', represents the number of the file in which the bit is located. The **Literal** instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The **Control** instructions may use some of the following operands:

- A program memory address (specified by 'n')
- The mode of the CALL or RETURN instructions (specified by 's')
- The mode of the table read and table write instructions (specified by 'm')
- No operand required (specified by '---')

All instructions are a single word, except for four double-word instructions. These instructions were made double-word to contain the required information in 32 bits. In the second word, the 4 MSbs are '1's. If this second word is executed as an instruction (by itself), it will execute as a NOP.

All single-word instructions are executed in a single instruction cycle, unless a conditional test is true or the Program Counter (PC) is changed as a result of the instruction. In these cases, the execution takes two instruction cycles with the additional instruction cycle(s) executed as a NOP.

The double-word instructions execute in two instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu$ s. If a conditional test is true, or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s. Two-word branch instructions (if true) would take 3  $\mu$ s.

Figure 27-1 provides the general formats that the instructions can have. All examples use the convention 'nnh' to represent a hexadecimal number.

The instruction set summary, provided in Table 27-2, lists the standard instructions recognized by the Microchip MPASM<sup>™</sup> Assembler.

Section 27.1.1 "Standard Instruction Set" provides a description of each instruction.

## TABLE 27-1: OPCODE FIELD DESCRIPTIONS

Field	Description
a	RAM access bit:
	a = 0: RAM location in Access RAM (BSR register is ignored)
	a = 1: RAM bank is specified by BSR register
bbb	Bit address within an 8-bit file register (0 to 7)
BSR	Bank Select Register. Used to select the current RAM bank
C, DC, Z, OV, N	ALU Status bits: Carry, Digit Carry, Zero, Overflow, Negative
d	Destination select bit:
	d = 0: store result in WREG
	d = 1: store result in file register f
dest	Destination: either the WREG register or the specified register file location
f	8-bit register file address (00h to FFh), or 2-bit FSR designator (0h to 3h)
f <sub>s</sub>	12-bit register file address (000h to FFFh). This is the source address
f <sub>d</sub>	12-bit register file address (000h to FFFh). This is the destination address
GIE	Global Interrupt Enable bit
k	Literal field, constant data or label (may be either an 8-bit, 12-bit or a 20-bit value)
label	Label name
mm	The mode of the TBLPTR register for the table read and table write instructions
	Used only with table read and table write instructions
*	No Change to register (such as TBLPTR with table reads and writes)
*+	Post-Increment register (such as TBLPTR with table reads and writes)
*_	Post-Decrement register (such as TBLPTR with table reads and writes)
+*	Pre-Increment register (such as TBLPTR with table reads and writes)
n	The relative address (2's complement number) for relative branch instructions or the direct address for
	Call/Branch and Return instructions
PC	Program Counter
PCL	Program Counter Low Byte
PCH	Program Counter High Byte
PCLATH	Program Counter High Byte Latch
PCLATU	Program Counter Upper Byte Latch
PD	Power-Down bit
PRODH	Product of Multiply High Byte
PRODL	Product of Multiply Low Byte
S	Fast Call/Return mode select bit:
	s = 0: do not update into/from shadow registers
	s = 1: certain registers loaded into/from shadow registers (Fast mode)
TBLPTR	21-Bit Table Pointer (points to a program memory location)
TABLAT	8-Bit Table Latch
TO	Time-out bit
TOS	Top-of-Stack
u	Unused or Unchanged
WDT	Watchdog Timer
WREG	Working register (accumulator)
X	Don't care ('0' or '1'). The assembler will generate code with $x = 0$ ; it is the recommended form of use for compatibility with all Microchip software tools
Zs	7-bit offset value for Indirect Addressing of register files (source)
zd	7-bit offset value for Indirect Addressing of register files (destination)
{ }	Optional argument
[text]	Indicates Indexed Addressing
(text)	The contents of text
[expr] <n></n>	Specifies bit n of the register indicated by the pointer, expr
$\rightarrow$	Assigned to
< >	Register bit field
E	In the set of
italics	User-defined term (font is Courier New)

Byte-oriented file register operations	Example Instruction
15 10 9 8 7 0	
OPCODE d a f (FILE #)	ADDWF MYREG, W, B
d = 0 for result destination to be WREG register d = 1 for result destination to be file register (f) a = 0 to force Access Bank a = 1 for BSR to select bank f = 8-bit file register address	
Byte to Byte move operations (2-word)	
15 12 11 0	
OPCODE f (Source FILE #)	MOVFF MYREG1, MYREG
15 12 11 0	
1111 f (Destination FILE #)	
f = 12-bit file register address	
Bit-oriented file register operations	
15 12 11 9 8 7 0	
OPCODE b (BIT #) a f (FILE #)	BSF MYREG, bit, B
<ul> <li>b = 3-bit position of bit in file register (f)</li> <li>a = 0 to force Access Bank</li> <li>a = 1 for BSR to select bank</li> <li>f = 8-bit file register address</li> </ul>	
Literal operations	
15 8 7 0	
OPCODE k (literal)	MOVLW 7Fh
k = 8-bit immediate value	
Control operations	
CALL, GOTO and Branch operations	
15 8 7 0	
OPCODE n<7:0> (literal)	GOTO Label
15 12 11 0	
1111 n<19:8> (literal)	
n = 20-bit immediate value	
15 8 7 0	
OPCODE S n<7:0> (literal)	CALL MYFUNC
15 12 11 0	
1111 n<19:8> (literal)	
S = Fast bit	
15 11 10 0	
15 11 10 0 OPCODE n<10:0> (literal)	BRA MYFUNC
	BRA MYFUNC

Mnem	onic,	Description	Quality	16-Bit Instruction Word				Status	Notoo
Opera	inds	Description	Cycles	MSb			LSb	Affected	Notes
BYTE-ORI	ENTED C	PERATIONS							
ADDWF	f, d, a	Add WREG and f	1	0010	01da	ffff	ffff	C, DC, Z, OV, N	1, 2
ADDWFC	f, d, a	Add WREG and Carry bit to f	1	0010	00da	ffff	ffff	C, DC, Z, OV, N	1, 2
ANDWF	f, d, a	AND WREG with f	1	0001	01da	ffff	ffff	Z, N	1,2
CLRF	f, a	Clear f	1	0110	101a	ffff	ffff	Z	2
COMF	f, d, a	Complement f	1	0001	11da	ffff	ffff	Z, N	1, 2
CPFSEQ	f, a	Compare f with WREG, Skip =	1 (2 or 3)	0110	001a	ffff	ffff	None	4
CPFSGT	f, a	Compare f with WREG, Skip >	1 (2 or 3)	0110	010a	ffff	ffff	None	4
CPFSLT	f, a	Compare f with WREG, Skip <	1 (2 or 3)	0110	000a	ffff	ffff	None	1, 2
DECF	f, d, a	Decrement f	1	0000	01da	ffff	ffff	C, DC, Z, OV, N	1, 2, 3, 4
DECFSZ	f, d, a	Decrement f, Skip if 0	1 (2 or 3)	0010	11da	ffff	ffff	None	1, 2, 3, 4
DCFSNZ	f, d, a	Decrement f, Skip if Not 0	1 (2 or 3)	0100	11da	ffff	ffff	None	1, 2
INCF	f, d, a	Increment f	1	0010	10da	ffff	ffff	C, DC, Z, OV, N	1, 2, 3, 4
INCFSZ	f, d, a	Increment f, Skip if 0	1 (2 or 3)	0011	11da	ffff	ffff		4
INFSNZ	f, d, a	Increment f, Skip if Not 0	1 (2 or 3)	0100	10da	ffff	ffff	None	1, 2
IORWF	f, d, a	Inclusive OR WREG with f	1 ΄	0001	00da	ffff	ffff	Z, N	1, 2
MOVF	f, d, a	Move f	1	0101	00da	ffff	ffff		1
MOVFF	f <sub>s</sub> , f <sub>d</sub>	Move f <sub>s</sub> (source) to 1st word	2	1100	ffff	ffff	ffff	None	
	3. u	f <sub>d</sub> (destination) 2nd word		1111	ffff	ffff	ffff		
MOVWF	f, a	Move WREG to f	1	0110	111a	ffff	ffff	None	
MULWF	f, a	Multiply WREG with f	1	0000	001a	ffff	ffff	None	1, 2
NEGF	f, a	Negate f	1	0110	110a	ffff		C, DC, Z, OV, N	·
RLCF	f, d, a	Rotate Left f through Carry	1	0011	01da	ffff	ffff		1, 2
RLNCF	f, d, a	Rotate Left f (No Carry)	1	0100	01da	ffff	ffff		·
RRCF	f, d, a	Rotate Right f through Carry	1	0011	00da	ffff	ffff		
RRNCF	f, d, a	Rotate Right f (No Carry)	1	0100	00da	ffff	ffff	Z, N	
SETF	f, a	Set f	1	0110	100a	ffff	ffff		1, 2
SUBFWB	f, d, a	Subtract f from WREG with	1	0101	01da	ffff	ffff		,
	, , -	Borrow							
SUBWF	f, d, a	Subtract WREG from f	1	0101	11da	ffff	ffff	C, DC, Z, OV, N	1, 2
SUBWFB	f, d, a	Subtract WREG from f with	1	0101	10da	ffff	ffff		,
	, , -	Borrow							
SWAPF	f, d, a	Swap Nibbles in f	1	0011	10da	ffff	ffff	None	4
TSTFSZ	f, a	Test f, Skip if 0	1 (2 or 3)		011a	ffff		None	1, 2
XORWF	f, d, a	Exclusive OR WREG with f	1	0001	10da	ffff	ffff		, _
Note 1			•						L

#### TABLE 27-2: PIC18F46J50 FAMILY INSTRUCTION SET

**Note 1:** When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

2: If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned.

**3:** If the Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

4: Some instructions are two-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

Mnem	onic,	Description	Cyceler	16-	Bit Instr	uction V	Vord	Status	Natas
Opera	ands	Description	Cycles	MSb			LSb	Affected	Notes
BIT-ORIEN	NTED OP	ERATIONS							
BCF	f, b, a	Bit Clear f	1	1001	bbba	ffff	ffff	None	1, 2
BSF	f, b, a	Bit Set f	1	1000	bbba	ffff	ffff	None	1, 2
BTFSC	f, b, a	Bit Test f, Skip if Clear	1 (2 or 3)	1011	bbba	ffff	ffff	None	3, 4
BTFSS	f, b, a	Bit Test f, Skip if Set	1 (2 or 3)	1010	bbba	ffff	ffff	None	3, 4
BTG	f, b, a	Bit Toggle f	1	0111	bbba	ffff	ffff	None	1, 2
CONTROL	OPERA	TIONS							
BC	n	Branch if Carry	1 (2)	1110	0010	nnnn	nnnn	None	
BN	n	Branch if Negative	1 (2)	1110	0110	nnnn	nnnn	None	
BNC	n	Branch if Not Carry	1 (2)	1110	0011	nnnn	nnnn	None	
BNN	n	Branch if Not Negative	1 (2)	1110	0111	nnnn	nnnn	None	
BNOV	n	Branch if Not Overflow	1 (2)	1110	0101	nnnn	nnnn	None	
BNZ	n	Branch if Not Zero	1 (2)	1110	0001	nnnn	nnnn	None	
BOV	n	Branch if Overflow	1 (2)	1110	0100	nnnn	nnnn	None	
BRA	n	Branch Unconditionally	2	1101	0nnn	nnnn	nnnn	None	
BZ	n	Branch if Zero	1 (2)	1110	0000	nnnn	nnnn	None	
CALL	n, s	Call Subroutine 1st word	2	1110	110s	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
CLRWDT	—	Clear Watchdog Timer	1	0000	0000	0000	0100	TO, PD	
DAW	—	Decimal Adjust WREG	1	0000	0000	0000	0111	С	
GOTO	n	Go to Address 1st word	2	1110	1111	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
NOP	—	No Operation	1	0000	0000	0000		None	
NOP	—	No Operation	1	1111		XXXX		None	4
POP	—	Pop Top of Return Stack (TOS)	1	0000	0000	0000	0110	None	
PUSH	—	Push Top of Return Stack (TOS)	1	0000	0000	0000	0101	None	
RCALL	n	Relative Call	2	1101	1nnn	nnnn	nnnn	None	
RESET		Software Device Reset	1	0000	0000	1111		All	
RETFIE	S	Return from Interrupt Enable	2	0000	0000	0001	000s	GIE/GIEH, PEIE/GIEL	
RETLW	k	Return with Literal in WREG	2	0000	1100	kkkk	kkkk	None	
RETURN	S	Return from Subroutine	2	0000	0000	0001	001s	None	
SLEEP	_	Go into Standby mode	1	0000	0000	0000	0011	TO, PD	

#### TABLE 27-2: PIC18F46J50 FAMILY INSTRUCTION SET (CONTINUED)

**Note 1:** When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

2: If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned.

**3:** If the Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

4: Some instructions are two-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

<b>TABLE 27-2</b> :	PIC18F46J50 FAMILY INSTRUCTION SET	)
		,

IADLE 2				<u>г</u>			,	_	
Mnem		Description	Cycles	16-Bit Instruction Word				Status	Notes
Opera	anas	-	-	MSb			LSb	Affected	
LITERAL	OPERA	TIONS							
ADDLW	k	Add Literal and WREG	1	0000	1111	kkkk	kkkk	C, DC, Z, OV, N	
ANDLW	k	AND Literal with WREG	1	0000	1011	kkkk	kkkk	Z, N	
IORLW	k	Inclusive OR Literal with WREG	1	0000	1001	kkkk	kkkk	Z, N	
LFSR	f, k	Move Literal (12-bit) 2nd word	2	1110	1110	00ff	kkkk	None	
		to FSR(f) 1st word		1111	0000	kkkk	kkkk		
MOVLB	k	Move Literal to BSR<3:0>	1	0000	0001	0000	kkkk	None	
MOVLW	k	Move Literal to WREG	1	0000	1110	kkkk	kkkk	None	
MULLW	k	Multiply Literal with WREG	1	0000	1101	kkkk	kkkk	None	
RETLW	k	Return with Literal in WREG	2	0000	1100	kkkk	kkkk	None	
SUBLW	k	Subtract WREG from Literal	1	0000	1000	kkkk	kkkk	C, DC, Z, OV, N	
XORLW	k	Exclusive OR Literal with WREG	1	0000	1010	kkkk	kkkk	Z, N	
DATA MEI	MORY +	PROGRAM MEMORY OPERATION	ONS						
TBLRD*		Table Read	2	0000	0000	0000	1000	None	
TBLRD*+		Table Read with Post-Increment		0000	0000	0000	1001	None	
TBLRD*-		Table Read with Post-Decrement		0000	0000	0000	1010	None	
TBLRD+*		Table Read with Pre-Increment		0000	0000	0000	1011	None	
TBLWT*		Table Write	2	0000	0000	0000	1100	None	
TBLWT*+		Table Write with Post-Increment		0000	0000	0000	1101	None	
TBLWT*-		Table Write with Post-Decrement		0000	0000	0000	1110	None	
TBLWT+*		Table Write with Pre-Increment		0000	0000	0000	1111	None	

**Note 1:** When a PORT register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

2: If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned.

**3:** If the Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

4: Some instructions are two-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

#### 27.1.1 STANDARD INSTRUCTION SET

ADD	LW	ADD Litera	l to W		4	DDWF	ADD W to	f	
Synta	ax:	ADDLW	k		S	yntax:	ADDWF	f {,d {,a}}	
Oper	ands:	$0 \leq k \leq 255$			C	perands:	$0 \leq f \leq 255$		
Oper	ation:	$(W) + k \rightarrow V$	N				d ∈ [0,1] a ∈ [0,1]		
Statu	is Affected:	N, OV, C, D	0C, Z			noration		doot	
Enco	oding:	0000	1111 kkk	k kkkk		peration: tatus Affected:	$(W) + (f) \rightarrow$		
Desc	ription:	The conten	The contents of W are added to the		-		N, OV, C, E		
			k' and the resu	ult is placed in		ncoding:	0010	01da ffi	
14/	1	W.			L	escription:		egister 'f'. If 'd' red in W. If 'd'	
Word		1						red back in re	
Cycle		1					(default).		
QC	ycle Activity:	02	02	04				he Access Bar	
	Q1 Decode	Q2 Read	Q3 Process	Q4 Write to	1		GPR bank	he BSR is use (default).	a to select the
	Decoue	literal 'k'	Data	Wille to				nd the extend	ed instruction
							set is enabl	ed, this instruc	ction operates
Exan	nple:	ADDLW 1	.5h					Literal Offset A never f ≤ 95 (5	•
	Before Instruc	tion						.2.3 "Byte-Or	,
	W = After Instruction	10h						ed Instruction	
	W =	25h						set Mode" for	details.
						Vords:	1		
						Sycles:	1		
						Q Cycle Activity:			
						Q1	Q2	Q3	Q4
						Decode	Read register 'f'	Process Data	Write to destination
							109.000	2010	acountation
					<u>E</u>	xample:	ADDWF	REG, 0, 0	
						Before Instruc	tion		
						W REG	= 17h = 0C2h		
						After Instruction			
						W	= 0D9h		
						REG	= 0C2h		

Note: All PIC18 instructions may take an optional label argument preceding the instruction mnemonic for use in symbolic addressing. If a label is used, the instruction format then becomes: {label} instruction argument(s).

ADDWFC	ADD W an	ADD W and Carry bit to f					
Syntax:	ADDWFC	f {,d {,a	a}}				
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$						
Operation:	(W) + (f) +	$(C) \rightarrow de$	st				
Status Affected:	N,OV, C, D	C, Z					
Encoding:	0010	00da	ffff	ffff			
Description:	Add W, the location 'f'. placed in W placed in d	lf 'd' is '0 /. lf 'd' is '	, the resu 1', the re	ult is sult is			
	lf 'a' is '1', t	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).					
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
Words:	1						
Cycles:	1						
Q Cycle Activity:							
Q1	Q2	Q3		Q4			
Decode	Read register 'f'	Proces Data	-	/rite to stination			
Example:	ADDWFC	REG,	0, 1				
Before Instruc Carry bit REG W After Instructio Carry bit REG W	= 1 = 02h = 4Dh						

ANDLW	AND Litera	AND Literal with W						
Syntax:	ANDLW	k						
Operands:	$0 \le k \le 255$	5						
Operation:	(W) .AND.	$k \rightarrow W$						
Status Affected:	N, Z							
Encoding:	0000	1011	kkk	k	kkkk			
Description:	The conter 8-bit literal W.							
Words:	1							
Cycles:	1							
Q Cycle Activity:								
Q1	Q2	Q	3		Q4			
Decode	Read literal 'k'	Proce Dat		V	/rite to W			
Example:	ANDLW	05Fh						
Before Instruc	ction = A3h							
vv After Instructi								

ANDWF	AND W wit	th f		вс		Branch if C	Carry	
Syntax:	ANDWF	f {,d {,a}}		Synt	ax:	BC n		
Operands:	$0 \leq f \leq 255$			Oper	ands:	-128 ≤ n ≤ ′	127	
	$\begin{array}{l} d \in [0,1] \\ a \in [0,1] \end{array}$			Oper	ation:	if Carry bit i (PC) + 2 + 2		
Operation:	(W) .AND.	(f) $\rightarrow$ dest		Statu	s Affected:	None		
Status Affected:	N, Z			Enco	ding:	1110	0010 nnr	n nnnn
Encoding:	0001	01da ff	ff ffff		ription:		bit is '1', then	
Description:	Description: The contents of W are ANDed with register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default).		200		will branch. The 2's con added to th	nplement num e PC. Since th	ber '2n' is le PC will	
If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).				have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.				
		ind the extend		Word	ls:	1		
		led, this instrue Literal Offset A	•	Cycle	es:	1(2)		
	mode wher	never f ≤ 95 (5 7.2.3 " <b>Byte-Or</b>	Fh). See	Q C If Ju	ycle Activity: mp:			
		ed Instruction			Q1	Q2	Q3	Q4
		set Mode" for	detalls.		Decode	Read literal 'n'	Process Data	Write to PC
Words:	1				No	No	No	No
Cycles:	1				operation	operation	operation	operation
Q Cycle Activity			<b>.</b>	lf No	o Jump:			
Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination		Decode	Read literal 'n'	Process Data	No operation
Example:	ANDWF	REG, 0, 0		Exar	nple:	HERE	BC 5	
Before Inst W REG After Instru W REG	= 17h = C2h				Before Instruct PC After Instructi If Carry PC If Carry	= ad on = 1; = ad = 0;	dress (HERE)	+ 12)
W	= 02h				PC	= ad = 0;	dress (HERE dress (HERE	

BCF	Bit Clear f			BN
Syntax:	BCF f, b	{,a}		Syntax:
Operands:	$0 \leq f \leq 255$			Operands:
	$\begin{array}{l} 0 \leq b \leq 7 \\ a \in [0,1] \end{array}$			Operation:
Operation:	$0 \rightarrow f \le b >$			Status Affected:
Status Affected:	None			Encoding:
Encoding:	1001	bbba ff	ff ffff	Description:
Description:	Bit 'b' in reo	gister 'f' is clea	ared.	<b>-</b>
	,	he BSR is use	nk is selected. ed to select the	
	set is enab in Indexed mode wher Section 27 Bit-Oriente	led, this instru Literal Offset A never f ≤ 95 (5 2.2.3 "Byte-Or	Fh). See riented and is in Indexed	Words: Cycles: Q Cycle Activity:
Words:	1			If Jump:
Cycles:	1			Q1 Decode
Q Cycle Activity:				Decode
Q1	Q2	Q3	Q4	No
Decode	Read	Process	Write	operation
	register 'f'	Data	register 'f'	If No Jump: Q1
Example:		FLAG_REG,	7, 0	Decode
Before Instru FLAG_ After Instruc	REG = C7h			Example:
	REG = 47h			Before Instru PC After Instruct

BN		Branch if N	legative					
Synta	ax:	BN n						
Oper	ands:	-128 ≤ n ≤ ′	$-128 \le n \le 127$					
Oper	ation:	if Negative (PC) + 2 + 2		;				
Statu	s Affected:	None						
Enco	ding:	1110	0110	nnnn	nnnn			
Desc	ription:	•	If the Negative bit is '1', then the program will branch.					
The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.					C will e next will be			
Word	ls:	1						
Cycle	es:	1(2)						
Q C If Ju	ycle Activity: mp:							
	Q1	Q2	Q3	5	Q4			
	Decode	Read literal 'n'	Proce Data		Vrite to PC			
	No	No	No		No			
	operation	operation	operat	ion o	peration			
lf No	o Jump:							
	Q1	Q2	Q3	}	Q4			
	Decode	Read literal	Proce		No			
		'n'	Data	a o	peration			
<u>Exan</u>	<u>nple:</u>	HERE	BN	Jump				
Before Instruction PC = address (HERE) After Instruction								

			uuui 000	(1101(0)	
fter	Instruction				
	If Negative	=	1;		
	РC	=	address	(Jump)	
	If Negative	=	0;		
	PC	=	address	(HERE	+

2)

BNC		Branch if N	lot Carry		BN
Synta	ax:	BNC n			Syr
Oper	ands:	-128 ≤ n ≤ 1	127		Op
Oper	ation:	if Carry bit i (PC) + 2 + 2			Op
Statu	is Affected:	None			Sta
Enco	oding:	1110	0011 nnr	in nnnn	End
Desc	cription:	If the Carry will branch.	bit is '0', then	the program	De
		added to th have incren instruction,	nplement num e PC. Since th nented to fetch the new addre n. This instruct istruction.	e PC will the next ess will be	
Word	ds:	1			Wo
Cycle	es:	1(2)			Сус
	ycle Activity: imp:				Q If s
	Q1	Q2	Q3	Q4	_
	Decode	Read literal 'n'	Process Data	Write to PC	
	No operation	No operation	No operation	No operation	
lf No	o Jump:				lfl
	Q1	Q2	Q3	Q4	,
	Decode	Read literal 'n'	Process Data	No operation	
Exan	nple:	HERE	BNC Jump		Exa
	Before Instruct PC After Instruction If Carry PC If Carry PC PC	= ado = 0; = ado = 1;	dress (HERE) dress (Jump) dress (HERE		

BNN		Branch if N	lot Negati	ve			
Synta	ax.	BNN n					
	ands:	-128 ≤ n ≤ <sup>2</sup>	127				
•	ation:	if Negative (PC) + 2 + 2	,				
Statu	s Affected:	None					
Enco	oding:	1110	0111	nnnn	nnnn		
Description:		If the Negator program wi		)', then t	he		
		The 2's con added to th have incren instruction, PC + 2 + 2r two-cycle ir	e PC. Sinc nented to f the new a n. This inst	ce the Po fetch the ddress v	C will next vill be		
Word	ls:	1	1				
Cycle Q C If Ju	ycle Activity: ımp:	1(2)					
	Q1	Q2	Q3		Q4		
	Decode	Read literal 'n'	Process Data	s V	/rite to PC		
	No	No	No		No		
	operation	operation	operatio	n op	eration		
lf No	o Jump:						
	Q1	Q2	Q3		Q4		
	Decode	Read literal	Process	-	No		
		'n'	Data	ор	eration		
<u>Exan</u>	nple:	HERE	BNN Jı	ump			
	Before Instruc PC After Instruction	= ad	dress (HE	ERE)			
	PC If Negativ	= ad	dress (Ju	ump)			
	PC		dress (HE	ERE + 2	2)		

BNO	v	Branch if N	lot Overflow			
Synta	ax:	BNOV n				
Oper	ands:	-128 ≤ n ≤ 1	127			
Oper	ation:	if Overflow (PC) + 2 + 2	,			
Statu	s Affected:	None				
Enco	ding:	1110	0101 nn	nn nnnn		
Desc	ription:		If the Overflow bit is '0', then the program will branch.			
		added to th have incren instruction,	nplement num e PC. Since the nented to fetch the new addread n. This instruction.	ne PC will h the next ess will be		
Word	ls:	1				
Cycle	es:	1(2)	1(2)			
Q C If Ju						
	Q1	Q2	Q3	Q4		
	Decode	Read literal 'n'	Process Data	Write to PC		
	No operation	No operation	No operation	No operation		
lf No	o Jump:	•	•			
	Q1	Q2	Q3	Q4		
	Decode	Read literal 'n'	Process Data	No operation		
Exan	nple:	HERE	BNOV Jump			
	Before Instruc PC After Instructio	= ad	dress (HERE	)		
	If Overflo PC If Overflo	= ado w = 1;	dress (Jump	)		
	PC	= ad	dress (HERE	+ 2)		

Opera Opera Statu		-128 ≤ n ≤ <sup>-</sup>					
Opera			127				
Statu		if Zero bit is '0', (PC) + 2 + 2n $\rightarrow$ PC					
Status Affected:		None					
Encoding:		1110	0001	nnnn	nnn		
Desc	ription:	If the Zero will branch.		then the	program		
		The 2's cor added to th have increr instruction, PC + 2 + 2 two-cycle ir	e PC. Si nented to the new n. This in	nce the F o fetch th address istruction	PC will e next will be		
Word	s:	1					
Cycle	es:	1(2)					
Q Cy If Ju	ycle Activity: mp:						
	Q1	Q2	Q3	3	Q4		
	Decode	Read literal 'n'	Proce Data		Write to PC		
	No operation	No operation	No operat		No peratio		
lf No	Jump:						
	Q1	Q2	Q3	3	Q4		
	Decode	Read literal	Proce		No		
		'n'	Data	a o	peratio		
Fxam	<u>iple:</u>	HERE	BNZ	Jump			
LXGII							

er Instruction		
If Zero	=	0;
PC	=	address (Jump)
If Zero	=	1;
PC	=	address (HERE + 2)

BRA		Unconditio	onal Branch	
Synta	ax:	BRA n		
Oper	ands:	-1024 ≤ n ≤	1023	
Oper	ation:	(PC) + 2 + 2	$2n \rightarrow PC$	
Statu	s Affected:	None		
Enco	ding:	1101	0nnn nni	nn nnnn
Desc	ription:	the PC. Sin incremented instruction,	ce the PC will d to fetch the the new addre n. This instruc	next ess will be
Word	IS:	1		
Cycle	es:	2		
QC	ycle Activity:			
	Q1	Q2	Q3	Q4
	Decode	Read literal 'n'	Process Data	Write to PC
	No	No	No	No
	operation	operation	operation	operation
	nple: Before Instruc PC After Instructic PC	= ado	BRA Jump dress (HERE dress (Jump	)

0	Bit Set f	( -)		
Syntax:	BSF f, b {	[,a}		
Operands:	$0 \le f \le 255$ $0 \le b \le 7$			
	0 ≤ D ≤ 7 a ∈ [0,1]			
Operation:	1 → f <b></b>			
Status Affected:	None			
Encoding:	1000	bbba	ffff	ffff
Description:	Bit 'b' in reg	gister 'f' i	s set.	
	,	he BSR i	is used t	is selected. to select the
	in Indexed mode wher <b>Section 27</b>	Literal O never f ≤ 7.2.3 "By ed Instru	ffset Ad 95 (5Fh r <b>te-Orie</b> Ictions	n). See nted and in Indexed
Words:	1			
<b>.</b> .	1			
Cvcles:				
Cycles: O Cycle Activity				
Cycles: Q Cycle Activity: Q1	Q2	Q	3	Q4
Q Cycle Activity:	Q2 Read	Q		Q4 Write
Q Cycle Activity:		1	ess	
Q Cycle Activity:	Read register 'f'	Proce	a a	Write register 'f'

BTFS	SC	Bit Test File	, Skip if Clear	
Synta	ax:	BTFSC f, b	{,a}	
Oper	ands:	$\begin{array}{l} 0\leq f\leq 255\\ 0\leq b\leq 7\\ a\in [0,1] \end{array}$		
Oner	ation:	skip if (f <b>)</b>	= 0	
	s Affected:	None	- 0	
			bbba fff	
Enco	U			
Desc	ription:	instruction is then the next the current in carded and a	jister 'f' is '0', th skipped. If bit instruction fet instruction exect a NOP is execu a two-cycle ins	'b' is '0', ched during ution is dis- ted instead,
			e Access Bank e BSR is used i lefault).	
		set is enable in Indexed Li mode whene Section 27.2 Bit-Oriented	d the extended d, this instructi iteral Offset Ad ever f ≤ 95 (5FH 2.3 "Byte-Orie I Instructions et Mode" for d	on operates dressing n). See nted and in Indexed
Word	s:	1		
Cycle		•	cles if skip and 2-word instruc	
QC	ycle Activity:	00	00	04
	Q1 Decode	Q2 Read	Q3 Process	Q4 No
	Decode	register 'f'	Data	operation
lf sk	ip:			
	Q1	Q2	Q3	Q4
	No	No	No	No
lf als	operation	operation	operation	operation
II SK	ip and followed Q1	Q2	Q3	Q4
	No	No	No	No
	operation	operation	operation	operation
	No	No	No	No
	operation	operation	operation	operation
<u>Exan</u>	nple:	HERE BI FALSE : TRUE :	FSC FLAG	, 1, 0
	Before Instruct PC	= add	ress (HERE)	
	After Instruction If FLAG<´ PC If FLAG<´ PC	1> = 0; = add 1> = 1;	ress (TRUE) ress (False)	

BTFSS	Bit Test File	, Skip if Set	
Syntax:	BTFSS f, b {	,a}	
Operands:	0 ≤ f ≤ 255		
-	$0 \le b < 7$		
	a ∈ [0,1]		
Operation:	skip if (f <b>)</b>	= 1	
Status Affected:	None		
Encoding:	1010	bbba fff	f ffff
Description:	instruction is then the nex the current in carded and a	gister 'f' is '1', to skipped. If bit t instruction fet nstruction exect a NOP is execu a two-cycle ins	'b' is '1', tched during cution is dis- ted instead,
	,	e Access Bank e BSR is used default).	
	set is enable in Indexed L mode where Section 27.2 Bit-Oriented	d the extended d, this instructi iteral Offset Ac ever f ≤ 95 (5FI 2.3 "Byte-Orie d Instructions et Mode" for d	ion operates ddressing h). See ented and in Indexed
Words:	1		
Cycles:	1(2)		
		ycles if skip an a 2-word instru	
Q Cycle Activity:			
Q Cycle Activity:			
	Q2 Read	Q3 Process	Q4
Q1 Decode	by a	Q3	Q4
Q1 Decode If skip:	Q2 Read register 'f'	Q3 Process Data	Q4 No operation
Q1 Decode If skip: Q1	by a Q2 Read register 'f' Q2	Q3 Process Data Q3	Q4 No operation Q4
Q1 Decode If skip: Q1 No	by a Q2 Read register 'f' Q2 No	Q3 Process Data Q3 No	Q4 No operation Q4 No
Q1 Decode If skip: Q1 No operation	Dy a Q2 Read register 'f' Q2 No operation	Q3 Process Data Q3 No operation	Q4 No operation Q4
Q1 Decode If skip: Q1 No operation If skip and followed	Q2 Read register 'f' Q2 No operation I by 2-word ins	Q3 Process Data Q3 No operation truction:	Q4 No operation Q4 No operation
Q1 Decode If skip: Q1 No operation	Dy a Q2 Read register 'f' Q2 No operation	Q3 Process Data Q3 No operation	Q4 No operation Q4 No
Q1 Decode If skip: Q1 No operation If skip and followed Q1	Q2 Read register 'f' Q2 No operation I by 2-word ins Q2	Q3 Process Data Q3 No operation truction: Q3	Q4 No operation Q4 No operation Q4
Q1 Decode If skip: Q1 No operation If skip and followed Q1 No operation No	Q2 Read register 'f' Q2 No operation I by 2-word ins Q2 No	A 2-word instru Q3 Process Data Q3 No operation truction: Q3 No	Q4 No operation Q4 No operation Q4 No
Q1 Decode If skip: Q1 No operation If skip and followed Q1 No operation	Q2 Read register 'f' Q2 No operation by 2-word ins Q2 No operation	Q3 Process Data Q3 No operation truction: Q3 No operation	Q4 No operation Q4 No operation Q4 No operation
Q1 Decode If skip: Q1 No operation If skip and followed Q1 No operation No operation	Q2 Read register 'f' Q2 No operation I by 2-word ins Q2 No operation No operation	A 2-word instru Q3 Process Data Q3 No operation truction: Q3 No operation No operation	Q4 No operation Q4 No operation Q4 No operation No
Q1 Decode If skip: Q1 No operation If skip and followed Q1 No operation No operation	Q2 Read register 'f' Q2 No operation I by 2-word ins Q2 No operation No operation HERE B' FALSE : TRUE : ion = add	A 2-word instru Q3 Process Data Q3 No operation truction: Q3 No operation No operation	Q4 No operation Q4 No operation Q4 No operation No operation
Q1 Decode If skip: Q1 No operation If skip and followed Q1 No operation No operation Example: Before Instruct PC	Q2           Read register 'f           Q2           No operation           by 2-word ins Q2           No operation           No operation           No operation           FALSE TRUE           ion           =           1>           =           add 1>           1>           =           1>           =           add 1>	A 2-word instru Q3 Process Data Q3 No operation truction: Q3 No operation No operation	Q4 No operation Q4 No operation Q4 No operation No operation

BTG	Bit Toggle f	BOV	Branch if Overflow
Syntax:	BTG f, b {,a}	Syntax:	BOV n
Operands:	$0 \leq f \leq 255$	Operands:	$-128 \le n \le 127$
	0 ≤ b < 7 a ∈ [0,1]	Operation:	if Overflow bit is '1', (PC) + 2 + 2n $\rightarrow$ PC
Operation:	$(f \le b >) \rightarrow f \le b >$	Status Affected:	None
Status Affected:	None	Encoding:	1110 0100 nnnn nnnn
Encoding: Description:	0111 bbba ffff ffff Bit 'b' in data memory location 'f' is	Description:	If the Overflow bit is '1', then the program will branch.
	inverted. If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default). If 'a' is '0' and the extended instruction set is enabled, this instruction operates		The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.
	in Indexed Literal Offset Addressing	Words:	1
	mode whenever $f \le 95$ (5Fh). See	Cycles:	1(2)
	Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.	Q Cycle Activity: If Jump:	
Words:	1	Q1	Q2 Q3 Q4
Cycles:	1	Decode	Read literal Process Write to PC 'n' Data
Q Cycle Activity	:	No	No No No
Q1	Q2 Q3 Q4	operation	operation operation operation
Decode	Read Process Write	If No Jump:	
	register 'f' Data register 'f'	Q1	Q2 Q3 Q4
Example:	BTG PORTC, 4, 0	Decode	Read literalProcessNo'n'Dataoperation
Before Instr PORT After Instruct PORT	C = 0111 0101 [75h] ction:	Example: Before Instruct PC After Instruction If Overfic PC If Overfic PC	= address (HERE) on pw = 1; = address (Jump) pw = 0;

ΒZ		Branch if Z	ero				
Synta	ax:	BZ n					
Oper	ands:	$-128 \le n \le 1$	27				
Oper	ation:	if Zero bit is (PC) + 2 + 2	,				
Statu	s Affected:	None					
Enco	ding:	1110	0000 nnr	nn nnnn			
Description:		If the Zero I will branch.	If the Zero bit is '1', then the program will branch.				
		added to th have incren instruction,	Plement num e PC. Since the nented to fetch the new addree n. This instruct struction.	ne PC will In the next less will be			
Word	s:	1					
Cycle	es:	1(2)					
Q Cy If Ju	ycle Activity: mp:						
	Q1	Q2	Q3	Q4			
	Decode	Read literal 'n'	Process Data	Write to PC			
	No operation	No operation	No operation	No operation			
lf No	Jump:						
	Q1	Q2	Q3	Q4			
	Decode	Read literal 'n'	Process Data	No operation			
<u>Exam</u>	<u>iple:</u>	HERE	BZ Jump				
	Before Instruc PC After Instructio	= ad	dress (HERE	)			
	If Zero PC	= 1; = ad	dress (Jump	\ \			

		Subroutin	e Call			
Syntax:		CALL k {,	s}			
Operands:		$0 \le k \le 104$ s $\in$ [0,1]	18575			
Operation:		$\begin{array}{l} (PC) + 4 - \\ k \rightarrow PC < 2 \\ \text{if s = 1,} \\ (W) \rightarrow WS \\ (STATUS) \\ (BSR) \rightarrow E \end{array}$	0:1>; ; → STATI	JSS,		
Status Affe	cted:	None				
Encoding: 1st word (k 2nd word(k	,	1110 1111	110s k <sub>19</sub> kkk	k <sub>7</sub> kk kkki		kk <sub>C</sub> kk <sub>8</sub>
		stack. If 's' BSR registers a respective STATUSS update occ 20-bit valu PC<20:1>	re also po shadow and BSR curs (defa e 'k' is loa	ushed i registe S. If 's' ault). Th aded in	into their rs, WS, ' = 0, no hen, the ito	r
		instruction			,	
Words:		instruction			,	
Words:		2			,	
Cycles:	ctivity:				,	
Cycles: Q Cycle A		2 2			Q4	
Cycles: Q Cycle A	ctivity: Q1 code	2	Q Push P stac	3 PC to :k	Q4 Read lite 'k'<19:8 Write to	3>,
Cycles: Q Cycle A De	Q1	2 2 Q2 Read literal	Q3 Push P	3 IC to k	Read lite 'k'<19:8	3>, PC
Cycles: Q Cycle A De t ope Example: Before F	Q1 code No	2 2 Read literal 'k'<7:0>, No operation HERE tion = addres	Q3 Push P stac No opera CALL	3 VC to k tion	Read lit 'k'<19:8 Write to No operati	3>, PC

CLRF	Clear f	CLRWDT	Clear Watchdog Timer
Syntax:	CLRF f {,a}	Syntax:	CLRWDT
Operands:	$0 \leq f \leq 255$	Operands:	None
	a ∈ [0,1]	Operation:	000h $\rightarrow$ WDT,
Operation:	$\begin{array}{l} 000h \rightarrow f, \\ 1 \rightarrow Z \end{array}$		$\begin{array}{l} 000h \rightarrow WDT \text{ postscaler,} \\ 1 \rightarrow \overline{TO}, \end{array}$
Status Affected:	z		$1 \rightarrow \overline{PD}$
Encoding:		Status Affected:	TO, PD
Description:	Clears the contents of the specified	Encoding:	0000 0000 0000 0100
	register.	Description:	CLRWDT instruction resets the
	If 'a' is '0', the Access Bank is selected.		Watchdog Timer. It also resets the postscaler of the WDT. Status bits, $\overline{\text{TO}}$
	If 'a' is '1', the BSR is used to select the GPR bank (default).		and PD, are set.
	If 'a' is '0' and the extended instruction	Words:	1
	set is enabled, this instruction operates	Cycles:	1
	in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See	Q Cycle Activity:	
	Section 27.2.3 "Byte-Oriented and	Q1	Q2 Q3 Q4
	Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.	Decode	NoProcessNooperationDataoperation
Words:	1		oporation Data oporation
Cycles:	1	Example:	CLRWDT
Q Cycle Activity:		Before Instruc	ction
Q Cycle Activity. Q1	Q2 Q3 Q4	WDT Co After Instructio	
Decode	Read Process Write	WDT Co	•
	register 'f' Data register 'f'	WDT Po	
Fuerenley		TO PD	= 1 = 1
Example: Before Instruc	CLRF FLAG_REG,1	-	
FLAG RI			
After Instructio	n		
FLAG_RI	EG = 00h		

COMF	Compleme	ent f		CPFSEQ	Compare f	with W, Skip	if f = W
Syntax:	COMF f	{,d {,a}}		Syntax:	CPFSEQ	f {,a}	
Operands:	0 ≤ f ≤ 255	0 0 11		Operands:	$0 \leq f \leq 255$		
operander	d ∈ [0,1]				a ∈ [0,1]		
	a ∈ [0,1]			Operation:	(f) – (W),		
Operation:	$\overline{f} \rightarrow dest$				skip if (f) =	· · /	
Status Affected:	N, Z					comparison)	
		11.1. 55		Status Affected:	None	<u> </u>	
Encoding:	0001	11da ff		Encoding:	0110	001a ff:	ff ffff
Description:	complemer stored in W	nts of register ' nted. If 'd' is '0 /. If 'd' is '1', th	', the result is le result is	Description:	ory location	the contents on 'f' to the cont an unsigned s	ents of W by
	stored back	k in register 'f'	(default).		If 'f' = W th	en the fetched	1 instruction is
	,	he BSR is use	nk is selected. d to select the		discarded a	and a NOP is e aking this a two	xecuted
	set is enabl in Indexed	Literal Offset	ction operates Addressing			he Access Baı he BSR is use (default).	
	Section 27 Bit-Oriente	never f ≤ 95 (5 7.2.3 "Byte-Or ed Instructior set Mode" for	riented and is in Indexed		set is enabl in Indexed	Ind the extend led, this instruct Literal Offset	ction operates Addressing
Words:	1					never f ≤ 95 (5 <b>'.2.3 "Byte-Or</b>	,
Cycles:	1				Bit-Oriente	ed Instruction set Mode" for	ns in Indexed
Q Cycle Activity:			<b>.</b>	Words:	1		
Q1	Q2	Q3	Q4	Cycles:	1(2)		
Decode	Read register 'f'	Process Data	Write to destination	Cycles.	Note: 3 cy	cles if skip and 2-word instru	
<b>-</b> .				Q Cycle Activity:			
Example:	COMF	REG, 0, 0	1	Q1	Q2	Q3	Q4
Before Instruc				Decode	Read	Process	No
REG After Instructio	= 13h				register 'f'	Data	operation
REG	= 13h			If skip:			
W	= ECh			Q1	Q2	Q3	Q4
				No operation	No operation	No operation	No operation
				If skip and follow			operation
				II SKIP AND IOIOW	Q2	Q3	Q4
				No	No	No	No
				operation	operation	operation	operation
				No	No	No	No
				operation	operation	operation	operation
				Example:	HERE NEQUAL	CPFSEQ REG	G <b>,</b> O
					EQUAL	:	
				Before Instru	iction		

Before Instruction PC Address W REG	= = =	HERE ? ?	
After Instruction If REG	=	W:	
PC If REG	=	Address W:	(EQUAL)
PC	≠ =	vv, Address	(NEQUAL)

CPFSGT	Compare f	with W, Skip	if f > W	CPF	SLT	Compare f	with W, Skip	if f < W
Syntax:	CPFSGT	f {,a}		Synta	ax:	CPFSLT	f {,a}	
Operands:	0 ≤ f ≤ 255 a ∈ [0,1]			Oper	ands:	0 ≤ f ≤ 255 a ∈ [0,1]		
Operation:	(f) – (W),			•				
operation	skip if (f) >	(W)		Operation:		(f) – (W), skip if (f) < (W)		
		comparison)				• • • • • • • • • • • • • • • • • • • •	omparison)	
Status Affected:	None			Statu	s Affected:	None		
Encoding:	0110 010a ffff ffff		ff ffff		Encoding:			
Description:	Compares	the contents o	f data mem-		•	0110	000a ffi	
·		i 'f' to the cont ng an unsigne	ents of the W d subtraction.	Desc	ription:	ory location	the contents o 'f' to the cont an unsigned s	ents of W by
		nts of 'f' are gr					0	
		WREG, then t					nts of 'f' are le W, then the fe	
		is discarded an Istead, making					s discarded a	
	two-cycle in	-				executed in two-cycle in	stead, making	g this a
		he Access Bar					ne Access Bar	nk is calented
	GPR bank	、 ,					ne BSR is use	
		nd the extend		Word	ls.	1	, , , , , , , , , , , , , , , , , , ,	
		ed, this instruc Literal Offset A		Cycle		1(2)		
		never $f \le 95$ (5)	•	Cyck		. ,	cles if skip ar	nd followed
	Section 27	.2.3 "Byte-Or	iented and				a 2-word instru	
		d Instruction		QC	vcle Activity:			
		set Mode" for	details.		Q1	Q2	Q3	Q4
Words:	1				Decode	Read	Process	No
Cycles:	1(2) Note: 3 c	cycles if skip a	nd followod			register 'f'	Data	operation
		a 2-word instr		lf sk	ip:			
Q Cycle Activity:	- ,				Q1	Q2	Q3	Q4
Q1	Q2	Q3	Q4		No	No	No	No
Decode	Read	Process	No		operation	operation	operation	operation
	register 'f'	Data	operation	IT SK	•	d by 2-word in		04
lf skip:					Q1	Q2	Q3	Q4 No
Q1	Q2	Q3	Q4		No operation	No operation	No operation	operation
No operation	No operation	No operation	No operation		No	No	No	No
If skip and followe			operation		operation	operation	operation	operation
Q1	Q2	Q3	Q4					
No	No	No	No	Exan	nple:	HERE	CPFSLT REG,	1
operation	operation	operation	operation			NLESS	:	
No	No	No	No			LESS	:	
operation	operation	operation	operation		Before Instruc	ction		
Example:	HERE	CPFSGT RE			PC W	= Ad = ?	dress (HERE	)
<u>Example.</u>	NGREATER		10, 0		After Instruction	•		
	GREATER	:			If REG	< W:		
Before Instruc	tion				PC If REG		dress (LESS	)
PC W	= ?	dress (HERE	)		PC		dress (NLES	S)
After Instructio								
If REG	> W; = Ad	dress (grea	ጥፑዮ)					
Ρι.								
PC If REG PC	≤ W;							

DAW	Decimal A	djust W Regis	ter	DECF	Decrement	tf			
Syntax:	DAW			Syntax:	DECF f{,c	d {,a}}			
Operands: Operation:	None If [W<3:0> > 9] or [DC = 1] then, (W<3:0>) + 6 $\rightarrow$ W<3:0>;		Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$					
	(W<3.0>) + else,	$0 \rightarrow VV < 3.0^{>},$		Operation:	• • •				
	(W<3:0>) –	→ W<3:0>		Status Affected:	C, DC, N, C				
	If [\\/<7·4>	> 9] or [C = 1]	then	Encoding:	0000	01da ff	ff ffff		
	•	$6 \rightarrow W < 7:4>,$	uicii,	Description:	result is sto	register 'f'. If red in W. If 'd red back in re	l' is '1', the		
Status Affected: Encoding: Description:	C DAW adjusts the eight-bit value in W,		ng: 0000 0000 0000 0111		If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).				
Words:	resulting fro variables (e	om the earlier a each in packed es a correct pa	ddition of two BCD format)		set is enabl in Indexed mode wher <b>Section 27</b>	ed, this instru Literal Offset never f ≤ 95 (5 . <b>2.3 "Byte-O</b>	Fh). See riented and		
Cycles:	1					ed Instruction set Mode" for	ns in Indexed		
Q Cycle Activity:	•			Words:	1		dotano.		
Q1	Q2	Q3	Q4	Cycles:	1				
Decode	Read	Process	Write	Q Cycle Activity:	·				
	register W	Data	W	Q1	Q2	Q3	Q4		
Example 1:	DAW			Decode	Read register 'f'	Process Data	Write to destination		
Before Instruc W C DC After Instructi W C DC	= A5h = 0 = 0			Example: Before Instru CNT Z After Instruct CNT	DECF ( ction = 01h = 0	CNT, 1, (			
Example 2: Before Instruct W C DC After Instructi W C DC	= CEh = 0 = 0			Z	= 00n = 1				

DEC	FSZ	Decrement	f, Skip if 0				
Synta	ax:	DECFSZ f	<sup>-</sup> {,d {,a}}				
Oper	ands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d  \in  [0,1] \\ a  \in  [0,1] \end{array}$					
Oper							
Status Affected: None							
Enco	ding:	0010	11da fff	f ffff			
Desc	ription:	decremente placed in W	The contents of register 'f' are decremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).				
		which is alread	is '0', the nex eady fetched i s executed ins le instruction.	s discarded			
		,	ne Access Bar ne BSR is use (default).				
		set is enabl in Indexed I mode when Section 27 Bit-Oriente	nd the extended ed, this instruct Literal Offset A ever $f \le 95$ (50 .2.3 "Byte-Or id Instruction set Mode" for	ction operates Addressing Fh). See <b>iented and</b> <b>s in Indexed</b>			
Word	ls:	1					
Cycle	es:	•	cles if skip an 2-word instru				
QC	ycle Activity:						
	Q1	Q2	Q3	Q4			
	Decode	Read register 'f'	Process Data	Write to destination			
lf sk	ip <sup>.</sup>	Tegister T	Dala	uesunation			
	Q1	Q2	Q3	Q4			
	No	No	No	No			
	operation	operation	operation	operation			
lf sk	-	d by 2-word in					
	Q1	Q2	Q3	Q4			
	No operation	No	No	No			
	No	operation No	operation No	operation No			
	operation	operation	operation	operation			
<u>Exan</u>	<u>nple:</u>	HERE	DECFSZ GOTO	CNT, 1, 1 LOOP			
	Before Instruc PC	CONTINUE tion = Address	G (HERE)				
	After Instructio	, 1441 000					
	If CNT	= 0;		\ \			
	PC If CNT	<ul> <li>= Address</li> <li>≠ 0;</li> </ul>	G (CONTINUE	)			
	PC	= Address	6 (HERE + 2	)			

DCF	SNZ	Decrement	t f, Skip if not	0				
Synta	ax:	DCFSNZ	f {,d {,a}}					
	ands:	$0 \le f \le 255$						
		d ∈ [0,1] a ∈ [0,1]						
Oper	ation:	(f) $-1 \rightarrow \text{dest}$ , skip if result $\neq 0$						
Statu	is Affected:	None						
	oding:	0100						
	0							
Desc	cription:	decremente placed in W	The contents of register 'f' are decremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).					
		instruction v discarded a	is not '0', the which is alreac and a NOP is e aking it a two-c	ly fetched is cecuted				
			he Access Bar he BSR is used (default).					
		set is enabl in Indexed I mode when Section 27 Bit-Oriente	nd the extende ed, this instruct Literal Offset A never $f \le 95$ (51 .2.3 "Byte-Oried Instruction set Mode" for	ction operates addressing Fh). See iented and s in Indexed				
Word	ds:	1						
Cycle	es:		ycles if skip ar a 2-word instri					
QC	ycle Activity:							
	Q1	Q2	Q3	Q4				
	Decode	Read register 'f'	Process Data	Write to destination				
lf sk	in:	register i	Data	destination				
ii on	Q1	Q2	Q3	Q4				
	No	No	No	No				
	operation	operation	operation	operation				
lf sk	ip and followe	5	struction:					
	Q1	Q2	Q3	Q4				
	No	No operation	No	No				
	operation No	No	operation No	operation No				
	operation	operation	operation	operation				
<u>Exan</u>	Example: HERE DCFSNZ TEMP, 1, 0 ZERO : NZERO :							
	Before Instruc TEMP	tion =	?					
	After Instructio		TEMP					
	TEMP If TEMP	=	TEMP – 1, 0;					
	PC If TEMP	<b>=</b> <i>→</i>	Address (2	ZERO)				
	PC	≠ =	0; Address (1	NZERO)				

GOT	0	Unconditi	Unconditional Branch				
Synta	ax:	GOTO k	GOTO k				
Oper	ands:	$0 \le k \le 10^4$	$0 \leq k \leq 1048575$				
Oper	ation:	$k \rightarrow PC<2$	$k \rightarrow PC < 20:1 >$				
Statu	s Affected:	None					
	ding: ord (k<7:0>) vord(k<19:8>)	1110 1111	1111 k <sub>19</sub> kkk	k <sub>7</sub> kk kkk		kkkk <sub>0</sub> kkkk <sub>8</sub>	
2030	Description: GOTO allows an unconditional branch anywhere within entire 2-Mbyte mem- ory range. The 20-bit value 'k' is loaded into PC<20:1>. GOTO is always a two-cycle instruction.						
Word	ls:	2					
Cycle	es:	2					
QC	ycle Activity:						
	Q1	Q2	Q	Q3		Q4	
	Decode	Read literal 'k'<7:0>,	No operat		'k'<	nd literal <19:8>, te to PC	
	No operation	No operation	No operat		ор	No eration	
Exam	n <u>ple:</u> After Instructio PC =	GOTO THE on Address (1					

INCF	Increment	f				
Syntax:	INCF f{,	d {,a}}				
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$					
Operation:	(f) + 1 $\rightarrow$ d	(f) + 1 $\rightarrow$ dest				
Status Affected:	C, DC, N, OV, Z					
Encoding:	0010	10da	ffff	ffff		
Description:	incremente placed in V	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).				
	If 'a' is '0', t If 'a' is '1', t GPR bank	the BSR i	s used to			
	11 a 13 0 a	and the e	xtended	instruction		
	set is enab in Indexed mode when Section 27 Bit-Oriente Literal Off	led, this i Literal O never f ≤ 7.2.3 "By ed Instru	nstructio ffset Ado 95 (5Fh) te-Orien ictions i	n operate Iressing J. See Ited and Indexee		
Words:	set is enab in Indexed mode when Section 27 Bit-Oriente	led, this i Literal O never f ≤ 7.2.3 "By ed Instru	nstructio ffset Ado 95 (5Fh) te-Orien ictions i	n operate Iressing J. See Ited and Indexee		
Words: Cycles:	set is enab in Indexed mode when Section 27 Bit-Oriento Literal Off	led, this i Literal O never f ≤ 7.2.3 "By ed Instru	nstructio ffset Ado 95 (5Fh) te-Orien ictions i	n operate Iressing J. See Ited and Indexee		
Cycles:	set is enab in Indexed mode when Section 27 Bit-Orient Literal Off	led, this i Literal O never f ≤ 7.2.3 "By ed Instru	nstructio ffset Ado 95 (5Fh) te-Orien ictions i	n operate Iressing J. See Ited and Indexee		
	set is enab in Indexed mode when Section 27 Bit-Orient Literal Off	led, this i Literal O never f ≤ 7.2.3 "By ed Instru	nstructio ffset Adc 95 (5Fh) <b>te-Orien</b> Ictions i e" for de	Iressing See Ited and Indexed		
Cycles: Q Cycle Activity:	set is enab in Indexed mode when Section 27 Bit-Oriente Literal Off 1	led, this i Literal O never f ≤ 7.2.3 "By ed Instru set Mode	nstructio ffset Adc 95 (5Fh) <b>te-Orien</b> <b>icctions i</b> <b>e</b> " for de	n operate Iressing ). See Ited and n Indexed tails.		
Cycles: Q Cycle Activity: Q1	set is enab in Indexed mode when Section 27 Bit-Oriente Literal Off 1 1 2 Q2 Read	led, this i Literal O never f ≤ 7.2.3 "By ed Instru set Mode Q3 Proce Data	nstructio ffset Adc 95 (5Fh) <b>te-Orien</b> <b>icctions i</b> <b>e</b> " for de	n operate Iressing ). See Ited and n Indexed tails. Q4 Write to		

INCF	SZ	Increment	Increment f, Skip if 0					
Synta	ax:	INCFSZ f	{,d {,a}}					
Opera	ands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d \in [0,1] \\ a \in [0,1] \end{array}$	-					
Oper	ation:	.,	(f) + 1 $\rightarrow$ dest, skip if result = 0					
Statu	s Affected:	None						
Enco	ding:	0011	11da fff	f ffff				
Desc	ription:	incremented placed in W	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f'. (default)					
		which is alread	is '0', the next eady fetched is s executed ins le instruction.	s discarded				
		-	ne Access Ban ne BSR is useo (default).					
		set is enable in Indexed I mode when Section 27 Bit-Oriente	nd the extended ed, this instruct Literal Offset A ever $f \le 95$ (5F 2.3 "Byte-Ori d Instruction at Mode" for	tion operates addressing Fh). See <b>iented and</b> <b>s in Indexed</b>				
Word	s:	1						
Cycle	es:		ycles if skip a a 2-word instr					
QC	ycle Activity:							
	Q1	Q2	Q3	Q4				
	Decode	Read	Process	Write to				
16 - 14		register 'f'	Data	destination				
lf sk	ip: Q1	Q2	Q3	Q4				
	No	No	No	No				
	operation	operation	operation	operation				
lf sk	ip and followe	d by 2-word ins	struction:					
	Q1	Q2	Q3	Q4				
	No	No	No	No				
	operation	operation	operation	operation				
	No operation	No operation	No operation	No operation				
	operation	operation	operation	operation				
<u>Exan</u>	<u>nple:</u>	HERE I NZERO : ZERO :		т, 1, 0				
	Before Instruc PC After Instructic	= Address	G (HERE)					
	CNT If CNT	= CNT + 1 = 0;						
	PC If CNT	<ul> <li>Address</li> <li>≠ 0;</li> </ul>						
	PC	= Address	(NZERO)					

INFS	NZ	Increment f	nt f, Skip if not 0				
Synta	ax:	INFSNZ f	{,d {,a}}				
Oper	ands:	$0 \leq f \leq 255$	$0 \le f \le 255$				
		$d \in [0,1]$					
		a ∈ [0,1]					
Oper	Operation: $(f) + 1 \rightarrow dest$ ,						
	skip if result ≠ 0						
Status Affected: None							
Enco	oding:	0100	10da fff	f fff			
Desc	cription:	The content	s of register 'f	' are			
		placed in W	l. If 'd' is '0', th . If 'd' is '1', th ∶in register 'f'	e result is			
			is not '0', the I				
		instruction w discarded an instead, mal	which is alread nd a NOP is ex king it a two-c	ly fetched is cecuted			
		instruction.					
		, -	e Access Ban e BSR is used default).				
		set is enable	nd the extende	tion operates			
			iteral Offset A	•			
			ever f ≤ 95 (5⊦ <b>2.3 "Byte-Or</b> i				
			d Instruction				
			et Mode" for				
Word	ds:	1					
Cycle	es.	1(2)					
- )		• •	cles if skip an	d followed			
		by a	2-word instru	ction.			
QC	ycle Activity:						
	Q1	Q2	Q3	Q4			
	Decode	Read	Process	Write to			
		register 'f'	Data	destination			
lf sk	ip:						
	Q1	Q2	Q3	Q4			
	No	No	No	No			
	operation	operation	operation	operation			
lf sk	ip and followe	d by 2-word ins	struction:				
	Q1	Q2	Q3	Q4			
	No	No	No	No			
	operation	operation	operation	operation			
	No	No	No	No			
	operation	operation	operation	operation			
<u>Exan</u>	nple:	HERE I ZERO NZERO	NFSNZ REG	<b>,</b> 1 <b>,</b> 0			
	Before Instruc	tion					
	PC		(HERE)				
	After Instructio						
	REG If REG	= REG + 1 ≠ 0;					
	PC	= Address	(NZERO)				
	10 0 0 0	<u>^</u>					
	If REG PC	= 0; = Address	(ZERO)				
	lf REG PC		(ZERO)				

IORI	W	Inclusive	Inclusive OR Literal with W					
Synt	ax:	IORLW k	IORLW k					
Oper	ands:	$0 \le k \le 25$	$0 \le k \le 255$					
Oper	ration:	(W) .OR. k	(W) .OR. $k \rightarrow W$					
Statu	is Affected:	N, Z						
Enco	oding:	0000	1001	kkkk	kkkk			
Desc	cription:	The contents of W are ORed with the eight-bit literal 'k'. The result is placed in W.						
Word	ds:	1						
Cycle	es:	1						
QC	ycle Activity:							
	Q1	Q2	Q	3	Q4			
	Decode	Read literal 'k'	Proce Dat		Write to W			
Exar	<u>nple:</u>	IORLW	35h					
	Before Instruc W	= 9Ah						

After Instruction W = BFh

IORWF	Inclusive C	R W with	f	
Syntax:	IORWF f	{,d {,a}}		
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d  \in  [0,1] \\ a  \in  [0,1] \end{array}$			
Operation:	(W) .OR. (f)	$\rightarrow$ dest		
Status Affected:	N, Z			
Encoding:	0001	00da	ffff	ffff
Description:	Inclusive O '0', the resu the result is (default).	lt is placed	d in W. I	f 'd' is '1',
	lf 'a' is '0', th If 'a' is '1', th GPR bank (	ne BSR is i		
	If 'a' is '0' a set is enabl in Indexed I mode when Section 27 Bit-Oriente Literal Offs	ed, this ins ∟iteral Offs ever f ≤ 98 .2.3 "Byte d Instruct	etruction et Addr 5 (5Fh). - <b>Orient</b> tions in	operates essing See ed and Indexed
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q3		Q4
Decode	Read register 'f'	Process Data		Vrite to stination
Example: Before Instruc RESULT W After Instructio RESULT W	tion = 13h = 91h on	ESULT, O	, 1	

DS39931C-page 454

LFSF	र	Load FSR				
Synta	ax:	LFSR f, k				
Oper	ands:	$\begin{array}{l} 0 \leq f \leq 2 \\ 0 \leq k \leq 409 \end{array}$	95			
Oper	ation:	$k\toFSRf$				
Statu	s Affected:	None				
Enco	oding:	1110 1111				
Description: The 12-bit literal 'k' is loaded into the file select register pointed to by 'f'.						
Word	ls:	2				
Cycles: 2						
QC	ycle Activity:					
	Q1	Q2	Q3		Q4	
	Decode	Read literal 'k' MSB	Proce Data		Write literal 'k' MSB to FSRfH	
	Decode	Read literal 'k' LSB	Proce Data		Vrite literal ‹' to FSRfL	
Exan	nple:	LFSR 2,	3ABh			
	After Instructi FSR2H FSR2L	on = 03 = AE				

мον	/F	Move f			
Synt	ax:	MOVF f{	,d {,a}}		
Oper	rands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d  \in  [0,1] \\ a  \in  [0,1] \end{array}$			
Oper	ration:	$f \to \text{dest}$			
Statu	is Affected:	N, Z			
Enco	oding:	0101	00da fff	f ffff	
Desc	cription:	to a destina status of 'd' placed in W placed bac Location 'f'	The contents of register 'f' are moved to a destination dependent upon the status of 'd'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). Location 'f' can be anywhere in the 256-byte bank.		
		If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).			
		set is enabl in Indexed mode wher Section 27 Bit-Oriente	nd the extende ed, this instruc Literal Offset A never f ≤ 95 (5f .2.3 "Byte-Ori ed Instruction set Mode" for	tion operates addressing Th). See ented and s in Indexed	
Word	ds:	1			
Cycle	es:	1			
QC	ycle Activity:				
	Q1	Q2	Q3	Q4	
	Decode	Read register 'f'	Process Data	Write W	
<u>Exar</u>	<u>nple:</u>		EG, 0, 0		
	Before Instruct REG W	tion = 22 = FF			
	After Instructio REG W	n = 22 = 22			

MOVFF	Move f to f			
Syntax:		,f <sub>d</sub>		
Operands:	$\begin{array}{l} 0 \leq f_{s} \leq 409 \\ 0 \leq f_{d} \leq 409 \end{array}$			
Operation:	$(f_s) \to f_d$			
Status Affected:	None			
Encoding: 1st word (source) 2nd word (destin.)	1100 1111	ffff ffff	ffff ffff	ffff <sub>s</sub> ffff <sub>d</sub>
Description:	The contents of source register ' $f_s$ ' are moved to destination register ' $f_d$ '. Location of source ' $f_s$ ' can be anywhere in the 4096-byte data space (000h to FFFh) and location of destination ' $f_d$ ' can also be anywhere from 000h to FFFh.			
	Either source or destination can be W (a useful special situation).			
	MOVFF is p transferring a periphera transmit bu	a data r I registe	nemory lo (such as	cation to the
	The MOVFE PCL, TOSU destination	J, TOSH		
Words:	2			
Cycles:	2			
Q Cycle Activity:				
Q1	Q2	Q	3	Q4
Decode	Read register 'f' (src)	Proce Data		No peration
Decode	No operation No dummy read	No operat	ion re	Write gister 'f' (dest)

Before Instruction		
REG1	=	33h
REG2	=	11h
After Instruction		
REG1	=	33h
REG2	=	33h

MOVLB	Move Literal to Low Nibble in BSR				
Syntax:	MOVLW	k			
Operands:	$0 \le k \le 255$	5			
Operation:	$k \to BSR$	$k \rightarrow BSR$			
Status Affected:	None				
Encoding:	0000	0001	kkk	k	kkkk
Description:	The eight-I Bank Select of BSR<7: regardless	ct Registe 4> alway	er (BSI s rema	R). T ains	<b>he value</b> '0'
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q	3		Q4
Decode	Read literal 'k'	Proce Dat			te literal to BSR
Example:	MOVLB	5			
Before Instruct	ion				

02h

05h

BSR Register =

BSR Register =

After Instruction

DS39931C-page 456

MOVLW Move Literal to W						
Synta	ax:	MOVLW	k			
Oper	ands:	$0 \le k \le 25$	5			
Oper	ation:	$k\toW$				
Status Affected: None						
Enco	ding:	0000	1110	kkk	k	kkkk
Desc	ription:	The eight-bit literal 'k' is loaded into W.				
Word	ls:	1				
Cycle	es:	1				
QC	ycle Activity:					
	Q1	Q2	Q3	6		Q4
	Decode	Read literal 'k'	Proce Data		W	/rite to W
<u>Exan</u>	nple:	MOVLW	5Ah			
	After Instructic W	on = 5Ah				

MOVWF	Move W to f				
Syntax:	MOVWF f {,a}				
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ a \ \in \ [0,1] \end{array}$				
Operation:	$(W) \rightarrow f$				
Status Affected:	None				
Encoding:	0110 111a ffff fff				
Description:	Move data from W to register 'f'. Location 'f' can be anywhere in the 256-byte bank.				
	If 'a' is '0', the Access Bank is selected If 'a' is '1', the BSR is used to select th GPR bank (default).				
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2 Q3 Q4				
Decode	ReadProcessWriteregister 'f'Dataregister 'f'				
Example:	MOVWF REG, 0				
Before Instruc W REG	= 4Fh = FFh				
After Instructio W REG	n = 4Fh = 4Fh				

MULLW	Multiply Li	iteral with W		MULWF	Multiply W w	vith f	
Syntax:	MULLW	k		Syntax:	MULWF f {	,a}	
Operands:	$0 \le k \le 255$	5		Operands:	$0 \leq f \leq 255$		
Operation:	(W) x k $\rightarrow$	PRODH:PRO	DL		a ∈ [0,1]		
Status Affected:	None			Operation:	$(W) x (f) \to P$	(W) x (f) $\rightarrow$ PRODH:PRODL	
Encoding:	0000	1101 kk	kk kkkk	Status Affected:	None		
Description:	An unsigne	ed multiplication	n is carried	Encoding:	0000	001a ffi	ff ffff
	8-bit literal placed in P	'k'. The 16-bit RODH:PROD ontains the hig	L register pair.	Description:	between the register file lo stored in the	PRODH:PRO	and the 16-bit result is
	None of the	e Status flags	are affected.			Status flags are	e affected
	possible in		w nor Carry is . A Zero result ed.		Note that neit	her Overflow is operation. A	
Words:	1				•		is selected. If
Cycles: Q Cycle Activity:	1				,	BSR is used to	
Q1 Decode	Q2 Read literal 'k'	Q3 Process Data	Q4 Write registers PRODH: PRODL		is enabled, th Indexed Liter whenever f ≤ Section 27.2 Bit-Oriented	the extended is instruction of al Offset Addr 95 (5Fh). See .3 "Byte-Orie Instructions t Mode" for d	essing mode nted and in Indexed
Example:	MULLW	0C4h		Words:	1		elans.
Before Instruc				Cycles:	1		
W PRODH	= E2 = ?	2h		Q Cycle Activity:			
PRODL	= ?			Q Cycle Activity. Q1	Q2	Q3	Q4
After Instructic W PRODH PRODL	on = E2 = AE = 08	Dh		Decode	Read register 'f'	Process Data	Write registers PRODH: PRODL
				Example: Before Instri W		REG, 1 4h	

Before Instruction		
W	=	C4h
REG	=	B5h
PRODH	=	?
PRODL	=	?
After Instruction		
W	=	C4h
REG	=	B5h
PRODH	=	8Ah
PRODL	=	94h

NEGF	Negate f
Syntax:	NEGF f {,a}
Operands:	0 ≤ f ≤ 255 a ∈ [0,1]
Operation:	$(\overline{f}) + 1 \rightarrow f$
Status Affected:	N, OV, C, DC, Z
Encoding:	0110 110a ffff ffff
Description:	Location 'f' is negated using two's complement. The result is placed in the data memory location 'f'.
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.
Words:	1
Cycles:	1
Q Cycle Activity:	

_	Q1	Q2	Q3	Q4
	Decode	Read	Process	Write
		register 'f'	Data	register 'f'

Example:	NEGF	REG,	1
----------	------	------	---

Before Instruc	ction			
REG	=	0011	1010	[3Ah]
After Instructi	on			
REG	=	1100	0110	[C6h]

NOP		No Operat	ion				
Synta	ax:	NOP					
Oper	ands:	None	None				
Oper	ation:	No operati	No operation				
Statu	s Affected:	None					
Enco	ding:	0000	0000	000	0	0000	
		1111	XXXX	XXX	XX	XXXX	
Desc	ription:	No operati	on.				
Word	ls:	1					
Cycle	es:	1					
QC	ycle Activity:						
	Q1	Q2	Q	3		Q4	
	Decode	No	No			No	
		operation	operat	tion	op	peration	

Example:

None.

POP	Рор Тор о	Top of Return Stack			
Syntax:	POP				
Operands:	None				
Operation:	$(TOS) \rightarrow b$	it bucket			
Status Affected:	None				
Encoding:	0000	0000	0000	0110	
Description:	stack and i then becon was pushe This instruc the user to	The TOS value is pulled off the return stack and is discarded. The TOS value then becomes the previous value tha was pushed onto the return stack. This instruction is provided to enable the user to properly manage the return stack to incorporate a software stack.			
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q3		Q4	
Decode	No operation	POP TO value		No peration	
Example:	POP GOTO	NEW			
Before Instru TOS Stack (1	ction level down)		)31A2h  4332h		
After Instruct TOS PC	ion	•	4332h EW		

PUSI	4	Push Top o	of Ret	urn Stac	:k	
Synta	ax:	PUSH				
Oper	ands:	None				
Oper	ation:	$(PC + 2) \rightarrow$	TOS			
Statu	s Affected:	None				
Enco	ding:	0000	0000	000	0	0101
Desc	ription:	The PC + 2 the return s value is pus This instruc software sta then pushin	tack. shed c tion a ack by	The prev lown on llows imp modifyir	ious the ៖ blem ng T	TOS stack. enting a OS and
Word	s:	1				
Cycle	es:	1				
QC	cle Activity:					
	Q1	Q2		Q3		Q4
	Decode	PUSH PC + 2 onto return stack		No ration	ор	No eration
Exam	<u>iple:</u>	PUSH				
	Before Instruc TOS	tion	=	345Ah		
	PC		=	0124h		

RCA	LL	Relative Ca	Relative Call			
Synta	ax:	RCALL n	RCALL n			
Oper	ands:	-1024 ≤ n ≤	$-1024 \le n \le 1023$			
Oper	ation:	• •	$(PC) + 2 \rightarrow TOS,$ (PC) + 2 + 2n $\rightarrow$ PC			
Statu	s Affected:	None				
Enco	ding:	1101	1nnn	nnn	n	nnnn
Desc	ription: Is:	Subroutine from the cu address (PC stack. Then number '2n will have ind instruction, PC + 2 + 2r two-cycle in	rrent loc C + 2) is , add the ' to the F crement the new n. This ir	ation. pushe e 2's c PC. Sir ed to f addre	First ed or omp nce f etch ss v	t, return nto the blement the PC the next vill be
Cycle		2				
	ycle Activity:	-				
	Q1	Q2	Q	3		Q4
	Decode	Read literal 'n' PUSH PC to stack	Proce Dat		Wri	te to PC
	No operation	No operation	No opera		ор	No eration

RESET	Reset				
Syntax:	RESET				
Operands:	None	None			
Operation:		Reset all registers and flags that are affected by a MCLR Reset.			
Status Affected:	All				
Encoding:	0000	0000	1111	L	1111
Description:	This instruction provides a way to execute a MCLR Reset in software.				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q	3	C	Q4
Decode	Start	No			lo
	reset	operat	tion	oper	ation

Example:

After	Instruction
Allel	mstruction

Registers =	Reset Value
Flags* =	Reset Value

RESET

Example: HERE RCALL Jump

Before Instruction

PC = Address (HERE) After Instruction PC = Address (Jump) TOS = Address (HERE + 2)

© 2009 Microchip Technology Inc.

RET	FIE	Return fro	Return from Interrupt				
Synta	ax:	RETFIE {	s}				
Oper	ands:	$s \in [0,1]$					
Oper	ation:	if s = 1, (WS) $\rightarrow$ W (STATUSS (BSRS) $\rightarrow$	$1 \rightarrow \text{GIE/GIEH}$ or PEIE/GIEL;				
Statu	s Affected:	GIE/GIEH,	PEIE/GI	EL.			
Enco	ding:	0000	0000	000	1 000s		
Desc	ription:	and Top-of- the PC. Intr setting eith global inter contents of STATUSS their corres	-Stack (T errupts a er the hig rupt enai f the shad and BSR sponding nd BSR.	OS) is re enal gh or lo ble bit. dow reg S are l registe If 's' =	ow-priority If 's' = 1, the gisters WS, loaded into ers W, 0, no update		
Word	ls:	1	-				
Cycle	es:	2					
	ycle Activity:						
	Q1	Q2	Q	3	Q4		
	Decode	No operation	No opera	tion	POP PC from stack Set GIEH or GIEL		
	No	No	No		No		
	operation	operation	opera	uon	operation		
<u>Exan</u>	nple: After Interrupt PC W BSR STATUS	RETFIE	= \ = E	TOS WS BSRS STATU	SS		
	GIE/GIEł	H, PEIE/GIEL	= ^	1			

<: nds: tion: Affected: ling: iption: ::	RETLW k $0 \le k \le 255$ $k \rightarrow W$ , (TOS) $\rightarrow P$ PCLATU, P None 0000 W is loaded The program the top of the address). T (PCLATH) m 1 2	1100 1 with the em counter the stack (the high ac	kkkk eight-bit is loade the return ddress la	kkkk literal 'k'. d from n atch		
tion: Affected: ing: ption: ::	$k \rightarrow W$ , $(TOS) \rightarrow P$ PCLATU, P None 0000 W is loaded The programent the top of the address). T (PCLATH) = 1	1100 1 with the em counter the stack (the high ac	kkkk eight-bit is loade the return ddress la	kkkk literal 'k'. d from n atch		
Affected: ling: iption: ::	$(TOS) \rightarrow P$ PCLATU, P None 0000 W is loaded The prograther the top of the address). T (PCLATH) m 1	1100 1 with the em counter the stack (the high ac	kkkk eight-bit is loade the return ddress la	kkkk literal 'k'. d from n atch		
ing: iption: ::	0000 W is loaded The prograthe top of the address). T (PCLATH) n	d with the e m counter ne stack (the he high ac	eight-bit is loade he returi ddress la	literal 'k'. ed from n atch		
iption:	W is loaded The program the top of th address). T (PCLATH) n 1	d with the e m counter ne stack (the he high ac	eight-bit is loade he returi ddress la	literal 'k'. ed from n atch		
;; ;; 3;	The program the top of th address). T (PCLATH) n 1	m counter ne stack (tl he high ac	is loade he returi ddress la	ed from n atch		
S:	-					
	2					
			2			
cle Activity:						
Q1	Q2	Q3		Q4		
Decode	Read literal 'k'	Proces Data	fro	OP PC m stack, ite to W		
No operation	No operation	No operatio	on op	No peration		
<b>de:</b> Pall Table	; offset v ; W now ha	value as	Le			
	No operation	Decode Read literal 'k' No No operation operation ALL TABLE ; W conta: ; offset v ; W now ha ; table va	Decode     Read literal 'k'     Process Data       No     No     No operation       No     No     operation       operation     operation     operation       ALL TABLE     ; W contains table     ; offset value       ; W now has     ; table value	Decode     Read literal 'k'     Process Data     P fro wr       No     No     No       operation     operation     operation       ALL TABLE     ; W contains table       ; offset value       ; W now has       ; table value		

```
:
TABLE
ADDWF PCL ; W = offset
RETLW k0 ; Begin table
RETLW k1 ;
:
RETLW kn ; End of table
```

#### Before Instruction

W	=	07h
After Instruc	tion	
W	=	value of kn

RETI	JRN	Return from	n Subroutine	•			
Synta	ax:	RETURN	{s}				
Oper	ands:	$s \in [0,1]$					
Oper	eration: $(TOS) \rightarrow PC;$ if s = 1, $(WS) \rightarrow W,$ $(STATUSS) \rightarrow STATUS,$ $(BSRS) \rightarrow BSR,$ PCLATU, PCLATH are unchanged						
Statu	s Affected:	None					
Enco	ding:	0000	0000 00	01 001s			
Dest	ription:	is loaded in 's'= 1, the c registers W loaded into registers W 's' = 0, no u	popped and the top of the stack (TOS) is loaded into the program counter. If 's'= 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers W, STATUS and BSR. If 's' = 0, no update of these registers occurs (default).				
Word	s:	1	1				
Cycle	es:	2	2				
QC	ycle Activity:						
	Q1	Q2	Q3	Q4			
	Decode	No operation	Process Data	POP PC from stack			
	No operation	No operation	No operation	No operation			
Exam	n <u>ple:</u> After Instructio PC = TC						

RLCF	Rotate Left f through Carry						
Syntax:	RLCF f {,d {,a}}						
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d  \in  [0,1] \\ a  \in  [0,1] \end{array}$						
Operation:	$(f < n >) \rightarrow dest < n + 1 >,$ $(f < 7 >) \rightarrow C,$ $(C) \rightarrow dest < 0 >$						
Status Affected:	C, N, Z						
Encoding:	0011 01da ffff f	fff					
Description:	The contents of register 'f' are rotated one bit to the left through the Carry flag. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default).						
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).						
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
Words:	1						
Cycles:	1						
Q Cycle Activity:	I						
Q Cycle Activity. Q1	Q2 Q3 Q4	1					
Decode	Read Process Write register 'f' Data destina						
Example:	RLCF REG, 0, 0						
Before Instruction REG = 1110 0110 C = 0							
After Instructi REG W C	on = 1110 0110 = 1100 1100 = 1						

RLNCF	RLNCF Rotate Left f (No Carry)								
Syntax:	RLNCF	f {,d {,a}}							
Operands:	0 ≤ f ≤ 255 d ∈ [0,1] a ∈ [0,1]								
Operation:	$(f \le n >) \rightarrow d$ $(f \le 7 >) \rightarrow d$	lest <n +="" 1="">, lest&lt;0&gt;</n>							
Status Affected:	N, Z								
Encoding:	0100	0100 01da ffff ffff							
Description:	one bit to t is placed ir	The contents of register 'f' are rotated one bit to the left. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default).							
	selected. It	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).							
	If 'a' is '0' and the extended instruction set is enabled, this instruction oper- ates in Indexed Literal Offset Address- ing mode whenever $f \le 95$ (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.								
	-	register	f 🚽						
Words:	1								
Cycles:	1								
Q Cycle Activity:									
Q1	Q2	Q3	Q4						
Decode	Read register 'f'	Process Data	Write to destination						
Example:	RLNCF	REG, 1,	0						
Before Instruction REG = 1010 1011									
After Instructic REG	= 0101 0	0111							

RRCF	Rotate Right f through Carry					
Syntax:	RRCF f{,	d {,a}}				
Operands:	$0 \leq f \leq 255$					
	d ∈ [0,1]					
<b>o</b> <i>u</i>	a ∈ [0,1]					
Operation:	$(f < n >) \rightarrow de$ $(f < 0 >) \rightarrow C$ $(C) \rightarrow dest$	,	L>,			
Status Affected:	C, N, Z					
Encoding:	0011	00da	ffff	ffff		
Description:	The contents of register 'f' are rota' one bit to the right through the Car flag. If 'd' is '0', the result is placed W. If 'd' is '1', the result is placed b in register 'f' (default).					
If 'a' is '0', the Access Bank is selecter If 'a' is '1', the BSR is used to select t GPR bank (default).						
	cot is onabl	od this i		nstructior		
	set is enabl in Indexed mode wher Section 27 Bit-Oriente Literal Offs	Literal O never f ≤ .2.3 "By ed Instru	nstruction ffset Add 95 (5Fh). te-Orient actions in	n operate ressing See ted and Indexee		
	in Indexed mode wher Section 27 Bit-Oriente	Literal O never f ≤ .2.3 "By ed Instru set Mode	nstruction ffset Add 95 (5Fh). te-Orient actions in	n operates ressing See ted and Indexec		
Words:	in Indexed mode wher Section 27 Bit-Oriente Literal Offs	Literal O never f ≤ .2.3 "By ed Instru set Mode	nstructior ffset Add 95 (5Fh). te-Orient actions in e" for det	n operate ressing See ted and Indexee		
	in Indexed mode wher Section 27 Bit-Oriente Literal Offs	Literal O never f ≤ .2.3 "By ed Instru set Mode	nstructior ffset Add 95 (5Fh). te-Orient actions in e" for det	n operates ressing See ted and Indexec		
Cycles:	in Indexed mode wher Section 27 Bit-Oriente Literal Offs	Literal O never f ≤ .2.3 "By ed Instru set Mode	nstructior ffset Add 95 (5Fh). te-Orient actions in e" for det	n operate ressing See ted and Indexee		
	in Indexed mode wher Section 27 Bit-Oriente Literal Offs	Literal O never f ≤ .2.3 "By ed Instru set Mode	nstructior ffset Addi 95 (5Fh). <b>te-Orient</b> actions ir e" for det egister f	n operate ressing See ted and Indexee		
Cycles: Q Cycle Activity:	in Indexed mode wher Section 27 Bit-Oriente Literal Offs 1 1 1 2 Q2 Read	Literal O never f ≤ .2.3 "By d Instru- set Mode → re Q3 Proce	nstruction ffset Addi 95 (5Fh). te-Orient actions in e" for det egister f	operate ressing See ted and Indexed ails. Q4 Write to		
Q Cycle Activity: Q1	in Indexed mode wher Section 27 Bit-Oriente Literal Offs 1 1 2 2	Literal O never f ≤ .2.3 "By d Instru set Mode re re	nstruction ffset Addi 95 (5Fh). te-Orient actions in e" for det egister f	Q4		
Cycles: Q Cycle Activity: Q1 Decode	in Indexed mode wher Section 27 Bit-Oriente Literal Offs C 1 1 2 2 Read register 'f'	Literal O lever f ≤ .2.3 "By ded Instru set Mode → re re Q3 Proce Dat	nstruction ffset Addi 95 (5Fh). te-Orient ictions in e" for det egister f ess \ a de	operate ressing See ted and Indexed ails. Q4 Write to		
Cycles: Q Cycle Activity: Q1 Decode Example:	in Indexed mode wher Section 27 Bit-Oriente Literal Offs C 1 1 1 2 Q2 Read register 'f'	Literal O lever f ≤ .2.3 "By ded Instru set Mode → re re Q3 Proce Dat	nstruction ffset Addi 95 (5Fh). te-Orient actions in e" for det egister f	operate ressing See ted and Indexed ails. Q4 Write to		
Cycles: Q Cycle Activity: Q1	in Indexed mode wher Section 27 Bit-Oriente Literal Offs C 1 1 1 2 Q2 Read register 'f'	Literal O never f ≤ .2.3 "By ed Instru- set Mode → re Q3 Proce Dat	nstruction ffset Addi 95 (5Fh). te-Orient ictions in e" for det egister f ess \ a de	operate ressing See ted and Indexed ails. Q4 Write to		
Cycles: Q Cycle Activity: Q1 Decode <u>Example:</u> Before Instruc REG	in Indexed mode wher Section 27 Bit-Oriente Literal Offs - C 1 1 1 2 Q2 Read register 'f' RRCF tion = 1110 ( = 0	Literal O never f ≤ .2.3 "By ed Instru- set Mode → re Q3 Proce Dat	nstruction ffset Addi 95 (5Fh). te-Orient ictions in e" for det egister f ess \ a de	operate ressing See ted and Indexed ails. Q4 Write to		

RRN	CF	Rotate R	ight f (No C	arry)				
Synta	ax:	RRNCF	f {,d {,a}}					
Oper	ands:	$0 \le f \le 25$ $d \in [0,1]$ $a \in [0,1]$	5					
Oper	ation:	$(f < n >) \rightarrow dest < n - 1 >,$ $(f < 0 >) \rightarrow dest < 7 >$						
Statu	is Affected:	N, Z						
Enco	oding:	0100 00da ffff ffff						
Desc	cription:	The contents of register 'f' are rotated one bit to the right. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default).						
		If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).						
		If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
		Г	► reg	ister f				
Word	ds:	1						
Cycle		1						
	ycle Activity:							
	Q1	Q2	Q3	Q4				
	Decode	Read register 'f'	Proces Data	s Write to destination				
<u>Exar</u>	nple 1:	RRNCF	REG, 1,	0				
	Before Instruc REG	= 1101	0111					
	After Instructio		1011					
<u>Exan</u>	<u>nple 2:</u>	RRNCF	REG, 0,	0				
	Before Instruc	= ?						
	REG After Instructio	on	0111					
	REG		0111					

SETF	Set f					
Syntax:	SETF f{,;	a}				
Operands:	$0 \leq f \leq 255$					
	a ∈ [0,1]					
Operation:	$FFh\tof$					
Status Affected:	None					
Encoding:	0110 100a ffff ffff					
Description:	The conten are set to F		specified	register		
If 'a' is '0', the Access Bank is sele If 'a' is '1', the BSR is used to sele GPR bank (default).						
If 'a' is '0' and the extended instruction set is enabled, this instruction operate in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
Words:	1					
Cycles:	1					
Q Cycle Activity:						
Q1	Q2	Q	3	Q4		
Decode	Read register 'f'	Proce Data		Write gister 'f'		
Example:	SETF	RE	G <b>,</b> 1			
Before Instruction REG = 5Ah						
After Instructic REG	on = FF	h				

SLEEP	Enter Sle	ep Mode		SUBFWB
Syntax:	SLEEP			Syntax:
Operands:	None			Operands:
Operation:	$00h \rightarrow WE$ $0 \rightarrow WDT$ $1 \rightarrow TO,$ $0 \rightarrow PD$	DT, postscaler,		Operation: Status Affected:
Status Affected:	TO, PD			Encoding:
Encoding:	0000	0000 000	00 0011	Description:
Description:	cleared. T is set. The	r-Down status he Time-out st Watchdog Tir are cleared.	Description.	
	•	ssor is put into scillator stoppe	•	
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q3	Q4	
Decode	No operation	Process Data	Go to Sleep	
Example:	SLEEP			Words:
Before Instruc TO = PD =	tion ? ?			Cycles: Q Cycle Activity: Q1
After Instructio TO = PD =	on 1† 0			Decode
PD = † If WDT causes v	-	oit is cleared.		<u>Example 1:</u> Before Instru REG W C

Syntax:	SUBFWB f	{,d {,a}}				
Operands:	$0 \leq f \leq 255$					
	d ∈ [0,1] a ∈ [0,1]					
Operation:	$(W) - (f) - (\overline{C})$	$\frac{1}{2}$ ) $\rightarrow$ dest				
Status Affected:	N, OV, C, DC					
Encoding:		01da fff	f ffff			
Description:	Subtract regi	ster 'f' and Ca	rry flag			
	method). If 'd	n W (2's compl l' is '0', the resu , the result is s efault).	ult is stored in			
If 'a' is '0', the Access Bank is selected. 'a' is '1', the BSR is used to select the GPR bank (default).						
If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
Words:	1					
Cycles:	1					
Q Cycle Activity:						
Q1	Q2	Q3	Q4			
Decode	Read register 'f'	Process Data	Write to destination			
Example 1:	SUBFWB	REG, 1, 0				
Before Instruc	tion					
REG W C	= 3 = 2 = 1					
After Instruction						
REG W	= FF = 2					
C Z	= 0 = 0					
Ñ		sult is negative	e			
Example 2:	SUBFWB	REG, 0, 0				
Before Instruc REG	tion = 2					
W	= 5					
C After Instructio	= 1 on					
REG	= 2					
W C	= 3 = 1					
Z	= 0	oult is positive				
N Example 3:	= 0 ; re SUBFWB	sult is positive REG, 1, 0				
Before Instruc		100, 1, 0				
REG	= 1					
W C	= 2 = 0					
After Instruction	on					
REG W	= 0 = 2					
С	= 1	out is				
Z N	= 1 ; re = 0	sult is zero				

Subtract f from W with Borrow

SUBLW	S	Subtract W from Literal				
Syntax:	SI	JBLW	k			
Operands:	0	≤ k ≤ 25	5			
Operation:	k٠	– (W) –	→ W			
Status Affected:	N	, OV, C,	DC, Z			
Encoding:		0000	1000	kk}	ck	kkkk
Description:		W is subtracted from the eight-bit literal 'k'. The result is placed in W.				
Words:	Words: 1					
Cycles:	1					
Q Cycle Activity:						
						Q4
Decode		ead ral 'k'	Proces Data		W	/rite to W
Example 1:	St	JBLW	02h			
Before Instruction						
W C	=	01h ?				
After Instructio	n	•				
W C	=	01h 1 :	result is p	neitiv	<u>م</u>	
Z	=	0	result is p	03111	C	
N Evenale 2:	=	0	02h			
Example 2:		JBLW	U∠n			
Before Instruct W	=	02h				
Č	=	?				
After Instructio W	n =	00h				
CZ	=		result is z	ero		
N	=	0				
Example 3:	St	JBLW	02h			
Before Instruct	ion					
W C	=	03h ?				
After Instructio	-	-				
W	=		(2's comp			
C Z	=	0	result is r	legati	ve	
Ν	=	1				

SUBWF	Sub	tract	W 1	from f		
Syntax:	SUBWF f {,d {,a}}					
Operands:	0 ≤ f	≤ 255	5			
	d ∈   a ∈					
Operation:	(f) –	(W) –	→ d	est		
Status Affected:	N, O	V, C,	DC	C, Z		
Encoding:		01	-	11da fff	f ffff	
Description:				rom register 'f'		
Description.	com resu	pleme It is st	ent ore	method). If 'd' ed in W. If 'd' is k in register 'f'	is '0', the '1', the result	
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).					
If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
Words:	1					
Cycles:	1					
Q Cycle Activity:						
Q1	Q2			Q3	Q4	
Decode	R	ead		Process	Write to	
	regi	ster 'f	,	Data	destination	
Example 1:	St	JBWF		REG, 1, 0		
Before Instruct	tion					
REG W	=	3 2 ?				
Č	=	?				
After Instructio	n					
REG W	=	1 2				
C	=	1	; r	esult is positiv	e	
Z	=	0				
Example 2:	SI	JBWF		REG, 0, 0		
Before Instruct				100, 0, 0		
REG	=	2 2				
W C	=	2				
After Instructio	n	•				
REG	=	2				
W C	=	0 1	۰n	esult is zero		
Z	=	1	,.			
N	=	0				
Example 3:		JBWF		REG, 1, 0		
Before Instruct REG	:ion =	1				
W	=	2				
C After Instructio	=	?				
After Instructio REG	n =	FFh	•(*	2's complemer	nt)	
W	=	2		•		
C Z	=	0 0	; r	esult is negativ	/e	
Z N	=	ĩ				

SUBWFB	Subtract W from f with Borrow					
Syntax:	SI	JBWFB	f {,d {,a}	}		
Operands:	0	≤ f ≤ 255	5			
		∈ [0,1]				
		∈ [0,1]	_			
Operation:			$(\overline{C}) \rightarrow de$	st		
Status Affected:	Ν,	OV, C, I	DC, Z			
Encoding:		0101	10da	fff		
Description:	fro m in	om regist ethod). I W. If 'd' i	ter 'f' (2's f 'd' is '0',	completion the reference to the reference to the completion of the	flag (borrow) ement sult is stored s stored back	
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).					
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.					
Words: 1						
Cycles:	1					
Q Cycle Activity:						
Q1		Q2	Q	3	Q4	
Decode		Read	Proce	ess	Write to	
	re	gister 'f'	Dat	а	destination	
Example 1:	:	SUBWFB	REG, 1	L, O		
Before Instruc		401				
REG w	=	19h 0Dh	(000 (000			
С	=	1			,	
After Instructio	on		(000	0 1 0 1	7.)	
REG W	=	0Ch 0Dh		0 101 0 110		
C	=	1 0				
Z N	=	0	; resu	lt is po	ositive	
Example 2:	:	SUBWFB	REG, 0	, 0		
Before Instruc	tion					
REG W C	= = =	1Bh 1Ah 0	(000 (000			
After Instructio REG W	on = =	1Bh 00h	(000	1 101	.1)	
C Z	=	1 1	· resu	lt is ze	ero	
Ň	=	Ó	,			
Example 3:	:	SUBWFB	REG, 1	L, O		
Before Instruc						
REG w	=	03h 0Eh		0 001 0 110	,	
С	=	1	(		_,	
After Instructio REG	on =	EEb	/111	1 010	0.0	
REG	-	F5h		1 010 comp]		
W C	=	0Eh 0	(000	0 110	)1)	
Z N	=	0 1	; resu	lt is ne	egative	

SWAPF	Swap f						
Syntax:	SWAPF f	{,d {,a}}					
Operands:	$0 \leq f \leq 255$						
	d ∈ [0,1] a ∈ [0,1]						
Operation:	(f<3:0>) →	dest<7:4	<b>↓&gt;</b> ,				
	(f<7:4>) →	dest<3:0	)>				
Status Affected:	None						
Encoding:	0011	0011 10da ffff ffff					
Description:	'f' are excha is placed in	The upper and lower nibbles of register 'f' are exchanged. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in register 'f' (default).					
	If 'a' is '0', the Access Bank is selected. If 'a' is '1', the BSR is used to select the GPR bank (default).						
	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.						
Words:	1						
Cycles:	1						
Q Cycle Activity:							
Q1	Q2	Q	3	Q4			
Decode	Read register 'f'	Proce Data		Write to destination			
	register i	Dat	a ['	acounation			
Example:	SWAPF F	EG, 1,	0				
Before Instruc							
REG = 53h After Instruction							
REG	= 35h						

TBL	RD	Table Read					
Synta	ax:	TBLRD (*;	*+; *	-; +*)			
Oper	ands:	None					
Oper	ation:	if TBLRD *, (Prog Mem (TBLPTR)) $\rightarrow$ TABLAT, TBLPTR – No Change; if TBLRD *+, (Prog Mem (TBLPTR)) $\rightarrow$ TABLAT, (TBLPTR) + 1 $\rightarrow$ TBLPTR; if TBLRD *-, (Prog Mem (TBLPTR)) $\rightarrow$ TABLAT, (TBLPTR) – 1 $\rightarrow$ TBLPTR; if TBLRD +*, (TBLPTR) + 1 $\rightarrow$ TBLPTR, (Prog Mem (TBLPTR)) $\rightarrow$ TABLAT					
Statu	s Affected:	None					
Enco	ding:	0000	00	000	000	0	10nn nn=0 * =1 *+ =2 *- =3 +*
Desc	ription:	This instruct of Program program me Pointer (TBI	Men emor	nory (l y, a p	P.M.). <sup>-</sup> ointer (	To ac	dress the
		The TBLPT each byte ir TBLPTR ha	the	progr	am me	emor	у.
		TBLPTR<0>	• = 0				nt Byte of ory Word
		TBLPTR<0>	• = 1				nt Byte of ory Word
		The TBLRD value of TB					y the
		no chang	е				
		<ul> <li>post-increase</li> </ul>	emei	nt			
		<ul> <li>post-decr</li> </ul>	eme	ent			
pre-increment							
Word	ls:	1					
Cycles: 2							
QC	ycle Activity	:					
	Q1	Q2		1	23		Q4
	Decode	No operation		N oper	lo ation	о	No peration

Decode	No	No	No
	operation	operation	operation
No operation	No operation (Read Program Memory)	No operation	No operation (Write TABLAT)

TBLRD	d (Co	ontinued)	
Example 1:	TBLRD *	+;	
Before Instructi TABLAT TBLPTR MEMORY After Instructior	(00A356h)	= = =	55h 00A356h 34h
TABLAT TBLPTR		= =	34h 00A357h
Example 2:	TBLRD +	*;	
	(01A357h) (01A358h)	= = =	01/100/11
TABLAT TBLPTR		=	34h 01A358h

TBLWT	Table Write					
Syntax:	TBLWT ( '	*; *+; *-; +*	r)			
Operands:	None					
Operation:	if TBLWT*, (TABLAT) $\rightarrow$ Holding Register, TBLPTR – No Change; if TBLWT*+, (TABLAT) $\rightarrow$ Holding Register, (TBLPTR) + 1 $\rightarrow$ TBLPTR; if TBLWT*-, (TABLAT) $\rightarrow$ Holding Register, (TBLPTR) – 1 $\rightarrow$ TBLPTR; if TBLWT+*, (TBLPTR) + 1 $\rightarrow$ TBLPTR, (TABLAT) $\rightarrow$ Holding Register					
Status Affected:	None					
Encoding:	0000	0000	0000	11nn nn=0 * =1 *+ =2 *- =3 +*		
Description:						
Words:	<ul> <li>pre-incr</li> <li>1</li> </ul>	ement				
Cycles: Q Cycle Activity:	2					
	Q1	Q2	Q3	Q4		
	Decode	No	No	No operation		
	No		operation No			
	-	No operation (Read TABLAT)	-	No operation (Write to Holding Register)		

### TBLWT Table Write (Continued)

Example 1:	TBLWT	*+

Example 1:	TBLWT *+;		
Before Instru	uction		
TABLA TBLPT HOLDI	-	=	55h 00A356h
(00A35		=	FFh
After Instruc	tions (table write	comp	letion)
TABLA	Т	=	55h
TBLPT	R	=	00A357h
HOLDI	NG REGISTER		
(00A35	56h)	=	55h
Example 2:	TBLWT +*;		
Before Instru	uction		
TABLA	Т	=	34h
TBLPT	R	=	01389Ah
HOLDI	NG REGISTER		
(01389		=	FFh
	NG REGISTER		
(01389	Bh)	=	FFh
After Instruc	tion (table write c	omple	etion)
TABLA	Т	=	34h
TBLPT		=	01389Bh
HOLDI (01389		=	FFh
	NG REGISTER	_	
(01389		=	34h

TSTF	SZ	Test f, Skip	Test f, Skip if 0				
Synta	ax:	TSTFSZ f {	,a}				
Oper	ands:	0 ≤ f ≤ 255 a ∈ [0,1]					
Oper	ation:	skip if f = 0					
Statu	s Affected:	None					
Enco	ding:	0110	011a fff	f fff			
Desc	ription:	during the c is discarded	If 'f' = 0, the next instruction fetched during the current instruction execution is discarded and a NOP is executed, making this a two-cycle instruction.				
		,	he Access Bar he BSR is used (default).				
If 'a' is '0' and the extended instruction set is enabled, this instruction operate in Indexed Literal Offset Addressing mode whenever f ≤ 95 (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed Literal Offset Mode" for details.							
Words: 1							
Cycles: 1(2) Note: 3 cycles if skip and followed by a 2-word instruction.							
QC	ycle Activity:						
	Q1	Q2	Q3	Q4			
	Decode	Read	Process	No			
lf ski	in:	register 'f'	Data	operation			
II SK	φ. Q1	Q2	Q3	Q4			
	No	No	No	No			
	operation	operation	operation	operation			
lf sk	ip and followed	d by 2-word in	struction:				
	Q1	Q2	Q3	Q4			
	No	No	No	No			
	operation No	operation No	operation	operation No			
	NO operation	operation	NO operation	operation			
<u>Exan</u>	<u>nple:</u>	NZERO :	NZERO :				
	Before Instruc PC	= Ad	dress (HERE	)			
After Instruction         If CNT         =         00h,           PC         =         Address (ZERO)         If CNT         ≠         00h,           PC         =         Address (NZERO)         #         Address (NZERO)							

XORLW	Exclusive	Exclusive OR Literal with W					
Syntax:	XORLW	k					
Operands:	$0 \le k \le 25$	5					
Operation:	(W) .XOR	$k \rightarrow W$					
Status Affected:	N, Z						
Encoding:	0000	1010	kkk}	k kkk			
Description:	The conte the 8-bit li in W.			Red with ult is placed			
Words:	1	1					
Cycles:	1	1					
Q Cycle Activity:							
Q1	Q2	Q3		Q4			
Decode	Read literal 'k'	Proces Data		Write to W			
Example: XORLW 0AFh							
Before Instruct W After Instructio W	= B5h						

XORWF	Exclusive	Exclusive OR W with f					
Syntax:	XORWF	f {,d {,a}}					
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d  \in  [0,1] \\ a  \in  [0,1] \end{array}$	d ∈ [0,1]					
Operation:	(W) .XOR. (	(f) $\rightarrow$ dest					
Status Affected:	N, Z						
Encoding:	0001	10da f	fff	ffff			
Description:	Exclusive C register 'f'. stored in W stored back	lf 'd' is '0', tl . If 'd' is '1',	ne resu the re	ult is sult is			
	lf 'a' is '0', th lf 'a' is '1', th GPR bank (	ne BSR is u					
	set is enabling in Indexed I mode when Section 27	If 'a' is '0' and the extended instruction set is enabled, this instruction operates in Indexed Literal Offset Addressing mode whenever $f \le 95$ (5Fh). See Section 27.2.3 "Byte-Oriented and Bit-Oriented Instructions in Indexed					
Words:	1						
Cycles:	1						
Q Cycle Activity:							
Q1	Q2	Q3		Q4			
Decode	Read register 'f'	Process Data	-	Vrite to stination			
Example:XORWFREG, 1, 0Before InstructionREGW=After InstructionREGREG=D5h							
••	0011						

## 27.2 Extended Instruction Set

In addition to the standard 75 instructions of the PIC18 instruction set, the PIC18F46J50 Family of devices also provide an optional extension to the core CPU functionality. The added features include eight additional instructions that augment Indirect and Indexed Addressing operations and the implementation of Indexed Literal Offset Addressing for many of the standard PIC18 instructions.

The additional features of the extended instruction set are enabled by default on unprogrammed devices. Users must properly set or clear the XINST Configuration bit during programming to enable or disable these features.

The instructions in the extended set can all be classified as literal operations, which either manipulate the File Select Registers (FSR), or use them for Indexed Addressing. Two of the instructions, ADDFSR and SUBFSR, each have an additional special instantiation for using FSR2. These versions (ADDULNK and SUBULNK) allow for automatic return after execution.

The extended instructions are specifically implemented to optimize re-entrant program code (that is, code that is recursive or that uses a software stack) written in high-level languages, particularly C. Among other things, they allow users working in high-level languages to perform certain operations on data structures more efficiently. These include:

- Dynamic allocation and deallocation of software stack space when entering and leaving subroutines
- Function Pointer invocation
- Software Stack Pointer manipulation
- Manipulation of variables located in a software stack

A summary of the instructions in the extended instruction set is provided in Table 27-3. Detailed descriptions are provided in **Section 27.2.2 "Extended Instruction Set"**. The opcode field descriptions in Table 27-1 (page 432) apply to both the standard and extended PIC18 instruction sets.

Note: The instruction set extension and the Indexed Literal Offset Addressing mode were designed for optimizing applications written in C; the user may likely never use these instructions directly in assembler. The syntax for these commands is provided as a reference for users who may be reviewing code that has been generated by a compiler.

## 27.2.1 EXTENDED INSTRUCTION SYNTAX

Most of the extended instructions use indexed arguments, using one of the FSRs and some offset to specify a source or destination register. When an argument for an instruction serves as part of Indexed Addressing, it is enclosed in square brackets ("[]"). This is done to indicate that the argument is used as an index or offset. The MPASM<sup>™</sup> Assembler will flag an error if it determines that an index or offset value is not bracketed.

When the extended instruction set is enabled, brackets are also used to indicate index arguments in byte-oriented and bit-oriented instructions. This is in addition to other changes in their syntax. For more details, see Section 27.2.3.1 "Extended Instruction Syntax with Standard PIC18 Commands".

Note: In the past, square brackets have been used to denote optional arguments in the PIC18 and earlier instruction sets. In this text and going forward, optional arguments are denoted by braces ("{ }").

Mnemonic, Operands		Description	Cycles	16-Bit Instruction Word			/ord	Status
		Description	Cycles	MSb			LSb	Affected
ADDFSR	f, k	Add Literal to FSR	1	1110	1000	ffkk	kkkk	None
ADDULNK	k	Add Literal to FSR2 and Return	2	1110	1000	11kk	kkkk	None
CALLW		Call Subroutine using WREG	2	0000	0000	0001	0100	None
MOVSF	z <sub>s</sub> , f <sub>d</sub>	Move z <sub>s</sub> (source) to 1st word	2	1110	1011	0 z z z	ZZZZ	None
		f <sub>d</sub> (destination) 2nd word		1111	ffff	ffff	ffff	_
MOVSS	z <sub>s</sub> , z <sub>d</sub>	Move z <sub>s</sub> (source) to 1st word	2	1110	1011	1zzz	ZZZZ	None
		z <sub>d</sub> (destination) 2nd word		1111	XXXX	XZZZ	ZZZZ	—
PUSHL	k	Store Literal at FSR2,	1	1110	1010	kkkk	kkkk	None
		Decrement FSR2						_
SUBFSR	f, k	Subtract Literal from FSR	1	1110	1001	ffkk	kkkk	None
SUBULNK	k	Subtract Literal from FSR2 and	2	1110	1001	11kk	kkkk	None
		Return						

## TABLE 27-3: EXTENSIONS TO THE PIC18 INSTRUCTION SET

## 27.2.2 EXTENDED INSTRUCTION SET

ADDFSR Add Literal to FSR							
Synta	ax:	ADDFSR	ADDFSR f, k				
Oper	ands:	$0 \le k \le 63$	$0 \le k \le 63$				
		f ∈ [ 0, 1,	f ∈ [ 0, 1, 2 ]				
Operation: $FSR(f) + k \rightarrow FSR(f)$							
Statu	s Affected:	None					
Enco	oding:	1110	1000	ffkk	kkkk		
Desc	ription:	The 6-bit	The 6-bit literal 'k' is added to the				
		contents of	contents of the FSR specified by 'f'.				
Word	ls:	1	1				
Cycle	es:	1	1				
QC	ycle Activity:						
	Q1	Q2	Q3		Q4		
	Decode	Read	Proces	ss V	Vrite to		
		literal 'k'	Data		FSR		

ADDFSR 2, 23h

03FFh

ADDULNK	Add Lite	ral to FSF	R2 and Re	eturn	
Syntax:	ADDULNK k				
Operands:	$0 \le k \le 63$				
Operation:	FSR2 + k	$\rightarrow$ FSR2	,		
	$(TOS) \rightarrow PC$				
Status Affected:	None				
Encoding:	1110 1000 11kk kkkk				
Description:	The 6-bit literal 'k' is added to the contents of FSR2. A RETURN is then executed by loading the PC with the TOS.				
	The instruction takes two cycles to execute; a NOP is performed durin the second cycle.				
	This may be thought of as a special case of the ADDFSR instruction, where f = 3 (binary '11'); it operates only on FSR2.			on,	
Words:	1				
Cycles:	2				

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	Read	Process	Write to
	literal 'k'	Data	FSR
No	No	No	No
Operation	Operation	Operation	Operation

Example:	AD	DULNK 23h
Before Instru	uction	
FSR2	=	03FFh
PC	=	0100h
After Instruc	tion	
FSR2	=	0422h
PC	=	(TOS)

**Note:** All PIC18 instructions may take an optional label argument preceding the instruction mnemonic for use in symbolic addressing. If a label is used, the instruction format then becomes: {label} instruction argument(s).

Example:

Before Instruction FSR2 =

After Instruction

FSR2 = 0422h

CALI	LW	Subroutine	Subroutine Call using WREG				
Synta	ax:	CALLW	CALLW				
Oper	ands:	None					
Oper	ation:	$(W) \rightarrow PCL$ $(PCLATH)$	$(PC + 2) \rightarrow TOS,$ $(W) \rightarrow PCL,$ $(PCLATH) \rightarrow PCH,$ $(PCLATU) \rightarrow PCU$				
Statu	s Affected:	None					
Enco	ding:	0000	0000 000	1 0100			
Desc	ription	pushed ont contents of existing val contents of latched into tively. The s a NOP instru- instruction Unlike CAL	First, the return address (PC + 2) is pushed onto the return stack. Next, the contents of W are written to PCL; the existing value is discarded. Then, the contents of PCLATH and PCLATU are latched into PCH and PCU, respec- tively. The second cycle is executed as a NOP instruction while the new next instruction is fetched. Unlike CALL, there is no option to				
Word	e.	update W, s 1	update W, STATUS or BSR.				
Cycle		-	2				
	ycle Activity:	2					
QU	Q1	Q2	Q3	Q4			
	Decode	Read WREG	Push PC to stack	No operation			
	No	No	No	No			
	operation	operation	operation	operation			
<u>Exarr</u>	<u>nple:</u> Before Instruc	HERE	CALLW				
PC = PCLATH = PCLATU = W = After Instruction PC = TOS = PCLATH = PCLATU =		= address = 10h = 00h = 06h m = 001006 = address = 10h	h	)			

MOV	SF	Move Inde	xed to f				
Synta	ax:	MOVSF [	z <sub>s</sub> ], f <sub>d</sub>				
Oper	ands:	$0 \le z_s \le 12$ $0 \le f_d \le 409$					
Oper	ation:	((FSR2) + :	$z_s) \rightarrow f_d$				
Statu	s Affected:	None					
	oding: /ord (source) word (destin.)	1110 1111	1110 1011 Ozzz zzzz				
Desc	ription:	moved to d actual addr determined offset ' $z_s$ ', i of FSR2. T tion registe eral ' $f_d$ ' in ti addresses 4096-byte The MOVSE	The contents of the source register are moved to destination register ' $f_d$ '. The actual address of the source register is determined by adding the 7-bit literal offset ' $z_s$ ', in the first word, to the value of FSR2. The address of the destina- tion register is specified by the 12-bit lit- eral ' $f_d$ ' in the second word. Both addresses can be anywhere in the 4096-byte data space (000h to FFFh). The MOVSF instruction cannot use the PCL, TOSU, TOSH or TOSL as the				
		If the result an Indirect	destination register. If the resultant source address points to an Indirect Addressing register, the value returned will be 00h.				
Word	ls:	2	2				
Cycle	es:	2					
QC	ycle Activity:						
	Q1	Q2	Q	3	Q4		
	Decode	Determine source addr	Detern source		Read source reg		
	Decode	No operation No dummy read	No operat		Write register 'f' (dest)		
<u>Exan</u>		MOVSF	[05h],	REG2			
	Before Instruct FSR2 Contents of 85h REG2 After Instruction FSR2 Contents of 85h REG2	= 80 = 33 = 11 on = 80	ih h ih				

MOVSS	Move Indexed to Indexed			
Syntax:	MOVSS [z <sub>s</sub> ], [z <sub>d</sub> ]			
Operands:	$\begin{array}{l} 0 \leq z_s \leq 127 \\ 0 \leq z_d \leq 127 \end{array}$			
Operation:	$((FSR2) + z_s) \rightarrow ((FSR2) + z_d)$			
Status Affected:	None			
Encoding: 1st word (source) 2nd word (dest.)	1110 1011 1zzz zzzz <sub>s</sub> 1111 xxxx xzzz zzzz <sub>d</sub>			
Description	The contents of the source register are moved to the destination register. The addresses of the source and destina- tion registers are determined by adding the 7-bit literal offsets ' $z_s$ ' or ' $z_d$ ', respectively, to the value of FSR2. Both registers can be located anywhere in the 4096-byte data memory space (000h to FFFh).			
	The MOVSS instruction cannot use the PCL, TOSU, TOSH or TOSL as the destination register.			
	If the resultant source address points to an Indirect Addressing register, the value returned will be 00h. If the resultant destination address points to an Indirect Addressing register, the instruction will execute as a NOP.			
Words:	2			
Cycles:	2			
Q Cycle Activity:				

Cycles:	2	
Q Cycle Activity:		
Q1	Q2	Q3

Q1	Q2	Q3	Q4
Decode	Determine	Determine	Read
	source addr	source addr	source reg
Decode	Determine dest addr	Determine dest addr	Write to dest reg

Example:	MOVSS	[05h],	[06h]
		L · · J /	

Before Instruction		
FSR2	=	80h
Contents of 85h Contents	=	33h
of 86h	=	11h
After Instruction		
FSR2	=	80h
Contents		0.01
of 85h Contents	=	33h
of 86h	=	33h

PUSHL	Store Litera	al at FSR	2, Decr	ement FSR2		
Syntax:	PUSHL k	PUSHL k				
Operands:	$0 \leq k \leq 255$	$0 \le k \le 255$				
Operation:		$k \rightarrow$ (FSR2), FSR2 – 1 $\rightarrow$ FSR2				
Status Affected:	None					
Encoding:	1110	1010	kkkl	k kkkk		
	memory ad FSR2 is der operation. This instruc values onto	cremente	d by 1 a /s users	after the s to push		
Words:	1					
Cycles:	1	1				
Q Cycle Activity:						
Q1	Q2	G	3	Q4		
Decode	Read 'k'	Proc da		Write to destination		
Example:	PUSHL 0	8h				

Before Instruction FSR2H:FSR2L Memory (01ECh) 01ECh = = 00h After Instruction FSR2H:FSR2L Memory (01ECh) 01EBh 08h = =

Subtract Literal from FSR2 and Return

SUBULNK

SUB	SUBFSR Subtract Literal from FSR						
Synta	ax:	SUBFSR f, k					
Oper	ands:	$0 \le k \le 63$					
		f ∈ [ 0, 1,	2]				
Oper	ation:	FSRf – k	$\rightarrow$ FSRf				
Statu	s Affected:	None		-			
Enco	ding:	1110	1001	ffk}	< c	kkkk	
Description:		The 6-bit	The 6-bit literal 'k' is subtracted from				
			the contents of the FSR specified				
		by 'f'.	by 'f'.				
Word	IS:	1	1				
Cycle	es:	1	1				
QC	ycle Activity:						
Q1		Q2	Q3			Q4	
	Decode	Read	Proce	SS	W	rite to	
		register 'f'	Data	a	des	tination	

Example:	SUBFSR 2,	23h	
Before Instructio	'n		
FSR2 =	03FFh		

03DCh

After Instruction FSR2

=

Synta	ax:	SUBULNK k								
Oper	ands:	$0 \le k \le 63$								
Oper	ation:	FSR2 – k	→ FSR2,							
		$(TOS) \rightarrow F$	с							
Statu	s Affected:	None								
Enco	ding:	1110	1001	11kk	kkkk					
Desc	ription:	The 6-bit literal 'k' is subtracted from the contents of the FSR2. A RETURN is then executed by loading the PC with the TOS.								
		The instruction takes two cycles to execute; a NOP is performed during the second cycle.								
		This may b of the SUB (binary '11	FSR instrue	ction, whe	ere f = 3					
Word	ls:	1								
Cycle	es:	2								
QC	ycle Activity:									
	Q1	Q2 Q3 Q4								
	Decode	Read	Proc	cess	Write to					
		register	f' Da	ata c	lestination					
	No	No	N	lo	No					
	Operation	Operatio	n Oper	ation	Operation					

Example: SUBULNK 23h

<u>ampic.</u>		50D0DINK
Before Instru	ction	
FSR2	=	03FFh
PC	=	0100h
After Instructi	on	
FSR2	=	03DCh
PC	=	(TOS)

#### © 2009 Microchip Technology Inc.

### 27.2.3 BYTE-ORIENTED AND BIT-ORIENTED INSTRUCTIONS IN INDEXED LITERAL OFFSET MODE

Note:	Enabling the PIC18 instruction set exten-
	sion may cause legacy applications to
	behave erratically or fail entirely

In addition to eight new commands in the extended set, enabling the extended instruction set also enables Indexed Literal Offset Addressing (Section 5.6.1 "Indexed Addressing with Literal Offset"). This has a significant impact on the way that many commands of the standard PIC18 instruction set are interpreted.

When the extended set is disabled, addresses embedded in opcodes are treated as literal memory locations: either as a location in the Access Bank (a = 0) or in a GPR bank designated by the BSR (a = 1). When the extended instruction set is enabled and a = 0, however, a file register argument of 5Fh or less is interpreted as an offset from the pointer value in FSR2 and not as a literal address. For practical purposes, this means that all instructions that use the Access RAM bit as an argument – that is, all byte-oriented and bit-oriented instructions, or almost half of the core PIC18 instructions – may behave differently when the extended instruction set is enabled.

When the content of FSR2 is 00h, the boundaries of the Access RAM are essentially remapped to their original values. This may be useful in creating backward-compatible code. If this technique is used, it may be necessary to save the value of FSR2 and restore it when moving back and forth between C and assembly routines in order to preserve the Stack Pointer. Users must also keep in mind the syntax requirements of the extended instruction set (see Section 27.2.3.1 "Extended Instruction Syntax with Standard PIC18 Commands").

Although the Indexed Literal Offset mode can be very useful for dynamic stack and pointer manipulation, it can also be very annoying if a simple arithmetic operation is carried out on the wrong register. Users who are accustomed to the PIC18 programming must keep in mind that, when the extended instruction set is enabled, register addresses of 5Fh or less are used for Indexed Literal Offset Addressing.

Representative examples of typical byte-oriented and bit-oriented instructions in the Indexed Literal Offset mode are provided on the following page to show how execution is affected. The operand conditions provided in the examples are applicable to all instructions of these types.

## 27.2.3.1 Extended Instruction Syntax with Standard PIC18 Commands

When the extended instruction set is enabled, the file register argument 'f' in the standard byte-oriented and bit-oriented commands is replaced with the literal offset value 'k'. As already noted, this occurs only when 'f' is less than or equal to 5Fh. When an offset value is used, it must be indicated by square brackets ("[]"). As with the extended instructions, the use of brackets indicates to the compiler that the value is to be interpreted as an index or an offset. Omitting the brackets, or using a value greater than 5Fh within the brackets, will generate an error in the MPASM Assembler.

If the index argument is properly bracketed for Indexed Literal Offset Addressing, the Access RAM argument is never specified; it will automatically be assumed to be '0'. This is in contrast to standard operation (extended instruction set disabled) when 'a' is set on the basis of the target address. Declaring the Access RAM bit in this mode will also generate an error in the MPASM Assembler.

The destination argument 'd' functions as before.

In the latest versions of the MPASM Assembler, language support for the extended instruction set must be explicitly invoked. This is done with either the command line option,  $/_{\mathbb{Y}}$ , or the PE directive in the source listing.

### 27.2.4 CONSIDERATIONS WHEN ENABLING THE EXTENDED INSTRUCTION SET

It is important to note that the extensions to the instruction set may not be beneficial to all users. In particular, users who are not writing code that uses a software stack may not benefit from using the extensions to the instruction set.

Additionally, the Indexed Literal Offset Addressing mode may create issues with legacy applications written to the PIC18 assembler. This is because instructions in the legacy code may attempt to address registers in the Access Bank below 5Fh. Since these addresses are interpreted as literal offsets to FSR2 when the instruction set extension is enabled, the application may read or write to the wrong data addresses.

When porting an application to the PIC18F46J50 Family, it is very important to consider the type of code. A large, re-entrant application that is written in C and would benefit from efficient compilation will do well when using the instruction set extensions. Legacy applications that heavily use the Access Bank will most likely not benefit from using the extended instruction set.

ADDWF	ADD W to Indexed (Indexed Literal Offset mode)							
Syntax:	ADDWF	[k] {,d}						
Operands:	$\begin{array}{l} 0 \leq k \leq 95 \\ d  \in  [0,1] \end{array}$							
Operation:	(W) + ((FS	SR2) + k)	$\rightarrow$ des	t				
Status Affected:	N, OV, C,	DC, Z						
Encoding:	0010	01d0	kkk	k kkkk				
Description:	The conte contents o FSR2, offs	f the regis	ster in	dicated by				
	If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default).							
Words:	1							
Cycles:	1							
Q Cycle Activity:								
Q1	Q2	Q3	3	Q4				
Decode	Read 'k'	Proce Data		Write to destination				
Example:	ADDWF	[OFST]	,0					
Before Instruction W OFST FSR2 Contents of 0A2Ch After Instruction W Contents of 0A2Ch	= = = =		ı					

BSF	Bit Set Ind (Indexed L	exed iteral Offset r	node)					
Syntax:	BSF [k], b							
Operands:	$\begin{array}{l} 0 \leq f \leq 95 \\ 0 \leq b \leq 7 \end{array}$							
Operation:	$1 \rightarrow$ ((FSR2	2) + k) <b></b>						
Status Affected:	None							
Encoding:	1000	bbb0 kkł	k kkkk					
Description:		e register indic et by the value						
Words:	1							
Cycles:	1							
Q Cycle Activity:								
Q1	Q2	Q3	Q4					
Decode	Read register 'f'	Process Data	Write to destination					
Example:	BSF [	FLAG_OFST]	, 7					
Before Instruct FLAG_OI FSR2		0Ah 0A00h						
Contents of 0A0Ah After Instructio		55h						
Contents of 0A0Ah	=	D5h						
SETF	Set Indexe (Indexed L	d iteral Offset r	node)					
SETF Syntax:			node)					
-	(Indexed L		node)					
Syntax:	(Indexed L SETF [k]	iteral Offset r	node)					
Syntax: Operands:	(Indexed L SETF [k] 0 ≤ k ≤ 95	iteral Offset r	node)					
Syntax: Operands: Operation:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS	iteral Offset r						
Syntax: Operands: Operation: Status Affected:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten	iteral Offset r SR2) + k)	kk kkkk er indicated					
Syntax: Operands: Operation: Status Affected: Encoding:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten	SR2) + k) 1000 kkł ts of the regist	kk kkkk er indicated					
Syntax: Operands: Operation: Status Affected: Encoding: Description:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o	SR2) + k) 1000 kkł ts of the regist	kk kkkk er indicated					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1	SR2) + k) 1000 kkł ts of the regist	kk kkkk er indicated					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1	SR2) + k)	kk kkkk er indicated					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1	BR2) + k) 1000 kkł ts of the regist ffset by 'k', are	kk kkkk er indicated e set to FFh.					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity: Q1	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1 2 Read 'k'	SR2) + k) 1000 kkł ts of the regist ffset by 'k', are Q3 Process	kk kkkk er indicated e set to FFh. Q4 Write					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity: Q1 Decode Example: Before Instruct	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1 2 Read 'k' SETF [	iteral Offset r SR2) + k) 1000 kkł ts of the regist ffset by 'k', are Q3 Process Data	kk kkkk er indicated e set to FFh. Q4 Write					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity: Q1 Decode Example:	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1 2 Read 'k' SETF [ ition = 20	iteral Offset r SR2) + k) 1000 kkk ts of the regist ffset by 'k', are Q3 Process Data COFST] Ch	kk kkkk er indicated e set to FFh. Q4 Write					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity: Q1 Decode Example: Before Instruct OFST FSR2 Contents	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1 2 Read 'k' SETF [ setF [ conten by FSR2]	iteral Offset r SR2) + k) 1000 kkł ts of the regist ffset by 'k', are Q3 Process Data OFST]	kk kkkk er indicated e set to FFh. Q4 Write					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity: Q1 Decode Example: Before Instruct OFST FSR2 Contents of 0A2Ch	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1 Q2 Read 'k' SETF [ SETF [ = 0A = 00	iteral Offset r SR2) + k) 1000 kkł ts of the regist ffset by 'k', are Q3 Process Data OFST]	kk kkkk er indicated e set to FFh. Q4 Write					
Syntax: Operands: Operation: Status Affected: Encoding: Description: Words: Cycles: Q Cycle Activity: Q1 Decode Example: Before Instruct OFST FSR2 Contents	(Indexed L SETF [k] $0 \le k \le 95$ FFh $\rightarrow$ ((FS None 0110 The conten by FSR2, o 1 1 2 Read 'k' SETF [ SETF [ = 2C = 0A = 00 n	iteral Offset r SR2) + k) 1000 kkł ts of the regist ffset by 'k', are Q3 Process Data OFST] th 00h h	kk kkkk er indicated e set to FFh. Q4 Write					

## 27.2.5 SPECIAL CONSIDERATIONS WITH MICROCHIP MPLAB<sup>®</sup> IDE TOOLS

The latest versions of Microchip's software tools have been designed to fully support the extended instruction set for the PIC18F46J50 Family. This includes the MPLAB C18 C Compiler, MPASM assembly language and MPLAB Integrated Development Environment (IDE).

When selecting a target device for software development, MPLAB IDE will automatically set default Configuration bits for that device. The default setting for the XINST Configuration bit is '0', disabling the extended instruction set and Indexed Literal Offset Addressing. For proper execution of applications developed to take advantage of the extended instruction set, XINST must be set during programming.

To develop software for the extended instruction set, the user must enable support for the instructions and the Indexed Addressing mode in their language tool(s). Depending on the environment being used, this may be done in several ways:

- A menu option or dialog box within the environment that allows the user to configure the language tool and its settings for the project
- · A command line option
- · A directive in the source code

These options vary between different compilers, assemblers and development environments. Users are encouraged to review the documentation accompanying their development systems for the appropriate information.

## 28.0 DEVELOPMENT SUPPORT

The PIC<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Assemblers/Compilers/Linkers
  - MPASM<sup>™</sup> Assembler
  - MPLAB C18 and MPLAB C30 C Compilers
  - MPLINK™ Object Linker/
  - MPLIB™ Object Librarian
  - MPLAB ASM30 Assembler/Linker/Library
- Simulators
  - MPLAB SIM Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - MPLAB REAL ICE™ In-Circuit Emulator
- In-Circuit Debugger
  - MPLAB ICD 2
- Device Programmers
  - PICSTART<sup>®</sup> Plus Development Programmer
  - MPLAB PM3 Device Programmer
  - PICkit<sup>™</sup> 2 Development Programmer
- Low-Cost Demonstration and Development Boards and Evaluation Kits

## 28.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16-bit microcontroller market. The MPLAB IDE is a Windows<sup>®</sup> operating system-based application that contains:

- A single graphical interface to all debugging tools
  - Simulator
  - Programmer (sold separately)
  - Emulator (sold separately)
  - In-Circuit Debugger (sold separately)
- · A full-featured editor with color-coded context
- A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- Visual device initializer for easy register initialization
- · Mouse over variable inspection
- Drag and drop variables from source to watch windows
- · Extensive on-line help
- Integration of select third party tools, such as HI-TECH Software C Compilers and IAR C Compilers

The MPLAB IDE allows you to:

- Edit your source files (either assembly or C)
- One touch assemble (or compile) and download to PIC MCU emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - Source files (assembly or C)
  - Mixed assembly and C
  - Machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost-effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increased flexibility and power.

## 28.2 MPASM Assembler

The MPASM Assembler is a full-featured, universal macro assembler for all PIC MCUs.

The MPASM Assembler generates relocatable object files for the MPLINK Object Linker, Intel<sup>®</sup> standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM Assembler features include:

- Integration into MPLAB IDE projects
- User-defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

## 28.3 MPLAB C18 and MPLAB C30 C Compilers

The MPLAB C18 and MPLAB C30 Code Development Systems are complete ANSI C compilers for Microchip's PIC18 and PIC24 families of microcontrollers and the dsPIC30 and dsPIC33 family of digital signal controllers. These compilers provide powerful integration capabilities, superior code optimization and ease of use not found with other compilers.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

### 28.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK Object Linker combines relocatable objects created by the MPASM Assembler and the MPLAB C18 C Compiler. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB Object Librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

## 28.5 MPLAB ASM30 Assembler, Linker and Librarian

MPLAB ASM30 Assembler produces relocatable machine code from symbolic assembly language for dsPIC30F devices. MPLAB C30 C Compiler uses the assembler to produce its object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- Support for the entire dsPIC30F instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- Rich directive set
- Flexible macro language
- · MPLAB IDE compatibility

## 28.6 MPLAB SIM Software Simulator

The MPLAB SIM Software Simulator allows code development in a PC-hosted environment by simulating the PIC MCUs and dsPIC<sup>®</sup> DSCs on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a comprehensive stimulus controller. Registers can be logged to files for further run-time analysis. The trace buffer and logic analyzer display extend the power of the simulator to record and track program execution, actions on I/O, most peripherals and internal registers.

The MPLAB SIM Software Simulator fully supports symbolic debugging using the MPLAB C18 and MPLAB C30 C Compilers, and the MPASM and MPLAB ASM30 Assemblers. The software simulator offers the flexibility to develop and debug code outside of the hardware laboratory environment, making it an excellent, economical software development tool.

## 28.7 MPLAB ICE 2000 High-Performance In-Circuit Emulator

The MPLAB ICE 2000 In-Circuit Emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PIC microcontrollers. Software control of the MPLAB ICE 2000 In-Circuit Emulator is advanced by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The architecture of the MPLAB ICE 2000 In-Circuit Emulator allows expansion to support new PIC microcontrollers.

The MPLAB ICE 2000 In-Circuit Emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft<sup>®</sup> Windows<sup>®</sup> 32-bit operating system were chosen to best make these features available in a simple, unified application.

## 28.8 MPLAB REAL ICE In-Circuit Emulator System

MPLAB REAL ICE In-Circuit Emulator System is Microchip's next generation high-speed emulator for Microchip Flash DSC and MCU devices. It debugs and programs PIC<sup>®</sup> Flash MCUs and dsPIC<sup>®</sup> Flash DSCs with the easy-to-use, powerful graphical user interface of the MPLAB Integrated Development Environment (IDE), included with each kit.

The MPLAB REAL ICE probe is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with either a connector compatible with the popular MPLAB ICD 2 system (RJ11) or with the new high-speed, noise tolerant, Low-Voltage Differential Signal (LVDS) interconnection (CAT5).

MPLAB REAL ICE is field upgradeable through future firmware downloads in MPLAB IDE. In upcoming releases of MPLAB IDE, new devices will be supported, and new features will be added, such as software breakpoints and assembly code trace. MPLAB REAL ICE offers significant advantages over competitive emulators including low-cost, full-speed emulation, real-time variable watches, trace analysis, complex breakpoints, a ruggedized probe interface and long (up to three meters) interconnection cables.

## 28.9 MPLAB ICD 2 In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD 2, is a powerful, low-cost, run-time development tool, connecting to the host PC via an RS-232 or high-speed USB interface. This tool is based on the Flash PIC MCUs and can be used to develop for these and other PIC MCUs and dsPIC DSCs. The MPLAB ICD 2 utilizes the in-circuit debugging capability built into the Flash devices. This feature, along with Microchip's In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) protocol, offers costeffective, in-circuit Flash debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by setting breakpoints, single stepping and watching variables, and CPU status and peripheral registers. Running at full speed enables testing hardware and applications in real time. MPLAB ICD 2 also serves as a development programmer for selected PIC devices.

## 28.10 MPLAB PM3 Device Programmer

The MPLAB PM3 Device Programmer is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular, detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 Device Programmer can read, verify and program PIC devices without a PC connection. It can also set code protection in this mode. The MPLAB PM3 connects to the host PC via an RS-232 or USB cable. The MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an SD/MMC card for file storage and secure data applications.

## 28.11 PICSTART Plus Development Programmer

The PICSTART Plus Development Programmer is an easy-to-use, low-cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient. The PICSTART Plus Development Programmer supports most PIC devices in DIP packages up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus Development Programmer is CE compliant.

## 28.12 PICkit 2 Development Programmer

The PICkit<sup>™</sup> 2 Development Programmer is a low-cost programmer and selected Flash device debugger with an easy-to-use interface for programming many of Microchip's baseline, mid-range and PIC18F families of Flash memory microcontrollers. The PICkit 2 Starter Kit includes a prototyping development board, twelve sequential lessons, software and HI-TECH's PICC<sup>™</sup> Lite C compiler, and is designed to help get up to speed quickly using PIC<sup>®</sup> microcontrollers. The kit provides everything needed to program, evaluate and develop applications using Microchip's powerful, mid-range Flash memory family of microcontrollers.

## 28.13 Demonstration, Development and Evaluation Boards

A wide variety of demonstration, development and evaluation boards for various PIC MCUs and dsPIC DSCs allows quick application development on fully functional systems. Most boards include prototyping areas for adding custom circuitry and provide application firmware and source code for examination and modification.

The boards support a variety of features, including LEDs, temperature sensors, switches, speakers, RS-232 interfaces, LCD displays, potentiometers and additional EEPROM memory.

The demonstration and development boards can be used in teaching environments, for prototyping custom circuits and for learning about various microcontroller applications.

In addition to the PICDEM<sup>™</sup> and dsPICDEM<sup>™</sup> demonstration/development board series of circuits, Microchip has a line of evaluation kits and demonstration software for analog filter design, KEELOQ<sup>®</sup> security ICs, CAN, IrDA<sup>®</sup>, PowerSmart battery management, SEEVAL<sup>®</sup> evaluation system, Sigma-Delta ADC, flow rate sensing, plus many more.

Check the Microchip web page (www.microchip.com) for the complete list of demonstration, development and evaluation kits.


## 29.0 ELECTRICAL CHARACTERISTICS

## Absolute Maximum Ratings<sup>(†)</sup>


Ambient temperature under bias	40°C to +125°C
Storage temperature	65°C to +150°C
Voltage on any digital only I/O pin or MCLR with respect to Vss (except VDD)	0.3V to 6.0V
Voltage on any combined digital and analog pin with respect to Vss (except VDD)	0.3V to (VDD + 0.3V)
Voltage on VDDCORE with respect to Vss	0.3V to 2.75V
Voltage on VDD with respect to Vss	0.3V to 4.0V
Voltage on VUSB with respect to VSS	(VDD – 0.3V) to 4.0V
Total power dissipation (Note 1)	1.0W
Maximum current out of Vss pin	300 mA
Maximum current into VDD pin	250 mA
Maximum output current sunk by any PORTB, PORTC and RA6 I/O pin	25 mA
Maximum output current sunk by any PORTA (except RA6), PORTD and PORTE I/O pin	4 mA
Maximum output current sourced by any PORTB, PORTC and RA6 I/O pin	25 mA
Maximum output current sourced by any PORTA (except RA6), PORTD and PORTE I/O pin	4 mA
Maximum current sunk by all ports	200 mA
Maximum current sourced by all ports	200 mA
<b>Note 1:</b> Power dissipation is calculated as follows: $PDIS = VDD x \{IDD - \sum IOH\} + \sum \{(VDD - VOH) x IOH\} + \sum (VOL x IOL)$	

**† NOTICE:** Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.









2: When the USB module is enabled, VUSB should be provided 3.0V-3.6V while VDDCORE must be ≥2.35V. When the USB module is not enabled, the wider limits shaded in grey apply. VUSB should be maintained ≥ VDD, but may optionally be high-impedance when the USB module is not in use.

PIC18F46J50 Family			Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial					
Param No.	Symbol	Characteristic	Min	Тур	Мах	Units	Conditions	
D001	Vdd	Supply Voltage	2.15	_	3.6	V	PIC18F4XJ50, PIC18F2XJ50	
D001A	Vdd	Supply Voltage	2.0	_	3.6	V	PIC18LF4XJ50, PIC18LF2XJ50	
D001B	VDDCORE	External Supply for Microcontroller Core	2.0	—	2.75	V	PIC18LF4XJ50, PIC18LF2XJ50	
D001C	AVdd	Analog Supply Voltage	Vdd - 0.3	_	VDD + 0.3	V		
D001D	AVss	Analog Ground Potential	Vss – 0.3		Vss + 0.3	V		
D001E	Vusb	USB Supply Voltage	3.0	3.3	3.6	V	USB module enabled <sup>(2)</sup>	
D002	Vdr	RAM Data Retention Voltage <sup>(1)</sup>	1.5	—	—	V		
D003	VPOR	VDD Start Voltage to Ensure Internal Power-on Reset Signal	—	_	0.7	V	See Section 4.3 "Power-on Reset (POR)" for details	
D004	Svdd	<b>VDD Rise Rate</b> to Ensure Internal Power-on Reset Signal	0.05	_	—	V/ms	See Section 4.3 "Power-on Reset (POR)" for details	
D005	VBOR	VDDCORE Brown-out Reset Voltage	—	2.0	—	V	PIC18F4XJ50, PIC18F2XJ50 only	
D006	VDSBOR	VDD Brown-out Reset Voltage	—	1.8	—	V	DSBOREN = 1 on "LF" device or "F" device in Deep Sleep	

## 29.1 DC Characteristics: Supply Voltage PIC18F46J50 Family (Industrial)

Note 1: This is the limit to which VDDCORE can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

2: VUSB should always be maintained ≥ VDD, but may be left floating when the USB module is disabled and RC4/RC5 will not be used as general purpose inputs.

PIC18LF	46J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial								
PIC18F4	6J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial								
Param No.	Device	Тур	Max	Units	Conditions					
	Power-Down Current (IPD) <sup>(1)</sup>	– Slee	o mode							
	PIC18LFXXJ50	0.01	1.4	μA	-40°C					
		0.06	1.4	μA	+25°C	VDD = 2.0V,				
		0.52	6.0	μΑ	+60°C	VDDCORE = 2.0V				
		1.8	10.2	μΑ	+85°C					
	PIC18LFXXJ50	0.035	1.5	μA	-40°C					
		0.13	1.5	μΑ	+25°C	VDD = 2.5V,				
		0.63	8.0	μA	+60°C	VDDCORE = 2.5V				
		2.2	12.6	μΑ	+85°C		Sleep mode,			
	PIC18FXXJ50	2.4	5.0	μA	-40°C		REGSLP = 1			
		3.0	5.0	μΑ	+25°C	VDD = 2.15V Vddcore = 10 μF				
		3.8	8.0	μA	+60°C	Capacitor				
		5.6	16	μΑ	+85°C	·				
	PIC18FXXJ50	3.5	7.0	μA	-40°C					
		3.2	7.0	μA	+25°C	VDD = 3.3V Vddcore = 10 μF				
		4.2	10	μA	+60°C	Capacitor				
		6.4	19	μA	+85°C					
	Power-Down Current (IPD) <sup>(1)</sup>	– Deep	Sleep	mode						
	PIC18FXXJ50	1	25	nA	-40°C					
		15	100	nA	+25°C	VDD = 2.15V, VDDCORE = 10 μF				
		115	250	nA	+60°C	Capacitor				
		0.46	1.0	μA	+85°C		Deep Sleep mode			
	PIC18FXXJ50	3	50	nA	-40°C		Deep oleep mode			
		33	150	nA	+25°C	VDD = 3.3V, VDDCORE = 10 μF				
		191	389	nA	+60°C	Capacitor				
		0.65	2.0	μA	+85°C					

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSs and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/Vss;

- MCLR = VDD; WDT disabled unless otherwise specified.
- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF	46J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial									
PIC18F4	6J50 Family			perature		s (unless otherwise °C ≤ TA ≤ +85°C for i					
Param No.	Device	Тур	Max	Units	Conditions						
	Supply Current (IDD) <sup>(2)</sup>										
	PIC18LFXXJ50	5.3	14.2	μA	-40°C						
		6.2	14.2	μA	+25°C	VDD = 2.0V, VDDCORE = 2.0V					
		8.5	19.0	μΑ	+85°C	VDDCORE - 2.0V					
	PIC18LFXXJ50	8.0	16.5	μA	-40°C						
		8.7	16.5	μA	+25°C	VDD = 2.5V, VDDCORE = 2.5V	Fosc = 31 kHz				
		11.3	22.4	μA	+85°C		(RC_RUN mode,				
	PIC18FXXJ50	37	77	μA	-40°C	VDD = 2.15V	Internal RC Oscillator, INTSRC = 0)				
		48	77	μA	+25°C	VDDCORE = 10 µF	INTSRC = 0				
		60	93	μA	+85°C	Capacitor					
	PIC18FXXJ50	45	84	μA	-40°C	VDD = 3.3V					
		54	84	μA	+25°C	VDDCORE = 10 µF					
		65	108	μA	+85°C	Capacitor					
	PIC18LFXXJ50	1.1	1.5	mA	-40°C	VDD = 2.0V,					
		1.1	1.5	mA	+25°C	VDD = 2.0V, VDDCORE = 2.0					
		1.2	1.6	mA	+85°C						
	PIC18LFXXJ50	1.5	1.7	mA	-40°C	VDD = 2.5V,					
		1.6	1.7	mA	+25°C	VDDCORE = 2.5V	Fosc = 4 MHz,				
		1.6	1.9	mA	+85°C		<b>RC RUN</b> mode,				
	PIC18FXXJ50	1.3	2.6	mA	-40°C	VDD = 2.15V,	Internal RC Oscillator				
		1.4	2.6	mA	+25°C	VDDCORE = $10 \mu\text{F}$					
		1.4	2.8	mA	+85°C						
	PIC18FXXJ50	1.6	2.9	mA	-40°C	VDD = 3.3V,					
		1.6	2.9	mA	+25°C	VDDCORE = 10 $\mu$ F					
		1.6	3.0	mA	+85°C						

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/VSS; MCLR = VDD; WDT disabled unless otherwise specified.

**3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.

4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF	F46J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial							
PIC18F4	46J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial							
Param No.	Device	Тур	Typ Max Units			Conditions			
	Supply Current (IDD) <sup>(2)</sup>								
	PIC18LFXXJ50	1.9	3.6	mA	-40°C				
		2.0	3.8	mA	+25°C	VDD = 2.0V, VDDCORE = 2.0V			
		2.0	3.8	mA	+85°C	VDDCORE - 2.0V			
	PIC18LFXXJ50	2.8	4.8	mA	-40°C				
		2.8	4.8	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V			
		2.8	4.9	mA	+85°C		Fosc = 8 MHz,		
	PIC18FXXJ50	2.3	4.2	mA	-40°C	$\lambda = 0.4E \lambda$	RC_RUN mode, Internal RC Oscillator		
		2.3	4.2	mA	+25°C	VDD = 2.15V, VDDCORE = 10 μF			
		2.4	4.5	mA	+85°C	VDDOOKE 10 µ			
	PIC18FXXJ50	2.8	5.1	mA	-40°C				
		2.8	5.1	mA	+25°C	VDD = $3.3V$ , VDDCORE = $10 \mu$ F			
		2.8	5.4	mA	+85°C				
	PIC18LFXXJ50	1.9	9.4	μA	-40°C	VDD = 2.0V,			
		2.3	9.4	μA	+25°C	VDD = 2.0V, VDDCORE = 2.0V			
		4.5	17.2	μA	+85°C				
	PIC18LFXXJ50	2.4	10.5	μA	-40°C	VDD = 2.5V,			
		2.8	10.5	μA	+25°C	VDD - 2.5V, VDDCORE = 2.5V	Fosc = 31 kHz,		
		5.4	19.5	μA	+85°C		RC_IDLE mode,		
	PIC18FXXJ50	33.3	75	μA	-40°C	VDD = 2.15V,	Internal RC Oscillator, INTSRC = 0		
		43.8	75	μA	+25°C	VDD = 2.13V, VDDCORE = $10 \ \mu F$			
		55.3	92	μA	+85°C				
	PIC18FXXJ50	36.1	82	μA	-40°C	VDD = 3.3V,			
		44.5	82	μA	+25°C	VDDCORE = $10 \ \mu F$			
		56.3	105	μA	+85°C				

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSs and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/VSS;

MCLR = VDD; WDT disabled unless otherwise specified.

- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistors use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF	46J50 Family	$\begin{array}{llllllllllllllllllllllllllllllllllll$										
PIC18F4	6J50 Family			rating C		s (unless otherwise °C ≤ TA ≤ +85°C for i						
Param No.	Device	Тур	Max	Units	Conditions							
	Supply Current (IDD) <sup>(2)</sup>											
	PIC18LFXXJ50	0.531	0.980	mA	-40°C							
		0.571	0.980	mA	+25°C	VDD = 2.0V, VDDCORE = 2.0V						
		0.608	1.12	mA	+85°C	VDDCORE - 2.0V						
	PIC18LFXXJ50	0.625	1.14	mA	-40°C							
		0.681	1.14	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V						
		0.725	1.25	mA	+85°C		Fosc = 4 MHz, <b>RC_IDLE</b> mode,					
	PIC18FXXJ50	0.613	1.21	mA	-40°C	VDD = 2.15V,	Internal RC Oscillator					
		0.680	1.21	mA	+25°C	VDD = $2.15V$ , VDDCORE = 10 $\mu$ F						
		0.730	1.30	mA	+85°C	•						
	PIC18FXXJ50	0.673	1.27	mA	-40°C	VDD = 3.3V,						
		0.728	1.27	mA	+25°C	VDD = $3.3V$ , VDDCORE = 10 $\mu$ F						
		0.779	1.45	mA	+85°C							
	PIC18LFXXJ50	0.750	1.4	mA	-40°C	VDD = 2.0V,						
		0.797	1.5	mA	+25°C	VDDCORE = 2.0V						
		0.839	1.6	mA	+85°C							
	PIC18LFXXJ50	0.91	2.4	mA	-40°C	VDD = 2.5V,						
		0.96	2.4	mA	+25°C	VDDCORE = 2.5V	Fosc = 8 MHz,					
		1.01	2.5	mA	+85°C		RC_IDLE mode,					
	PIC18FXXJ50	0.87	2.1	mA	-40°C	VDD = 2.15V,	Internal RC Oscillator					
		0.93	2.1	mA	+25°C	VDDCORE = 10 $\mu$ F						
		0.98	2.3	mA	+85°C							
	PIC18FXXJ50	0.95	2.6	mA mA	-40°C	VDD = 3.3V,						
		1.01	2.6 2.7	mA	+25°C	VDDCORE = 10 $\mu$ F						
		1.06	2.1	mA	+85°C		<u> </u>					

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/Vss; MCLR = VDD; WDT disabled unless otherwise specified.

**3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.

4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF46J50 Family		Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial							
PIC18F4	6J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial							
Param No.	Device	Тур	Мах	Units		Conditions			
	Supply Current (IDD) <sup>(2)</sup>								
	PIC18LFXXJ50	0.879	1.25	mA	-40°C				
		0.881	1.25	mA	+25°C	VDD = 2.0V, VDDCORE = 2.0V			
		0.891	1.36	mA	+85°C	VBBOOKE 2.0V			
	PIC18LFXXJ50	1.35	1.70	mA	-40°C				
		1.30	1.70	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V	Fosc = 4 MHz, <b>PRI_RUN</b> mode,		
		1.27	1.82	mA	+85°C				
	PIC18FXXJ50	1.09	1.60	mA	-40°C	VDD = 2.15V,	EC Oscillator		
		1.09	1.60	mA	+25°C	VDD = 2.15V, VDDCORE = $10 \mu F$			
		1.11	1.70	mA	+85°C				
	PIC18FXXJ50	1.36	1.95	mA	-40°C	VDD = 3.3V,			
		1.36	1.89	mA	+25°C	VDD = $3.3V$ , VDDCORE = 10 $\mu$ F			
		1.41	1.92	mA	+85°C				
	PIC18LFXXJ50	10.9	14.8	mA	-40°C				
		10.6	14.8	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V VDD = 3.3V, VDDCORE = 10 µF			
		10.6	15.2	mA	+85°C		Fosc = 48 MHz, PRI_RUN mode,		
	PIC18FXXJ50	12.9	23.2	mA	-40°C		EC Oscillato	EC Oscillator	
		12.8	22.7	mA	+25°C				
		12.7	22.7	mA	+85°C	1 i i i i i i i			

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSs and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

- 2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:
  - OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/VSS;
    - MCLR = VDD; WDT disabled unless otherwise specified.
- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF46J	50 Family		-	<b>rating C</b> perature		s (unless otherwise $^{\circ}C \leq TA \leq +85^{\circ}C$ for i					
PIC18F46J5	0 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial									
Param No.	Device	Тур	Max	Units		Cond	litions				
	PIC18LFXXJ50	0.28	0.70	mA	-40°C						
		0.30	0.70	mA	+25°C	VDD = 2.0V, VDDCORE = 2.0V					
		0.34	0.75	mA	+85°C	VDDCORE - 2.0V					
	PIC18LFXXJ50	0.37	1.0	mA	-40°C		Fosc = 4 MHz <b>PRI_IDLE</b> mode, EC Oscillator				
		0.40	1.0	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V					
		0.50	1.1	mA	+85°C	VDDCORE - 2.3V					
	PIC18FXXJ50	0.36	0.85	mA	-40°C	VDD = 2.15V,					
		0.38	0.85	mA	+25°C	VDDCORE = 10 $\mu$ F					
		0.41	0.90	mA	+85°C	Capacitor					
	PIC18FXXJ50	0.45	1.3	mA	-40°C	VDD = 3.3V,					
		0.48	1.2	mA	+25°C	VDDCORE = 10 $\mu$ F					
		0.55	1.2	mA	+85°C	Capacitor					
	PIC18LFXXJ50	4.5	6.5	mA	-40°C	) (== 0.5) (					
		4.5	6.5	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V					
		4.6	6.5	mA	+85°C	V BBOOKE - 2.3V	Fosc = 48 MHz				
	PIC18FXXJ50	4.8	12.4	mA	-40°C	VDD = 3.3V,	PRI_IDLE mode, EC Oscillator				
		4.9	11.5	mA	+25°C	VDDCORE = 10 $\mu$ F					
		5.1	11.5	mA	+85°C	Capacitor					

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/Vss;

MCLR = VDD; WDT disabled unless otherwise specified.

- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistors use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF	46J50 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial									
PIC18F4	6J50 Family		Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial								
Param No.	Тур	Max	Units	Conditions							
	PIC18LFXXJ50	8.2	11	mA	-40°C						
		8.1	11	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V	Fosc = 24 MHz				
		8.0	10	mA	+85°C	VDDCORE - 2.5V	PRI_RUN mode, ECPLL Oscillator				
	PIC18FXXJ50	8.1	15	mA	-40°C	VDD = 3.3V,					
		8.1	14	mA	+25°C	VDDCORE = 10 $\mu$ F	(4 MHz Input)				
		8.1	14	mA	+85°C	Capacitor					
	PIC18LFXXJ50	12	14	mA	-40°C						
		12	14	mA	+25°C	VDD = 2.5V, VDDCORE = 2.5V	Fosc = 48 MHz				
		11	14	mA	+85°C	VDD00112 - 2.0V	PRI_RUN mode,				
	PIC18FXXJ50	14	24	mA	-40°C	VDD = 3.3V,	ECPLL Oscillator				
		14	23	mA	+25°C	VDDCORE = $10 \ \mu F$	(4 MHz Input)				
		14	23	mA	+85°C	Capacitor					

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/Vss;

- MCLR = VDD; WDT disabled unless otherwise specified.
- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF46J	50 Family		-	<b>rating C</b> perature		s (unless otherwise $^{\circ}C \le TA \le +85^{\circ}C$ for i					
PIC18F46J5	0 Family	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial									
Param No.	Device	Тур	Max	Units		Cond	itions				
	PIC18LFXXJ50	9.9	45	μA	-40°C						
		11	45	μA	+25°C	VDD = 2.5V, VDDCORE = 2.5V					
		13	61	μA	+85°C	VDDCORE - 2.3V	Fosc = 32 kHz <sup>(3)</sup> SEC_RUN mode, LPT1OSC = 0				
	PIC18FXXJ50	39	95	μA	-40°C	VDD = 2.15V,					
		50	95	μA	+25°C	VDDCORE = 10 $\mu$ F					
		57	105	μA	+85°C	Capacitor					
	PIC18FXXJ50	42	110	μA	-40°C	VDD = 3.3V,					
		54	110	μA	+25°C	VDDCORE = 10 $\mu$ F					
		57	150	μA	+85°C	Capacitor					
	PIC18LFXXJ50	3.5	31	μA	-40°C						
		3.8	31	μA	+25°C	VDD = 2.5V, VDDCORE = 2.5V					
		4.3	50	μA	+85°C	V BBCOILE - 2.0V					
	PIC18FXXJ50	34	87	μA	-40°C	VDD = 2.15V,	Fosc = 32 kHz <sup>(3)</sup>				
		45	89	μA	+25°C	VDDCORE = 10 $\mu$ F	SEC_IDLE mode,				
		56	97	μA	+85°C	Capacitor	LPT1OSC = 0				
	PIC18FXXJ50	35	100	μA	-40°C	VDD = 3.3V,					
		46	100	μA	+25°C	VDDCORE = 10 $\mu$ F					
		56	140	μA	+85°C	Capacitor					

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/Vss;

MCLR = VDD; WDT disabled unless otherwise specified.

- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF	46J50 Family			<b>rating C</b> perature		s (unless otherwise $^{\circ}C \le TA \le +85^{\circ}C$ for						
PIC18F4	6J50 Family			rating C perature		s (unless otherwise $^{\circ}C \le TA \le +85^{\circ}C$ for						
Param No.	Device	Тур	Max	Units	Conditions							
	Module Differential Currents	a (∆lwdi	r, ∆ <b>i</b> hlv	D, ∆losc	B, $\Delta$ IAD, $\Delta$	UUSB)						
D022	Watchdog Timer	0.84	8.0	μA	-40°C	VDD = 2.5V,						
(∆lwdt)		0.96	8.0	μA	+25°C	VDD = 2.5V, VDDCORE = 2.5V	PIC18LFXXJ50					
		0.97	10.4	μA	+85°C							
		0.65	7.0	μA	-40°C	VDD = 2.15V,						
		0.78	7.0	μA	+25°C	VDDCORE = 10 $\mu$ F						
		0.77	10	μA	+85°C	Capacitor	PIC18FXXJ50					
		1.3	12.1	μA	-40°C	VDD = 3.3V,						
		1.3	12.1	μA	+25°C	VDDCORE = 10 $\mu$ F						
		1.3	13.6	μA	+85°C	Capacitor						
D022B	High/Low-Voltage Detect	3.9	8.0	μA	-40°C	VDD = 2.5V,						
(∆Ihlvd)		4.7	8.0	μA	+25°C	VDDCORE = 2.5V	PIC18LFXXJ50					
		5.4	9.0	μA	+85°C							
		2.6	6.0	μA	-40°C	VDD = 2.15V,						
		3.1	6.0	μA	+25°C	VDDCORE = $10 \mu F$						
		3.5	8.0	μA	+85°C	Capacitor	PIC18FXXJ50					
		3.5	9.0	μA	-40°C	VDD = 3.3V,						
		4.1	9.0	μA	+25°C	VDDCORE = $10 \mu F$						
		4.5	12	μA	+85°C	Capacitor						
D025	Real-Time Clock/Calendar	0.80	4.0	μA	-40°C	VDD = 2.15V,						
(∆IOSCB)	with Low-Power Timer1 Oscillator	0.00	4.5	μA	+25°C	VDDCORE = 10 µF						
	Oscillator	0.95	4.5	μA	+60°C	Capacitor						
		1.2	4.5	μA	+85°C							
		0.75	4.5	μA	-40°C	VDD = 2.5V,	PIC18FXXJ50					
		0.92	5.0	μA	+25°C	VDDCORE = 10 µF	32.768 kHz <sup>(3)</sup> , T1OSCEN = 1,					
		1.1	5.0	μA	+60°C	Capacitor	LPT1OSC = 0					
		1.1	5.0	μA	+85°C							
		0.95	6.5	μA	-40°C	VDD = 3.3V,						
		1.1	6.5	μA	+25°C	VDDCORE = 10 µF						
		1.2	8.0	μA	+60°C	Capacitor						
		1.4	8.0	μA	+85°C							

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or Vss and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

- 2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:
  - OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/VSS;
  - MCLR = VDD; WDT disabled unless otherwise specified.
- **3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.
- 4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistors use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

PIC18LF	46J50 Family		-	rating (		<b>s (unless otherwis</b> ) $^{\circ}C \le TA \le +85^{\circ}C$ for						
PIC18F4	6J50 Family		•	rating C		s (unless otherwise °C ≤ TA ≤ +85°C for						
Param No.	Device	Тур	Max	Units	Conditions							
	Module Differential Currents	a (∆lwdi	, ∆Ihlv	D, ∆losc	B, $\Delta$ IAD, $\Delta$	lusb)						
D026 (∆IAD)	A/D Converter	3.0 3.0 3.0	10 10 10	μΑ μΑ μΑ	-40°C +25°C +85°C	VDD = 2.5V, VDDCORE = 2.5V	PIC18LFXXJ50 A/D on, not converting					
		3.0 3.0 3.0	10 10 10	μΑ μΑ μΑ	-40°C +25°C +85°C	VDD = 2.15V, VDDCORE = 10 μF Capacitor	PIC18FXXJ50					
		3.2 3.2 3.2	11 11 11	μΑ μΑ μΑ	-40°C +25°C +85°C	VDD = 3.3V, VDDCORE = 10 μF Capacitor	A/D on, not converting					
D027 (∆IUSB)	USB Module	1.6 1.6 1.5	3.2 3.2 3.2	mA mA mA	-40°C +25°C +85°C	VDD and VUSB = 3.3V,	PIC18FXXJ50 USB enabled, no cable connected. <sup>(4)</sup> Traffic makes a					
		1.5	5.2	mA	+00 C	VDDCORE = 10 μF Capacitor	difference, see Section 21.6.4 "USB Transceiver Current Consumption"					

**Note 1:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD or VSS and all features that add delta current disabled (such as WDT, Timer1 oscillator, BOR, etc.).

2: The supply current is mainly a function of operating voltage, frequency and mode. Other factors, such as I/O pin loading and switching rate, oscillator type and circuit, internal code execution pattern and temperature, also have an impact on the current consumption. All features that add delta current are disabled (USB module, WDT, etc.). The test conditions for all IDD measurements in active operation mode are:

OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD/VSS;

MCLR = VDD; WDT disabled unless otherwise specified.

**3:** Low-power Timer1 with standard, low-cost 32 kHz crystals have an operating temperature range of -10°C to +70°C. Extended temperature crystals are available at a much higher cost.

4: This is the module differential current when the USB module is enabled and clocked at 48 MHz, but with no USB cable attached. When the USB cable is attached or data is being transmitted, the current consumption may be much higher (see Section 21.6.4 "USB Transceiver Current Consumption"). During USB Suspend mode (USBEN = 1, SUSPND = 1, bus in Idle state), the USB module current will be dominated by the D+ or D- pull-up resistor. The integrated pull-up resistor use "resistor switching" according to the resistor\_ecn supplement to the USB 2.0 Specifications, and therefore, may be as low as 900Ω during Idle conditions.

## 29.3 DC Characteristics:PIC18F46J50 Family (Industrial)

DC CHA	ARACTE	RISTICS				unless otherwise stated) ≤ +85°C for industrial
Param No.	Symbol	Characteristic	Min	Мах	Units	Conditions
	VIL	Input Low Voltage				
		All I/O ports:				
D030		with TTL Buffer <sup>(4)</sup>	Vss	0.15 Vdd	V	Vdd < 3.3V
D030A		with TTL Buffer <sup>(4)</sup>	Vss	0.8	V	3.3V < VDD < 3.6V
D031		with Schmitt Trigger Buffer	Vss	0.2 Vdd	V	
D032		MCLR	Vss	0.2 Vdd	V	
D033		OSC1	Vss	0.3 Vdd	V	HS, HSPLL modes
D033A		OSC1	Vss	0.2 Vdd	V	EC, ECPLL modes
D034		T1OSI	Vss	0.3	V	T1OSCEN = 1
	Viн	Input High Voltage				
		I/O Ports without 5.5V Tolerance:				
D040		with TTL Buffer <sup>(4)</sup>	0.25 VDD + 0.8V	Vdd	V	Vdd < 3.3V
D040A		with TTL Buffer <sup>(4)</sup>	2.0	Vdd	V	3.3V < VDD < 3.6V
D041		with Schmitt Trigger Buffer	0.8 VDD	Vdd	V	
		I/O Ports with 5.5V Tolerance: <sup>(5)</sup>				
Dxxx		with TTL Buffer	0.25 VDD + 0.8V	5.5	V	Vdd < 3.3V
DxxxA			2.0	5.5	V	$3.3V \leq V\text{DD} \leq 3.6V$
Dxxx		with Schmitt Trigger Buffer	0.8 VDD	5.5	V	
D042		MCLR	0.8 VDD	5.5	V	
D043		OSC1	0.7 Vdd	Vdd	V	HS, HSPLL modes
D043A		OSC1	0.8 Vdd	Vdd	V	EC, ECPLL modes
D044		T1OSI	1.6	Vdd	V	T1OSCEN = 1
	lı∟	Input Leakage Current <sup>(1,2)</sup>				
D060		I/O Ports	_	±0.2	μA	$Vss \le VPIN \le VDD,$ Pin at high-impedance
D061		MCLR	_	±0.2	μA	$Vss \leq VPIN \leq VDD$
D063		OSC1	—	±0.2	μA	$Vss \leq V PIN \leq V DD$
	IPU	Weak Pull-up Current				
D070	IPURB	PORTB, PORTD <sup>(3)</sup> and PORTE <sup>(3)</sup> Weak Pull-up Current	80	400	μA	VDD = 3.3V, VPIN = VSS

**Note 1:** The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

2: Negative current is defined as current sourced by the pin.

- 3: Only available in 44-pin devices.
- 4: When used as general purpose inputs, the RC4 and RC5 thresholds are referenced to VUSB instead of VDD.
- 5: Refer to Table 9-2 for pin tolerance levels.

DC СНА	ARACTE	RISTICS		Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial					
Param No.	Symbol	Characteristic	Min	Max	Units	Conditions			
	Vol	Output Low Voltage							
D080		I/O Ports:							
		PORTA (except RA6), PORTD, PORTE	_	0.4	V	IOL = 2 mA, VDD = 3.3V, -40°C to +85°C			
		PORTB, PORTC, RA6	—	0.4	V	IOL = 8.5 mA, VDD = 3.3V, -40°C to +85°C			
	Vон	Output High Voltage							
D090		I/O Ports:			V				
		PORTA (except RA6), PORTD, PORTE	2.4	—	V	IOH = -2 mA, VDD = 3.3V, -40°С to +85°С			
		PORTB, PORTC, RA6	2.4	_	V	IOH = -6 mA, VDD = 3.3V, -40°С to +85°С			

### 29.3 DC Characteristics:PIC18F46J50 Family (Industrial) (Continued)

**Note 1:** The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

50

400

pF

pF

To meet the AC Timing

Specifications I<sup>2</sup>C™ Specification

2: Negative current is defined as current sourced by the pin.

3: Only available in 44-pin devices.

SCL<sub>x</sub>, SDA<sub>x</sub>

**4:** When used as general purpose inputs, the RC4 and RC5 thresholds are referenced to VUSB instead of VDD.

5: Refer to Table 9-2 for pin tolerance levels.

**Capacitive Loading Specs** 

on Output Pins

All I/O Pins and OSC2

D101

D102

Сю

Св

DC CHA	DC CHARACTERISTICS			Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial					
Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions		
		Program Flash Memory							
D130	Eр	Cell Endurance	10K	—	—	E/W	-40°C to +85°C		
D131	Vpr	VDDcore for Read	VMIN	—	2.75	V	Vміn = Minimum operating voltage		
D132B	Vpew	VDDCORE for Self-Timed Erase or Write	2.25	—	2.75	V			
D133A	Tiw	Self-Timed Write Cycle Time	_	2.8	_	ms	64 bytes		
D133B	TIE	Self-Timed Block Erase Cycle Time	—	33.0	—	ms			
D134	TRETD	Characteristic Retention	20	_	—	Year	Provided no other specifications are violated		
D135	IDDP	Supply Current during Programming	—	3	_	mA			

### TABLE 29-1:MEMORY PROGRAMMING REQUIREMENTS

† Data in "Typ" column is at 3.3V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

### TABLE 29-2: COMPARATOR SPECIFICATIONS

<b>Operating Conditions:</b> 3.0V < VDD < 3.6V, -40°C < TA < +85°C (unless otherwise stated)										
Param No.	Sym	Characteristics	Min	Тур	Мах	Units	Comments			
D300	VIOFF	Input Offset Voltage	—	+/-5	+/-25	mV				
D301	VICM	Input Common Mode Voltage	0	_	Vdd	V				
	VIRV	Internal Reference Voltage	0.57	0.60	0.63	V				
D302	CMRR	Common Mode Rejection Ratio	55	_	_	dB				
300	TRESP	Response Time <sup>(1)</sup>	_	150	400	ns				
301	Тмс2о∨	Comparator Mode Change to Output Valid	—	—	10	μS				

Note 1: Response time measured with one comparator input at VDD/2, while the other input transitions from Vss to VDD.

### TABLE 29-3: VOLTAGE REFERENCE SPECIFICATIONS

Operating	<b>Operating Conditions:</b> 3.0V < VDD < 3.6V, -40°C < TA < +85°C (unless otherwise stated)										
Param No.	Sym	Characteristics	Min	Тур	Max	Units	Comments				
D310	VRES	Resolution	VDD/24	_	VDD/32	LSb					
D311	VRAA	Absolute Accuracy	—	_	1/2	LSb					
D312	VRur	Unit Resistor Value (R)	—	2k	—	Ω					
310	TSET	Settling Time <sup>(1)</sup>	—	_	10	μS					

**Note 1:** Settling time measured while CVRR = 1 and CVR<3:0> bits transition from '0000' to '1111'.

### TABLE 29-4: INTERNAL VOLTAGE REGULATOR SPECIFICATIONS

Operati	<b>Operating Conditions:</b> -40°C < TA < +85°C (unless otherwise stated)										
Param No.SymCharacteristicsMinTypMaxUnitsComments											
	Vrgout	Regulator Output Voltage	2.35	2.5	2.7	V	Regulator enabled, VDD = 3.0V				
	CEFC	External Filter Capacitor Value <sup>(1)</sup>	5.4	10	18	μF	ESR < $3\Omega$ recommended ESR < $5\Omega$ required				

**Note 1:** CEFC applies for PIC18F devices in the family. For PIC18LF devices in the family, there is no specific minimum or maximum capacitance for VDDCORE, although proper supply rail bypassing should still be used.

### TABLE 29-5: ULPWU SPECIFICATIONS

рс сн	HARACTERISTICS			Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial					
Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions		
D100	IULP	Ultra Low-Power Wake-up Current	_	60	-	nA	Net of I/O leakage and current sink at 1.6V on pin, VDD = 3.3V See Application Note AN879, "Using the Microchip Ultra Low-Power Wake-up Module" (DS00879)		

† Data in "Typ" column is at 3.3V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

### TABLE 29-6: CTMU CURRENT SOURCE SPECIFICATIONS

DC CHARACTERISTICS			$\begin{tabular}{lllllllllllllllllllllllllllllllllll$					
Param No.	Sym	Characteristic	Min	Typ <sup>(1)</sup>	Мах	Units	Conditions	
	IOUT1	CTMU Current Source, Base Range	_	550		nA	CTMUICON<1:0> = 01	
	IOUT2	CTMU Current Source, 10x Range	—	5.5	_	μA	CTMUICON<1:0> = 10	
	IOUT3	CTMU Current Source, 100x Range	—	55	_	μA	CTMUICON<1:0> = 11	


**Note 1:** Nominal value at center point of current trim range (CTMUICON<7:2> = 000000).

#### **TABLE 29-7: USB MODULE SPECIFICATIONS**

<b>Operating Conditions:</b> -40°C < TA < +85°C (unless otherwise stated)							
Param No.	Sym	Characteristics	Min	Тур	Max	Units	Comments
D313	VUSB	USB Voltage	3.0	—	3.6	V	Voltage on VUSB pin must be in this range for proper USB operation
D314	lı∟	Input Leakage on D+ or D-	—	—	+/-0.2	μΑ	Vss <u>&lt;</u> Vpin <u>&lt;</u> Vusb
D315	VILUSB	Input Low Voltage for USB Buffer	—	_	0.8	V	For VUSB range
D316	VIHUSB	Input High Voltage for USB Buffer	2.0	—	—	V	For VUSB range
D318	VDIFS	Differential Input Sensitivity	-	—	0.2	V	The difference between D+ and D- must exceed this value while VCM is met
D319	Vсм	Differential Common Mode Range	0.8	—	2.5	V	
D320	Zout	Driver Output Impedance <sup>(1)</sup>	28	_	44	Ω	
D321	Vol	Voltage Output Low	0.0	-	0.3	V	1.5 k $\Omega$ load connected to 3.6V
D322	Vон	Voltage Output High	2.8	—	3.6	V	1.5 k $\Omega$ load connected to ground

Note 1: The D+ and D- signal lines have built-in impedance matching resistors. No external resistors, capacitors or magnetic components are necessary on the D+/D- signal paths between the PIC18F46J50 Family device and a USB cable.





### TABLE 29-8: HIGH/LOW-VOLTAGE DETECT CHARACTERISTICS

Param No.	Symbol	Charac	teristic	Min	Тур	Мах	Units	Conditions
D420		HLVD Voltage on VDD	HLVDL<3:0> = 1000	2.33	2.45	2.57	V	
		Transition High-to-Low	HLVDL<3:0> = 1001	2.47	2.60	2.73	V	
		HLVDL<3:0> = 1010	2.66	2.80	2.94	V		
			HLVDL<3:0> = 1011	2.76	2.90	3.05	V	
			HLVDL<3:0> = 1100	2.85	3.00	3.15	V	
			HLVDL<3:0> = 1101	2.97	3.13	3.29	V	
			HLVDL<3:0> = 1110	3.23	3.40	3.57	V	
D421	TIRVST	Time for Internal Reference become Stable	me for Internal Reference Voltage to ecome Stable		20	_	μS	
D422	Tlvd	High/Low-Voltage Detect Pulse Width		200		—	μS	

## 29.4 AC (Timing) Characteristics

### 29.4.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created following one of the following formats:

1. TppS2ppS	5	3. Tcc:st	(I <sup>2</sup> C specifications only)
2. TppS		4. Ts	(I <sup>2</sup> C specifications only)
Т			
F	Frequency	Т	Time
Lowercase le	etters (pp) and their meanings:		
рр			
сс	CCP1	osc	OSC1
ck	CLKO	rd	RD
CS	CS	rw	RD or WR
di	SDI	sc	SCK
do	SDO	SS	SS
dt	Data in	tO	TOCKI
io	I/O port	t1	T13CKI
mc	MCLR	wr	WR
Uppercase le	etters and their meanings:		
S			
F	Fall	Р	Period
Н	High	R	Rise
I	Invalid (High-impedance)	V	Valid
L	Low	Z	High-impedance
I <sup>2</sup> C only			
AA	output access	High	High
BUF	Bus free	Low	Low
TCC:ST (I <sup>2</sup> C s	specifications only)		
CC			
HD	Hold	SU	Setup
ST			
DAT	DATA input hold	STO	Stop condition
STA	Start condition		


#### 29.4.2 TIMING CONDITIONS

The temperature and voltages specified in Table 29-9 apply to all timing specifications unless otherwise noted. Figure 29-4 specifies the load conditions for the timing specifications.

#### TABLE 29-9: TEMPERATURE AND VOLTAGE SPECIFICATIONS – AC


	Standard Operating Conditions (unless otherwise stated)					
AC CHARACTERISTICS	Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial					
	Operating voltage VDD range as described in <b>Section 29.1</b> and <b>Section 29.3</b> .					

#### FIGURE 29-4: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



#### 29.4.3 TIMING DIAGRAMS AND SPECIFICATIONS





Param. No.	Symbol	Characteristic	Min	Мах	Units	Conditions
1A	Fosc	External CLKI Frequency <sup>(1)</sup>	DC	48	MHz	EC Oscillator mode
			DC	48		ECPLL Oscillator mode <sup>(2)</sup>
		Oscillator Frequency <sup>(1)</sup>	4	16	MHz	HS Oscillator mode
			4	16 <sup>(4)</sup>		HSPLL Oscillator mode <sup>(3)</sup>
1	Tosc	External CLKI Period <sup>(1)</sup>	20.8	_	ns	EC Oscillator mode
			20.8	—		ECPLL Oscillator mode <sup>(2)</sup>
		Oscillator Period <sup>(1)</sup>	62.5	250	ns	HS Oscillator mode
			62.5 <sup>(4)</sup>	250		HSPLL Oscillator mode <sup>(3)</sup>
2	Тсү	Instruction Cycle Time <sup>(1)</sup>	83.3	DC	ns	Tcy = 4/Fosc, Industrial
3	TosL, TosH	External Clock in (OSC1) High or Low Time	10	—	ns	EC Oscillator mode
4	TosR, TosF	External Clock in (OSC1) Rise or Fall Time	_	7.5	ns	EC Oscillator mode

#### TABLE 29-10: EXTERNAL CLOCK TIMING REQUIREMENTS

Note 1: Instruction cycle period (TCY) equals four times the input oscillator time base period for all configurations except PLL. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "max." cycle time limit is "DC" (no clock) for all devices.

- 2: In order to use the PLL, the external clock frequency must be either 4, 8, 12, 16, 20, 24, 40 or 48 MHz.
- 3: In order to use the PLL, the crystal/resonator must produce a frequency of either 4, 8, 12 or 16 MHz.
- 4: This is the maximum crystal/resonator driver frequency. The internal FOSC frequency when running from the PLL can be up to 48 MHz.

TABLE 29-11:       PLL CLOCK TIMING SPECIFICATIONS (VDDcore = 2.35V TO 2.75V)
-------------------------------------------------------------------------------

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
F10	Fosc	Oscillator Frequency Range	4	_	48	MHz	
F11	Fsys	On-Chip VCO System Frequency		96	—	MHz	
F12	t <sub>rc</sub>	PLL Start-up Time (lock time)	—	_	2	ms	

TABLE 29-12: INTE	RNAL RC ACCURACY	(INTOSC AND INTRC SOURCES)
-------------------	------------------	----------------------------

Param No.	Device	Min	Тур	Max	Units	Conditions					
	INTOSC Accuracy @ Freq = 8 MHz, 4 MHz, 2 MHz, 1 MHz, 500 kHz, 250 kHz, 125 kHz, 31 kHz <sup>(1)</sup>										
	All Devices	vices -1 +/-0.15 +1 9				VDD = 2.4V-3.6V VDDCORE = 2.3V-2.7V					
		-1	+/-0.25	+1	%	-40°C to +85°C	VDD = 2.0V-3.6V VDDCORE = 2.0V-2.7V				
	INTRC Accuracy @ Freq = 31 kHz <sup>(1)</sup>										
	All Devices	20.3			VDD = 2.0V-3.6V VDDCORE = 2.0V-2.7V						

Note 1: The accuracy specification of the 31 kHz clock is determined by which source is providing it at a given time. When INTSRC (OSCTUNE<7>) is '1', use the INTOSC accuracy specification. When INTSRC is '0', use the INTRC accuracy specification.





TABLE 29-13:	CLKO AND I/O TIMING REQUIREMENTS
--------------	----------------------------------

Param No.	Symbol	Characteristic	Min	Тур	Мах	Units	Conditions
10	TosH2ckL	OSC1 ↑ to CLKO ↓		75	200	ns	(Note 1)
11	TosH2ckH	OSC1 ↑ to CLKO ↑	—	75	200	ns	(Note 1)
12	ТскR	CLKO Rise Time	—	15	30	ns	(Note 1)
13	ТскF	CLKO Fall Time	—	15	30	ns	(Note 1)
14	TcĸL2IoV	CLKO $\downarrow$ to Port Out Valid	—		0.5 Tcy + 20	ns	
15	ТюV2скН	Port In Valid before CLKO ↑	0.25 Tcy + 25		—	ns	
16	TckH2iol	Port In Hold after CLKO ↑	0		—	ns	
17	TosH2IoV	OSC1 ↑ (Q1 cycle) to Port Out Valid	—	50	150	ns	
18	TosH2ıol	OSC1 ↑ (Q2 cycle) to Port Input Invalid (I/O in hold time)	100	—	_	ns	
19	TioV2osH	Port Input Valid to OSC1 ↑ (I/O in setup time)	0		_	ns	
20	TioR	Port Output Rise Time	—	_	6	ns	
21	TIOF	Port Output Fall Time		_	5	ns	
22†	TINP	INTx pin High or Low Time	Тсү	_	_	ns	
23†	Trbp	RB7:RB4 Change INTx High or Low Time	Тсү		—	ns	

† These parameters are asynchronous events not related to any internal clock edges.

Note 1: Measurements are taken in EC mode, where CLKO output is 4 x Tosc.



## FIGURE 29-7: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING

## TABLE 29-14:RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER<br/>AND BROWN-OUT RESET REQUIREMENTS

Param. No.	Symbol	Characteristic	Min	Тур	Мах	Units	Conditions
30	ТмсL	MCLR Pulse Width (low)	2	_	—	μS	
31	Twdt	Watchdog Timer Time-out Period (no postscaler)	2.67	4.0	5.53	ms	
32	Tost	Oscillator Start-up Timer Period	1024 Tosc	_	1024 Tosc	_	Tosc = OSC1 period
33	TPWRT	Power-up Timer Period	_	1.0	—	ms	
34	Tioz	I/O High-Impedance from MCLR Low or Watchdog Timer Reset	—		3 Tcy + 2	μS	(Note 1)
36	TIRVST	Time for Internal Reference Voltage to become Stable	—	20	—	μS	
37	Tlvd	High/Low-Voltage Detect Pulse Width	_	200	—	μS	
38	TCSD	CPU Start-up Time	—	200	—	μS	(Note 2)

Note 1: The maximum TIOZ is the lesser of (3 TCY + 2  $\mu$ s) or 700  $\mu$ s.

2: MCLR rising edge to code execution, assuming TPWRT (and TOST if applicable) has already expired.







TABLE 29-15:	TIMER0 AND TIMER1	EXTERNAL	CLOCK REQUIREMENTS
--------------	-------------------	----------	--------------------

Param No.	Symbol		Characteristic		Min	Мах	Units	Conditions
40	T⊤0H	T0CKI High P	ulse Width	No prescaler	0.5 Tcy + 20	—	ns	
				With prescaler	10	_	ns	
41	T⊤0L	T0CKI Low Pu	ulse Width	No prescaler	0.5 Tcy + 20	—	ns	
				With prescaler	10	_	ns	
42	T⊤0P	T0CKI Period		No prescaler	Tcy + 10	—	ns	
				With prescaler	Greater of: 20 ns or (Tcy + 40)/N	_	ns	N = prescale value (1, 2, 4,, 256)
45	T⊤1H		Synchronous, no prescaler		0.5 Tcy + 20	—	ns	
		High Time	Synchronous, with prescaler		10	—	ns	
			Asynchronous		30	_	ns	
46	T⊤1L		Synchronous, n	o prescaler	0.5 Tcy + 5	_	ns	
		Low Time	Synchronous, with prescaler		10	_	ns	
			Asynchronous		30	_	ns	
47	T⊤1P	T1CKI/T3CKI Input Period	Synchronous		Greater of: 20 ns or (Tcy + 40)/N	_	ns	N = prescale value (1, 2, 4, 8)
			Asynchronous		83	—	ns	
	F⊤1	T1CKI Input F	requency Range <sup>(1)</sup>		DC	12	MHz	
48	TCKE2TMRI	Delay from Ex Timer Increme	tternal T1CKI Clo ent	ock Edge to	2 Tosc	7 Tosc		

**Note 1:** The Timer1 oscillator is designed to drive 32.768 kHz crystals. When T1CKI is used as a digital input, frequencies up to 12 MHz are supported.

#### FIGURE 29-9: ENHANCED CAPTURE/COMPARE/PWM TIMINGS



#### TABLE 29-16: ENHANCED CAPTURE/COMPARE/PWM REQUIREMENTS

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
50	TccL	ECCPx Input Low Time	No prescaler	0.5 TCY + 20	_	ns	
			With prescaler	10	_	ns	
51	ТссН	ECCPx Input High Time	No prescaler	0.5 Tcy + 20	—	ns	
			With prescaler	10	—	ns	
52	TCCP	ECCPx Input Period		<u>3 Tcy + 40</u> N	—	ns	N = prescale value (1, 4 or 16)
53	TccR	ECCPx Output Fall Time		—	25	ns	
54	TCCF	ECCPx Output Fall Time		—	25	ns	





TABLE 29-17: PARALLEL MASTER PORT READ TIMING REQU	JIREMENTS
----------------------------------------------------	-----------


Param. No	Symbol	Characteristics	Min	Тур	Мах	Units
PM1		PMALL/PMALH Pulse Width		0.5 TCY		ns
PM2		Address Out Valid to PMALL/PMALH Invalid (address setup time)	—	0.75 Tcy	—	ns
PM3		PMALL/PMALH Invalid to Address Out Invalid (address hold time)	—	0.25 TCY	—	ns
PM5		PMRD Pulse Width	_	0.5 TCY	_	ns
PM6		PMRD or PMENB Active to Data In Valid (data setup time)	—	—	—	ns
PM7		PMRD or PMENB Inactive to Data In Invalid (data hold time)	_	_	_	ns



#### FIGURE 29-11: PARALLEL MASTER PORT WRITE TIMING DIAGRAM

TABLE 29-18: PARALLEL MASTER PORT WRITE TIMING REQUIREMENT
------------------------------------------------------------

Param. No	Symbol	Characteristics	Min	Тур	Мах	Units
PM11		PMWR Pulse Width		0.5 TCY		ns
PM12		Data Out Valid before PMWR or PMENB goes Inactive (data setup time)	—	_	—	ns
PM13		PMWR or PMEMB Invalid to Data Out Invalid (data hold time)	—	—	—	ns
PM16		PMCS Pulse Width	Tcy – 5	_	—	ns



Param No.	Symbol	Characteristic	Min	Мах	Units	Conditions
73	TDIV2scH, TDIV2scL	Setup Time of SDIx Data Input to SCKx Edge	35		ns	VDD = 3.3V, VDDCORE = 2.5V
			100		ns	VDD = 2.15V, VDDCORE = 2.15V
73A	Тв2в	Last Clock Edge of Byte 1 to the 1st Clock Edge of Byte 2	1.5 Tcy + 40	_	ns	
74	TscH2dlL, TscL2dlL	Hold Time of SDIx Data Input to SCKx Edge	30	_	ns	VDD = 3.3V, VDDCORE = 2.5V
			83	_	ns	VDD = 2.15V
75	TDOR	SDOx Data Output Rise Time	—	25	ns	PORTB or PORTC
76	TdoF	SDOx Data Output Fall Time	—	25	ns	PORTB or PORTC
78	TscR	SCKx Output Rise Time (Master mode)	_	25	ns	PORTB or PORTC
79	TscF	SCKx Output Fall Time (Master mode)	—	25	ns	PORTB or PORTC





TABLE 29-20:	<b>EXAMPLE SPI MODE REQUIREMENTS (</b>	(MASTER MODE, CKE = 1)
--------------	----------------------------------------	------------------------

Param. No.	Symbol	Characteristic	Min	Max	Units	Conditions
73	TDIV2scH, TDIV2scL	Setup Time of SDIx Data Input to SCKx Edge	35		ns	VDD = 3.3V, VDDCORE = 2.5V
			100	_	ns	VDD = 2.15V, VDDCORE = 2.15V
74	TscH2dlL, TscL2dlL	Hold Time of SDIx Data Input to SCKx Edge	30	_	ns	VDD = 3.3V, VDDCORE = 2.5V
			83	_	ns	VDD = 2.15V
75	TDOR	SDOx Data Output Rise Time	—	25	ns	PORTB or PORTC
76	TDOF	SDOx Data Output Fall Time	—	25	ns	PORTB or PORTC
78	TscR	SCKx Output Rise Time (Master mode)	—	25	ns	PORTB or PORTC
79	TscF	SCKx Output Fall Time (Master mode)	—	25	ns	PORTB or PORTC
81	TDOV2scH, TDOV2scL	SDOx Data Output Setup to SCKx Edge	Тсү		ns	





Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	$\overline{\text{SSx}} \downarrow$ to SCKx $\downarrow$ or SCKx $\uparrow$ Input		3 Тсү		ns	
70A	TssL2WB	$\overline{SSx} \downarrow$ to Write to SSPxBUF		3 Tcy	_	ns	
71	TscH	SCKx Input High Time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single byte	40		ns	(Note 1)
72	TscL	SCKx Input Low Time	SCKx Input Low Time Continuous 1.			ns	
72A		(Slave mode)	Single byte	40		ns	(Note 1)
73	TDIV2scH, TDIV2scL	Setup Time of SDIx Data Input to SCKx Edge		25	—	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to the First Clock Edge of Byte 2		1.5 Tcy + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDIx Data Input to SC	I Time of SDIx Data Input to SCKx Edge		_	ns	VDD = 3.3V, VDDCORE = 2.5V
				100		ns	VDD = 2.15V
75	TDOR	SDOx Data Output Rise Time		—	25	ns	PORTB or PORTC
76	TDOF	SDOx Data Output Fall Time		—	25	ns	PORTB or PORTC
77	TssH2doZ	SSx ↑ to SDOx Output High-Imped	ance	10	70	ns	
80	TscH2doV, TscL2doV	SDOx Data Output Valid after SCKx Edge		—	50	ns	VDD = 3.3V, VDDCORE = 2.5V
					100	ns	VDD = 2.15V
83	TscH2ssH, TscL2ssH	SSx ↑ after SCKx Edge		1.5 Tcy + 40	_	ns	

**Note 1:** Requires the use of Parameter #73A.

**2:** Only if Parameter #71A and #72A are used.





TABLE 29-22:	EXAMPLE SPI SLAVE MODE REQUIREMENTS (	CKE = 1

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	$\overline{SSx} \downarrow$ to SCKx $\downarrow$ or SCKx $\uparrow$ Input	↓ or SCKx ↑ Input		—	ns	
70A	TssL2WB	$\overline{SSx} \downarrow$ to Write to SSPxBUF		3 Tcy	—	ns	
71	TscH	SCKx Input High Time	Continuous	1.25 Tcy + 30	—	ns	
71A		(Slave mode)	Single byte	40	—	ns	(Note 1)
72	TscL	SCKx Input Low Time	Continuous	1.25 Tcy + 30	—	ns	
72A		(Slave mode)	Single byte	40	—	ns	(Note 1)
73	TDIV2SCH, TDIV2SCL	Setup Time of SDIx Data Input to SCKx Edge		25		ns	
73A	Тв2в	Last Clock Edge of Byte 1 to the First Clock Edge of Byte 2		1.5 Tcy + 40	—	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDIx Data Input to SCKx	Hold Time of SDIx Data Input to SCKx Edge		_	ns	VDD = 3.3V, VDDCORE = 2.5V
				100	_	ns	VDD = 2.15V
75	TDOR	SDOx Data Output Rise Time		—	25	ns	
76	TDOF	SDOx Data Output Fall Time		—	25	ns	
77	TssH2doZ	SSx ↑ to SDOx Output High-Impedan	се	10	70	ns	
80	TscH2doV, TscL2doV	SDOx Data Output Valid after SCKx E	dge	—	50	ns	VDD = 3.3V, VDDCORE = 2.5V
				—	100	ns	VDD = 2.15V
81	TDOV2scH, TDOV2scL	SDOx Data Output Setup to SCKx Ed	Ox Data Output Setup to SCKx Edge		_	ns	
82	TssL2DoV	SDOx Data Output Valid after $\overline{\text{SSx}} \downarrow$ E	dge	_	50	ns	
83	TscH2ssH, TscL2ssH	SSx ↑ after SCKx Edge		1.5 Tcy + 40	—	ns	

**Note 1:** Requires the use of Parameter #73A.

**2:** Only if Parameter #71A and #72A are used.




## TABLE 29-23: I<sup>2</sup>C<sup>™</sup> BUS START/STOP BITS REQUIREMENTS (SLAVE MODE)

Param. No.	Symbol	Characte	ristic	Min	Max	Units	Conditions	
90	TSU:STA	Start Condition	100 kHz mode	4700	_	ns	Only relevant for Repeated	
		Setup Time	400 kHz mode	600	—		Start condition	
91	THD:STA	Start Condition	100 kHz mode	4000	_	ns	After this period, the first	
		Hold Time	400 kHz mode	600	_		clock pulse is generated	
92	Tsu:sto	Stop Condition	100 kHz mode	4700	_	ns		
		Setup Time	400 kHz mode	600	_			
93	THD:STO	Stop Condition	100 kHz mode	4000	_	ns		
		Hold Time	400 kHz mode	600				

#### FIGURE 29-17:

### I<sup>2</sup>C<sup>™</sup> BUS DATA TIMING




Param. No.	Symbol	Characteris	tic	Min	Max	Units	Conditions
100	Тнідн	Clock High Time	100 kHz mode	4.0	_	μs	
			400 kHz mode	0.6	_	μS	
			MSSP modules	1.5 TCY	_		
101	TLOW	Clock Low Time	100 kHz mode	4.7	—	μS	
			400 kHz mode	1.3	—	μS	
			MSSP modules	1.5 TCY	—		
102	TR	SDAx and SCLx Rise Time	100 kHz mode	—	1000	ns	
			400 kHz mode	20 + 0.1 CB	300	ns	CB is specified to be from 10 to 400 pF
103	TF	SDAx and SCLx Fall Time	100 kHz mode	—	300	ns	
			400 kHz mode	20 + 0.1 Св	300	ns	CB is specified to be from 10 to 400 pF
90	TSU:STA	Start Condition Setup Time	100 kHz mode	4.7	—	μS	Only relevant for Repeated
			400 kHz mode	0.6	—	μS	Start condition
91	THD:STA	Start Condition Hold Time	100 kHz mode	4.0	—	μs	After this period, the first clock
			400 kHz mode	0.6	—	μs	pulse is generated
106	THD:DAT	Data Input Hold Time	100 kHz mode	0	—	ns	
			400 kHz mode	0	0.9	μS	
107	TSU:DAT	Data Input Setup Time	100 kHz mode	250	—	ns	(Note 2)
			400 kHz mode	100	—	ns	
92	Tsu:sto	Stop Condition Setup Time	100 kHz mode	4.7	_	μS	
			400 kHz mode	0.6	—	μS	
109	ΤΑΑ	Output Valid from Clock	100 kHz mode	—	3500	ns	(Note 1)
			400 kHz mode		_	ns	
110	TBUF	Bus Free Time	100 kHz mode	4.7	_	μS	Time the bus must be free
			400 kHz mode	1.3	—	μS	before a new transmission can start
D102	Св	Bus Capacitive Loading		_	400	pF	

### TABLE 29-24: I<sup>2</sup>C<sup>™</sup> BUS DATA REQUIREMENTS (SLAVE MODE)

**Note 1:** As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCLx to avoid unintended generation of Start or Stop conditions.

2: A Fast mode I<sup>2</sup>C<sup>™</sup> bus device can be used in a Standard mode I<sup>2</sup>C bus system, but the requirement, TSU:DAT ≥ 250 ns, must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCLx signal. If such a device does stretch the LOW period of the SCLx signal, it must output the next data bit to the SDAx line, TR max. + TSU:DAT = 1000 + 250 = 1250 ns (according to the Standard mode I<sup>2</sup>C bus specification), before the SCLx line is released.





### TABLE 29-25: MSSPx I<sup>2</sup>C<sup>™</sup> BUS START/STOP BITS REQUIREMENTS

Param. No.	Symbol	Characteristic		Min	Max	Units	Conditions
90	TSU:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)		ns	Only relevant for
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_		Repeated Start
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	—		condition
91	THD:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	After this period, the first clock pulse is generated
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)			
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)			
92	Tsu:sto	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)			
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)			
93	THD:STO	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ns	
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)	_	1	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)		1	

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.




FIGURE 29-19: MSSPx I<sup>2</sup>C™ BUS DATA TIMING


Param. No.	Symbol	Charac	teristic	Min	Max	Units	Conditions	
100	Тнідн	Clock High Time	100 kHz mode	2(Tosc)(BRG + 1)	_	μS		
			400 kHz mode	2(Tosc)(BRG + 1)		μS		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)		μs		
101	TLOW	Clock Low Time	100 kHz mode	2(Tosc)(BRG + 1)	—	μs		
			400 kHz mode	2(Tosc)(BRG + 1)		μS		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)		μs		
102	TR	SDAx and SCLx	100 kHz mode	_	1000	ns	CB is specified to be	
		Rise Time	400 kHz mode	20 + 0.1 Св	300	ns	from 10 to 400 pF	
			1 MHz mode <sup>(1)</sup>	_	300	ns		
103	TF	SDAx and SCLx	100 kHz mode	_	300	ns	CB is specified to be	
		Fall Time	400 kHz mode	20 + 0.1 Св	300	ns	from 10 to 400 pF	
			1 MHz mode <sup>(1)</sup>	_	100	ns		
90	TSU:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	μs	Only relevant for	
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	—	μS	Repeated Start condition	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	μs		
91	THD:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	μS	After this period, the first	
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)	_	μs	clock pulse is generated	
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	μs		
106	THD:DAT	Data Input	100 kHz mode	0	_	ns		
		Hold Time	400 kHz mode	0	0.9	μs		
			1 MHz mode <sup>(1)</sup>	TBD	_	ns		
107	TSU:DAT	Data Input	100 kHz mode	250		ns	(Note 2)	
		Setup Time	400 kHz mode	100		ns		
			1 MHz mode <sup>(1)</sup>	TBD	_	ns		
92	Tsu:sto	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	μs		
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_	μs		
			1 MHz mode <sup>(1)</sup>	2(Tosc)(BRG + 1)	_	μs		
109	ΤΑΑ	Output Valid	100 kHz mode	_	3500	ns		
		from Clock	400 kHz mode	_	1000	ns		
			1 MHz mode <sup>(1)</sup>	_	—	ns		
110	TBUF	Bus Free Time	100 kHz mode	4.7	—	μS	Time the bus must be	
			400 kHz mode	1.3	_	μs	free before a new	
			1 MHz mode <sup>(1)</sup>	TBD	_	μs	transmission can start	
D102	Св	Bus Capacitive Lo	bading	_	400	pF		

### TABLE 29-26: MSSPx I<sup>2</sup>C<sup>™</sup> BUS DATA REQUIREMENTS

Legend: TBD = To Be Determined

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.


<sup>2:</sup> A Fast mode I<sup>2</sup>C bus device can be used in a Standard mode I<sup>2</sup>C bus system, but parameter #107 ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCLx signal. If such a device does stretch the LOW period of the SCLx signal, it must output the next data bit to the SDAx line, parameter #102 + parameter #107 = 1000 + 250 = 1250 ns (for 100 kHz mode), before the SCLx line is released.



#### TABLE 29-27: EUSARTx SYNCHRONOUS TRANSMISSION REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Мах	Units	Conditions
120	TCKH2DTV	<u>Sync XMIT (Master and Slave)</u> Clock High to Data Out Valid	_	40	ns	
121	TCKRF	Clock Out Rise Time and Fall Time (Master mode)	_	20	ns	
122	TDTRF	Data Out Rise Time and Fall Time	_	20	ns	

#### FIGURE 29-21: EUSARTx SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING




#### TABLE 29-28: EUSARTx SYNCHRONOUS RECEIVE REQUIREMENTS

Param. No.	Symbol	Characteristic	Min	Max	Units	Conditions
125	TDTV2CKL	Sync RCV (Master and Slave) Data Hold before CKx $\downarrow$ (DTx hold time)	10	_	ns	
126	TCKL2DTL	Data Hold after CKx $\downarrow$ (DTx hold time)	15	_	ns	

Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
A01	NR	Resolution	_		10	bit	$\Delta VREF \ge 3.0V$
A03	EIL	Integral Linearity Error	_	_	<±1	LSb	$\Delta VREF \ge 3.0V$
A04	Edl	Differential Linearity Error	_	_	<±1	LSb	$\Delta VREF \ge 3.0V$
A06	EOFF	Offset Error	_	_	<±3	LSb	$\Delta VREF \ge 3.0V$
A07	Egn	Gain Error	_	_	<±3.5	LSb	$\Delta VREF \ge 3.0V$
A10		Monotonicity	G	uarantee	d <sup>(1)</sup>		$VSS \leq VAIN \leq VREF$
A20	$\Delta VREF$	Reference Voltage Range (VREFH – VREFL)	2.0 3			V V	$\begin{array}{l} VDD < 3.0V \\ VDD \geq 3.0V \end{array}$
A21	VREFH	Reference Voltage High	VREFL	_	VDD + 0.3V	V	
A22	VREFL	Reference Voltage Low	Vss – 0.3V	_	VREFH	V	
A25	VAIN	Analog Input Voltage	VREFL	_	VREFH	V	
A30	ZAIN	Recommended Impedance of Analog Voltage Source	—		10	kΩ	
A50	IREF	VREF Input Current <sup>(2)</sup>	—		5 150	μA μA	During VAIN acquisition. During A/D conversion cycle.

#### TABLE 29-29: A/D CONVERTER CHARACTERISTICS: PIC18F46J50 FAMILY (INDUSTRIAL)

 Note 1: The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.
 2: VREFH current is from RA3/AN3/VREF+/C1INB pin or VDD, whichever is selected as the VREFH source. VREFL current is from RA2/AN2/VREF-/CVREF/C2INB pin or VSS, whichever is selected as the VREFL source.



#### FIGURE 29-22: A/D CONVERSION TIMING


#### TABLE 29-30: A/D CONVERSION REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Max	Units	Conditions
130	Tad	A/D Clock Period	0.7	25.0 <sup>(1)</sup>	μS	Tosc based, VREF $\geq$ 3.0V
131	TCNV	Conversion Time (not including acquisition time) <sup>(2)</sup>	11	12	Tad	
132	TACQ	Acquisition Time <sup>(3)</sup>	1.4	—	μS	-40°C to +85°C
135	Tswc	Switching Time from Convert $\rightarrow$ Sample		(Note 4)		
137	TDIS	Discharge Time	0.2	_	μS	

**Note 1:** The time of the A/D clock period is dependent on the device frequency and the TAD clock divider.

- 2: ADRES registers may be read on the following TCY cycle.
- **3:** The time for the holding capacitor to acquire the "New" input voltage when the voltage changes full scale after the conversion (VDD to Vss or Vss to VDD). The source impedance (Rs) on the input channels is 50Ω.
- 4: On the following cycle of the device clock.

#### FIGURE 29-23: USB SIGNAL TIMING



#### TABLE 29-31: USB LOW-SPEED TIMING REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
	Tlr	Transition Rise Time	75	_	300	ns	CL = 200 to 600 pF
	Tlf	Transition Fall Time	75	_	300	ns	CL = 200 to 600 pF
	TLRFM	Rise/Fall Time Matching	80		125	%	

#### TABLE 29-32: USB FULL-SPEED REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Тур	Max	Units	Conditions
	Tfr	Transition Rise Time	4	_	20	ns	CL = 50 pF
	Tff	Transition Fall Time	4	—	20	ns	CL = 50 pF
	TFRFM	Rise/Fall Time Matching	90	_	111.1	%	

NOTES:

### **30.0 PACKAGING INFORMATION**

### 30.1 Package Marking Information

#### 28-Lead SPDIP



#### 28-Lead SSOP




#### 28-Lead SOIC (.300")



#### 28-Lead QFN



Example



### Example



#### Example




### Example



Legend	d: XXX	Customer-specific information
	Y	Year code (last digit of calendar year)
	YY	Year code (last 2 digits of calendar year)
	WW	Week code (week of January 1 is week '01')
	NNN	Alphanumeric traceability code
		Pb-free JEDEC designator for Matte Tin (Sn)
	*	This package is Pb-free. The Pb-free JEDEC designator ( $(e_3)$ )
		can be found on the outer packaging for this package. $\smile$
Note:	In the eve	nt the full Microchip part number cannot be marked on one line, it will
		d over to the next line, thus limiting the number of available s for customer-specific information.


44-Lead QFN



Example



44-Lead TQFP



Example




### 30.2 Package Details

The following sections give the technical details of the packages.

### 28-Lead Skinny Plastic Dual In-Line (SP) – 300 mil Body [SPDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units				
	Dimension Limits			MAX	
Number of Pins	N	28			
Pitch	e		.100 BSC		
Top to Seating Plane	A	-	-	.200	
Molded Package Thickness	A2	.120	.135	.150	
Base to Seating Plane	A1	.015	-	-	
Shoulder to Shoulder Width	E	.290	.310	.335	
Molded Package Width	E1	.240	.285	.295	
Overall Length	D	1.345	1.365	1.400	
Tip to Seating Plane	L	.110	.130	.150	
Lead Thickness	С	.008	.010	.015	
Upper Lead Width	b1	.040	.050	.070	
Lower Lead Width	b	.014	.018	.022	
Overall Row Spacing §	eB	-	-	.430	


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-070B

### 28-Lead Plastic Shrink Small Outline (SS) – 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS	6
Dimensio	n Limits	MIN	NOM	MAX
Number of Pins	Ν		28	
Pitch	е		0.65 BSC	
Overall Height	А	-	-	2.00
Molded Package Thickness	A2	1.65	1.75	1.85
Standoff	A1	0.05	-	-
Overall Width	E	7.40	7.80	8.20
Molded Package Width	E1	5.00	5.30	5.60
Overall Length	D	9.90	10.20	10.50
Foot Length	L	0.55	0.75	0.95
Footprint	L1		1.25 REF	
Lead Thickness	с	0.09	_	0.25
Foot Angle	ф	0°	4°	8°
Lead Width	b	0.22	-	0.38

#### Notes:

1. Pin 1 visual index feature may vary, but must be located within the hatched area.

2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.20 mm per side.


- 3. Dimensioning and tolerancing per ASME Y14.5M.
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.


REF: Reference Dimension, usually without tolerance, for information purposes only.


Microchip Technology Drawing C04-073B


### 28-Lead Plastic Small Outline (SO) – Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging









	Units		MILLIMETERS	;
	Dimension Limits	MIN	NOM	MAX
Number of Pins	N		28	
Pitch	e		1.27 BSC	
Overall Height	А	-	-	2.65
Molded Package Thickness	A2	2.05	-	-
Standoff §	A1	0.10	-	0.30
Overall Width	E	10.30 BSC		
Molded Package Width	E1	7.50 BSC		
Overall Length	D		17.90 BSC	
Chamfer (optional)	h	0.25	-	0.75
Foot Length	L	0.40	-	1.27
Footprint	L1		1.40 REF	
Foot Angle Top	φ	0°	-	8°
Lead Thickness	С	0.18	-	0.33
Lead Width	b	0.31	-	0.51
Mold Draft Angle Top	α	5°	-	15°
Mold Draft Angle Bottom	β	5°	-	15°

Notes:

1. Pin 1 visual index feature may vary, but must be located within the hatched area.

2. § Significant Characteristic.

3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15 mm per side.


- 4. Dimensioning and tolerancing per ASME Y14.5M.
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-052B

## 28-Lead Plastic Quad Flat, No Lead Package (ML) – 6x6 mm Body [QFN] with 0.55 mm Contact Length

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS	
Dimensio	n Limits	MIN	NOM	MAX
Number of Pins	Ν		28	
Pitch	е		0.65 BSC	
Overall Height	А	0.80	0.90	1.00
Standoff	A1	0.00	0.02	0.05
Contact Thickness	A3		0.20 REF	
Overall Width	E		6.00 BSC	
Exposed Pad Width	E2	3.65	3.70	4.20
Overall Length	D		6.00 BSC	
Exposed Pad Length	D2	3.65	3.70	4.20
Contact Width	b	0.23	0.30	0.35
Contact Length	L	0.50	0.55	0.70
Contact-to-Exposed Pad	К	0.20	-	_

#### Notes:

1. Pin 1 visual index feature may vary, but must be located within the hatched area.

2. Package is saw singulated.


3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-105B

## 28-Lead Plastic Quad Flat, No Lead Package (ML) – 6x6 mm Body [QFN] with 0.55 mm Contact Length





Units			MILLIM	ETERS
Dimensior	Dimension Limits		NOM	MAX
Contact Pitch	E		0.65 BSC	
Optional Center Pad Width	W2			4.25
Optional Center Pad Length	T2			4.25
Contact Pad Spacing	C1		5.70	
Contact Pad Spacing	C2		5.70	
Contact Pad Width (X28)	X1			0.37
Contact Pad Length (X28)	Y1			1.00
Distance Between Pads	G	0.20		

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2105A

### 44-Lead Plastic Quad Flat, No Lead Package (ML) – 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging





	Units		MILLIMETERS	6
Dimensio	n Limits	MIN	NOM	MAX
Number of Pins	Ν		44	
Pitch	е		0.65 BSC	
Overall Height	Α	0.80	0.90	1.00
Standoff	A1	0.00	0.02	0.05
Contact Thickness	A3		0.20 REF	
Overall Width	Е		8.00 BSC	
Exposed Pad Width	E2	6.30	6.45	6.80
Overall Length	D		8.00 BSC	
Exposed Pad Length	D2	6.30	6.45	6.80
Contact Width	b	0.25	0.30	0.38
Contact Length	L	0.30	0.40	0.50
Contact-to-Exposed Pad	K	0.20	_	_

#### Notes:

1. Pin 1 visual index feature may vary, but must be located within the hatched area.

2. Package is saw singulated.

3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-103B

#### 44-Lead Plastic Quad Flat, No Lead Package (ML) – 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimensio	n Limits	MIN	NOM	MAX
Contact Pitch	E		0.65 BSC	
Optional Center Pad Width	W2			6.80
Optional Center Pad Length	T2			6.80
Contact Pad Spacing	C1		8.00	
Contact Pad Spacing	C2		8.00	
Contact Pad Width (X44)	X1			0.35
Contact Pad Length (X44)	Y1			0.80
Distance Between Pads	G	0.25		

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2103A

### 44-Lead Plastic Thin Quad Flatpack (PT) – 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Notes:

1. Pin 1 visual index feature may vary, but must be located within the hatched area.

2. Chamfers at corners are optional; size may vary.

Mold Draft Angle Top

Mold Draft Angle Bottom

3. Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.25 mm per side.

α

β

11°

11°

12°

12°

4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.


Microchip Technology Drawing C04-076B

13°

13°

### 44-Lead Plastic Thin Quad Flatpack (PT) – 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



**RECOMMENDED LAND PATTERN** 

	Units	MILLIM	ETERS	
Dimension	Limits	MIN	NOM	MAX
Contact Pitch	E		0.80 BSC	
Contact Pad Spacing	C1		11.40	
Contact Pad Spacing	C2		11.40	
Contact Pad Width (X44)	X1			0.55
Contact Pad Length (X44)	Y1			1.50
Distance Between Pads	G	0.25		

Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2076A

NOTES:

## APPENDIX A: REVISION HISTORY

### **Revision A (September 2008)**

Original data sheet for the PIC18F46J50 family of devices.

### **Revision B (March 2009)**

Changes to the Electrical Characteristics and minor text edits throughout the document.

### **Revision C (October 2009)**

Removed "Preliminary" marking.

### APPENDIX B: DEVICE DIFFERENCES

The differences between the devices listed in this data sheet are shown in Table B-1,

Features	PIC18F24J50	PIC18F25J50	PIC18F26J50	PIC18F44J50	PIC18F45J50	PIC18F46J50
Program Memory	16K	32K	64K	16K	32K	64K
Program Memory (Instructions)	8,192	16,384	32,768	8,192	16,384	32,768
I/O Ports (Pins)		Ports A, B, C			Ports A, B, C, D, E	
10-Bit ADC Module		10 Input Channels			13 Input Channels	
Packages	28-Pin QFN,	SOIC, SSOP and SP	DIP (300 mil)		44-Pin QFN and TQFP	1

#### TABLE B-1: DEVICE DIFFERENCES BETWEEN PIC18F46J50 FAMILY MEMBERS

NOTES:

## INDEX

Α

A/D	
A/D Converter Interrupt, Configuring	
Acquisition Requirements	. 346
ADCAL Bit	. 349
ADRESH Register	. 344
Analog Port Pins, Configuring	. 347
Associated Registers	
Automatic Acquisition Time	
Calibration	
Configuring the Module	
Conversion Clock (TAD)	
Conversion Requirements	
Conversion Status (GO/DONE Bit)	
Conversions	
Converter Characteristics	
Operation in Power-Managed Modes	
Special Event Trigger (ECCPx)	
Use of the ECCP2 Trigger	. 348
Absolute Maximum Ratings	. 485
AC (Timing) Characteristics	. 504
Load Conditions for Device Timing Specifications .	. 505
Parameter Symbology	
Temperature and Voltage Specifications	
Timing Conditions	
ACKSTAT	
ACKSTAT Status Flag	
5	
ADCAL Bit	. 349
ADCON0 Register	
GO/DONE Bit	
ADDFSR	
ADDLW	437
ADDULNK	. 474
ADDWF	. 437
ADDWFC	. 438
ADRESL Register	. 344
Analog-to-Digital Converter. See A/D.	
ANDLW	. 438
ANDWF	
Assembler	
MPASM Assembler	482
Auto-Wake-up on Sync Break Character	
Auto-wake-up on Sync bleak character	. 550
В	
Roud Data Concreter	202
Baud Rate Generator	
BC	
BCF	
BF	
BF Status Flag	. 307
Block Diagrams	
+5V System Hardware Interface	. 126
8-Bit Multiplexed Address and Data Application	. 185
A/D	. 344
Analog Input Model	. 345
Baud Rate Generator	
Capture Mode Operation	
Clock Source Multiplexing	
Comparator Analog Input Model	
Comparator Output	
Comparator Voltage Reference	
Comparator Voltage Reference Output Buffer Exan	pie
389	
CTMU	. 397

CTMU Current Source Calibration Circuit CTMU Typical Connections and Internal Config for Pulse Delay Generation	uration
CTMU Typical Connections and Internal Config for Time Measurement	uration
Demultiplexed Addressing Mode	
Device Clock	
Enhanced PWM Mode	
EUSART Transmit	
EUSARTx Receive	
Fail-Safe Clock Monitor	
Fully Multiplexed Addressing Mode	
Generic I/O Port Operation	
High/Low-Voltage Detect with External Input Interrupt Logic	
LCD Control	
Legacy Parallel Slave Port	
MSSPx (I <sup>2</sup> C Master Mode)	
MSSPx (I <sup>2</sup> C Mode)	282
MSSPx (SPI Mode)	
Multiplexed Addressing Application	
On-Chip Reset Circuit	
Parallel EEPROM (Up to 15-Bit Address, 16-Bit I	
186 Parallel EEPROM (Up to 15-Bit Address, 8-Bit Da	
186	
Parallel Master/Slave Connection Addressed Buf	
Parallel Master/Slave Connection Buffered	
Partially Multiplexed Addressing Application	
Partially Multiplexed Addressing Mode	
PIC18F2XJ50 (28-Pin)	14
PIC18F4XJ50 (44-Pin)	
PMP Module	
PWM Operation (Simplified) Reads From Flash Program Memory	244
RTCC	
Simplified Steering	
Single Comparator	
Table Read Operation	
Table Write Operation	
Table Writes to Flash Program Memory	
Timer0 in 16-Bit Mode	
Timer0 in 8-Bit Mode	
Timer1	
Timer2	
Timer3	
Timer4	
USB Interrupt Logic	
USB Peripheral and Options	
Using the Open-Drain Output	
USTAT FIFO	
Watchdog Timer	
BN	
BNC	
BNN	441
BNOV	442
BNZ	442
BOR. See Brown-out Reset.	
BOV	445
BRA	
Break Character (12-Bit) Transmit and Receive	332
BRG. See Baud Rate Generator.	
Brown-out Reset (BOR)	59

and On-Chip Voltage Regulator	
Detecting	59
Disabling in Sleep Mode	
BSF	
BTFSC	
BTFSS	
BTG	
BZ	

### С

C Compilers	
MPLAB C18	482
MPLAB C30	.482
Calibration (A/D Converter)	.349
CALL	.446
CALLW	475
Capture (ECCP Module)	242
CCPRxH:CCPRxL Registers	
ECCP Pin Configuration	
Prescaler	
Software Interrupt	
Timer1/Timer3 Mode Selection	
Clock Sources	
Effects of Power-Managed Modes	
Selecting the 31 kHz Source	30
Selection Using OSCCON Register	
CLRF	
CLRWDT	.447
Code Examples	
16 x 16 Signed Multiply Routine	
16 x 16 Unsigned Multiply Routine	. 108
512-Byte SPI Master Mode Init and Transfer	280
8 x 8 Signed Multiply Routine	. 107
8 x 8 Unsigned Multiply Routine	. 107
A/D Calibration Routine	.349
Calculating Baud Rate Error	
Capacitance Calibration Routine	
Capacitive Touch Switch Routine	
Changing Between Capture Prescalers	
Communicating with the +5V System	
Computed GOTO Using an Offset Value	
Configuring EUSART2 Input and Output Functions	
Current Calibration Routine	
Erasing Flash Program Memory	
Fast Register Stack	
How to Clear RAM (Bank 1) Using Indirect Address	ng .
91	
Initializing PORTA	
Initializing PORTB	
Initializing PORTC	. 136
Initializing PORTD	. 139
Initializing PORTE	
Loading the SSP1BUF (SSP1SR) Register	267
Reading a Flash Program Memory Word	.101
Saving STATUS, WREG and BSR Registers in RAM	
124	
Setting the RTCWREN Bit	233
Setup for CTMU Calibration Routines	
Two-Word Instructions	
Ultra Low-Power Wake-up Initialization	
Writing to Flash Program Memory	
Code Protection	
COMF	
Comparator	
Analog Input Connection Considerations	
Associated Registers	. 385

Configuration	383
Control	
Effects of a Reset	
Enable and Input Selection	383
Enable and Output Selection	383
Interrupts	384
Operation	
Operation During Sleep	385
Registers	379
Response Time	382
Comparator Specifications	500
Comparator Voltage Reference	387
Accuracy and Error	389
Associated Registers	389
Configuring	388
Connection Considerations	389
Effects of a Reset	389
Operation During Sleep	389
Compare (ECCP Module)	
CCPRx Register	
Pin Configuration	
Software Interrupt	
Special Event Trigger	
Timer1/Timer3 Mode Selection	
Compare (ECCPx Module)	
Special Event Trigger	348
Computed GOTO	
Configuration Bits	
Configuration Mismatch (CM) Reset	
Configuration Register Protection	
Configuration Registers	
Bits and Device IDs	414
Mapping Flash Configuration Words	
Core Features	
Easy Migration	12
Expanded Memory	
Extended Instruction Set	
nanoWatt Technology	
Oscillator Options and Features	
Universal Serial Bus (USB)	
CPFSEQ	
CPFSGT	
CPFSLT	
Crystal Oscillator/Ceramic Resonators	
CTMU	
Associated Registers	411
Calibrating	
Creating a Delay with	
Effects of a Reset	
Initialization	
Measuring Capacitance with	
Measuring Time with	
-	
Operation Operation During Idle Mode	
Operation During Sleep Mode	
CTMU Current Source Specifications	
Customer Change Notification Service	
Customer Notification Service	
Customer Support	551
D	
– Data Addressing Modes	01
บลเล กับนเธออแบ่ เพบนธอ	

Data Ac	Idressing	Modes					91
Co	mparing	Addressing	Modes	with	the	Extended	١n
	structio	on Set Enabl	ed				95
Dii	rect						91
Inc	lexed Lite	eral Offset					94

BSR96
Instructions Affected94
Mapping Access Bank96
Indirect
Inherent and Literal91
Data Memory78
Access Bank80
Bank Select Register (BSR)78
Extended Instruction Set93
General Purpose Registers80
Memory Maps
Access Bank Special Function Registers81
Non-Access Bank Special Function Registers82
PIC18F46J50 Family Devices79
Special Function Registers81
Context Defined SFRs83
USB RAM78
DAW
DC Characteristics
Power-Down and Supply Current 488
Supply Voltage487
DCFSNZ451
DECF
DECFSZ
Development Support 481
Device Differences537
Device Overview11
Details on Individual Family Members12
Features (28-Pin Devices)13
Features (44-Pin Devices)13
Other Special Features12
Direct Addressing92

#### Е

Effect on Standard PICMCU Instructions Electrical Characteristics	485 485 498 239
Compare Mode. See Compare.	
ECCP Mode and Timer Resources	241
Enhanced PWM Mode	247
Auto-Restart	256
Auto-Shutdown	
Direction Change in Full-Bridge Output Mode .	
Full-Bridge Application	
Full-Bridge Mode	
Half-Bridge Application	
Half-Bridge Application Examples	
Half-Bridge Mode	
Output Relationships (Active-High and Active-L	,
Output Relationships Diagram	
Programmable Dead-Band Delay	
Shoot-Through Current	
Start-up Considerations	
Outputs and Configuration	
Enhanced Universal Synchronous Asynchronous Rece	lver
Transmitter (EUSART). See EUSART.	
Equations A/D Acquisition Time A/D Minimum Charging Time Bytes Transmitted for a Given DMABC	346 278
Calculating the Minimum Required Acquisition Time	

ς.	1	0
. <b>7</b> 4	-	n

346	
Calculating USB Transceiver Current	374
Estimating USB Transceiver Current Consumption	373
Errata	9
EUSART	317
Asynchronous Mode	327
12-Bit Break Transmit and Receive	332
Associated Registers, Reception	330
Associated Registers, Transmission	
Auto-Wake-up on Sync Break	
Receiver	
Setting Up 9-Bit Mode with Address Detect	
Transmitter	
Baud Rate Generator	
Operation in Power-Managed Mode	321
Baud Rate Generator (BRG)	
Associated Registers	
Auto-Baud Rate Detect	
Baud Rates, Asynchronous Modes	
Formulas	
High Baud Rate Select (BRGH Bit)	
Sampling	
Synchronous Master Mode	
Associated Registers, Reception	
Associated Registers, Transmission	
Reception	
Transmission	
Synchronous Slave Mode	
Associated Registers, Reception	
Associated Registers, Transmission	
Reception	
Transmission	337
Extended Instruction Set	
ADDFSR	474
ADDULNK	474
CALLW	475
MOVSF	475
MOVSS	476
PUSHL	476
SUBFSR	477
SUBULNK	477
Extended Instructions	
Considerations when Enabling	478
External Clock Input	
F = F =	

### F

Fail-Safe Clock Monitor	413, 427
Interrupts in Power-Managed Modes	429
POR or Wake-up From Sleep	429
WDT During Oscillator Failure	428
Fast Register Stack	
Features Overview	3
Comparative Table	4
Firmware Instructions	431
Flash Program Memory	97
Associated Registers	106
Control Registers	98
EECON1 and EECON2	98
TABLAT (Table Latch) Register	100
TBLPTR (Table Pointer) Register	100
Erase Sequence	102
Erasing	102
Operation During Code-Protect	106
Reading	101
Table Pointer	
Boundaries Based on Operation	100

Table Pointer Boundaries	
Table Reads and Table Writes	
Write Sequence	
Writing	
Unexpected Termination	
Write Verify	
FSCM. See Fail-Safe Clock Monitor.	

### G

GOTO	452
н	
Hardware Multiplier	
8 x 8 Multiplication Algorithms	
Operation	
Performance Comparison (table)	
High/Low-Voltage Detect	
Applications	
Associated Registers	
Characteristics	
Current Consumption	
Effects of a Reset	
Operation	
During Sleep	
Setup	
Start-up Time	
Typical Application	

### I

l	
I/O Ports	125
Open-Drain Outputs	126
Pin Capabilities	125
TTL Input Buffer Option	126
I <sup>2</sup> C Mode	282
I <sup>2</sup> C Mode (MSSP)	
Acknowledge Sequence Timing	310
Associated Registers	316
Baud Rate Generator	303
Bus Collision	
During a Repeated Start Condition	314
During a Stop Condition	315
Clock Arbitration	305
Clock Stretching	297
10-Bit Slave Receive Mode (SEN = 1)	297
10-Bit Slave Transmit Mode	297
7-Bit Slave Receive Mode (SEN = 1)	297
7-Bit Slave Transmit Mode	297
Clock Synchronization and CKP bit	298
Effects of a Reset	311
General Call Address Support	301
I <sup>2</sup> C Clock Rate w/BRG	304
Master Mode	301
Operation	303
Reception	307
Repeated Start Condition Timing	306
Start Condition Timing	305
Transmission	307
Multi-Master Communication, Bus Collision and A	rbitra-
tion	311
Multi-Master Mode	311
Operation	287
Read/Write Bit Information (R/W Bit)	7, 290
Registers	282
Serial Clock (SCLx Pin)	
Slave Mode	287
Addressing	287

Addressing Masking Modes	
5-Bit	288
7-Bit	289
Reception	
Transmission	
Sleep Operation	
Stop Condition Timing	
INCFSZ	
In-Circuit Debugger	
In-Circuit Serial Programming (ICSP)	430
Indexed Literal Offset Addressing and Standard PIC18 Instructions	179
Indexed Literal Offset Mode	
Indirect Addressing	
INFSNZ	
Initialization Conditions for All Registers ??	
Instruction Cycle	
Clocking Scheme	
Flow/Pipelining	
Instruction Set	431
ADDLW	437
ADDWF	437
ADDWF (Indexed Literal Offset Mode)	
ADDWFC	
ANDLW	
ANDWF	
BC	
BCF BN	
BN BNC	
BNC	
BNOV	
BNZ	
BOV	
BRA	
BSF	443
BSF (Indexed Literal Offset Mode)	479
BTFSC	444
BTFSS	
BTG	
BZ	
CALL	
CLRF	
COMF	
CPFSEQ	
CPFSGT	
CPFSLT	
DAW	450
DCFSNZ	451
DECF	
DECFSZ	
Extended Instructions	
Considerations when Enabling	
Syntax	
Use with MPLAB IDE Tools	
General Format GOTO	
INCF	
INCFSZ	
INFSNZ	
IORLW	
IORWF	
LFSR	455

MOVF	.455
MOVFF	
MOVLB	
MOVLW	. 457
MOVWF	. 457
MULLW	. 458
MULWF	. 458
NEGF	. 459
NOP	
Opcode Field Descriptions	
POP	
PUSH	
RCALL	
RESET	
RETURN RLCF	
RLNCF	
RRCF	
RRNCF	
SETF	
SETF (Indexed Literal Offset Mode)	
SLEEP	
Standard Instructions	
SUBFWB	
SUBLW	. 467
SUBWF	. 467
SUBWFB	. 468
SWAPF	. 468
TBLRD	. 469
TBLWT	
TSTFSZ	. 471
XORLW	
XORWF	. 472
XORWF	. 472 . 111
XORWF INTCON INTCON Registers	. 472 . 111 –113
XORWF INTCON INTCON Registers	. 472 . 111 –113 32
XORWF INTCON INTCON Registers	. 472 . 111 –113 32 33
XORWF	. 472 . 111 –113 32 33
XORWF INTCON INTCON Registers	.472 .111 –113 32 33 33
XORWF INTCON INTCON Registers	. 472 . 111 –113 32 33 33 . 423
XORWF	. 472 . 111 –113 32 33 33 . 423 . 501
XORWF	. 472 . 111 –113 32 33 33 . 423 . 501 . 551
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413 .345
XORWF	.472 .111 -113 32 33 .423 .501 .551 .413 .345 .242
XORWF	. 472 . 111 -113 32 33 33 . 423 . 501 . 551 . 413 . 345 . 242 . 243
XORWF	. 472 . 111 -113 32 33 33 . 423 . 501 . 551 . 413 . 345 . 242 . 243 . 132
XORWF	. 472 . 111 -113 32 33 33 . 423 . 501 . 551 . 413 . 345 . 242 . 243 . 132 . 191 . 199
XORWF	. 472 . 111 -113 32 33 33 . 423 . 501 . 551 . 413 . 345 . 242 . 243 . 132 . 191 . 199 , 215
XORWF	.472 .111 -113 32 33 33 .501 .551 .413 .345 .242 .243 .132 .191 .199 ,215 .218
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413 .345 .242 .243 .132 .191 .199 ,215 .218 .217
XORWF	.472 .111 -113 32 33 33 .501 .551 .413 .345 .242 .243 .132 .191 .199 ,215 .218 .217 .109
XORWF	.472 .111 -113 32 33 33 .501 .551 .413 .345 .242 .243 .132 .191 .199 ,215 .218 .217 .109
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413 .345 .242 .243 .132 .191 .199 ,215 .218 .217 .109 .109
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413 .345 .242 .243 .132 .191 .199 ,215 .218 .217 .109 .109 .124
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413 .345 .242 .191 .199 .215 .218 .217 .109 .109 .109 .124 .124
XORWF	. 472 . 111 -113 32 33 33 33 33 33 423 551 423 551 413 345 242 243 109 109 109 109 109 124 124 124
XORWF	.472 .111 -113 32 33 33 .423 .501 .551 .413 .345 .242 .131 .199 .215 .218 .217 .109 .109 .109 .124 .124 .124 .123

Interrupts, Flag Bits	
Interrupt-on-Change (RB7:RB4) Flag (RBIF Bit)	132
INTOSC Frequency Drift	33
INTOSC, INTRC. See Internal Oscillator Block.	
IORLW	454
IORWF	454
IPR Registers 120	)_??

#### L

_	
LFSR	455
Low-Power Modes	
Clock Transitions and Status Indicators	
Deep Sleep Mode	
and RTCC Peripheral	50
Brown-out Reset (DSBOR)	
Fault Detection	50
Preparing for	48
Registers	51
Typical Sequence	50
Wake-up Sources	49
Watchdog Timer (DSWDT)	49
Exiting Idle and Sleep Modes	47
By Interrupt	47
By Reset	47
By WDT Time-out	47
Without an Oscillator Start-up Delay	48
Idle Modes	
PRI_IDLE	
RC_IDLE	47
SEC_IDLE	
Multiple Sleep Commands	42
Run Modes	42
PRI_RUN	42
RC_RUN	44
SEC_RUN	42
Sleep Mode	45
Summary (table)	42
Ultra Low-Power Wake-up	54

### Μ

Master Clear (MCLR)	59
Master Synchronous Serial Port (MSSP). See MSSP.	
Memory Organization	71
Data Memory	78
Program Memory	71
Return Address Stack	73
Memory Programming Requirements 500	
Microchip Internet Web Site	. 551
MOVF	
MOVFF	. 456
MOVLB	. 456
MOVLW	. 457
MOVSF	. 475
MOVSS	. 476
MOVWF	. 457
MPLAB ASM30 Assembler, Linker, Librarian	. 482
MPLAB ICD 2 In-Circuit Debugger	. 483
MPLAB ICE 2000 High-Performance Universal In-Circuit	t Em-
ulator	. 483
MPLAB Integrated Development Environment Software	
MPLAB PM3 Device Programmer	. 483
MPLAB REAL ICE In-Circuit Emulator System	. 483
MPLINK Object Linker/MPLIB Object Librarian	. 482
MSSP	
ACK Pulse	, 290
I <sup>2</sup> C Mode. See I <sup>2</sup> C Mode.	

Module Overview	
SPI Master/Slave Connection	
TMR4 Output for Clock Shift	
MULLW	
MULWF	
Ν	

NEGF	459
NOP	459

### 0

Oscillator Configuration	
Internal Oscillator Block	
Oscillator Control	
Oscillator Modes	
Oscillator Modes and USB Operation	
Oscillator Types	
Oscillator Configurations	
Oscillator Selection	
Oscillator Settings for USB	
Configuration Options	
Oscillator Start-up Timer (OST)	
Oscillator Switching	
Oscillator Transitions	
Oscillator, Timer1193,	198, 211
Oscillator, Timer3	

### Ρ

P1A/P1B/P1C/P1D.See Enhanced (	Capture/Compare/PWM
(ECCP)	
Packaging	
Details	
Marking	
Parallel Master Port (PMP)	
Application Examples	
Associated Registers	
Data Registers	
Master Port Modes	
Module Registers	
Slave Port Modes	
Peripheral Pin Select (PPS)	
Peripheral Pin Select Registers	
PICSTART Plus Development Progra	
PIE Registers	
Pin Diagrams	
Pin Functions	
AVDD1	
AVDD2	
AVss1	
MCLR	
OSC1/CLKI/RA7	
OSC2/CLKO/RA6	
RA0/AN0/C1INA/ULPWU/PMA6/	/RP023
RA0/AN0/C1INA/ULPWU/RP0 .	
RA1/AN1/C2INA/PMA7/RP1	
RA1/AN1/C2INA/RP1	
RA2/AN2/VREF-/CVREF/C2INB .	
RA3/AN3/VREF+/C1INB	
RA5/AN4/SS1/HLVDIN/RCV/RP	2
RA6	
RA7	
RB0/AN12/INT0/RP3	
RB1/AN10/PMBE/RTCCS/RP4	
RB1/AN10/RTCC/RP4	
RB2/AN8/CTEDG1/PMA3/VMO/	
RB2/AN8/CTEDG1/VMO/REFO/	

RB3/AN9/CTEDG2/PMA2/VPO/RP6	24
RB3/AN9/CTEDG2/VPO/RP6	
RB4/KBI0/SCK1/SCL1/RP7	
RB4/PMA1/KBI0/SCK1/SCL1/RP7	
RB5/KBI1/SDI1/SDA1/RP8	19
RB5/PMA0/KBI1/SDI1/SDA1/RP8	25
RB6/KBI2/PGC/RP9	
RB7/KBI3/PGD/RP10	
RC0/T10S0/T1CKI/RP11	20, 26
RC1/T1OSI/UOE/RP12	20, 26
RC2/AN11/CTPLS/RP13	20, 26
RC4/D-/VM	20, 26
RC5/D+/VP	20, 26
RC6/PMA5/TX1/CK1/RP17	26
RC6/TX1/CK1/RP17	20
RC7/PMA4/RX1/DT1/SDO1/RP18	26
RC7/RX1/DT1/SDO1/RP18	20
RD0/PMD0/SCL2	
RD1/PMD1/SDA2	
RD2/PMD2/RP19	27
RD3/PMD3/RP20	
RD4/PMD4/RP21	
RD5/PMD5/RP22	27
RD6/PMD6/RP23	
RD7/PMD7/RP24	
RE0/AN5/PMRD	
RE1/AN6/PMWR	
RE2/AN7/PMCS	
VDD	
VDD	
VDD2	
VDD2 VDDCORE/VCAP	
	'
Vss1	ZI, ZO
V/cc2	01 00
Vss2	'
VUSB	'
VUSB Pinout I/O Descriptions	21, 28
Vuse Pinout I/O Descriptions PIC18F2XJ50 (28-Pin)	21, 28 16
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin)	21, 28 16 22
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–??
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–?? 32
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–?? 32
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–?? 32
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–?? 32
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–?? 32 460
VUSB Pinout I/O Descriptions PIC18F2XJ50 (28-Pin) PIC18F4XJ50 (44-Pin) PIR Registers	21, 28 16 22 14–?? 32 460
VUSB	21, 28 16 22 14–?? 32 460 54 131
VUSB	21, 28 16 22 14–?? 32 460 54 131 129
VUSB	21, 28 16 22 14–?? 32 460 54 131 129 129
VUSB	21, 28 16 22 14–?? 32 460 54 131 129 129
VUSB	21, 28 16 22 14–?? 32 460 54 131 129 129
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       1         POP       POR. See Power-on Reset.         PORTA       Additional Pin Functions         Ultra Low-Power Wake-up       Associated Registers         LATA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 135
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       1         POP       POR. See Power-on Reset.         PORTA       Additional Pin Functions         Ultra Low-Power Wake-up       Associated Registers         LATA Register       PORTA Register         PORTA Register       ITRISA Register         PORTB       Associated Registers         LATB Register       LATB Register	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 135 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       POP         POR. See Power-on Reset.       PORTA         Additional Pin Functions       Ultra Low-Power Wake-up         Associated Registers       LATA Register         PORTA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers         LATB Register       PORTB         Associated Registers       LATB Register	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 135 132 132
VUSB	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 135 132 132 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       POP         POR. See Power-on Reset.       PORTA         Additional Pin Functions       Ultra Low-Power Wake-up         Associated Registers       LATA Register         PORTA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers         LATB Register       PORTB         Associated Registers       LATB Register	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 135 132 132 132
VUSB	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 135 132 132 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       POP         POR. See Power-on Reset.       PORTA         Additional Pin Functions       Ultra Low-Power Wake-up         Associated Registers       LATA Register         PORTA Register       PORTA Register         PORTA Register       PORTA Register         PORTB Associated Registers       LATB Register         PORTB Register       PORTB Register         ASSOCIATE REGISTER       LATB Register         PORTB Register       PORTB Register         PORTB Register       PORTB Register         PORTB Register       PORTB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       PORTC	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 132 132 132 132 132 132 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       1         POR       See Power-on Reset.         PORTA       Additional Pin Functions         Ultra Low-Power Wake-up       Associated Registers         LATA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers         LATB Register       PORTB         Massociated Registers       LATB Register         PORTB       RBGISTER         LATB Register       RBT:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 132 132 132 132 132 132 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       POP         POR. See Power-on Reset.       PORTA         Additional Pin Functions       Ultra Low-Power Wake-up         Associated Registers       LATA Register         PORTA Register       PORTA Register         PORTA Register       PORTA Register         PORTB Associated Registers       LATB Register         PORTB Register       PORTB Register         ASSOCIATE REGISTER       LATB Register         PORTB Register       PORTB Register         PORTB Register       PORTB Register         PORTB Register       PORTB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       PORTC	21, 28 16 22 14–?? 32 460 54 131 129 129 129 132 132 132 132 132 132 138 136
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       1         POR       See Power-on Reset.         PORTA       Additional Pin Functions         Ultra Low-Power Wake-up       Associated Registers         LATA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers         LATB Register       PORTB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       LATC Register	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       POP         POR. See Power-on Reset.       PORTA         Additional Pin Functions       Ultra Low-Power Wake-up         Associated Registers       LATA Register         PORTA Register       PORTA Register         PORTA Register       PORTA Register         PORTB Associated Registers       LATB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       LATC Register	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132 132
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)         PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       1         POR       See Power-on Reset.         PORTA       Additional Pin Functions         Ultra Low-Power Wake-up       Associated Registers         LATA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers         LATB Register       PORTB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       LATC Register         PORTC       Associated Registers         LATC Register       PORTC Register         PORTC Register       TRISC Register	21, 28 16 22 14–?? 32 460 54 131 129 129 129 129 132 132 132 132 132 132 132 136 136 136
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       POP         POR. See Power-on Reset.       PORTA         Additional Pin Functions       Ultra Low-Power Wake-up         Associated Registers       LATA Register         PORTA Register       PORTA Register         PORTA Register       PORTA Register         PORTB Associated Registers       LATB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       LATC Register         PORTC       Associated Registers         LATC Register       PORTC         PORTC Register       PORTC Register         PORTC Register       PORTC Register	21, 28 16 22 14–?? 32 460 54 131 129 132 132 132 132 132 132 133 136 136 136 140
VUSB       Pinout I/O Descriptions         PIC18F2XJ50 (28-Pin)       PIC18F4XJ50 (44-Pin)         PIR Registers       1         PLL Frequency Multiplier       1         POP       POP         POR. See Power-on Reset.       1         PORTA       Additional Pin Functions         Ultra Low-Power Wake-up       Associated Registers         LATA Register       PORTA Register         PORTA Register       PORTA Register         PORTB       Associated Registers         LATB Register       PORTB Register         PORTB Register       RB7:RB4 Interrupt-on-Change Flag (RBIF Bit)         TRISB Register       PORTC         Associated Registers       LATC Register         PORTC       Associated Registers         LATC Register       PORTC Register         PORTC Register       PORTC Register	21, 28 16 22 14?? 32 460 54 131 129 129 129 129 132 132 132 132 132 136 136 136 139

Associated Registers	142
LATE Register	
PORTE Register	
TRISE Register	
Power-Managed Modes	171
and EUSART Operation	221
•	
and PWM Operation	
and SPI Operation	
Clock Sources	
Entering	41
Selecting	41
Power-on Reset (POR)	59
Power-up Delays	39
Power-up Timer (PWRT)	
Time-out Sequence	
Prescaler, Timer0	
Prescaler, Timer2 (Timer4)	
PRI_IDLE Mode	
—	
PRI_RUN Mode	
Product Identification System	
Program Counter	
PCL, PCH and PCU Registers	73
PCLATH and PCLATU Registers	73
Program Memory	
ALU	
STATUS	90
Extended Instruction Set	
Flash Configuration Words	
Hard Memory Vectors	
Instructions	
Two-Word	
Interrupt Vector	
Look-up Tables	75
Memory Maps	
Memory Maps Hard Vectors and Configuration Words	71
Hard Vectors and Configuration Words	71 72
Hard Vectors and Configuration Words Reset Vector	71 72 72
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection	71 72 72 429
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions	71 72 72 429 431
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering	71 72 429 431 258
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH	71 72 72 429 431 258 460
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions	71 72 429 431 258 460 74
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL	71 72 429 431 258 460 74
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module)	71 72 72 429 431 258 460 74 74
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL	71 72 72 429 431 258 460 74 74
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module)	71 72 72 429 431 258 460 74 476 476
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle	71 72 429 431 258 460 74 74 476 246
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions	71 72 429 431 258 460 74 74 476 246 244 245
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup	71 72 72 429 431 258 460 74 74 74 74 246 245 245
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period	71 72 72 429 429 431 258 460 74 74 476 246 244 245 244
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers	71 72 72 429 431 258 460 74 476 246 244 245 245 244 244
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match	71 72 72 429 431 258 460 74 476 246 244 245 245 244 244
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match	71 72 72 429 431 258 460 74 476 246 244 245 245 244 244
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match PWM (ECCP Module)	71 72 72 429 431 258 460 74 476 246 244 245 245 244 244 244 244 217
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match PWM (ECCP Module) Effects of a Reset	71 72 72 429 429 431 258 460 74 476 246 244 245 244 244 244 244 241 261
Hard Vectors and Configuration Words Reset Vector	71 72 72 429 429 431 258 460 74 476 246 244 245 245 244 244 244 241 261 261
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match PWM (ECCP Module) Effects of a Reset	71 72 72 429 429 431 258 460 74 476 246 244 245 245 244 244 244 241 261 261
Hard Vectors and Configuration Words Reset Vector	71 72 72 429 429 431 258 460 74 476 246 244 245 245 244 244 244 241 261 261 261
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match PWM (ECCP Module) Effects of a Reset Operation in Power-Managed Modes Operation with Fail-Safe Clock Monitor	71 72 72 429 431 258 460 74 476 246 244 245 245 244 244 241 261 261 261 258
Hard Vectors and Configuration Words Reset Vector	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words Reset Vector	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words Reset Vector	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match PWM (ECCP Module) Effects of a Reset Operation in Power-Managed Modes Operation with Fail-Safe Clock Monitor Pulse Steering Steering Synchronization PWM Mode. See Enhanced Capture/Compare/PWM	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words Reset Vector	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words Reset Vector Program Verification and Code Protection Programming, Device Instructions Pulse Steering PUSH PUSH and POP Instructions PUSHL PWM (CCP Module) Associated Registers Duty Cycle Example Frequencies/Resolutions Operation Setup Period PR2/PR4 Registers TMR2 (TMR4) to PR2 (PR4) Match TMR4 to PR4 Match PWM (ECCP Module) Effects of a Reset Operation in Power-Managed Modes Operation with Fail-Safe Clock Monitor Pulse Steering Steering Synchronization PWM Mode. See Enhanced Capture/Compare/PWM	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words         Reset Vector         Program Verification and Code Protection         Programming, Device Instructions         Pulse Steering         PUSH         PUSH and POP Instructions         PUSHL         PWM (CCP Module)         Associated Registers         Duty Cycle         Example Frequencies/Resolutions         Operation Setup         Period         PR2/PR4 Registers         TMR2 (TMR4) to PR2 (PR4) Match         TMR4 to PR4 Match         PWM (ECCP Module)         Effects of a Reset         Operation in Power-Managed Modes         Operation with Fail-Safe Clock Monitor         Pulse Steering         Steering Synchronization         PWM Mode. See Enhanced Capture/Compare/PWM         Q         Q Clock	71 72 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 74 
Hard Vectors and Configuration Words Reset Vector	71 72 72 72 72 72 72 72 72 72 72 72 72 72 74 74 74 246 245 261 261 261 261 261 261 261 261 245 245

$P(\cdot,  I\rangle) \models Mode$	17
RC_IDLE Mode RC RUN Mode	
-	
RCALL	401
RCON Register	~~
Bit Status During Initialization	
Reader Response	
Real-Time Clock and Calendar (RTCC)	219
Operation	231
Registers	220
Reference Clock Output	. 38
Register File	. 80
Register File Summary	-89
Registers	
ADCON0 (A/D Control 0)	341
ADCON1 (A/D Control 1)	
ALRMCFG (Alarm Configuration)	
ALRMDAY (Alarm Day Value)	
ALRMHR (Alarm Hours Value)	
	229
ALRMMIN (Alarm Minutes Value)	230
ALRMMNTH (Alarm Month Value)	228
ALRMRPT (Alarm Calibration)	
ALRMSEC (Alarm Seconds Value)	
ALRMWD (Alarm Weekday Value)	229
ANCON0 (A/D Port Configuration 2)	343
ANCON1 (A/D Port Configuration 1)	
Associated with Comparator	
Associated with Program Flash Memory	
BAUDCONx (Baud Rate Control)	
BDnSTAT	
BDnSTAT (Buffer Descriptor n Status, CPU Mode)	
BDnSTAT (Buffer Descriptor n Status, SIE Mode)	
BDnSTAT (SIE Mode)	
Buffer Descriptors, Summary	
CCPxCON (Enhanced Capture/Compare/PWM x C	
trol)	240
	240
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x)	240 381 380
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x)	240 381 380
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High)	240 381 380 416
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low)	240 381 380 416 415
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High)	240 381 380 416 415 418
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low)	240 381 380 416 415 418 417
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High)	240 381 380 416 415 418 417 420
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 Low)	240 381 380 416 415 418 417 420 419
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High)	240 381 380 416 415 418 417 420 419 421
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG3L (Configuration 4 High) CONFIG4H (Configuration 4 High)	240 381 380 416 415 418 417 420 419 421 420
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High)	240 381 380 416 415 418 417 420 419 421 420 409
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low)	240 381 380 416 415 418 417 420 419 421 420 409 410
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low)	240 381 380 416 415 418 417 420 419 421 420 409 409 410 411
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388 226
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388 226 421
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388 226 421
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Control Low) CTMUICON (COMparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2)	240 381 380 416 415 418 417 420 419 421 420 410 411 388 226 421 422
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388 226 421 422 276
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2)	240 381 380 416 415 418 417 420 419 421 420 409 411 388 226 421 422 276 277
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388 226 421 422 276 277 . 51
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2L (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 3 High) CONFIG3L (Configuration 3 Low) CONFIG4H (Configuration 4 High) CONFIG4L (Configuration 4 High) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DSCONH (Deep Sleep Control High Byte) DSCONL (Deep Sleep Control Low Byte)	240 381 380 416 415 418 417 420 4419 421 420 4410 411 388 226 421 422 276 2277 .51
trol) CMSTAT (Comparator Status)	240 381 380 416 415 418 417 420 4419 421 420 4410 411 388 226 421 422 276 2277 .51
trol) CMSTAT (Comparator Status)	240 381 380 416 415 418 417 420 419 421 420 410 411 388 226 421 422 276 277 .51 .51 .)).
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2H (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 4 High) CONFIG4H (Configuration 4 Low) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2) DSCONH (Deep Sleep Control High Byte) DSGPR0 (Deep Sleep Persistent General Purpose 0 52 DSGPR1 (Deep Sleep Persistent General Purpose 1 52	240 381 380 416 415 418 417 420 419 421 420 409 410 4388 226 277 .51 .51 .51 .)).
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2H (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3H (Configuration 3 Low) CONFIG3L (Configuration 4 High) CONFIG4H (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2) DSCONH (Deep Sleep Control High Byte) DSGPR0 (Deep Sleep Persistent General Purpose 0 52 DSGPR1 (Deep Sleep Persistent General Purpose 1 52 DSWAKEH (Deep Sleep Wake High Byte)	240 381 380 416 415 418 417 420 419 421 420 409 410 411 388 226 2277 .51 .51 .51 .53
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2H (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3H (Configuration 3 Low) CONFIG3L (Configuration 4 High) CONFIG4H (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2) DSCONH (Deep Sleep Control High Byte) DSGPR0 (Deep Sleep Persistent General Purpose 0 52 DSGPR1 (Deep Sleep Wake High Byte) DSWAKEH (Deep Sleep Wake High Byte) DSWAKEL (Deep Sleep Wake Low Byte)	240 381 380 416 415 418 417 420 419 421 420 410 411 388 6 422 277 51 .51 )) . .53 .53
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2H (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3H (Configuration 3 High) CONFIG3L (Configuration 4 High) CONFIG4H (Configuration 4 Low) CONFIG4L (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2) DSCONH (Deep Sleep Control High Byte) DSCONL (Deep Sleep Persistent General Purpose 0 52 DSGPR1 (Deep Sleep Persistent General Purpose 1 52 DSWAKEH (Deep Sleep Wake High Byte) DSWAKEL (Deep Sleep Wake Low Byte) ECCPxAS (ECCPx Auto-Shutdown Control)	240 381 380 415 417 420 419 421 420 410 411 388 6 422 77 51 51 9) () 53 53 255
trol) CMSTAT (Comparator Status) CMxCON (Comparator Control x) CONFIG1H (Configuration 1 High) CONFIG1L (Configuration 1 Low) CONFIG2H (Configuration 2 High) CONFIG2H (Configuration 2 Low) CONFIG3H (Configuration 3 High) CONFIG3H (Configuration 3 Low) CONFIG3L (Configuration 4 High) CONFIG4H (Configuration 4 Low) CTMUCONH (CTMU Control High) CTMUCONH (CTMU Control High) CTMUCONL (CTMU Control Low) CTMUICON (CTMU Current Control) CVRCON (Comparator Voltage Reference Control) DAY (Day Value) DEVID1 (Device ID 1) DEVID2 (Device ID 2) DMACON1 (DMA Control 1) DMACON2 (DMA Control 2) DSCONH (Deep Sleep Control High Byte) DSGPR0 (Deep Sleep Persistent General Purpose 0 52 DSGPR1 (Deep Sleep Wake High Byte) DSWAKEH (Deep Sleep Wake High Byte) DSWAKEL (Deep Sleep Wake Low Byte)	240 381 380 415 417 420 419 421 420 410 411 388 6 422 77 51 51 9) () 53 53 255

HLVDCON (High/Low-Voltage Detect Control)	391
HOURS (Hours Value)	
I <sup>2</sup> C Mode (MSSP)	282
INTCON (Interrupt Control)	
INTCON2 (Interrupt Control 2)	112
INTCON3 (Interrupt Control 3)	113
IPR1 (Peripheral Interrupt Priority 1)	100
IPR2 (Peripheral Interrupt Priority 2)	121
IPR3 (Peripheral Interrupt Priority 3)	
MINUTES (Minutes Value)	
MONTH (Month Value)	225
ODCON1 (Peripheral Open-Drain Control 1)	
ODCON2 (Peripheral Open-Drain Control 2)	127
ODCON3 (Peripheral Open-Drain Control 3)	128
OSCCON (Oscillator Control)	
OSCTUNE (Oscillator Tuning)	34
PADCFG1 (Pad Configuration Control 1)	
	120
PADCFG1 (Pad Configuration)	222
Parallel Master Port	. 164
PIE1 (Peripheral Interrupt Enable 1)	
PIE2 (Peripheral Interrupt Enable 2)	118
PIE3 (Peripheral Interrupt Enable 3)	119
PIR1 (Peripheral Interrupt Request (Flag) 1)	
PIR2 (Peripheral Interrupt Request (Flag) 2)	115
PIR3 (Peripheral Interrupt Request (Flag) 3)	
PMADDRH (Parallel Port Address High Byte)	171
PMADDRL (Parallel Port Address Low Byte)	171
PMCONH (Parallel Port Control High Byte)	104
PMCONL (Parallel Port Control Low Byte)	165
PMEH (Parallel Port Enable High Byte)	
PMEL (Parallel Port Enable Low Byte)	168
PMMODEH (Parallel Port Mode High Byte)	166
PMMODEL (Parallel Port Mode Low Byte)	
PMSTATH (Parallel Port Status High Byte)	
PMSTATH (Parallel Port Status High Byte)	169
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte)	169 169
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte) PPSCON (Peripheral Pin Select Input 0)	169 169 148
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte) PPSCON (Peripheral Pin Select Input 0)	169 169 148
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte) PPSCON (Peripheral Pin Select Input 0) PSTRxCON (Pulse Steering Control)	169 169 148 259
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte) PPSCON (Peripheral Pin Select Input 0) PSTRxCON (Pulse Steering Control) RCON (Reset Control)	169 169 148 259 ., 123
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte) PPSCON (Peripheral Pin Select Input 0) PSTRxCON (Pulse Steering Control)	169 169 148 259 ., 123 319
PMSTATH (Parallel Port Status High Byte) PMSTATL (Parallel Port Status Low Byte) PPSCON (Peripheral Pin Select Input 0) PSTRxCON (Pulse Steering Control)	169 169 148 259 ., 123 319
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         Status and Control)         REF0CON (Reference Clock Output)	169 169 148 259 123 319 38
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved	169 169 148 259 123 319 38 38
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)	169 169 148 259 123 319 38 225 149
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)	169 169 148 259 123 319 38 225 149
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)	169 169 148 259 123 319 38 225 149 151
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)	169 169 148 259 123 319 38 225 149 151 151
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)	169 169 148 259 123 319 38 225 149 151 151 152
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)	169 169 148 259 123 319 38 225 149 151 151 152
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)	169 169 148 259 123 319 38 225 149 151 151 152 152 152
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         PSTRxCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)	169 169 148 259 123 319 38 225 149 151 151 152 152 149
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)	169 169 148 259 123 319 38 225 149 151 151 152 152 149
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         PSTRxCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)	169 169 148 259 123 319 319 319 123 149 151 151 152 149 152 149 152
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         PSTRxCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)	169 169 148 259 123 319 319 225 149 151 151 152 152 149 152 149 152 149 152
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         PSTRxCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)	169 169 148 259 123 319 319 225 149 151 151 152 152 149 152 149 152 149 152
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         PSTRxCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR16 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 23)	169 169 148 259 123 319 38 225 149 151 151 152 152 149 152 149 152 149 153 153
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR18 (Peripheral Pin Select Input 17)         RPINR19 (Peripheral Pin Select Input 17)         RPINR10 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 24)	169 169 148 259 123 319 38 225 149 151 151 152 152 149 152 152 149 153 153 153
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR16 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 3)	169 169 148 259 123 319 38 225 149 151 151 152 152 149 152 153 153 153 149
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR16 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 3)	169 169 148 259 123 319 38 225 149 151 151 152 152 149 152 153 153 153 149
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR16 (Peripheral Pin Select Input 17)         RPINR17 (Peripheral Pin Select Input 17)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 3)         RPINR3 (Peripheral Pin Select Input 3)	169 169 148 259 123 319 38 225 149 151 151 152 152 149 152 153 153 153 149 153 153 149 153
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR18 (Peripheral Pin Select Input 17)         RPINR19 (Peripheral Pin Select Input 17)         RPINR20 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR24 (Peripheral Pin Select Input 23)         RPINR3 (Peripheral Pin Select Input 3)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 6)	169 169 148 259 123 319 38 225 149 151 151 152 152 152 153 153 153 153 150 150 150
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 14)         RPINR17 (Peripheral Pin Select Input 15)         RPINR18 (Peripheral Pin Select Input 16)         RPINR19 (Peripheral Pin Select Input 17)         RPINR20 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR24 (Peripheral Pin Select Input 2)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 6)         RPINR6 (Peripheral Pin Select Input 7)	169 169 148 259 123 319 38 225 149 151 151 152 152 152 153 153 153 153 150 150 150 150
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCSTAx (Receive Status and Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 17)         RPINR18 (Peripheral Pin Select Input 17)         RPINR19 (Peripheral Pin Select Input 17)         RPINR20 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR24 (Peripheral Pin Select Input 23)         RPINR3 (Peripheral Pin Select Input 3)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 6)	169 169 148 259 123 319 38 225 149 151 151 152 152 152 153 153 153 153 150 150 150 150
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 2)         RPINR16 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR21 (Peripheral Pin Select Input 2)         RPINR22 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 2)         RPINR24 (Peripheral Pin Select Input 2)         RPINR23 (Peripheral Pin Select Input 3)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 4)         RPINR3 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR5 (Peripheral Pin Select Input 7)	169 169 148 259 123 319 38 225 149 151 151 152 152 153 153 153 149 150 150 150 151
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR22 (Peripheral Pin Select Input 27)         RPINR23 (Peripheral Pin Select Input 28)         RPINR24 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 23)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 7)         RPINR8 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pin Select Input 7)         RPINR8 (Peripheral Pin Select Input 7)	169 169 148 259 123 319 38 225 149 151 151 152 152 153 153 153 153 149 150 150 151 151 151 151
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR22 (Peripheral Pin Select Input 27)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pi	169 169 148 259 123 319 38 225 149 151 151 152 149 152 153 153 153 149 150 150 150 151 154 154
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR21 (Peripheral Pin Select Input 27)         RPINR22 (Peripheral Pin Select Input 27)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pin Select Input 7)         RPINR4 (Peripheral Pi	169 169 148 259 123 319 38 225 149 151 151 152 149 152 153 153 153 149 150 150 150 151 154 154
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR16 (Peripheral Pin Select Input 21)         RPINR21 (Peripheral Pin Select Input 22)         RPINR21 (Peripheral Pin Select Input 22)         RPINR22 (Peripheral Pin Select Input 22)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 7)         RPINR8 (Peripheral Pin Select Input 8)         RPOR0 (Peripheral Pin Select Output 0)         RPOR1 (Peripheral Pin Select Output 0)         RPOR10 (Peripheral Pin	169 169 148 259 123 319 38 225 149 151 151 152 149 152 153 153 153 149 150 150 150 151 154 154 157
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 27)         RPINR2 (Peripheral Pin Select Input 28)         RPINR2 (Peripheral Pin Select Input 29)         RPINR2 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR6 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 7)         RPINR8 (Peripheral Pin Select Output 0)         RPOR0 (Peripheral Pin Select Output 0)         RPOR1 (Peripheral Pin Selec	169 169 148 259 123 319 38 225 149 151 151 152 152 152 153 153 153 153 150 150 151 154 157 157
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR2 (Peripheral Pin Select Input 22)         RPINR2 (Peripheral Pin Select Input 21)         RPINR2 (Peripheral Pin Select Input 22)         RPINR2 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Output 0)         RPOR0 (Peripheral Pin Select Output 1)         RPOR1 (Peripheral Pin Select Output 1)         RPOR10 (Peripheral Pin Sel	169 169 148 259 123 319 38 225 149 151 151 152 149 152 153 149 153 153 153 150 150 151 154 157 157 158
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR2 (Peripheral Pin Select Input 22)         RPINR2 (Peripheral Pin Select Input 21)         RPINR2 (Peripheral Pin Select Input 22)         RPINR2 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Output 0)         RPOR0 (Peripheral Pin Select Output 1)         RPOR1 (Peripheral Pin Select Output 1)         RPOR10 (Peripheral Pin Sel	169 169 148 259 123 319 38 225 149 151 151 152 149 152 153 149 153 153 153 150 150 151 154 157 157 158
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR2 (Peripheral Pin Select Input 22)         RPINR2 (Peripheral Pin Select Input 21)         RPINR2 (Peripheral Pin Select Input 22)         RPINR2 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 24)         RPINR4 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR5 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR5 (Peripheral Pin Select Output 0)         RPOR0 (Peripheral Pin Sele	169 169 148 259 123 319 38 225 149 151 151 152 149 152 153 153 153 153 150 150 151 154 157 157 158 158
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR16 (Peripheral Pin Select Input 21)         RPINR21 (Peripheral Pin Select Input 22)         RPINR22 (Peripheral Pin Select Input 21)         RPINR21 (Peripheral Pin Select Input 22)         RPINR22 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR3 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR5 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Se	169 169 148 259 123 319 38 225 149 151 151 152 149 152 152 149 152 153 153 153 150 150 157 157 158 158 158 158
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR16 (Peripheral Pin Select Input 21)         RPINR21 (Peripheral Pin Select Input 21)         RPINR22 (Peripheral Pin Select Input 22)         RPINR23 (Peripheral Pin Select Input 23)         RPINR24 (Peripheral Pin Select Input 3)         RPINR3 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 7)         RPINR8 (Peripheral Pin Select Input 7)         RPINR8 (Peripheral Pin Select Output 1)         RPOR0 (Peripheral Pin Select Output 1)         RPOR0 (Peripheral Pin Select Output 1)         RPOR1 (Peripheral Pin Select Output 1)         RPOR10 (Peripheral Pin Select Output 1)         RPOR11 (Peripheral Pin Sel	169 169 148 259 123 319 38 225 149 151 151 152 149 152 152 149 152 153 153 153 153 150 151 154 157 158 158 158 158 159
PMSTATH (Parallel Port Status High Byte)         PMSTATL (Parallel Port Status Low Byte)         PPSCON (Peripheral Pin Select Input 0)         PSTRxCON (Pulse Steering Control)         RCON (Reset Control)         RCON (Reset Control)         REF0CON (Reference Clock Output)         Reserved         RPINR1 (Peripheral Pin Select Input 1)         RPINR12 (Peripheral Pin Select Input 12)         RPINR13 (Peripheral Pin Select Input 13)         RPINR16 (Peripheral Pin Select Input 16)         RPINR17 (Peripheral Pin Select Input 21)         RPINR16 (Peripheral Pin Select Input 21)         RPINR21 (Peripheral Pin Select Input 22)         RPINR22 (Peripheral Pin Select Input 21)         RPINR21 (Peripheral Pin Select Input 22)         RPINR22 (Peripheral Pin Select Input 23)         RPINR23 (Peripheral Pin Select Input 24)         RPINR3 (Peripheral Pin Select Input 3)         RPINR4 (Peripheral Pin Select Input 4)         RPINR3 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 4)         RPINR8 (Peripheral Pin Select Input 4)         RPINR4 (Peripheral Pin Select Input 4)         RPINR5 (Peripheral Pin Select Input 4)         RPINR6 (Peripheral Pin Se	169 169 148 259 123 319 38 225 149 151 151 152 149 152 152 149 152 153 153 153 153 150 151 154 157 158 158 158 158 159

RPOR2 (Peripheral Pin Select Output 2)	154
RPOR20 (Peripheral Pin Select Output 20)	
RPOR21 (Peripheral Pin Select Output 21)	
RPOR22 (Peripheral Pin Select Output 22)	
RPOR23 (Peripheral Pin Select Output 23)	
RPOR24 (Peripheral Pin Select Output 24)	
RPOR3 (Peripheral Pin Select Output 3)	
RPOR4 (Peripheral Pin Select Output 4)	155
RPOR5 (Peripheral Pin Select Output 5)	
RPOR6 (Peripheral Pin Select Output 6)	156
RPOR7 (Peripheral Pin Select Output 7)	
RPOR8 (Peripheral Pin Select Output 8)	
RPOR9 (Peripheral Pin Select Output 9)	
RTCCAL (RTCC Calibration)	
RTCCFG (RTCC Configuration)	
SECONDS (Seconds Value)	
SPI Mode (MSSP)	
SSPxCON1 (MSSPx Control 1, I <sup>2</sup> C Mode)	284
SSPxCON1 (MSSPx Control 1, SPI Mode)	
SSPxCON2 (MSSPx Control 2, I <sup>2</sup> C Master Mode)	
SSPxCON2 (MSSPx Control 2, I <sup>2</sup> C Slave Mode) .	
SSPxMSK (I <sup>2</sup> C Slave Address Mask)	
SSPxSTAT (MSSPx Status, I <sup>2</sup> C Mode)	283
SSPxSTAT (MSSPx Status, SPI Mode)	265
STATUS	90
STKPTR (Stack Pointer)	74
T0CON (Timer0 Control)	189
T1CON (Timer1 Control)	
T1GCON (Timer1 Gate Control)	194
T2CON (Timer2 Control)	205
T3CON (Timer3 Control)	207
T3GCON (Timer3 Gate Control)	208
T4CON (Timer4 Control)	217
T4CON (Timer4 Control) TCLKCON (Timer Clock Control)	217 5, 209
T4CON (Timer4 Control)	217 5, 209
T4CON (Timer4 Control) TCLKCON (Timer Clock Control)	217 5, 209 318
T4CON (Timer4 Control)	217 5, 209 318 359
T4CON (Timer4 Control)	217 5, 209 318 359 355 353
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       19         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10	217 5, 209 318 359 355 353 371
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       19         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10	217 5, 209 318 359 355 353 371 370
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       19         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10	217 5, 209 318 359 355 353 371 370
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       19         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       10	217 5, 209 318 359 355 353 371 370 358 359
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       19         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11	217 5, 209 318 359 355 353 371 370 358 359 359 369
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11	217 5, 209 318 359 355 353 371 370 358 359 369 367
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       19         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11	217 5, 209 318 359 355 353 371 370 358 359 369 367 357
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UADDR         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       11	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UADDR         UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       11	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 225
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WEAR (Year Value)       12         RESET       12         Reset       13	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 225 461 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UFPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       12         WEAR (Year Value)       12         RESET       12         Reset       12         Brown-out Reset       12	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 225 461 57 59
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Status)       10         UEPn (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       12         YEAR (Year Value)       12         RESET       12         Reset       13         Brown-out Reset       14         Brown-out Reset       15	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 225 461 57 59 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Status)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         UIR (USB Interrupt Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       12         YEAR (Year Value)       12         RESET       12         Reset       13         Brown-out Reset       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 225 461 57 59 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Status)       10         UER (USB Endpoint n Control)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       12         YEAR (Year Value)       12         RESET       12         Reset       13         Brown-out Reset       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14         Configuration Mismatch Reset       14	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 225 461 57 57 57 57 60
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       10         UEIR (USB Entror Interrupt Enable)       10         UERn(USB Endpoint n Control)       11         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Enable)       11         UIR (USB Interrupt Enable)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       12         YEAR (Year Value)       12         RESET       13         Reset       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14         Configuration Mismatch Reset       14         Deep Sleep       14	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 225 461 57 57 57 57 57 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCFG (USB Control)       10         UEFG (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Enable)       10         UEIR (USB Endpoint n Control)       11         UFRMH: UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Enable)       11         UIR (USB Interrupt Enable)       11         UIR (USB Interrupt Enable)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       12         YEAR (Year Value)       YEAR (Year Value)         RESET       12         Reset       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14         Configuration Mismatch Reset       14         Deep Sleep       14         Fast Register Stack       15	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 225 461 57 57 57 57 57 57 75
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Enable)       19       10         UEIR (USB Error Interrupt Enable)       10       10         UER (USB Interrupt Interrupt Status)       10       10         UFRMH:UFRML       11       11       11         UIE (USB Interrupt Enable)       11       11       11         UIR (USB Interrupt Enable)       11       11       11       11         UIR (USB Interrupt Status)       11       11       11       11       11         USTAT (USB Status)       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       1	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 225 426 225 424 225 57 57 57 59
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       UEIE (USB Error Interrupt Enable)       10         UEIR (USB Error Interrupt Enable)       19       10         UEIR (USB Error Interrupt Enable)       10       10         UER (USB Interrupt Interrupt Status)       10       10         UFRMH:UFRML       11       11       11         UIE (USB Interrupt Enable)       11       11       11         UIR (USB Interrupt Enable)       11       11       11       11         UIR (USB Interrupt Status)       11       11       11       11       11         WDTCON (Watchdog Timer Control)       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11       11 <td> 217 5, 209  318  359  355  353  371  370  358  359  369  367  357  424  226  461 7  57  57  57  57  59  57  57</td>	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 226 461 7 57 57 57 57 59 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Enable)       10         UEIR (USB Endpoint n Control)       11         UFRMH: UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       YEAR (Year Value)         YEAR (Year Value)       YEAR (Year Value)         RESET       12         Reset       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       15         Configuration Mismatch Reset       16         Deep Sleep       16         Fast Register Stack       16         MCLR       17         MCLR Reset, Normal Operation       16	217 5, 209 318 359 355 353 371 370 358 359 369 367 357 424 225 461 7 57 57 57 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Enable)       10         UER (USB Interrupt Status)       10         UFRMH: UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       12         YEAR (Year Value)       13         Brown-out Reset       14         Brown-out Reset       14         Deep Sleep       14         Fast Register Stack       16         MCLR       16       10         MCLR Reset, Normal Operation       10	217 5, 209 318 359 355 353 371 370 358 359 359 359 369 369 367 357 424 226 225 461 57 57 57 57 57 57 57 57 57 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Enable)       10         UEIR (USB Interrupt Status)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       YEAR (Year Value)         YEAR (Year Value)       12         RESET       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14         Configuration Mismatch Reset       14         Deep Sleep       14         Fast Register Stack       14         MCLR       19         MCLR Reset, Normal Operation       19         Power-on Reset       10         Power-on Reset       10         Power-on Reset       10	217 5, 209 318 359 355 353 371 370 358 359 359 359 359 369 367 357 424 226 225 461 7 57 57 57 57 57 57 57 57 57 57 57 57 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Enable)       10         UEIR (USB Interrupt Status)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       YEAR (Year Value)         YEAR (Year Value)       12         RESET       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14         Configuration Mismatch Reset       14         Deep Sleep       14         Fast Register Stack       14         MCLR Reset, Normal Operation       14         Power-on Reset       14 <td> 217 5, 209  318  359  355  353  371  370  358  359  359  359  359  369  369  367  357  424  226  225  461  57  57</td>	217 5, 209 318 359 355 353 371 370 358 359 359 359 359 369 369 367 357 424 226 225 461 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       0         UADDR       0         UCFG (USB Configuration)       0         UCON (USB Control)       0         UEIE (USB Error Interrupt Enable)       0         UEIR (USB Error Interrupt Enable)       0         UFRMH:UFRML       0         UIR (USB Interrupt Enable)       0         UIR (USB Interrupt Enable)       0         UIR (USB Interrupt Status)       0         USTAT (USB Status)       0         WDTCON (Watchdog Timer Control)       0         WKDY (Weekday Value)       YEAR (Year Value)         YEAR (Year Value)       YEAR         RESET       Brown-out Reset (BOR)         Configuration Mismatch (CM)       Configuration Mismatch Reset         Deep Sleep       Fast Register Stack         MCLR       Reset, Normal Operation         Power-on Reset       Power-on Reset         Power-on Timer       RESET Instruction <td> 217 5, 209  318  359  355  353  371  370  358  359  359  369  369  367  357  424  226  225  461 7  57  57</td>	217 5, 209 318 359 355 353 371 370 358 359 359 369 369 367 357 424 226 225 461 7 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57
T4CON (Timer4 Control)       19         TCLKCON (Timer Clock Control)       19         TXSTAx (Transmit Status and Control)       19         UADDR       UCFG (USB Configuration)       10         UCON (USB Control)       10         UEIE (USB Error Interrupt Enable)       19         UEIR (USB Error Interrupt Enable)       10         UEIR (USB Interrupt Status)       10         UFRMH:UFRML       11         UIE (USB Interrupt Enable)       11         UIR (USB Interrupt Status)       11         USTAT (USB Status)       11         WDTCON (Watchdog Timer Control)       11         WKDY (Weekday Value)       YEAR (Year Value)         YEAR (Year Value)       12         RESET       13         Brown-out Reset (BOR)       14         Configuration Mismatch (CM)       14         Configuration Mismatch Reset       14         Deep Sleep       14         Fast Register Stack       14         MCLR Reset, Normal Operation       14         Power-on Reset       14 <td> 217 5, 209  318  359  355  353  371  370  358  359  359  359  359  369  369  367  357  424  226  225  461  57  57</td>	217 5, 209 318 359 355 353 371 370 358 359 359 359 359 369 369 367 357 424 226 225 461 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57 57

State of Registers	62
Watchdog Timer (WDT) Reset	57
Resets	413
Brown-out Reset (BOR)	
Oscillator Start-up Timer (OST)	
Power-on Reset (POR)	
Power-up Timer (PWRT)	
RETFIE	
RETLW	
RETURN	
Return Address Stack	
Associated Registers	
Revision History	
RLCF	
RLNCF	
RRCF	
RRNCF	465
RTCC	
Alarm	
Configuring	235
Interrupt	
Mask Settings	
Alarm Value Registers (ALRMVAL)	
Control Registers	221
Low-Power Modes	236
Operation	
Calibration	234
Clock Source	232
Digit Carry Rules	232
General Functionality	233
Leap Year	233
Register Mapping	
ALRMVAL	
RTCVAL	
Safety Window for Register Reads and Writes	233
Write Lock	
Peripheral Module Disable (PMD) Register	
Register Interface	
Register Maps	
Reset	
Device	
Power-on Reset (POR)	
Value Registers (RTCVAL)	
RTCEN Bit Write	
	201
S	
SCKx	264
SDIx	
SDOx	
SEC_IDLE Mode	
SEC_RUN Mode	
Serial Clock, SCKx	
Serial Data In (SDIx)	
Serial Data III (SDIX)	
Serial Peripheral Interface. See SPI Mode.	-04

 SETF
 465

 Shoot-Through Current
 257

 Slave Select (SSx)
 264

 SLEEP
 466

 Software Simulator (MPLAB SIM)
 482

 Special Event Trigger. See Compare (ECCP Mode).
 413

 SPI Mode (MSSP)
 264

 Associated Registers
 273

 Bus Mode Compatibility
 272

 Clock Speed, Interactions
 272

Effects of a Reset	272
Enabling SPI I/O	268
Master Mode	269
Master/Slave Connection	268
Operation	
Open-Drain Output Option	
Operation in Power-Managed Modes	272
Registers	265
Serial Clock	264
Serial Data In	264
Serial Data Out	264
Slave Mode	
Slave Select	264
Slave Select Synchronization	270
SPI Clock	
SSPxBUF Register	269
SSPxSR Register	269
Typical Connection	
SSPOV	
SSPOV Status Flag	307
SSPxS <u>TA</u> T Register	
R/W Bit	
SSx	
Stack Full/Underflow Resets	
SUBFSR	
SUBFWB	
SUBLW	
SUBULNK	
SUBWF	
SUBWFB	
SWAPF	468

#### т

Table Pointer Operations (table)	100
Table Reads/Table Writes	
TAD	347
TBLRD	469
TBLWT	470
Timer0	189
Associated Registers	191
Operation	
Overflow Interrupt	191
Prescaler	
Switching Assignment	
Prescaler Assignment (PSA Bit)	
Prescaler Select (T0PS2:T0PS0 Bits)	
Reads and Writes in 16-Bit Mode	190
Source Edge Select (T0SE Bit)	190
Source Select (T0CS Bit)	
Timer1	
16-Bit Read/Write Mode	
Associated Registers	
Clock Source Selection	196
Gate	200
Interrupt	199
Operation	196
Oscillator 193,	198
Layout Considerations	
Resetting, Using the ECCP Special Event Trigger	200
TMR1H Register	193
TMR1L Register	193
Use as a Clock Source	199
Timer2	205
Associated Registers	206
Interrupt	206
Operation	205

Output	206
Timer3	
16-Bit Read/Write Mode	211
Associated Registers	215
Gate	211
Operation	210
Oscillator2	207, 211
Overflow Interrupt2	
Special Event Trigger (ECCP)	215
TMR3H Register	207
TMR3L Register	
Timer4	
Associated Registers	
Interrupt	
MSSP Clock Shift	218
Operation	
Output	218
Postscaler. See Postscaler, Timer4.	
PR4 Register	217
Prescaler. See Prescaler, Timer4.	
TMR4 Register	
TMR4 to PR4 Match Interrupt2	217, 218
Timing Diagrams	
A/D Conversion	522
Asynchronous Reception	
Asynchronous Transmission	
Asynchronous Transmission (Back-to-Back)	
Automatic Baud Rate Calculation	
Auto-Wake-up Bit (WUE) During Normal Operati	
Auto-Wake-up Bit (WUE) During Sleep	
Baud Rate Generator with Clock Arbitration	
BRG Overflow Sequence	
BRG Reset Due to SDAx Arbitration During Star	t Condi-
tion	
Bus Collision During a Repeated Start Condition	
1)	
Bus Collision During a Repeated Start Condition 2)	•
Bus Collision During a Start Condition (SCLx = 0	
Bus Collision During a Stop Condition (Case 1)	
Bus Collision During a Stop Condition (Case 2)	
Bus Collision During Start Condition (SDAx Only	
Bus Collision for Transmit and Acknowledge	
CLKO and I/O	
Clock Synchronization	
Clock/Instruction Cycle	
Enhanced Capture/Compare/PWM	
EUSARTx Synchronous Receive (Master/Slave)	
EUSARTx Synchronous Transmission (Master/S 521	slave)
Example SPI Master Mode (CKE = 0)	513
Example SPI Master Mode (CKE = 1)	
Example SPI Slave Mode (CKE = 0)	
Example SPI Slave Mode (CKE = 1)	
External Clock	
Fail-Safe Clock Monitor	
First Start Bit	305
Full-Bridge PWM Output	
Half-Bridge PWM Output2	
High/Low-Voltage Detect Characteristics	
High-Voltage Detect (VDIRMAG = 1)	395
I <sup>2</sup> 2C Bus Data	517
I <sup>2</sup> C Acknowledge Sequence	
	310
I <sup>2</sup> C Bus Start/Stop Bits I <sup>2</sup> C Master Mode (7 or 10-Bit Transmission)	517

I <sup>2</sup> C Master Mode (7-Bit Reception)
01001)
$I^2C$ Slave Mode (10-Bit Reception, SEN = 1)
I <sup>2</sup> C Slave Mode (10-Bit Transmission)
$I^2C$ Slave Mode (7-Bit Reception, SEN = 0, ADMSK =
01011)
$I^{2}C$ Slave Mode (7-Bit Reception, SEN = 0)
I <sup>2</sup> C Slave Mode (7-Bit Reception, SEN = 1)
I <sup>2</sup> C Slave Mode General Call Address Sequence (7 or
10-Bit Addressing Mode) 301
I <sup>2</sup> C Stop Condition Receive or Transmit Mode 310
Low-Voltage Detect (VDIRMAG = 0)
MSSPx I <sup>2</sup> C Bus Data
Parallel Master Port Read
Parallel Master Port Write
Parallel Slave Port Read 173, 175
Parallel Slave Port Write 173, 176
PWM Auto-Shutdown with Auto-Restart Enabled 256
PWM Auto-Shutdown with Firmware Restart
PWM Direction Change253PWM Direction Change at Near 100% Duty Cycle254
PWM Output
PWM Output (Active-High)
PWM Output (Active-Low) 249
Read and Write, 8-Bit Data, Demultiplexed Address 180
Read, 16-Bit Data, Demultiplexed Address
Read, 16-Bit Multiplexed Data, Fully Multiplexed 16-Bit Address
Read, 16-Bit Multiplexed Data, Partially Multiplexed Ad-
dress
Read, 8-Bit Data, Fully Multiplexed 16-Bit Address . 182
Read, 8-Bit Data, Partially Multiplexed Address 180
Read, 8-Bit Data, Partially Multiplexed Address, Enable Strobe
Read, 8-Bit Data, Wait States Enabled, Partially Multi-
plexed Address
Repeated Start Condition
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer
(OST) and Power-up Timer (PWRT)
Send Break Character Sequence
Slow Rise Time (MCLR Tied to VDD, VDD Rise > TPWRT)
SPI Mode (Master Mode) 269
SPI Mode (Slave Mode, CKE = 0)271
SPI Mode (Slave Mode, CKE = 1)
Steering Event at Beginning of Instruction (STRSYNC = 1)260
Steering Event at End of Instruction (STRSYNC = 0) 260
Synchronous Reception (Master Mode, SREN) 335
Synchronous Transmission
Synchronous Transmission (Through TXEN)
Time-out Sequence on Power-up (MCLR Not Tied to VDD), Case 1
Time-out Sequence on Power-up (MCLR Not Tied to
VDD), Case 2 61
Time-out Sequence on Power-up (MCLR Tied to VDD,
VDD Rise < TPWRT)
Timer Pulse Generation236Timer0 and Timer1 External Clock509

Timer1 Gate Count Enable Mode200 Timer1 Gate Single Pulse Mode
Timer1 Gate Single Pulse/Toggle Combined Mode . 204
Timer1 Gate Toggle Mode
Timer3 Gate Count Enable Mode
Timer3 Gate Single Pulse Mode
Timer3 Gate Single Pulse/Toggle Combined Mode . 214
Timer3 Gate Toggle Mode
Transition for Entry to Idle Mode
Transition for Entry to SEC_RUN Mode
Transition for Entry to Sleep Mode45
Transition for Two-Speed Start-up (INTRC to HSPLL)
427
Transition for Wake From Idle to Run Mode
Transition for Wake From Sleep (HSPLL)
Transition From RC_RUN Mode to PRI_RUN Mode . 44
Transition From SEC_RUN Mode to PRI_RUN Mode
(HSPLL)43
Transition to RC_RUN Mode44
USB Signal 523
Write, 16-Bit Data, Demultiplexed Address 183
Write, 16-Bit Multiplexed Data, Fully Multiplexed 16-Bit
Address184
Write, 16-Bit Multiplexed Data, Partially Multiplexed Ad-
dress
Write, 8-Bit Data, Fully Multiplexed 16-Bit Address . 182
Write, 8-Bit Data, Partially Multiplexed Address 181
Write, 8-Bit Data, Partially Multiplexed Address, Enable
Strobe
Write, 8-Bit Data, Wait States Enabled, Partially Multi-
plexed Address
Timing Diagrams and Specifications
AC Characteristics Internal RC Accuracy506
•
CLKO and I/O Requirements 507
CLKO and I/O Requirements
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       1)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         515       Example SPI Slave Mode Requirements (CKE = 1)         516       External Clock Requirements
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       518         517       517
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       518         S17       MSSPx I <sup>2</sup> C Bus Data Requirements       520
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519         Parallel Master Port Read Requirements       511
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519         Parallel Master Port Read Requirements       511         Parallel Master Port Write Requirements       512
CLKO and I/O Requirements507Enhanced Capture/Compare/PWM Requirements510EUSARTx Synchronous Receive Requirements521EUSARTx Synchronous Transmission Requirements521Example SPI Mode Requirements (Master Mode, CKE = 0)513Example SPI Mode Requirements (Master Mode, CKE = 1)514Example SPI Mode Requirements (Slave Mode, CKE = 0)515Example SPI Mode Requirements (Slave Mode, CKE = 0)515Example SPI Slave Mode Requirements (CKE = 1)516External Clock Requirements506I <sup>2</sup> C Bus Data Requirements (Slave Mode)518I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)517MSSPx I <sup>2</sup> C Bus Data Requirements520MSSPx I <sup>2</sup> C Bus Data Requirements519Parallel Master Port Read Requirements511Parallel Master Port Write Requirements512PLL Clock506
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519         Parallel Master Port Read Requirements       511         Parallel Master Port Write Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Pow-
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519         Parallel Master Port Read Requirements       511         Parallel Master Port Write Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Powerup Timer and Brown-out Reset Requirements
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements (Slave Mode)       519         Parallel Master Port Read Requirements       519         Parallel Master Port Write Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Power-up Timer and Brown-out Reset Requirements       508
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements (Slave Mode)       519         Parallel Master Port Read Requirements       510         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       511         Parallel Master Port Write Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Power-up Timer and Brown-out Reset Requirements       508         Timer0 and Timer1 External Clock Requirements       509
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       518         SPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519         Parallel Master Port Read Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Power-up Timer and Brown-out Reset Requirements       508         Timer0 and Timer1 External Clock Requirements       509         USB Full-Speed Requirements       523
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements (Slave Mode)       519         Parallel Master Port Read Requirements       510         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       511         Parallel Master Port Write Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Power-up Timer and Brown-out Reset Requirements       508         Timer0 and Timer1 External Clock Requirements       509
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Data Requirements       519         Parallel Master Port Read Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Power-up Timer and Brown-out Reset Requirements       508         Timer0 and Timer1 External Clock Requirements       523         USB Low-Speed Requirements       523         USB Low-Speed Requirements       523
CLKO and I/O Requirements       507         Enhanced Capture/Compare/PWM Requirements       510         EUSARTx Synchronous Receive Requirements       521         EUSARTx Synchronous Transmission Requirements       521         Example SPI Mode Requirements (Master Mode, CKE =       0)         0)       513         Example SPI Mode Requirements (Master Mode, CKE =       1)         1)       514         Example SPI Mode Requirements (Slave Mode, CKE =       0)         0)       515         Example SPI Slave Mode Requirements (CKE = 1)       516         External Clock Requirements       506         I <sup>2</sup> C Bus Data Requirements (Slave Mode)       518         I <sup>2</sup> C Bus Start/Stop Bits Requirements (Slave Mode)       517         MSSPx I <sup>2</sup> C Bus Data Requirements       520         MSSPx I <sup>2</sup> C Bus Start/Stop Bits Requirements       519         Parallel Master Port Read Requirements       511         Parallel Master Port Write Requirements       512         PLL Clock       506         Reset, Watchdog Timer, Oscillator Start-up Timer, Power-up Timer and Brown-out Reset Requirements       508         Timer0 and Timer1 External Clock Requirements       523         USB Low-Speed Requirements       523

TXSTAx Register	004
BRGH Bit	. 321
U	
Ultra Low-Power Wake-up	54
Universal Serial Bus	
Address Register (UADDR)	
Associated Registers	
Buffer Descriptor Table	
Buffer Descriptor Table	
Address Validation	
Assignment in Different Buffering Modes	
BDnSTAT Register (CPU Mode)	
BDISTAT Register (CFO Mode) BDnSTAT Register (SIE Mode)	
Byte Count	
Example	
Memory Map	
Ownership	
Ping-Pong Buffering	
Register Summary	
Status and Configuration	
Endpoint Control	
External Pull-up Resistors	
Eye Pattern Test Enable	
Firmware and Drivers	. 375
Frame Number Registers	. 359
Internal Pull-up Resistors	. 356
Internal Transceiver	. 354
Interrupts	. 366
and USB Transactions	. 366
Oscillator Requirements	
Overview	
Class Specifications and Drivers	
Descriptors	
Enumeration	
Frames	
Layered Framework	
Power	
Speed	
Transfer Types	
Ping-Pong Buffer Configuration	
Power Modes	
Bus Power Only	
Dual Power with Self-Power Dominance	
Self-Power Only	. 372
Transceiver Current Consumption	
RAM	
Memory Map	
Status and Control	
UFRMH:UFRML Registers	
USB Specifications	. 502
USB. See Universal Serial Bus.	
M.	

#### ۷

Voltage Reference Specifications	. 500
Voltage Regulator (On-Chip)	. 425
Operation in Sleep Mode	. 426

### W

Watchdog Timer (WDT)	413, 423
Associated Registers	
Control Register	
During Oscillator Failure	
Programming Considerations	423
WCOL	
WCOL Status Flag	305, 306, 307, 310

WWW Address WWW, On-Line Support	•••••
х	
XORLW	
XORWF	

### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- **Product Support** Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Micro-chip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com, click on Customer Change Notification and follow the registration instructions.

### **CUSTOMER SUPPORT**

Users of Microchip products can receive assistance through several channels:

- Distributor or Representative
- Local Sales Office
- Field Application Engineer (FAE)
- Technical Support
- Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://support.microchip.com

### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

To:	Technical Publications Manager	Total Pages Sent	
RE:	Reader Response		
From	: Name		
	Company		
	Address		
	City / State / ZIP / Country		
	Telephone: ()	FAX: ()	
Appli	cation (optional):		
Woul	ld you like a reply? <u>Y</u>		
Devi	ce: PIC18F46J50 Family	Literature Number: DS39931C	
Ques	stions:		
1. V	What are the best features of this do	cument?	
2. ⊦	2. How does this document meet your hardware and software development needs?		
_			
_			
3. E	B. Do you find the organization of this document easy to follow? If not, why?		
_			
_			
4. V	What additions to the document do y	ou think would enhance the structure and subject?	
-			
-			
5. V	What deletions from the document co	ould be made without affecting the overall usefulness?	
-			
-		· · · · · · · · · · ·	
6. Is	s there any incorrect or misleading in	nformation (what and where)?	
_			
	low would you improve this do	at 2	
7. ⊦	low would you improve this docume	au. (	
-			

### **PRODUCT IDENTIFICATION SYSTEM**

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

PART NO.	x <u>xx xxx</u>	Examples:
Device	Temperature Package Pattern Range	<ul> <li>a) PIC18F46J50-I/PT 301 = Industrial temp., TQFP package, QTP pattern #301.</li> <li>b) PIC18F46J50T-I/PT = Tape and reel, Industrial temp., TQFP package.</li> </ul>
Device	PIC18F24J50 PIC18F25J50 PIC18F26J50 PIC18F44J50 PIC18F45J50 PIC18F46J50 PIC18LF24J50 PIC18LF25J50 PIC18LF26J50 PIC18LF44J50 PIC18LF45J50 PIC18LF45J50 PIC18LF46J50	
Temperature Range	I = $-40^{\circ}$ C to $+85^{\circ}$ C (Industrial)	
Package	SP = Skinny PDIP SS = SSOP SO = SOIC ML = QFN PT = TQFP (Thin Quad Flatpack)	
Pattern	QTP, SQTP, Code or Special Requirements (blank otherwise)	



## WORLDWIDE SALES AND SERVICE

#### AMERICAS

Corporate Office 2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support: http://support.microchip.com Web Address: www.microchip.com

Atlanta Duluth, GA Tel: 678-957-9614 Fax: 678-957-1455

Boston Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL Tel: 630-285-0071 Fax: 630-285-0075

**Cleveland** Independence, OH Tel: 216-447-0464 Fax: 216-447-0643

**Dallas** Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Kokomo Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

**Santa Clara** Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

Toronto Mississauga, Ontario, Canada Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Asia Pacific Office Suites 3707-14, 37th Floor Tower 6, The Gateway Harbour City, Kowloon Hong Kong Tel: 852-2401-1200 Fax: 852-2401-3431

Australia - Sydney Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

**China - Beijing** Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

**China - Chengdu** Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

**China - Hong Kong SAR** Tel: 852-2401-1200 Fax: 852-2401-3431

China - Nanjing Tel: 86-25-8473-2460

Fax: 86-25-8473-2470 China - Qingdao

Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

**China - Shanghai** Tel: 86-21-5407-5533 Fax: 86-21-5407-5066

China - Shenyang Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

**China - Shenzhen** Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

**China - Wuhan** Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

**China - Xiamen** Tel: 86-592-2388138 Fax: 86-592-2388130

**China - Xian** Tel: 86-29-8833-7252 Fax: 86-29-8833-7256

**China - Zhuhai** Tel: 86-756-3210040 Fax: 86-756-3210049

#### ASIA/PACIFIC

India - Bangalore Tel: 91-80-3090-4444 Fax: 91-80-3090-4080

India - New Delhi Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

**Japan - Yokohama** Tel: 81-45-471- 6166 Fax: 81-45-471-6122

**Korea - Daegu** Tel: 82-53-744-4301 Fax: 82-53-744-4302

Korea - Seoul Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Malaysia - Kuala Lumpur Tel: 60-3-6201-9857 Fax: 60-3-6201-9859

**Malaysia - Penang** Tel: 60-4-227-8870 Fax: 60-4-227-4068

Philippines - Manila Tel: 63-2-634-9065 Fax: 63-2-634-9069

Singapore Tel: 65-6334-8870 Fax: 65-6334-8850

**Taiwan - Hsin Chu** Tel: 886-3-6578-300 Fax: 886-3-6578-370

**Taiwan - Kaohsiung** Tel: 886-7-536-4818 Fax: 886-7-536-4803

Taiwan - Taipei Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

**Thailand - Bangkok** Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### EUROPE

Austria - Wels Tel: 43-7242-2244-39 Fax: 43-7242-2244-393 Denmark - Copenhagen Tel: 45-4450-2828 Fax: 45-4485-2829

France - Paris Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany - Munich** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

**Italy - Milan** Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen Tel: 31-416-690399 Fax: 31-416-690340

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**UK - Wokingham** Tel: 44-118-921-5869 Fax: 44-118-921-5820

03/26/09

## **Mouser Electronics**

Authorized Distributor

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

Microchip:

 PIC18F25J50-I/ML
 PIC18F24J50-I/SS
 PIC18LF44J50T-I/PT
 PIC18F46J50T-I/PT
 PIC18F46J50T-I/ML

 PIC18LF45J50T-I/ML
 PIC18LF44J50T-I/ML
 PIC18LF45J50-I/PT
 PIC18F46J50-I/ML
 PIC18LF44J50-I/PT

 PIC18LF44J50-I/ML
 PIC18LF45J50T-I/ML
 PIC18LF45J50T-I/PT
 PIC18F46J50-I/ML
 PIC18LF44J50-I/PT